

**T.No. 2336**

# MADRAS GOVERNMENT ORIENTAL SERIES

PUBLISHED UNDER  
THE AUTHORITY OF  
THE GOVERNMENT OF MADRAS

General Editor :

T. CHANDRASEKHARAN, M.A., L.T.,  
*Curator, Govt. Oriental Manuscripts Library, Madras.*

No. CLVII

தென்னிந்திய

கேரளச் சாசனங்கள்

பாகம் 3—பகுதி 2



# **SOUTH INDIAN TEMPLE INSCRIPTIONS**

**VOLUME III**

**PART II**

**Critically edited with Introduction and Notes**

**BY**

**T. N. SUBRAMANIAM**

**GOVERNMENT ORIENTAL MANUSCRIPTS LIBRARY,  
MADRAS.**

**1957**

**Price Rs. 25**

---

---

**Printed at**  
**RATHNAM PRESS,**  
**Madras-1.**

---

---

## INTRODUCTION

The Government of Madras took up for consideration the question of publication of the various manuscripts in different languages on subjects like Philosophy, Medicine, Science, etc., early in May 1948. Important Manuscripts Libraries in the Madras Presidency were requested to send a list of unpublished manuscripts with them for favour of being considered by the Government for publication. The Honorary Secretary of the Tanjore Maharaja Serfoji's Saraswathi Mahal Library, Tanjore, alone complied with this request. This list as well as a similar list of unpublished manuscripts in the Government Oriental Manuscripts Library, Madras, were carefully examined and a tentative selection of manuscripts suitable for publication was made. The Government in their Memorandum No. 34913/48-10, Education, dated 4th April, 1949, constituted an Expert Committee with the Curator of the Government Oriental Manuscripts Library, Madras, as the Secretary, for the final selection of manuscripts suitable for printing and for estimating the cost of publication.

The following were the members of the Committee :—

1. Sri T. M. Narayanaswami Pillai, M.A., B.L.
2. „ R. P. Sethu Pillai, B.A., B.L.
3. „ C. M. Ramachandra Chettiar, B.A., B.L.
4. „ R. Krishnamoorthy. (*Kalki*)
5. Dr. N. Venkataramanayya, M.A., PH.D.
6. Sri M. Ramanuja Rao Naidu, M.A.
7. „ V. Prabhakara Sastri.
8. „ N. Venkata Rao, M.A.
9. „ H. Sessa Ayyangar.
10. „ Masti Venkatesa Ayyangar.
11. „ M. Mariappa Bhat, M.A., L.T.
12. Dr. C. Achyuta Menon, B.A., PH.D.
13. „ C. Kunhan Raja, M.A., D.PHIL.
14. „ A. Sankaran, M.A., PH.D., L.T.
15. Sri Polakam Rama Sastri.
16. „ S. K. Ramanatha Sastri

17. Dr. M. Abdul Huq, M.A., D.PHIL. (Oxon.)
18. Sri Afzul-ul-Ulama Hakim Khader Ahamed.
19. Sri P. D. Joshi.
20. „ S. Gopalan, B.A., B.L.
21. „ T. Chandrasekharan, M.A., L.T., Curator.

With the exception of Sri Masti Venkatesa Ayyangar, and Dr. C. Kunhan Raja, the above members continued to be members of the Expert Committee for 1950-51 also to which the following gentlemen were added in Government Memo. No. 7297-E/50-3, Education, dated 19th May, 1950, and Government Memo. No. 15875-E/50-4, Education, dated 7th September, 1950:—

1. Dr. A. Chidambaranatha Chettiar, M.A. PH.D.
2. Sri S. Govindarajulu, B.A., B.L., LL.B., Bar-at-Law.
3. Capt. G. Srinivasamoorthy, B.A., B.L., M.B. & C.M.
4. Dr. Muhammad Hussain Nainar, M.A., PH.D.
5. Sri T. V. Subba Rao, B.A., B.L.
6. Principal, College of Indian Medicine, Madras.

In Government Memorandum No. 18947-E/52-2, Education, dated 7th August, 1952, a few changes were made in the personnel of the Expert Committee.

The names of the following members were deleted:—

1. Sri V. Prabhakara Sastri.
2. Dr. C. Achyuta Menon.
3. „ M. Abdul Huq.

The following gentlemen were included as members of the Expert Committee:—

1. Sri M. Somasekhara Sarma.
2. Dr. V. Raghavan, M.A., PH.D.
3. „ R. Nagaraja Sarma, M.A., PH.D.
4. „ S. Krishnan Nayar, M.A., PH.D.
5. Prof. S. A. W. Bukhari, M.A., L.T.

In G. O. Ms. No. 1819 Edn., dated 8-11-1955, the Government reconstituted the Expert Committee with the following members:—

#### SANSKRIT

1. Dr. A. Sankaran, M.A., Ph. D., L.T.
2. Sri P. S. Rama Sastri.

3. Dr. V. Raghavan, M.A., Ph. D.
4. „ R. Nagaraja Sarma, M.A., Ph. D., L.T.
5. Sri K. Balasubramania Iyer, B.A., B.L., M.L.C.

### TAMIL

6. Sri T. M. Narayanaswami Pillai, M.A., B.L., M.L.C.
7. „ R. P. Sethu Pillai, B.A., B.L.
8. „ C. M. Ramachandran Chettiar, B.A., B.L.,
9. „ T. P. Meenakshi Sundaram Pillai, M.A., M.O.L.
10. Dr. A. Chidambaranatha Chettiar, M.A. Ph. D.
11. Sri N. T. Viswanathan, B.A., B.L.

### KANNADA

12. Captain G. Srinivasamurthi, B.A., B.L., M.B. & C.M.
13. Sri M. Mariappa Bhat, M.A., L.T.
14. „ H. Sesha Iyengar.

### MALAYĀLAM

15. Dr. S. Krishnan Nayar, M.A., Ph. D.

### MARĀTHI

16. Sri P. D. Joshi.

### ISLAMIC LANGUAGES

17. Professor S. A. W. Bukhari, M.A., L.T.
18. Dr. M. Abdul Huq. M.A., D. Phil (Oxon).
19. Sri S. M. Fazlullah, M.A., L.T.

### OTHERS

20. Sri S. K. Ramanatha Sastri, Sanskrit & Malayalam.
21. „ T. V. Subba Rao, B.A., B.L., Music in all languages.
22. The Principal, College of Indigenous Medicine,  
Madras-10. Medicine in all languages.
23. Sri S. Gopalan, B.A. B.L. Sanskrit, Tamil and Telugu.
24. T. Chandrasekharan, M.A., L.T., In all languages  
(Secretary of all the Committees).

The members of the Committee met at Madras and at Tanjore to examine the manuscripts and make a selection. The recommendations of the Committee were accepted by the Government and they decided to call these publications as the "MADRAS GOVERNMENT ORIENTAL SERIES," and appointed the Curator, Government Oriental Manuscripts Library, Madras, as the General Editor of the publications under this series.

The following manuscripts were taken up for publication till now :—

---

**"A" FROM THE GOVERNMENT ORIENTAL MANUSCRIPTS  
LIBRARY, MADRAS.**

**TAMIL**

1. Kappal Śāttiram.
2. Anubhava Vaiddiya Murai.
3. Āttānakōlāhalaṃ.
4. Upadēśa Kāṇḍam.
5. Cōlaṃ Pūrva Paṭṭayam.
6. Śivajñāna Dīpaṃ.
7. Daṭṭanāyanār Vaiddiya Aṭṭavanai.
8. Vaiddiyak Kaḷaṇciyam.
9. Anubhava Vaiddiya Murai, Vol. 3
10. Saptariṣināḍi, Vol. I, Meṣa Lagnaṃ.
11. Karnāṭakarājākkaḷ Savistāra Carittiram
12. Bharata Siddhāntam.
13. Piḷlaippiṇivākaṭam (on infantile diseases), Vol. I.
14. Anubhava Vaiddiyam, Vol. 4
15. Māṭṭuvākaṭam.
16. Saptariṣināḍi, Vol. II —Viruṣabha Lagnaṃ.
17. South Indian Temple Inscriptions, Vol. I
18. Saptariṣināḍi, Vol III, Mithuna Lagnaṃ.
19. South Indian Temple Inscriptions, Vol. II.
20. Piḷlaippiṇivākaṭam (on infantile diseases), Vol. II.
21. Saptariṣināḍi, Vol. IV, Kaṭaka Lagnaṃ.
22. Pērūr-k-Kōvai.



23. Siddhāntavilakkam.
24. Sāmudrikalakṣaṇam.
25. Ānandaraṅga-k-Kōvai.
26. South Indian Temple Inscriptions, Vol. III, Part I.
27. Saptariṣināḍi, Vol. V, Simha Lagnam.
28. Māghasnāna Purāṇa Ammānai.
29. Kōlācala Stalapurāṇam.
30. Dina Kavitai.
31. South Indian Temple Inscriptions, Vol- III. Part II.

### SANSKRIT

1. Viṣanārāyaṇīyam (Tantrasārasaṅgraha).
2. Bhārgava Nāḍikā.
3. Hariharacaturaṅgam.
4. Brahmasūtravṛtti—Mitākṣarā.
5. Nyāyasiddhānta Tattvāmṛtam.
6. Ārogyacintāmaṇi.
7. Tattvasāra with Ratnasārīṇi.
8. Sūtrārthāmṛta Laharī.
9. (a) Ratnadīpikā.  
(b) Ratnaśāstram.
10. Devakeraḷam—Candrakalā Nāḍi, Vol. I
11. Pātañjala yogasūtra bhāṣya vivaraṇa by Śrī  
Śaṅkarācārya.
12. Nyāyaratnam with the commentary Dyutimālikā.
13. Cīkitsātilakam.
14. Nṛttaratnāvali.
15. Daivajñābharaṇam.
16. Ābhoga.
17. Aumāpatam.
18. Mahābhāskarīyam with Govindabhāṣya
19. Devakeraḷam—Candrakalā Nāḍi, Vol. II.
20. Nayadyumaṇi.
21. Tattva Prakāśikāvyaḅhyā—Bhāvabodha.

### TELUGU

1. Auṣadhayōgamulu.
2. Vaidyanighaṇṭuvu.
3. Dhanuṛvidyā Vilāsam.

4. Yōgadarśana viṣayamu.
5. Khadgalakṣaṇaśīrōmaṇi.
6. Śaivācārasaṅgrahamu.
7. Anubhavavaidyamu.
8. Abhinayadarpaṇamu.
9. Brahma vidyāsudhāṇavamamu.
10. Rāgatālacintāmaṇi.
11. Vaidyacintāmaṇi.
12. Kumāra rāmuni Kathā.
13. Kaṭamrāju Kathā.
14. Śārīramu.
15. Bharatasārasaṅgraha.
16. Bobbilyuddhakathā
17. Haidar caritramu.
18. Āryabhaṭṭiya Vyākhyā.

### MALAYĀLAM

1. Garbha Cikitsā.
2. (a) Vāstulakṣaṇam.  
(b) Śilpa viṣayam.
3. Mahāsāram.
4. Kaṇakkusāram.
5. Kriyākramam.
6. Kaṇakkusāram (Bālaprabōdham).
7. Āśvacikitsā.
8. Phalasārasamuccayam.
9. Kīlivaṇḍusamvādam.
10. Advaita Vedāntam.
11. Bārhaspatyasūtra with Malayālam commentary.
12. Karaṇapaddhati.
13. Vidyāmādhaviyam.
14. Sarvasādhāraṇa Cikitsā.
15. Viśacikitsā and Viśappāṭṭusāram.
16. Jñānapīyūṣam.
17. Vēṭālapaṇcaviṃśati.
18. Yudhiṣṭhiraviṣayam.
19. Kathakālī Mañjari.
20. Vaidyagrantham.

## KANNADA

1. Lōkōpakāram.
2. Raṭṭamatam.
3. Aśvaśāstram.
4. Vividhavaidyaviṣayagaḷu.
5. Saṅgītaratnākara.
6. Sūpaśāstra.
7. Vaidyasārasaṅgraham, Vol. I.
8. Sadgururahasyam.
9. Vaidyasārasaṅgraham, Vol. II.
10. Manmathavijaya.
11. Abhidhānaratnamālā.
12. Vyavahāraganita.
13. Jīvasambōdhanam.
14. Kāmandaka Nīti Sāra.

ISLAMIC LANGUAGES  
PERSIAN

1. Jami-Al-Ashya.
2. Tibb-E-Faridi.
3. Tahqiq-Al-Buhran.
4. Safinat-Al-Najat.
6. Baharistan Sukhan.
7. Nuskha-e-Shajahani.
8. Tuhfa-e-Khani.
9. Ruqa'at-e-Wālājāhi.

## ARABIC

1. Shawakil-Ul-Hur.

**"B" FROM THE TANJORE MAHARAJA SERFOJI'S  
SARASWATHY MAHAL LIBRARY, TANJORE.**

## TAMIL

1. Śarabhendra Vaiddiya Murai (Diabetes).
2. Do. (Eyes).
3. Do. (Anaemia).
4. Do. (Śvāsakāśam).

5. Agastiyar 2000.
6. Konkaṇarsārkku Vaippu.
7. Tiruccirrambalakkōvaiyār with Padavurai.
8. Tālasamudram.
9. Bharatanāṭyam.
10. (a) Pāṇḍikēli Vilāsa Nāṭakam.  
(b) Purūravacakravarti Nāṭakam.  
(c) Madanasundaravilāsanāṭakam.
11. Percy Macqueen's Collection of Folklore in the  
Madras University Library.
12. Rāmaiyan Ammānai.

### TELUGU

1. Kāmandakanītisāramu.
2. Tāladaśāprāṇapradīpikā.
3. Raghunātha Nāyakābhyudayamu.
4. Rājagōpāla Vilāsamu.
5. Rāmāyaṇamu by Kaṭṭa Varadarāju.

### MAHRĀTHI

1. Nāṭyaśāstra Saṅgraha.
2. (a) Book of Knowledge.  
(b) Folk Songs.  
(c) Dora Darun Veni Paddhati.  
(d) Aśvasa Caṭula Dumani.
3. (a) Pratāpasimhendra Vijaya Prabandha.  
(b) Sarabhendra Tīrthāvali.  
(c) Lāvaṇi.
4. Devendra Kuṛavañji.
5. Bhakta Vilāsa.
6. Śloka Baddha Rāmāyaṇa.

### SANSKRIT

1. Aśvaśāstra with Tricolour illustrations.
2. Rājamṛgāṅka.
3. Ānandakandam.
4. Āyurvedamahodadhi.
5. Gīta Govinda Abhinaya.

6. (a) Coḷacampā.  
(b) Sahendra Vilāsa.
7. Dharmākūṭam—Sundara Kāṇḍa.
8. Jātakasāra.
9. Viṣṇutattvanirṇaya Vyākhyā.
10. Saṅgīta Darpaṇam.

The Government in their G. O. Ms. No. 1820, Education, dated 4th August 1952, sanctioned a grant of Rs. 9,000 to the Dr. V. Swaminatha Aiyar's Tamil Library, Adyar, towards the publication of the following manuscripts as part of the "Madras Government Oriental Series":—

1. Tīruvācaka Vyākhyānam.
2. Mahābharata Cūḍāmaṇi.

It is hoped that the publication of most of the important manuscripts will be completed within the next few years.

Some of the manuscripts taken up for publication are represented by single copies in the Library and consequently the mistakes that are found in them could not be corrected by comparing them with other copies. The editors have, however, tried their best to suggest correct readings. The wrong readings are given in round brackets and correct readings have been suggested in square brackets. When different readings are found, they have been given in the foot-notes except in the case of a few books in which the correct readings have been given in the foot-note or incorporated in the text itself.

The Government of Madras have to be thanked for financing the entire scheme of publication, although there is a drive for economy in all the departments. My thanks are due to the members of the Expert Committee who spared no pains in selecting the manuscripts for publication. I have also to thank the various editors, who are experts in their own field, for readily consenting to edit the manuscripts and see them through the Press. The various Presses that have co-operated in printing the manuscripts in the best manner possible also deserve my thanks for the patience exhibited by them in carrying out the corrections made in the proofs.

The present part is a continuation of the I Part of Volume III published in 1955. 38 Inscriptions in the Mackenzie Collections are included in this volume. The information promised in my Introduction of the earlier part, with the exception of the chronological list, is given in this volume. The most important of it is the list of the technical terms that are generally found in inscriptions and their meanings. This is bound to be of considerable help to scholars engaged in reading and interpreting inscriptions. Though more materials can be placed before the public by way of adding appendices like the evolution of the various scripts employed in inscriptions they have been omitted lest the volume should grow out of size.

The completion of the 3 volumes in 4 parts containing almost all the inscriptions relating to the South Indian Temples recorded by Colonel Mackenzie is an onerous task undertaken successfully by this Library. The learned editor in spite of his ill-health has worked hard to execute the work entrusted to him in the best manner acceptable to the scholars in the field. Something more has yet to be done as pointed out by the editor. It is hoped it will be possible to undertake this also in the future.

MADRAS, }  
24-4-'57. }

T. CHANDRASEKHARAN,  
*General Editor,*  
*Madras Government Oriental Series.*



## PREFACE

---

The second part of the Third volume of the **South Indian Temple Inscriptions** now issued contains thirty-five inscriptions since traced and not included in the previous volumes, thus bringing the total to 1299, as also the texts of three records for which only summaries were given previously.

The Historical Survey included in this part comes only upto the time of the accession of the Chōla monarch Rājārāja III. It has to stop with that as it has already out-grown the size. Similarly, the history of the Koṅgu line of kings promised to be discussed here has to be reserved for another occasion.

The Glossary of Epigraphical terms ordered by the Government of Madras in their G.O. No. Ms. 1082, Education, dated the 3rd August 1954 is also included in this volume. I should thank the Government for having given me this opportunity, especially when the Tamil language is being made the official language of the State just as it was when these inscriptions were written.

The inclusion of the *avatāra ślokas* of the Vaishṇava Ālvārs and Āchāryas in this part makes it necessary to review the date of the great Vaishṇava teacher Rāmānuja and a note on the same has also been added.

This collection of the Tamil inscriptions copied by the assistants of Col. Mackenzie may be considered as a representative one covering the entire Tamil area and containing records of almost all the dynasties that ruled over South India. A perusal of these records will give a fair idea of the nature of the epigraphical material available in this country. Anyhow, to have a clear picture of the same, a section dealing with the South Indian Epigraphy, indicating parallels from the North also, has been added.

Any study on epigraphy presupposes a working knowledge of Palæography; but no work on the subject is now available.

Dr. G. Buhler brought out his German work *Indischen Palæographie* in 1896 with the plates issued separately. This German book was translated into English as *The Indian Palæography* by J. F. Fleet and published as Appendix to *Indian Antiquary*, vol. XXXIII (1904). Subsequent to that, Mahāmahōpādhyāya Paṇḍit Gaurishankar Hirachand Ojha wrote his *Bhāratiya Prāchīna Lipimālā* in Hindi (Second Edition, 1918). These two works dealt with all the scripts prevalent in the country and naturally the South Indian scripts were not treated in detail. Recently, in 1952, Dr. R. B. Pandey of the Banaras Hindu University has brought out Part I of his book *Indian Palaeography*. It deals only with the introductory portion of the subject. The evolution of the several scripts illustrated with their relative charts is promised in the Second part yet to come. But even in the first part, South India has not received its due share, being completely ignored or dealt with cursorily.

So far as the South Indian scripts are concerned, the earliest work on the subject, *Elements of South Indian Palæography* by Dr. A. C. Burnell, was published in 1874 and the second edition of it, fully revised, came out in 1878. This was even before Dr. Buhler wrote his German book. Long after, T.A. Gopinatha Rao published in two numbers of the *Travancore Archaeological Series* his study on them, one entitled 'Some Chōla Inscriptions with a Chapter on the Evolution of the Tamil-Grantha Alphabet' (No. XIV) and the other 'Specimens of Vaṭṭeḷuttu Inscriptions' (No. XVI). In 1938, *Paṇḍai-t-Tamiḷ Eluttukkal* in Tamil was published by me. And recently, in 1952, C. Sivaramamurti wrote his *Indian Epigraphy and South Indian Scripts*, issued as a part of the Bulletin of the Madras Government Museum.

All the above works have gone out of print and none is available. The method of treatment varies with each book and there is still a demand and necessity for a good work on the subject mainly dealing with the South Indian varieties. So a section on *Tamiḷ palaeography* has been added to this part.

It was also suggested that I should add illustrative charts showing the comparative development of the several scripts in the different areas in the respective periods. Such a chart, not

hitherto attempted by any other scholar, will be highly interesting and instructive in bringing out clearly the salient features in the evolution of writing as a whole, thus pointing to the 'unity in the diversity.' But this could not be included here in consideration of the heavy cost it would involve.

With regard to the Tamil inscriptions copied by the surveyors of Col. Mackenzie, the following items of work still remain to be done.

There are still about half a dozen inscriptions, the texts of which are available, but not included in these volumes. They are in the Grantha script.

As already mentioned in my Preface to the second volume of this collection, the surveyors of Col. Mackenzie have prepared eye-copies of some inscriptions, exactly as found on stone, as they probably could not decipher them. So far as the Tamil area is concerned, such eye-copies are mostly of the Vatteluttu inscriptions. They have to be deciphered first before taking any action on them. But the work is not easy. The originals, for which there are no copies, will not be lent out of the Library and any person who has to study them should do it in the Library itself, providing himself with the necessary reference books and other literature. Nothing can be said about the value of these records, which are getting damaged in course of time, till they are deciphered. Some arrangement has to be made urgently to decipher them before it is too late.

In addition to the above two categories, there is one other item also to be considered. Several of the *Kaifiyats* or the Local Records collected from villages in the Tamil area by the surveyors of Col. Mackenzie contain references to inscriptions pertaining to the respective villages, sometimes coupled with the dates of the records and the names of the royal donors. It is quite likely that even though the texts of those inscriptions are not available in the collection, they are traceable in those copied by the Epigraphy Department either from the respective villages or in their neighbourhood. It is also possible that some new information may come to light by a study of these. As such, these also have to be published.

The Government Epigraphist for India and Prof. K. A. Nilakanta Sastri, as usual evinced keen interest in this publication. Dr. N. Venkataramanayya, Reader in Indian History (Retired), University of Madras, Dr. T. V. Mahalingam, Professor of Archaeology, University of Madras, Sri K.R. Srinivasan, Superintendent for Archaeology, Temple Survey Project, Southern Region, Madras, Sri P. R. Srinivasan, Curator, Archaeological Section, Government Museum, Madras and Sri M. Somasekhara Sarma, Editor, Andhra Volume, Telugu Encyclopaedia, Madras have read through the manuscript at various stages and offered me useful suggestions. I am indebted to all of them.

Sri T. Chandrasekharan, M.A., L.T., Curator of the Government Oriental Manuscripts Library, Madras and the staff of the Library, among whom Sri M. S. Vaidyanathan, Sanskrit Pandit, deserves special mention, obligingly helped me whenever I approached them, and this facilitated my work very much. Finally I have also to record the kind co-operation of the Rathnam Press and its Proprietor in the printing of the book, which, at times, exacted much of their patience and resources. I offer my thanks to them.

Madras }  
21-3-57 }

T. N. SUBRAMANIAM.

## மு ன் னு ரை

—: \* :—

இப்போது வெளிவரும் தென்னிந்திய கோயிற் சாசனங்கள் மூன்றாம் பாகம் இரண்டாம் பகுதியில் முன் பாகங்களில் சேராதனவும் புதிதாகக் கிடைத்தனவுமான முப்பத்தைந்து சாசனங்கள் அடங்கியுள்ளன. ஆகவே இதுகாறும் வெளியான சாசனங்களின் மொத்தத் தொகை ஆயிரத்து இருநூற்றுத் தொண்ணூற்றென்பது ஆகும். அன்றி, இதற்கு முன் மூலபாடம் கிடைக்காமல் சுருக்கம் மட்டுமே வெளியான மூன்று சாசனங்களின் மூல பாடம் பின்னால் கிடைத்தது. அதுவும் இந்தப் பாகத்திலே சேர்ந்திருக்கிறது.

இதிலே காணும் 'ஆராய்ச்சிக் குறிப்பு' பதின்மூன்றாம் நூற்றாண்டின் ஆரம்பத்தில் மூன்றாம் இராஜ ராஜ சோழன் சிங்காதனம் ஏறிய காலத்தோடு நின்றுவிடுகிறது. அதுவே பெருகிவிட்டதால் மேலும் பக்கங்களை வளர்த்தாமல் நிறுத்த வேண்டியதாயிற்று. அதே காரணத்துக்காக, இந்தப் பாகத்தில் கொடுக்கப்போவதாகக் கூறியிருந்த கொங்கு நாட்டுச் சோழ மன்னர்களின் வரலாற்றையும் நிறுத்திவிட நேர்ந்தது. மற்றொரு சமயம் அவைகளை ஆராயலாம்.

சாசனங்களில் காணும் சொற்களை அவற்றின் பொருள் விளக்கத்தோடு ஒரு பிற்சேர்க்கையாகக் கொடுக்கவேண்டுமென்று 3-8-1954உ கொண்ட தங்கள் Ms. நெ. 1082 (எடுகேஷன்) உத்தரவில் அரசாங்கத்தார் தெரிவித்திருந்தார்கள். அந்த அகராதி இந்தப் பாகத்தில் சேர்க்கப்பட்டுள்ளது. இந்தச் சாசனங்கள் தோன்றிய காலத்தில் இருந்ததுபோலவே மறுபடியும் தமிழ் அரசியல் ஆட்சிமொழியாகப் பீடம் ஏறும் இந்தச் சமயத்திலே இத்தகைய திருப்பணியைச் செய்வதற்கு எனக்கு ஒரு சந்தர்ப்பம் அளித்ததற்காக அரசாங்கத்தாருக்கு நான் நன்றி செலுத்தவேண்டும்.

வைஷ்ணவ ஆழ்வார்கள், ஆசாரியர்கள் ஆகியோருடைய அவதார சுலோகங்கள் இந்தத் தொகுதியிலே சேர்க்கப்பெற்றுள்ளன. அதனாலே வைஷ்ணவ ஆசாரியர்களிலே தலை சிறந்த ஸ்ரீ இராமாநுஜருடைய காலத்தைப் புனராலோசனை

செய்யவேண்டியது அவசியமாகிறது. அதைப்பற்றிய ஒரு குறிப்பும் இதிலே சேர்க்கப்பட்டுள்ளது.

கர்னல் மக்கென்ஸியின் உதவியாளர்கள் சேகரித்த தமிழ்ச் சாசனங்களின் தொகுப்பிலே தமிழ்நாட்டின் பல பகுதிகளிலிருந்தும் பிரதி செய்த சாசனங்கள் கொடுக்கப்பட்டுள்ளன. அன்றி, தென்னாட்டை ஆண்ட அரசு பரம்பரைகள் பலவற்றுக்கும் உரித்தான சாசனங்கள் இந்தத் தொகுப்பிலே அடங்கியுள்ளன. இத் தொகுப்பில் உள்ள சாசனங்களைக் கவனித்தாலே நம் நாட்டில் கிடைக்கக்கூடிய சாசனங்களின் அருமை பெருமையும் அவை எந்த எந்த விஷயங்களைப்பற்றிக் கூறுவனவாக இருக்கும் என்பதும் ஓர் அளவு தெரியவரும். எனினும், சாசனங்களைப்பற்றி நன்றாக அறிந்து கொள்வதற்காகத் 'தமிழ்நாட்டுச் சாசனங்கள்' என்ற ஒரு பகுதியும் இதிலே சேர்க்கப்பெற்றிருக்கிறது. அதிலே தமிழ்நாட்டுச் சாசனங்களோடு இந்தியாவின் பிற பகுதிகளில் கிடைப்பனவும் அங்கங்கே ஒப்பிட்டுக் காட்டப் பெற்றுள்ளன.

சாசன ஆராய்ச்சிக்கு எழுத்துக்களின் வளர்ச்சிமுறையை அறிந்திருப்பதும் அவசியமாகிறது. ஆனால் அந்தத் துறையிலே சரியான புத்தகம் எதுவும் இப்போது கிடைப்பதில்லை. கி.பி. 1896-ல் டாக்டர் பீலர் என்பார் இந்திய எழுத்துக்களின் வரிவடிவ வளர்ச்சியைப்பற்றி ஜெர்மன் பாஷையில் ஒரு நூலை வெளியிட்டார். அதற்கான படங்களையும் தனியாகவே கொடுத்திருந்தார். ஜெ. எப். பிளீட் என்பவரால் அது ஆங்கிலத்தில் மொழிபெயர்க்கப்பட்டு நூல் மட்டும் 'இந்தியன் ஆண்டிகுவரி' பத்திரிகையின் முப்பத்து மூன்றாம் வால்யூமில் (1904-ஆம் ஆண்டு) ஒரு பிற்சேர்க்கையாகக் கொடுக்கப்பட்டது. பிறகு மஹாமஹோபாத்யாய பண்டித கௌரிசங்கர ஹிராசந்த் ஓஜா என்பவர் ஹிந்தியில் பாரதீய ப்ராசீன விபிமாலா என்று ஒருநூல் எழுதிவெளியிட்டார் (இரண்டாம் பதிப்பு 1918). இவ்விரண்டு நூல்களும் நம் நாட்டில் வழக்கில் இருந்த எல்லா எழுத்துக்களைப்பற்றியும் கூறுவன. ஆகவே தென்னிந்திய விபிகளைப்பற்றி விவரமாக இல்லை.

சமீபத்திலே, 1952-ல், காசி சர்வகலாசாலையைச் சேர்ந்த டாக்டர் ராஜபலி பண்டே என்பார் (இந்தியன் பாஷியாகிரபி)



‘இந்திய எழுத்துக்களின் வரி வடிவ வளர்ச்சி’ என்ற ஆங்கில நூலின் முதற்பாகத்தை வெளியிட்டுள்ளார். இதிலே அதன் பூர்வாங்கப் பகுதியே உள்ளது. எழுத்துக்களின் வடிவ வளர்ச்சிகளைப் படங்களுடன் இரண்டாம் பாகத்தில் காணலாம் என்று கூறியிருக்கிறார். அது இன்னும் வெளிவரவில்லை. வெளிவந்துள்ள முதல் பாகத்திலும் தென்னாட்டுக்கு உரிய ஸ்தானம் கிடைக்கவில்லை. முற்றிலும் அது புறக்கணிக்கப்பட்டே உள்ளது. சிற்சில இடங்களில் அது பெரும்படியாக மேற்போக்கான நிலையில் குறிக்கப்பட்டுள்ளது. எனினும் அவ்விடங்களில் குறிக்கப்பட்டிருக்கும் விஷயங்கள் பல விதங்களில் தவறாக இருப்பதைத்தான் காணலாம்.

தென்னிந்தியா சம்பந்தப்பட்டவரையில் முதன் முதலாக டாக்டர் எ.ஸி. பர்ணல் என்பார் 1874-ல் ‘எலிமெண்டல் ஆப் ஸௌத் இந்தியன் பாலியாகிரபி’ (தென்னிந்தியப் பிராசீனலிபி) என்ற பெயரில் ஒரு நூலை ஆங்கிலத்தில் எழுதினார். 1878-ல் அதன் திருத்திய இரண்டாம் பதிப்பு வெளியாகியது. இவையெல்லாம் டாக்டர் பீலர் தம் ஜெர்மன் நூலை எழுதுவதற்கு நீண்ட காலத்துக்கு முன்பே நடந்தது. அப்பால் வெகுநாள் கழித்து, து. அ. கோபிநாதராயர் அவர்கள் ‘திருவாங்கூர் ஆர்க்கியலாஜிகல் சீரிஸ்’ முதல் தொகுதியில் இரண்டு கட்டுரைகளை ஆங்கிலத்தில் எழுதி விளக்கப்படங்களுடன் வெளியிட்டார். ‘சில சோழ சாசனங்களும் கிரந்த-தமிழ் எழுத்துக்களின் வளர்ச்சியைப்பற்றிய கட்டுரையும்’ என்பது (பதினான்காம் நெ.) ஒன்று. ‘வட்டெழுத்துச் சாசனங்களின் மாதிரிகள்’ என்பது (பதினாறாம் நெ.) மற்றொன்று. அப்பால் 1938-ல் நான் பண்டைத் தமிழ் எழுத்துக்கள் என்னும் நூலைத் தமிழில் எழுதினேன். சமீபத்தில் 1952-ல் ஸ்ரீ ஸி. சிவராம மூர்த்தி என்பார் ‘இந்தியச் சாசனவியலும் தென்னிந்திய எழுத்துக்களும்’ என்ற நூலை ஆங்கிலத்தில் எழுதிச் சென்னை சர்க்கார் மியூசியம் புல்லெட்டினில் ஒரு பாகமாக வெளியிட்டார்.

இந்த நூல்களில் எதுவுமே இப்போது கிடைப்பதில்லை. ஒவ்வொன்றும் ஒவ்வொரு முறையில் எழுதப்பெற்றது. ஆகவே தென்னிந்திய எழுத்துக்களைப்பற்றியவரையில் நல்ல முறையில் எழுதப்பெறும் நூல் ஒன்றுக்கு அவசியம் இப்போதும் உண்டு. ஆதலின், தமிழ் எழுத்துக்களின் வரிவடிவ

வளர்ச்சி என்ற பெயரில் ஆங்கிலத்தில் ஒரு கட்டுரையும் எழுதி விளக்கப் படங்களுடன் இதிலே சேர்த்திருக்கிறேன்.

அன்றி, அந்த அந்தக் காலங்களில் நம் நாட்டின் பல பாகங்களிலும் எழுத்துக்கள் எவ்விதம் வளர்ச்சி பெற்று வரி வடிவ மாற்றுதல்களை எந்த எந்த விதங்களில் அடைந்தனவென்பதை ஒப்பிட்டுக் காட்டும் முறையில் வரி வடிவப் படங்களையும் தயாரித்துக் கொடுக்க வேண்டும் எனவும் சொன்னார்கள். இது வரையில் அந்த மாதிரி யாரும் செய்தது இல்லை. இத்தகைய ஒப்புமுறைப்படம் மிகவும் உபயோகமாக இருக்கும்; எழுத்துக்களின் வரிவடிவ வளர்ச்சியிலே பல புதியவிஷயங்களை நமக்கு அறிவிக்கும். அன்றி நம் நாட்டிலே பலவகை எழுத்துக்கள் இருந்தாலும் அவற்றுக்கு உள்ள ஒற்றுமையும் நன்கு விளங்கும். எனினும் அதைச் செய்து முடிப்பதற்கு அதிகச் செலவு ஏற்படும். ஆகையால் அதை இதிலே சேர்க்க முடியவில்லை.

கர்னல் மக்கென்ஸியின் உதவியாளர்கள் சேகரித்த தமிழ்ச் சாசனங்கள் சம்பந்தமாகப் பின்வரும் வேலைகள் இன்னும் பாக்கியுள்ளன.

இந்தத் தொகுப்பில் சேர்த்து வெளியிடப்பெறாமல் விட்டுப் போன ஐந்தாறு சாசனங்களின் மூல பாடங்கள் கிடைத்துள்ளன. அவை கிரந்த எழுத்தில் உள்ளன.

ஏற்கெனவே இரண்டாம் பாகத்தின் முன்னுரையில் கூறியுள்ளபடி, கர்னல் மக்கென்ஸியின் உதவியாளர்கள் சில சாசனங்களைக் கல்லில் கண்ட வரிவடிவத்திலே படம் எழுதுவதுபோலப் பிரதி செய்திருக்கிறார்கள். அவர்களால் அந்தச் சாசனங்களைப் படிக்க முடியவில்லைபோலும். தமிழ் சம்பந்தப்பட்ட வரையில் அத்தகைய சாசனங்கள் வட்டெழுத்தில் உள்ளவை. அவை வெளியிடப்பெற வேண்டுமா வென்பதை நிர்ணயிப்பதற்கு முன்னர் அவற்றை வாசித்துத் தற்கால எழுத்தில் பெயர்த்து எழுதவேண்டும். இது சலபமாக நிறைவேறக் கூடியதல்ல. அவற்றுக்கு மக்கென்ஸியின் உதவியாளர்கள் தயாரித்த மூலப் பிரதிகள் மட்டுமே உள்ளன. வேறு பிரதிகள் இல்லை. அவற்றை ஒலைச்சுவடி நிலயத்திலிருந்து வெளியே எடுத்துச் செல்லவும் அனுமதிக்கமாட்டார்கள். ஆகவே அவற்றை ஆராய்வோர் அவ்வாராய்ச்சிக்குத்

தேவையான் இதர நூல்களைத் தாங்களே சேகரித்துக் கொண்டு ஓலைச்சுவடி நிலைத்துக்குப் போய் அங்கேயே அவற்றை ஆராயவேண்டும். அவற்றைத் தற்கால எழுத்தில் பெயர்த்து எழுதியிறுக்கே அவற்றின் மதிப்பை நாம் உணர முடியும். அந்த மூலப் பிரதிகள் காலக் கிரமத்தில் மசி மங்கிப் பாழாகிவிடக் கூடுமாதலால் விரைவில் அவற்றை ஆராய்ந்து பெயர்த்து எழுதுவதற்கான ஏற்பாடுகளைச் செய்யவேண்டும்.

இவ்விரண்டையும் தவிர மற்றொரு வகையும் இருக்கிறது. மக்கென்ஸியின் உதவியாளர்கள் தாங்கள் சென்ற கிராமங்கள் பலவற்றிலிருந்து ஊர் வரலாறுகளைக் கேட்டு அறிந்து எழுதி வாங்கிவந்திருக்கிறார்கள். அவை கைப்பிடி அல்லது கைபியத் எனப் பெறும். அந்த வரலாறுகளிலும் சில இடங்களில் அந்த அந்தக் கிராமங்களைப் பற்றிய சாசனங்களையும் அவற்றை வழங்கிய அரசர் பெயர், வருஷம் முதலிய விவரங்களுடன் குறித்திருக்கிறார்கள். அந்தச் சாசனங்களின் பிரதிகள் கிடைக்கவில்லை என்றும் குறிப்பிட்டிருக்கிறார்கள். எனினும் அவை முற்றிலும் மறைந்து போயிருக்கா. சாசன இலாகாவின் பிரதி செய்தவற்றுள் அவை கிடைக்கலாம். அவ்விதம் கிடைத்தால் அந்த கைப்பிடிகளில் காணும் விஷயங்கள் உறுதியாவதுடன் பல புதிய செய்திகளையும் அறிய இயலும். ஆகவே அவற்றையும் தொகுத்து வெளியிடவேண்டும்.

வழக்கம்போலவே இந்திய அரசாங்கத்தின் சாசன இலாகாவின் தலைவர், பேராசிரியர் க. அ. நீலகண்ட சாஸ்திரி ஆகியோர் இந்த வெளியீட்டில் சிரத்தை காட்டிவந்தனர். சென்னைச் சர்வகலாசாலையில் இந்திய சரித்திர ஆராய்ச்சித் துறையில் ரீடராக இருந்த டாக்டர் என். வேங்கடரமணய்யா, அதே சர்வகலாசாலையில் இப்போது புதை பொருள் ஆராய்ச்சித் துறைப் பேராசிரியராக இருக்கும் டாக்டர் டி. வி. மகாலிங்கம், புதைபொருள் ஆராய்ச்சி இலாகாவில் தென்பிரதேசக்கோயிற்கலை ஆராய்ச்சித் துறைத் தலைவர் ஸ்ரீ கே. ஆர். ஸ்ரீநிவாஸன், சென்னை சர்க்கார் மியூஸியத்தில் ஆர்க்கியாலஜி பிரிவின் நிர்வாக அதிகாரி ஸ்ரீ பி. ஆர். ஸ்ரீநிவாஸன், தெலுங்குக் கலைக் களஞ்சியத்தின் ஆந்திர வால்பூம் ஆசிரியர் ஸ்ரீ மல்லம்பள்ளி சோமசேகர சர்மா ஆகியோர் இந்நூலின் கையெழுத்துப் பிரதிகளைப் பற்பல நிலைகளில் படித்து, உபயோகப்படக்கூடிய

பல ஆலோசனைகளைக் கூறினர். அவர்கள் எல்லோருக்கும் நான் கடமைப்பட்டவனாவேன்.

சென்னை சர்க்கார் ஓலைச்சுவடி நிலையத்தின் தலைவர் ஸ்ரீ தி. சந்திரசேகரன் அவர்களும் நிலையத்து அதிகாரிகள் பலரும் நான் வேண்டியபொழுதெல்லாம் என் சந்தேகங்களைத் தீர்த்து உதவி புரிந்தனர். அவர்களுள் சமஸ்கிருத பண்டிதர் ஸ்ரீ எம். எஸ். வைத்தியநாதன் அவர்களை முக்கியமாகக் குறிப்பிடவேண்டும். கடைசியாக, சிரம சாத்தியமான இந்த நூலை மிகுந்த பொறுமையுடன் ஒத்துழைத்து நல்ல முறையில் அச்சிட்டு வெளிக்கொணர்ந்த ரத்தினம் அச்சகத்தாரையும் அதன் சொந்தக்காரரையும் மறக்கலாகாது. அவர்கள் எல்லோருக்கும் என் நன்றி.

சென்னை }  
21—3—1957 }

தி. நா. சுப்பிரமணியன்

# CONTENTS

---

	Page No.
General Editor's Introduction ... ..	i
Preface (in English) ... ..	xi
„ (in Tamil) ... ..	xv
 Historical Survey (pages 1—146)	
Rājarāja I ... ..	1
Rājendra I ... ..	16
Successors of Rājendra I ... ..	27
Adhirājendra and the accession of Kulōttuṅga I ... ..	50
Kolōttuṅga I ... ..	69
The Ceylonese affair ... ..	79
Parāntaka III and Vikrama Chōla ... ..	86
Kulōttuṅga II and Rājarāja II ... ..	92
Rājādhirāja II and Kulōttuṅga III ... ..	97
The Pāṇḍyan Civil war ... ..	101
The effects of the accession dispute ... ..	113
Expedition of Kulōttuṅga III against Warangal ... ..	113
Kulōttuṅga III and Ballāḷa II ... ..	117
Index ... ..	129
Postscript ... ..	146
 A Note on the date of Rāmānuja ... ..	147
 South Indian Epigraphy (pages 161—252)	
1. Inscriptions ... ..	161
2. Ancient Historical literature ... ..	165
3. Inscriptions as the main source for history ... ..	172
4. Literary and Historical Inscriptions ... ..	181
Literary Inscriptions ... ..	182

			Page No.
	Historical Inscriptions	...	186
5.	Varieties of Inscriptions	...	190
6.	Religious Records	...	196
7.	Secular Records	...	202
8.	Spurious Records	...	209
9.	Writing Materials	...	213
	Metals	...	213
	Gold	...	213
	Silver	...	214
	Brass	...	214
	Bronze	...	215
	Copper	...	215
	Iron	...	217
	Substances other than Metal	...	218
	Crystal	...	218
	Bricks	...	218
	Clay and Terra-cotta	...	219
	Earthenware	...	220
	Wood	...	220
	Stone	...	221
	Conch, ivory, etc.	...	224
	Note on other Writing Materials	...	225
	Palm-leaf	...	225
	Birch-bark	...	226
	Paper	...	227
	Cotton cloth	...	227
	Leather	...	228
	Ink	...	228
10.	Epigraphical forms and contents	...	229
	Maṅgala	...	230
	Donor	...	231
	Donee	...	232
	Gifts	...	232



			Page No.
Conclusion	...	...	232
Scribe	...	...	233
Composer	...	...	234
Signature	...	...	235
Seal	...	...	236
11. Dating of the Inscriptions	...	...	239
Numeral Notation	...	...	243
Bhūta-samkhyā	...	...	244
12. Some Epigraphical conventions	...	...	246
List of abbreviations	...	...	252
Historical Survey, etc. (in Tamil : pages 1—386)			
Note on Transliteration			(387)
" (in Tamil)			(388)
<b>Texts of Inscriptions</b>			
Kaṇḍiyūr (Tañjāvūr Dt.)	...	1265-66	1295-96
Śrīraṅgam (Tiruchirāpaḷḷi Dt.)	...	1267-69	1296-1301
Chidambaram (South Arcot Dt.)	...	1270-73	1301-24
Chingleput (Chingleput Dt.)	...	1274-79	1325-43
Kāñchīpuram ( " )	...	1280-97	1343-73
Śrīperumbūdūr( " )	...	1298	1373-75
Kadiri (Madurai Dt.)	...	1299	1375-76
<b>Appendix I</b>			
Texts of three old inscriptions since traced	...	1256-58	1377-84
<b>Appendix II</b>			
Additions and Corrections	...	...	1385
<b>Appendix III</b>			
Epigraphical Glossary (in Tamil)	...	...	1387

*Appendix IV*

## Tamil Palaeography (pages 1499-1610)

I. Introductory	...	...	1499
II. The Brāhmī inscriptions of Tamil-nāḍu			1505
III. The Brāhmī and the Archaic Grantha	...		1513
IV. The Grantha script	...	...	1522
V. The Tamil script	...	...	1535
VI. The Vaṭṭeḷuttu script	...	...	1546
VII. Mixed scripts	...	...	1559
VIII. The Numerals	...	...	1562
IX. History of the Art of Writing	...	...	1569
Note on Further references to Pictographs in Tamil literature			...
			1580
X. The Antiquity and origin of the Brāhmī		"	1587
XI. Conclusion	...		1609

*Annexure*

Epigraphical Glossary (in English)	...	i-xcvi
Index (English)	...	xcvii-civ
„ (Tamil)	...	cv-cxii

---

# பெருளடக்கம்

—: 0 :—

பக்கம் .

தொகுதியின் பதிப்பாசிரியர் முகவுரை	....	i
முன்னுரை (ஆங்கிலம்)	...	xi
„ (தமிழ்)	...	xv
ஆராய்ச்சிக் குறிப்புகள் (ஆங்கிலம் 1-146)		
இராமாதுஜர் காலத்தைப்பற்றிய குறிப்பு (ஷெ. 147-160)		
தென்னிந்திய சாசன இயல் (ஷெ. 161-252)		
ஆராய்ச்சிக் குறிப்பு (தமிழ்) (க-உஉ௦)		
முதலாம் இராஜராஜன்	...	(1)
முதலாம் இராஜேந்திர சோழன்	...	(23)
இராஜேந்திரனை யடுத்துப் பட்டம் பெற்றவர்கள்	....	(39)
அதிராஜேந்திரனும் முதற் குலோத்துங்க னுடைய முடிசூட்டும்	...	(76)
முதற் குலோத்துங்க சோழன்	...	(105)
இலங்கை விவகாரம்	...	(118)
மூன்றாம் பராந்தகனும் விக்கிரமசோழனும்	...	(128)
இரண்டாம் குலோத்துங்கனும் இரண்டாம் இராஜராஜனும்	...	(137)
இரண்டாம் இராஜாதிராஜனும், மூன்றாம் குலோத்துங்கனும்	...	(146)
பாண்டியர் தாயாதிச் சண்டை	...	(151)
தாயாதிச் சண்டையின் விளைவு	...	(168)
குலோத்துங்கன் வாரங்கல்மீது படையெடுத்துச் சென்றது	...	(169)
மூன்றாம் குலோத்துங்க சோழனும் இரண்டாம் பல்லாள தேவனும்	...	(176)
பெருட்குறிப்பகராதி	...	(193)
ஸ்ரீ இராமாதுஜர் காலத்தைப்பற்றிய ஒரு குறிப்பு	...	(221)
பிற்குறிப்பு	...	(242)

தமிழ்நாட்டுச் சாசனங்கள் (பக்கங்கள் ௨௪௩-௩௮௬)

1. சாசனங்கள்	...	(243)
2. பழைய சரித்திர நூல்கள்	...	(249)
3. சரித்திர ஆதாரங்களும் சாசனங்களும்	...	(259)
4. இலக்கிய சாசனங்களும் சரித்திரக் கல்வெட்டுகளும்	...	(274)
இலக்கிய சாசனங்கள்	...	(274)
சரித்திரக் கல்வெட்டுகள்	...	(282)
5. சாசன வகைகள்	...	(287)
6. மத சம்பந்தமான சாசனங்கள்	...	(295)
7. உலகவாழ்க்கை பற்றிய சாசனங்கள்	...	(307)
8. போலிச் சாசனங்கள்	...	(317)
9. சாசனங்களைப் பொறித்திருக்கும் பொருள்கள்		(324)
உலோகம்	...	(324)
தங்கம்	...	(324)
வெள்ளி	...	(325)
பித்தளை	....	(326)
வெண்கலம்	....	(327)
செம்பு	....	(327)
இரும்பு	....	(333)
உலோகம் அல்லாதவை	....	(334)
பளிங்கு	....	(334)
செங்கல்	....	(335)
களிமண்ணும் சுட்ட மண்ணும்	....	(336)
மண்பாண்டம்	....	(337)
மரம்	....	(338)
கருங்கல் பாறை	....	(340)
சங்கு, தந்தம், முதலியன	....	(345)
எழுதுவதற்கு உபயோகிக்கும் வேறு		
பொருள்களைப் பற்றிய குறிப்பு	....	(345)
பனை ஓலை	....	(345)
பூர்ஜ பத்திரம்	....	(348)
காகிதம்	....	(349)
பருத்தி நூல் துணி	....	(350)
தோல்	....	(351)
மசி	....	(351)

	பக்கம்
10. சாசனங்களின் அமைப்பு	.... (353)
மங்கல வாசகம்	.... (353)
தானம் வழங்கியவர்	.... (355)
தானம் பெற்றவர்	.... (357)
தான விவரம்	... (357)
முடிவு	.... (357)
எழுதுவோர்	.... (359)
பிரசஸ்தி புனைந்தவர்	... (361)
கையெழுத்து	.... (362)
முத்திரை	.... (364)
11. கல்வெட்டுகளில் காலம் குறிக்கும் முறை	... (367)
அப்தங்கள்	... (370)
எழுத்துக்களுக்கு எண் மதிப்பிடும்முறை	... (374)
பூதசங்கியை	... (377)
12. சில சாசன வழக்காறுகள்	... (379)
சாசனங்களின் பதிப்பைப்பற்றிய குறிப்பு (ஆங்கிலம்)	(387)
,, (தமிழ்)	(388)

#### சாசனங்கள்

(தஞ்சாவூர் ஜில்லா) , கண்டிபூர்	1265—66	1295—96
(திருச்சிராப்பள்ளி ஜில்லா) ஸ்ரீரங்கம்	1267—69	1296—1301
(தென் ஆர்க்காடு ஜில்லா) சிதம்பரம்	1270—73	1301—24
(செங்கற்பட்டு ஜில்லா) செங்கற்பட்டு	1274—79	1325—43
காஞ்சீபுரம்	1280—97	1343—73
ஸ்ரீபெரும்புதூர்	1298	1373—75
(மதுரை ஜில்லா) கதிரி	1299	1375—76

#### பிற்சேர்க்கை I

பின்னல் கிடைத்த மூன்று

சாசனங்களின் மூலபாடங்கள்	1256—58	1377—84
-------------------------	---------	---------

பிற்சேர்க்கை II	
குறிப்பும் திருத்தமும்	1385
பிற்சேர்க்கை III	
சாசனச்சொல் அகராதி	1387
பிற்சேர்க்கை IV	
தமிழ் எழுத்துக்களின் வரிவடிவ வளர்ச்சி (ஆங்கிலம்)	1499—1510
[படங்கள்	
தமிழ்நாட்டுப் பிராமி எழுத்துக்கள்	1512
பிராமியும் பழைய கிரந்தமும்	1518
கிரந்த எழுத்துக்கள்	1532—33
தமிழ் எழுத்துக்கள்	1540—41
வட்டெழுத்துக்கள்	1548—49
கலப்பு எழுத்து	1560
எண்கள்	1565]
பிற்சேர்க்கை V	
சாசனச் சொல் அகராதி (ஆங்கிலம்)	i-xcvi
பொருட்குறிப்பகராதி (ஆங்கிலம்)	xcvii-civ
" (தமிழ்)	cv-cxii

---

['ஆராய்ச்சிக் குறிப்பு' பகுதியில் ௨௯ முதல் ௨௯௯ வரை  
யில் பக்க எண் தொடர்பு விட்டுப் போயுள்ளது. ஆனால்  
விஷயத் தொடர்பு விட்டுப் போகவில்லை].

---

## HISTORICAL SURVEY

(continued from page xcvi of the first part)

It may be said that the history of the Chōlas rests on surer grounds from the time of Rājarāja I; yet there are still many points which require elucidation.

### *Rājarāja I*

The present collection contains about fifteen inscriptions of Rājarāja I with dates going up to the 27th as his highest regnal year.

Many of his inscriptions which do not have the *meykkīrtti* beginning with the words *Tirumagalpōla* commence with a shorter title *Kāndaḷūr-śālai-k-kalam-aruttarūḷiya* or merely *Śālai-k-kalam-aruttarūḷiya* preceding the name of the king. The earliest mention of this is found in the records of his fourth regnal year. This was perhaps the first military achievement of his reign and he probably also considered this as one of his important victories.

The exact nature of this achievement has been the subject of much discussion. It would be interesting to note that this phrase was originally translated as '(The king) was pleased to build a jewel-like hall at Kāndaḷūr'<sup>1</sup> and this was later corrected as '(The king) was pleased to cut the vessel at Kāndaḷūr.'<sup>2</sup> It was finally revised as '(The king) was pleased to destroy the ships at the roadstead of Kāndaḷūr.'<sup>3</sup> This is now the prevailing view. There is also one other explanation taking the phrase to refer to the feeding-house at Kāndaḷūr. One scholar<sup>4</sup> takes it that the king discontinued the feeding in the feeding-house at Kāndaḷūr

---

1. *S.I.I.*, vol. I, p. 65.

2. *Ibid.*, vol. II, pp. 35, 47, etc.

3. *Ibid.*, pp. 241, 250.

4. T. A. Gōpinātha Rao in the *Travancore Archaeological Series*, vol. II, pp. 3-4.

while another<sup>1</sup> takes it to mean that the 'scale of feeding in the feeding-house of Kāndaḷūr was regulated by the king.' This explanation referring it to a feeding-house has been brushed aside as far-fetched.

This achievement of the Chōḷa king at Kāndaḷūr, whatever its nature might have been, is claimed not only by Rājārāja I, but also successively by his son Rājendra I and grandson Rājādhirāja I as well as by Kulōttuṅga I and the Pāṇḍyan king Jaḷavarman Parāntaka Pāṇḍya. An inscription<sup>2</sup> from Tiruvāṇḍārkōyil near Pondicherry dated in the 10th regnal year of Rājendra Chōḷa I having the *meykkīrtti* commencing with the words *Tirumanni valara* mentions this victory at the end of the *meykkīrtti*, just before introducing the name of the king (*taṇḍār-chālai-k-kalam-arutta Kō-p-Parakēsari*)<sup>3</sup> along with two other events relating to the southern portion of the country, viz., 'the construction at Madurai in the Pāṇḍi-maṇḍalam of a huge palace (*māḷigai*) as an ornament to the whole world and the consecration of his son with the title Śōḷa-Pāṇḍya.'

The *meykkīrtti* of Rājādhirāja I beginning with the words *Tiṅgaḷēr-taru*<sup>4</sup> mentions that the king performed the feat of 'śālai-k-kalam-aruttal at Kāndaḷūr on the never decreasing ocean.'

The *Vikramaśōḷan-ulā*<sup>5</sup> describes Kulōttuṅga I as the king 'with the army which routed the carp of the enemy (Pāṇḍya), destroyed the bow (emblem of the Chēra) and twice achieved the

---

1. S. Dēśikavināyakam Piḷḷai in *Kerala Society Papers*, Series II, pp. 100 ff; see also his brochure *Kāndaḷūrśālai*.

2. No. 363 of 1917.

3. *An.Rep. on S.I.Epigraphy*, 1918, p.144; *The Cōḷas*, vol.I, p.552

4. *S.I.I.*, vol. III, p. 56.

5. *Vikramaśōḷan-ulā*, kaṇṇi 24,

—*mēvalar-tam*

*śēlai-t-turantu-śilaiyai-t-taḍind-irukāl*

*Śālai-k-kalam-arutta taṇḍināṇ*



feat of *kalam-aruttal* at Śālai'. The *Kaliṅgattuṣṣaraṇi*<sup>1</sup> confirms this when it puts the words, "was it not with the army that Viḷiṇam on the sea was destroyed and Śālai captured?" as addressed to Anantavarman, the king of Kalinga, by one of his ministers.

The Kanyākumari inscription<sup>2</sup> of the Pāṇḍya king Jaṭavarman Parāntaka Pāṇḍya, who is considered a contemporary of Vikrama Chōḷa, mentions in the *meykkīrtti* commencing with the words *Tiru vaḷara-ch-cheyam vaḷara* with which it opens, that he gained his maiden victory in his achievement of *Kāndaḷūr-ch-chālai-k-kalam-aruttal*. It is possible that this victory was gained by him on behalf of the suzerian power, the Chōḷa.

It will be seen from the above that the achievement of *śāli-a-k-kalam-aruttal* at Kāndaḷūr, whatever it might have been, had to be carried out by the successive Chōḷa kings during the course of the period of nearly one and a half centuries and that military force had to be employed on every occasion to gain the object.

And Kāndaḷūr appears to have been an important place even from earlier times, as the Muttaraiya chief Śuvaran Māran, a contemporary of the Pallava king Nandivarman Pallavamalla in the eighth century A.D. is eulogised in his inscriptions to have gained a victory at this place.<sup>3</sup>

Of the four words, *Kāndaḷūr*, *śālai*, *kalam* and *arutta* making up this short phrase, excepting the first one Kāndaḷūr denoting the name of a place, every one of the other three words is capable of being interpreted in more than one way. But it must be

---

1. *Kaliṅgattu-ṣṣaraṇi*, tāḷiśai 370,  
vēlai koṇḍa Viḷiṇam-aḷittadum  
Śālai koṇḍadum taṇḍu koṇḍ-allavō !

2. *Trav. Arch. Series*, vol. I, pp. 18. ff.

3. *Sendalai Pillar Inscriptions* in the *Ep. Ind.*, vol. XIII, No. 10, p. 146.

admitted that the words *śālai* and *kalam* were used respectively to mean 'a feeding house' and '(eating) plate' and the use of the word *śālai* in the sense of a 'roadstead' in those days is not known in any other context. Kāndaḷūr has been identified with a part of Trivandram now called Valiya Śālai.

A copper-plate grant<sup>1</sup> registering the establishment of a *śālai* at Pārthivaśekharaapuram on the model of the one at Kāndaḷūr by the Āy king of Vēṇāḍu, Karunandaḍakkan in A.D. 866 perhaps gives the clue for the elucidation of the nature of this achievement. This inscription, of which only five plates are now available with some of the intervening plates missing, is couched in terse language and though incomplete still contains sufficient materials to proclaim its importance which has not been properly appraised.

The very fact that the *śālai* at Pārthivaśekharaapuram was created on the model of the one at Kāndaḷūr would indicate that the *śālai* at Kāndaḷūr was very famous and served as a model in those days and that even though we do not have full particulars of the *śālai* at Kāndaḷūr, we have the details of a similar institution at another place.

The inscription states that the chief acquired gradually cultivable lands in exchange of other lands from the *sabhā* of Minchirai, fixed its boundaries, erected a temple for Viṣṇubhaṭṭāraka on it, named the village as Pārthivaśekharaapuram and established a *śālai* on the model (*maryādi*) of Kāndaḷūr, for ninety-five *śaṭṭar*. What interests us in the record is the portion giving the particulars of the *śālai* "Of the seats (*kalam*) provided in in this *śālai*, forty-five *kalam* are for the members of the *Paviḷiya charaṇa*; thirty-six *kalam* are for the members of the *Taittiriya-charaṇa*; fourteen *kalam* are for the members of the *Talavakāra charaṇa*." The total of ninety-five seats provided is thus arrived at. It is further stated that future seats should be likewise for the three *charaṇas*.

---

1. The Huzur Office Plates, *Trav. Arch. Series*, vol. I, pp. 1-14.

“Conditions for admission: One who gets a certificate on oath by five *śaṭṭar* (*pañchakkam*) that he is proficient in *Vyākaraṇa*, *Mīmāṃsā* and *Paurohitya*, that he is free from the fault (*puviśram?*) of forgetfulness, and that he has the knowledge or learning (*ōttu*) necessary for the affairs of the three kingdoms (*trairājya vyvahāra*) will get admission.” Then comes the condition or mode of keeping afresh what these *śaṭṭar* have already learnt of the several branches of learning from forgetting by resorting to the method of *vāram* recitation. After this the following is found mentioned.

“If a *śaṭṭan* speaks abusively of another *śaṭṭan* within the precincts of *mukkāl-vaṭṭam* (i.e., a temple) he shall eat in the *śālai* after paying a fine (*daṇḍam*) of five *kāṇam* of gold to the elders (*perumakkal*). If he strikes (*kuṭṭu*) he shall take his meals in the *śālai* paying a fine of one *kāśu*. He that is struck also shall take his meals in the *śālai* paying a fine of five *kāṇam* of gold. He who makes a wound with a weapon of warfare (*paḍaikkalam*) shall be outside the pale of the right conduct (*aram* or *dharma*). The *śaṭṭar* shall not go to the assembly armed with weapons of warfare.....

“.....no kind of deceit shall be practised. They shall not fight within the precincts of *mukkāl-vaṭṭam* (temple). Those that fight shall lose that day's *kalam*. *Śaṭṭar* shall not keep the *vellāṭṭigal*<sup>1</sup> (maid servants) in the *maṭha*. They shall not alienate (the lands of) the *śālābhōga* and the *dēvadāna*. Those that alinate shall not take their meals in the *śālai* without paying a fine of five *kaḷaṇṇu* of gold individually. Amount (*mudal*) collected by force (coercion) from tenant in the *śālābhōga* and *dēvadāna* shall be returned tenfold. Those that owe the taxes (payable) to the *sabhā*, shall be bound by the decision arrived at by three (*śaṭṭar*) representing the three *charaṇas*. If the decision is transgressed, a fine of fifty-four *kāṇam* of gold shall be paid and also the tax-dues paid. They shall not stop (remove) on any excuse

---

1. This word has in later days come to connote a concubine also,

the daily routine of worship of the god (*dēvar-śennāḍai*) and the *śālai* of ten-*nāli*. Those that stop shall not eat in the *śālai* without paying a daily fine of one *kaḷañju* of gold. The servants (*paṇimakkal*) who speak abusively of the *śaṭṭar* shall become subject to a fine of one *kāśu*."

It will be seen from the above that the *śālai* at Pārthivaśēkharapuram, as also the one at Kāndaḷūr on the model of which the other was established, was a *pāṭhaśālā*, more or less in the nature of a free residential university of modern conception. It was an autonomous institution, the entire control of which vested with the *śaṭṭar* of a fixed number who composed the institution.

The word *śaṭṭar* is derived from the Sanskrit *chāṭtra* and generally taken to mean a student.<sup>1</sup> But a reference to the context in the present inscription will show that the word does not mean a mere pupil. Here we find the *śaṭṭar* highly proficient in at least three branches of learning, viz., *Mīmāṃsā*, *Vyākaraṇa* and *Paurōhitya*, in addition to the *Vēda* and vested with the management of the entire properties of not only the *śālābhōga*, but also the *dēvadāna* of the temple attached to the *śālai*. It would therefore appear that the *śaṭṭar* were the teachers placed in charge of the institution rather than the pupils.

The famous Enṇāyiram (South Arcot district) inscription<sup>2</sup> of the time of Rājendra Chōḷa I registering the arrangements made for the feeding of the pupils and the remuneration of the teachers of a college there by the *sabhā* of Rājarāja-chaturvedimaṅgalam in accordance with the terms of an order made by the king himself is also helpful in this connection. It provides for two hundred and seventy *brahmachāris*, seventy *śāṭṭirar* and fourteen professors. Each *brahmachāri* was allowed six *nāli* of paddy per diem while a *chāṭtra* had an allowance of ten *nāli*.<sup>3</sup>

1. *Tamil Lexicon*, s.v. *Caṭṭan*.

2. No. 333 of 1917.

3. The Pārthivaśēkharapuram record also provides ten *nāli* of grain per diem to every *Śaṭṭar*.

Among the professors, the teacher of Vēdānta got the largest daily allowance in grain of one *kalam* and three *kurun̄is*. The *nambis* who taught the Mīmāṃsā and Vyākaraṇa got one *kalam* each and the others only three *kurun̄is* per diem. Besides these daily allowances of grain, all the professors and *chāttaras*, except the professor of Vēdānta<sup>1</sup> got other allowances in gold as remuneration for teaching—at the rate of one *kaḷaṇ̄ju* per *adhyāya* taught in the case of Vyākaraṇa and Mīmāṃsā, thus entitling the teachers to 8 and 12 *kaḷaṇ̄jus* respectively for a whole course, and a half *kaḷaṇ̄ju* per head per annum for the rest.<sup>2</sup> It will be seen from the above that the *chāttara* had to do teaching in the institution.

This interpretation of the word *śaṭṭar* as not a mere pupil, but also a teacher is strengthened by another inscription of about the same period of the Pārthivaśēkharapuram record. This inscription<sup>3</sup> from Kāvērīppākkam in the North Arcot district dated in the 25th regnal year of the Pallava king Nripatun̄gavarman (circa A. D. 886) registers the gift of gold for the provision of oil for lamps and the endowment was placed in charge of the *maḍattu śaṭṭa-p-ṣerumakkal* which means a group of scholars of the *maṭha*. That *śaṭṭar* were living in *maṭhas* is also referred to in the present plates. And the *Amarakōśa* says: 'maṭhaschhātrādi nilayah'—a *maṭha* is an abode for the *chāttaras* and others.

It would therefore seem that a *śaṭṭa* was an eternal *brahmachāri*, wedded to life-long study and teaching with no other worldly attachment. The picture of sage Kaṇva as presented by Kālidāsa in his immortal epic *Śākuntalam* may be taken as the picture of a *śaṭṭa*. Kaṇva was a teacher, *kulapati*, having with him many students residing in his *āśrama* and studying under him. It was there that Dushyanta met Śākuntalā. When he

---

1. Vēdānta should not be taught for money consideration. It was evidently for this that no cash allowance was provided for him. This probably accounts for the largest grain allowance to him.

2. *An. Rep. on S.I. Epigraphy*, 1918, para 28.

3. *S.I.I. (Texts)*, vol. XII, No. 79.

enquired who she was, her friend replied that Śakuntalā was the daughter of the sage Kaṇva. This reply astonished the king and he was made to ask wondering how could that be when the sage was a life-long *brahmachāri*.

Besides these colleges which provided for higher education in various branches of study for a large number of students living with the teachers under the same roof, there were numberless little endowments for the pursuit of particular branches by a smaller and limited number of students under the guidance of individual teachers, of course providing free boarding and lodging. A careful study of the inscriptions where the terms *śālai* and *śālābhōgam* occur would show that they denoted not the mere feeding-house and the landed property attached to it, but the feeding-house attached to an educational institution.

We need not go into the several interesting pieces of information furnished by this charter which deserves a critical edition afresh. What interest us in this charter are the statements (1) that the *śaṭṭar* should be well-versed in the learning necessary for the affairs of the three kingdoms, (*trairājya vyavahāra*) meaning evidently the three traditional kingdoms of the Chēra, the Chōḷa and the Pāṇḍya and (2) that they were allowed the use of the weapons of warfare with certain restrictions. These would imply that the institution provided instruction, both theoretical and practical, to those studying there in the arts of warfare and administration of the country. We know that the civil and military aspects in the administration of a country were not separate as now and that both these functions devolved on an administrator in those days. It may even be said that an administrative officer of some rank without any military knowledge and experience was inconceivable in those days. It will be evident from the above that the *śālai* at Pārthivaśekhara-puram and likewise the one at Kāndaḷūr, were residential institutions imparting advanced courses of study, both in theory and practice, in the administration of the country both in the civil and the military branches of government. These were of the sort of Staff College or Administrative Training Institution of an

advanced type, not dependent on the government of the country or of the day, but autonomous of independent and sufficient means. That the *ghatikā* at Kāñchīpuram, to the existence of which we have references as late as the middle of the ninth century A.D., was imparting similar instructions at an earlier date would be evident from the fact that Mayūraśarman who sought admission to it as a *tārkuka* with his preceptor Viraśarman 'desirous of learning the entire *pravachanam*' was able, when he had a quarrel with the Pallava 'horseman', to wield the flashing weapons of warfare with the hand accustomed to handle the *kuśa* grass and other sacrificial oblations and carve out a kingdom of his own.<sup>1</sup>

There are also other evidences which support the above surmise. *Anantapura-varṇanam*<sup>2</sup>, a classical work in Malayalam of the fourteenth century A. D., depicting the sacredness and greatness of Anantapura or Trivandrum refers to the existence of a college of advanced Vedic studies at Kāndaḷūr, forming part of the city, as also to the proficiency of the scholars thereat in the use of the weapons of warfare.

In Kēraḷa, there is still performed a folk-play called *chāttira-k-kalī* in which the display of swordsmanship by the actors, who are the *Nambūtiris* of some specified families, forms an important function.<sup>3</sup> The participants (actors) have also to perform at an earlier stage of the play the recitation of some verses known as *nālu-pādam* (four feet or quarters) in the manner of reciting the *Sāmaveda*. The Pārthivaśēkharapuram record above referred to also mentions in the portion describing the mode of *vāram* recitation, *nālu-pādam* and the *ahattūham* of the *Sāmaveda*.

---

1. *Ep. Car.*, vol. VII, Sk. 176; *Ep. Ind.*, vol. VIII, No. 5.

2. *Anantapura-varṇanam* (Travancore University Language publication No. 81), vv. 106 ff. Sri K. N. Eḷuttachchan of the Malayalam department of the Madras University kindly drew my attention to it.

3. I am indebted to Dr. S. K. Nayar, M.A., PH.D., Head of the Malayalam department of the Madras University for this information. He allowed me a perusal of his doctorate thesis, *The Folk-drama of Kēraḷa* (in manuscript) wherein the details in the performance of this play are described.

From the foregoing discussion, it will be seen that we may not be far wrong if we take the *śālai* at Kāndaḷūr as an educational institution of an advanced type imparting among others instructions in political and military sciences. That such an institution existed is testified by the references in the inscriptions to the *Trairājya-Ghaṭika-Madhyasta*—arbitrator of the College (*Ghaṭikā*) of *Trairājya*.<sup>1</sup>

What was the nature of the victory gained by the Chōḷa at Kāndaḷūr is not clear. But the phrase *kalam-aruttu* occurs in another inscription at about the same period in a different context. An inscription<sup>2</sup> dated in the 14th regnal year of Rājakesari-varman from Kōyil-Tēvarāyanpēṭṭai in the Tañjāvūr district registers the endowment of twenty *kāśu* by a brāhmaṇa to the temple of that place, from the interest of which amounting to three *kāśu* per annum, a prize has to be given a person who comes out successful in the competition of reciting the *Sāma-veda* of the Jaimini School on the night of the *ārdra* day in the month of Mārgaḷi every year. This record has the following: *orukār koṇḍār-allādārai meykkāṭṭu-t-tiṭṭinār ellārum tammil aṇju-puriyilum śolli-k-kalam-aruttu nallār-ānār-oruvarku vridhhiyāna i-k-kāśu mūṇrum i-t-tēvarē kuḍuppārāga*.

It is stipulated therein that persons who have once obtained the prize should not compete in the succeeding years. The winner in the contest is described therein as *kalam-aruttu nallār-ānār oruvar*. It will be seen therefrom that the phrase *kalam-aruttu* has been used in this inscription in the sense of having gained a victory defeating the opponents. Literally, the phrase may be translated as 'determining the rights' or 'regulated by the document (charter).'

Adopting this interpretation, one would be tempted to take that Rājārāja entered into a competition of reciting the Vedic lore or a contest of a literary nature in some branch of learning

1. *Annual Report on the South Indian Epigraphy*, 1916, para 8.

2. *S.I.I. (Texts)*, vol. XIII, No. 250.



with the members of the *śālai* at Kāndaḷūr and came out victorious. This could not have been impossible as the Chōlas claimed a *kshatriya* lineage of the solar race entitling a study of the Vēdas for them and as Rājādhirāja, his grandson, is known to have performed the *aśvamēdha* (horse-sacrifice). But the mention, as pointed out already, of the fact that military force was employed in achieving this feat precludes the possibility of such a postulation.

Then the nature of the victory gained by the king over the institution with the aid of army needs an explanation. Perhaps it will become apparent from the very nature of the institution.

It is possible that Rājarāja, when he formulated his plan of the Chōla expansion and began to pursue from the very commencement of his reign the policy of extending the borders of his dominion and founding an empire, might have come into conflict with the members of this academy even from the beginning. He might have thought that he could not achieve his object unless he had the *śālai* under his control and its members made to follow his line of thought. The *śālai* being an autonomous institution with its own finances would not have easily submitted itself to the wishes of the Chōla monarch: but tried to resist with its own militia any outside control of its policy and internal affairs. That was probably the reason why Rājarāja had to use force in getting control over it.

It appears that the Pallava kings had also some occasions to interfere with the administration of the *ghaṭikā* at Kāñchi. The Vēlūrpālaiyam plates state that Skandaśishya, the grandson of Virakūrcha, the founder the Pallava line of kings at Kāñchi, seized the *ghaṭikā* from Satyasēna. (Skandaśishyas-tato bhavad-dvijānām *ghaṭikām* rājñāḥ Satyasēnaj-jahāra yaḥ) <sup>1</sup> The verb 'jahāra' implies that the Pallava king seized it from an enemy. The same grant later on says that Rājasimha reorganised the *ghaṭikā* of the twice-born (tat-putra sūnur-Narasimhavarmā punar vyadhādyō *ghaṭikām* dvijānām). <sup>2</sup> The Talagunḍa pillar inscrip-

1. S.I.I., vol. II, p. 508; lines 12-13.

2. *Ibid.*, lines 19-20.

tion<sup>1</sup>, above referred to, also implies that the Pallava king had some sort of control over the *ghaṭikā* there, as we find Mayūraśarman directing his wrath on the king. That the members of the *ghaṭikā* had also some voice in the administration of the country will be evident from the Vaikuṇṭha-perumāl temple inscription<sup>2</sup> from Kāñchīpuram mentioning the *ghaṭikaiyar*, the members or representatives of the *ghaṭikā*, as included in the deputation which waited on Hiraṇyavarman, the father of Nandi-varman Pallavamalla, to allow his son accept the Pallava crown.

One other factor should also be noted in this connection. The characters of the copper-plate grant recording the creation in A.D. 866 of the *śālai* at Pārthivaśekharapuram by Karunandaḍakan, the Āy king of Vēṇāḍu, and the regulations for the conduct of the same are somewhat later than the period to which they purport to belong. Palaeographically, the grant may be assigned to the time of the Chōḷa king Rājarāja I and the very fact that it is written in the Grantha-Tamil script and not the Vaṭṭeḷuttu script which was prevalent in the area before its occupation by the Chōḷas lends support to it. Again, in the earlier portion of the grant mentioning the purchase of lands by exchange from the *sabhā*, creation of the village, erection of the temple, establishment of the *śālai*, and the provision made for the daily routine of worship in the temple, the name of the ruler who is himself the donor, is found introduced in the third person and not in the first person as found generally in the other inscriptions of the period. The whole portion reads as if recording some past transaction.

The Vēṇāḍu chief who founded the *śālai* seems to have had the surname Śrīvallabha, probably in token of his subordination to the then Pāṇḍya monarch bearing that name. That he had the surname Śrīvallabha will be evident not only from the verse at the end of the grant couched in a double *entendre* so that the

---

1. *Ep. Ind.*, vol. VIII, No. 5.

2. *S.I.I. (Texts)*, vol. IV, p. 10; also *The Historical Sculptures of the Vaikuṇṭha-perumāl Temple* by Dr. C. Minākshi, (Memoirs of the Archaeological Survey of India, No. 63), p. 33.

verse might be applied to the praise of both the king and Viṣṇu, but also from the Tirupparappu (fragmentary set of) copper-plate inscription<sup>1</sup> where the scribe is described as Śrīvallava-p-perumbāṇaikan *alias* Aviyalaṇ-ṛaḍakkan of Viḷiṇṇam, the arms-manufacturer to the king Śrī-Karunandaḍakkar. The institution of Śrīvallava-p-peruñchālai referred to in an inscription<sup>2</sup> from Kanyākumari of the 30th regnal year of the Chōla king Rājādhiraṇḍa I probably refers to the same as that of Pārthivaśekharaṇḍapuram. *Peruñ-chālai* is only the Tamil term for *Mahāśālā* which refers to an educational institution imparting instructions to advanced students of the Vēdic school.<sup>3</sup> The same inscription refers to the institution as also Rājarāja-p-peruñchālai (*Śrīvallava-p-peruñchālai y-āna Rājarāja-p-peruñchālai*). This will mean that the educational institution originally founded by Śrīvallaḅha was also named after Rājarāja, probably in consideration of some connection of Rājarāja with the same. Evidently, he remodelled the institution and placed it on a firm footing and issued a fresh charter.

Possibly the *śālai* at Kāndaḷūr, which served as model for the one at Pārthivaśekharaṇḍapuram, was also taken over by Rājarāja I under his control and remodelled with revised regulations curtailing the military influence exercised by its members. It is evidently this achievement that is referred to in the *meykkīrtti*.<sup>4</sup>

1. *Trav. Arch. Series*, vol. I, pp. 199-200.

2. *Ibid.*, p. 163.

3. *Śrāvasti in Indian Literature*, pp. 14-15.

4. As already stated, the word *kalam* has got so many meanings. Even though, the use of the word *śālai* in the sense of a roadstead was not known in those days, the word *kalam* was certainly used then to denote a sea-borne vessel or ship. The *meykkīrtti* of Rājendra I, while referring to his Kaḍāram expedition, has the expression *alai-kaḍal naḍuvul pala kalam śelutti* (having despatched many ships in the midst of the rolling sea), where the word *kalam* can mean only a sea-borne vessel. That the Chōlas had a well organised and efficient naval fleet is well-known and can be attested by their conquests in distant lands beyond the seas. There is a canal in the Tirutturaip-pūṇḍi taluk of the Tañjāvūr district known as *Marakkala-k-kōrai-yāru*. It is a blind canal running inland for about ten miles from the lagoon,

A stone record<sup>1</sup> from the Virattānēśvara temple at Kīlūr near Tirukkōvalūr dated in the 27th regnal year of Rājarāja I ascribes

It would be apparent from the name of the canal that it should have served as a wharf to berth the sea-borne vessels in those days.

It is possible to make out from a reference found in the *Kulōt-tuṅga-śōlan pillai-t-tamil* (verse 91) that pearl-fishing operations were being conducted at Kandaḷūr in those days.

‘taṇḍil Viḷiṇa-t-t-eyil  
tahart-t-uḍaiya muttu-ch  
chalāpa muḷudum Poraiyaṇ  
Śalai-y-oḍu koṇḍāy’

“You (who) with the army destroyed the fort at Viḷiṇam and obtained the entire (proceeds of) the pearl-oysters with ‘the śālai of Poraiyaṇ, i.e., the Chēra.’” Pearl-fishing appears to have been conducted even in the west (Malabar) coast in those days. This seems to have continued even as late as the 17th century A.D. as recorded by John Fryer who travelled in those parts between 1672 and 1681 A.D.

“They (*sic.* pearls) are also found between Cape Comory and Ceilon as I formerly declared; but these are not to be compared with the Persian, which are the true Oriental ones: They are of them in the Island Sumatra, by those that place the Golden Cheronese in Java, disputed to be the Ancient Taproban. Betwixt greater Java and India, there are very many; between Panana and Cochin are good store, but very small, as also all along the Coast of Malabar.” (John Fryer's *East India and Persia*, vol. II, published by the Hakluyt Society, Second Series, vol. XX, p. 365.)

It might be that Rājarāja did not want the pearl-fishing to be conducted on the west coast by the Chēras, but confined to the east coast to be operated by the Pāṇḍyas. Or it is also possible that the vessels used for pearl-fishing might have out-grown and interfered with the normal shipping movement of trade in the Arabian sea, which we know was then invested with sea-pirates. But the use of the word śālai in the context precludes such an interpretation, at least in the days of Rājarāja, even though it might be possible to interpret it likewise in later days as we do not find the word *kalam* used and the place is referred to merely as śālai instead of Kandaḷūr Śalai, thus denoting that it had come to denote the place Kandaḷūr as well then.

1. S.I.I. (Texts), vol. VII, No. 863; also *Sen Tamil*, vol. IV, p. 231.

the titles *Narapati*, *Aśvapati* and *Gajapati* to him. *Gajapati* is the well-known title of the Kalinga kings. We also know that in later days the title *Narapati* was borne by the Vijayanagara rulers. Prior to them, the Western Chālukyas of Kalyāṇa appear to have borne that <sup>1</sup>. It has already been pointed out in an earlier page<sup>2</sup> that the Sēuṇas of Dēvagiri had used the third one, *Aśvapati*. This title was also borne by the Gūrjaras and the kings of Mālava. We know that Rājarāja had gained victories over the Western Chālukya and the Kalinga kings entitling him for the titles *Narapati* and *Gajapati*. Similarly, it may reasonably be assumed that he should have had some victory or power over the Mālava ruler to entitle him for the other title *Aśvapati*. The Udaipūr *praśasti*<sup>3</sup> of the Paramāra rulers of Mālava states that Vākpati (II) Muñja, the uncle of the celebrated Bhōja, gained a victory over the Chōḷa king.

Karṇāṭa-Lāṭa-Kērala-Chōḷa-śiro-ratna-rāgi pada-kamalaḥ  
yaś ca praṇayi-gaṇārthita-dātā kalpadrumapraḥyaḥ.

“He whose lotus feet were covered by the jewels on the heads of the Karṇāṭas, Lāṭas, Kēralas and Chōḷas and who possessed a fame of a tree of paradise, since he granted to a crowd of supplicants whatever they desired.”

Vākpati who came to the Mālava throne in *circa* 975 A.D. is said to have defeated Tailapa, the Western Chālukya ruler six times; but was finally captured by Tailapa on the seventh occasion and beheaded. Rājarāja who was an inveterate enemy of the Western Chālukya would certainly have joined hands with the Mālava ruler in crushing Tailapa from both sides. This suggestion gains more force from the statement in the *Koṅgu-dēśa Rājākaḥ* that Rājarāja I gained many victories in the Narmadā regions :

1. *The Inscriptions of Nagai* (Hyderabad Archaeological Series, No. 8), p. 6.

2. Page lii of part I above.

3. *Ep. Ind.*, vol. I, p. 237, verse 14.

"When Bhīma(rāya) heard this news (that the general of Rājārāja had obtained great victories and became very famous in the world planting pillar of victory in the western regions) he came to war and (the general) won him in the battle and killed his son. Thereafter, he went to Kalinga for war and receiving tribute from its king, he proceeded to the Narmadā region. In those countries he gained victory over many kings and planted a pillar of victory in the Narmadā regions and another pillar of victory with the tiger-emblem in the southern direction on the Mahēndragiri hill. At that time, he conquered Vaidumba(rāyan), Kāmārṇava(rāyan), Dānapālliya Bhīma(rāyan), Amma(rāyan) and other kings and received from them many ornaments, riches and harem-women and the like as tribute, as also an image (*bhāva-pratimā*) in gold of the likeness of Bhīma(rāyan) after which he returned with his army and met the king."<sup>1</sup> Bhīma above referred to could be no other than the Telugu Chōḍa chief Jaṭā-Chōḍa Bhīma and Kāmārṇava, the Eastern Gaṅga ruler of Kalinga. It is also seen that Rājendra, the son and successor of Rājārāja was a confederate of Bhōja in his wars with the Western Chālukyas as will be discussed below.

### *Rājendra I*

There are about twenty inscriptions of this king in the present collection ranging between the 3rd and 31st years of his reign. Some of the records have the *meykkīrtti* beginning with the words *Tirumanṇi vaḷara*; but the shorter title *Pūrvadēsamum Gaṅgaiyum Kaḍāramum koṇḍa* found in some of his inscriptions is not met here.

The important event of his reign was his expedition to the Ganges. The inscription of his 11th regnal year mentions this expedition; but the detailed account of the campaign first appears only in his twelfth year inscriptions. Judging from the records, the duration of this expedition might be taken as about two years. The Tiruvālaṅgāḍu plates say of this expedition: "The light of the Solar race (Rājendra), mocking Bhagīratha who by

1. *Koṅṇudēsa Rājakkal* (Madras Govt. Oriental Series, No. VI), p. 15.

the force of his austerities caused the descent of the Gaṅgā, set out to sanctify his own land with the waters of that stream brought (thither) by the strength of his arm.”<sup>1</sup>

At the end of the expedition he erected, according to the same source, a ‘liquid pillar of victory’ (*jalamayam jayastambham*) in his capital with the waters of the Ganges in the form of the tank *Chōḷagaṅgā*. And he also assumed the title *Gaṅgaikoṇḍa Chōḷa* at the same time and constructed a city called *Gaṅgaikoṇḍa śōḷapuram* which became his capital and continued as such even under his successors for about two centuries thereafter.

It is generally taken that this feat of Rājendra was more in the nature of a *digvijaya* and “an exhibition of the Chōḷa empire and a demonstration of its strength to the rulers of Northern India” than as a mere pilgrimage to the Gaṅgā.

To have a correct perspective of the expedition and its results it is necessary to know the time and the manner in which it was undertaken and the references to the victories gained in Northern India in the *meykkīrttis* of his sons as well.

It was at this time that the Northern India was subjected to the frequent, almost annual, raids of the Muslim ruler, Mahmud of Ghazna. His ponderous forces with ‘an innumerable host of foot,’ hundred-thousand cavalry and many elephants marched on Hindustan like foaming torrents. He aimed more on the plunder and getting as much money and valuables as possible than ‘the conquest of the infidels’ and spread of Islam. The kings of the North who were directly affected by his invasions or were liable to his attacks appear to have joined together and resisted his incursions; but their resistance was not sufficient to stem his advances and every year he was directing his attention on some new area whose ruler joined the confederation of kings opposing him.

---

1. *S.I.I.*, vol. III, No: 205, v. 109

Rājyapāla was the king of Kanyākubja or Kanauj at this time. He also seems to have helped his brother-kings in warding off the Muslim incursion. So he also had to face an invasion of Mahmud on his kingdom in A.D. 1018. When the Muslim army arrived before the gates of the city of Kanyākubja, Rājyapāla became panic-stricken and fled across the Ganges to Bāri, without serious resistance even though his capital held a very strategic position. Meeting with no opposition, the invader took the entire kingdom in one day and gave licence to his soldiers to plunder. The temples were destroyed and many of the inhabitants were slain. It is said that at the end of the campaign Mahmud returned to Ghazna laden with a large booty.

This cowardly action of Rājyapāla enraged the neighbouring rulers, who, on the departure of the invader, formed under the leadership of a monarch whose name as found in the Muslim sources has been variously read as Ganda, Nanda or Bida, a confederacy to punish Rājyapāla. It has been established beyond reasonable doubt that Vidyādhara, the Chandella ruler of Kālāñjara was the leader of the confederacy.<sup>1</sup> The names of the other rulers who joined the confederation are nowhere found.

Vidyādhara who was entrusted with the command was able to achieve his purpose. Rājyapāla was killed in battle and his son Trilōchanapāla was installed on the throne. When Mahmud received advice of this 'he was furious' and determined to chastise the miscreant rulers for their audacity. He accordingly again came on Kanauj in the next year, *i.e.*, A.D. 1019. Unlike his father, Trilōchanapāla offered resistance; but was defeated in a surprise raid and he had to abandon Bāri, which had become a secondary capital, to the invader.

Mahmud next turned his attention to Vidyādhara who came to oppose him with a stupendous force. It is stated that he also

---

1. *Dynastic History of Northern India* by Dr. H. C. Ray, vol. II, p. 688.



became alarmed and "fled with some of his personal attendants leaving all his baggage and equipments."

But this seems to have been an inconclusive engagement. In 1021-22 A.D. Mahmud again marched on Kālañjara. Vidyādhara "then sent some verses which he had composed in the Hindu tongue in praise of the Sultan. The latter showed them to the eloquent men of Hindustan and other poets who were in attendance on him. They all praised them. The Sultan sent his congratulations and a mandate conferring the command of fifteen fortresses and other presents in return for them. Nandā (*i.e.*, Vidyādhara) also sent much treasure and precious gems for the acceptance of the Sultan."<sup>1</sup>

A study of the panegyrical accounts of the Muslim chroniclers would only lead to the conclusion that even after a long investment Mahmud could not capture Kālañjara and the campaign ended in a draw with mutual gifts and compliments.<sup>2</sup> And with this the invader seems to have given up his ambitions as regards the Gangetic valley.<sup>3</sup> Frustrated in the east, he subsequently turned his attention to Gūrjara which culminated in his notorious attack on Sōmanāthapura. The northern expedition of Rājendra Chōḷa I took place in the very year when Mahmud of Ghazna came down to chastise Vidyādhara and retired without achieving a complete victory. This expedition of Rājendra is described in his *meṃkkīrtti* as follows :

"(He seized) Śakkarakkōṭṭam, whose warriors were brave; Madura-maṇḍalam destroyed in a trice, the prosperous city of Nāmaṇaik-kōṇam with its dense groves, Pañchappallī whose warriors (bore) cruel bows, Māṣuṇi-dēśa with its green fields; a large heap of family-treasures together with many (other) treasures (which

---

1. *Tabaqat-i-Akbari*, translated by B. Dey in the *Bibliotheca Indica* Series, p. 14.

2. *The Imperial Gūrjaras* being Part III of *The Glory that was Gūrjaradēśa* by K. M. Munshi, pp. 134-5.

3. *Ind. Ant.*, vol. XXXVII, p. 142.

he carried away), after having captured Indraratha of the ancient race of the moon, together with (his) family, in a fight which took place (at) Ādinagar, a city whose great fame knew no decline; Oḍḍa-vishaya which was difficult of approach on account of its dense forest defence; the good Kōśalai-nāḍu, where Brāhmaṇas assembled; Taṇḍabutti, in whose gardens bees abounded, (land which he acquired) after having destroyed Dharmapāla in a hot battle; Takkaṇa-lāḍam whose fame reached (all) directions, and (which he occupied) after having forcibly attacked Raṇaśūra; Vaṅgāḷa-dēśa, where the rain water never stopped, (and from which) Gōvindachandra fled, having descended (from his) male elephant; elephants of rare strength, women and treasure, (which he seized) after having been pleased to put to flight in a hot battle-field the strong Mahipāla together with Śaṅgu who wore the anklet (of valour); Uttira-lāḍam (on the shore of) the expansive ocean (producing) pearls; and the Gaṅgā whose waters bearing fragrant flowers dashed against the bathing places (*tīrtha*)."<sup>1</sup>

Indraratha of the lunar race whom Rājendra is said to have defeated at Ādinagar is evidently the same as the opponent of Bhōja, the Paramāra king of Dhārā, mentioned in the Udayapūr inscription.<sup>2</sup> The Kulenūr inscription<sup>3</sup> of Jayasimha, the

1. K. A. Nilakanta Sastri: *The Cōlas*; vol. I, pp. 248-9.

2. *Ep. Ind.*, vol. I, pp. 223-38.

3. *Ibid.*, vol. XV, p. 333. Kundiga, a general of the king, who made the grant is eulogised as follows:

moneyoḷ Kundiga ninnan-endu perar-  
inn-e vaṇṇipar-ddāna-durd-  
dina-matt-ēbhadin-aṭṭu pettu raṇadoḷ  
benn-ittu dant-āhavakk-  
inisun-nillade tūḷdu pōda bhayadim  
benn-ittu bāy-viṭṭu Chō  
ḷana Gaṅgēyana Bhōjarājana gaja  
nikamṇaḷ-em pēlavē.

"O Kundiga, when they name thee in respect of courage what further praise can others give? Is it not what is said by the troops of elephants of the Chōḷa, Gaṅgēya and king Bhōja with open mouths as they flee away in the battle where they are pressed by (thy) elephants

Western Chālukya king, dated 1028 A.D. states that the king routed the elephant squadrons of the Chōla, Gāṅgēya and Bhōja-rāja. Another inscription<sup>1</sup> of the same monarch dated 1019 A.D. informs us that the king "was a moon to the lotus which was king Bhōja" and that "he searched out, beset, pursued, ground down and put to flight the confederacy of Mālava." The Chōla monarch who joined the confederation of Gāṅgēya and Bhōja and waged war with Jayasimha, the Western Chālukya king, could only be Rājendra I. From the Banswara plates<sup>2</sup> and the Betma plates<sup>3</sup> of Bhōja, both of them dated 1020 A.D., it is learnt that Bhōja had conquered Koṅkaṇa and celebrated his victory (Koṅkaṇa-graḥaṇa-vijaya-parvaṇi) that year with great pomp. The battle of Muṣaṅgi and the capture of Raṭṭapādi by Rājendra I claimed in his *meykkīrtti* also took place about this time. And the other member of the confederation was the Kalachūri king Gāṅgēya Vikramāditya of Tripuri.

Both Bhōja and Gāṅgēya had fought with the Muslim invaders. The Udayapūr *prasaṁsi* of the kings of Mālava contains the following verse<sup>4</sup> about Bhōja :

Chēdiśvar-Emḍraratha-[Togga]la-[Bhīma-mu]khyān  
 Karṇāṭa-Lāṭa-pati-Gūrjjara-rāṭ-Turushkān  
 yad-bhṛtya-mātra-vijitān avalō[kya] maulā  
 dōshṇām va(ba)lāni kalayaṁti na [yoddhr]-lō[kān]

which can be translated as : "Seeing the Karṇāṭas, the lord of Lāṭa, the king of Gūrjjara, the *Turushkas*, chief among whom were the lord of Chēdi, Indraratha, Toggala (?) and Bhīma, conquered by his mercenaries alone, his hereditary warriors thought only of the strength of their arms, not of the numbers of the fighters."

---

furious with storms of rutting ichor, as they flee away in terror through which they gallop off without waiting at all to charge with their tusks."

1. *Ind. Ant.*, vol. V, p. 17.
2. *Ep. Ind.*, vol. XI, p. 182.
3. *Ibid.*, vol. XVIII, p. 320.
4. *Ibid.*, vol. I, p. 235, v. 19.

Firishta<sup>1</sup> tells us that: "In the year 399 H. (1008 A.D.) Mahmud having collected his force, determined again to invade Hindustan and to punish Anandpāl who had shewn much insolence during the late invasion of Multān. Anandpāl, hearing of his intentions, sent ambassadors on all sides, inviting the assistance of the other princes of Hindustan, who now considered the expulsion of the Muhammadans from India as a sacred duty. Accordingly, the Rājas of Ujjain, Gwāliar, Kālinjar, Kanauj, Delhi and Ajmir entered into a confederacy, and collecting their forces, advanced towards the Punjab." The Rāja of Ujjain mentioned by Firishta could be no other than Bhōja as Ujjain was the capital of Mālava in those days.

Gāṅgēya-Vikramāditya, the Kalachūri king of Chēdi, and the other member of the confederation was also a powerful king. His earliest known date is 1019 A. D.<sup>2</sup> and his reign appears to have closed shortly before 1042 A. D.<sup>3</sup> The Mahoba inscription of the Chandellas while eulogising Vidyādhara, who led the campaign against Rājyapāla of Kanauj and killed him, recites: <sup>4</sup>

"vihita-Kanyākubja-bhūpāla-bhaṅgam  
samara-gurum upāsata prauḍha-bhīs talpa-bhājam  
saha Kalachūri-chandrah śishyavad Bhōjadēvaḥ "

"Bhōjadēva, together with the moon of the Kalachūris, worshipped, full of fear like a pupil (this) master of warfare (*i. e.*, Vidyādhara,) who had caused the destruction of Kanyākubja." It will be seen from the above that both Bhōja and Gāṅgēya-Vikramāditya (followed Vidyādhara, *i. e.*) were members of the confederation of Vidyādhara against Rājyapāla, the king of Kanyākubja, in 1019 A. D.

---

1. *History of India as told by its own historians* translated by Elliot and Dowson, vol. II, pp. 446 ff.

2. *Journal of the Asiatic Society of Bengal*, 1903, part I, p. 18.

3. *Ep. Ind.*, vol. II, p. 297.

4. *Ibid.*, vol. I, pp. 221-22, v. 21.

When considered in the light of the above, it is quite possible that Rājendra Chōla I who is known to have allied himself with Bhōja and Gāṅgēya about this time, as evidenced by the Kalenūr inscription referred to already, also joined them in helping the Chandella ruler, Vidyādhara and fought against the Muslim invader when the latter attacked Kālāñjara in 1021-22 A. D.

This presumption can be further strengthened by the names of places said to have been conquered by Rājendra in his *meṃkkirtti*.

After seizing Śakkarakkōṭṭam he said to have conquered Madurai-maṇḍalam, Nāmaṇaikkōṇam city, Pañchappaḷli and Māṣuṇidēśa. Śakkarakkōṭṭam has been identified with Chakra-kōṭya mentioned in a copper-plate grant<sup>1</sup> from Rājāpura of the Bastar State of the Nāgavamśi chief Madhurāntaka dated A.D. 1065, and its modern representative Chitrakōṭa. Māṣuṇidēśa, which literally means the land of the snakes, has been taken to refer to the area ruled by the kings of Chimdaka family (of the Rājāpura plates) who called themselves Nāgavamśōdbhava (born of the Nāga or Cobra race) and Bhōgavatipuravarēśvara (lord of Bhōgavati, the best of cities) and "on this assumption, Maduraimaṇḍalam, Nāmaṇaikkōṇam and Pañchappaḷli must be sought in the same region and held to be parts of Māṣuṇidēśam" which itself probably was included in Śakkarakkōṭṭam.<sup>2</sup> Thus it will be seen that all these places have been taken to refer to a small area.

But one point has to be noted. It is not usual to translate place names when mentioning them in the *meṃkkirtti* and we cannot cite another instance of such a translation as example. As such, Māṣuṇidēśa should not be taken as an equivalent of the Nāga-land, but as some territory really having that name. And such a territory seems to have existed in Upper Sind. Diodorus

---

1. *Ep. Ind.*, vol. IX, pp. 178-9.

2. *The Cōlas*, vol. I, p. 250.

describing the course of Alexander sailing down the Indus after leaving the confluence of the Panjāb rivers writes,<sup>1</sup> "continuing his descent of the river, he received the submission of the Sodrae and the *Massanae*, nations on opposite banks of the stream." This is the only locality in the whole of India we know of having a similar name. We may not therefore be far wrong if the Māṣupidēsa of the *meykkīrtti*, is taken as the land of the *Massanae* in Sind, especially when we know that Bhōjadēva, the Paramāra ruler and ally of the Chōḷa, is credited with a victory over the Muslims in Sind.<sup>2</sup>

Madura-maṇḍalam is more probably the country round Mathurā on the river Yamunā. In the Tamil country, only two Madurais are known : one Ten-Madurai, the capital of the Pāṇḍyas and the other, Vaḍa-Madurai of *purāṇic* fame. The Northern Mathurā continued to be famous even in the days of Rājendra I. The place figures prominently in the names of the cities plundered by Mahmud, the Sultan of Ghazna. Hēmachandra<sup>3</sup> in his *Dvayāśraya* relates that when Durlabharāja of Aṇahila-pāṭaka (1010-22 A.D.) won the hands of Durlabha-dēvī, the sister of Mahēndrarāja, king of Nadūladēśa, in the *svayamvara* arranged of her, he had to fight a number of other claimants amongst whom were the kings of Aṅgadēśa, Kāśi, Avanti (Ujjayini), Chēdidēśa, Kurudēśa, Hūṇadēśa, **Mathuradesa** and Vindhya-dēśa. *Kūḷōt-tuṅga-Śōḷan piḷḷai-t-tamiḷ*<sup>4</sup> also mentions that Vaḍa-Madurai, *i.e.*, Mathurā on the river Yamunā, belonged to the Chōḷas and was ruled over by them.

Even a cursory glance at the *meykkīrtti* will reveal that, if the above interpretation is considered plausible, after Śakkarak-kōṭṭam, it omits several intervening territories before reaching the banks of the Gaṅgā. The intervening land belonged to his

1. Cunningham's *The Ancient Geography of India*, ed. by Surendranath Majumdar Sastri, p. 290.

2. K. M. Munshi, *op. cit.*, pp. 139, 280-81 (App. F.); D. C. Ganguly: *History of the Paramara dynasty*, pp. 99-101.

3. *Dvayāśraya*, Sarga VII, pp. 547 ff.

4. Verses 34 and 95.

allies, Bhōja, Gāṅgēya and Vidyādhara, through which he had, of course, to pass with his army. That was probably the reason why Rājendra did not include these countries in the list of his victories even though the lands beyond this area find mention in the *meykkīrtti*.

We also find that both Bhōja and Gāṅgēya claim victories over the territories said to have been conquered by the Chōḷa. Mērutuṅga<sup>1</sup> says that Bhōja enjoyed his sovereignty over the territories inclusive of Gauḍa and Dakṣiṇāpatha. Indraratha was an adversary of both Bhōja and Rājendra. The Chēdi ruler Gāṅgēya is said to have defeated the ruler of Aṅga.<sup>2</sup> His reign extended up to Rewa in the west as evidenced by the Piawan rock-inscription<sup>3</sup> dated in A. D. 1038.

The city of Banāras or Kāśī also seems to have been included in the territory ruled over by Gāṅgēya.

Baihaqi,<sup>4</sup> the Muslim historian, tells us that the city was then (in A.D. 1033) in the possession of Gāṅgēya. At that time, Ahmed Nialtigin, the Muslim Governor of the Panjab and the general of the Yamīni king Ma'sūd I (c. 1030-40 A.D.) leading an expedition, invaded the Kanyākubja region and came as far as Banāras to get hold of the accumulated riches of its myriad temples in order to further his schemes of independence from Ghazna. Banāras was then in possession of Gang who has been identified with Gāṅgēyadēva of Chēdi. Nialtigin plundered the city, which no Muslim ruler had ever before attacked, and soon returned by way of Kanauj.

1. *Prabandha-chintāmaṇi*, *Muñja-prabandha*, p. 57.

Pañchāṣat-pañcha-varshāṇi-māsāḥ sapta dina-trayam  
bhōktavyam Bhōjarājēna sa-Gauḍam-Dakṣiṇāpatham

2. Goharwa plates of Lakṣmī-Karṇa, *Ep. Ind.*, vol. XI, p. 143., verse 17.

3. Edited by Cunnigham in the *Archaeological Survey Reports*, vol. XXI, pp. 112-13.

4. *Tarikh-i-Baihaqi*, extract translated in the *History of India as told by its own Historians*, by Elliot and Dowson, vol. II, p. 123.

The surname Gāṅgēya<sup>1</sup> borne by the Chēdī ruler Vikramāditya resounds very much like the title Gaṅgaikoṇḍa Chōla of Rājendra I, who was also known as *Paṇḍita-Chōla*, i.e., the Scholar king of the Chōlas like his other contemporary and ally, Bhōja of Dhārā.

The statement in the Udayapūr *praśasti*<sup>2</sup> of the kings of the Paramāra dynasty that Bhōja "possessed the earth upto Kailāsa, up to the Malaya hills, and up to the two mountains of the setting and the rising suns," can best be understood only if we take the Chōla emperor Rājendra I, in whose dominions the Malaya hills were situated, as a brother-in-arms of Bhōja.

When considered in the light of the above facts, it is but natural to arrive at the irresistible temptation to conclude that the Ganges-expedition of the Chōla emperor Rājendra I was undertaken by him jointly with Bhōja, Gāṅgēya and other Hindu kings of the North to ward off the Muslim invasion of Mahmud of Ghazna. This will be strengthened further when we find the successors of Rājendra I appointing princes of their family as viceroys to rule over distant lands in the North on the banks of the Gaṅgā.

---

1. An earlier date, 1019 A.D., for his name Gāṅgēya would militate with the suggestion that he should have assumed the name at the conclusion of the Muslim invasion. This date is arrived at from the colophon of a Nepal manuscript of the Rāmāyaṇa running as follows: *Samvat 1076 Āshāḍha vadi 4 Mahārājādhirāja Punyāvalōka Sōmavamśōdbhava Gṛuḍa-(Garuḍa)dhvaja Śrīmad-Gaṅgāyadēva-bhūjyamāne-Tīrabhuktau kalyāṇa-vijaya-rājye* taking the year as referring to the Vikrama era. Mahamahōpadhyaya V.V. Mirashi thinks (Silver Jubilee volume of the *Annals of the Bhandarkar Oriental Research Institute*, pp. 299-301) that the king was the Karnaṭa king Gaṅgadēva of Mithila and the year of the Śāka era equivalent to A.D. 1154. See also *A. B. O. R. I.*, vol. XXXV. (1954), pp. 102-106.

2. *Ep. Ind.*, vol. I, pp. 233-238, verse 17.



### Successors of Rājendra I

The *meykkīrtti* of Rājādhirāja I beginning with the words *Tiṅgaḷer-taru* mentions that he appointed many princes of the royal blood as rulers over several provinces of the empire.<sup>1</sup>

“(He) bestowed crowns of brilliant jewels, adorned with gold, on his father’s younger brother, (*his*) glorious elder brother, his distinguished younger brothers (literally, ‘young princes’), and his royal sons who knew the (*right*) path, (*along with the titles*) ‘Vānavan of great beauty,’ ‘Vallavan,’ ‘Mīnavan,’ ‘Gaṅgan,’ ‘the king of the people of Lankā,’ ‘Pallavan (*who wears*) golden ankle-rings’, (*and*) ‘the protector of the people of **Kannakuchchi (Kanyakubja)**’ and granted to these (*relatives*) of great renown the dominions of these (*respective kings*).”

These nominations are mentioned in the early portion of the *meykkīrtti*. But his *meykkīrttis* are found in his inscriptions only from the 26th year of his reign and this form, beginning with the words *Tiṅgaḷer-taru*, from his 27th regnal year.

We know that princes of the royal blood were appointed as administrators of different provinces of the Chōḷa empire even during the reign of Rājendra I and we have inscriptions of such viceroys appointed over the Pāṇḍya and Chēra countries with the titles Śōḷa-Pāṇḍyan and Śōḷa-Kēraḷan respectively. In the appointments made by Rājādhirāja I, mentioned above, we find one prince appointed as ruler of the Kanyākubja country.

Rājādhirāja was not the only king who made such postings. His brother and successor Rājendra II also made similar appointments as will be evident from his *meykkīrtti* beginning with the words *Tirumādu-puviyeṇum*.<sup>2</sup>

“(He) bestowed high crowns, resplendent with large jewels, on Gaṅgaikoṇḍa-Śōḷan, who was the younger brother of his father

1. S. I. I., vol. III., No. 28, pp. 55 - 56.

2. Ibid., No. 29, p. 62.

(and who was) powerful in defeating, (his enemies) (with the title) 'Irumaḍi-Śōlan of exuberant valour;' among his royal younger brothers of warlike strength, on the victorious Mummaḍi-Śōlan, (with the title) **Sola-Ayottirajan**; among (his) sons, who regarded with kindness (the people) in distress.....on Kaḍāraṅkoṇḍa-Śōlan of great valour (with the title) '**Sola-Janakarajan** in whom the eminence of the race of the Sun rests';..... on Iraṭṭapāḍi-koṇḍa-Śōlan, (who was) the rock of support to pure Tamil, (with the title) '**Sola-Kannakuchchiyarajan**, the lord of the ancient earth'; then among the sons of his sons....."

The Maṇimaṅgalam inscription of the fourth year, of which the above is an extract, mentions no fewer than thirteen persons—a paternal uncle (*śiriyā-tātai*) of the king, four younger brothers of his, six sons and two grandsons. The later records of the reign give a shorter list of only six persons so employed comprising the paternal uncle of the earlier record, his son—a new figure, only three of the four younger brothers mentioned before and one son of the king. This will show that these postings were not permanent, but were liable to be revised and changed as necessitated according to the exigencies of time.

Virarājendra, another brother who succeeded Rājendra II on the Chōla throne, also mentions in some of the earlier versions of his *meykkīrtti* beginning with the words *Tiruvalar tirai puyattu*<sup>1</sup> similar appointments. "(The King) duly, on account of relationship, bestowed a splendid crown of jewels on (his) elder brother Ālavandān, (whose like was) hard to be found, (along with the title) 'Rājarāja who is praised on the great earth'; [and to his son Madhurāntaka, the Toṇḍai-maṇḍalam with the title Chōlendra.] (He) was pleased to grant the Pāṇḍi-maṇḍalam, whose crown of jewels is exalted in this world, to his royal son Gaṅgaikoṇḍa-Śōlan, (along with the title) 'Śōla-Pāṇḍiyan' (the leader) of an

1. Ibid., No. 20, pp. 36 - 37.

2. This is corroborated by an inscription from Śērmadēvi in the Tirunelvēli district dated in the 3rd year, 380th day of the reign of Jaṭavarman Uḍaiyar Śrī Chōla-Pāṇḍya dēva 'declaring tax-free certain *dēvadāna* lands under the orders of his father (*nammayyar*) the Chōla

army of very tall elephants.' (He) bestowed a brilliant crown on Muḍikoṇḍa-Śoḷan, whose hand (held) the sword (and) whose spear had a sharp point, (along with the title) Sundara-Śoḷan and conferred endless great distinctions (on him). (And he) granted to each of the world of his relations separate suitable territories individually." This portion though found in the records of the earlier years is deleted from the records of the later period. No specific reference to the appointment of viceroys to territories in Northern India is made in this *meykkīrtti*. But his other *meykkīrtti* beginning with the words *Viramē tunaiyāgvum* mentions the recovery of Kanyākubja (*Kannakuchchi mīttu*).<sup>1</sup>

These definite statements in the *meykkīrtti* cannot be brushed aside as exaggerations or mere fancies of the court-poet and we cannot also conclude that the Chōḷa monarchs were vain-glorious enough to be pleased with such fanciful statements in their *meykkīrttis*. The kings would certainly have not made the appointments—let alone the fact whether the appointees would have accepted such an empty honour—and mention the same eulogistically in the *meykkīrttis*, if such postings had not been actually made and if the countries to which such viceroys were assigned had not been under the control of the Chōḷas.

It is also to be noted that nowhere do these monarchs claim in their *meykkīrttis* the conquest of these Northern countries. But Rājādhirāja I claims in his *meykkīrtti* beginning with the words *Tiṅgaḷer-taru* to have collected "the tribute paid without remissions by the Villavar (Chēra), Minavar (Pāṇḍya), Vēḷkula Śaḷukkiyar (Chāḷukya of the *vēḷir* origin), Vallavar, Kauśalar, Vaṅgaṇar, Koṅkaṇar, Sindhurar, Aiyaṇar, Śiṅgaḷar (Ceylonese), Paṅgaḷar, Andirar (Āndhra) and other kings."<sup>2</sup> As this statement is found in his inscriptions from the very commencement of his independent reign, we have to take that those rulers acknowledged the over-lordship of the Chōḷas in the reign of his father Rājendra Chōḷa himself.

---

emperor (Virarajendra) whose *meykkīrtti* commences with the words *Viramē tunaiyāgvum*.' (No. 642 of 1916.)

1. S. I. I., vol. III, No. 83, pp. 201-2.

2. Ibid., p. 57.

Trilōchanapāla set up on the throne of Kanyākubja by the confederacy of Vidyādhara and others in 1019 A. D. seems to have survived the Muslim incursions and continued to rule over the area including Allahabad. This is evident from his inscription dated 1027 A. D. from Jhusi on the left bank of the Ganges, opposite the city of Allahabad, registering the grant of a village to some brāhmaṇas, after bathing in the Ganges on the occasion of the *dakṣiṇāyana saṁkrānti*. But this region was found included a few years later in the reign of the Kalachūri king Gāṅgēya-dēva. The Piawan rock inscription<sup>2</sup> dated 1038 A. D. shows that at that time his authority extended to within fifty miles of the city. The Kalachūri records mention that Gāṅgēya took up his residence at the feet of the holy fig-tree at Prayāga. The Goharwa plates<sup>3</sup> of his son, Lakshmi-Karṇa, state that Gāṅgēya imprisoned the king of Kira in the Kangra valley. He is also known to have "found salvation (*mukti*) with his hundred wives (*grihiṇīs*)" at Prayāga.<sup>4</sup>

It is possible that Gāṅgēya obtained the suzerainty over Kanyākubja as a result of the Muslim invasion on Kālāñjara as we find that Vidyādhara, the Chandella king of Kālāñjara, who is said to have headed the confederacy of the Hindu kings against Mahmud of Ghazna, fades away after the incident. It might be that Vidyādhara was not completely subdued by the invader; but the onslaught certainly crippled his prestige, resources and power. The power of the Chandellas was eclipsed by that of others for about a century afterwards.

But Bhōja also is credited with the sovereignty of Kanyākubja. The Basahi plate<sup>5</sup> of Gōvindachandra, the Gāhaḍavāla king of Kanauj, dated 1104 A. D., states that, "in the lineage named

1. *Ind. Ant.*, vol. XVIII, pp. 33-35.

2. Cunningham: *Arch. Survey Report*, vol. XXI, pp. 112-13.

3. *Dynastic History of Northern India*, vol. II, p. 775.

4. *Ep. Ind.*, vol. II, p. 4, v. 12; vol. XII, p. 211, v. 12.

5. *Ind. Ant.*, vol. XIV, p. 103

yātē śrī-Bhōja-bhūpē vivu(bu)dha-vara-vadhū  
nētra-sīmā-tithitvaṃ

Gāhaḍavāla there was a victorious king, the son of Mahāla, named Chandradēva, who, when on the death of king Bhōja and Karṇa, the world became troubled, came to the rescue and became king and established his capital at Kanyākubja." Mērutuṅga also refers to Bhōja's conquest of that country in his statement <sup>1</sup> that when Bhōja went out for conquests "the king of Kanyākubja is here bent double."

The incomplete drama *Pārijāta-mañjarī*<sup>2</sup> or *Vijaya Śrī* by Madana, the royal preceptor of Arjunavarman, which has survived in fragments inscribed on a stone in the Bhōjaśālā at Dhārā, mentions that Bhōja "fulfilled his desires in a festival which was the defeat of Gāṅgēya." Evidently, Bhōja wanted from the very beginning to have his sway over Kanyākubja which was then considered to be the centre of all activities in the Uttarāpatha entitling its ruler to all the privileges of an imperialistic nature. But on the withdrawal of the Muslim invader it was annexed by Gāṅgēya to his own kingdom and Bhōja would not brook it. He was waiting for an opportunity to take possession of the country and this seemed to have occurred towards the closing years of their reigns.

Gāṅgēya seems to have died in 1041 A. D.,<sup>3</sup> as the earliest grant of his son and successor Karṇa, also called Lakshmi-Karṇa,

śrī-Karṇṇe kīrtti-śēsham gatavati ca nripē  
kshmatyayē jāyamānē  
bharttāram yam va (dha)ritrī tri-diva-vibhu-nibham  
priti-yōgād upētā  
trātā viśvāsa-pūrvvam samabhavad iha sa  
kshamā-patis-Chandradēvaḥ  
dvishat-kshitibhṛtaḥ sarvvān vidhāya vivaśān vaśē  
Kanyākubjē 'karod rāja rājadhānīm animditām.

1. *Prabandha-chintāmaṇi*, p. 44.

2. *Ep. Ind.*, vol. VIII, p. 101, verse 3.

"tūrṇṇam pūrṇṇa-manōrathas chiram abhūd  
Gāṅgēya-bhaṅgōtsavē"

3. *Ep. Ind.*, vol. II, pp. 297-310. Fleet calculated that he died on the 22nd January 1041 A. D. (See *ibid.*, vol. XII, p. 206, fn.)

from Banāras dated in 1042 A. D. refers to the *samvatsara-śrāddha* performed that year. The statement in the grant that the Chēdi ruler found salvation with his hundred queens at Prayāga is probably intended to convey that he immolated himself in the sacred river in the same way as Śōmēśvara, his Western Chāḷukya ally, put an end to his life a few years later.

That the Kanyākubja country came under the sway of Bhōja about this time can be gleaned from another source. Firishta<sup>1</sup> states that, "in the year 435 A. H. (1043 A. D.), the raja of Dehli, in conjunction with other rajas, retook Hansy, Tahnesur and their dependencies, from the governors to whom Madood had entrusted them. The Hindus from thence marched towards the fort of Nagrakote, which they besieged for four months; and the garrison, being distressed for provisions, and no succours coming from Lahore, was under the necessity of capitulating." Nagarkot is the modern Kot-Kangra, the chief place of the Kangra district in the Punjab, between the rivers Ravi and Beas. The locality comprised the territories known as Champā and Trigarta in mediaeval days. Tilakwada copper-plate grant<sup>2</sup> of Bhōja, dated 1047 A. D., informs us that the general Surāditya stabilised the royal fortune of Bhōja by slaughtering Sāhavāhana and others in battle. This Sāhavāhana has been indentified with the Champā ruler Sālāvāhana-dēva<sup>3</sup>, also known as Sāhilladēva and Sāhasāṅka, who claims to have defeated the Kīra forces, the lord of Durgara, and the Turushkas, and received homage from the lord of Kulūta, and whose alliance was sought by the ruler of Trigarta.<sup>4</sup>

---

1. *Tarikh-i-Firishta*, tr. by Briggs (History of the rise of the Muhammadan power in India), vol. I, p. 118.

2. Sāhavāhana-saṁgrāmē-anyēśhām api bhūbhujām  
hatvā yōdhām(?) sthīrām lakshmīm Bhōjadēvē chakāra yaḥ.  
Proceedings and Transactions of the (First) Oriental Conference, Poona, 1919, p. 324.

3. *Ind. Ant.*, vol. XVII, pp. 8-9.

4. D. C. Ganguly: *History of the Paramāra dynasty*, p. 110.

Kalhana<sup>1</sup> mentions in his *Rājatarāṅgiṇī* that Bhōja, the Paramāra king, arranged through Padmarāja, a foreign trader who for sometime held even the royal diadem of Ananta, the then Kashmir king as security for his debts, for the regular supply of water from the sacred spring of Kapaṭeśvara in Kashmir to Mālava. It may not therefore be far wrong if we take that Bhōja brought Kanyākubja under his rule by about 1040-41 A. D.

The Chōla king also appears to have engaged himself in this campaign aiding Bhōja, whose adversary, the Chēdi monarch, had the help as usual of the Western Chālukya ruler. There are also evidences which might lead to the conclusion that the first war with the Western Chālukya described in the *meṃkkirtti* of Rājādhirāja took place about this time.<sup>2</sup> Evidently, the victories claimed in the North for Rājādhirāja before 1044 A. D. and the assignment of the viceroyalty over Kanyākubja to a Chōla prince were the outcome of this expedition.

Again, a member of the ruling royal family of Kanyākubja figures in the South at this period. Some of the early inscriptions<sup>3</sup> of Rājādhirāja mention the king to have invaded Ceylon after his victory at Kāndaḷūr-śālai and to have beheaded "the king of Laṅkā, the Vallava (wearing) a garland, and the lord of Kanna-kuchchi." A more detailed account of the occurrences as found in some of the later records is as follows:

"With a single unequalled army (he) took the crown of Vikramabāhu, the king of the people of Laṅkā on the tempestuous ocean; the crown of large jewels, (belonging to) the lord of Laṅkā, Vikrama-Pāṇḍyan, who, having lost the whole of the southern Tamiḷ country out of fear of himself (Rājādhirāja) had entered Īlam (surrounded by) the seven oceans; the beautiful golden crown of the king of Simhaḷa, Vira-Śālāmēghan, who

1. *Rājatarāṅgiṇī*, English translation by M. A. Stein, vol. I. p. 284.

2. *The Cōlas*, vol. I, pp. 273-77; N. Venkataramanayya: *The Eastern Cālukyas Vēṅgi*, pp. 230-21.

3. *S.I.I. (Texts)*, vol. IV, No 539.

believing that Īlam (surrounded by) the ocean was superior to the beautiful Kannakuchchi (Kanyākubja) which belonged to him, had entered (the island) with his relatives and (those of) his country-men who were willing (to go with him), and had put on the brilliant crown ; who, having been defeated on the battle-field and having lost his black elephant had fled ignominiously ; and who, when (the Chōḷa king) seized his elder sister along with (his) wife (or daughter—*kāḍali*) and cut off the nose of (his) mother, had returned in order to remove the disgrace (caused) thereby, and, having fought hard with the sword, had withered in a hot battle ; and the extremely brilliant crown of large jewels. (belonging to) Śrī Vallavan (Śrī Vallabha) Madanarājan, who had come of the family of Kannaran (Kriṣṇa) and become the proud king of Īlam".<sup>1</sup>

The above account is corroborated by *Mahāvamsa*, the Ceylon chronicle.<sup>2</sup> Rājendra I, in the fifth year of his reign, (1017 A. D.), conquered the whole of Īlamanḍalam, captured its king Mahinda V and deported him to the Chōḷa country, where he died twelve years later. Thereafter, Mahinda's son Kassapa revolted against the Chōḷa rule in Ceylon and began to rule over Rōhaṇa, the south-eastern portion of the island, under the title Vikkamabāhu. This happened about 1029 A.D. *Mahāvamsa* says that he suddenly died of a disease in the twelfth year of his reign (1040 A.D.) in the midst of extensive preparations for a Chōḷa war. After a rule of eight days by Kittī, a former court-official, the 'mighty Mahālānakitti' became king of Rōhaṇa and he, vanquished in his third year in battle against the Chōḷas, ended his life. Vikkama Paṇḍu, the only son of Mahālānakitti, who, having left his country through fear and lived for a time in the Dulu country, returned to Rōhaṇa when he heard the fate of his father, and was killed, after a short rule, in a fight with Jagatipāla. This Jagatipāla is described in the *Mahāvamsa* as 'a powerful prince of the line of Rāma', and, 'a sovereign's son who had come from the town Ayojjha (Ayōdhyā).'

1. *S.I.I.*, vol. III, No. 28, p. 56; See also *The Cōḷas*, vol. I, pp. 296-7.

2. *Çūlavamsa*, Chapter LVI.



" Him also the Chōlas slew in battle and sent the Mahēsi with her daughter and all the valuable property to the Chōla kingdom.<sup>1</sup> The king Parākkama, son of the Paṇḍu king, reigned two years. The Chōlas slew him also when fighting with him." Thereafter an army leader called Lōka or Lōkeśvara took possession of the government and died after a reign of six years when another officer, a Chief of the 'Kesadhātus, Kassapa by name, got the upper hand of the people. Kittī, a young prince of seventeen years of age, and grandson of Vikkamabāhu, drove this Kassapa in six months and took possession of his ancestral kingdom and strove to free the island from the Chōlas. The accession of Kittī, who assumed the title Vijayabāhu, to the Rōhaṇa throne is placed in the year 1055 A.D.

The *Mahāvamsa* clearly brands the rulers between Vikrama-bāhu and his grandson Vijayabāhu as usurpers. Vikrama Pāṇḍya of the Chōla *meṃkkīrtti* is to be identified with Vikkama Paṇḍu of the *Mahāvamsa*, who, according to the Chronicle, was the only son of Mahālānakitti and leaving his country through fear was living in the Dulu country at the time of his father's death. The Chōla inscriptions imply that he was a Pāṇḍya prince who had once ruled over the southern country and was compelled by Rājādhirāja to abandon southern India and seek his fortune in Ceylon. The Dulu country of the Chronicle was evidently the Tuḷu country in the West Coast which was ruled over by the Ālupas. The Pāṇḍyas had close dynastic alliances with both the Ceylonese kings and the Ālupas. The Sinhalese kings followed the patriarchal line of succession; but the matriarchal system also was recognised and this, we find, had been adopted on many occasions. The Ālupas also seem to have likewise followed the matriarchal system sometimes. Many of the Ālupa kings had borne the cognomen Pāṇḍya.<sup>2</sup> Thus there will be no difficulty in the above identification.

---

1. Jagatīpala's queen and her daughter Lilavati escaped later on from their captivity in the Chōla country to Ceylon where Lilavati married Vijayabāhu I and became his *Mahēsi* or chief queen.

2. The relationship between the Pāṇḍyas of the Tamil country and the Tuḷu-Pāṇḍyas is being discussed later on.

Vira-Śālāmēgha of the *meykkīrtti* could be no other than Jagatīpāla of the Chronicle. It is taken that there is discrepancy between the two about the place of origin. The Chōla inscriptions say that Kanyākubja belonged to him, *i.e.*, that he came from the ruling royal family of Kanyākubja, while the Chronicle says that he belonged to the line of Rāma and came from the town of Ayōdhyā. But there is a striking similarity between the two in their fortunes. Jagatīpāla of the Chronicle was probably his name and Vira-Śālāmēgha of the *meykkīrtti*, his official title as a ruler. The rulers of Ceylon adopted the titles Śālāmēgha or Śīlāmēghavaṇṇa (usually referred to in inscriptions as *Salamevan*) and Saṅghabōdhi (usually referred to in inscriptions as *Siri Sangbo*) alternately<sup>1</sup> like the titles Rājakēsari and Parakēsari of the Chōla monarchs. The accession of Jagatīpāla to the throne of Rōhaṇa is placed by the historians of Ceylon in 1045 A.D.<sup>2</sup> and the death of Vira-Śālāmēgha is mentioned in the *meykkīrtti* in an inscription dated towards the end of 1046 A.D. (3rd December.)<sup>3</sup>

It is to be noted that the kings of Kanyākubja at this period, who belonged to the family of the Pratihāras, also claimed descent from the Raghu family. Mahīpāla, the grandfather of Rājyapāla who submitted to Mahmud of Ghazna, is described by his court-poet Rājasēkhara in his *Bālabhārata*<sup>4</sup> as the 'pearl jewel of the lineage of Raghu'. Mahēndrapāla, the father of Mahīpāla, is described in the same work<sup>5</sup> as the 'leading person of Raghu's family' and in *Viddhaśālabhañjikā*<sup>6</sup> of the same poet as 'the ornament of the race of Raghu.' The Gwalior inscription<sup>7</sup> of Bhōja I (of Kanauj),

1. Geiger: *Cūlavamsa*, Eng. trans., Part I, p. 185, n. 5.

2. G. C. Mendis: *The Early History of Ceylon*, (4th edition, 1940) pp. 153-4.

3. *S.I.I.*, vol. III, p. 53.

4. Tēna (-Mahīpālādēvēna) ca Raghuvamśa muktāmaṇinā  
— *Bālabhārata*, p. 2.

5. Devōyasya Mahēndrapālanṛpatiḥ śishyō Raghurāmaṇiḥ.  
— *Ibid* I.

6. Raghukulatilakō Mahēndrapālaḥ  
— *Viddhaśālabhañjikā* I, 6.

7. *Ep. Ind.*, vol. XVIII, p. 106, verse 3.

the father of Mahēndrapāla, more expressly describes Lakshmaṇa, the brother of Rāma, as the progenitor of the family: "Saumitri, his (Rāma's) honourable younger brother of staff severe, was the door-keeper (*pratihāra*) since he repelled (the enemies) in the battle with Mēganāda, the destroyer of Indra's pride." It may therefore be concluded that we have here only one prince mentioned under two different names in the two sources<sup>1</sup>

Śrī Vallabha Madanarāja, the last of the princes mentioned in the *meykkīrtti*, who is taken to be a Vallabha (of the line of Kannara) by descent, has been identified with Parākkama, the son of the Paṇḍu king, of the *Mahāvamsa*.<sup>2</sup> Probably, he belonged to the Tuḷu-Pāṇḍyas among whom succession took place also according to matriarchal descent and this would possibly explain his being described as of the line of Kannara by patriarchal descent in the Chōḷa inscriptions.

It will be evident from the above that during the troublous days following the Muslim invasion, some members of the royal family migrated from Kanyākubja to the Chōḷa country.<sup>3</sup> Very

---

1. During the days of Muslim invasion, Kanyākubja was forsaken and Bari became the secondary capital, which also subsequently shared the same fate. We cannot say which town was the capital of the country in those troublous times. It is possible the kings moved on to Ayōdhya. Nothing is known about the existence of a ruling family at Ayōdhya in those days.

2. Hultzsch: *Journal of the Royal Asiatic Society*, 1913, pp. 519-21.

3. Rājendra II, the successor of Rājadhiraṇa, in his *meykkīrtti*, beginning with the words *Tirumādu puviyenum* also mentions his encounter with a Vira-Śālāmēgha of Ceylon as follows: "(The King) despatched a war-like army into the southern region, captured Laṅkā, (surrounded by) the black ocean, Vira-Śālāmēgha, the king of the Kalingas (who had) a powerful army, with (his) elephants (which resembled) the ocean, caused to be cut off (his head which wore) a brilliant crown, and seized on the battle-field the two sons of Mānābharaṇa, the king of the people of Laṅkā". (*S.I.I.*, vol. III, No. 29, line 12). This is first mentioned in the inscriptions of his

likely, Jagatīpāla was one of them and the Chōlas found for him a position in Ceylon as viceroy.

The successes gained in the north by Bhōja and Rājādhirāja could not be maintained for long. Karṇa, who succeeded his father Gāṅgēya on the Chēdi throne in 1041 A. D., wanted to avenge the defeat inflicted on them by Bhōja and his father's death. He was able not only to recover the lost territories but also to chastise Bhōja for his aggression. In this he was helped by Āhavamalla Sōmēśvara, the Western Chālukya king and Bhīma, the Chaulukya ruler of Aṇahilapāṭaka. The *Vikramāṅkadēva-charita*<sup>1</sup> tell us that Āhavamalla "stormed Dhārā, the capital of the Paramāra in Mālava, from which Bhōja had to flee." Sōmēśvara captured, ravaged and plundered the city. This is also borne out by his inscriptions. One record<sup>2</sup> states that he assailed even the city of Dhārā, 'which proved invincible to early kings'. Another inscription<sup>3</sup> of his from Nagai in the Haiderabad State dated 1058 A. D. mentions the burning of Dhārā and Ujjain by the king. Mādhuva, a feudatory under him, himself joined in this enterprise and takes to himself the credit of driving away the lord of Dhārā from his capital. A record<sup>4</sup> dated 1060 A. D. glorifies the king by stating that he was "a royal swan, strolling on both

---

fourth regnal year (1055 A.D.). Later records (e.g., No. 87 of 1895 of the ninth year) mention only Vira-Śālamēgha. It is sometimes taken that "despite his being called 'king of the Kālīṅgas of the strong army' (*virar-paḍai-k-kālīṅgar-man*), there is no reason to distinguish him from the *Kannakuchchiyar-kāvalan* of the Rājādhirāja inscriptions." It has been pointed out above that Vira-Śālamēgha was only a title of the Ceylon king and not his name. Further, the mention in the *meykkīrtti* that one was of the ruling family of Kanyākubja and the other the ruler of Kālīṅga, does differentiate between the two and they have therefore to be taken as different persons. Vira-Śālamēgha of Rājendra's inscription should have very likely been the immediate predecessor of Vijayabāhu I whose reign commenced in c. 1055 A.D.

1. Canto I, 91-96; also *Ind. Ant.*, vol. V, p. 319.
2. *An. Rep. of the Mysore Arch. Dept.* for 1928, p. 72.
3. *The Inscriptions from Nagai* (Haiderabad Arch. Series, No. 8.)
4. *An. Rep. of the Mysore Arch. Dept.* for 1929, pp. 68-69.

the banks of the Narmadā, an evil comet to the Mālava people, capturer of the fort named Maṇḍeva (modern Mandu), and was held in honour in the city of Dhārā." *Prabandha-chintāmaṇi*<sup>1</sup> says that the Dāhala king Karṇa (*i. e.*, the Chēdi ruler) attacked Bhōja in company with one hundred and thirty-six princes, "and at the same time he invited Bhīma to attack the country of Mālava in the rear, promising him the half of Bhōja's kingdom. Then king Bhōja, being attacked by those two kings, lost his pride, as a snake, overcome with a charm, loses its poison. And then a sudden corporeal malady took hold of Bhōja" of which he died. After this Karṇa, "broke down the fort and took all the wealth of Bhōja." Mērutuṅga<sup>2</sup> further tells us that after the conquest of Mālava, there was a dispute between Karṇa and Bhīma in sharing the spoils between them and this is also corroborated by Hēmachandra in his *Dvayāśraya*<sup>3</sup>. The Nagpur *prāśasti*<sup>4</sup> of the Paramāra kings of Mālava dated 1104 A.D. states that "when he (Bhōja) had become Indra's companion and when the realm was overrun by floods, (*kulyākula*-crowded with nobles), in which the sovereign was submerged, his relation (*bandhu*) Udayāditya became king. Delivering the earth, which was troubled by kings and taken possession of by Karṇāṭas, was like the mighty ocean, this prince indeed act like holy boar." Mērutuṅga narrates an incident<sup>5</sup> that on one occasion when Bhōja went to pay his devotions to his family goddess in the outskirts of the city of Dhārā, he was very nearly captured by some Gūrjara soldiers; but he escaped unhurt.

It is stated that Bhōja died of a sudden malady (small-pox?) when he was in the midst of his preparations for driving away the enemies and recovering his patrimony. This appears to have taken place in 1050-51 A. D., as evidenced from the Tamil inscrip-

- 
1. *Prabandha-chintāmaṇi*, pp. 36-7.
  2. *Ibid.*, pp. 74-75.
  3. *Dvayāśraya*, Sarga IX, v. 57, p. 692.
  4. *Ep. Ind.*, vol. II, p. 192, v. 32.
  5. *Prabandha-chintāmaṇi*, pp. 73-5.

tions of the Chōlas. One version<sup>1</sup> of the *meykkīrtti* of Rājādhirāja I. beginning with the words *Tinglēr taru* mentions "the offer of protection by the Chōla to the descendants of the Gūrjara king Uppala, slain (formerly) by Tailapa and the restoration to them of the crown of the former seized and attached by the latter to his war-drum." This occurs for the first time in the inscriptions of his 33rd regnal year, i.e., 1050-51 A.D. The Gūrjara king Uppala mentioned in the Chōla *meykkīrtti* can be no other than Vākpati II Muñja, otherwise known as Utpala, the uncle of Bhōja.

It will be evident from the above that the Imperial Chōlas of Tanjāvūr also took part in the war and helped Bhōja against the confederacy of the Western Chālukya king Sōmēśvara, the Kalachūri king Karṇa and Bhīma, the Chaulukya ruler of Aṇahilapāṭaka. The exact course of events in the war is not known. Bhōja was defeated and he evidently lost his kingdom to the combined forces of his enemies. When he was making the preparations to recover his lost kingdom, he suddenly died of some malady. Very likely, the invading forces were formidable and the rightful heirs had to seek shelter with the Chōlas till they could rally their forces and regain their patrimony with the Chōla help.

The history of Mālava also is far from clear at this period. Jayasimha, the son of Bhōja, was ruling over Mālava in the year 1055 A. D. according to the Mandhata plates<sup>2</sup> and in 1059 A. D. according to the Panhera inscription<sup>3</sup> of his feudatory Maṇḍalika, of a minor branch of the Paramāras, governing the Vāgaḍa region. The latter record says that Maṇḍalika captured in battle the commander Kanha with his horses and elephants and handed over to Jayasimha. The identity of this Kanha is not known. But the record shows that Jayasimha was not having a peaceful reign and that he had enemies whom he had to conquer.

---

1. *S.I.I. (Texts.)* vol. V, No. 465.

2. *Ep. Ind.*, vol. III, p. 46.

3. *Ibid.*, vol. XXI, p. 40.

Bilhana<sup>1</sup> states that during the reign of Āhavamalla Sōmēśvara, his son Vikramāditya "lent his assistance to the king of Mālava who came to him for protection, to regain his kingdom." The name of the Mālava ruler helped by the Chālukya is not known. But we know that the Paramāras of Mālava had been the hereditary enemies of the Western Chālukyas with whom they had been at incessant war from the very beginning. So the Mālava prince who sought the aid of Sōmēśvara himself, putting aside all racial jealousies and family pride, should be different from the prince who sought the aid of the Chōḷas and who was set up on the Mālava throne by them. Evidently he was inimical to the Chōḷas and a rival to the candidate supported by them.

The Soḍasa grant<sup>2</sup> of Bhōja dated 1011 A. D. mentions the donor *Mahārājaputra* Vatsarāja as ruling over Mōhaḍavāsaka (Seven hundred and fifty), a small area of the country. It is possible he was a son of Bhōja;<sup>3</sup> but it is not known whether he is the same as Jayasimha who seems to have succeeded Bhōja or a different person. According to the Nagpūr inscription<sup>4</sup>, the realm, on the death of Bhōja, "was overrun by floods crowded with relations in which its sovereign was submerged" implying that there were more than one claimant to the throne. And from the evidence adduced above we find that one of the claimants was supported by the Chōḷas and another by the Western Chālukyas.

- 
- i. sa Mālavēndram śaraṇam pravishṭam  
 akantakē sthāpayati sma rājyē  
 kanyā-pradāna-chchhalataḥ kshitīśaḥ  
 sarvasva dānaṁ bahavō 'sya chakruḥ

— *Vikramāṅkadēva-charita*, Sarga III, verse 67.

2. *Bhāratiya Vidyā*, vol. VI, Supplement, pp. 37-40.  
 3. The word *Mahārājaputra* is sometimes taken as the title of an official (*Ind. Ant.*, vol. XVIII, p. 212, fn. 3).  
 4. *Ep. Ind.*, vol. II, p. 192.

The Nagpur *prāśasti* does not mention Jayasimha, but simply states that at the end of the period of confusion, Udayāditya emerged and "uplifted the realm." This Udayāditya is sometimes taken as the candidate supported by the Chōlas<sup>1</sup> and Jayasimha as the rival candidate sponsored by Western Chālukyas.<sup>2</sup> But the situation seems to be the other way.

The known dates of Udayāditya are 1080-81 A. D. of the Udayapūr stone-inscription<sup>3</sup> and 1086-7 A.D. of the Jhalrapatan stone inscription.<sup>4</sup> But a 'modern inscription' in vernacular (dated 1560 A. D.) at Udayapur, in Gwalior, gives the dates Vikramā samvat 1116 and Śāka 981, corresponding to 1059-60 A.D., for the reign of Udayāditya and speaks of him as having built a temple of Śiva.<sup>5</sup> It is therefore likely that Udayāditya was the ruler who ousted Jayasimha from the throne. Bilhana states that the Western Chālukya monarch not only established the Mālava ruler on his throne, but also gave him all presents (*bahavō sarvasva-dānam*) on the pretext of giving a princess in marriage (*kanyā-dāna*). The *Rās Mālā*<sup>6</sup>, the traditional history of Gujarat "written by Sir Kinlock Forbes in the middle of the last century from a few Jaina Prabandhas which were available to him and the bardic tales collected by Kavi Dalpatram", relates that 'Oodoyadit (Udayāditya) had two wives, one belonging to the Solunkhee (Chālukya) dynasty and the other to the Waghela clan. By the Solunkhee queen he had a son Jug Dev (Jagaddēva) and by the Waghela queen another son named Rindhuwal (Raṇadhavalā). Udayāditya, influenced by his Waghela queen, made Rindhuwal his heir-apparent. Jug Dev, through the jealousy of his

---

1. *Journal of Oriental Research*, vol. XVI, pp. 147-8.

2. D. C. Ganguly: *op. cit.*, p. 123.

3. *Ind. Ant.*, vol. XX, p. 83.

4. *Journal and Proceedings of the Asiatic Society of Bengal*, vol. X, pp. 241. ff.

5. *Journal A.S.B.*, vol. IX, pp. 545-50.

6. Forbes' *Rās Mālā*, edited by H. G. Rawlinson, (1924), vol. I, pp. 117 ff.



step-mother, was reduced to poverty. He left Malwa, and, in order to make a living, accepted military service under Sidh Raj in Gujarat.' According to Mērutunga,<sup>1</sup> Jagaddēva entered the military service of Paramardin (a title of the Western Chālukya, Vikramāditya VI), king of Kuntala, and was highly honoured by the Chaulukya Siddharāja-Jayasimha of Gujarat. Very likely, the Solāṅkī queen of Udayāditya mentioned in the bardic chronicle was the Chālukya princess married to him as mentioned by Bilhaṇa, and then it was but natural that Jagaddēva, born of this union, lived in the court of his uncle Vikramāditya VI and rendered military service under him. Epigraphic testimony is also available that Jagaddēva was serving under Vikramāditya VI as an officer in charge of the Koḷlippākkai (modern Kulpak) region for a long time.<sup>2</sup>

Further, Udayāditya belonged to a junior branch of the Paramāras and not to the main line from which Vākpati and Bhōja came. Detailed information of his pedigree is obtained from an inscription<sup>3</sup> from Udayapūr in Bhilsa. It is mentioned therein that he was the great-grandson of Sauravīra (Śūravīra), a member of the Pāvāra (Paramāra) family. His grandfather was Gondala whose son Gyātā (Jñātā) was his father. It is also stated therein that Udayāditya, having obtained the eastern territory, proceeded to the interior of Mālava, (*Mālava madhya-dēśam gatvā sthānam prasiddhih.....*) which was formerly governed by his ancestors. He could not, therefore, be one of the descendants of Utpala restored to his ancestral throne by the Chōḷas according to their *meykirtti*. Evidently, he was the rival candidate supported by the Western Chālukya.

Some of the Mālava princes appear also to have entered into service with the Chōḷas and served as their officers about this time. Similarly, some others of them appear to have served under the

---

1. *Prabandha-chintāmaṇi*, 186: cf. Sōmēśvara's *Kirttikaumudī-Sargā* II, v. 99.

2. *Teliṅgāna Inscriptions*.

3. *Journal of the A. S. B.*, vol. IX, p. 547.

Western Chālukyas. The *meṃkkirṭi* of Virarājendra beginning with the words *Tiruvaḷar tirai puyattu*<sup>1</sup> mentions that immediately after his coronation, the king "despatched (the banner of) the ferocious tiger into all directions, and cut off the beautiful heads, surrounded by garlands (won) on battle-fields, of the king of Pottappi, whose horses chafed under the bridle, of the Kerala who wore large ankle-rings bound by straps,<sup>2</sup> and of the younger brother of Jananātha." This is mentioned for the first time in his inscriptions of the fourth regnal year. Some of the versions mention clearly this Jananātha as Jananātha of Dhārā thereby indicating that he was of the Paramāra family. Later on, the same *meṃkkirṭi* says that the king, in the course of his expedition against Vēṅgi for the second time in his fifth regnal year,<sup>3</sup> in a decisive battle on the banks of the river Kṛishṇa, in the neighbourhood of Vijayavāḍa, inflicted a crushing defeat on the Western Chālukyan forces commanded by Jananātha, Rājamayyan and others, compelling them to flee into the jungle for refuge. It is possible that Jananātha mentioned on these two occasions refer to the same person. Then both Jananātha and his brother, both of them princes of the Paramāra dynasty of Mālava, would appear to have fought on the side of the Western Chālukyas against the Chōḷas. But the name Jananātha, which was first borne as a title by Rājarāja I and later on by some of his descendants, would show that he should have obtained his name from the Chōḷas. Probably he was at first a subordinate of the Chōḷas and when the country, the region in the neighbourhood of the Kṛishṇa, was conquered by the Western Chālukyas, he also transferred his allegiance to them and in that capacity had subsequently to fight with his erstwhile masters.

---

1. S. I. I., vol. III., No. 20.

2. The official translation of the above has "of Vāran of Kēraḷa who wore large ankle-rings" thus making Vāran as the name of the Kēraḷa king. The text is *vār-aṇai vau-kalar-Kēraḷan-taṇnai* which means "of the Kēraḷa who wore large ankle-rings bound with straps." No person of the name Vāran is mentioned; it is only *vār-aṇai* "bound with straps".

3. S. I. I., vol. III., No. 20.

4. Ibid., No. 30.

The imperialistic expansion of the Chōlas received a set back at about this time by the growing power of the Western Chālukyas under the energetic monarch Āhavamalla Sōmeśvara I and his more ambitious son Vikramāditya VI. The rivalry of these two powers was manifest not only in the Dakhan, but also further north. The drama of setting up rival candidates to the throne of Mālava by these two powers appears to have been again enacted about this time in the Chakrakōṭa region.

We have already referred to the Chindaka Nāgas ruling over the Chakrakōṭa territory of the former Bastar state in the Madhya Pradesh. The earliest record in this area of the members of the family, who belonged to the same stock as the Sindhas of the Sindavādi country embracing portions of Anantapur, Bellary, and Raichur districts, is a fragmentary epigraph<sup>1</sup> from Erragat of about ten miles from Jagadalpūr, of a Nāgavamśi king, part of whose name is lost although it may have been [Nripa]tibūṣhaṇa or [Kshi]tibūṣhaṇa, bearing date Śaka 945, corresponding to 1023 A. D. From this it has been suggested<sup>2</sup> that "the Chindaka-Nāgas entered Bastar in the train of Rājendra Chōla's army" on its Ganges expedition some time before 1023 A. D. Another family of Telugu-Chōla chiefs also appears to have been installed in the region as subordinates to these Nāgas. The Bastar region was ruled, according to an inscription<sup>3</sup> dated 1060 A. D. from Bārasāru, by the Chindaka-Nāga Mahārāja Jagadēkabhūṣhaṇa otherwise known as Dhārāvarsha, when his Telugu-Chōla feudatory Mahāmaṇḍalīśvara Chandrāditya-Mahārāja, lord of Ammagāma, built a Śiva temple on the bank of a tank excavated by himself at the capital city of Bārasāru (modern Bārsūr). This Dhārāvarsha is evidently the same Dhārāvarsha, the ruler of Śakkrakkōṭam from whom Kulōttuṅga I is credited,<sup>4</sup> according to

1. S. I. I., (Texts), vol. X, No. 643; See also *Inscriptions in the Central Provinces and Berar* by Hiralal, No. 285.

2. *Quarterly Journal of the Mythic Society*, vol. XLIV, p. 2.

3. Hiralal: *op. cit.*, No. 269.

4. S. I. I., vol. II, pp. 142, 146.

his *meykkīrtti* beginning with the words *Pugaḷ śūḷnda puṇari*, to have exacted tribute while he was yet a prince (i.e., in his *iḷaṅgō-p-paruvam*). Within a very few years, in 1065 A.D., we find the region under the rule of Madhurāntaka, another member of the family.<sup>1</sup> But the same region appears to have soon passed over to the rule of Sōmēśvara, son of Dhārāvarsha-Jagadēkabhūshaṇa. There are several inscriptions of this Sōmēśvara, the earliest of which found in Kuruspal is dated in 1069 A.D.<sup>2</sup> Another epigraph<sup>3</sup> found at the same place says that this Sōmēśvara, who is described as the hereditary ruler of the Chakrakōṭa region, killed the powerful king Madhurāntaka, evidently the grantor of the Rājāpura plates. Between Dhārāvarsha whom Kulōttuṅga is said to have conquered and his son Sōmēśvara, who are known to have reigned in 1060 A. D. and 1069 A. D. respectively, the region was ruled over by Madhurāntaka, by killing whom Sōmēśvara obtained his patrimony. The names of these two rivals for the Chindaka-Nāga throne of Bārasūru, viz., Madhurāntaka and Sōmēśvara, may suggest that while Madhurāntaka was a protege of Chōḷas, Sōmēśvara received help from the Western Chāḷukyas.

While the Chōḷas and the Chāḷukyas were pursuing their rivalry to the bitter end in the Dakhaṇi, kārṇa, the Kalachūri ruler of Tripurī and the former ally of the Chāḷukya, was consolidating his position in the north. From the find-spots of his inscriptions and the significance of his assumption of the title of *Trikalingādhipati*,<sup>4</sup> it may be presumed that "for a time at least he dominated the whole region extending from the sources of the Banas and the Mahi rivers in the west to the estuaries of the Hoogly in the east, and from the Ganges-Jumna valley in the north to the upper waters of the Mahānadi, Wainganga, Wardha and Tapi."<sup>5</sup> He is also said to have built a temple of the *Mēru*

---

1. Rājāpura plates of Madhurāntaka in *Ep. Ind.*, vol. IX, pp. 174, ff.

2. *Ep. Ind.*, vol. X, p. 31.

3. *Ibid.*, p. 25.

4. *Ibid.*, vol. II, pp. 297 - 310.

5. H. C. Ray: *op. cit.* vol. II, p. 779.

type at Kāsi, which came to be known as *Karṇamēru*.<sup>1</sup> He is credited in the inscription<sup>2</sup> of his great-grandson, Jayasimha, to have been waited upon by the Chōḷa, Kuṅga, Hūṇa, Gauda, Gūrjara and Kīra princes. Similarly, the Bhēraghat inscription<sup>3</sup> of Alhaṇadēvī, queen of his grandson Gayā-Karṇa, says that "while this king (Lakshmi-Karṇa) of unprecedented lustre, gave full play to his heroism, the Pāṇḍya relinquished violence, the Murala gave up his arrogant bearing, the Kuṅga entered the path of the good, Vaṅga trembled with the Kaliṅga, the Kīra stayed at home like a parrot in the cage, (and) the Hūṇa left off being merry." Muralas were the people who inhabited the country on the banks of the river Murala in North Konkaṇa.<sup>4</sup> Kuṅga has been taken as the Koṅgu country.<sup>5</sup> From the mention of the Chōḷas and the Pāṇḍyas along with the above, it has been proposed that Lakshmi-Karṇa should have also fought in South India. Perhaps he takes this credit from the engagements in which he participated along with the Western Chāḷukyas against the Chōḷas. But one thing seems clear. Karṇa seems to have strengthened his hold in the north and Kanyākubja passed under his sway. This is evident from the Basahi plates<sup>6</sup> of Gōvindachandra, the Gāhaḍavāla king of Kanyākubja, which says that before Chandradēva of that family became the ruler of Kanyākubja, the country was ruled by Bhōja and Karṇa.

But the Chōḷas would not have allowed this loss of their prestige in the North to go unchecked. They would certainly have

---

1. *Ep. Ind.*, vol. II, p. 4, verse 14. Gaṅgēyadēva, his father, is said to have constructed a *mēru* at Banāras (Ibid., p. 15, verses 9.) Karṇa named his construction as *Karṇamēru* after his own name evidently to distinguish it from the other. *Mēru*, according to the *Bṛhat-Samhitā*, denotes a particular kind of temple, hexagonal, with twelve stories variegated windows, and four entrances.

2. *Ind. Ant.*, vol. XVIII, pp. 215-17.

3. *Ep. Ind.*, vol. II, pp. 11.

4. N. Venkataramanyya; *The Chāḷukyas of Lēmulavāḍa*, p. 67.

5. H. C. Ray: *Dynastic History of Northern India*, vol. II, p. 778.

6. *Ind. Ant.*, vol. XIV, p. 103.

tried to regain their former position. The *meykkīrtti* of Virarājendra<sup>1</sup> commencing with the words *Viramē tuṇaiyāgavum* mentions that he "recovered Kannakuchchi," i.e., Kanyākubja (*Kannakuchchi miṭṭu*). This victory, according to the epigraph, was obtained by him in the course of his campaign marching his forces to Śakkarak-kōṭṭam after his success over the Western Chālukya Sōmeśvara II before he had time even to unite his *kanthikā*, i.e., the occasion of his coronation as king (on the 11th April A.D. 1068). At the end of the campaign, the Chōla is said to have maintained the boundries (*ellai-keḍādu-nilaiyiṭṭu*<sup>2</sup>) of his kingdom which lay spread from the Himālayas to the Sētu. (*vaḍa tiṣai-Imayattoḍuṇ-kiḍanda-Sētu varambāga-ḥ-chengōl śelutti*<sup>3</sup>). In these campaigns, Virarājendra was perhaps helped by his nephew and the Eastern Chālukya prince, the future Kulōttuṅga Chōla I, who was then staying at the court of his maternal uncle having lost his patrimony, the Vēṅgī country, to his paternal uncle Vijayāditya. The inscriptions<sup>4</sup> of Kulōttuṅga I state that in his *iḷaṅgo-p-paruvam*, when he was still a prince, with the aid only of the strength of his arms and his sword, he overcame the treachery of his enemies, captured many herds of elephants, levied tribute from Dhārāvarsha of Śakkarak-kōṭṭam and routed an army of the king of Kuntala and thus donned the garland of victory in the north. These epigraphs, though they elaborate his achievements as a ruler make only a brief reference to the victories gained as a prince. The *Kalīṅgattu-p-parani*<sup>5</sup> mentions that Kulōttuṅga I gained a victory in Mithilā in the battle of which many elephants were killed. But this victory is not mentioned in any of his *meykkīrttis* even though

1. S.I.I., vol. III, No. 83.

2. The variant reading is *ellai kadandu nilaiyiṭṭu* which will mean 'crossed the boundaries and fixed them.'

3. *Ep. Ind.*, vol. XXI, p.

4. S.I.I., vol. III, Nos. 64-8.

5. Kaḍid-aḷindu pōr Mitilaiyirpaḍum  
kari-maruppinai-t-tiraḷ tulam-eṇum  
paḍi parappi y-ap-paruma yaṇaiyin  
paḷu-v-elumbinil pā-v-aḍukkiyē

*Kalīṅgattupparani*, tāḷiṣai 87 (Pandit A. Gopala Aiyar's edition).

we have several *meykkīrttis* each with some variant forms.<sup>1</sup> Very likely it took place in his campaign in the north during the reign of Virarājendra.

Vikramāditya also was engaged, according to the *Vikramāṅka-dēva charita*, during the last years of his father Sōmēśvara I, in a military expedition in the course of which he is said to have marched his armies as far as Gauḍa and Kāmarūpa.<sup>2</sup> He was encamped on the banks of the Krishṇa on his way back home after his conquests when the news of his father's death reached him.<sup>3</sup> It is possible that while the two brothers were engaged in attending to the affairs created by the death of their father, Virarājendra pushed north and regained the territories lost during Vikramāditya's expedition, culminating in the recovery of Kanyākubja.

It will thus be seen that the Chōlas were able to maintain, in spite of a temporary set back in the middle in consequence of the bitter rivalry between the Chōlas and the Western Chālukyas for supremacy, their sway in the north obtained during the days of Rājendra Chōla's expedition to the Gangetic region, up to the close of reign of Virarājendra.

This hostile relation between these two rival powers underwent a change on the death of Āhavamalla Sōmēśvara and a further change on the death of Virarājendra two years later.

Soon after his father's death and brother's accession, Vikramāditya VI quarrelled with his brother and left Kalyāṇa with his younger brother Jayasimha, and destroyed the troops sent by his elder brother Sōmēśvara in pursuit of him. He reached the Tuṅgabhadra and rested his army for a time.<sup>4</sup> Virarājendra mentions in his *meykkīrtti* that he forced Sōmēśvara (II) to abandon the Kannaḍa country and invested the Śaḷukki Vikramāditya with the

1. K. A. Nilakanta Sastri, *The Chōlas*, vol. II, p. 2.

2. *Ind. Ant.*, vol. V, p. 319.

3. *Vikramāṅkadēva charita*, Sarga VI, verse 36.

4. *Ibid.*, Sarga IV, verse 69 to Sarga V, verse 10.

*kaṇṭhikā* and Raṭṭapādi Seven and a half lakh country conquered on behalf of the latter who sought the aid of the Chōḷa.<sup>1</sup> Jayakēśi the Kaḍamba king of Goa who was ruling in this period, is said in Kaḍamba inscriptions<sup>2</sup> to have placed the Western Chāḷukya firmly on his own throne, and that he caused the Chāḷukyas and the Chōḷas to become friends at Kāñchī. Bilhaṇa states that Virarājendra gave his daughter in marriage to Vikramāditya and cemented the alliance.<sup>3</sup> Thus as a consequence of the powerful intercession of the Chōḷa monarch, Sōmēśvara II was compelled to part with portions of his hereditary dominions to Vikramāditya almost immediately after his accession to the throne. The Chāḷukyan empire thus became divided and the southern part seemed to have gone to Vikramāditya. One phase of the Chōḷa-Chāḷukya rivalry thus came to an end. If Virarājendra had lived for some years after this settlement instead of dying very soon after it, the course of history may have been very different from what it turned out to be.

*Adhirājendra and the accession of Kulōttunga I.*

Virarājendra died in the first half of A.D. 1070 in the eighth year of his reign and was succeeded by his son Adhirājendradēva. An inscription<sup>4</sup> from Sittamalli near Muttupetṭai in the Tanjāvūr district discovered by me early in 1944, dated in the 3rd year 329th day of the reign of Adhirājendra contains astronomical details, Rishaba, Śu. prathamā, Tuesday and Rōhiṇī yielding the equivalent date, 3rd May, 1071 A.D. This will give the 9th June, 1068 A.D. as the date for the commencement of his reign.

---

1. S.I.I., vol. III, p. 84.

2. *Journal of the Bombay Branch of the Royal Asiatic Society*, vol. IX, p. 282: see also *Bombay Gazetteer*, vol. I, part II, p. 567.

3. *Vikramāṅkadēva charita*, Sarga V verse 28 to Sarga VI verse 3.

4. This has since been copied by the Epigraphy Department and registered as No. 5 of 1945-46. It is being edited by me jointly with Prof. K. A. Nilakanta Sastri for publication in the *Epigraphia Indica*.



Hitherto it was presumed that Kulōttuṅga I ascended the Chōḷa throne after the demise of Adhirājendra whose reign was taken to be a very short period, probably of some weeks' duration, as there was no direct heir to the throne in the main line and as the realm was in the throes of anarchy. But we have seen above that Adhirājendra was alive and ruling the Chōḷa kingdom nearly eleven months after the date claimed for Kulōttuṅga's accession, i.e., the 9th June, 1070 A.D. which is generally taken as to the Chōḷa throne.<sup>1</sup> It is therefore necessary to re-examine the circumstances under which Kulōttuṅga I got the Chōḷa throne.

The majority of his later inscriptions, especially those from the Telugu country giving both his regnal years and Śaka dates reckon 1070 A.D. as the initial year of his reign. It is generally considered not possible to take this date as that of his accession to his patrimony, the Vēṅgī throne, as that country had long ago slipped out of his hands.

Vēṅgī was the hot-bed for intrigues and severe incessant warfare even during the days of his father Rājarāja-Narēndra, who was not allowed to have a peaceful life or reign. Rājarāja-Narēndra was the son of Kundavai, daughter of the Chōḷa emperor Rājarāja I, who was married to Vimalāditya of the Eastern Chāḷukyas during the days of their exile in the Chōḷa country. Vimalāditya was crowned king of Vēṅgī on the 10th May, 1011 A.D.<sup>2</sup> He is said to have occupied the Eastern Chāḷukya throne for seven years.<sup>3</sup> But his Raṇastapūṇḍi grant<sup>3</sup> is dated in his eighth regnal year. He should have died early in his eighth regnal year, sometime late in 1018 A.D. Several of Rājarāja's inscriptions, which are dated in the Śaka as well as in his regnal years, definitely indicate that his reign commenced about this time. Yet his coronation took place only in A.D. 1022, which according to his Kōrumelli plates<sup>3</sup> corresponded to Thursday 16th August of

---

1. *S.I.I.*, vol. III, p. 127.

2. *Ep. Ind.*, vol. VI, p. 359.

3. *Kōrumelli grant of Rājarāja-Narēndra in Ind. Ant.*, vol. XIV

that year. There is thus an interval of nearly four years before the commencement of his reign and his actual coronation. The reason for this interval has not been satisfactorily accounted for. There is good ground to believe that Vijayāditya, another son of Vimalāditya, born of Meḷama or Mēdama, also a princess of the Chōḍa family, probably of the Telugu-Chōḍa origin, and thus a half-brother of Rājarāja-Narēndra, captured the throne of Vēngī on the death of his father, probably with the help of the Western Chālukyas of Kalyāṇa.<sup>1</sup> The unfortunate Rājarāja had to turn to his maternal uncle Rājendra Chōḷa I for help.

Tamil inscriptions<sup>2</sup> from Kottaśivaram and Madakasira in the Madakasira taluk of the Anantapur district, dated in the 10th regnal year of Rājendra Chōḷa I refer to a Chōḷa invasion over Vēngī which was led by Araiyan Rājarājan *alias* Vikrama Chōḷa Śōḷiyavaraiyan at the instance of his master. Śōḷiyavaraiyan, according to these inscriptions, compelled the king of Vēngī to flee from his country, destroyed the family of Jayasiṅga and defeated in battle the Kaliṅgas, the Teliṅgas, the Kuliṅgas and the Oḍḍas. It will be clear from this that Vēngī was ruled, in this interval, by a king who was hostile to the Chōḷas and friendly with the Western Chālukyas (of the family of Jayasimha), the political rivals of the Chōḷas. This monarch could not have been Rājarāja-Narēndra, not only because of the close kinship between them, but because of his coronation immediately following the Chōḷa victory in Vēngī as also of the friendly relations evidenced in the inscriptions between them throughout his reign. The subsequent history of Vijayāditya also points to the same conclusion. The intervention of Rājendra I in the affairs of Vēngī and the consequential coronation of Rājarāja-Narēndra as king there, driving out Vijayāditya, did not secure for Narēndra the uninterrupted reign he desired. Once again, Vijayāditya drove his half-brother out of the kingdom and crowned himself monarch on the 27th June, 1031 A.D.<sup>3</sup> In this he seems to have been

1. N. Venkataramanayya: *The Eastern Chālukyas*, pp. 218-22.

2. Inscriptions Nos. 23, 24, 30, 31, 751 and 752 of 1917.

3. *Pāmulavāka plates of Vijayāditya* in the *Journal of the Andhra Historical Research Society*, vol 11, p. 287.

helped by the Western Chālukyas whose subordinate he was. The Chōlas had again to intervene in the affairs of Vēngi taking up the cause of their protege and subordinate Rājarāja-Narēndra and restore him on the throne. Thus the throne of Vēngi, instead of merely being the cause of a civil war between two brothers, became the bone of contention between the rival powers, the Chōlas and the Western Chālukyas, espousing the cause of their respective candidates.

The fortunes of Rājarāja-Narēndra again underwent a change. The accession of Āhavamalla Sōmēśvara to the Western Chālukya throne in 1042 A.D. and the death of Rājēndra Chōla two years later brought the issue to a crisis. Vēngi, together with Kalinga which formed part of it, passed into the hands of the Western Chālukyas from the Chōlas. The attempts made by Rājādhirāja and Rājēndra II to oust Sōmēśvara from Vēngi were not successful.<sup>1</sup> This is borne out clearly by the Chōla records themselves. The Chārāla plates<sup>2</sup> of Virarājēndra, the *praśasti* portion of which is the same as that of his Kanyākumari inscription<sup>3</sup> expressly state that "the Vēngi and the Kalinga countries which had been inherited by his two brothers but left uncared for by them, having been taken away by powerful enemies were conquered back by this king Vallabha-Vallabha (i.e., Virarājēndra) crushing these highly powerful foes."<sup>4</sup> The failure of the Chōlas to free Vēngi from enemy

1. N. Venkataramanayya : *The Eastern Chālukyas of Vēngi*, pp. 231 ff.

2. *Ep. Ind.*, vol. XXV, No. 25.

3. *Trav. Arch. Series*, vol. III.

4. Bhrātṛibhyām sam-upēkshitam janapadam  
vamsa-kram-abhyāgatam  
krāntam vairi-mahiśvarair-atibalair-v  
Vēngi-Kalingān-api  
jitva śatru-param-param-atibalām  
bhitva cha durgān bahūn  
śrīman Vallabha-Vallabhaḥ kṣhitipatiḥ  
kṣhēmēṇa tam sō-nvasāt.

Chārāla plates; verse 77.

occupation compelled Rājarāja-Narēndra to accept the suzerainty of the Western Chālukyas, thus retaining his crown, as an alternative to his fleeing from his kingdom as a fugitive to the Chōlas. He accepted some of the characteristic Western Chālukya titles as also a representative of his overlord in his court. Nārāyaṇa Bhaṭṭa, one of Sōmēśvara's *pradhānis* is found there. 'He was also a great poet and a fellow student of Nannaya Bhaṭṭa, Rājarāja's poet-laureate, whom he helped in the composition of the *Āndhra Mahābhārata*. Rājarāja granted him in A.D. 1051-52 the village of Nandamapūṇḍi, as a reward for his labours.' He also figures in an inscription dated 1055-56 A.D. at Drākshārāmam.<sup>1</sup>

Rājarāja-Narēndra reigned Vēṅgī for forty-one years, at the end of which period, Vijayāditya appropriated the kingdom of the earth, "in the absence of his half-brother Rājarāja." <sup>2</sup> The actual word used is *parōksham* which means 'when not seen.' The language of the inscription even raises a doubt if Vijayāditya waited till the natural end of his brother's life or deposed him earlier. Yet he did not himself rule the kingdom which he had so eagerly seized. He installed his son Śaktivarman II on the throne and this coronation took place on Thursday, the 18th October 1061 A.D. Śaktivarman II ruled only for a short period. His reign lasted, according to the Ryāli plates, for one year at the end of which period he is said to have gone to heaven 'like Abhimanyu.' This implies that he lost his life while fighting against heavy odds. Vijayāditya, like his puranic ancestor Arjuna with whom he compares himself, resumed the government of Vēṅgī despite the calamity. This is corroborated by an inscription <sup>3</sup> at Drākshārāmam of his daughter Sōvaladēvi dated Śaka 987 (A.D. 1065). It will be seen from the above that Vijayāditya was hostile to his half-brother Rājarāja-Narēndra from the beginning and that he bore the same attitude towards the latter's son, the future Kulōttuṅga. He is said to have ruled over Vēṅgī for fifteen years.

---

1. S.I.I. (Texts), vol. IV, No. 1010.

2. Ryāli plates of Vijayāditya, *Journal of the Andhra Historical Research Society*, vol. IX, p. 31.

3. S.I.I., (Texts), vol. IV, No. 1007.

Virarājendra had, of course, before him always the aim of reconquering Vēṅgī and Kaliṅga which formerly formed part of the Chōḷa dominion. He invaded Vēṅgī twice.<sup>1</sup> It is only in the second invasion which took place in his fifth regnal year (1067. A.D.) that any mention is made of Vijayāditya. Vēṅgī, then conquered by the Chōḷa, was bestowed on Vijayāditya who submitted to the victor. Kulōttuṅga, who was then known only as prince Rājendra, is nowhere mentioned.

It is generally believed that the date 9th June A.D. 1070 claimed for the accession of Kulōttuṅga I could not refer to the throne of Vēṅgī, but to that of the Chōḷa kingdom. It could not also be the date of his accession for the Chōḷa throne as the Sittamalli epigraph clearly points out that Adhirājendra was then alive and ruled the realm for eleven months subsequently.

Then what does this date signify? For an answer to this question, it is necessary to have a clear idea of the happenings in the country immediately following the death of Virarājendra and in the early years of the reign of Kulōttuṅga I.

The *Vikramāṅkadēva charita* of Bilhaṇa gives the story as follows : Shortly after the marriage of Vikramāditya, his father-in-law the Chōḷa king died and the Chōḷa kingdom fell into a state of anarchy. When he heard of these, he set out for Kāñchī, with the

---

1. S. I. I., vol. III, No. 30, p. 67. The first invasion of Vēṅgī appears to have taken place in 1063 A.D. immediately on his accession to the Chōḷa throne. The chief opponent was Āhavamalla and except for the defeat of the Chāḷukyan general Chāmuṇḍarāja, this expedition did not accomplish much (*Ep. Ind.*, vol. XXV, pp. 248, 251). The death of Śaktivarman II probably also took place sometime about this period. From the Tirumukkūḍal inscription which is also dated in his fifth regnal year, a third invasion also appears to have taken place early in 1068 A.D. (*Ibid.*, vol. XXI, p. 232). This portion of the *meykkīrtti* is very much damaged. The opponent was 'that Chāḷukya' (*ach-chalukki*) who came out with an army twice in numerical strength to what he had marshalled on a former occasion and the scene of action was Vēṅgī.

definite object of helping the late king's son to the throne. At Kāñchi Vikramāditya spent some days in bringing the wicked (*dushtavarga*) to their knees, and then marched to Gaṅgākūṇḍa where he destroyed the forces of the enemy and finally secured the throne for the Chōḷa prince. After spending about a month in that city, Vikramāditya, apparently satisfied that peace had been restored, returned to the Tuṅgabhadra. "After the lapse of only a few days, when the Chōḷa (Adhirājendra) was slain in a rebellion of his subjects, the lord of Vēṅgī, Rājiga by name, took possession of his throne by the concurrence of fortune. This crooked-minded man suspected danger from him (Vikramāditya), and in order to create a diversion in the rear, he put himself straight with Somadēva, i.e., Sōmēśvara II, his (Vikramāditya's) natural enemy.....What has this noble-minded (Vikramāditya) done to his elder brother, that the latter should, with intent to injure him, enter into a compact with their family foe, the Chōḷa Rājiga? When the king's son (Vikramāditya) started on his expedition for the chastisement of the impolitic Rājiga, Sōmadēva (i.e., Sōmēśvara II) pursued him quickly at the back with his entire forces.....When the mass of the Drāviḍa army drew near the liberal-handed prince (Vikramāditya), this king (Sōmēśvara) also approached, having gained at last an opportunity of injuring (him)."<sup>1</sup> The battle was fought. But the victory rested with Vikramāditya; Rājiga fled and Sōmēśvara was taken prisoner. This lost Sōmēśvara the throne; and shortly afterwards, according to the poem, Vikramāditya allowed himself to be proclaimed ruler of the Dakhan<sup>2</sup>.

The version of Bilhaṇa given above designates Rājiga, i.e., Rājendra, the former name of Kulōttuṅga I by which he was then known, as the lord of Vēṅgī, when he seized the Chōḷa throne rendered vacant by the death of Adhirājendra an account of a fresh rebellion in the country. It might be that Bilhaṇa described him likewise to show that Rājiga had no right to the

1. K. A. Nilakanta Sastri, *The Chōḷas*, vol. II, pp. 8-9.

2. *Ind. Ant.*, vol. XX, p. 281.

Chōḷa throne. But it is also possible that he was actually the ruler of Vēṅgī at that time. Bilhaṇa was the court-poet of Vikramāditya, and Vijayāditya who had been ruling over Vēṅgī was the trusted subordinate of the Western Chāḷukyas. The poet would certainly have had reliable information and as such would not have mentioned Rājiga as the lord of Vēṅgī had he not been actually ruling over that country then. It is also to be noted that in the same *sarga* a few lines later, Bilhaṇa designates Rājiga as the Chōḷa and we know that he was then the actual ruler of the Chōḷa kingdom. Thus there is no reason to doubt the above statement.

The death of Adhirājendra could not be placed earlier than the date of his Sittamalli inscription on which date he was alive. And it is also possible to fix fairly approximately the time of his death. An inscription <sup>1</sup> from Śrīraṅgam containing the *meykkīrtti* beginning with the words *Pugal śūḷṇḍa puṇari* and dated in the 11th regnal year of Rājakēsarivarman Chakravartin Kulōttuṅga I mentions an interesting piece of information in this connexion. It registers the decision of the *sabhā* of the village Rājamahēndra-chaturvēdi-maṅgalam remitting the taxes on certain lands belonging to the temple of Mummudi Śōḷa Viṇṇagar Ālvār of their village for the consideration of a lump sum of seventy *kaḷaṇṇu* of gold. The record mentions "that in the second regnal year of the king there was a clash between the Right-hand and Left-hand communities, in which the village was burnt down, the sacred places destroyed, and the images of the deities and the treasury in the temple looted by the robbers. The articles that escaped their spoliation could not be properly safe-guarded in the temple. Hence as the village had to be rehabilitated, the temples renovated and reconsecrated and new walls had to be built for the *prākāra*, the *sabhā* took a loan of fifty *kaḷaṇṇu* of gold which is stated to have been half a carat less in fineness than the *Rājendra-Śōḷan-māḍai* from the temple. The interest on this accumulated to twenty-five *kaḷaṇṇu* in one year and out of the total seventy-five *kaḷaṇṇu*, five *kaḷaṇṇu* was spent towards the renovation and reconsecration

---

1. No. 31 of 1937.

of the temple in the third regnal year and the balance of seventy *kaḷaṇḍu* was utilised in purchasing and making tax-free some specified lands for the upkeep of the temple".<sup>1</sup> On the margin of the record on stone, it is inscribed that 'this *kaḷvetṭu* (epigraph) belongs to Rājamahēndra-chaturvēdimāṅgalam'. This village is stated to be situated in Kāṇḍāra-nāḍu, a sub-division of Nittavinōḍa-vaḷanāḍu, comprising the modern taluks of Nannilam and Pāpanāśam in the Tañjāvūr district. From a record<sup>2</sup> from Nellitōppu (in the Pāpanāśam taluk) which is at distance of about five miles to the east of Tañjāvūr, it can be inferred that Rājamahēndra-chaturvēdimāṅgalam was close to that village. It is not clear why an inscription relating to this village, instead of being inscribed on the walls of the local temple, should be engraved on the walls of the Śrīraṅgam temple nearly forty miles away.

But one thing seems clear from the record. There was a very serious trouble very near Tañjāvūr in the second regnal year of Kulōttuṅga I in which much damage was done to the properties and even temples did not escape the nefarious activities of the rebels. The inscription states that this rebellion took place in the month of Āni of the second year,<sup>3</sup> which would correspond to June, 1071 A.D. An inscription<sup>4</sup> of Rājakēsarivarman Rājēndra with the *meykkīrtti* beginning with the words *Tirumanni viḷaṅgum* dated in his second regnal year has been secured from Kaṇḍamaṅgalam on the northern bank of the Coleroon in the South Arcot district. Another record<sup>5</sup> of the same regnal year with the *meykkīrtti* beginning with the words *Pūmaruviya tiru-maḍandaiyum* from Vaḷuvūr in the Tañjāvūr district yields the date 29th

---

1. *Annual Report on S. I. Epigraphy* for 1936-37, para. 27.

2. No. 537 of 1921.

3. The mention of the month of Āni in the record is not referred to in the Report. I owe it to the courtesy of the Government Epigraphist for India who allowed me a perusal of the ink-impression of the record.

4. No. 358 of 1917.

5. No. 425 of 1912.



November, 1071 A.D.<sup>1</sup> These will show that Kulōttuṅga was then in possession of the heart of the Chōḷa country. As such, the death of Adhirājendra, which should have taken place earlier than this, should have occurred between the months of May and November of that year. We may not therefore be far wrong if we take the rebellion which took place in June 1071 A.D. at the commencement of the fourth regnal year of Adhirājendra as the one in which he lost his life.

It is quite possible that Kulōttuṅga I or Rājendra as he was then known, was the ruler of Vēṅgī at that time. The Korni plates<sup>2</sup> and the Vizagapatam plates<sup>3</sup> of the Kalinga king Anantavarman Chōḍagaṅga state that his father Rājarāja "first became the husband of the goddess of victory in battle with the Dramiḷas, and then wedded Rājasundari, the daughter of the Chōḍa king ; and when Vijayāditya beginning to grow old, left (the country of) Vēṅgī, as if he were the sun leaving the sky (i.e., the setting sun), and was about to sink in the great ocean of the Chōḍas, he, Rājarāja, the refuge of the distressed, caused him to enjoy prosperity for a time in the western region." The Eastern Gaṅga king Rājarāja ascended the Kalinga throne on the 20th May, 1070 A.D.<sup>4</sup> As such, these victories claimed for him should have taken place only after that date.

The flight of Vijayāditya from Vēṅgī and his subsequent restoration to its throne by the Kalinga king should have taken place earlier than 1072 A.D. as we have a few inscriptions<sup>5</sup> of Vijayāditya dated in his 12th and 13th years even though no records of his reign have been found for a period of four years

---

1. *An. Rep. on S.I. Epigraphy*, 1914, App. D.

2. *Journal of the Andhra His. Research Soc.*, vol. I, pp. 106 ff.

3. *Ind. Ant.*, vol. XVIII, pp. 166 - 9.

4. *An. Rep. on S.I. Epigraphy*, 1919, App. A, No. 4.

5. Nos. 8 and 9 of 1924-25 ; *S.I.I. (Texts)*, vol. VI, No. 1011; *Journal of the Andhra Hist. Res. Soc.*, vol. VII, pp. 177-78.

previous to that. The Dīrghasi inscription<sup>1</sup> of Vanapati, the commander of Rājarāja Dēvēndravarmān, dated in 1075 A.D. makes a pointed reference to the successes gained by him on behalf of his overlord against the Chōḷa forces.

It is also to be noted that Vijayāditya when he had to flee from his country this time took refuge in Kalinga and did not go to the Western Chāḷukya whom he had served faithfully for long. This would imply that the enemy who drove him out should have had the support of the Western Chāḷukya. Evidently Vijayāditya lost the favour of his former overlord. The Western Chāḷukya kingdom itself was at this time divided into two : Vikramāditya ruling over the southern parts with the title Tribhuvanamalla and Sōmēśvara II from Kalyāṇa over the northern part. Thus if Vijayāditya were to turn to the Western Chāḷukya for help, it would have been only to Sōmēśvara II, who seemed to have withheld such help from Vijayāditya and probably offered it to his enemy. Very likely, Vijayāditya had earlier sided with Vikramāditya and his father-in law the Chōḷa king in their attempt to secure a portion of the Western Chāḷukya kingdom to Vikramāditya and this would certainly have inflamed Sōmēśvara against him. The only person who could then have captured Vēṅgi from its actual ruler was prince Rājendra, the future Kulōttuṅga I. We know that he was in friendly terms with Sōmēśvara II and obtained his help when he, Kulōttuṅga, had subsequently seized the Chōḷa throne on the death of Adhirājendra and Vikramāditya marched on the Chōḷa country to chastise him. Probably, the friendship between Kulōttuṅga and Sōmēśvara originated even earlier when the latter became hostile to his brother.

Evidently, Kulōttuṅga also found the circumstances as such that unless he made a bold bid then and seize his hereditary throne, his chances of ever getting it were very remote and that the present time was most favourable for making such an attempt. Vīrarājendra who had conquered Vēṅgī only a few years earlier bestowed it

---

1. *Ep. Ind.*, vol. VII, p. 317.

back on Vijayāditya, ignoring his own nephew and the rightful heir to the throne, probably because he had to reckon with the power of the Western Chālukyas whose subordinate Vijayāditya was. But now the Western Chālukya empire itself was divided between the two brothers who were bitter rivals. Virarājendra was now dead, and was succeeded by his son Adhirājendra for whom Kulōttuṅga had no love.

Very likely, Kulōttuṅga had an eye on the Chōḷa throne from the very beginning and in this he was probably encouraged by Sōmēśvara who might have thought that the alliance of Adhirājendra and Vikramāditya would become formidable. He might also have found it difficult to openly rise in rebellion and invade the Chōḷa dominion. He therefore tried to foment internal unrest in the country and in this he was probably aided by his ally Sōmēśvara.

From the Śrīraṅgam inscription referred to above, it is seen that the rebellion in which Adhirājendra lost his life took the form of a clash between the *Valaṅgai* and *Iḍaṅgai* divisions. It appears that there was a deep-seated antagonism between these two sections which often burst into open hostilities in later days. The quarrels among these divisions often threatened to fill the streets of Madras with blood in the days of the East India Company. At Kāñchipuram, it is said that these two divisions would not worship in the same temple or use the same pavilion (*maṇḍapa*) for religious purposes.<sup>1</sup> These disputes are almost of a social character and the compacts referring to them are the settlements defining the social privileges to which members of each section were entitled.

The existence of these two broad-divisions among the various sections of the population in the Tamil country has been known for a very long time; but what exactly these terms signify is not clear. Their origin seems to have been forgotten even seven hundred years ago as evidenced by an inscription<sup>2</sup> from Ūṭṭattūr

---

1. *An. Rep. on S.I. Epigraphy*, 1921, para. 47.

2. No. 489 of 1912.

in the Tiruchirāppalli district of the fortieth regnal year of Kulōttuṅga III which gives the earliest account so far known of the beliefs of the *Idaṅgai* classes regarding their origin. "They claimed to have been created from the *agni-kunḍa* (fire-pit) for the protection of the sacrifice of Kaśyapa, and to have settled in the Chōḷa country in the time of the emperor Arindama; this emperor imported a large colony of holy Brahmins from *Antarvēdi* (i.e., the country of the Gaṅgā-Yamunā doab) and the *idaṅgai* classes accompanied these Brahmin colonists as the bearers of their slippers and their umbrellas. They got some lands in five villages, all of them now in the Tiruchirappalli district, and had long lost the memory of their origin".<sup>1</sup> They then recovered it and entered into a compact among themselves to the effect that they should thenceforth behave like sons of the same parents. It will be clear from this that the origin of these divisions was not known even then and that the *Śrutimāns* had to resort to mythical stories to explain the same.

It is to be noted that the name *valaṅgai* is found associated with several regiments of the Chōḷa army like *Valaṅgai-p-paḷampadaigal*, *Alaḡiyaśōḷa-terinda Valaṅgai Vēḷaikkārappadaigal*, *Rājarājat-terinda Valaṅgai Vēḷaikkārar*, etc.,<sup>2</sup> from the days of Rājarāja I. The *vēḷaikkārar* of the *valaṅgai* appears to be a large section of the army comprising several regiments. These were the most permanent and dependable troops in the royal service.

But curiously enough, the term *idaṅgai* is not heard of in this connexion, though we hear of it otherwise even from about this time. It is always mentioned associated with the other section *valaṅgai*. An inscription<sup>3</sup> from Tiruvenkāḍu in the Tanjāvūr district dated in the second regnal year of Virarājendra making over to

---

1. *An. Rep. on S.I. Epigraphy*, 1913, para. 39.

2. *S. I. I.*, vol. II, *Introduction*, p. 9.

3. *S.I.I. (Texts)*, vol. V, No. 976.

the temple the proceeds of certain taxes from several villages named includes *valāṅgai-iḍāṅgai-maganmai* as one of the items thus made over. Another inscription<sup>1</sup> from Tiruvallam in the North Arcot district dated in the 3rd year, 200th day of Adhirājendra also mentions this tax. This has been interpreted as the poll-tax levied on all the male members of both factions who were capable of using weapons of warfare. But a perusal of the names of the sub-sects comprising the *iḍāṅgai* would show that it was composed mostly of mercantile communities and artisans.

A Tamil inscription<sup>2</sup> from Polonnaruva in Ceylon dated in the closing days of the Ceylon king Vijayabāhu perhaps contains information leading to the elucidation of the problem. The record registers the placing of the Great Temple of the Tooth Relic constructed there by the monarch under the protection of the *Vēlaikkārar* naming the temple as *Mūṇru-kai-t-tiruvēlaikkāran Daladāya-p-perumpalli*. The undertaking of the *vēlaikkārar* to have the temple under their control was arrived at by them in a meeting described in the record in the following terms: "We, of the *Mahātantra*, having called together the *Valaṅṇiyars* who are our progenitors<sup>3</sup> and the *Nagarattār* and others who always accompany us, gave it the sacred name." The epigraph is signed by the Tiruvēlaikkārar as follows: "We, the exalted *Vēlaikkārars* consisting of the *Valāṅgai*, *Iḍāṅgai*, *Śirudanam*, *Pillaiṅgal-danam*, *Vaḍugar*, *Malaiyālar*, *Parivārakkondam* and various other classes of workmen (*palakalanai*)."

The *Valaṅṇiyar* who were the progenitors of the members of the body *Mahātantra* and the *nagarattār* who always accompanied such members are known to be traders and merchantmen, even though the difference or distinction between them is not clear at present. Most probably, the term *valaṅṇiyar* represented the parental organisation known as *Nānādēsi-tisai-y-āyirattu-aiṇ-*

---

1. Ibid., vol. III, p. 115.

2. *Ep. Ind.*, vol. XVIII, p. 338.

3. The actual word used in the record is *mūtādaiyar* which has been translated as 'leaders' by the editor.

*ñūruvar* with its head-quarters at Ayyapōḷil or Ayyāvaḷi, the modern Aihole in the Bijāpur district of the Bombay State, while the other, *nagarattār*, represented the merchantmen residing in the locality. The word *tantra*, though having several meanings, would mean in the present context only the military science and the army and as such the *Mahātantra* would mean the great council of the army. It would appear from this that the *vēḷaikkārar* of the present record had something to do with the mercantile community or the merchantmen.

It is further learnt from the record that the *Mahātantra* in order to maintain the undertaking given by them, allotted one soldier from each regiment and one *vēḷi* of land for each such soldier for doing service in the temple. There are many instances in South India of temples being placed under the protection of the army. In an inscription<sup>1</sup> of the time of Kulōttuṅga Chōḷadēva (I) in the Bhaktavatsala temple at Sermādēvi in the Tirunelveli district, *Mūṇru-kai-Mahāsēnai* are represented as protecting certain charitable endowments made to that temple. In another record<sup>2</sup> from Tiruvāḷisvaran in the same district, it is stated that the local temple, its treasury and the temple servants were placed under the protection of the Chōḷa army called *mūṇru-kai-mahāsēnai*. Similarly, in a record<sup>3</sup> copied at Saṅgrāmanallūr in the Coimbatore district, which was evidently fortified and garrisoned in olden days, the soldiers were required to protect the *gōpura*, the temple and its premises.

An inscription<sup>4</sup> from Puñjai refers to *tiru-ch-shūla-vēḷaikkārar* (i.e., Vēḷaikkāra of the Śiva Temple) who sacrificed their lives by entering fire to attest the ownership of the temple in some *dēvadāna* lands. Many of the bigger temples in the country had high walls and served occasionally as forts in times of emergency, offering refuge to residents of the locality. A Pāṇḍya inscription<sup>4</sup> assigned to Rājasimha, the contemporary of the early Chōḷa

1. No. 189 of 1895.

2. No. 167 of 1909.

3. No. 188 of 1925.

4. *Ep. Ind.*, vol. XXIII, p. 285.

king Parāntaka I, from Ukkirāṅkōṭṭai, in the Tirunelveli district, which was known as Karavandapuram in those days, states that the temple was placed under protection of the *maḍiṭṭhēvakar*, i.e., 'the soldiers guarding the walls or the ramparts.' A late inscription<sup>1</sup> from Śrīvilliputtūr in the Ramnad district states that the *tiruvāśal* (sacred entrance) of the temple of Viṣṇu, Vaḍaperuṅ kōyil-uḍaiyān was to be considered as the *abhayam* (place of refuge) for the residents of the locality and certain other villages, or what was known as the *añjinān-pugaliḍam*, i.e., the place of refuge for the distressed or persons afraid. We also find a class of valiant persons of temple servants known as *Vīramuṣṭi* or *Vīrabhadra*.<sup>2</sup> We may not be far wrong if we presume that at least some temples also had in those days a regular militia.

The Polonnaruva inscription referred to above mentions the *vēlaikkārar*, as of *mūṇru-kai*, i.e., three arms or hands and some inscriptions from South India also refer to *mūṇru-kai-mahāsēnai*, i.e., the Great Army of the Three Arms or Hands. *Valāṅgai* and *iḍāṅgai* are evidently the two arms of the army while the name of the third arm is not found mentioned anywhere. *Valāṅgai* or the Right-hand probably represented the permanent military force of the State while *iḍāṅgai* or the Left-hand represented the army of the merchantmen or the mercantile guild. The third arm might possibly be the section of the militia intended for the temple.<sup>3</sup>

That members of the mercantile-guild were employed in high offices of the state in those days will be clear from an inscription<sup>4</sup> from Drākshārāmam dated in the 49th year 70th day of the reign of Kulōttuṅga I wherein Uyyavandān Tiruvaṇṇāmalaiyan Vijayabāhu Māsāttunāyan, a *pradhāni* of king Vikramabāhu of Ceylon figures as the donor. In another stone record<sup>5</sup> from Vikra-

1. No. 587 of 1926; See also *An. Rep. on S.I. Epigraphy*, 1927, para. 54.

2. Ibid. for the year, 1917, para. 36.

3. It is also possible that the three arms refer to the elephant-corps, cavalry and the infantry.

4. *S.I.I. (Texts)*; vol. IV, No. 1227.

5. Jas. Burgess and S. M. Natesa Sastri: *Tamil and Sanskrit Inscriptions* (Arch. Survey of Southern India, vol. IV), p. 14.

maṅgalam in the Madhurai district dated in the reign of the Pāṇḍyan king Māravarman Parākrama Pāṇḍya, an officer Parākrama Pāṇḍya Māsāttuvāyan figures as one of the signatories. The title *māsāttunāyan* borne by them will show that they were chiefs of the merchants.

From this it will be seen that the rebellion in the second regnal year of Kulōttuṅga referred to in his inscription from Śrīraṅgam as the clash between the Right and Left hand communities was really the clash between the royal army of the State and the army of the mercantile guild, answering to the description of the King's army and the Company's army of the early days of the East India Company.

The immediate cause and the actual course of events of this rebellion are not known. A late inscription <sup>1</sup> from Āḍuturai in the Tiruchirapalli district which mentions the ninety-eight sub-sects of the *iḍaṅgai* records the hardships to which these sub-sects were exposed at the hands of the Vanniya tenants and the Brāhmaṇa and Vellāla landlords, backed by government officials. Similar inscriptions mentioning the hardships and oppressive taxation experienced by the *iḍaṅgai* communities in different periods are found in other parts of the country. An inscription <sup>2</sup> of the third year of Kulōttuṅga I from Āvaṇi in the Mysore State is interesting in this connexion. The inscription is a record of the *Periya-vishaiyam*, the Great Assemblage, held at the suggestion of the king. It opens by saying that since the race of Chōla rulers began, no tax had been levied on cows and she-buffaloes in all the territories comprising the seventy-eight *nāḍus* of Nigarili-Śōla-maṇḍalam, the forty-eight thousand *bhūmi* of Jayankōṇḍa-Śōla-maṇḍalam, the Rājendra Śōla-p-padineṇbhūmi assigned to the *Perumbāḍai-valaṅgai-mahāsēnai* and that consequently the new levy introduced by Adigārikaḷ Śōla-mūvēndaveḷān need not be paid. The record also fixes the schedule of taxes to be levied in the eighteen *vishayas*. An identical record has been secured from

1, No. 34 of 1913.

2, No. 464 of 1911; *Ep. Car.*, vol., X, Mb. 49 (a) ; also *Introduction*, p. xxviii.



Uttanūr<sup>1</sup>. To placate the members of the mercantile community who evidently formed the *iḍangai*, the monarch abolished the *śūṅgam*, the tax on commodities carried in ships and carts, which include what we now call the 'tolls' and 'customs'. He is given the title *Śūṅgam-tavirttu-irunikki ulagāṇḍa* meaning 'who abolished the tolls and ruled the world after dispelling darkness' in an inscription<sup>2</sup> from Marudāḍu in the North Arcot district. *Kulōttuṅga-Śōlan-ulā*<sup>3</sup> mentions that he abolished this tax (*śūṅgam*) which was not abolished even in the days of the kings like Manu and others. This will show that he wanted very much to please the mercantile communities and retain their favour. This was probably the price he had to pay for the help rendered by the *iḍangai* in securing the Chōḷa throne for him by creating internal trouble and rebellion in the Chōḷa country in which Adhirājendra was killed thus paving the way for Kulōttuṅga I to seize the kingdom.

Jayaṅḍār, a court-poet of Kulōttuṅga, in his poem *Kalīṅgattupparani*, ignores the reign of Adhirājendra and makes no reference to it. After a conventional account of the early years of the prince, the poet states that Abhaya, (i.e., the Chōḷa king) made him crown-prince, and then proceeds to describe his *digvijaya* of which particulars are furnished only with reference to the northern direction, Vayirāgaram and Śakkarakkōṭṭam.<sup>4</sup> He was still in the north when the Chōḷa monarch died in the south, and there ensued anarchy and confusion until Abhaya Kulōttuṅga returned and restored order. His picture of the anarchy that preceded the advent of Kulōttuṅga is drawn in deeper colours.<sup>5</sup>

1. No. 458 of 1911; *Ep. Car.*, vol. X, Mb. 119. See also Kolar 42, *Mys. Arch. Report*, 1909-10, p. 29.

2. No. 408 of 1912.

3. "puvi-rāsa raśar Manu-mudalōr naḷil  
tavirāda śūṅgam tavirttōn."

*Kulōttuṅga-śōlan-ulā*, Kaṇṇi 26.

4. *Kalīṅgattupparani*, canto X.

5. *Ibid*, verses 27-32.

But the *Vikramaśōlan-ulā*<sup>1</sup> is explicit in stating that Virarājendra was succeeded by another king before Kulōttuṅga came to the throne. The attempt made by Kulōttuṅga to combine the *meyk-kirtti* beginning with the words *Viramē tunaiyāgavum* of Virarājendra with that of his beginning *Pugaḷ mādu viḷaṅga* was probably intended to show that he should be considered as the direct successor of Virarājendra.<sup>2</sup>

The Tēki plates<sup>3</sup> of Rājarāja Chōḍagaṅga, and the Chellūr<sup>4</sup> and Piṭhāpuram<sup>5</sup> plates of Virachōḍa, both of them sons of Kulōttuṅga and viceroys of Vēṅgī under their father, dated in the seventeenth, twenty-first and twenty-third regnal years respectively of Kulōttuṅga narrate in almost identical terms the course of events in Vēṅgī, as it was described by Kulōttuṅga himself to his son Rājarāja Mummaḍichōḷa, while sending him to Vēṅgī as viceroy. 'At the death of Rājarāja-Narēndra after a rule of forty-one years, Rājendra was first crowned as lord of Vēṅgī and attained great celebrity. He was then crowned in the Chōḍa-rājya, not less exalted in status than the position of Dēvēndra. He married Madhurāntakī, the very Lakshmi risen from the ocean, namely Rājēndradēva, the *tilaka* of the Solar race. He had seven children by her, and to one of them, Rājarāja, he said, "Child, the great kingdom of Vēṅgī was, in days gone by, entrusted by me to my paternal uncle, king Vijayāditya, as I was desirous of undertaking a conquering tour (or according to the Chellūr plates, 'as I was desirous of securing the Chōḷa kingdom'). He too, who was like a god and resembled a lion in his strength, went to heaven after ruling the kingdom for fifteen years."

The restoration of Vijayāditya to the Vēṅgī throne by the Eastern Kālīṅga king Rājarāja seems to have taken place when Kulōttuṅga was busy in completing his seizure of the Chōḷa country, settling his affairs there and bringing the realm to norm.

1. Lines 44-5—'āṅgavanpin kavalpurind-avani kāttōnum '

2. *An. Rep. on S.I. Epigraphy*, 1913, para. 33.

3. *Ep. Ind.*, vol. VI, No. 35.

4. *S.I.I.*, vol. I, No. 39; *Ind. Ant.*, vol. XIX, p. 427.

5. *Ep. Ind.*, vol. V, No. 10.

Yaśaḥ-Karṇadēva, the Chēdi king of Dāhaḷa or Tripurī, also seems to have been engaged in this expedition against Kulōttuṅga. His Khairha grant <sup>1</sup> dated in [Kalachūri] Samvat 823 or 1073 A.D. contains the following verse : “ Extirpating with ease the ruler of Āndhra, (even though) the play of (that king’s) arms disclosed no flaw, revered with many ornaments the holy Bhīmēśvara passing close to whom the Gōdāvarī with waves as her eye - brows, sings (his praises) with the seven notes of her (seven) streams, sweet like the cries of the intoxicated flamingo.” The god Bhīmēśvara of the above passage has been identified with god Bhīmēśvara at Drākshārāma. This place was the residence of the Chōḷa princes who were sent as viceroys to Vēṅgī during the reign of Kulōttuṅga I. Even a century later, when Rājādhirāja II was driven out of the Chōḷa kingdom by his rival Kulōttuṅga III, the former took refuge in Vēṅgī and resided at Drākshārāma wielding the nominal rights of a suzerain. It is likely that even in the reign of Vijayāditya, the place served as the seat of Government. This will show that the recapture of Vēṅgī by Vijayāditya with the help of the Eastern Kalinga king Rājarāja and the Chēdi ruler Yaśaḥ-Karṇa was complete. Evidently, Kulōttuṅga found it impossible to dislodge his uncle from Vēṅgī and considering his old age thought it prudent to allow him to rule over there provided the normal suzerainty of the Chōḷas, whose throne Kulōttuṅga had by that time occupied, was accepted.

The above account will show that the evidences, both literary and epigraphic, on the subject of Kulōttuṅga’s accession to the Chōḷa throne, though seem to give apparently conflicting information, are all correct in as much they contain only partial statements instead of giving the complete picture.

#### *Kulōttuṅga I.*

The Chōḷa-Chālukya relationship, when the two kingdoms were ruled by Kulōttuṅga I and Vikramāditya VI respectively, both of them powerful and having a fairly long and contemporary reigns requires a special study.

---

1. *Ep. Ind.*, vol. XII, p. 213, verse 23.

An incomplete inscription<sup>1</sup> engraved on the walls of the temple of Gaṅgaikoṇḍaśōlapuram contains a good part of the Gāhaḍavāla *praśasti* which begins *Akunṭhōtkanṭha*. The epigraph opens by citing the forty-first regnal year (1110-11 A.D.) of Kulōttuṅga and then proceeds to give the *praśasti*, but stops abruptly after mentioning Chandradēva, without giving the name of the actual ruler who makes the record or detailing the gift which furnishes the occasion for it. Madanapāla and his son Gōvindachandra were his Gāhaḍavāla contemporaries. The latest date<sup>2</sup> available for Madanapāla is 1109 A.D. and the earliest date<sup>3</sup> so far known of his successor Gōvindachandra is 1114 A.D. But the son seems to have been associated with the government even during his father's life time. Most probably the son was the donor of this record. It may also be noted in this connexion that a certain *Saugata-parivrājaka-mahāpāṇḍita* Vāgīśvara-rakshita, (a resident) of the Chōḍa-dēśa and a disciple of Śākyarakshita of Utkala-dēśa is mentioned in a copper-plate grant<sup>4</sup> dated 1129 A.D. of Gōvindachandra. Kulōttuṅga is known to have built for the Sun-god a temple known as Kulōttuṅga-śōla-mārttāṇḍālaya at Sūryanār-kōyil in the Tañjāvūr district.<sup>5</sup> His close association with the Gāhaḍavāla kings of Kanauj who were great worshippers of the sun may have given him the impetus for the construction of the temple. In the central shrine of this temple is set up god Viśvēśvara with his consort Viśālākshī, both of whom are worshipped at Banāras even to this day, and this may be taken to show that the worship of the sun was introduced from Banāras. When viewed in the light of the foregoing discussion of the Chōḍa influence in the north, especially over the Kanyākubja country from the days of Rājendra I, it seems very likely that Kulōttuṅga I also was able to maintain the same.

- 
1. No. 29 of 1908; *An. Rep. on S.I. Epigraphy*, 1908, paras. 58-60.
  2. Rahan grant in *Ind. Ant.*, vol. XVIII, pp. 14-19.
  3. *Ep. Ind.*, vol. IV, pp. 101-103.
  4. *Ibid.*, vol. XI, No. 3
  5. *An. Rep., on S.I. Epigraphy*, 1927, paras. 19-21.

The Gāhaḍavālas themselves had come to occupy the Kanyākubja region only very recently and Chandradēva whose known dates range between 1090 A.D.<sup>1</sup> and 1100 A.D.<sup>2</sup>, was the first ruler of this family who "by the valour of his arm acquired the matchless sovereignty over the glorious Kanyākubja."<sup>3</sup> He is said to have made his power felt by 'Narapati, Gajapati, Triśaṅkupati and Giripati'<sup>4</sup> and praised as 'the protector of the holy places of Kāśī, Kuśika, Uttarakōśala and Indrasthāna after he had obtained them.'<sup>5</sup> Kāśī is the well-known Banāras. Kuśika signifies Kanauj itself. Uttarakōśala was the region round Ayōdhyā. Indrasthāna has been taken as Indraprastha or ancient Delhi.<sup>6</sup> This would show that Chandradēva became practically the ruler of the whole area now known as the Uttar-Pradesh.

1. *Ep. Ind.*, vol. IX, pp. 302-05.

2. *Ibid.*, vol. XIV, pp. 197-200.

3. *Ind. Ant.*, vol. XVIII, p. 18: Cf. 'nija-bhujōpārjita-Kanyakubjādhipatya Śrī Chandradēvaḥ.'

4. *Ep. Ind.*, vol. XIV, p. 193, lines 11-12.

The last two terms *Triśaṅkupati* and *Giripati* are not met with elsewhere and it is not also known whom these two titles refer to. *Giripati* may be taken as the title of a king whose dominions embraced the hilly region for the most part. But what the other one, *Triśaṅkupati*, signifies is not clear. We hear of Śaṅku, one of the three principal cities of Nepal, the other two being Katmandu and Patan and also of a Śaṅku, whom Rajendra Chōla is said to have conquered in the course of his northern expedition. It is not known whether either of these has any connexion with this title. Then there is also the famous mythical person *Triśaṅku* for whom the sage Viśvamitra is said to have created a new universe. According to the *Si-yu-ki*, when there is no paramount monarch, the Southern, Western, Northern and Eastern parts of the Jambūdvīpa are respectively supposed to be ruled over by four kings called Gajapati, Chatrapati, Aśvapati, and Narapati. (Beal I, p. 13 and Note).

5. *Ind. Ant.*, vol. XIV, pp. 7-8: Cf. 'tīrthani Kāśī-Kuśik-Ottarakōśal-Endrasthāniyakani paripālayatādīgamyā.'

6. *Ibid.*, vol. XVIII, p. 13, fn. 33.

He also seems to have come into conflict with the Muslims. Ibrāhīm, the son of Mas'ūd I and the grandson of the celebrated invader Mahmūd, ascended the throne of Ghazna in 1059 A. D. and ruled his kingdom until 1099 A. D. He appointed his son Mahmūd, governor of his Indian possessions in 1075 A. D. Mahmūd launched an extensive campaign against Hindustan. Agra fell before his sword, and many Hindu kings offered their submission to his authority. He is said have received a large number of elephants as presents from the neighbouring ruling chiefs. Stables were erected at Kanauj for keeping these elephants and Chand Rāi was appointed to take charge of them.<sup>1</sup> This Chand Rāi has been identified with Chandradēva of the Gāhaḍavāla dynasty.

After the conquest of Kanauj, Mahmūd is said to have directed his armies towards Mālava. Mas'ud ibn Sa'd ibn Salmān, ordinarily referred to as Salmān, a Persian poet and contemporary of the Sultan Ibrāhīm and Mahmūd, describes this invasion as follows when addressing Mahmūd: "Thou didst encamp at pleasant spots in each province in the hottest season of the year. On this journey thy army destroyed a thousand idol temples, and thy elephants trampled over more than a hundred strong-holds. Thou didst march thy army to Ujjain; Malwa trembled and fled from thee."<sup>2</sup> Lakshmadēva seems to have been the king of Mālava at that time. According to the Nāgpur *prāsasti*<sup>3</sup>, this king and his brother Naravarman succeeded one after the other, their father Udayāditya. It states that 'encamped on the banks of the river Vankshu (a small branch of the Gaṅges), Lakshmadēva was presented with 'teams of frisky horses' by the Turushka, 'whom he had eradicated with ease'.

Mālava and Kanyākubja kingdoms appear to have had some close connexion in those days. The *Ṭabaqāt-i-Nāshiri* mentions

1. *History of India as told by its own Historians*, by Elliot and Dowson, vol. IV, p. 524.

2. *Ibid.*, p. 525.

3. *Ep. Ind.*, vol. II, pp. 185-95.

another such expedition on the Gaṅgā-Yamunā valley in the reign of Mas'ud III (circa 1099-1115 A.D.). We are told that the "Hājib Tughātigīn crossed the river Gaṅg, in order to carry on a holy war in Hindustan, and penetrated to a place where except Sultān Mahmūd, no one had reached so far with an army before."<sup>1</sup> Some of the details of this campaign are perhaps recorded in a poem of the above mentioned Salmān. The poet describes Kanauj as 'the capital of India, the Ka'aba of the Shamans and the Kibla of the Kāfirs.' We are told that 'all the treasures of India go to this city as the small streams pour into a large river. It has armies, wealth, elephants, and weapons.' Its king Malhī or Malhīrā was a powerful ruler, and as furious 'as a hyena.' But in spite of all his wealth and bravery, he was defeated by Mas'ud III and compelled to ransom his person by a large sum of money.<sup>2</sup>

The identity of this king Malhī or Malhīrā is not known. Scholars are inclined to identify him with Madanapāla, the Gāhaḍavāla king of Kanauj.<sup>3</sup> Jagaddēva, another son of Udayāditya, is credited in his Jainad stone inscription<sup>4</sup> to have killed a large number of soldiers of the king of Malahara at Dōrasamudra.

"In every house the weeping widows of his enemies, having seen in Dōrasamudra peak-like heaps of the skulls of their lords, who came in contact with the pointed club-like tusks of his best elephants, increase with tears the acute pain in the heart of the chief of Malahara". (verse 9).

"*Malaharakshōṇīśa* of the verse seems to be the translation of the Kanarese epithet *Malaparōḷ-gaṇḍa*, a title assumed by the Hoysaḷa rulers. *Malapa* or *Malaha* was the name of a hill-tribe to the family of whose chiefs the Hoysaḷas probably originally be-

---

1. *Tabaqāt-i-Nāshirī*, Translated by Raverty, vol. I, p. 107.

2. Elliot and Dowson, *History of India*, vol. IV, pp. 526-27.

3. *Dynastic History of Northern India* by Dr. H. C. Ray, vol. I, p. 515.

4. *Ep. Ind.*, vol. XXII, No. 11,

longed. (cf. *Ep. car.*, vol. VI, Introduction, p. 14)''<sup>1</sup> Hoysaḷas were at this time the subordinates of the Western Chāḷukya monarch Vikramāditya VI and Mālava also was under his rule as will be evident from the stone inscription<sup>2</sup> of his dated in 1087 A. D. found at Sitabaldi, six miles to the east of the city of Nagpur.

That the Hoysaḷa kings at this period had something to do with the Mālava country will be evident from the following: Kumārapāla, the Chaulukya ruler of Aṇahilapāṭaka (1144-73 A.D.), is said to have conquered a certain Ballāla who was the ruler of Mālava. The *Dvayāśraya* states that Kumārapāla, after his victory over Ānna, i.e., Arṇōrāja of the Sapādalaksha or Śākāmbharī country, was advised to win fame by subduing Ballāla. The reason why his ministers counselled him to attack Ballāla is given by Hēmachandra in another passage, where he writes that before Ānna advanced upon the frontiers of Gujarat, he formed an alliance with Ballāla, the king of Avanti, and, it was arranged that both the powers should simultaneously attack the Chaulukya kingdom from the north and the east.<sup>3</sup> It is stated that after the king had returned to Patana, "News was brought to Kumārapāla that Vijaya and Krishṇa, the two *sāmantas* whom he had sent to oppose Ballāla, when he himself advanced against Ānna, had gone over to the king of Ujjain, and that monarch was already in his territory and was advancing on Anahillapura. Kumārapāla, assembling his troops, went against Ballāla, who was defeated and struck from his elephant." This Arṇōrāja was the loyal feudatory and son-in-law of Siddharāja-Jayasimha, the predecessor of Kumārapāla who, it is to be noted, was not the son of Jayasimha but only a collateral member of the family and seized the throne driving out the adopted son of the deceased monarch. It will be evident therefrom that the trouble arose as a

---

1. *Ibid.*, p. 58, fn. 5.

2. *Ibid.*, vol. III, p. 304.

3. *Ind. Ant.*, vol. IV, p. 268.



result of the civil war. Kumārapāla is said to have sent an army to Mālava under his general Karka or Kāka—Gūrjara-Brahma-sēnānī—who was in charge of the army of Lāṭa at Nandapurī. Yaśōdhavāla, the Paramāra ruler of Arbuda or Adbhuta-maṇḍala, (Mount Abu), was also a military leader of this campaign. This will be clear from the Mount Abu *praśasti* of Tējaḥpāla which tells us that Yaśōdhavāla “quickly killed Ballāla, the lord of Mālava, when he had learnt that he had become hostile to the Chaulukya king Kumārapāla.”<sup>1</sup> Karka or Kāka who probably led this campaign had no easy time against Ballāla. Vijaya and Krishṇa, the two feudatories of Kumārapāla, openly joined Ballāla. “At one time, the army of Gujarat began to retreat, despite general’s extortations. But his enthusiasm was catching, and Ballāla was ultimately brought down from his elephant and killed in front of the Gūrjara-Brahma-sēnānī.”<sup>2</sup>

This victory of Kumārapāla over Ballāla, the ruler of Mālava, is also referred to in the Vērāval *praśasti*<sup>3</sup> of Bhāva-Brihaspati wherein Kumārapāla his patron is described as “a lion to jump on the heads of (those) elephants-Ballāla, king of Dhārā,” while his Vāḍanagar *praśasti*<sup>4</sup> states that the Chaulukya king charmed the goddess Chaṇḍī, “when she was desirous of taking a toy-lotus with the lotus head of the Mālava lord, that was suspended at his gate.”

---

1. *Ep. Ind.*, vol. VIII, pp. 210-16, verse 35.

rodaḥ-kamdaravartti-kīrtti-laharī-liptamaṇḍitaṃsu-dyutēr  
apradyumna-vaśō Yaśōdhavāla ity-asīt tanūjas tataḥ  
yaś Chaulukya-Kumārapāla-nṛipati-pratyarthitām agatām  
matvā satvaram eva Mālava-patiṃ Ballālam ālabdhavān.

2. *Ind. Ant.*, vol. IV, p. 268; *Dvyāśraya*, XVI, 22-23; *Prabandha-ehintāmaṇi*, p. 95; *Vasantavilāsa*, III, 29.

3. *Journal of the Bombay Branch of the Royal Asiatic Society*, vol. VIII, pp. 59 ff.

4. *Ep. Ind.*, vol. I, p. 302, verse 15.

These sources definitely state that Ballāla was the ruler of Mālava with Dhārā as his capital. This name was very common among the Hoysaḷas who were themselves feudatories of the Western Chāḷukyas of Kalyāṇa, like the Paramāras of Mālava. Viṣṇuvardhana who was on the Hoysaḷa throne from about 1100 to 1150 A.D. had also a son known as Ballāla. An inscription<sup>1</sup> dated 1130 A.D. mentions him as Śrīmat Tribhuvanamalla Kumāra Ballāladēva and the 'eldest son' (*agra-tanuja*) of Viṣṇuvardhana and also states that he was then ruling the world. Very likely this Ballāla was the ruler of Mālava conquered by Kumārapāla.

We may not therefore be far wrong if we presume that in those days some Hoysaḷa princes were placed by the Western Chāḷukya monarchs of Kalyāṇa to be in charge of the northern provinces of their empire like the Mālava and other regions and that such viceroys had also control over Kanauj.

About this time we also find some Rāshtrakūṭa princes ruling over Kanauj. A Set-Mahet Buddhist stone-inscription<sup>2</sup> dated in Vikrama-Samvat 1176 (A.D. 1119-20) mentions (*Gādhipurādhipa*) the lords of Gādhipura, another name of Kanauj, Gopāla and his son Madana, who are most probably to be identified with the Rāshtrakūṭa rulers of the Budaun stone record<sup>3</sup> of Lakhaṇapāla, bearing the same names.<sup>4</sup> Probably both the powers, the Western Chāḷukyas and the Chōḷas who had been trying their best to retain their hold on the north, had each of them their own representatives to rule over those regions.

This could have been possible only if these two powers had come to end their bitter rivalry arriving at some sort of an agreement. A Kannada inscription<sup>5</sup> from the Raṅganātha temple at

---

1. *Ep. Car.*, vol. VI, Mg. 22.

2. *Ind. Ant.*, vol. XVII, pp. 61-64,

3. *Ep. Ind.*, vol. I, pp. 61-66.

4. *Journal of the Asiatic Society of Bengal*, 1925, pp. 105 ff.

5. No. 204 of 1942.

Śrīraṅgam dated in the 29th regnal year of Kulōttuṅga I registers the gift of two lamps by an officer of the Western Chālukya king Vikramāditya VI, the *Kannadq-Sandhivigrahin* and *Daṇḍanāyaka* who seems to have constructed of brick and mortar the shrine of Sēnāpati, i.e., Vishvaksēna in the Raṅganātha temple. This will show that these two powers had come to have some sort of respite between them.

The Chōla monarch probably found it expedient to come to such an arrangement. A quaint reference in a Tamil manuscript of the Mackenzie collection is suggestive in this connexion. *The Pāṇḍyan Chronicle* while narrating the capture of Madurai and the establishment of a Muslim garrison there in May-June 1323 A.D. writes as follows: "Afterwards, in the Salivahana Sakabdam one thousand two hundred and forty-six corresponding with the year of the era reckoned from the destruction of Gollam (Kollam or Quilon) two hundred and twenty-seven, agreeing with Ani month of Rudhirottakari, when one named Paracrama Pandian was reigning, Athi Sultan Mulk and one called Nemi came from Delhi" and conquered the country.<sup>1</sup>

The *Chronicle* gives the date of the Muslim conquest of Madurai in two eras: (1) Śaka 1246, Rudhirōdgārin, Āni. The Śaka year given is the current year and it corresponds to May-June 1323 A.D. (2) This Śaka date is said to correspond to the 227th year of another era reckoned from the year of the Destruction of Kollam. This era is not identical with the well-known Kollam era commencing in 824 A.D. to commemorate probably the foundation of the city; but another starting some two hundred and seventy years later in 1096 A.D. when the city must have suffered destruction.<sup>2</sup>

It appears that about this time there was trouble in Veṇāḍu and that Kulōttuṅga commissioned Naralōkavira, one of his commanders, to put down the revolt and that the general des-

---

1. Taylor; *Historical Manuscripts*, vol. I, p. 203.

2. Dr. N. Venkataramanayya; *The Early Muslim Expansion in South India*, pp. 71-3.

troyed the city of Kollam.<sup>1</sup> This fact is to be inferred from the considerable number of inscriptions which describe the services of Naralōkavira, the earliest date in these inscriptions being the twenty-eighth regnal year of Kulōttuṅga I.

The circumstances and the method of citing this era, otherwise unknown, in the *Chronicle* require an explanation when it is known that Madurai, the capital of the Pāṇḍya country, is not within the orbit wherein even the other well-known Kollam era of 824 A.D. has been in vogue. The use of this era to denote the Muslim occupation of Madurai is significant. The author of the chronicle had advisedly given both the Śaka and the cyclic years in addition, as he was quite aware that quoting merely the second Kollam era alone (commemorating its destruction) would be unintelligible and that his purpose would not be served. Thus purposely quoting this era to mark the event of the Muslim occupation of Madurai has evidently some connexion with the event.

Possibly the Kollam era of 1096 A.D. also had something to do with the Muslims, even though we do not have further details of the same. An undated inscription<sup>2</sup> of Kulōttuṅga I in Sanskrit from Chidambaram states that he erected a pillar of victory on the shore of the (western) ocean and that his praises were sung by the young women of the Pārasika country (Persia) on the further shore of the ocean. What this implies is not clear. But this in way suggests that Kulōttuṅga had some clash with the Muslims.

It is also to be noted that both Hoysaḷa Viṣṇuvardhana and the Western Chāḷukya Vikramāditya VI claim victories over Turushkas. Probably Kulōttuṅga had patched up his differences with Vikramāditya in the face of the common enemy and all of them joined hands in inflicting a crushing defeat on the Muslims.

---

1. K. A. Nilakanta Sastri: *Studies on Chōḷa History and Administration*, page 191; (See also Nos. 1271-3 of this collection).

2. *Ep. Ind.*, vol. V, pp. 103-4; (See also No. 1270 of this collection).

*The Ceylonese affair :*

It is generally believed that Kulōttuṅga I lost Ceylon early in his reign and was not able to regain it even though he made some attempts in that direction.

Prince Kitti who became the ruler, assuming the official name Vijayabāhu, of Rōhaṇa, the inaccessible hill-country in the south-eastern part of the island, freeing that country of enemies in 1055 A.D.<sup>1</sup> when he was only seventeen years old, lived up to a ripe age of seventy-three years, reigning for fifty-five years. In the fifteenth year of his reign, i.e., in 1070 A.D.<sup>2</sup> he entered Anurādhapura becoming the ruler of all-Ceylon and was crowned two years later thus establishing the independence of the island by putting an end to the Chōla power there. The time he chose for freeing the country from the supremacy of the Chōlas who had been in occupation of the northern portion of the island from about 991 A.D. and of the whole island, probably with the exception of its remotest parts, from about 1017-18 A.D., was the most favourable one. The Chōla kingdom was then in confusion consequent on the death of Virarājendra and the seizure of the throne by Kulōttuṅga waging a civil war with Adhirājendra. It is to be noted that no inscription of Kulōttuṅga or of his successors are found in Ceylon even though we have inscriptions of even the third regnal year of Adhirājendra there.<sup>3</sup>

The success of Vijayabāhu should have naturally rankled in the mind of Kulōttuṅga who was possibly waiting for a favourable opportunity. The Chōla records are silent about the steps he took or of their results. The Ceylon chronicle on the other hand refers to two such incidents. The first one took place in the 30th year of the reign of Vijayabāhu, i.e., about 1085 A.D.

---

1. *Chūlavamsa*, Chap. 57, verses 65-66; See also *Epigraphia Zeylanica*, vol. II, p. 207.

2. The dates followed are from the revised chronology in *The Early History of Ceylon* by Dr. G. C. Mendis (4th Edn., 1940), pp. 86-90 and 154. See also *Ep. Zey.*, vol. V.

3. *S.I.I. (Texts)*, vol. IV, No. 1388,

“Envoys sent by the Kaṇṇāṭa Monarch and by the Chōḷa King came hither with rich presents. They sought out the Monarch. He was greatly pleased thereat and after rendering both embassies what was their due, he sent at first with the Kaṇṇāṭa messengers his own envoys to Kaṇṇāṭa with choice of gifts. But the Chōḷas maimed the noses and ears of the Sihala messengers horribly when they entered their country. Thus disfigured they returned hither and told the King everything that had been done to them by the Chōḷa King. In flaming fury Vijayabāhu in the midst of all his courtiers had the Damiḷa envoys summoned and gave them the following message for the Chōḷa King. ‘Beyond ear-shot, on a lonely island in the midst of the ocean shall a trial of strength of our arms take place in a single combat, or, after arming the whole forces of thy kingdom and of mine a battle shall be fought at a spot to be determined by thee; exactly in the manner I have said it shall ye report to your master.’ After these words he dismissed the envoys clad in women’s apparel in haste to the Chōḷa King, then he betook himself with his army to Anurādhapura. To the seaports Mattikāvāṭatittha and Mahātīttha he sent two generals to betake themselves to the Chōḷa kingdom and begin the war. While the generals were procuring ships and provisions in order to send the troops to the Chōḷa kingdom, then, in the thirtieth year (of the king’s reign), the division of the troops called Vēḷakkāra revolted as they did not want to go tither. They slew the two generals and like rutting elephants in their unbridledness, they plundered the country round Pulatthinagara. They captured the younger sister of the King with her three sons and burned down with violence the King’s palace. The King left the town and betook himself in haste to Dakkiṇadēsa and having hidden all his valuable possessions on the Vātagiri rook, he advanced together with the Uparāja Virabāhu, of lion-like courage, and

---

1. This and the other incidents mentioned in the *chronicle* are reminiscent of the happenings in the Chōḷa - Chāḷukya wars a few years earlier. It is not known whether these were intended as reprisals to the high-handed action of the Chōḷas or were common to the period.

surrounded by a great force, to Pulatthínagara where after a sharp fight he shortly put the assembled troops to flight. Placing them around the pyre on which were laid the remains of the murdered generals, he had the recreant leaders of the troops, their hands bound fast to their backs, chained to a stake and burnt in the midst of the flames blazing up around them. The Ruler having (thus) executed there the ring leaders of the rebels, freed the soil of Lankā everywhere from the briers (of the rebels)."<sup>1</sup>

The Vēlaikkara division of the army was probably composed mainly of the Tamils, as we find in an inscription<sup>2</sup> dated 1114 A.D. a few years after the suppression of this revolt, a certain Śēdarāyan *alias* Malaimaṇḍala Nāyakan as a Vēlaikkāran of Jayabāhudeva, the brother and successor of this Vijayabāhu. These Vēlaikkāras figure very largely in the Tamil country and they are considered as the trusted and loyal members of the army. Evidently they were there in the days of the Chōla occupation of the island and continued even after the withdrawal of their regime from the island.

The Kaṇṇātas mentioned in the account probably refer to the Western Chālukyas of Kalyāṇa. That the Chālukyas had something to do with Ceylon at this period can be surmised from the following. The Nagpur *prasaṁsi*<sup>3</sup> of the Parāmara rulers contains the largest number of verses, as many as twenty *ślokas* (35-54), in praise of Lakshmadēva, the son and successor of Udayāditya. He is said to have conquered Gauḍa, Tripuri (the Chēdi country), Aṅga and Kalinga. It further states :

"When, like the pitcher-born Agastya, he directed his steps towards the south, the Chōlas and other tribes, bowing low before him, acted the part of the Vindhya Mountain. (46)

1. *Chūlavamsa*, Eng. translation by Geiger, vol. I, pp. 216-8.

2. No. 509 of Ceylon, *Ceylon Journal of Science*, Section G, vol. ii, p. 122.

3. *Ep. Ind.*, vol. II, pp. 193-4.

"The water of the Tāmraparṇī, which is famed all the earth over for pearls which the wives of the feudatories in his army, while they mirthfully bathed in the stream, dropped into it from the breaking girdles of their hips, behold, even to this day the water affords a livelihood to the Pāṇḍya Chief. (47)

"Respectfully informed by the people that the dam before him which looked like the growing Vindhya range, was the bridge of holy Rāma constructed of many mountain peaks which were fetched by Māruti, he listened attentively, but he scornfully crossed over to the opposite island simply on the elephants of his army." (48)

Nothing further is known. Evidently, the rebellion by the Vēlaikkāra troops took place at the instigation of the Chōḷas and Kulōttuṅga had a hand in it ; but the attempt did not succeed.

The other took place fifteen years later, i.e., in the 45th year of Vijayabāhu or 1100 A.D. This is described in the Chronicle as follows: "The King did not lose sight of the aim he had set himself of fighting with the Chōḷa (King), and in the forty-fifth year (of his reign) he marched with war-equipped troops to the port on the sea and stayed there some time awaiting his arrival. But as the Chōḷa (King) did not appear, the King dismissed his envoys and returned to Pulatthinagara and resided there a considerable time."

The circumstances which necessitated these two encounters and the course of events on these two occasions are not known. But one thing seems certain. The Chōḷas did not appear to have taken down meekly their defeat and the consequent loss of territory, but tried to retrieve their former position on more than one occasion as circumstances permitted. Probably they were not able to achieve their end during the reign of Vijayabāhu. But on his death in C. 1110-11 A.D. the island was again thrown into confusion by a civil war for succession to the Sinhalese throne.

According to *Mahāvamsa*, when Vijayabāhu died after a reign of fifty-five years, his son Vikramabāhu, was not at the capital by his father's side, but was ruling the distant south-



eastern province of Rohaṇa. The news of father's death was not immediately conveyed to the son who was kept in ignorance of it. Jayabāhu, the brother of the dead king, ascended the throne and nominated his sister's son, Mānābharaṇa, a prince of the Pāṇḍya line, as heir-apparent. Vikramabāhu, who was thus kept aside, did not accept the position of a mere prince assigned to him and waged a civil war with his uncle Jayabāhu for the throne. It is said that he regained his ancestral throne after two years.

It is known that Vikramabāhu was recognised as the successor even during the life-time of his father and that he was ruling over a portion of the kingdom. A Tamil inscription<sup>1</sup> from Pālamōṭṭai near Kantalāy in the Trincomallee district of Ceylon dated in the 42nd regnal year of Vijayabāhu registers the donation made by a *brāhmaṇa* lady in memory of her deceased husband to the temple of Vijayarāja-Isvaram at Kantalāy *alias* Vijayarāja-chaturvēdimaṅgalam. The record places the charity given under the protection of Śrī Vikkīrama-Śālāmēgha-t-terinda-Vēḷaikkāra naming it as such. It is therefore natural that he should have had active local support on which he could depend in his attempt to seize the throne, his patrimony.

Jayabāhu also should have had strong influence to maintain his position. At this time a foreigner, Viradēva by name, who is described in the Chronicle as Āryadēśīśa (lord of the Āryadēśa, i.e., a king from the mainland) and the sole monarch of the Palandipa country came with his army and fought battles. We do not know who this Viradēva was. But the name of his country Palandipa brings to our mind *munuṇṇir-p-palandivu-panṇṇirāyiram* (old islands of the sea numbering twelve thousands, the Maldives<sup>2</sup>) conquered by Rājārāja I. These islands are mentioned as *saṅga-adir-vēlai-t-tol peruṅkāval pal palandivu* (many ancient islands, whose old, great guard was the ocean which makes the conch resound)<sup>3</sup> in the *meykkīrtti* of Rājendra I. These islands appear

1. *Ep. Zey.*, vol. IV, No. 24.

2. *The Chōlas*, vol. I, p. 200, n.

3. *Ep. Ind.*, vol. IX, p. 233; also *The Chōlas*, vol. I, p. 241.

to have been treated as a distinct and independent region as will be evidenced by the term *Kaṇṇi-t-tenkarai-k-kaṭ-palandivam* (the old islands on the southern coast of the Kumari) occurring in a verse detailing the list of regions where impure Tamil is spoken, quoted by Mayilaināthar in his commentary on the *Nannūl*<sup>1</sup> It is also to be noted that an inscription in Tamil<sup>2</sup> from Budamuttāva in Ceylon dated in the 8th regnal year of Jayabāhu, who also claims to be a Śālāmegha like Vikramabāhu, registers the gift of a perpetual lamp to god Vikkiramasiḷāmēgha-Iśvara in the town of Mahāgala *alias* Vikkiramā Śālāmēghapura by Śuttamalliyār, wife of Virap-perumāḷ, the Pāṇḍyan, and daughter of the Chōḷa king Kulōttuṅga Chōḷa.

A Tamil inscription<sup>3</sup> from Drākshārāma in the West Godavari district dated in the 49th year 70th day of the reign of Kulōttuṅga Chōḷadēva (I) registers the gift of land and other articles by Uyyavandān Tiruvaṇṇāmalaiyan Vijayabāhu Māsattunāyan, the *pradhāni* of the Ceylon king Vikramabāhu, on the occasion of a solar eclipse for feeding fifteen *tapasvins* in the Mahēśvara-*maṭha* constructed by him there. This *maṭha* was constructed by him there in the 43rd regnal year of Kulōttuṅga I with provision for feeding thirty *tapasvins*. The landed property necessary for feeding fifteen *tapasvins* was gifted by him then<sup>4</sup> and that for the remaining fifteen was made now. The donor, evidently a person from the Tamil country, was the *pradhāni* of the Ceylon king and he made large endowments to the Śiv temple at Drākshārāma in the Telugu country. Considering that the city was the seat of provincial government in those days, the presence of this officer there becomes significant.

It is also to be noted that this was the period when Vikrama Chōḷa and Parāntaka, both of them sons of Kulōttuṅga I, were waging a civil war for the Chōḷa throne as will be

1. *Peruntogai*, No. 2109.

2. *Ep. Zey.*, vol. III, pp. 302-12.

3. *S.I.I. (Texts)*, vol. IV, Nos. 1227 and 1225.

4. *Ibid.*, No. 1246.

discussed in the sequel. Probably the Ceylonese *pradhāni* was there to help Kulōttuṅga I and his son Parāntaka in their fight against Vikrama Chōla who was being supported by the Hoysaḷas and the Western Chālukyas. This could have been possible only if the ruler of Ceylon had then been subordinate to the Chōlas. Considering the political condition which developed in the island on the death of Vijayabāhu who freed the country from foreign yoke, we may not be far wrong if we conclude that the country was once again brought under the Chōla control.

That Ceylon for some time after the death of Vijayabāhu was under foreign control is evident from the Devanagala inscription<sup>1</sup> of Parākramabāhu wherein he records as follows: "With the resolve I shall cause the revival of the State and the Church which have been ruined for forty-two years since the time when my grand-father, king Vijayabāhu, became a denizen of heaven." It will be seen therefrom that Parākramabāhu thought that for 42 years after the death of Vijayabāhu, both the government and religion of the island were not functioning properly.

It is also to be remembered that it was this Parākramabāhu who, a few years later, invaded the mainland taking up the cause of Parākrama Pāṇḍya in the Pāṇḍyan civil war. The crypt statement of the Devanagala inscription probably refers to the Chōla control over the island. Kulōttuṅga II also claims in his *meyk-kīrtti*<sup>2</sup> beginning with the words *Pūmaruviya puvi-y-ēlum* that *vīṇai-k-koḍi-ch-chiṅgaḷavar*, i.e., the Singhalese with the flag having the emblem of a *vīṇā*, were subordinate to him and paid him tribute. The same is found repeated in the *Kulōttuṅgan-piḷḷai-t-tamiḷ*<sup>3</sup> by its author, Oṭṭakkūttar, the court-poet and the tutor of the king. Kambar in his *Rāmāyaṇa* says that *vīṇā* was the emblem on the flag of Rāvaṇa, the mythical Lord of Laṅkā, who is sometimes referred to therein as *vīṇaiḱkoḍiyōn*.<sup>4</sup> But this

---

1. *Ep. Zey.* vol. III, p. 324.

2. *S.I.I.*, (Texts), vol. V, No. 645.

3. *Kulōttuṅgan-piḷḷai-t-tamiḷ*, verse 64.

4. *Kamba-Rāmāyaṇam*, Yuddha-kāṇḍam, verse 240.

information is not found in the original of Vālmiki. Evidently, Kambar had the contemporary flag of Ceylon in his mind when he wrote his *Rāmāyaṇa*.

### *Parāntaka III and Vikrama Chōla*

Kulōttuṅga I is referred to in later inscriptions as having ruled for fifty years the five *Drāvidas* together with the Andhra country.<sup>1</sup> We have inscriptions of his 49th year 333rd day as also of his 50th regnal years<sup>2</sup>. There is also an inscription<sup>3</sup> from Iḍai-yāttūr of the former Pudukkōṭṭai State of his 52nd regnal year. This king who commenced his reign with a civil war in which he came out victorious had to end in another civil war. But this time it was among his own sons.

He had seven sons through Madhurāntakī, the daughter of the Chōla monarch Rājēndradēva II, who was his senior queen.<sup>4</sup> These sons became successively viceroys of Vēṅgī after the death of Vijayāditya in 1076-77 A.D. Parāntaka, one of them, was nominated by his father as successor to the throne and crowned as co-regent with the title Parakēsari in Śaka 1033 or 1111-12 A.D. There are inscriptions of this Parāntaka III with the *meykkīrtti* commencing with the words *Pūmaṅgai vaḷara* or *Puvi-maṅgai vaḷara* up to his 9th regnal year.<sup>5</sup> His inscriptions in the Tamil country are very few. Yet we have a large number in the Telugu country. His reign is known to have continued till the last year of his father's reign, corresponding to 1119-20 A.D.

---

1. The Piṭṭapuram inscription of Mallapadēva : *Ep. Ind.*, vol. IV, No. 33, vv. 22-24.

2. No. 284 of 1923 ; 520 of 1920 ; *S.I.I.*, (Texts), vol. VII, No. 763.

3. *Inscriptions (Texts) of the Pudukkōṭṭai State*, No. 127.

4. *Ep. Ind.*, vol. VI, p. 335.

5. This has been discussed in detail by me in the paper *Two Inscriptions of Chōla Parāntakadēva : 9th year* under publication in the *Epigraphia Indica* jointly with Prof. K. A. Nilakanta Sastri.

But Kulōttuṅga I was succeeded on the Chōla throne by Vikrama Chōla another son of his and not by this Parāntaka. Vikrama Chōla counts his regnal years from the date of his accession to the Chōla throne which took place on or about the 29th June, 1118 A.D. But Parāntaka who counted his reign from some date in Śaka 1033 or A.D. 1111-12 was ruling the kingdom in his ninth regnal year, i.e., 1119-20 A.D., even after the initial date of 1118 A.D. claimed for Vikrama Chōla. We thus find Vikrama Chōla and Parāntaka, both of them sons of Kulōttuṅga, claim to rule the Chōla kingdom with the official title Parakēsarivarman as co-regents along with their father Kulōttuṅga I during the last two years of the latter's reign.

This position can only be explained by presuming that Vikrama Chōla did not recognise the selection of Parāntaka as co-regent and claimed that he, Vikrama Chōla, alone was the rightful heir. If that be the case, he could not have asserted his right and achieved his object by peaceful means. There must have been a civil war between these two brothers for the Chōla throne.

The disruption caused to the peace of the empire by the civil-war is referred to in a damaged inscription<sup>1</sup> from Karūr, one of the capitals of the Kōṅgu kingdom, dated in the 3rd year of the reign of Vikrama Chōla, corresponding to 1120-21 A.D. It states that the idol of Kūttar (i.e., Naṭarāja) in the temple of Tiruvānilai-Āḷudaiya-Nāyanār at Karuvūr in Veṅgāla-nāḍu, a subdivision of Viraśōla-maṇḍalam, which had been lost in the (days of the) revolt (*kalahattil-śēman-tappinamaiyil*) was brought back after a search and set up by the Śivabrāhmaṇas of the temple who also made provision for worshipping the same. There are inscriptions in the Tañjāvūr district dated in the 47th and 49th regnal years of Kulōttuṅga I stating that the lands of the tenants

---

1. S.I.I., (Texts), vol. IV. No. 387; See also No. 703 of this collection.

who had deserted the villages unable to pay the taxes over two years were confiscated and sold to the temples.<sup>1</sup>

A record<sup>2</sup> from Ādutturai in the Perambalūr taluk of the Tiruchirappalli district dated in the 4th year of the reign of Parākrama Pāṇḍya renews with the additional privilege for some money consideration, an old charter said to have been issued to certain *Pallī* residents in the 4th regnal year of Vikrama Chōḷa-dēva under peculiar circumstances. It is stated that 'during the war of the Periya-Vaḍugan, when the images of gods and Nāya-nārs were carried away to be deposited to Dōrasamudra (i.e., Halebid in Mysore), (the *Pallīs*) rescued them, reconsecrated them in the temple, and agreed to provide for the expense of maintaining the worship of these images, making it a part of their communal obligation, in return for which act of service, the members of the community were to enjoy the temple honours of silk *parivaṭṭam* and *aruḷappāḍu*.' It is also said that the above arrangement was approved and sanctioned by Perumāḷ Kulōttuṅga Chōḷadēva thereby indicating that the rescue of the idols was effected immediately after the removal within the life-time of Kulōttuṅga I.<sup>3</sup>

It is not clear from the inscription who the Periya-Vaḍugan waging war in the Chōḷa country was; but the mention of Dōrasamudra makes it evident that the Hoysaḷas were among the invaders. Biṭṭiga Viṣṇuvardhana, the Hoysaḷa ruler of the period, claims the title *Taḷakāḍu-koṇḍa* which is first applied to him in an inscription dated in 1117 A.D.<sup>4</sup> and in the same year he is described as ruling in Taḷakāḍu and Kolāla (Kolar) and over the whole of Gaṅgavāḍi-Ninety-six thousand as far as Koṅgu.<sup>5</sup> This province

---

1. Nos 620 and 647 of 1909 from Tiruchchirai and Kōnērirajapuram respectively. See also V. Raṅgāchārya: *A Topographical List of Inscriptions in the Madras Presidency*, Tj. 74 and 1219.

2. No. 35 of 1913.

3. *An. Rep. on S.I. Epigraphy*, for 1913, paras, 46-7.

4. *Ep. Car.*, vol. III, Ml. 31; also vol. IV, Yd. 6.

5. *Ibid.*, vol. IV, Ch. 83.

which was under the Chōlas at the time and regularly administered as a division of the Chōla empire was conquered for the Hoysala by his *daṇḍanāyaka* Gaṅga-rāja. This is graphically described in several of the Hoysala inscriptions.<sup>1</sup>

The victory gained in Gaṅgavādi was pursued by the Hoysalas even in regions beyond its frontiers. The Hoysala inscriptions of this period mention Koṅgu, Chēram, and Ānamalē as forming the southern extremities of Viṣṇuvardhana's kingdom, Viṣṇuvardhana claims to have squeezed Madurai in the palm of his hand<sup>2</sup> and extended his victorious march even upto Rāmēśvaram.<sup>3</sup>

The Hoysala incursions into the Chōla dominion were not restricted to the southern part. They appear to have carried on the expedition in the eastern direction also in the course of which Tereyūr and Kōyattūr (modern Laḍḍigam in the Chittoor district) became subject to Viṣṇuvardhana who is also credited with the conquest of Kāñchī, on which he took the title of *Kāñchī-gonḍa*. His inscriptions claim that "after conquering Kāñchī and Madurai he burnt Jananāthapura".<sup>4</sup> It is also said that he slew an Āndhra king.<sup>5</sup> Jananāthapura was another name of Drākshārāma, then the provincial capital of Vēṅgī.

There are about half a dozen undated inscriptions<sup>6</sup> of Parāntakadēva at Drākshārāma registering the oaths of fealty taken by certain persons to serve him faithfully. The occasion which necessitated such a step is not clear. But it is significant to note that these oaths were taken to serve faithfully Parāntakadēva personally and not in respect of the throne or kingdom of the Chōla or Chālukya as the case may be, probably indicating that there was

1. Ibid., vol. III, SB. 240, (old 90).

2. Ibid., vol. VI, Cm. 160.

3. *An. Rep. on S. I. Epigraphy*, 1913, para. 47.

4. *Ep. Car.*, vol. VI, Cm. 160.

5. *Mysore Inscriptions*, p. 213.

6. *S. I. I. (Texts)*, vol. IV, Nos. 1270-1274 and 1275-A.

another person at that time claiming equal rights as Parāntaka-dēva and that the oath was meant to safeguard the interests of their liege-lord Parāntaka against such a person.

It is also to be noted that the capture of Kāñchī and the burning of the city Jananāthapura are claimed not only by the generals of Vishṇuvardhana, but also by the generals of another monarch, viz., Vikramāditya VI, the Western Chālukya ruler of Kalyāṇa, at about the same time. We know that the Hoysaḷas were from the very beginning the feudatories of the Western Chālukyas and they continued to be so even at this time. It is therefore quite possible, that the Hoysaḷas were waging the war in the northern front as the subordinates and under the banner of their suzerain power, the Western Chālukya.

Viewed in this light, the Periya-Vaḍugan mentioned in the Āḍuturai inscription referred to above as waging war in the heart of the Tamil country would only mean the 'big or (elder) great northerner,' Western Chālukya king Vikramāditya VI. The exact course of the events of this campaign in the north is not clear. But that at the end of this campaign practically the whole of the Telugu country came under the sway of Vikramāditya VI is evident from the provenance of his inscriptions. Thus the Western Chālukya Vikramāditya and his Hoysaḷa subordinate Vishṇuvardhana, between themselves, overran the entire Chōḷa empire from the west and the north.

It was at this time that Vikrama Chōḷa, began to assert his rights to the Chōḷa throne and wage the civil war with his brother or half-brother Parāntakadēva. It may even be taken that these troubles started after he proclaimed himself as the rightful heir to the Chōḷa throne. An inscription<sup>1</sup> on a pillar in front of the Chōḷēśvara temple at Niḍubrōlu in the Guntur district registering the gift of land and lamps to the temple of Gōṅkēśvara at Ikshupallī by Mārāya Paṇḍa, the *daṇḍādhipa* and *mātula* of Velanāṇṭi Gōṅka is dated in Śaka 1054 and the 17th regnal year of Tribhuvana chakravartin Vikrama Chōḷa yielding Śaka 1038

1: S.I.I. (Texts), vol. VI, No. 123.



(or 1115-16 A.D.) as the date of his accession, three years earlier than the date usually assigned to him.

Kulōttuṅga I was alive when these two sons of his were fighting one another for the throne. We do not know whom he supported, but it is natural to presume that having already chosen and associated Parāntaka with the government, he would have espoused the cause of that son against Vikrama Chōḷa. And the inscriptions of Parāntaka show in unmistakable terms the above. Then Vikrama Chōḷa would have had to contend both against his brother Parāntakadēva and his father Kulōttuṅga I to achieve his object. His ultimate success, even during the life-time of his father, clearly implies that he must have had the active support of not only strong and influential local faction, but also of some strong foreign power, mightier than the Chōḷa. He was the son of Kulōttuṅga I, not by Madhurāntakī, the Chōḷa princess, but by a Hoysaḷa princess.<sup>1</sup> The invasion of the Chōḷa dominion by the Hoysaḷa king with the support of his ally and overlord the Western Chāḷukya, the avowed enemy of the reigning Chōḷa monarch, in which the Hoysaḷa bore the brunt of the war in the south as well as in the north, just before the formal proclamation of the accession of Vikrama Chōḷa, was perhaps motivated by ties of kinship. The loss of Gaṅgavāḍi in the west and of Vēṅgī in the north was perhaps the price Vikrama Chōḷa had agreed to pay the Hoysaḷa and the Western Chāḷukya respectively for the help rendered by them in securing the Chōḷa throne for him.

A stray verse<sup>2</sup> in Tamil, popular in South Travancore, records that in Kollam 292 (or 1116-17 A.D.) the Kūpaka king conquered Pāṇḍya Rājasimha and captured Nāñjil-nāḍu and Kōṭṭūru. Kulōttuṅga is known to have fortified Kōṭṭūru in South Travancore and stationed a garrison (*nilaiṇṇaḍai*) there. Jaṭavarman Parāntaka

---

1. *Kulōttuṅga-śōḷan-ulā*, kaṇṇis, 28-31. This has been discussed in the paper *A Note on the Pallavarāyanpēṭṭai Inscription of Rājādhirāja II* under publication in the *Epigraphia Indica* jointly with Prof. K. A. Nilakanta Sastri.

2. Dr. K. K. Pillai : *The Suchindram Temple*, p. 30.

Pāṇḍya who is considered to have taken part in the expedition of Vikrama Chōḷa against Teluṅga Bhīma of Kuḷam, i.e., Kolanu, modern Ellore near the Colair lake, and the Southern Kalingam<sup>1</sup> was the son-in-law of the Kūpaka king having married his daughter. It is possible that the rising of the Kūpaka ruler in spite of the strong safe-guards taken by Kulōttuṅga I was connected with and probably a part of the revolt of Vikrama Chōḷa.

### *Kulōttuṅga II and Rājārāja II*

Vikrama Chōḷa was succeeded on the throne by Kulōttuṅga II who is generally taken as his son. The Chellūr plates<sup>2</sup> of the latter mention him likewise as the son of the former. But really Kulōttuṅga II was the grandson of Vikrama Chōḷa, perhaps by a daughter, later on adopted by the king as his son. This will be clear from the Pallavarāyanpēṭṭai inscription<sup>3</sup> of the time of Rājādhirāja. The coronation of Edirilipperumāḷ, son of Neriyuḍaiipperumāḷ and grandson of Vikrama Chōḷa, who was no other than Kulōttuṅga II, as successor to Vikrama Chōḷa furnished a precedent for the coronation of Rājādhirāja II, ascertained by enquiry (*munnaḷilē kāriyam irundapaḍi vi[chāraṇai] seydu*).

Evidently the Kumāra Kulōttuṅga of the Tamil literature has to be identified with Kulōttuṅga II who is known to have been brought up even from his early years by his grandfather Vikrama-Chōḷa and studied Tamil literature under the court-poet Oṭṭakkūttar. The teacher-pupil relationship of the poet and the prince is finely expressed in a verse given in the *Tamil-Nāvalar-charitai*<sup>4</sup> in which the first half is said to have been composed by the poet and the latter half completing the verse by Kulōttuṅga when he was actually ruling the kingdom. This is also

1. *Trav. Arch. Series*, vol. I, pp. 15 ff.

2. *S.I.I.*, vol. I, No. 39; *Ind. Ant.*, vol. XIX, p. 427.

3. This has been discussed in detail in the paper *A Note on the Pallavarāyanpēṭṭai Inscription of Rājādhirāja II* under publication in the *Epigraphia Indica* jointly with Prof. K. A. Nilakanta Sastri.

4. verse 131,

confirmed by the epigraphy. An inscription<sup>1</sup> from Tirumayānam in the Tañjāvūr district dated in the 9th regnal year of Kulōttuṅga III registers the order of the *Peruñkuri-p-perumakkaḷ* of Maṇalkuḍi *alias* Uttamaśōḷa chaturvēdimāṅgalaṁ remitting the *kaḍamai* and *kuḍimai* dues on lands at Komara-Kulōttuṅgaśōḷa chaturvēdimāṅgalaṁ given in the third year of Periyadēvar, who may be taken as Rājādhiraṇḍa II, to Tirumayānam-uḍaiyār at Tirukkaḍavūr after purchase. Another damaged inscription<sup>2</sup> the date of which is lost from Tiruvilimilalai in the same district belonging to Rājakēsarivarman *alias* Tribhuvana chakravartin, identifiable with Rājādhiraṇḍa II, mentions the village Komaran-Kulōttuṅgaśōḷa chaturvēdimāṅgalaṁ. These records will show that Kumāra Kulōttuṅga after whom the village was named should have been anterior to Rājādhiraṇḍa II.

The reign of Kulōttuṅga II, as well as that of his son Rājārāja II, is generally taken as a period of peace, good government and prosperity, as there is no record of any warfare in their *meykkīrttis* of which there are many forms. But two incidents, both of them credited to Rājārāja II, are found in the literature of the period. One of them is cutting open a dam thrown across the Kāvērī, thus obstructing the free flow of water to the Chōḷa country. This is referred to by Oṭṭakūttar, the court-poet, in his *Takka-yāga-paṇi* as well as in the *Rājārāja-śōḷan-ulā*. The former<sup>3</sup> states that Gaṇḍan *alias* Vara Rājārājan destroyed the rock which obstructed the free flow of the sacred water (*gaṅgai*) and made way to *Ponni*, i.e., the river Kāvērī. The *ulā*<sup>4</sup> states that the king made way with his sword to the

1. No. 259 of 1925.

2. No. 420 of 1908.

3. alai-konru varu-gaṅgai vāramal mēnmāl  
aḍaikkīṇra kuṇṇ-ūḍ-aṇukkiṇra bhūtam  
malaikonru *Ponnikku* vaḷikaṇḍa Gaṇḍan  
Vara-Rājārājan-kai vaḷ-enna vandē.

—*Takka-yāga-paṇi*, verse 549.

4. śūli-yiṭṭa Kāvirikku-ch.chōṇaḍu vāḷa  
vaḷiyiṭṭa vāḷ-kaṇa vārīr.

—*Rājārāja-śōḷan-ulā*, kaṇṇi, 83.

river Kāvērī of numerous whirls for the prosperity of Śōṇāḍu. The commentary of Nachchinārkkiniyar on the *Tolkāppiyam* quotes an old verse<sup>1</sup> which also refers to this incident. Perhaps this is the earliest reference to the construction of a dam across the Kāvērī in the upper reaches of the river, thus diverting the waters in other directions for the benefit of that area. This should have been done by the Hoysala ruler. The Chōḷa monarch evidently had to take military action against the Hoysalas to achieve his object. But the *Periyapurāṇam*<sup>2</sup> has a verse wherein the feat of cutting open the rock or hill and making the way is attributed to Kulōttuṅga II, the patron of its author Śekkiḷār. It is known that both Rājarāja II and Kulōttuṅga II had a joint rule of about five or six years from 1145 to 1150 A.D. Evidently the event took place during this period and Rājarāja was the monarch who actually led the expedition.

The other one is the setting up of a Western Chāḷukya king on the throne of Kalyāṇa. Another verse<sup>3</sup> in the final benedictory portion of the *Takka-yāga-parani* states that Rājagambhira, i.e., Rājarāja II, removed the crown of the imposter (*bhrashta*) and crowned the Raṭṭa to rule over the great 'Seven and a half lakh country.' A verse in the *Tamiḷ-Nāvalar-charitai*<sup>4</sup> states that the gates of the cities Kapāṭapura (i.e. Madurai, the capital of the Pāṇḍyas), Laṅkāpura (the capital of Ceylon) and Kalyāṇapura (the capital of the Western Chāḷukya kingdom) were always open to him. This verse evidently refers to his victory in Kalyāṇapura.

1. *Tolkāppiyam*, *Poruḷadhikāram*, *Purattinaiyiyal*, *sūtra* 36.

2. *Periyapurāṇam*, *Eṇipatta-Nāyanār purāṇam*, verse 2.

3. Pirattanaiyē paṭṭaṇ kaṭṭ-aḷittu-p-  
pēr-ēḷaraiyilakkam purakka

Iraṭṭanaiyē paṭṭaṇ kaṭṭi viṭṭa

Rājagambhiraṇai vāḷttinavē.

—*Takka-yāga-parani*, verse 774;

4. karattuṇ śirattuṇ kaḷikkun kaḷiṇ-uḍai-k Kaṇḍan vandaṇ  
irattuṇ kapāḍam ini-t-tirappay paṇḍ-ivan aṇaṅē  
urattuṇ śirattuṇ kapāḍan tirantiṭṭatuṇḍ-Ilaṅka  
purattuṇ Kapāḍapurattuṇ Kalyāṇapurattinumē.

—*Tamiḷ-Nāvalar charitai*, verse 128.

We know that great events were happening in the Western Chālukya kingdom in those days. Bijjala, the Kalachūri subordinate of Tailapa III, the Western Chālukya ruler, slowly usurped the powers of his overlord and finally overthrew him. Tailapa, deprived of his throne and capital, was holding some outlying provinces with the help of some loyal feudatories. About 1163 A.D. Tailapa appears to have died and we find Jagadekamalla III styling himself as the Western Chālukyan monarch. It was possibly to instal Jagadekamalla on the throne that Rājarāja had to intervene in the affairs of the Kalyāṇa kingdom. In the present state of our knowledge it is very difficult to definitely postulate the course of events that took place then.

As already stated, these two incidents are not mentioned in the *meykkīrtti* which are not without interest.

Kulōttuṅga II in his *meykkīrtti* beginning with the words *Pūmannu paḍumam* claims to have levied and received tributes from the Pallavar, Teluṅgar, Māḷuvar (Mālavas), Kaliṅgar, Kōśālar, Kannāḍar, Kaḍārar, Tennar (the Pāṇḍya), Śēralar, Śiṅgaṇar, Koṅgaṇar, Chōḍipar, Trikarttar, Vaṅgar, Aṅgar, Vattavar (Vatsa), Mattirar (Madra), Gaṅgar, Śōṇakar, Kaikayar (Haihaya?) and Śinar.

The *Kulōttuṅga-piḷḷai-t-taṇṇi* mentions<sup>1</sup> that the king who had the *makara* as the emblem on his flag was subordinate to the hero of the poem, i.e., Kulōttuṅga II. From the Leiden plates<sup>2</sup> it is seen that the Sailendra kings of Kaḍāram or Śrī Vijaya had the *makaradhvaja*. It will be seen from this that Kaḍārar of the above list denotes the ruler of Śrī Vijaya and that the Chōḷa supremacy over the Far-East kingdom continued even in the days of this king. Similarly, we find the names of Trikarttar and Mattirar included in the above list as subordinates to the Chōḷas. The Trikartta kingdom lay in the Kaṅgra valley and the Madras also were living in the Panjab. The *Vikramaśōḷan-ulā*<sup>3</sup> mentions

1. verse 56.

2. *Ep. Ind.*, vol. XXII, pp. 242, 257.

3. Kaṇṇi, 88.

Tigatta (Trigarta) as an officer of Vikramachōḷa. It is possible that the officer came from the Trikartta country or that he belonged to the ruling family of that land. Even supposing that it was only a title bestowed by the Chōḷa monarch on the person, this will show that the Chōḷas had some sort of claim over the distant land at that time.

Similarly, Rājarāja II in his *meykkīrtti* beginning with the words *Pūmaruviya poḷil-ēḷum* claims to have received tribute from the Kannaḍar, Kāḷingar, Torraṇavar, Śiṅgaḷar, (Singhalese), Kaikayar (Haihaya?), Koṅgaṇar, Kūpakar, Kāśikar, Kambōdar, Kōśalar, Koṇṭaḷar, Kappalar, Pappalar, Pāñchālar, Poppalar, Pūluvar, Mattirar (Madra), Mārāṭṭar, Vattavar (Vatsa) and Māghadar.

It is generally taken that these are mere conventional praises and no great importance should be attached to them. But it has to be noted that these are found in official *meykkīrttis* of the kings and that such exaggerated praises are not found in the *meykkīrttis* of either their predecessors or successors. Further, similar claims are also attributed to the Western Chāḷukya kings at this period.

Sōmēśvara III, who assumed the titles Bhūlōkamalla and *Sarvajñabhūpa* or Sarvajña-chakravartin, the son and successor of the Western Chāḷukya king Vikramāditya VI, is represented to have 'placed his feet on the heads of Andhra, Draviḷa, Maghada, Nēpāla; and to have been lauded by all learned men'.<sup>1</sup> The Kalachūri Bijjala, who overthrew Tailapa III, the son of Sōmēśvara III, is praised in an epigraph for having destroyed the stability of Nēpāla.<sup>2</sup> About this time we also find a family of rulers from Karṇāṭa established having sway over Tirhut and Mithilā.<sup>3</sup> Nānyadēva, the first king of this line, is said, according

1. *Journal of the Bombay Branch of the Royal Asiatic Society*, vol. XI, p. 268.

2. *Ep. Ind.*, vol. V, pp. 29, 149.

3. *Dynastic History of Northern India*, vol. I, pp. 204-5.

to Nepalese tradition, to have captured the Nēpāla. This event is placed in 1141 A.D.<sup>1</sup> It is also to be noted that we find Sōmēśvara as the name of a Nēpāla prince at this period.<sup>2</sup> This name is unique amongst the names of that country and curiously reminds us of the Western Chāḷukya king of the same name who claims a victory over Nepal.

After the accession of Vikrama Chōḷa to the Chōḷa throne, possibly with the help of the Western Chāḷukya king Vikramāditya VI, no serious trouble seems to have cropped up between these two major powers; on the other hand it appears that some sort of peace prevailed between them. It is also claimed that Rājarāja II helped to instal Western Chāḷukya prince on the throne of Kalyāṇa driving out therefrom an imposter. We may not therefore be wrong if we presume that both the Chōḷas and the Chāḷukyas jointly participated in the expedition to the north. It might be that this expedition also was against the Muslims as Kulōttuṅga II is credited in the *Piḷḷai-t-tamiḷ* to have gained a victory over the Turukkar (Turushkas), Vaḍa-Kōśalar (Northern Kōśalas) and others<sup>3</sup>. Similarly, the Hoysala ruler of the period, Vishṇuvardhana is also said to have encountered the Turushkas,<sup>4</sup> as according to an inscription, "Biṭṭi of Kolevūr, the faithful servant of Balla-veggade, a sword in the hand of Poysala-Dēva, slew many Turukkas and died."

#### *Rājādhirāja II and Kulōttuṅga III*

A Tamil inscription<sup>5</sup> from Hē mavati in the Madakasira taluk of the Anantapur district dated in the cyclic year Vyaya, which was the second regnal year of Tribhuvana chakravartin Kulōttuṅga Chōḷadēva registers the gift of some land to the temple of god Maṅgēśvaradēva at Peruñjēru in Śirainādu, a sub-division of Nigariliśōḷa-maṇḍalam by one Śikkal-uḍaiya-Ṣeṭṭiyār who is

1. *Annals of the Bhandarkar Oriental Res. Institute*, 1954, p. 98.

2. *Dynastic History of Northern India*, vol. I, p. 204.

3. verse 52.

4. *Ep. Car.*, vol. VI, Mg. 3.

5. *S.I.I. (Texts)*, vol. VI, No. 553. This record has been edited by me jointly with Prof. K. A. Nilakanta Sastri for publication in the *Epigraphia Indica*.

described as *vaḍḍa-vyavahāri* and *dēśi-mukhya*; the gift was made with the permission of Śrīman Mahāmaṇḍalēśvara Uṟaiyūrpura-varādhīśvara Śrī Māheśvaran Tribhuvanamalla Mallidēva Chōḷa Mahārāja and with the libation of water by the illustrious hand of the king. The chief Tribhuvanamalla Mallidēva Chōḷa Mahārāja figures also in other records found in that locality, as ruling over the Śiraināḍu with Heñjēru, which is only another form of Peruñjeru, as his capital. He belongs to the Nidugal Chōḍa family and his known dates are from 1162 A.D. to 1179 A.D.<sup>1</sup> As such the cyclic year Vyaya of this record should be the one coinciding with the Śaka 1088, corresponding to 1166-67 A.D. This being the 2nd regnal year of Kulōttuṅga, he should have ascended the throne in 1165-66 A.D. Curiously enough, we do not know of any Chōḷa king who commenced his reign in this year; but it is known that Rājādhirāja II counts his regnal years from some day in the year 1166 A.D.

From the Pallavarāyanpēṭṭai record<sup>2</sup> we know that Rājādhirāja II was chosen by Rājarāja II as his successor on the throne as there was no regular and proper heir in the male line available then. For making this selection some princes were brought from Gaṅgaikōṇḍaśōḷapuram and one of them, Rājādhirāja, probably came out successful in the test. It is likely that Kulōttuṅga was one of the unsuccessful candidates thus brought for the test. The wording of the inscription implies that there was opposition to the selection and that it could be subdued only with great difficulty. Evidently, Kulōttuṅga, though unsuccessful in the selection, did not consider his elimination and the selection of Rājādhirāja as final. Probably, he thought that he was the rightful claimant to the Chōḷa throne and proclaimed himself as such.

This attempt which was made with the assistance of Tribhuvanamalla Mallidēva did not succeed as there was a strong government in the Chōḷa country. Evidently he had not also much support locally. It is possible that this attempt of Kulōt-

1. *Ibid.*, vol. IX, Nos. 268 and 273.

2. *Ep. Ind.*, vol. XXI, pp. 184-93.



tunga and the civil-war in the Pāṇḍya country might have hastened the coronation of Rājādhirāja II which took place in 1166 A.D. three years, i.e., (*nālām tirunākshatram*) after his selection and nomination as heir-apparent in March 1163 A.D.

Śikkal-uḍaiya Śeṭṭiyār, the donor of the above Hēnavati inscription, who had the grant given away by the hands of the king, i.e., Kulōttunga III, is described in the record as *vaḍḍa-vyavahāri dēsimukhya* which term may be translated as 'the Senior merchant and leader of the *dēśi* community'. In some of the later inscriptions, this is expressed as *Srīman Mahāpattu vyāpāri ubhaya nānādēśikku mukkiyamāna* in Tamil<sup>1</sup> and *Śrīman mahā vaḍḍa vyavahāri ubhaya nānā dēsiyaragā mahāprabhu mukhya-rappa* in Kannada.<sup>2</sup> It would thus appear that the donor was a member of the merchant guild known as *Nānādēśi* and as 'five-hundred valiant men' which had its head-quarters at Ayyavole, the modern Aihole in the Bombay State. An undated inscription<sup>3</sup> from Pirānmalai in the Rāmanāthapuram district contains a panegyric of this body from which it will be evident that it had something to do with another organization known as Śittiramēli-Periyanāṭṭavar. Another undated inscription<sup>4</sup> from Tirukkōvalūr in the South Arcot district recording the transaction of the Śittiramēli-Periyanāṭṭavar contains a substantial portion of the above *prasaṣti*. And a record<sup>5</sup> from Tiṭṭagudi in the same district dated in the 4th year of the reign of Rājādhirāja II registers the benefactions to the temple jointly by the Śittiramēli-Periyanāḍu of the seventy-nine *nāḍus* and the *disai disai viṭangum Tiṣai āyirattu Ainnūrruvar*. Probably the two bodies Śittiramēli-Periyanāḍu and the Tiṣai-āyirattu-Ainnūrruvar were two branches of the same parental organisation *Nānādēśis*. The term *ubhaya-nānādēśi* found mentioned in the inscriptions of the Kannada country probably denotes these two branches.

1. *Ep. Car.*, vol. X, Kl. 71.

2. *Ibid.*, No. 72, 73.

3. *S.I.I.* (Texts), vol. VIII, No. 442.

4. *Ibid.*, vol. VI, No. 129.

5. *Ibid.*, vol. VII, No. 291.

This organisation of Śittiramēli-p-periyanāṭṭavar, also referred to sometimes in inscriptions simply as Periyanāṭṭavar, evidently comprised of agriculturists as implied by its name *chitramēli*, 'the beautiful plough', appears to have come into existence about this period. It was spread all over the Chōḷa empire with a net work of local branches during the reign of Kulōttuṅga III. The Viṣṇu temple at Nellore in the Andhra State which was constructed during his reign, was known as Tiruppārkaḍal Paḷḷikonḍa perumāḷ Śittiramēli Viṇṇagaram.<sup>1</sup> We also have a Chitramēli-maṇḍapa at Attirāla in the Cuddapah district.<sup>2</sup> A temple priest in the Coimbatore district was known as Śittiramēli-bhaṭṭar.<sup>3</sup> The Viṣṇu temple of Kariyamāṇikkar at Vijayaṁgalam in the same district was known also Śittiramēli-Viṇṇagar.<sup>4</sup> This organisation had a *meykkīrtti* of its own as also its emblems. Some of the later inscriptions<sup>5</sup> of this organisation open with the expression *Puyal vāyttu* at the commencement and then begin the regular inscription. This phrase contains the opening words of one of the *meykkīrttis* of Kulōttuṅga III with which many of his inscriptions begin. The *meykkīrtti* of the Śittiramēli organisation fairly echoes this *praśasti* of Kulōttuṅga III. It appears reasonable to conclude that the *meykkīrtti* beginning with the words *Puyal vāyttu* was later on appropriated by this organisation and that the opening words of the same were given at the commencement of some of their records as a contracted form of the entire eulogy. This organisation was probably the creation of Kulōttuṅga himself after the failure of his first attempt to seize the Chōḷa throne. It was evidently with the assistance and through the manouvres of this organisation that he was able to capture the Chōḷa throne in his later attempt.

---

1. Nos. 938, 939 etc. of this Collection. See also *S.I.I. (Texts)*, vol. V, Nos. 496, 493, *Nellore District Inscriptions*, Nl. 61, 62.

2. No. 404 of 1914.

3. No. 258 of 1920.

4. Nos. 270 and 271 of this Collection; See also 544 of 1905.

5. *S.I.I. (Text)*, vol. Nos. 40 and 41.

From an inscription<sup>1</sup> from Śembonārkōyil in the Tanjāvūr district dated in the 6th regnal year of Kulōttuṅga III it is learnt that there was an invasion (*durita-kālamāy-paḍaiyēra*) in the 11th regnal year of Rājādhirāja II when the images of the temple of Tiruchchempon-palli-uḍaiyār had to be removed elsewhere for safety. It is likely that this incursion was one sponsored or undertaken by Kulōttuṅga III.

### *The Pāṇḍyan Civil war*

One of the major events in the history of South India in the latter half of the twelfth century A.D. was the succession dispute which broke out in the Pāṇḍya country and raged fiercely for a period of over thirty years among two generations on both the sides. One of the rival parties appealed to the Singhalese ruler and the other to the Chōḷas. Thus war was not confined to the Pāṇḍyas, but it dragged also the other powers of the South into the war, which soon resolved itself into a continuation of the old struggle between the Chōḷas and the Ceylonese.

The early stages of the war are described in the *Mahāvamsa* while the later stages have to be gleaned from three or four Chōḷa inscriptions and a complete picture of the war has to be obtained, thus drawing materials from both the sources. Yet there will naturally be many gaps still to be filled up in future.

The account<sup>2</sup> commences with the appeal sent by Parākrama Pāṇḍya of Madurai to the Singhalese ruler Parākramabāhu I for help against Kulaśēkhara who was investing the city of Madurai. Before the Ceylonese army sent under Laṅkāpura in response to this appeal could reach the mainland, events in the Pāṇḍya country had moved rather fast. Kulaśēkhara had captured Madurai

1. No. 171 of 1925. *An. Rep. on S.I. Epigraphy* for 1925, para. 22 links this invasion with the Pāṇḍyan civil-war. But the Pāṇḍyan civil war does not appear to have spread to the Chōḷa country, even though the Chōḷas took a leading part in it and fought battles which were confined to the Pāṇḍya territory.

2. *Chūḷavamsa*, Chapters 76 and 77.

and put an end to the lives of Parākrama, his wife and children at a place called Tirumalakke. On hearing this, Parākrambāhu sent word to Laṅkāpura that the war should be continued until the kingdom of Maḍurai was taken from Kuḷaśekhara and bestowed on a scion of the house of Parākrama. Laṅkāpura effected a landing on the opposite coast in the face of opposition, and advancing by way of Rāmēśvaram, he strongly fortified himself at Kundukala, on the tongue of land projecting from the mainland into the sea near Rāmēśvaram.

The Chronicle gives in detail the numerous battles of the campaign and the names of the several officers and subordinates who fought on the Pāṇḍyan side. All these places and persons can be identified. But that cannot be attempted here.<sup>1</sup> Without going into these details we may note that Laṅkāpura's task proved more difficult than was anticipated and the war was marked by savage ill-treatment of the prisoners of war, the Tamils who fell into Laṅkāpura's hands being either impaled or transported to Ceylon to labour at the restoration of the Buddhist Vihāras of the island that had suffered during the Tamil domination. Kuḷaśekhara long kept up a brave resistance and Laṅkāpura had to send for reinforcements to Ceylon which came under another general named Jagadvijaya, whose name is found as Jayadratha in the Chōḷa inscriptions. The Ceylonese general learnt that Parākrama Pāṇḍya's son Vira Pāṇḍya, who had escaped the massacre of Kuḷaśekhara, was living in the Malaya (mountain) country, and he invited the prince to him. Finally, Kuḷaśekhara was driven out of the kingdom and Vira Pāṇḍya was crowned as the king.

The Koṅgu king Kulōttuṅga I was the uncle of the Pāṇḍya contestant Kuḷaśekhara and he also took an effective part in the war as testified in the Ceylon chronicle. A record<sup>2</sup> from Nērūr in the Tiruchirapalli district dated in his 17th regnal year registers the gift of a village to his *purōhita* as *yātrādāna* before starting out on an expedition to Maḍurai to get the kingdom for his

1. *An. Rep. on S. I. Epigraphy*, 1899, paras. 23-38.

2. No. 336 of 1928. See also No. 716 of this collection.

nephew (*marumaganār*) Kulaśekhara. This Koṅgu king came to the throne in Śaka 1072 (A.D. 1150-51) as evidenced by an inscription<sup>1</sup> of his from Vijayamaṅgalam in the Coimbatore district, giving the 13+1st year of his reign as corresponding to Śaka 1085. Thus the date of his Nērūr inscription would be 1166-7 A.D. and this would show that the Pāṇḍyan civil war had already commenced and probably reached the second stage. An inscription<sup>2</sup> from Tirupputtūr in the Ramanāthapuram district dated in the 4th+1st year of the reign of the Pāṇḍya king Tribhuvana chakravartin Kulaśekhara-dēva contains astronomical details yielding 23rd July, 1166 A.D. as the date of the record.<sup>3</sup> This would give A.D. 1161-2 as the initial regnal year of the Kulaśekhara. The record contains some interesting information.

It states that the *Mūlaparishad-Mahāsabhā* of the village met in their general assembly in the *āyirattelunūrruvan-tirumanḍapa* of the Tiruttali-āṇḍa-nāyanār temple and resolved to assign the cultivation-rights of some lands belonging to the temple to certain persons in return for 200 [śō]ḷiya-narpaḷaṅkāśu paid into the temple treasury, as money was required by the *sabhā* to go to Madurai to pay their respects to Perumāḷ Kulaśekhara-dēva. (*Perumāḷ Kulaśekhara dēvarai-t-tiruvaḍi-t-toḷa Madurai-y-era pōgaikkū śimatu dravyam veṇḍinaimaiyil*).<sup>4</sup> It is usual for leading and important personages of a realm to present themselves before the monarch and pay their respects and presents (*abhishēka-k-kaṇikkai*) some time soon after his coronation. It is evidently this custom that is referred to in the Tirupputtūr inscription. So Kulaśekhara should have captured Madurai, killing his rival Parākrama Pāṇḍya, some time before July 1166, probably one or

1. No. 598 of 1905.

2. No. 101 of 1908.

3. *Ind. Ant.*, vol. XLIV, p. 255.

4. This record was transcribed by me while working as the Dēvasthānam Epigraphist attached to the Tiruvaṅṅmalai Adhīnam at Kuṇṇakkūḍi in the Ramanāthapuram district and I am quoting from the same.

two years earlier. We may therefore safely take 1165 A.D. as the year in which he captured the capital city.

The *Mahāvamsa* account ends with the coronation of Vira Pāṇḍya at Madurai after expelling Kulaśekhara from the city and the kingdom, return of the Ceylonese generals Lankāpura and Jagadvijaya to the island and the celebration of the victory by the Ceylon king Parākramabāhu, founding a town Pāṇḍuvijaya in commemoration of the same.

But the civil-war did not end there. Kulaśekhara appealed to the Chōla king Rājādhirāja II who treated him suitably during his stay in the Chōla country and ordered his generals that Kulaśekhara was to be restored to his throne. Pallavarāyan *alias* Tiruchchirrambalam-uḍaiyān Perumānambi who was entrusted with this task carried out his master's orders and nailed the heads of Lankāpura-daṇḍanāyaka and others to the gates of Madurai. Kulaśekhara thus became the Pāṇḍyan king once again. These facts are gathered from the inscriptions from Ārppākkam in Chingleput district<sup>1</sup> and Pallavarāyanpēṭṭai in the Tañjāvūr district.<sup>2</sup> The Ārppākkam record dated in the fifth year of Rājādhirāja mentions the havoc caused to the Pāṇḍya country by the Ceylon generals and the defeat inflicted on them by the Chōla army. The other details are found only in the Pallavarāyanpēṭṭai record dated in his 8th regnal year.

That the war was continued further is mentioned in the Tiruvālaṅgāḍu stone inscription dated in the 12th regnal year of Rājādhirāja II. Hearing that Parākramabāhu of Ceylon was preparing for another attack on the mainland, the Chōla ruler decided to counteract all the machinations of the Ceylon ruler. So he set up the Pāṇḍyan prince Śrīvallabha, son of Mānābharaṇa and nephew (*marumaganār*) of Parākramabāhu, who was a claimant to the Ceylon throne but kept out, then living in the Chōla

---

1. *S.I.I.* (Texts), vol. VI, No. 456.

2. *Ep. Ind.*, vol. XXI, pp. 184-93.

country and offered him military assistance in pursuing his claim, The Chōla expedition with Śrīvallabha at its head obtained numerous victories in the island and frustrated the aim of Parākrama,

To counter this move of the Chōlas, Parākramabāhu decided to wean Kuḷaśekhara from the protection of Rājādhirāja and with this end in view he tried to entice Kuḷaśekhara by recognising him as the Pāṇḍya ruler and proposed marriage alliance with him. Finding that Kuḷaśekhara was an accomplice of his enemy, the Chōla ruler expelled him from Madurai and re-installed on the throne Vira Pāṇḍya, the son of Parākrama in whose time the civil war started.

This was the final position in the 12th regnal year of Rājādhirāja II as gleaned from the Tiruvālaṅgāḍu inscription.<sup>1</sup> This was very near the end of his reign. He did not survive as the Chōla ruler for long afterwards. He was expelled from the Tamiḻ country by his rival Kulōttuṅga III whose accession to the Chōla throne is claimed to be between the 6th and 8th July, 1178 A.D.

But the change in the attitude of Rājādhirāja II against Kuḷaśekhara was probably due also to another cause. It is possible that the Pāṇḍya ruler Kuḷaśekhara favoured the rival candidate to the Chōla throne, Kulōttuṅga III. We have already referred to an inscription from Sembonārkōyil mentioning an invasion on the Chōla country in his 11th regnal year, just prior to the removal of Kuḷaśekhara by the Chōla ruler as narrated in the Tiruvālaṅgāḍu inscription. This should have been led by Kulōttuṅga. This is well borne out by the fact that there was once again a change in the rulership of the Pāṇḍya dominion immediately after the accession of Kulōttuṅga III to the Chōla throne. The Chidambaram inscription<sup>2</sup> dated in his 9th regnal year mentions that the king despatched an army, when Vikrama Pāṇḍya sought his aid, to attack Vira Pāṇḍya who was turned out. Madurai and the throne were captured and handed over to Vikrama Pāṇḍya, probably a son of Kuḷaśekhara who had

1. *Ep. Ind.*, vol. XXII, pp. 86-92.

2. *S.I.I.*, vol. III, No. 86,

evidently died in the meanwhile, on which he assumed the title (*Maduraiyum Pāṇḍiyan muḍittalaiyum koṇḍaruḷiya*) "who was pleased to take Madurai and the crowned head of the Pāṇḍya." As this title is found in the inscriptions from his fourth regnal year onwards this campaign should have taken place early in his reign, most probably immediately on his accession to the throne. The Ceylonese also appear to have been involved in this attack, as we find them fighting on the side of Vira Pāṇḍya against Kulōttuṅga.

Vira Pāṇḍya, who was thus defeated, took refuge in Kollam, marshalled his forces and came back to retrieve his former position. He was again defeated. But the Chōla *meykkīrtti* says that he subsequently submitted along with another person, the Pāṇḍya Vira Kēraḷa (*mīnavanām Virakēraḷan*), when Kulōttuṅga III gave him land and crown.

In Ceylon also Parākramabāhu died and after a very short reign of two princes, the cumulative period of which did not exceed one year, Kittī Niśsaṅka Malla became ruler of the island in 1187 A.D. This king claims in his inscriptions to have led three successful expeditions to the Pāṇḍya country and to have renovated a temple at Rāmeśvaram which came thereafter to be called Niśsaṅkamallēśvara.<sup>1</sup>

From two inscriptions<sup>2</sup> found in the Puḍukkōṭṭai State, dated in his 31st and 34th regnal years, it is learnt that the Chōla monarch had to interfere in the Pāṇḍyan affairs once again. It was at the end of this campaign that he had 'the anointment of the heroes' (*vīrābhishēka*) performed at Madurai. This incident is first mentioned in his inscriptions about the 29th regnal year. This should have happened sometime about 1205 A.D. The name of the Pāṇḍya against whom this expedition was undertaken is not found. But it is generally taken as against Jaṭāvarman Kulaśēkhara who ascended the Pāṇḍyan throne in 1190 A.D. We do not have further particulars of

1. *Ceylon Journal of Science*, Section G, vol. II, pp. 105-6.

2. *Inscriptions of the Puḍukkōṭṭai State*, Nos. 163 and 166,



this expedition, and as such it is not possible to say whether this also took place in continuation of the succession dispute or as a separate incident.

One interesting feature of this civil war was that the Pāṇḍyas had throughout the period to depend on some foreign power which in its turn crushed the former very much. But within a very few years, out of the ashes of the war arose afresh the Pāṇḍya power which in its renewed strength soon swallowed up both the kingdoms which had espoused the rival causes of the protagonists in the civil war. It appears that the Pāṇḍyas had, not only during the period of civil war but also afterwards, the support of another power, the *ēlagattār* who are found mentioned in the Chōḷa inscriptions of this period always associated with the *maras* (i.e., the Maravas or the Pāṇḍyas).

The Tiruvāṅgāḍu stone inscription of Rājādhirāja II states that Kuḷaśekhara lost all consideration for the good done to him before by the Chōḷa king and resolved to enter into a matrimonial alliance with the king of Ceylon and to co-operate with him in hostilities against the Chōḷa kingdom. "As part of the move, (they) drove from (their) places to the north bank of (the river) Vēllāru, persons like Rājarāja-k-Karkuḍiyarāyan and Rājagambhira Añjukōṭṭai-Nāḍālvān and others from the *ēlagattār* of the Pāṇḍya country and from the *marach-chāmantas* (i.e., feudatories of the Mara) who were serving our cause having associated with us."<sup>1</sup>

The Chidambaram inscription of the 9th regnal year of Kulōttuṅga III states as follows: "While by our army despatched at the request of Vikrama Pāṇḍya, the son of Vira Pāṇḍya was subdued, while *ēlagam* was subdued, while the *Mara* army was subdued,<sup>2</sup> while the Śiṅgaḷa soldiers had (their) noses cut off

1. *Ep. Ind.*, vol. XXII, p. 90. The text as given there is *namakku-ch-chērvupattu ninruḍan śeygira*. But this can be read clearly from plate published as *namakku-ch-chērvupattu ninru paṇi śeygira*.

2. *S.I.I.*, vol. III, No. 86. This portion can also be translated as 'while the *ēlaga* army (and) the *mara* army were subdued.'

and rushed into the rolling sea (he) attacked Vira Pāṇḍya (forcing him) to turn (his) back, took Madurai and the throne." The Pudukkōṭṭai inscriptions mention that he "reduced the combined strength of the Marapaḍai and the Eḷagappaḍai and took them captive." It will thus be seen that the *eḷagappaḍai* is always associated with the *marappaḍai*.

The *eḷagattār* figuring therein have not been properly identified.<sup>1</sup> The expression *Pāṇḍi-nāṭṭu-eḷagattār* in the inscription would show that the *eḷagattār* were present not only in the Pāṇḍya country, but also in other dominions and those living in the Pāṇḍya dominion were concerned in this affair.

We also find the name Eḷaga-ch-chakravartin in epigraphy. Vira Pāṇḍyapuram *alias* Eḷaga-ch-chakravartti-p-perunderu is mentioned in an inscription<sup>2</sup> from the former Pudukkōṭṭai State as situated in Kīl-kunḍāru division. Kaḷanivāśal in Vira Pāṇḍyapuram *alias* Eḷagapperunderu is mentioned in another record.<sup>3</sup> This Kaḷanivāśal is identifiable with a place of the same name near the modern Kāraikkudi. Another record<sup>4</sup> dated in the 5th regnal year of Māravarman Sundara Pāṇḍya I from Neyvāśal of the Pudukkōṭṭai State registering the sale to the temple of watering rights by the assembly (*ūr*) of the village mentions the exemptions of all dues payable to the (treasury of the) king's palace and to the (treasury of the) palace of Eḷagattār (*irāśa [Rāja-] kōyir-ramattilum Eḷagattār kōyirramattilum*). These will show that the Eḷagattār belonged to a ruling family and that they had their own palace, army, treasury and other royal paraphernalia.

---

1. This would mean the people of Eḷagam. Dr. Hultzsch thought that it could be identical with Eḷ-gam village in the Madurai taluk, (S.I.I., vol. III, p. 212; n. 1) even though it figured as Eḷagam only in the *Tēvāram*. Sri K. R. Srinivasan thinks Eḷakam has to be located in Kaḷanivāśal which is near the modern Kāraikkudi (*Inscriptions of the Pudukkōṭṭai State*, Eng. translation, Part II, p. 141, note 62).

2. *Pudukkōṭṭai State Inscriptions*, No. 450.

3. *S. I. I. (Texts)*, vol. VIII, No. 183.

4. *Pudukkōṭṭai State Inscriptions*, No. 259.

In the account of the war as given in the *Mahāvamsa* we find the names of Nishadarājan and Mālava-chakravartin in the list of officers and feudatories who fought on the Pāṇḍyan side. Members of the families of chiefs with the titles Nishadarājan and Mālava-chakravartti figure largely in inscriptions of the period in the area now known as *Chettinādu*. But the members of the Eḷagam (*ēḷagattār*) or their forces are not mentioned in the *Mahāvamsa*. While the Chōḷa inscriptions make special mention of them, it would look strange that they are ignored and their name not specially mentioned in the Chronicle, unless it be that the account took the *Eḷagattār* to be a division or part of the Pāṇḍya's main force. Probably, the *ēḷagattār* were a branch of the Pāṇḍyas belonging to a region outside the Pāṇḍya country and some members of the branch were at this time living in the country of their forefathers helping their kinsmen in their struggle for the throne.

A clue for this problem is perhaps found in some of the inscriptions from the Koṅgu country. A record from Kīranūr *alias* Koḷumam-koṇḍasōḷanallūr near Palni in the Madurai district, which in those days was included in the Koṅgu-nāḍu, dated in the 13th regnal year of the Koṅgu king Tribhuvana chakravartin Virarājendradeva states that the gold paid for a *sandhyā-dīpa* by Amara-bhujāṅga-p-Pallavaraiyan was deposited with the Śivabrāhmaṇa Kāśyapan Pāṇḍya Dhanāñjayan Śaivēśvaram-uḍaiyān *alias* Śaiva-chakravartin, who held the *kāṇi* rights in the temple. Another record<sup>2</sup> there dated in the 11th regnal year of the same king registers that the gold paid for a similar lamp by Araiyan Śiriyān *alias* Vēnda-chūḷāmaṇi-p-Pallavaraiyan was deposited with Kāśyapan Pāṇḍya Dhanāñjaya Sundara *alias* Kulōttuṅgaśōḷa bhaṭṭa. A third inscription<sup>3</sup> dated in the 12th regnal year of the king states that a similar gift made by

---

1. *S.I.I. (Texts)*, vol. V, No. 262.

2. *Ibid.*, No. 264.

3. *Ibid.*, No. 265.

Kuṟuḷan Kūttan *alias* Uttamakkōṇi was deposited with both the *Śivabrāhmaṇas* mentioned above.

This king Virarājendra ascended the Koṅgu throne in Śaka 1129 (or 1207-08 A.D.) as will be evident from his inscription<sup>1</sup> found at Kumaraliṅgam in the Udumalpet taluk of the Coimbatore district dated in his 25th regnal year, corresponding to Śaka 1153, registering the gift of some land for offerings to the ten *āḷvārs* in the temple of Aḷagar at Tirumāliṟuñjōlai of the Pāṇḍi-maṇḍalam. As such, the above records have to be assigned to the period 1217 to 1220 A.D. It was at this time that the Pāṇḍyas under Māṟavarman Sundara Pāṇḍya I who ascended the throne in 1216 A.D. turned the tables, overran the entire Tamil country and inflicted a crushing defeat on the Chōḷas. The surname of *Pāṇḍya Dhanañjaya* borne by the *Śivabrāhmaṇas* should have been bestowed on them by the Pāṇḍya who was in occupation of the area at that time, probably as a result of this victory gained by the Pāṇḍyas.

But Dhanañjaya is not known as one of the surnames of Māṟavarman Sundara Pāṇḍya. In fact this name is not known to have been borne by any king of the Pāṇḍya line ruling from Madurai. Curiously enough, we have gold coins with the legend Śri Pāṇḍya Dhanañjaya.<sup>2</sup> These coins have on the obverse two fishes to the right with a lamp-stand on either side, royal umbrella above and flower work and bow below. The legend on the reverse side is in Kannaḍa characters.

The Kannaḍa characters of the coin would indicate that the coin belongs to the Kannaḍa area. The name Dhanañjaya is known to have been borne by some of the Āḷupa kings of the West Coast, who had also the cognomen Pāṇḍya. One such king was ruling the

---

1. No. 135 of 1909.

2. *Transactions of the Archaeological Society of South India*, vol. I (1955), pp. 28, 31.

Ālupa kingdom at this period. A stone inscription<sup>1</sup> in Kannada verse from Varāṅga in the Karkal taluk of the South Kanara district, giving publicity to a grant made by Jākalamādēvī, queen of the ruler Kulaśekhara, ascribes the titles *Pāṇḍita Pāṇḍya* and *Pāṇḍya Dhanañjaya* to the ruler. This Kulaśekhara is known to have ruled in Śaka 1127 (or 1205-6 A.D.)

We have already mentioned<sup>2</sup> while discussing the conquest of Ceylon claimed for Rājādhiraīa I in his *meykkīrttis* that, according to the *Mahāvamsa*, Vikrama Pāṇḍya who was the only son of Mahālānakitti, having left his country through fear of Rājādhiraīa, was living at the time of his father's death in the Dulu i.e., the Tuḷu country of the West Coast. Ballamahādēvī, who was ruling the Ālupa kingdom in the latter half of the 13th century A.D. is mentioned in an inscription<sup>3</sup> from Ammanji in the Udupi taluk of the South Kanara district, as "born in the family of Mānābharaṇēśvaradēva and Sōmakula." An inscription<sup>4</sup> from Śrīraṅgam of the Pāṇḍya king Jaṭāvarman Sundara Pāṇḍya I having 1251 A.D. as the date of his accession, states that he defeated the Kēraḷa and Hoysaḷa kings and that he made his younger brother Vira Pāṇḍya the ruler of Koṅkaṇarājya. Most probably the Koṅkaṇarājya referred to in this inscription was the Tuḷu country. We find a Vira Pāṇḍya Ālupēndra ruling over the Ālupa kingdom in Śaka 1173 (or 1261-2 A.D.) as evidenced by his inscription<sup>5</sup> from Mangalore. But curiously enough, we also find a Vira Pāṇḍya 'conqueror of the two Koṅḡus' with his initial date as 1254 A.D. ruling over the Koṅḡu country. It is not possible to state whether the Koṅḡu country had any affiliation to the Koṅkaṇa country. But the sway of the Ālupa king with the title *Pāṇḍya Dhanañjaya* is significant.

---

1. No 526 of 1929.

2. *Ante*. p. 35.

3. No. 336 of 1932.

4. No. 81 of 1939.

5. No. 370 of 1929.

About this time we also find Jaṭavarman Vira Pāṇḍya of the main line with 1253 or 1254 A.D. as the date of his accession.<sup>1</sup> In the present state of our knowledge it is not possible to say whether these Vira Pāṇḍyas, of the main line, of Koṅgu and of the Tuḷu country, would represent the same or different persons. It is also to be noted that an inscription<sup>2</sup> of Jaṭavarman Vira Pāṇḍya dated in his 11th regnal year states that he employed in his army horsemen from the Kaṇṇaḍa country.

It will be seen from the above that the Pāṇḍyas of Madurai had very close connections with the Pāṇḍyas in the Tuḷu country. The matriarchal system of succession adopted by the Tuḷus was evidently helpful in some of the Madurai princes ascending the Ālupa throne.

Considering the above one will be tempted to suggest that the Eḷagattār of the Chōḷa inscriptions might be none other than the Tuḷu Pāṇḍyas. The Tuḷu land or Koṅkāṇam formed part of the Tamil country originally. We have many references to the land and its people in the Tamil literature of the Śaṅgam period.<sup>3</sup> A verse<sup>4</sup> in the *Narriṇai* states that *ēḷir-kunṇam*, i.e., the hill of Eḷil was situated in the Koṅkāṇam, rich in gold, the territory of the chief Nannan.

pon-paḍu Koṅkāṇa Nanna-ṇan-nāt  
t-*Eḷir Kunṇam* perinūm poruḷvayin  
yarō pirigir-pavarē.

Eḷagam of the mediaeval period is perhaps the same as the Eḷil of the Śaṅgam age and both the terms mean 'the seven houses'. Koṅkāṇam or the Koṅkaṇa is known to be comprised of seven divisions collectively known as *Sapta-Koṅkaṇa*. It is

1. *Ind. Ant.*, vol. XLII; Vol. XLIV, p. 196.

2. No. 134 of 1901.

3. *Aha-nānūru*, verse 15; *Kuruntogai*, verse 73.

4. *Narriṇai*, verse 391.

therefore reasonable to conclude that the Elagattār were the Pāṇdyas of the Tulu country.

### *The effects of the succession dispute*

The succession disputes in both the Pāṇḍya and the Chōḷa dominions convulsed the entire South India drawing the neighbouring powers also into the whirlpool and had far-reaching consequences. Even the political alignment of the several states in the area underwent a change. This altered condition appeared to have continued till the original disputants were alive.

A perusal of the *meykkīrtti*s of Kulōttuṅga III will show that he was constantly waging war with some neighbouring power or the other throughout his reign. It is possible that the presence of the deposed monarch Rājādhirāja II in Vēṅgī, the northern province of the erstwhile Chōḷa empire, where the chieftains owed nominal allegiance to the ruler in distress, was a source of constant trouble to him. The chiefs of the Vēṅgī area rather preferred the nominal allegiance to and the suzerainty of their former overlord, entailing no obligations on their part or control by the suzerain to that of the powerful newcomer and would have tried their best to resist any advance made by him in this direction.

### *Expedition of Kulōttuṅga III against Warangal.*

The unique form of the *meykkīrtti* beginning with the words *Puyal vāyttu vaḷam peruga* found in two records of his from the former Pudukkōṭṭai State<sup>1</sup> already referred to, mentions that he "in a battle, the ferocity of which was beyond endurance, conquered the Vadugar (i.e., the Āndhras), and made the Vēṅgi-maṇḍalam his own and entered the golden city of Uraṅgai after making a shower of gold." Uraṅgai or Oruṅgallu is Warangal, capital of the Kākatiyas and the statement in the *meykkīrtti* will mean that Kulōttuṅga waged war with the Kākatiya ruler and, obtaining a victory, entered the capital Warangal after making a *shower of gold*. This claim of the Chōḷa monarch has been taken as a case of exaggeration.

---

1. *Inscriptions of the Pudukkōṭṭai State*, Nos. 163 and 166,

But curiously enough, this 'shower of gold' in the Kākatiya capital is found mentioned in another context. An inscription<sup>1</sup> dated in Vikrama Samvat 1760 (A.D. 1703) in Sanskrit with a Hindi version found engraved on two slabs in the treasury of the temple of the goddess Dantēśvarī at Dantāvārā in the former Bastar State (in the Madhya Pradesh) refers to this incident. It states that Dikpālādēva whose genealogy and military exploits are described therein, came to Dantāvārā with all the residents of his capital and performed the ceremony *kuṭumba yātrā* to propitiate his tutelar deity, evidently Dantēśvarī. The king who belonged to the ruling family of the chiefs of Bastar traced his descent from a certain Annamarāja, brother of the Kākatiya king Pratāparudra of Warangal. The latter is stated to have lost his kingdom to the Yavanas, i.e., the Muslims and eventually died in consequence of the troubles caused by the *shower of gold*. Pratāparudra's brother Annamarāja then abandoned the dominion and went to Bastar where he carved out a kingdom of his own<sup>2</sup>.

The Kākatiya king Pratāparudra referred to in this record has been variously identified by scholars. Some have taken him to be the last king of the Kākatiyas who lost his kingdom to the Muslims. This Pratāparudra was captured by Ulugh Khān, eldest son and heir of Gaiyāṣ-ud-Dīn, king of Delhi, in the course of his second 'Tiling' expedition and sent with all his relations and dependants to Delhi, protected by a strong escort. But he did not reach the capital. He ended his life by his own desire on the banks of the Narmadā when the party was passing through the Vindhya regions. This event happened in 1323 A.D.<sup>3</sup> But no mention of 'the shower of gold' is made anywhere in connection with this incident.

This would give an interval of nearly 400 years between the first king who settled in Bastar and Dikpālādēva, the donor of the present record who was the tenth in descent and the period was

- 
1. *Ep. Ind.*, vol. XII, No. 30, pp. 242-50.
  2. *An. Rep. on S.I., Epigraphy*, 1909, para. 66.
  3. *The Early Muslim Expansion in South India*, pp. 118-120; See also *The Kākatiyas of Warangal* by Dr. M. Rama Rao, p. 98.



considered too long. So, Pratāparudra was thought to be 'another of the same name who apparently was ruling in the 15th century and was ousted by Ahmad Shāh Bahmani in 1422 A.D.' 'and sometimes sought to be identified with a member of the Gajapati family of Orissa.'<sup>3</sup>

A perusal of the inscriptions, both the Sanskrit one and its Hindi version, would show that they have mixed up some two or three events and recorded one composite version probably as handed down in the family. We can at best take the version as the tradition preserved. The overthrowal of the Kākatiya kingdom by the Muslims was well-known and Pratāparudra was the ruler of the kingdom at that time. There was a 'shower of gold' in the reign of a Pratāparudra and the kingdom also suffered then. These two incidents appear to have been mixed up and one Pratāparudra confused with another person of the same name. The 'shower of gold' might have rained only once and as such the incident mentioned in both the places might refer to one and the same.

Of the three Kākatiya rulers bearing the name of Rudra, the middle one was a female named Rudrāmbā. The third ruler, who was better known as Pratāparudra, was the grandson of Rudrāmbā and succeeded her on the throne. The first ruler of the name Rudra ruled the kingdom from 1151 A.D. to 1196 A.D.

A great calamity shook the Kākatiya realm at the end of his reign. He died in battle losing his kingdom. Jaitrapāla, the Sēuṇa ruler of Dēvagiri, is said have killed this king in battle. Hēmādri in the *Rājaprasasti*<sup>2</sup> contained in his *Vrtakhaṇḍa* writes of this king: "He assumed the sacrificial vow on the holy ground of the battle-field and throwing a great many kings into the fire of his prowess by means of the ladles of his weapons, performed a human sacrifice by immolating a

---

1. *Ep. Ind.*, vol. XII, p. 243.

2. *Ibid.*, p. 244, fn.

3. *Bombay Gazetteer*, vol. I, part II, pp. 238-9, verse 41 in p. 272

victim in the shape of the fierce Rudra, the lord of the Tailiṅgas, and vanquished the three worlds." Jaitrapāla, also known as Jaitugi, was ruling the Sēuṇa kingdom from 1191 A.D. to 1210 A.D. This achievement of Jaitugi is referred to in the Paiṭhan grant (of Rāmachandra dated 1272 A.D.)<sup>1</sup> in the statement that he killed the Trikaliṅga in battle and siezed the whole of his kingdom. It is also stated therein that he released Gaṇapati from prison and placed him on the throne of his country.

An inscription<sup>2</sup> from Bahāl of the time of Śiṅghaṇa mentions that Jaitrapāla 'liberated and made Gaṇapati, the lord of the Āndhra country.' The Pālampēt inscription<sup>3</sup> dated in 1213 A.D. of the Rēchērla chief Rudra, a subordinate of Gaṇapatidēva, mentions that "soon after the death of Rudradēva, a number of enemies invaded the Kākatiya kingdom with the object of snatching it away. Rudra opposed these enemies. He cut off the head of one of them and stuck it on a spear. Seeing this, these intruders like king Nāgati fled for their lives. Thus when the goddess of the Kākatiya kingdom stepped on thorns, Rudra lifted her up, removed the thorns and re-established her in security."

This Rudradēva of the Kākatiyas, it appears, had no son to succeed him on throne. The Upaparalle inscription<sup>4</sup> and the traditional accounts mention Gaṇapatidēva as the son of this Rudra, while, however, 'the bulk of literary and epigraphical evidence describes him as the son of Rudradēva's younger brother Mahādēva.'<sup>5</sup> There is also a story<sup>6</sup> that during the closing years of the reign of Rudra, sharp differences arose between Rudra and his brother Mahādēva who eventually fell out on this account. It appears that he had also other brothers.

---

1. *Ind. Ant.*, vol. XIV, p. 316; See also vol. XXI, p. 197.

2. Sewell: *Historical Inscriptions of Southern India*, p. 128.

3. *Hyderabad Archaeological Series*, No. 3, verses 21-24.

4. *Ibid.*

5. Dr. M. Rama Rao: *The Kākatiyas of Warangal*, p. 53.

6. *Pratāpacharitramu*, pp. 29-30.

The exact course of events is not known. But it is clear that there was an invasion by the Sēuṇas on the Kākatiya kingdom in this period. Evidently, Kulōttuṅga had joined with Jaitrapāla in this expedition. Possibly he had sufficient reasons for entertaining feelings of enmity towards Rudra.

The Kākatiyas owed their existence to the grant of the Anumakoṇḍa territory as a fief to Bēṭa by the Western Chālukya ruler Vikramāditya VI. They were loyal to their overlords and appeared to have opposed the Kalachūri usurpation. Rudra is credited in his Hanumakoṇḍa inscription<sup>1</sup> with a victory over a certain Mailagidēva, who has been sometimes identified with the Sēuṇa chief Mallugi. This does not seem to be correct. Mailugidēva whom Rudra is said to have defeated was more probably a Kalachūri prince.

The Tribhuvanam inscription<sup>2</sup> of Kulōttuṅga III as well as his *meṃkkirtti* mention that his sway extended from Śakkarakkōṭṭam in the north to Anurādhapura in Ceylon in the south. Bastar region was in those days included in the Śakkarakkōṭṭam area.

Then, Annamarāja, another brother of Rudradēva, who established himself in the Bastar region could have done so only with the help of Kulōttuṅga III.

### *Kulōttuṅga III and Ballāḷa II*

We have already noticed that when Kulōttuṅga first set up himself as a claimant to the succession on the Chōḷa throne instead of Rājādhirāja selected by Rājādhirāja II, he had the support of some of the powers in the Kannaḍa country. From the *Kulōttuṅga-kōvai*, it is learnt that his father was called Saṅkamarāja and his brother Nallaman. These names also suggest some Kannaḍa origin to him. It is possible that he was connected

1. *Ind. Ant.*, vol. XI. pp. 9. ff.

2. No. 190 of 1907. See also No. 1007 of this collection.

with the Chōla family through his mother, a Chōla princess married into some ruling family of the Kannaḍa country. The support of some of these foreign powers to Kulōttuṅga in his claim for the Chōla throne was perhaps intended as a reprisal to the intervention of Rājarāja II in the affairs of Kuntala by installing a Western Chālukya king on the throne of Kalyāṇa, causing the removal of an imposter therefrom. This should have taken place about 1163 A.D.

Rājarāja II would not have allowed the setting up of a pretender to the Chōla throne by some of the Kannaḍa powers. He would have certainly taken action against them. Kalachūri Bijjala, who usurped the Western Chālukya throne shortly before, is said to have abdicated the same in 1167 A.D. in favour of his son Sōmēśvara, also known as Rāya-Murāri and Sōvidēva, and fell a victim to the assassin's knife shortly thereafter. The abdication of Bijjala was brought about possibly by the Chōlas.

This can be surmised from the following. Vijaya Pāṇḍya also known as Kāmadēva of the Uchchaṅgi Pāṇḍyas, who was ruling over the Nōlambavāḍi province at this period, was one of the principal supporters of the Kalachūris. Rājarāja II appears to have fought with this Vijaya Pāṇḍya. This becomes clear from the inscriptions of Ballāḷa II.

This Hoysala ruler is credited with the capture of the fort of Uchchaṅgi and the person of its ruler Vijaya Pāṇḍya in 1177-78 A.D.<sup>1</sup> The fort was considered impregnable and its peaks were so high that even Garuḍa could not reach them. It was surrounded with a "moat like *pātāla*, as broad as the eight cardinal points, high as the sky, extending in both directions, so that it was famed in the three worlds."<sup>2</sup> The invincibility of the fort is suggested by the statement that "the Chōla had laid siege to it for twelve years without success and had to abandon it as hopeless." Ballāḷa is said to have captured the fort and its ruler with the least effort.

---

1. *Ep. Car.* vol. V. Bl. 137. 175.

2. *Ibid.*, Bl. 72.

Subsequently he released the Pāṇḍya and restored the throne to him. In commemoration of this victory which was obtained on a Saturday he assumed the titles *Giridurga-malla* and *Sanivāra siddhi*. But these titles belonged previously to the Kalachūris.

The siege of the Uchchaṅgi fort by the Chōla for twelve years without any avail should have taken place prior to its capture by Ballāla in 1171-78 A.D. Vijaya Pāṇḍya, the ruler of Uchchaṅgi who was then ruling over Nolambavāḍi, as a feudatory of the Kalachūris, assumed the title *Rājiga-Chōla-manōbhāṅga* even as early as 1171 A.D.<sup>1</sup> Rājiga Chōla of this title could refer only to the Chōla emperor Rājārāja II. This title is found assumed by a predecessor of his, Tribhuvanamalla Pāṇḍya,<sup>2</sup> who was a subordinate of the Western Chālukya king Vikramāditya VI, to commemorate the frustration of the designs of Rājiga, i.e., Rājendra as Kulōttuṅga I was then known. But this does not seem to be a family title and it does not also appear to have been borne by the intervening members. The old title was probably renewed now in view of the appropriateness of the situation. As such, the twelve years' siege of Uchchaṅgi without capture should have been conducted by Rājārāja II and possibly also by his successor Rājādhirāja II.

A lithic record<sup>3</sup> found in the *raṅga-maṇḍapa* of the Išvara temple at Āsandi in the Kadur district of the Mysore State registering some benefactions by Narasimha, the Gaṅga chief and general under the Hoysaḷa king Ballāla II contains the following verse eulogising the chief victories of the chief :

kari-patiy-appa Maḷava-mahīpati  
 baṇṭana Lāla-bhūmipam  
 turaga-chayaṅgaḷind eseṇa Gūrjjara-  
 bhūpati Chōla-bhūbhujar

1. *Ibid.*, vol. XI, Dg. 32.

2. *Ibid.*, Hk. 68.

3. *Ibid.*, VI, Kd 156.

nnered idirāntu tāge raṇa-raṅgadoḷ  
 ōrvvane kādi geldan-ī  
 narapati-Balla-bhūpana besam baḍed ī  
 Narasimha-bhūbhujam

This shows that there was a confederacy of the Mālava, Lāṭa, Gūrjjara and Chōḷa kings against the Hoysaḷa and that Ballāḷa gained a victory over them. 'The Mālava king who was the master of elephants, the Lāṭa (Lāṭa) king with his warriors, the Gūrjjara king shining with masses of horsemen and the Chōḷa king united came against him; but he, this Narasimha Bhūbhujā, by himself opposed, attacked and subdued on the field of battle, having received the command from Balla.'

The record is undated. But the Gaṅga general Narasimha is found mentioned in the Hoysaḷa records for a period of about forty years only from about 1190 A.D. As such, the Āsandi inscription should be assigned to the period between. A.D. 1190 and 1220 A.D., the last date of Ballāḷa II.

This encounter of Ballāḷa with the Mālavas is referred to in another inscription<sup>1</sup> also. The Huliya chief Ballēya, son of *Mahā-sāmanta* Gōvidēva, claims 'to have trampled on Chōḷa and Kalinga, thrown down the Mālāva army, destroyed the army of Nēpāḷa and plundered and driven away Pāṇḍya.'

To have a clear picture of the confederacy referred to in this record it is necessary to know the relation of Ballāḷa and Kulottuṅga.

An incomplete record<sup>2</sup> of which only the beginning is found from Āvaṇi in the Mysore State dated in Śaka 1112, Saumya mentions that Vallāḷadēva was ruling the earth in the twelfth regnal year of Kulōttuṅga. From this it can be surmised that Ballāḷa II was a Subordinate to the Chōḷa king Kulōttuṅga III in 1189-90 A.D.

1. *Ep. Car.*, vol. XII, CK. 17.

2. *Ibid.*, vol. X, Mb. 44(b).

But he does not seem to have remained in that position for long. Very soon thereafter we find him assuming paramount titles.<sup>1</sup> He even started an era of his own<sup>2</sup> to mark his reign as paramount sovereign, commencing with Śaka 1114 or A.D. 1191-92. He appears to have gained this position by inflicting a crushing defeat at Soratūr in 1190 A.D. on Bhillama, the Yādava king of Dēvagiri. The power of the Western Chālukyas of Kalyāṇa had very much weakened by that time. Both the Yādavas from the north and the Hoysaḷas from the south coveted the remains of the old Chālukyan kingdom, especially the Kuntala, the Chālukyan home-land. But Jaitrapāla, the son and successor of Bhillama, was able to capture and hold at least the northern part of the Kuntala. We have already seen that Jaitrapāla was in friendly terms with Kulōttuṅga III and that both of them were engaged in their joint attack on the Kākatiya kingdom in 1195 A.D. The Hoysaḷa inscriptions mention that the flames of the valour of Ballāḷa charred black the Chōḷika territory.<sup>3</sup>

According to the Huliyaṇa chief's record mentioned above, the Kālīṅgas also appear to have been engaged in this conflict. Ever since the Chōḷas began their expansion under Rājārāja I, the Kālīṅga country seems to have been included in the Chōḷa empire, except probably for periods of short and temporary intervals. Kulōttuṅga I wanted to assert his power there and tried to control the administration of the country. A new epoch appears to have started in the history of Kālīṅga from about this time. Anantavarman, son of Rājārāja Dēvēndravarmān who helped Vijayāditya against Kulōttuṅga, bore the surname Chōḍagaṅga, which probably became more prominent than his name. About the same time, we find Rājārāja, one of the sons of Kulōttuṅga I, also bearing this surname Chōḍagaṅga. Very likely, he was the

---

1. *Ep. Car.*, vol. VII, Ci. 64; vol. VIII, Sb. 140; *Mysore Arch. Report*, 1913, p. 37.

2. *Mysore Inscriptions*, p. 137.

3. *Ep. Car.*, vol. V, Cn. 220.

viceroys over Kalinga during the minority of Anantavarman. From this time onwards there was close relationship between the two countries.

The *Mahāvamsa* mentions a Chōḷagaṅga as one of the leaders who fought on the side of the Pāṇḍya Kulaśekhara against the Ceylonese general Lankāpura-Daṇḍanātha in the Pāṇḍyan civil war.<sup>1</sup> Subsequent to this event, we find one Chōḷagaṅga and another Anikaṅka (Aniyaṅga) becoming rulers of Ceylon for short periods with the help of the Tamil soldiers. The invasion of Anikaṅka which took place in the eighth year of Queen Kalyāṇavati is described in a stone inscription<sup>2</sup> from Ceylon in the following terms: "the great host of Tamils descended on this Lankā, destroyed the minister named Āti and, unhampered in all mountain-fastnesses and forest-fastnesses, swept over the whole of Lankā in the manner of the world-consuming flames at the end of an aeon, having destroyed the entire social structure and the religious organisation." This event is placed by the Ceylon historians in 1210 A. D. and we know that Kulōttunga III was the Chōḷa ruler at that time. As such, this could have happened only with his active help.

An inscription<sup>3</sup> from Perumānāḍu of the former Pudukkōṭṭai State dated in the 10th regnal year of the Pāṇḍyan king Tribhuvana chakravartin Sundara Pāṇḍyadēva registers the money gift and the arrangements for the supply of ghee for lamps by a certain Śrīman Mahāpradhāni Maṇḍalika-murāri Aniyega [Ge]ddaya Daṇḍanāyaka. It mentions that the gift was made with 'the libation of water poured out from the flower of illustrious hand of *tambirāṭṭiyār*', i.e., Her Majesty, evidently the queen of this person. It will be seen therefrom that this person belongs to some ruling family. The way in which the name of this chief is introduced in the inscription supports this. Two other records of this chief are also found in the collections from that

1. K. V. Subrahmanya Aiyar, *Historical Sketches of Ancient Dekhan*, p. 156.

2. *Ep. Zey.*, vol. V, p. 120.

3. *Inscriptions of the Pudukkōṭṭai State*, No. 518,



State. In one inscription<sup>1</sup> the name of this person has been read as 'Śrīmanu Mahāchākani Meychatrukandan Sāmantan' and in another<sup>2</sup> as 'Śrīman Mahāchragyāni Maṇḍalika-murāri.....ya Daṇṇāyaka.' Evidently the name has to be restored as 'Śrīman Mahāpradhāni Maṇḍalikamurāri Aṇiyaṅga Rāhuttarāya Daṇḍanāyaka.' A fragmentary Sanskrit inscription<sup>3</sup> from Trincomalee in Ceylon gives the date on which a certain Chōḍagaṅga landed in that island. The date has been calculated as Friday, the 14th of April, 1223 A.D. Thus it will be seen that there was close connection between the Chōḷas and the Kalingas in those days.

There is one interesting factor to be seen in the composition of the confederation formed against Ballāḷa as mentioned in the Āsandi inscription mentioned above. The kings of the Mālava, the Lāṭa and the Gūrjjara countries were with the Chōḷa monarch. But it is to be noted that their dominions were not contiguous to the Chōḷa empire in those days and that the Yādavas or the Sēuṇas of Dēvagiri and the Kākatiyas of Warangal were ruling over the intervening area. The rulers of the Mālava, the Lāṭa and the Gūrjjara countries would not have been able either to attack the Hoysaḷa dominion from the north or effect a conjunction with the Chōḷas without coming into contact with and crossing the territories of these two powers. But curiously enough no mention is made in the record of these two powers.

The victory of Ballāḷa II over Kalinga is also claimed by his son Vīra Narasimha.<sup>4</sup> It is not known whether these two refer to different engagements or to the same. Most probably both of them refer to the same incident. In that case the victory should have been gained by them, Ballāḷa II and his son, during the last years of the reign of the former.

- 
1. Ibid., No. 193.
  2. Ibid., No. 199.
  3. *Ep. Zey.*, vol. V, No. 14.
  4. *Ep. Car.*, vol. V, Cn. 203.

We have already referred to the fact that the reign of Kulōttuṅga which had witnessed many brilliant victories ended in a serious disaster. Māṇavarman Sundara Pāṇḍya who ascended the throne at Madurai in 1216 A.D. not only freed the Pāṇḍya country from the yoke of the Chōḷa domination, but also invaded the Chōḷa country and inflicted a crushing defeat on his quondom suzerain. This event is described graphically in his *meykkīrtti*.<sup>1</sup>

The Pāṇḍya captured the Chōḷa country, set fire to the cities of Tañjāvūr and Uraiyūr, destroyed many buildings, drove the Chōḷa who ran away and hid himself beyond the horizon (*Vāḷagiri* or the mythological *Chakravāḷagiri*), seized his crown and gave it to the Bāṇa, performed the *virābhishēka* at the palace (*āyirattalī*) of the Chōḷa in his capital, went to Chidambaram and worshipped the dancing-god there, reached Pon-Amarāvati, invited the Chōḷa who came back with his relatives and prostrated before the Pāṇḍya presenting his son saying 'Your name', and restored him to his title *Chōḷapati* and his city with a *tirumugam*.

Many of the incidents mentioned in the *meykkīrtti* are corroborated by other epigraphs. The demolition by Sundara Pāṇḍya of the Chōḷa palace, excepting the sixteen pillared *maṇḍapa*, where the *Paṭṭinappālai* by the poet Kaḍiyālūr Uruttiran-Kaṇṇan was published in olden days, is referred to in a record<sup>2</sup> from Tiruvellaṅgai in the Tiruchirappalli district. The gift of the Chōḷa country to the Bāṇapati, also referred to as Vira-Māḡadan, by the Pāṇḍya is referred to in two records<sup>3</sup> from Tiruvānaikkāval near Śrīraṅgam, while, another<sup>4</sup> from Śrīraṅgam clearly states that the Chōḷa country (*Kāviri-nāḍu*) was divided by the Pāṇḍya between the Vaḷava (Chōḷa) and the Māḡadar-kōn (the Bāṇa chief of the Magadai nāḍu). That this division actually happened could be surmised from the fact that the inscriptions of Kulōttuṅga III during the last two (39th and 40th) years of his reign are found only in the Kāvērī basin and that no inscriptions of his of these two years are found in the North and South Arcot and the Chingleput districts.

---

1. *Ep. Ind.*, vol. XXII, pp. 42 f.

2. No. 197 of 1939.

3. Nos. 481 and 482 of 1908

4. No. 196 of 1939

Sundara Pāṇḍya assumed the title *Śōṇāḍu valangi-y-aruliva*, 'who was pleased to give (back) the Chōḷa country' from the third year of his reign.<sup>1</sup> Another inscription of his fifteenth regnal year<sup>2</sup> states specifically that he gave a crown and Muḍikoṇḍaśōḷapuram (Paḷaiyārai or Rājarājapuram as it was known otherwise, the then capital) to Kulōttuṅga Chōḷa. These victories of Sundara Pāṇḍya should have been obtained by him immediately on his ascending the Madurai throne in 1216 A.D.

Who was the son presented to the Pāṇḍya by Kulōttuṅga saying, 'Your name' is not known. The incident as mentioned in the *meykkīrtti* would indicate that the son was known as Sundara. But we do not hear of any such Chōḷa prince then. Kulōttuṅga III was succeeded on the Chōḷa throne by Rājarāja III whose exact relationship to his predecessor is not clearly known. It is generally taken that Rājarāja III was the son of his predecessor.

The date<sup>3</sup> of accession of Rājarāja III is said to fall on some day between the 27th June and the 10th July, A.D. 1216, the very year in which Sundara Pāṇḍya also became king. The Pāṇḍyan subversion of the Chōḷa dominion should have taken place only after this. If Rājarāja had been the son of Kulōttuṅga, then he should have been the Chōḷa prince who was presented to the Pāṇḍya by his father and who was the beneficiary of the gift of the Chōḷa kingdom to Kulōttuṅga by Sundara Pāṇḍya.

But from the Hoysala inscriptions we learn that Rājarāja III was installed on the Chōḷa throne by the Hoysala kings, Ballāḷa II and his son Narasimha. Ballāḷa is described in an inscription<sup>4</sup> dated in 1218 A.D. 'as the establisher of the Chōḷa kingdom' and 'the lion to the Pāṇḍya-elephant' (*Chōḷa-rājya-pratishṭhāchāryam*, *Pāṇḍya-gaja-kēsari*), wherein his son Narasimha is mentioned as the sole protector of the Chōḷa line and the uprooter of the Magadha king, i.e., the Bāṇa ruler of the Magadaimaṇḍalam

---

1. No. 322 of 1928.

2. No. 9 of 1926.

3. *Ep. Ind.*, vol. VIII, p. 260. See also No. 160 of 1943 which couples Śaka 1162 (A.D. 1240) with his 24th regnal year.

4. *Ep. Car.*, vol. IV, Nl. 29.

(*Chōlakulaikaraksha*, *Magadhōrvipāla-nirmūlaka*). This would show that Ballāḷa II must have assumed these titles before the beginning of that year. Another inscription<sup>1</sup> mentions that when Ballāḷa was still living, his son Vira Narasimha marched against Śrīraṅgam in the South (*Hoysaṇa Srī Viraballāḷa-dēvana magam Vira-narasimha-dēvanu teṅkalu-Raṅgana mēle naḍavandu*). The *Jagannātha-vijaya*, a *chamṇū* work in Kannāḍa clearly states that the Chōḷa king protected and installed on the throne by Ballāḷa was Rājarāja (*rājarāja pratishtānirattam*).<sup>2</sup> It will be seen from the above that Rājarāja was installed on the Chōḷa throne by the Hoysaḷa Ballāḷa II defeating both the Pāṇḍya and the Bāṇa kings. The name of Kulōttuṅga is not mentioned anywhere in this connection.

A careful study of these would suggest that the incidents mentioned in the Hoysaḷa records do not relate to the restoration of the Chōḷa kingdom to Kulōttuṅga and his son mentioned in the Pāṇḍyan *meṅkkīrti*, but to an incident independant of it. This view is further confirmed from another source. It is learnt that there were great disorders in the Tañjāvūr district in the fifth year of the reign of Rājarāja III. An inscription<sup>3</sup> from Tiruvilakkuḍi dated in the 16+1st year states that in the troubles which took place in the fifth regnal year of Rājarāja, the images of the Tiruvēlvikkudī temple were carried away and deposited in the temple of Tiruchchattimurram by the followers of Vāṇakōvaraiyar and that they were later on recovered by a search instituted and reconsecrated redeeming them by payment of money. An undated record<sup>4</sup> from Uḍaiyālūr mentions the loss of title-deeds in a commotion (*kshōbham*) in the fifth year of the king in consequence of which the rights had to be regulated in accordance with the position that obtained upto to the fourth year. Another<sup>5</sup> from Talaichchaṅgāḍu dated in his 19th year, states that the title-deeds had to be issued to the residents who were in the enjoyment

---

1. Ibid., vol. VI, Cm. 56.

2. *Journal of Indian History*, vol. VI, p. 200.

3. No. 141 of 1926.

4. No. 309 of 1927.

5. No. 213 of 1925.

of the lands (*anubhōga-p-parrolugu*) as the old registers had been lost in the disturbed state (*duritaṅga*) of the country in the fifth year of his reign.

It will be seen from this that the Bāṇa chief was involved in these disturbances which took place almost immediately on the establishment of Rājārāja III on the Chōḷa throne by Hoysaḷa. And it is also very likely that the Pāṇḍyas were against Rājārāja helping the Bāṇa to regain the land bestowed on him previously. Hoysaḷa Narasimha claims in his inscriptions of this period<sup>1</sup> to have fought with the Sēuṇas in the north first and then turning south to have forcibly captured Adiyama, Chēra, Pāṇḍya, Makara and the powerful Kāḍavas and established the Chōḷa on his throne. The events would not have taken this course if Rājārāja III as the son of Kulōttuṅga III had been the beneficiary of the gift of Sundara Pāṇḍya. As such, he should be different from the son of Kulōttuṅga III presented to the Pāṇḍya as having the name Sundara. Very likely, he was a member of the line of Rājādhirāja II who was driven out of the Tamil country by Kulōttuṅga III.

We have already mentioned that Rājādhirāja II who took refuge in the Vēṅgi country lived there for practically throughout the reign of Kulōttuṅga III. The latest of his inscriptions<sup>2</sup> from Drākshārāma giving both the Śaka and the regnal years is dated in Śaka 1137 and his 49th regnal year, corresponding to A. D. 1215-16, almost to the very end of the reign of Kulōttuṅga. For how long he continued to rule after that is not known. But from Śaka 1138 or A.D. 1216-7 onwards we find another king bearing the same name Tribhuvana chakravartin Rājādhirāja (III) ruling there. We have a large number of his inscriptions going up to his 76th regnal year in Śaka 1215, corresponding to A.D. 1293.

These inscriptions found at Drākshārāma and published in the *South Indian Inscriptions* (Texts), vol. IV are as follows:

General No.	Regnal year	Saka year	Christian year A.D.
1043	36	1174	1252-53
1178	36	1174	1252-53

1. *Ep. Car.*, vol. V, Cn. 203; Bl. 74.

2. *S.I.I.* (Texts), vol. IV, No. 1330.

General No.	Regnal year	Saka year	Christian year A. D.
1045	36	1175	1253-54
1371	37	1175	1253-54
1033	37	1175	1253-54
1230	38	1176	1254-55
1032-A	43	1180	1258-59
1163	50	1188	1266-67
1373	59	1197	1275-76
1152	62	1200	1278-79
1019	72	121*	1289-90
1038	72	1211	1289 ?
1307	76	1215	1293-94

Curiously enough, the Chōḷas of the main line in the Tamil country had ceased to exist as an independent power by that time. The latest regnal year found in inscriptions for Rājendra III, the last of the Chōḷas in the Tamil country, is thirty-three<sup>1</sup> corresponding to A.D. 1279. For how long he ruled the country after that and who succeeded him on the throne are matters to be decided by future discoveries. But the Chōḷa line seems to have continued in the Telugu country for at least some fifteen years thereafter. It is also found that the Kākatiya ruler Rudra and some of his officers figure as donors in some of these inscriptions.

The history of South India, especially of the Tamil country of this period from the time when the Chōḷa empire began to decline to the time when the authority of the Vijayanagara empire was firmly established, has not been studied intensively and properly. It requires separate treatment. Already the Historical Survey has out-grown and as such these have to be reserved for discussion elsewhere. Similarly, the history of the Koṅḡu line of kings promised in the first part of this volume to be given here has also to be reserved for discussion elsewhere.

# INDEX

---

## A

- abhaya* 65  
 Abhaya Kulōttuṅga 67  
 Abhimanyu 54  
*abhiśhēka-k-kāṇikkai* 103  
 Adbhuta-maṇḍala 75  
 Adhirājendra 50, 51, 55, 56, 57, 59, 60, 61, 63, 67, 79  
*adhyāya* 7  
 Adigārikaḷ Sōla-mūvēṇḍavēḷan 66  
 Ādinagar 20  
 Administrative Training Institution 8  
 Agastya 81  
*agni-kunḍa* 62  
 Āgra 72  
*agra-tanuja* 76  
*ahattūham* 9  
 Āhavamalla 38  
 Āhavamalla Sōmēśvara 38, 41, 49, 53  
 Āhavamalla Sōmēśvara I 45  
 Ahmed Nialtigin 25  
 Ahmed Shah Bahmani 115  
 Aihole 64  
 Aiyaṇār 29  
 Ajmir 22  
*Akunṭhōtkanṭha* 70  
 Aḷagar 110  
*Aḷagiyaśōla-t-terinda Valaṅgai Vēlaikkāra-p-paḍaigal* 62  
 Ālavandār 28  
 Alexander 24  
 Alhaṇadēvi 47  
 Allahābad 30  
 Āḷupas 35  
 Āḷupa king 110, 111  
 Āḷupa kingdom 111, 112  
*ālvārs* 110  
 Amara bhuyanga-p-pallavaraiyan 109  
*Amarakōśa* 7  
 Ammarayan 16  
 Aṇahilapātaka 24, 38, 40, 74  
 Ānamalē 89  
 Anandapāl 22  
 Anaṅga Bhīma 123  
 Ananta 33  
 Anantapura (Trivandrum) 9  
*Anantapura varṇanam* 9  
 Anantavarman Chōḍa gaṅga (king of Kālīṅga) 3, 59  
 Āndhra 69, 86, 89, 96, 116  
*Āndra-Mahābhārata* 54  
 Andhra State 100  
 Āndirar 29  
 Aṅga 24, 25, 81  
 Aṅgar 95  
 Aṇikaṅga 122-3  
 Aṇiyaṅga Bhīma 122  
 Aṇiyaṅga Rāhuttaraya 122  
 Anna (Arṇōraja) 74  
 Annamarāja 114, 117  
*Antarvēdi* 62  
 Anumakoṇḍa 117  
 Anurādhapura 79, 80, 117  
 Araiyan Rājarājan *alias* Vikrama Chōḷa Sōliyavaraiyan 52  
*aram* 5  
*ārdrā* day 10  
 Arindama 62  
 Arjuna 54  
 Arjunavarma 31  
*arūḷappāḍu* 88  
 Āryadēśa 83  
 Āsandi 119

**āśrama** 7

**aśvamēdha** 11

**Aśvapati** (title) 15

**Attirala** 100

**Avanti** (Ujjain) 24, 74

**āyirattēlunūrruvan tiru maṇḍapa**  
103

**Ayōdhya** 36, 71

**Ayōjjha** (Ayōdhya) 34

**Ayyapolil** (Ayyavaḷi) 64, 99

## B

**Baihaqi** 25

**Bālabhārata** 36

**Ballala** 74, 75, 76

**Ballala II** 117, 118, 119, 120

**Ballaladēva**, **Srimat Tribhuvana-**  
**malla Kumāra**, 76

**Ballamahā dēvi** 111

**Balla-veggade** 97

**Ballēya** (Huliyera Chief) 120

**Banas** (river) 46

**Banaras** 25, 32, 70, 71

**bandhu** (relative) 39

**Bārasūru** (Bārsūr) 45, 46

**Bārī** 18

**Bastar** 114, 117

**Bastar State** 23, 45, 114

**Beas** (river) 32

**Bēṭa** 117

**Bhagīratha** 10

**Bhaktavatsala temple** 64

**Bhāva Brihaspati** 75

**bhāva-pratimā** 16

**Bhilsa** 43

**Bhīma** 16, 21, 38, 39, 40

**Bhīma**, **Teluṅga** 92

**Bhīmēśvara** (God) 69

**Bhōgavatipuravarēśvara** 23

**Bhōja** 15, 16, 20-23, 25, 26, 30-  
33, 36, 38-41, 43, 47

**Bhōjaśālā** 31

**Bhūlōkamlla** 96

**bhūmi** 66

**Bijjala** 95, 96, 118

**Bitti** 97

**Bilhaṇa** 41-43, 50, 55, 56, 57

**Biṭṭiga Vishṇuvardhana** 88

**Bombay State** 64, 97

**brahmachāri** 6, 7, 8

## C

**Ceylon** 34, 35, 38, 63, 65, 79, 81,  
83-86, 94, 102, 104, 106, 111, 117

**Ceylon Chronicle** 34 - 36, 79, 83,  
102, 109 see *Mahāvamsa*

**Chakrakōṭa** 45, 46

**Chakrakōṭya** 23

**Champā** 32

**Chandella** 22, 30

**Chandī** 75

**Chandradēva** 31, 70-72

**Chandraditya Mahārāja**, **Maha-**  
**maṇḍalēśvara** (Lord of **Amma-**  
**gama**) 45

**Chand Rājī** 72

**charaṇas** 4, 5

**Chāṭtra** 6, 7

**Chāṭtirakkālī** 9

**Chēdi** 21, 22, 26, 32, 81

**Chēdi dēśa** 24

**Chēdipar** 95

**Chēram** 89

**Chetti-naḍu** 109

**Chindaka**, **king** 23

**Chindaka Nagas** 45, 46

**Chitrakōṭa** 23

**Chitramēḷi** 100

**Chitramēḷi maṇḍapa** 100

**Chōḍagaṅga** 122-3

**Chōḍa-rajya** 68

**Chōḷa-gaṅga** (title) 17

**Chōḷēndra** 28

**Chōḷēśvara temple** 90

**Coimbatore** 103

**Colair Lake** 92



Coleroon (river) 58  
 Copper-plate grants from  
   Banswara 21  
   Basahi 47, 50  
   Chārāla 53  
   Chellūr 68, 92  
   Goharwa 30  
   Khaṇḥa 69  
   Kōrni 59  
   Kōrumelli 5  
   Leiden 95  
   Mandhāta 40  
   Parthivasēkharapuram 4  
   Pithapuram 68  
   Rājāpura 23, 46  
   Rāṇastapūṇḍi 51  
   Ryāli 54  
   Soḍasā 41  
   Tēki 68  
   Tilakwada 32  
   Tirupparappu 13  
   Tiruvalaṅgaḍu 16  
   Vēlūrpaḷaiyam 11  
   Vizakapatam 59  
*Cyclic Years*  
   Rudhirōdgārin 97  
   Saumya 120  
   Vyaya 97, 98

## D

Dakhan 45, 46, 56  
 Dakṣiṇadēsa 80  
 Dakṣiṇāpatha 25  
*dakṣiṇāyana saṁkrānti* 30  
 Dalpatraṁ, Kavi 42  
 Dānapalliya 16  
*daṇḍādhipa* 90  
*daṇḍam* (fine) 5  
 Daṇḍanāyaka 77  
 Dantavāra 114  
 Dantēśvari 114  
 Delhi 22, 71, 77, 114

*dēśi* 99  
*dēśi-mukhya* 98  
*dēvadāna* 5, 6, 64  
*dēvar-śeṇṇadai* 6  
 Devagiri 115  
 Dēvēndra 68  
 Dhanañjaya 110  
 Dhārā 20, 31, 38, 39, 44, 75, 76  
 Dhārāvarsha 48  
 Dharmapāla 20  
*digvijaya* 17, 67  
 Dikpaladēva 114  
 Diodorus 23  
*disai disai viḷaṅgum Tisai āyirattu*  
*Ainnūrruvar* 99  
*Districts*  
   Arcot, North 7, 63, 67  
   Arcot, South 6, 58, 99  
   Anantapur 45, 52, 97  
   Bellary 45  
   Bijāpur 64  
   Chingleput 104  
   Chittoor 89  
   Coimbatore 64, 100, 110  
   Cuddapah 100  
   Gōḍavari, West 84  
   Guntur 90  
   Kadur 119  
   Kanara, South 111  
   Kangra 32  
   Madhurai 65  
   Raichūr 45  
   Ramanathapuram 65, 99, 103  
   Tanjāvūr 10, 50, 58, 62, 70,  
     87, 93, 101  
   Tiruchirāpaḷli 62, 66, 88, 102  
   Tirunelvēli 64, 65  
   Trinicomallee 83  
 Dōrasamudra 73, 88  
 Drakṣharamam 54, 69, 84, 89  
 Draṁiḷas 59  
 Drāvīda 56, 86

Draviḷa 96  
 Dulu 34, 35, 111  
 Dushyanta 7  
 Durlabhadēvi 24  
 Durlabharāja 24  
*Dvayāśraya* 24, 39, 74

## E

East India Company 61, 66  
 Edirili-p-perumaḷ 92  
 Eḷaga-ch-chakravartī 108  
 Eḷagam 102, 107, 109  
 Eḷagappadai 108  
 Eḷaga-p-perunderu 108  
 Eḷagattar 107-109, 112, 113  
 Eḷil 112  
 Eḷir-kunram 112  
 Eḷlore 92  
 Eṇṇayiram 6  
 Erragat 45

## F

Feeding-house 1, 2, 4  
 Firishta 22, 32  
 Forbes Sir. Kinlock 42

## G

Gadhīpura (Kanauj) 76  
 Gāhaḍavala 30, 31, 47, 70-73  
*Gajapati* (title) 15, 71  
 Gaṇyas-ud-Din 114  
 Gaṇapati 116  
 Gaṇapati Dēva 116  
 Gaṇḍan *alias* Vararājan 93  
 Gaṅga 119, 120  
 Gaṅga (river) 17, 20, 26, 93  
 Gaṅgaikonda Śōḷan 17, 26, 27, 28  
 Gaṅgaikonda Śōḷapuram 17, 98  
 Gaṅgakuṇḍa 56  
 Gaṅgar 89

Gaṅgarāja, *daṇḍanāyaka* 89  
 Gaṅgavādi 89, 91  
 Gaṅgavādi Ninety-six thousand 88  
 Gaṅgā-Yamung valley 46, 73  
 Ganges (river Gaṅga) 16, 17, 30, 72, 73  
 Gangetic valley 19, 49  
 Gaṅgēya 21, 23, 25, 26, 31  
 Gaṅgēya 38  
 Gaṅgēyadēva 30  
 Gaṅgēya Vikramāditya (king of Kalachūri) 21, 22  
 Gauḍa 18, 25, 47, 49, 81  
 Gayākarna 47  
*ghaṭikā* 9, 10, 11, 12  
*ghaṭikaiyar* 12  
 Ghaṭṭidēva 126  
 Ghaṭṭidēva Yādavaraya 126  
 Ghazna 18, 25, 72  
*Giridurgamalla* (title) 119  
*Giripati* (title) 71  
 Goa 50  
 Gōḍavari (river) 69  
 Gollam era (Kollum or Quilon) 77  
 Gondala 43  
 Gōṅkēśvara temple 90  
 Gōpala 76  
*gōpura* 64  
 Gōvidēva, *Mahāsāmanda* 120  
 Gōvinda chandra 20, 30, 47, 70  
 Gujarat 42, 43, 74, 75 115  
 Gūrjjara 15, 19, 21, 39, 40, 47,  
 Gūrjjara Brahma sēnanī 75  
 Gwalior 22, 42  
*Gyātā* (*Jñāta*) 43

## H

Hajib Tughātigin 73  
 Haiderabad State 38  
 Halebid 88  
 Hansy 32

Hēmachandra 24, 39, 74  
 Hēmadri 115  
 Heñjēru 98  
 Himālayas 48  
 Hindusthan 17, 22, 72, 73  
 Hiranyavarman 12  
 Hoogly (river) 46  
 Hūṇa 47  
 Hūṇadēśa 24

## I

Ibrāhim 72  
*idangai* 61-63, 65-67  
 Ikshupaḷli 90  
 Ilam 33, 34  
 Ilamaṇḍalam 34  
*ilaṅgō-p-paruvam* 46, 48  
 Imperial Chōlas 40  
 India 22, 35, 37, 73  
   Northern India 17, 29  
   South India 47, 64, 65, 101, 113  
 Indraprastha 71  
 Indraratha 20, 21  
 Indrasthana 71  
*Inscriptions from*  
   Āḍuturai 66, 88, 90  
   Āśandi 120  
   Ārppākkam 104  
   Ammanji 111  
   Āvaṇi 66, 120  
   Bahāl 116  
   Barasūru 45  
   Bhēraghat 47  
   Budamuttava 84  
   Budaun 76  
   Chidambaram 78, 105, 107  
   Dantāvāra 114  
   Dēvanagala 85  
   Dīrghasi 60  
   Drāksharamam 54, 65, 84  
   Eṇṇāyiram 6  
   Gaṅgaikoṇḍa-Śōḷapuram 70

Gwalior 36  
 Hanumkoṇḍa 117  
 Hēmavati 97, 99  
 Idaiyāttūr 86  
 Jainad 73  
 Jhalrapatan 42  
 Jhusi 30  
 Kanyākumari 3, 13, 53  
 Karūr 87  
 Kavērippakkam 7  
 Kīlūr 14  
 Kottaśivaram 52  
 Kōyil Tēvarāyanpēttai 10  
 Kulēnūr 20, 23  
 Kumāralingam 110  
 Kuruspal 46  
 Madakasira 52  
 Mahōba 22  
 Mangalore 111  
 Maṇimaṅgalam 28  
 Marudaḍu 67  
 Nagai 38  
 Nerūr 102, 103  
 Neyvāśal 108  
 Niḍubrōlu 90  
 Paithan 116  
 Palamōṭṭai 83  
 Palampet 116  
 Pallavarāyanpēṭṭai 92, 98, 104  
 Piawan 30  
 Pirānmalai 99  
 Polonnaruva 63, 65  
 Pudukkōṭṭai 108  
 Puñjai 64  
 Saṅgrāmanallūr 64  
 Śēmbanārkōil 101, 105  
 Set-Mahet 76  
 Sitabaldi 74  
 Sittamalli 50, 55, 57  
 Śrīraṅgam 57, 61, 66, 76, 111  
 Srivilliputtūr 65  
 Talagunḍa 11

Tirubhuvanam 117  
 Tirukkōvalūr 99  
 Tirumayanam 93  
 Tiruputtūr 103  
 Tiruvālaṅgaḍu 104, 105, 107  
 Tiruvāliśvaram 64  
 Tiruvallam 63  
 Tiruvāṇḍarkōyil 2  
 Tiruveṇkāḍu 62  
 Tiruvīḷimīlalai 93  
 Tiṭṭaḷuḍi 99  
 Udayapūr 42, 43  
 Ukkiraṅkōṭṭai 65  
 Upparapalle 116  
 Uttanūr 67  
 Uṭṭattūr 61  
 Varāṅga 111  
 Vijayamaṅgalam 103  
 Vikkirmaṅgalam 65  
 Iraṭṭapaḍikonḍa Śōlan 28  
 Islam 17  
 Isvara temple 119

## J

Jagadālpūr 45  
 Jagaddēva 42, 43, 73  
 Jagadēkabhūṣhaṇa Chindaka  
 Naga Mahārāja (of Dharavar-  
 sha) 45, 46  
 Jagadēkamalla III 95  
 Jagadvijaya 102, 104  
 Jagatipala 34, 36, 38  
 Jaimini School 10  
 Jaina Prabhandhas 42  
 Jakala mādevi  
 Jaitrapala 115-117  
 Jaitugi 116  
 Jalamayam Jayasthamba 17  
 Jananātha 44  
 Jananātapura 89, 90  
 Jaṭa Chōḍa Bhīma 16  
 Jayabāhu 83, 84  
 Jayabāhudēva 81

Jayadratha 102  
 Jayakēśi (king of Kadamba) 50  
 Jayaṅkoṇḍar 67  
 Jayaṅkoṇḍa Śōḷamaṇḍalam 66  
 Jayasimha 20, 21, 40, 41, 42, 47,  
 49, 52, 74

## K

Ka'aba 73  
 kaḍamai 93  
 Kaḍamba 50  
 Kaḍaram (Sri Vijayam) 95  
 Kaḍaramkoṇḍa Śōlan 28  
 Kaḍarar 95  
 Kāfirs 73  
 Kaikayar 95, 96  
 Kailāsa 26  
 Kakatiya 113-117  
 Kalachūri 22, 30, 46, 95, 96, 117,  
 119  
 Kalachūri Samvat 69  
 kalam 4, 7  
 Kaḷanivāśal 108  
 Kaḷañjara 18, 19, 22, 23, 30  
 kaḷañju 5, 7, 57, 58  
 Kalhaṇa 33  
 Kalidasa 7  
 Kalinga 16, 47, 53, 55, 60, 81,  
 120  
 Kalinga, Southern 92  
 Kalingar 52, 95, 96  
 Kalingattu-p-parani 3, 48, 67  
 kalveṭṭu 58  
 Kalyāṇa 15, 49, 52, 60, 76, 81,  
 90, 94, 95, 97, 118  
 Kamaḍēva (Vijaya Paṇḍya) 118  
 Kāmārṇavarāyan 16  
 Kāmārūpa 46  
 Kambar 85, 86  
 Kāmbōdar 96  
 kāṇam 5  
 Kanauj 22, 70, 72, 73, 76  
 Kañchi 11, 50, 55, 56, 89, 90  
 Kañchi goṇḍa (title) 89

- Kāṅchīpuram 9, 12, 61  
 Kāṇḍalūr 1, 2, 3, 4, 6, 8, 9, 10, 11, 13  
 Kāṇḍalūr Salai 3  
 Kaṇḍamaṅgalam 58  
 Kāṇḍara naḍu 58  
 Kāṅgrā valley 30, 95  
 Kanha 40  
 Kannada dēśa 49  
 kāṇi 109  
 Kannada 117, 118  
 Kannadar 95, 96  
 Kannakuchchi 27, 33, 34, 48  
 Kannara 37  
 Kannaran (Krishṇa) 34  
 Kantalay 83  
 Kantalay *alias* Vijayarāja Chaturvēdi maṅgalam 83  
 kaṇṭhikā, 48, 50  
 Kaṇva 7, 8  
 kanyā dāna 42  
 Kanyakubja 18, 25, 29, 30, 31, 32, 33, 36, 37, 47, 49, 71, 72  
 Kanyakumari 13  
 Kapātapura (Madurai) 94  
 Kapaṭeśvara 33  
 Kappalar 96  
 Karaikuḍi 108  
 Karavandapuram 65  
 Kariyamānikkar (God) 100  
 Karka (Kaka) 75  
 Karṇa 31, 38, 39, 40, 46  
 Karṇamēru 47  
 Karṇāṭa 15, 21, 96  
 Karṇāṭar 39  
 Karunandadakka, Āy king of Vēṇaḍu 4, 12  
 Karuvūr 87  
 Kashmir 33  
 Kāśi 24, 25, 47, 71  
 Kāśīkar 96  
 Kassapa, Chief of Kēśadhatus 34, 35  
 kāsū 5, 6, 10  
 Kaśyapa 62  
 Kaśyapa Paṇḍya Dhanañjaya Sundara *alias* Kulōttuṅga śōla-bhatta 109  
 Kauśalar 29  
 Kavēri (river) 93, 94  
 Kāvērippakkam 7  
 Kēraḷa 9, 15, 111  
 Kibla 73  
 Kiḷ-kunḍaru division 108  
 Kinlock Forbes, Sir 42  
 Kira 30, 32, 47  
 Kiranūr *alias* Kolūmamgonḍa Śōlanallūr 109  
 Kitti 34, 35  
 Kitti Niśśanka Malla 106  
 Kitti, Prince 79  
 Kolāla (Kōlār) 88  
 Kolvūr 97  
 Kollam 78, 106  
 Kollam, Destruction of 77  
 Kollam era 72, 78, 91  
 Kolippakkai (Kulpak) 43  
 Koṅgaṇar 95, 96  
 Koṅgu 47, 88, 89, 102, 103, 109-112  
 Koṅgu dēśa Rājākkal 15  
 Koṅgu naḍu 109  
 Koṅkaṇa 21, 111, 112  
 Koṅkana, North 47  
 Koṅkaṇar 29  
 Koṅkaṇa rājya 111  
 Kōśalai naḍu 20  
 Kōśalar 95, 96  
 Kot-Kangra 32  
 Kōṭṭāru 91  
 Kōyattūr 89  
 Kōyil Tēvarayanpēṭṭai 10  
 Krishṇa 74, 75  
 Krishṇa (river) 44, 49

*kshatriya* 11  
*kuḍimai* 93  
*kulapati* (title) 7  
 Kulaśekhara 101-105, 107, 111  
 Kulaśekhara, Jātavarman 106  
 Kulaśekhara-dēva, Perumāḷ 103  
 Kulaśekhara-dēva, Tbc. 103  
 Kuliṅgar 52  
 Kulam (Kolam) 92  
 Kulōttuṅga 46, 48, 51, 54, 55,  
 59, 61, 66, 68, 69, 70, 82, 84, 98  
 105, 106, 117, 118  
 Kulōttuṅga, Kumāra 92, 93  
 Kulōttuṅga Chōḷa dēva, Perumāḷ  
 88  
 Kulōttuṅga Chōḷa dēva, Tbc. 97  
 Kulōttuṅga I 2, 45, 50, 56, 58,  
 60, 64, 65, 67, 69, 70, 77, 78, 79,  
 84-88, 91, 92, 102  
 Kulōttuṅga I, Rajakēsarivarman  
 Chakravarti 57  
 Kulōttuṅga II 85, 92, 93, 94, 95,  
 97, 101, 119  
 Kulōttuṅga III 62, 69, 93, 94, 97,  
 100, 105-107, 113, 117, 120  
*Kulōttuṅga Chōḷan-Pillai-t-tamil*  
 24, 85, 95, 97  
*Kulōttuṅgan-kōvai* 107  
 Kulōttuṅga Sōḷamartāṇḍalayam  
 70  
*Kulōttuṅga Sōḷan-ulā* 67  
 Kulūta 32  
 Kumārapāla 74-76  
 Kumari 84  
 Kundavai 51  
 Kundukula 102  
 Kuṅga 47  
 Kuntala 48, 118  
 Kūpaka 91, 92  
 Kūpakar 96  
 Kūrattālvār 124-7  
 Kurudēśa 24  
 KuruḷanKūttan *alias* Uttamakkōn  
 110

*kurunī* 7  
*kuśa* 9  
 Kuśika 71  
 Kūttar (Natarāja) 87  
*kuṭṭu* 5  
*kuṭumba-yātrā* 114

## L

Laḍḍigam 89  
 Lahore 32  
 Lakhaṇapāla 76  
 Lakshmadēva 72, 81  
 Lakshmaṇa 37  
 Lakshmi 68  
 Lakshmi Karpā 30, 31, 47  
 Lanka 33, 81, 85  
 Laṅkāpura (city) 94  
 Laṅkāpura-Daṇḍanāyaka 101, 102,  
 Lāṭa 21, 75, 120 104  
 Laṭar 15  
 Lōka (Lōkēśvara) 35

## M

Mackenzie 77  
 Madana 31, 76  
 Madanapāla 70, 73  
*maḍattu śaiṭṭa-p-perumakkal* 7  
 Madhurāntaka 28, 41, 46, 86, 91  
 Madhurāntaka, Chief of Naga-  
 vamsī 23  
 Madhurāntakī 68  
 Madhuva 38  
 Madhya Pradesh 45, 114  
*maḍiṭchēvakar* 65  
 Madood 32  
 Madras 61, 95  
 Madurai 2, 78, 89, 97, 101-6, 108  
 110, 112  
 Madurai maṇḍalam 19, 23, 24  
*Maduraiyum Pāṇḍiyan mudit-t-*  
*talaiyum koṇḍarūḷiya* (title)  
 106  
 Maghada 96  
 Māghadar 96

- Mahadēva 116, 117  
 Mahāgala *alias* Vikkīrama Śāla-  
   mēghapura 84  
 Mahālāna Kittī 34, 35, 111  
 Mahānadi (river) 46  
 Mahāśālā 13  
 Mahātāntra 63, 64  
 Mahātīttha 80  
 Mahāvamsa 34, 35, 37, 82, 101,  
   104, 109, 111  
 Mahēndragiri (hill) 16  
 Mahēndrapāla 36, 37  
 Mahēndrarāja 24  
 Mahēsi 35  
 Mahēśvara maṭha 84  
 Mahi (river) 46  
 Mahiala 31  
 Mahinda V 34  
 Mahipāla 20, 36  
 Mahmud (of Gazna) 17-19, 22,  
   24, 26, 30, 36, 72  
 makara 95  
 makaradhvaṇḍa 95  
 Malahara 73  
 Malahara-kshōṇiśa 73  
 Malaiyāḷar 63  
 Malapa *or* Malaha (hill tribe) 73  
 Malaparṣṭi-gaṇḍa (title) 73  
 Mālava 15, 21, 22, 38-45, 72, 74,  
   75, 76, 120  
 Malava Chakravartin 109  
 Malaya 102  
 Malaya hills 26  
 Maldives 83  
 Malhī *or* Malhīra 73  
 māḷigai 2  
 Mallidēva Chōḷa Mahārāja, Śrīman  
   Mahāmaṇḍalēśvara Uṇṇaiyūrpura-  
   varādhiśvara Śrī Mahēśvaran  
   Tribhuvanamalla 98  
 Mallugi 117  
 Maḷuvar 95  
 Malwa 43, 72  
 Māṅabharāṇa 83, 104  
 Manābharaṇēśvara dēva 111  
 Maṇalkuḍi *alias* Uttama Śōḷa  
   chaturvēdimāṅgalam 93  
 Maṇḍalika 40  
 maṇḍalika-murāri 122  
 Mandēva (Mandvi) fort 39  
 Maṅgēśvaradēva 97  
 mara 107  
 Mara army 107  
 mara-ch-chāmāntas 107  
 Marappaḍai 108  
 Marattar 96  
 Marava 107  
 marumaganūr 103, 104  
 Maruti 82  
 Mārāya Paṇḍa 90  
 maryādi 4  
 māsāttunāyan (title) 66  
 Māsāttunāyan, Uyyavandān Tīru-  
   vaṇṇāmalaiyan Vijayabāhu  
   84  
 Massanae 24  
 Maśūd I 72  
 Maśūd I (Yamini king) 25  
 Maśūd III 73  
 Maśuṇidēśa 19, 23, 24  
 maṭha 5, 7, 84  
 Mathurā 24  
 Mathurā dēśa 24  
 Mattikāvātātīttha 80  
 Mattirar (Madra) 95, 96  
 mātula 90  
 Mayilaināthar 84  
 Mayūra Sarma 9, 12  
 Mēḍama 52  
 Mēganāda 37  
 Mēḷama 52  
 mercantile-guild 65  
 Mēru temple 46  
 Mērutuṅga 25, 31, 39, 43  
 meykīrtti  
   Puḷamādu viḷaṅga 68

*Pugalśūlnda puṇari* 46, 57  
*Pūmaṅgai vaḷara* 86  
*Pūmannu paḍumam* 95  
*Pūmaruviya poḷilēlum* 96  
*Pūmaruviya puviyēlum* 85  
*Pāmaruviya tirumaḍandaiyum*  
 58  
*Puvimaṅgai vaḷara* 86  
*Puyalvāyṭṭu* 113  
*Tiṅgalēr taru* 2, 27, 29, 40  
*Tirumāḍu puviyenum* 27  
*Tirumagaḷ pōla* 1  
*Tirumanni vaḷara* 2, 16  
*Tirumanni viḷaṅgum* 58  
*Tiruvaḷara-ch-cheyam vaḷara* 3  
*Tiruvaḷar tiral puyattu* 28, 44  
*Viramē tunaiyāgavum* 20, 48,  
 68  
*Minchirai* 4  
*Mīmāṁsā* 5, 6, 7  
*Miṇavar* (Paṇḍya) 29  
*Mithilā* 48, 96  
*Mōhaḍavāsaka* 41  
*Month*  
 March 98  
 May 50, 51, 59, 77  
 June 50-52, 55, 58, 87, 103  
 July 103, 105  
 August 51  
 October 54  
 November 59  
 Āṇi 58, 77  
 Margaḷi 10  
 Rishaba 50  
 Mount Abu 75  
*mudal* 5  
*Muḍikoṇḍa Śōḷan* 29  
*mukṭi* 30  
*mukṭkāl vaṭṭam* (a temple) 5  
*Mūlapariśad-Mahāsabhā* 103  
*Mūltān* 22  
*Mummuḍi Śōla Viṇṇagara Ālvar*  
 temple 57  
*Mummuḍi Śōḷan* 28

*munṇirppalan iluvu paṇṇirāyiram*  
 83  
*Mūnrukai-Mahāsēnai* 64, 65  
*Mūnrukai-t-tiruvēlaikkāran*  
*Daladāya-p-perumpallī* 63  
 Murala 47  
 Muśaṅgi 21  
 Muttuppēṭṭai 50  
 Mysore 88  
 Mysore State 66, 116, 119, 120

## N

*Nāchchinārkkiniyar* 94  
*nāḍu* 66, 99  
*Nadūladēśa* 24  
*Naga* 23  
*Nagati* 116  
*Nagarattār* 63, 64  
*Nāgavamśōḍhbava* (title) 23  
*Nagpur* 74  
*Nagrakōṭe* 32  
*Nakshatra*  
 Rōhini 50  
*nāli* 6  
*Nallaman* 117  
*nālu-pādam* 9  
*Namaṇaikkōṇam* 23  
*nambis* 7  
*Nambūtiris* 9  
*Nānādēśi* 99  
*Nānādēśi-tiśai-y-āyirattu ainnūr-*  
*rūvar* 63  
*Nanda* 19  
*Nanda or Bida* 18  
*Nandamapūṇḍi* 54  
*Nandapurī* 75  
*Nandivarman Pallavamalla* 3, 10  
*Nāñjil nāḍu* 91  
*Nannan* 112  
*Nannaya Bhaṭṭa* 54  
*Nannūl* 84  
*Nānyadēva* 96  
*Naralōkavīra* 77, 78



*Narapati* (title) 15, 71  
 Narasimha 119, 120  
 Narasimha Bhūbhujā 120  
 Naravarman 72  
 Nārāyaṇa Bhaṭṭa 54  
 Narmadā (river) 15, 16, 39, 114  
 Narṛṇai 112  
 Nayanārs 88  
 Nellittōppu 58  
 Nēmi 77  
 Nellore 100  
 Nēpāla 96, 97, 100, 120  
 Neriyudai-p-perumaḷ 92  
 Niḍugal Chōḍa 98  
 Nigarili-Śōḷa maṇḍalam 65, 97  
*nilaiṇṇadai* 91  
 Nishadarayan 109  
 Niśśaṅkamalla 106  
 Niśśaṅkamallēśvara 106  
 Nittavinōḍa vaḷanaḍu 58  
 Nolambavaḍi 118, 119  
 [Nriṇṇa]ti bhūṣhaṇa or [Kshi]ti  
*bhūṣhaṇa* (title) 45  
 Nripatuṇḍavarman 7

## O

Oḍḍar 52  
 Oḍḍa-vishaya 20  
 Oṭṭakkūttar 85, 92, 93  
*ōttu* 5

## P

*paḍaikkalam* 5  
 Padmarāja 33  
 Palandīpa 83  
 Pallavarāyan *alias* Tiruchchiṇṇam-  
 balam uḍaiyan Perumanambi  
 104  
 Pallavarāyanpēṭṭai 104  
*Pallī* 88  
 Palni 109  
 Pañchalar 96

Pañchapallī 19, 23  
 Paṇḍi maṇḍalam 2, 28, 110  
 Paṇḍinaṭṭu ēlagattar 108  
 Paṇḍita Chōḷa 26  
 Paṇḍita Paṇḍya (title) 111  
 Paṇḍu 35  
 Paṇḍu 37  
 Paṇḍya Dhanaṇjaya 110, 111  
 Paṇḍya Dhanaṇjaya (title) 110  
 Paṇḍuvijayaka 104  
*Pandyan Chronicle* 77, 78  
 Paṇḍyan Civil War 85, 101, 103,  
 104  
 Paṇḍya Rajasimha 91  
 Paṇḍalar 29  
 Panjāb 22, 24, 25, 32, 95  
 Pappalar 96  
*Parakēsari* (title) 36, 86  
 Parakēsarivarman 87  
 Parakkama 35, 37  
 Parākrama 102, 105  
 Parākramabahu 85, 102, 104-106  
 Parākramabahu I 101  
 Parākrama Paṇḍya 77, 85, 88  
 101, 103  
 Parākrama Paṇḍya, Māṇavarman  
 65  
 Parākrama Paṇḍya Maśattuvāyan  
 66  
 Paramāra 33, 38-41, 43, 44, 75,  
 76, 81, 84, 85, 91  
 Parāntaka 87  
 Parāntaka I 65  
 Parāntaka III 86  
 Parāntakadēva 89, 90.  
 Parāntaka Paṇḍya, Jaṭavarman  
 2, 91  
*Pārijāta mañjari* 31  
*Parivārakkondam* 63  
*parivaṭṭam* 88  
 Parthivaśēkharapuram 4, 6, 7, 8,  
 9, 12, 13  
*pātāla* 118

*pāṭhaśālā* 6  
 Pattana 74  
*Paurōhitya* 5, 6  
*Pavīṭiya charaṇa* 4  
 Periyānambi 124  
 Periyānattavar 100  
*Periyapurānam* 94  
 Periya Vaḍugan 88, 90  
*Periya vishaiyam* 66  
 perpetual lamp 84  
*perumakkaḷ* 5, 6  
*Perumbaḍḍi-valaṅgai-mahāśēnai*  
 66  
*Peruñchālai* 13  
*Perundanattu Valaṅgai-p-paḷam-  
 paḍaigal* 62  
 Peruñjēru 97, 98  
*Peruñkuri-p-perumakkaḷ* 93  
 Piawan 25  
*pillaiḡalḍanam* 64  
*poll-tax* 63  
 Pondicherry 9  
*Ponni* (river) 93  
 Poppaḷar 96  
 Pottappi 44  
 Poysaḷa dēva 97  
*Prabandha chintāmaṇi* 39  
*prādhāni* 54, 65, 84, 85  
*prākāra* 57  
*prasasti* 53, 70, 93, 100  
     Gāhaḍavāla 70  
     Mount Abu 75  
     Nagpur 39, 41, 42, 72, 81  
     Udayapur 15, 20, 21, 26  
     Vaḍanagar 75  
     Vērāval 95  
 Pratihara 36  
*pravachanam* 9  
 Prayāga 30, 32  
 Pratāparudra 114, 115  
 Pudukkōṭṭai State 86, 106, 108,  
 113

Pulattthinagaram 80-82

Pūluvar 96

*purōhita* 102

## R

Raghu 36

Raghuvamsa 36

Rāja (of Delhi) 32

Rajadhirāja 11, 33, 35, 38, 53,  
 92, 104, 105, 117

Rajadhirāja I 2, 13, 27, 29, 40,  
 111

Rajadhirāja II 69, 93, 97-9, 101,  
 104, 105, 107, 113, 119

Rajagambhira (Rajarāja II) 94

Rajagambhira, Añjukōṭṭai Naḍal-  
 vān 107

Rājakēsarivarman 10

*Rājakēsari* (title) 36

Rājakēsarivarman Rājendra 58

Rājakēsarivarman *alias* Tbc. 93

Rājamahendra chaturvēdimaṅga-  
 lam 57, 58

Rājamayyan 44

*Raja Prasasti* 115

Rajarāja 10, 11, 13, 15, 16, 51,  
 52, 54, 59, 68, 95

Rajarāja (E. Kalinga king) 68, 69

Rajarāja I 1, 2, 12-14, 49, 51, 62,  
 83

Rajarāja II 92-94, 96, 97, 117,  
 119

Rajarāja III 120

Rajarāja chaturvēdimaṅgalam 6

Rajarāja Chōḍagaṅga 68

Rajarāja Dēvēndravarmān 60

Rajarāja-k-kaṅkuḍiyarāyan 107

Rajarāja Mummaḍi Chōḷa 68

Rajarāja Narēndra 51-54, 68

*Rajarāja-p-peruñchālai* 13

*Rajarāja-Sōlan ulā* 93

*Rāja-rājat-terinda Valaṅgai*

*Vēlaikkārar* 62

Rajasēkhara 36

Rājasimha 11, 64

Rajasundari 59

*Rajatarāṅgiṇi* 33

Rājendra 16, 17, 20, 25, 29, 34,

45, 49, 53, 55, 59, 60, 68

Rājendra I 2, 6, 16, 19, 21, 23,

24, 26, 27, 52, 70, 83

Rājendra II 28, 53, 86

*Rājendra Śōlan māḍai* 57

*Rājendraśōla-p-padinēnbhūmi* 66

Rājiga 56, 57, 119

Rājiga (Rājendra) 119

*Rājiga Chōḷa manōbhāṅga* (title)

119

Rājyapāla 18, 22, 36

Rāma 34, 36, 37, 82

Rāmachandra 116

Rāmānuja 123-8

*Rāmānujārya-Divya Charitai* 124

*Rāmāyana* 85, 86

Rāmēśvaram 89, 102, 106

Raṇadhavala 42

Raṇaśūra 20

*raṅga-maṇḍapa* 119

Raṅganātha temple 76, 77

*Rās Mālā* 42

Rāshtrakūṭa 70

Raṭṭa 94

Raṭṭapādi 21, 50

Ravana 85

Ravi (river) 32

Raya-Mūrari 118

Rēwa 52

Rōhaṇa 34-36, 79, 83

Rudra (Rēchērla chief) 116

Rudradēva 116

Rudrāmba 115

### S

*sabhā* 4, 6, 12, 57, 103

Sahasāṅka 32

Sahavahana 32

Sahilladēva 32

Sailendra 95

Śaivēśvaram Uḍaiyar *alias* Saiva  
chakravartin, Kāśyapan Paṇḍya  
Dhanañjayan 109

Śaka 42, 45, 51, 54, 77, 78, 86,  
87, 90, 98, 103, 110, 111, 120

Śakkarakkōṭṭam 19, 23, 24, 45,  
48, 67, 117

Śaktivarman II 54

Sakuntalā 7, 8

*Sākuntalam* 7

Śākyarakshita 70

*Śālābhōga* 5, 6, 8

Śalai 4, 5, 6, 8, 10, 11, 12, 13

Śalai (at Kandaḷūr) 3

Salāmēgha 84

*Śālāmēgha* (title) 86

Śalavāhana dēva 32

*Śalivāhana Sakābdam* 77

Salman 73

Salman, Mas'ud ibn Sa'd ibn 72

Śaḷukki Vikramāditya 49

*Sāmavēda* 9, 10

*sāmantas* 74

*samvatsara śrāddha* 32

*sandhyā dīpa* 109

Śāṅgam period 112

*Saṅghabōdhi* (title) 36

S'angu 20

*Śanivāra siddhi* (title) 119

Sankamarāja 117

Sapadalaksha *or* Śākāmbhari 74

*Sapta-Koṅkana* 112

Sarvajñabhūpa *or* Sarvajña Chak-  
ravartin 96

*śaṭṭar* 4-8

*śāttirar* 6

*Saugata-parivrajaka-mahā paṇ-*  
*ḍita Vāgīśvara-rakshita* 70

- Saumitri 37  
 Śedarayan *alias* Malaimaṇḍala  
     Nayakan 81  
 Śekkiḷar 94  
 Sēṇapati (Vishvaksēna) shrine 77  
 Śēralar 95  
 Sērmadēvi 64  
 Sētu 48  
 Sēuṇas (of Dēvagiri) 15, 115-117  
 Shamans 73  
*shower of gold* 113-115  
 Siddharāja-Jayasimha 74  
 Siddharāja-Jayasimha, Chaulukya  
     (of Gujarat) 43  
 Śikkal udaiya Śeṭṭiyar 97, 99  
 Śilāmēghavanna (title) 86  
 Simhaḷa 33, 35  
 Śinar 95  
 Sind 24  
 Sind, Upper 23  
 Sindhas (of Sindhavāḍi) 45  
 Sindhurar 29  
 Śiṅgaḷar 29, 96  
 Śiṅgaṇar 95  
 Śirai nāḍu 97, 98  
 Śiṛiya tālai (paternal uncle) 28  
 śiru danam 63  
 Śittiramēli 100  
 Śittiramēli Bhaṭṭar 100  
 Śittiramēli-Periyanāḍu 99  
 Śittiramēli Periyanāṭṭavar 99,  
     100  
 Śittiramēli Viṇṇagar 100  
 Śiva brāhmaṇas 87, 109, 110  
 Śiva temple 42, 45, 84, 87  
 Skandasishya 11  
 ślōka 81  
 Sodrae 24  
 Śōla Ayōtṭiyarājan (title) 28  
 Śōla Janakarājan (title) 28  
 Śōla Kānnakuchchiyarājan  
     (title) 28  
 Śōla Kēraḷan (title) 28  
 Śōla Pāṇḍya (title) 2, 27, 28  
 [Śō]ḷiya-narpaḷaṅkāṣu 103  
 Śōmadēva (Śōmēśvara II) 56  
 Śōmakula 111  
 Śōmanāthapura 19  
 Śōmēśvara 32, 40, 46, 54, 61, 97;  
     118  
 Śōmēśvara I 49  
 Śōmēśvara II 48-50, 60  
 Śōmēśvara III 96  
 Śōṇāḍu 14  
 Sōvaladēvi 54  
 Sōvidēva 118  
 Śrīraṅgam temple 58  
 Śrīvallabha 13, 104, 105  
 Śrīvallabha Madanarāja 34, 37  
 Śrīvallabha-p-perumbaṇaikkaṅ  
     *alias* Aviyalaṅ-raḍakkaṅ 13  
 Śrīvallava-p-peruñchālai 13  
 Śrutimāns 62  
 Staff College 8  
 Sultan Ibrahim 72  
 Sultan Mahmūd 73  
 Sundara Pāṇḍya I, Maṇavarman  
     108, 110  
 Sundara Śōla 29  
 ūṅgam 67  
 Surāditya 32  
 Śūravīra 43  
 Sūriyanarkōyil 70  
 Suttamalliyār 84  
 Śuvaran Māraṅ (Muttaraiya chief)  
     3  
 svayamvara 24  
  
 T  
 Tabaqat-i-Nashiri 72  
 Tahnēsūr 32  
 Tailapa 15, 40

- Tailapa III 95, 96  
 Tailiṅga 116  
*Taittiriya charaṇa* 4  
 Takkana Ladam 20  
*Takka-yāga-parani* 93, 94  
 Talaguṇḍa 11  
 Talakāḍu 88  
*Talakāḍukonda* (title) 88  
*Talavakāra charaṇa* 4  
*Taluk*  
     Karkal 111  
     Madakasira 52, 97  
     Nannilam 58  
     Pāpaṇāsam 58  
     Perambalūr 88  
     Udipi 111  
     Udumalpet 110  
*tambirāṭṭiyār* 122  
*Tamiḷ Nāvalar Charitai* 92, 94  
 Tamraparaṇi (river) 82  
 Taṇḍabutti 20  
*taṇḍār chālai-k-ka'am arutta*  
*Kōp-parakēsari* (title) 2  
 Tañjavūr 40, 58  
*tapasvin* 84  
 Tapti (river) 46  
*tārkuḷa* 9  
 Tējahpāla 75  
 Telugu Chōḍa 45, 52  
 Teluṅgar 52, 95  
 Ten-Madurai 24  
 Tennar 95  
 Tereyūr 89  
 Tigatta 96  
*tilaka* 68  
 Tirhut 96  
 Tiruchchempon-paḷli-uḍaiyār 101  
 tiruchchūla vēḷaikkāra. (Vēḷaikkāra of the Śiva temple) 64  
 Tirukkaḍavūr 93  
 Tirukkōvalūr 14  
 Tirumalakke 102  
 Tirumaliruṇjōlai 110  
 Tirumayanam uḍaiyār 93  
*tirunakṣatram* 99  
 Tiruppārkaḍal Paḷḷikonda peru-mal Śittiramēli Viṇṇagaram 100  
 Tiruttaḷiyāṇḍa nayanār temple 103  
 Tiruvāṇḍarkōyil 2  
 Tiruvaṇilai-Āḷuḍaiya-Nāyanār 87  
*tiruvāśal* 65  
*Tisai-āyirattu Ainnārruvar* 99  
*tiṭhi*  
     śu. pañchamī 126  
     śu. prathamā 30  
 Toggala 21  
*Tolkāppiyam* 94  
 Toṇḍaimaṇḍalam 28  
 Tooth Relic, Great temple of 63  
 Torravār 96  
*trairājya* 10  
*Trairājya-Ghaṭika Madhyastha* 10  
*trairājya vyavahāra* 5, 8  
 Travancore, South 91  
*Tribhuvanamalla* (title) 60  
 Tribhuvanamalla Pāṇḍya 119  
 Tribhuvanavirādēvarāja 126  
 Trigarta 32  
 Trikalīṅga 116  
*Trikalīṅgā-ṭhipati* (title) 46  
 Trikartā 95, 96  
 Trikarttar 95  
 Trilōchanapāla 18, 30  
 Tripurī 21, 46, 81  
*Trisāṅkupati* 71  
 Trivandrum 4  
 Tuḷu 35, 111, 112, 113  
 Tuḷu Pāṇḍyas 37, 111, 112  
 Tuṅgabhadra (river) 49, 56  
*Turushkar* 21, 32, 72, 78, 97

## U

- Ubhaya-nānādēśi* 99  
*Uchchaṅgi* 118, 119

- Uchchangi Paṇḍya 118  
 Udayaditya 39, 42, 43, 72, 73, 81  
 Udayapur 42  
 Ujjain 22, 38, 72, 74  
 Ujjain, Rājā of 22  
 Ulugh Khān 114  
 Uparāja Virabahu 80  
 Uppala 40  
 ūr 108  
 Uraṅgai 113  
 Utkaladēśa 70  
 Utpala 40, 43  
 Uttara Kōśala 71  
 Uttarāpatha 31  
 Uttar-Pradesh 71  
 Uttira Laḍam 20  
 Uyyavandan Tiruvaṇṇamalaiyan  
 Vijayabahu Maśāttunāyan 65
- V**
- vaḍḍa vyavahāri* 98  
*Vaḍḍavyavahāri, dēśimukhya* 99  
 Vaḍa Kōśalar 97  
 Vaḍa Madhurai 24  
 Vaḍaperunkōyil uḍaiyan 65  
*Vaḍugar* 63  
 Vaḍugar (Andhra) 113  
 Vagada region 40  
 Vaidumba 16  
 Vaikuṇṭha Perumaḷ temple 12  
 Vākpati 43  
 Vākpati II Muñja 40  
*Valaṅgai* 61, 62, 65  
*Valaṅgai-iḍaṅgai māgamai* 63  
*valaṅgiyar* 63  
 Valiya Salai 4  
 Vallabha Vallabha (i.e., Vīra  
 Rājendra) 53  
 Vallāḷa dēva 120  
 Vallava 33  
 Vallavar 29  
 Valmiki 86  
 Vaḷuvūr 58  
 Vanapati 60  
 Vaṅga 47  
 Vaṅgāḷa dēśa 20  
 Vaṅgaṇar 29  
 Vaṅgar 95  
 Vaṅkshu (river) 72  
*Vanniya* 66  
 Varadarājar of Nambūr 125  
*vāram* 5, 9  
 Vātagiri (river) 80  
 Vatsarāja, *Mahārājaputra* 41  
 Vattavar (Vatsa) 95, 96  
*Vattēluttu* 12  
 Vayirāgaram 67  
*Vēda* 6, 11  
 Vēdānta 7  
 Vēdic School 13  
*vēḷaikkārar* 62, 63, 64, 80, 81, 82, 105  
 Velanāṇṭi Gōṅka 90  
*vēli* 64  
 Vēḷkula Śaḷukkiyar 29  
*Vellāḷa* 66  
 Vellāru (river) 107  
*vellāṭṭigal* 5  
 Vēṇadu 13, 77  
 Vēnda-Chūḷamani-p.pallava-  
 raiyan, Araiyan Śīriyan *alias*  
 109  
 Vēṅgāḷa naḍu 87  
 Vēṅgi 44, 48, 51-57, 59, 60, 68,  
 69, 86, 89, 91, 113  
 Vēṅgi maṇḍalam 113  
 Viddhasalabhāṇjika 36  
 Vidyadhara 19, 22, 23, 25, 30  
 Vidyadhara (Chandella ruler) 18  
 Vijaya 74, 75  
 Vijayabahu 35, 63, 79, 80, 81, 82, 85  
 Vijayaditya 48, 52, 54, 55, 57,  
 59, 60, 68, 69, 86  
 Vijayamaṅgalam 100  
 Vijaya Paṇḍya 118, 119  
 Vijayarāja Śīvaran temple 83  
 Vijayaśrī 31  
 Vijayavāda 44

- Vikkamabāhu 35  
 Vikkama Paṇḍu 34  
 Vikkirama Śālamēgha-t-terinda  
     Vēḷaikkārar, Śrī 83  
 Vikkirama Śīlamēgha Iśvara 84  
 Vikramabāhu 33, 35, 65, 82, 83,  
     84  
 Vikrama Chōḷa 3, 84, 85, 86, 87,  
     88, 90, 91, 92, 96, 97  
 Vikrama Chōḷa, Tribhuvana chak-  
     ravartin 90  
*Vikramaśōlan-ulā* 2, 68, 95  
 Vikramāditya 26, 41, 45, 49, 50,  
     55, 56, 57, 60, 61, 78  
 Vikramāditya VI 49, 69, 74, 77,  
     78, 90, 96, 97, 117, 119  
*Vikramāṅkadēva charita* 38, 49,  
     55  
 Vikrama Paṇḍya 33, 35, 107,  
     111, 111  
*Vikrama samvat* 42, 76, 114  
 Viḷiṇam 3, 33  
 Villavar (Chēra) 29  
 Vimaladitya 51, 52  
*viṇā* 85  
 Vindhya 82, 114  
 Vindhya-dēśa 24  
 Vindhya Mountain 81  
*Virabhadra* 65  
*virābhishēka* 106  
 Vira Chōḷa 68  
 Viradēva 83  
 Virakēraḷan, Paṇḍyan 106  
 Virakūrcha 11  
*Vīramushṭi* 65  
 Vira Paṇḍya 102, 104, 105, 106,  
     107, 108, 111  
 Vira Paṇḍya, Jaṭavarman 112  
 Vira Paṇḍya Alūpēndra 111  
 Virapāṇḍyapuram *alias* Elāga-ch-  
     chakravartti-p-perunderu 108  
 Vira-p-perumāl 84  
 Virarājēndra 28, 44, 48, 49, 50,  
     53, 55, 60, 61, 62, 68, 79, 110  
 Virarājēndradēva, Tbc. 109  
 Virāśālamēghan 33, 36  
 Virāśarman 9  
 Virāśōḷa maṇḍalam 87  
 Viratṭānēśvara temple 14  
 Viśalakshi 70  
*viśayas* 66  
 Viśṇubhaṭṭāraka 4  
 Viśṇu temple 65, 100  
 Viśṇuvardhana 76, 78, 89, 90,  
     97  
 Viśvēśvara (God) 70  
*Vratākhaṇḍa* 115  
*Vyākaraṇa* 5, 6, 7
- W**
- Waingāṅga (river) 46  
 Warangal 113, 114  
 Wardha (river) 46  
*Week days*  
     Tuesday 50  
     Thursday 51, 54  
     Friday 124  
     Saturday 119
- Y**
- Yamuṅḡ (river) 24  
 Yaśaḡ Kārṇadēva (Chēdi king of  
     Dāhala or Tripuri) 69  
 Yaśōdhavala 75  
*yātradhāna* 102  
 Yavanas 114

## POSTSCRIPT

Gāṅgēya, the Chēdi ruler of Tripurī, is said to have found salvation with his hundred queens at Prayāga in 1041 A.D., probably by immolating himself in the sacred river to put an end to his life. This was already referred to above (pp. 31-2) and it was also suggested that he might have been driven to follow that fatal course, not able to bear the crushing defeat inflicted on him by the combined action of Bhōja, the Paramāra ruler and of the Chōḷas. In a unique inscription<sup>1</sup> from Tiruvāliśvaram near Ambāsamudram in the Tirunelveli district furnishing the military history of a regiment which calls itself *Mūnrukāi-Mahāsēnai*, that regiment claims to have killed Gāṅgēya. "In this inscription the Mahāsēnai is said to have constantly worshipped Viṣṇu and Śiva, to have defeated the Kannara and pursued him, to have killed the Gāṅgēya, to have captured Kalmāḍam and destroyed Viḷiñam on the sea, to have crossed the sea on the other (eastern) side and raged Mātōṭṭam to the ground, to have taken the Hill country (*Malai-nāḍu*) and routed the fleet (*Kalamaruttu*) at Śālai, to have put to flight the Vallān (Chālukya) and captured Vana-vāsi and to have been praised in song for these achievements by the Tamil poets of Kāḷahasti."<sup>2</sup> The record is undated but there can be no doubt that it belongs to the period of Rājendra I and his sons. That the Chōḷas fought in the north with Gāṅgēya and brought about his death is thus corroborated by this record.

---

1. No. 120 of 1905.

2. *The Chōḷas*, vol. II, p. 226.



## A NOTE ON THE DATE OF RAMANUJA

It is nearly four decades since the late T. A. Gopinatha Rao discussed the date of the great Śrī Vaishṇava teacher Śrī Rāmānuja.<sup>1</sup> Since then, scholars have generally adopted the conclusions arrived at by him, even though there were materials tempting enough to revise and review the chronology.<sup>2</sup>

The traditional accounts<sup>3</sup> give Kali 4118 (expired), corresponding to Śaka 939 (expired) expressed by the Chronogram *dhīrṛlabdhā*, which was the cyclic year Piṅgaḷa, Chaitra, Śu. pañchamī, Thursday and Ārdra, as the date of birth of Śrī Rāmānuja. This would yield the equivalent date Thursday, the 4th April, 1017 A.D. on

---

1. *The History of Śrī Vaishṇavas* being the Sir Subrahmanya Ayyar Lectures of the Madras University delivered by T. A. Gopinatha Rao in 1917.

2. Prof. K. A. Nilakanta Sastri writes in his *The Chōḷas*: "The leading instance of religious intolerance in the period of Chōḷa rule is that of the persecution of Rāmānuja and his followers by a Chōḷa monarch whose identity is not altogether free from doubt. We have seen reason to believe that this persecution led to a popular revolt in which Adhirajēndra, the last ruler in the male line descending from Vijayalaya, lost his life." (vol. II, p. 487). *Krimikaṇṭha* (the putrid neck), the name by which this Chōḷa monarch is mentioned in the Vaishṇava hagiology, "is said to have uprooted and thrown into the sea the image of Gōvindarāja from the front of the Naṭarāja shrine at Chidambāram, and this act of sacrilege is placed by the *Divyasūricharita* at the very beginning of the Chōḷa persecution of Viṣṇuism, (xviii, 72). The same fact is recalled by the much later *Prapannāmritam* (quoted by Dr. S. K. Aiyangar in his *Ancient India*, p. 320). The poet Oṭṭakkūttan seems to attribute this deed to Kulōttunga II—*Kulōttungaśōḷan-ulā* ll. 76-8; *Rājārājaśōḷan-ulā* ll. 64-6 which is most explicit, and *Takkayāgapparaṇi* v. 777. But no one, on this account, seems to be prepared to identify the persecutor of Rāmānuja with Kulōttunga II. This king is, however, known to have extended the temple of Naṭarāja by putting up new structures and 'gilding' it, and it may be that the Tamil poet in describing this act of his attributes to him a deed of one of his predecessors." (vol. I, p. 355)

3. These have been collected by Gopinatha Rao and given in his book,

which day the *tithi* ended 9 *ghaṭikās* and 36 *vinādis* and the *nakshatra* ended 45 *ghaṭikās* after sunrise. He is said to have lived for 120 years and as such his death would have to be placed in Śāka 1059 or 1137-38 A.D., which date is again expressed by the Chronogram *dharmōnashṭah*.

To fit in with this scheme of traditional dates, Gopinatha Rao corrected the Śāka date given in a Tamil verse for the completion by Rāmānuja of his commentary *Śrī Bhāshyam* on the *Vedānta Sūtras* by thirty years and identified the contemporary Chōla king who is said to have persecuted this *āchārya* with Kulōttuṅga I, even though this king was not known to have been inimical towards the Vaishṇava faith.

But in the Sanskrit verse and the Tamil prose passage giving the date of birth of this *āchārya* published in this volume (Nos. 1292, 1293), this date is pushed forward by eight years: Kali 4126, Śāka 947 and the cyclic year Krōdhana. The other details, Śittirai, Śu. pañchamī, Thursday and Ārdrā are the same as those found in the traditional accounts. One additional detail is found here; it is said that it was 14th day of the solar month. It is not known how this date was obtained. But its inclusion in the collection would make it clear that the tradition is not uniform in giving the date of birth of this *āchārya*.

The details of the date given in this collection yield the 5th April, 1025 A.D. as its equivalent. The *tithi* ended 30 *ghaṭikās* and the *nakshatra* commenced 3 *ghaṭikās* and 36 *vinādis* after sunrise. But the week-day was Monday and not Thursday as stated in the record. Similarly, the other date, 4th April, 1017 A.D. as given by the tradition would have the 13th day of the solar month Śittirai and not the 14th as mentioned in this record.

So also, the date traditionally assigned for the birth of Ālavandār is Kali 4017, Dhātu, Ādi, Uttirādam (A.D. 917), while the date given in the Sanskrit verse published in this volume (Nos. 1296-7) is fifty years later: the Kali 4067, Śāka 888 and Akshaya (A.D. 966-7).

Again, according to the tradition, Gōvinda-bhaṭṭar, the cousin and the colleague of Rāmānuja and who was later on converted to Vaishṇavism and who became a *sannyāsin* under the name Embār, was born eight years later than Rāmānuja in Kali 4126, Krōdhana, Tai, Punarvasu. The *Rāmānujārya divya charitai* while giving the date of birth of Rāmānuja according to the tradition in the cyclic year Piṅgala mentions that Gōvinda was born in the same year, Tai, Paurṇami, Punarvasu. The record published in this volume gives the cyclic year Krōdhana which is the traditional year of birth of Gōvinda as the year for the birth of Rāmānuja.

It will be clear from the above that the tradition is not uniform in its dates. In fact, it appears to have taken a shape long after. As such, we should not rely entirely on the tradition in determining the age of this *āchārya*, but should also consider the other evidences.

The important event in the life of this *āchārya* was his flight from Śrīraṅgam to the Mysore country owing to the religious presecution of the then Chōḷa monarch. Who this king was has not yet been satisfactorily identified. It is generally taken that he was Kulōttuṅga I.<sup>1</sup> Tradition calls him *Kṛimi-kaṇṭha* and in one place he is named as Kulōttuṅga.<sup>2</sup> Two events are mentioned to prove that the reigning monarch was inimical to the Vaishṇava faith and its followers: one is the destruction of the Viṣṇu temple at Chitrakūṭam, i.e., Chidambaram by throwing the image of Gōvindarāja enshrined there into the sea. The other is the compulsion exercised by the Chōḷa ruler over Rāmānuja to sign a declaration that 'Lord Siva is Supreme' (*Śivāt parataram nāsti*: literally meaning 'there is no [god] above Śiva').

---

1. Other identifications also are occasionally made. "It is just possible to identify the Chōḷa who died as Krimikaṇṭha in consequence of the persecution to which he subjected Ramanuja and his followers with either Adhirājendra, or possibly with Virarājendra with whom the direct Chōḷa line practically comes to a close." (*The Chōḷas*, vol. I, p.345)

2. It is considered that "it is possible that 'Kulottunga' is used in late works as a generic name for Chōḷa." (*Ibid.*, p. 355, n)

The story of the religious persecution which necessitated his flight goes on to say that when the royal messengers arrived at Śrīraṅgam to fetch Rāmānuja to the court at Gaṅgaikoṇḍa-śōlapuram, Periyānambi, the preceptor of Rāmānuja donned the yellow robe of the *sannyāsin* and followed the royal messengers personating the *āchārya*, together with Kūrattālvān. This gave the breathing space of time for Rāmānuja to escape and he left the Chōḷa country for the Hoysaḷa kingdom in which he arrived after many privations on the way. Periyānambi who went to the Chōḷa court in his stead with Kūrattālvān did not sign the declaration. On the other hand it is said that the declaration was subscribed with the expression *drōṇam-asti tataḥ param* (literally: there is *drōṇa* above that, i.e., *Siva*) thus playing upon the words *Śiva* and *drōṇa* meaning different measures. This action was considered as impertinent and contemptuous and the eyes of Periyānambi as well as those of Kūrattālvān were put out. The former, being old and not able to bear the effects of the blinding, died on his way home. This event is stated to have taken place in the cyclic year Kālayukti.

Kūrattālvān is said to have stayed in the house of a servant-maid of the palace on the out-skirts of the city till the wound was healed and then reached Śrīraṅgam. Rāmānuja had already left the place and Kūrattālvān could not obtain quarters there. So he left Śrīraṅgam and went to Tirumāliruṇjōlai where he is said to have resided for eleven years until he met the *āchārya* after his return from the Mysore country.

The cyclic year Kālayukti in which Periyānambi breathed his last is generally taken as the one corresponding to 1078-79 A.D. in the reign of Kulōttuṅga I. Since his death occurred shortly after his visit to the Chōḷa capital, the persecution of Rāmānuja by the Chōḷa king and his flight to the Hoysaḷa country are considered to have taken place in that year.

Rāmānuja is said to have stayed in the Hoysaḷa country for a period of twelve years at the end of which period, on hearing the demise of the Chōḷa king who persecuted him, i.e., Kulōttuṅga,

he returned to Śrīraṅgam when his reunion with his pupil Kūrat-tālvān took place. It is also stated that during his sojourn in the Hoysala territory, the *āchārya* converted its Jaina king Biṭṭidēva or Biṭṭiga-dēva to Vaishṇavism and re-named him Viṣṇu-vardhanadēva.

If the return of Rāmānuja from the Mysore country to Śrīraṅgam is to be placed after the death of the Chōla king who persecuted him, i.e., Kulōttuṅga I according to the above scheme, then it should have taken place sometime after 1120 A.D. as we know that Kulōttuṅga I who came to the throne in 1070 A.D. had ruled for fifty years. This would give a long stay of more than forty years to Rāmānuja in the Mysore Country. But the period was only twelve years according to the tradition.

According to the tradition, Biṭṭigadēva, the Hoysala king, was originally a Jaina and assumed the name of Viṣṇu-vardhana after his conversion to Vaishṇavism by this *āchārya*. But in the inscriptions, we find him referred to by the name of Viṣṇuvardhana from the very commencement and throughout the period of his reign. Further, Biṭṭiga or Biṭṭi is only another form, through Prākṛit, of Viṣṇu.

The *Rāmānujārya-divya-charitai* by Piḷlai Lōkam-Jiyar, dealing with the life of Rāmānuja in Tamil, gives some quotations from another work. These verses in Tamil appear to have been taken from a more ancient work of good historic value. But it has not been possible to trace either the name of the work or the name of its author. Three of the verses thus found quoted contain dates which are highly valuable in determining the date of Rāmānuja.

This *āchārya* is said to have begun his famous *Śrī Bhāṣyam* more than once and he had only advanced about two-thirds of its length, when he was obliged to flee the Chōla country. The remaining one-third was completed by him after his return to Śrīraṅgam and his re-union with his disciple Kūrat-tālvān from his

self-imposed exile to Tirumāliṛuñjōlai. One of the verses<sup>1</sup> quoted in the *Rāmānujārya-divya charita* mentions that the *Śrī Bhāshyam* was completed in Śaka 1077 or 1155-6 A.D. This date would be too late for the date of his death which according to the tradition is said to have taken place in Śaka 1059 or A.D. 1137-8. So the date of completion of the *Śrī Bhāshya* was taken by Gopinatha Rao as Śaka 1047, which would correspond to 1125-26 A.D., to suit the traditional dates of the *āchārya*.

But it is to be noted that the date given in the Tamil verse is perhaps the earliest mention of a date for an incident in the life of this *āchārya* and that it is in conformity with two other dates mentioned in two of the Tamil verses quoted in the same work.

The return of Rāmānuja to Śrīraṅgam from the Hoysaḷa dominion is described in another verse.<sup>2</sup> It states that he left Śrīraṅgam in Śaka 1059, and returned to Śrīraṅgam after staying in the place of his temporary sojourn for eleven years. The period of his stay in the Hoysaḷa kingdom is, according to tradition, twelve years and not eleven years as stated in the verse.

1. innavāru tiruppatigal  
eṅum valvit-t-Etirajan  
taṇṇatakki-t tariṣanamum  
daraṇi-y-eṅum viḷaṅguvittu  
muṇṇam uraitta *Bāḍiyattin*  
murra-mūṇrat-t-oru kūru  
taṇṇai-ch-chenraṇḍ āyirat tāṅg  
elupattēlil sāttiṇaṇ.  
—*Rāmānujārya divya charitai*, p. 243

2. āynda-Śakābdam āyirattaimpat  
t-onpadi-ṇiṅgi niṇṇum  
pōndu paṇiṇṇōr-aṇḍ-iṇṇan  
pugaḷadāṇ vaḷarnda Perumbudūr  
vēndan eṇṇilā-v-anbar-  
uḍan Araṅga nagar-eydi-p-  
pāndaḷ-aṇai-t-tuyil Paraman  
paḍam paṇind-aṅg-uraindiḍu naḷ

Evidently both are correct. The period of his actual stay there was eleven years,<sup>1</sup> while the other year represented the time spent in his journey in both the directions.

This interpretation is in a way corroborated by another verse<sup>2</sup> quoted in the same book. It states that when Kūrattālvān was refused admission to the Śrīraṅgam temple, he went to Tirumālirunṅṭṭalai and stayed there for eleven years before he re-joined his preceptor Rāmānuja. It is said that after his eyes were put out in the capital city of the Chōḷa kingdom he lived in the house of a servant-maid of the palace on the outskirts of the capital for some time till the wound was healed and then only he set out for Śrīraṅgam. It is quite possible that he might have taken one year to reach Tirumālirunṅṭṭalai after he was blinded at Gaṅgaikoṇḍaśōḷapuram.

According to the verse cited above the flight of Rāmānuja from the Chōḷa country took place in Śaka 1059, which if taken as expired would correspond to A.D. 1137-8. Then the cyclic year Kāḷa-

---

1. Gopinatha Rao quoting this verse in his work writes (*op. cit.* p. 40) that "He (*sic.* Rāmānuja) returned to Śrīraṅgam eleven years before his death, according to a stanza of the *Rāmānujārya divya charitam*". This interpretation of his is not supported by the text of the verse. The context also is against such a supposition. Evidently Gopinatha Rao was led to adopt this interpretation, as Śaka 1059 in which according to this verse Rāmānuja is said to have fled the Chōḷa country, happened according to the tradition of the Vaishṇava hagiologists, in the year of his death.

2.   aṅṟ-aṅṟ-irundavaruḷ Kūrat-  
           tālvān-Araṅga naḡar-aḍaiya  
   aṅṟ-Etirāṣaṇ-aḍiyar  
           tammai vāśal viḍādiruppa-ch  
   cheṇṟu Tirumālirunṅṭṭalai-ch  
           chelvar tammai-t-tōttiram śeyd-  
   oṇṟi-y-Aḷagar tam padiyil  
           paḍinōr-aṇḍ-uraindadar pin

—*Ibid.*, p229

yukti in which Periyānambi died, due to the effects of the blinding inflicted, would be the one which coincided with the Śaka 1060 or A. D. 1138-9. The account does not mention that Periyānambi died immediately on his being blinded, but that he lingered on for some time thereafter and that he died only on his way back. Further, the *āchārya* is said to have fled from Śrīraṅgam immediately following the departure of Periyānambi and Kūrattālvān for the capital with the royal messengers. It might have taken some time for these two to have reached the capital, met the inquisitors and lost their eyes. It is therefore possible to take that the flight of Rāmānuja took place towards the close of the Śaka year 1059 and that the death of Periyānambi took place early next year in Śaka 1060. Then these events should have happened in 1138 A.D.

Rāmānuja is said to have returned to Śrīraṅgam after an absence of eleven or twelve years on hearing the death of the Chōḷa monarch who persecuted him. Then his return should have taken place in 1150 A.D. and a Chōḷa king should have died about that time.

Kulōttuṅga II was then the contemporary Chōḷa monarch. He ascended the throne some time in May-July, 1133 A.D.<sup>1</sup> and ruled for over sixteen years. The latest regnal year found in his inscriptions is seventeen<sup>2</sup>. From his inscriptions in the Telugu country quoting both his regnal years and the Śaka dates, it is seen that his sixteenth regnal year corresponded to Śaka 1070-71.<sup>3</sup> We may therefore safely take that his reign came to a close in A.D. 1150.

It is also known that Kulōttuṅga II was a fanatic Śaiva. This will be evident from the fact that he 'removed the little God (Vishṇu) from the courtyard of the Sacred Hall of Tillai' and 'threw it into the sea, his abode.' This event is mentioned clearly

1. *Ep. Ind.*, vol. X, p. 135; vol. XI, p. 287.

2. No. 6 of 1908.

3. *S. I. I. (Texts)*, vol. IV, No. 1044; vol. VI, No. 13



by his court poet Oṭṭakkūttar in the *Kulōttuṅga-śōlan-ulā*,<sup>1</sup> the *Rājarāja-śōlan-ulā*<sup>2</sup> and the *Takkayāgapparaṇi*.<sup>3</sup> The commentary on the *Takkayāgapparaṇi* definitely ascribes this to Kulōttuṅga II. The same incident is also found mentioned in an inscription of his from Ādutturai in the Tañjāvūr district dated in his 14th regnal year.<sup>4</sup> We thus find that both the literature and the epigraphy are unanimous in ascribing this event to Kulōttuṅga II.<sup>5</sup>

The Vaishṇava tradition also mentions Kulōttuṅga as the Chōḷa monarch who committed this sacrilege. The *Rāmānujārya divya charitai* quotes in this connection an incomplete verse which clearly refers to Senni Kulōttuṅga as the author of it.<sup>6</sup> It will

1. 'Tillai-t-tirumaṇṇin muṇṇir chirudeyva-t  
tollai-k kuṛumbu tolaitteḍuttu'  
—*Kulōttuṅgaśōlan ulā*, kaṇṇi, 49

2. 'poṇṇir kuyirri-p puṛambir kuṛumb-aruttu  
muṇṇar-k kaḍal-agaḷin mūḷguvitta—Senni'  
—*Rājarājaśōlan-ulā*; kaṇṇi, 33

3. 'muṇṇir-k-kiḍanta karuṅkaḍal pōy  
muṇṇai-k-kaḍal puga-p piṇṇai-t-Tillai  
maṇṇir-k-iḍaṅkaṇḍa *Koṇḍan*-maindan  
marakata mēruvai vaḷttiṇavē'  
—*Takkayāgapparaṇi*, v. 777

4. No. 363 of 1907. The inscription appears to open with a reference to this fact; but this part of the record seems to have been wantonly damaged as the rest of it is in excellent state of preservation:

5. It cannot therefore be said that the Tamil poet while describing the extension of the Naṭarāja temple by Kulōttuṅga II 'attributes to him a deed of one of his predecessors.' Further, the poet is known to have lived in the courts of three successive Chōḷa kings, Vikrama Chōḷa, Kulōttuṅga II and Rājarāja II and to have composed an *ulā* on each of them. But he attributes this deed among them only to Kulōttuṅga II and not to any other.

6. "ampor kuḍai-c-Chakaṇ-āyira-t-t-  
onpadām varushattu-t-tenpāl  
Senni Kulōttuṅgan Chittirakūṭa-ch-  
cheṅgaṇmal-tannai alai-y-eṇi naḷ-taṇ."

—*Rāmānujārya divya charitai*, p. 226.

thus be seen that one of the two incidents narrated by the hagiologists to show that the Chōla monarch who was a contemporary of Rāmānuja was inimical to the Vaishṇava faith took place in the reign of Kulōttuṅga II.

This conclusion receives support from another incident mentioned by the tradition in connection with the same event. On hearing of the destruction of the shrine of Gōvindarāja at Chidambaram, Rāmānuja is said to have decided to enshrine the image in a temple at Tirupati to which place it had been carried by its votaries and kept in the house of a house-holder thus remaining homeless. He accordingly had the temple constructed and the image consecrated. In this, he is said to have been helped by Ghaṭṭidēva Yādavarāya, the local ruler, who had become a convert to the Vaishṇava religion by this *āchārya*.

Ghaṭṭidēva with whose help Rāmānuja was able to carry on his work at Tirupati was a member of the Yādavarāya family which was holding sway over the area round Tirupati and Kālahastī in those days. A certain Ghaṭṭidēva *alias* Kulōttuṅga-Yādavarāya figures in an inscription<sup>1</sup> from Kālahastī dated in the sixth regnal year of Kulōttuṅga II as the donor of the village Viramaṅgalam for the daily feeding of Brāhmaṇas, *tapasvins* and others in the temple. It is quite possible that this Ghaṭṭidēva was the same chief who helped Rāmānuja in enshrining the image.

Tradition states this as the last event of the active works of this *āchārya* in the cause of the Vaishṇava faith, as he had become

---

The Śaka date according to this verse is Śaka 1009 for the removal of the Viṣṇu image from Chitrakūṭam to the sea. This would fall in A.D. 1087-8, early in the reign of Kulōttuṅga I. But we have seen above that the incident took place in the reign of Kulōttuṅga II. The Śaka date should therefore be some year between Śaka 1055, the date of his accession and Śaka 1068 or his 14th regnal year as an inscription of his from Āḍuturai bearing this date mentions the event. Evidently it was Śaka 1059 (*āyirattaimpattonpadu*). The verse is incomplete and only a portion of it is found. It is not possible to get at the correct and complete text of the verse.

1. No. 83 of 1922.

very old by that time. Possibly it took place after the death of Kuḷōttuṅga II and return of the *āchārya* from Mysore to the Chōḷa country.

The story of the Vaishṇava hagiologists about the religious persecution by the Chōḷa monarch compelling the followers of the Vaishṇava faith to sign a declaration acknowledging the supremacy of Śiva is not mentioned anywhere else. So it is possible to doubt even the veracity of the story taking it as the outcome of the fertile imagination of the religious fanatics. But curiously enough an echo of it is found in a verse in the *Tiruttoṇḍar-purāṇam*<sup>1</sup>, otherwise known as the *Periyapurāṇam*, written by Śēkkiḷār. It occurs in the *Tirujñānasambandha-śvāmigal-purāṇam* comprised in it, while describing the third and the final round of the contest between Sambandha and the Jainas at Madurai in the presence of the Pāṇḍya king.

The story is that Sambandha and the Jainas should both write the truths of their respective religions on palm-leaves and place those leaves in the river Vaigai. That which was not carried along with the current but goes up the stream should be considered as having won the contest.

Tradition has it that Sambandha wrote the *padikam* commencing with the words *vāḷga-v-antaṇar*. The palm-leaf written with this hymn went against the current up the river Vaigai forcing its way while the palm-leaf similarly placed in the river by the Jainas containing the words *atti-nātti* (*asti-nāsti*) being the main tenet of their scriptures and religion went down along with the current. The contest was won by the Śaivas.

- 
1. *Embirāṇ Śivanē ellā-p-  
poruḷum enr-eludum eṭṭil  
tambirāṇ aruḷal vēndaṇ  
tannai mun-ōṅga-p-paḍa  
ambuya malarāl māṇpan  
Anapāyan enṇuṇi śirtti-ch  
Chembiyaṇ seṅgōl enṇa-t-  
Tēṇṇaṇ kūṇ nimirntad-anrē*

—*Tirujñānasambandhar-purāṇam*, v. 847

The verse states that, "when it was sung that the king should prosper (and engrossed) on the palm-leaf written (with the words) that 'Lord Siva is Supreme' [lit. all things are (manifestations of) Lord Siva], the hunch on the back of the Pāṇḍya became straight as the sceptre of *Anapāya*, i.e., the Chōla king." The expression that 'the king should prosper,' actually occurs in the first verse of the *padikam*; but the expression *Embirān Śivanē ellā-p-porulum* is not found in the hymn. The use of this expression not found in the *padikam*, but which conveys the essence of the Śaiva faith, would require an explanation.

The *pāyiram* of the work *Periyapurāṇam* mentions that it was written in the days of the Chōla monarch Anapāya who covered the Pērambalam with fine gold. The *Śekkiḷār-nāyanār-purāṇam* of Umāpati Śivāchārya dealing with the life of this author mentions that the author was born in the family known as *Śekkiḷār* at Kunṛattūr and was named Aruṇmolī-t-tēvar. He served the Chōla monarch as a minister with the title Uttamaśōla-p-Pallavarāyan and had a younger brother Pāraṇvāyar. It seems most probable that the officer mentioned under the name *Śekkiḷār Pāraṇvāyar* Kaḷappālarāyar of Kunṛattūr in an early inscription of the reign of Kulōttuṅga II is the brother of the author of the *Periyapurāṇam*.

It will thus be seen that the author of the *Periyapurāṇam* was a high official in the court of Kulōttuṅga II and he would have had intimate knowledge of the activities of his monarch in the cause of the Śaiva religion. It is just possible that *Śekkiḷār* had in his mind the campaign that was going on the Chōla dominion requiring the followers of faiths other than Śaivism and more especially the followers of the Vaishṇava faith to sign a declaration that "Lord Siva is Supreme" when writing this portion of the *purāṇam*. Otherwise, the use of the expression *Embirān Śivanē ellā-p-porulum* which is not found in the *padikam* in the context cannot be explained.

The closing years of Rāmānuja appear to have passed without much trouble. The Vaishṇava accounts say that the new

Chōla king was his patron. The *āchārya* nominated Parāśara-bhaṭṭa, son of Kūrattālvān as his successor. From the *Guruparam-parai* of Pinpalagiya-perumāl Jiyar, familiarly known as *Arāyirap-paḍi* it is learnt that Bhaṭṭar's contemporary on the Chōla throne was Tribhuvanaviradēvarāya. We know that Tribhuvanavira was the title of Kulōttuṅga III, many of whose inscriptions name him as such. His period of reign lasted for forty years from 1178 A.D. to 1217 A.D.

There is a belief among the Śrīvaishnavas that Bhaṭṭar died very early. Relying on this, Aṇṇā-appaṅgār in his *Paḷanadai-vilakkam* says that he died in his twenty-eighth year.<sup>1</sup> Whatever might have been the correctness of this statement, it can be taken that the duration of the occupation of Bhaṭṭar of the pontifical seat was very short.

Bhaṭṭa was succeeded on the pontifical seat by Nañjiyar who in turn was succeeded by Nambūr Varadarājar, under the name of Nambillai, who later on received the title *Lōkāchārya*. According to the *Kōyilolugu* this Nambillai was alive about Śaka 1175 (A.D. 1253) when the Pāṇḍya monarch Jaṭāvarman Sundara Pāṇḍya is said to have covered the central shrine of Śrīraṅgam with gold.

It may also be noted that Dr. S. Krishnasvami Aiyangar also adopts a more or less similar scheme of chronology. He identifies the Chōla monarch who removed the image of Gōvindarāja enshrined at Chidambaram and threw it into sea with Kolōttuṅga II. And he writes: "If in A. D. 1119, he (Rāmānuja) was 102 he must have lived on 18 years longer which would mean that he passed away some time about the year A.D. 1139 which, having regard to the precise dating of the accession of Kulōttuṅga II, would make it much too early. But if we take in the 15 or 16 years of discrepancy by way of antedating that we have noted already, it would mean that he actually passed away in A.D. 1155, and this date, it is just possible may be correct."<sup>2</sup>

---

1. Gopinatha Rao, *op. cit.*, p. 40.

2. S. K. Aiyangar, *History of Tirupati*, vol. I, p. 287.

Scholars who have studied the question previously have taken the *Divyasāri charitam* and the *Yatirāja-vaibhavam* as the earliest biographies of this great teacher and also that the former was a contemporary composition when the *āchārya* was still living. But subsequent studies<sup>1</sup> have shown that these were later compositions.

From the foregoing discussion, it will be seen that the Tamil verses quoted in the *Rāmānujārya divya charitai* are perhaps the earliest of the available materials and give the correct dates for the events which happened in the life of this *āchārya* pointing to the following conclusions :

(1) Kulōttuṅga II was the Chōla monarch who was the contemporary of Rāmānuja and who persecuted him and the followers of the Vaishṇava faith;

(2) the flight of Rāmānuja from the Chōla dominion to the Hoysala country took place in 1138 A.D.;

(3) he returned to Śrīraṅgam after twelve years on hearing the death of the Chōla who persecuted him in 1150 A.D.; and

(4) the *Srī Bhāshyam* was completed only in Śaka 1077 or 1155-56 A.D. after his return from Mysore.

---

1. *Journal of Indian History*, vol. XIII, part II for a discussion on the *Divyasūricharitam* and the *Indian Antiquary*, vol. XL, p. 152 for the other.

# SOUTH INDIAN EPIGRAPHY

## I. INSCRIPTIONS.

India, the *Bharata Varsha* of the Purāṇas, is sometimes referred to as the 'Holy land' (*puṇya-bhūmi*). No wonder, the country is rich in temples, more in the South than the North which was much subjected to religious persecution and vandalism during certain periods of its history.

There is a saying in Tamil that one should not reside in a village having no temple. So we see in every village in Tamil-nāḍu a Śiva or a Viṣṇu temple or at least a shrine for Gaṇēśa or a village goddess. South India rightly deserves the appellation of the 'Land of Temples' given to it.

Many of the bigger temples in Tamil-nāḍu were constructed either by the kings or under their patronage. Munificent gifts were made by them to these temples for the performance of regular worship and various special services and also for the celebration of festivals on important and specific occasions. With the idea that these gifts should be enjoyed by them perpetually without any hindrance even by future kings or dynasties, they were incised on stones kept in prominent places.

Originally these temples were built of brick and mortar and these inscribed stones were kept either fixed in the walls or planted in the enclosures. Later on when the temples came to be constructed of stone these records were incised on their walls instead of on loose stones. When temples were renovated or reconstructed, copies of the epigraphs on their walls were taken before dismantling the structure and re-engraved on the walls after renovation.

Besides the temple walls inscriptions are found incised on their pillars, beams and eaves, pedestals of images and sometimes even on their backs as also the pillars of victory planted in villages, on rocks and boulders. These records on stone are variously called as *śilā-lēkhai*; *śilā-śāsanam*, *kal-veṭṭu*, *kal-eḷuttu* and the like; but they are generally known as *śāsanam* and sometimes even as *prāśastis*.

A few of the records on stone, instead of being donative in nature are merely votive. Mostly they register the visits of pilgrims to places of religious importance. Occasionally we also find votive tablets

and votive figures. There are also descriptive labels incised as accompaniments to statues and sculptures.

Just as we have inscriptions on stone, there are records incised on copper-plates. Many of them are found in the possession of some old families. Sometimes they are recovered from underground buried in small vaults or in the basement of buildings. These are known as *tāmra-śāsanam*, *tāmra-paṭṭayam*, *śeṭṭu-p-paṭṭayam*, *seṭṭeḍu* or merely *paṭṭayam*.

Where the grant contains more than one leaf or plate they are strung together with a ring passing through holes made in the middle of the plates on one side, generally left. The ends of the ring are soldered having the seal of the king with the royal emblems.

In addition to copper we have inscribed plates of other metals like gold, silver, brass, tin, etc. Similarly inscriptions are also found not only on stone but also on mud vessels, bricks, burnt clay, terracotta, etc. There are also a few inscriptions not engraved, but written in ink.

There are writings on coins of gold, silver and other metals and these are termed 'legends' to avoid confusion. They are of a special class and come under the category of Numismatics and as such they are not included in this study.

The word *śāsanam* in Sanskrit means an order or command. As the majority of the inscriptions whether on stone or copper contains the order of the king granting land or other privileges to the temples and others, the word came in course of time to denote such documents and ultimately any sale-deed.

Not all the inscriptions contain grants by the kings to temples. There are records registering gifts by ministers, generals and other officers of the king as also by pious private individuals to the temples as well as to learned brāhmaṇas and other institutions. We have also some epigraphs registering private transactions or exchange of properties. Some others record deeds of public utility like the construction of tanks, etc. There are also inscriptions containing literary pieces as well as plain statements of facts of a historical nature.

The documents registering the gifts made by the kings or other donors are found to have been drawn up according to the rules contained in the *Dharma-Śāstras*; but there are differences between the records on stone and on copper-plates. The records on stone



are generally in the local languages and in prose. Occasionally they are in Sanskrit and very rarely in other foreign languages where the donors were important persons of the foreign realm. But the copper-plate grants are mostly in Sanskrit verse; sometimes the grant portion like the description of the boundaries of the gift village is in the local language.

Inscriptions on stone in many cases begin with the *meṃkkīrtti* of the king after the usual auspicious symbol or expression, narrate the particular gift made in the particular regnal year of the king and end with the signatures of the officers responsible for drafting the deed and the usual imprecation. The copper-plate grant on the other hand contains, after the introductory auspicious symbol and invocation, detailed information about the ancestry and genealogy of the king and also of the donor where he happens to be some other person. It then narrates how on the petition of a particular person at such and such a time, the king ordered the gift of the grant with the official or dignitary named therein as the executor. After the mention of the registry of the orders in the various registers of the state, under the signatures of the heads of the several departments the document will close with the imprecatory verses. Sometimes the name of the person who drafted the deed as well as of the scribe who incised the grant and occasionally the royal sign-manual are also found.

Earlier inscriptions are generally short. With the passing of time conventions came to be established and the documents grew in length. This change is perceptible in the records on both stone and copper.

To understand the importance of the inscriptions it is necessary to know how they came to be written.

The kings of old used to bestow gifts on auspicious occasions like the solar and lunar eclipses, their birthdays and the days having their natal stars and the like. They seem to have followed the dictum of the *Dānakāṇḍas* of the *Dharmaśāstras* that *dāna*, gift, being more meritorious is to be preferred to *yāga*, sacrifice. In fact we find several of the *dānas* prescribed in those books mentioned in these records as having been made by them. The performance of the *tulābhāra*, the *hiranyagarbha* and the like is also frequently mentioned.

There are many inscriptions in Tamil registering grants made by kings or others which do not fall in the category of the *dānas* above mentioned. They mention that the king issued oral orders making the

grant on representations made to him by some responsible officials. Sometimes the time and place where the king heard the petition are also noted. The officer, *tiruvāy-k-kēlvi*, in immediate attendance of the king received the orders, reduced them to writing and transmitted the same to the concerned authorities for necessary action. Then the necessary orders were drawn up for transmission to administrative authorities, after entry in the various registers under the signatures of the several officers in charge of the respective departments, also naming the officer entrusted with the duty of executing the orders. Such orders are generally addressed to the local assembly, *sabhā* of the village where the gift-property was situated and the grantee resided; on receipt of which, the *sabhā* finalises the process by putting the grantee in possession of the property and giving him the written document on the strength of which he could enjoy the same. Such deeds are given in the first instance on palm-leaf, *ōlai*, which being of perishable nature, they are then recorded in some public places, usually the walls of temple, to make them public and also to preserve them for posterity. Simultaneously the donee is also given a copy of the deed inscribed on copper-plate. Sometimes the copper-plate grant is called *triphalī-tāmrāśāsana*, 'a triplicate copper charter', probably it being the third copy:

These inscriptions thus being mainly in the nature of the 'record of rights' to a property or privilege to be enjoyed, it is possible sometimes to forge such documents by persons not entitled to such enjoyment, in support of their claim for the same. Such spurious grants are mostly found in the copper-plate charters and not in stone records. Spurious grants can easily be detected; but even they are valuable sometimes historically.

J. F. Fleet defines<sup>1</sup> the inscriptions in the study of epigraphy, as "notifications, very frequently of an official character, and generally more or less of a public nature, which recite facts, simple or complex, with or without date, and were intended to be lasting records of the matters to which they refer."

It will thus be seen that they do not intend to give us the history of our past. Still they are our main sources for reconstructing the history of the land.

The records when narrating the donation given also mention the dates when the gifts mentioned therein were made. These dates give

---

1. *The Imperial Gazetteer of India, The Indian Empire*, vol.II, p. 1.

the regnal years of the kings, sometimes coupled with the year of an era like the Śaka, Kollam, etc. They also contain occasionally astronomical details in addition giving the month, day, *tilhi*, the asterism and other particulars like an eclipse. These help us to fix the dates of the grants precisely and thus the duration of the reign of those kings. The *meṃkkīrtti* or the *praśasti* of the kings narrate the victories and other glorious deeds of those monarchs. The presence of an inscription mentioning the reign of a king at a place will also show that the place was then under the control and rule of that particular king.

Incidentally these inscriptions throw light upon the administration and the machinery set up for the same, the economic condition of the people, the nature of taxation, the several components of the society and the social life, the commerce and conditions of the mercantile community, in fact every aspect of the life and conditions of the society in those days. These inscriptions being written in the local languages, in prose as also in verse, are also the guiding materials for a study of the language and literature and their growth.

These studies will be fruitful only if the texts of all the inscriptions relating to the dynasty, period, or region are examined in detail chronologically and their results collated. During the last three-quarters of a century, more than twenty thousand inscriptions have been copied from the Tamil districts alone. And fresh inscriptions are being copied every year. Of these only about four thousands have been published. The bulk of the records copied from the year 1904 onwards still remains unpublished. And this collection covers only about half the area of the Tamil districts. The other half still remains to be surveyed.

## 2. ANCIENT HISTORICAL LITERATURE.

It has been stated above that inscriptions are the main sources for reconstructing the ancient history of our land. They are at present used mostly in shaping the political history of the past, even though they are useful in every other line of research. But these are not the only sources. There are the traditions, literature, coins, art, architecture, remarks left by foreigners and the like serving as sources for our history. Still we are dependent more on epigraphy as it regulates everything we learn from other sources.

It is generally said that the Indians have not bequeathed any historical work which can be accepted as reliable for the early times. This complaint is not of recent origin and seems to be as old as the eleventh century A.D., if not earlier. Al Bērūnī, the famous Arabian traveller writes that, 'the Hindus do not pay much attention to the historical order of things, they are very careless in relating the chronological succession of their kings and when they are pressed for information and are at a loss, not knowing what to say, they invariably take to tale telling.'<sup>1</sup>

The same sentiment is expressed even today not only by foreign scholars, but also by the scholars of our own country.

It is true that our ancestors had not left us chronicles of our past history in the manner in which we desire them. But it is not correct to say that they never possessed true historical sense or that they had no faculty of putting together genuine history on broad and critical lines. It is not also correct to say that they had not left us any history of the past. They had left us works on our past history. But their outlook on human life was quite different from that of ours and as such the works written by them with their outlook do not conform to our standards.

The values for the several aspects of human life and the outlook on the various problems confronting humanity vary from time to time and from place to place. What is considered necessary at one place at a given time may not be so at a different place at the same time or even at the same place at a different time.

Our forefathers considered *bhakti* and the moral side of social life as also literary workmanship as of primary importance and bestowed more attention on those aspects. It may be even said that all their compositions were shaped with this bias. They did not consider the production of pure histories as quite essential.

Yet, they have bequeathed us some histories written in their own way. The *Purāṇas* are such compositions. They purport to give us the history of our land from the days of creation. The texts of several of them, as we now have, contain admittedly later interpolations with many omissions and commissions. The history of the several earlier dynasties mentioned therein as having ruled over

---

1. Sachau's translation of Al Bērūnī's *India*, vol. II, p. 10.

different parts of the land are not now taken serious notice of. They are relegated aside as fictitious.

But the *Bhavishyat* portion of these *Purāṇas* which is supposed to predict as to how the earth will be ruled in the future and couched in the future tense are considered as authentic. This portion is the same in all the *Purāṇas* and any differences found therein are only textual variations. This has been collated and critically edited by F. E. Pargiter as *The Purāṇa Text of the Dynasties of the Kali Age*. It gives the history from the fourth century B. C. to the fourth century A. D. and furnishes the details and the successive list of kings of the dynasties like the Mauryas, the Śuṅgas, the Kaṇvas and the Āndhras or the Śatavāhanas. It will thus be seen that the history given by them is not for the whole of India, but only for a portion of it, *viz.*, the Magadha country and the surrounding parts, probably considering that only the rulers of Magadha wielded the imperial powers and that others were subordinate to them.

The information contained in this portion of the *Purāṇas* is really historical and not only is it corroborated by the epigraphical and numismatic evidences obtained, but it also serves as the guiding factor in fixing up the values of the evidences available and framing the chronology and filling up the gaps.

But there is one defect in the narration. The history of the dynasties are given in the order in which they rose to imperial power and while doing so, each dynasty is described in detail from its inception. For example, the Śuṅga dynasty was established in the early years of the second century B.C. and ruled for a hundred and twelve years when it was succeeded by the Kaṇva dynasty which held sway for forty-five years. The last Kaṇva ruler was killed by an Āndhra prince about 27 B.C. and his kingdom annexed. But the Āndhra dynasty had been established some two centuries earlier and had acquired a wide dominion in the Dakhan and it was then one of the most powerful states. The *Purāṇas* give the history of the Āndhra family after that of the Kaṇvas; and they begin with its first king thus making it appear that it was established only about 27 B.C., while actually it captured Magadha and attained imperial power and prestige just then. With this correction, the other details contained in that portion are quite correct.

A similar history covering a period of nearly one thousand and five hundred years from *circa* 700 B.C. to 770 A.D. is contained

in the Buddhist work *Mañju Śrī Mūlakalpa*. The Sanskrit text of this portion, corrected with the aid of its Tibetan version, has been critically edited and its historical contents discussed by K. P. Jayswal in his work *An Imperial History of India*.

The *Rājatarāṅgiṇī*, written in Sanskrit by Kalhaṇa in 1148-49 A.D. gives the history of Kashmīr up to that time. That there were similar previous works then will be evident from the fact that Kalhaṇa himself refers to the previous authors who wrote such works by name; Kshēmendra the author of *Nripāvalī*, Hēlarāja who composed the *Pārthivāvalī* in twelve-thousand verses, Nilamuni, who wrote the *Nilamata-Purāṇa*, Suvrata, Padmamihira and others. He also says that in his work he sought to remove the errors found in them by consulting inscriptions and manuscripts. He was the son of a high official in the government of Kashmīr then, and as such would have had ample facilities to consult official records and other materials to arrive at correct conclusions on various problems which confronted him.

But still it has its own defects and is not fully reliable. It is true that it gives a fairly correct account of the country and its government during his days and for some considerable time preceding him, say for about four or five centuries. But beyond that, the chronology is certainly defective, though in other respects, the work is not so.

There are similar compilations in the south also. In the early years of the last century, Col. Mackenzie collected a large mass of materials containing copies of inscriptions on stone and copper, local histories, *kaṣṭhāyats*, *sthala-māhātmyas*, *purāṇas* and the like with a view to compile a comprehensive history of the land. It contains manuscripts like the *Koṅgudēśa Rājāṅkaḥ charitram* (History of the kings of the Koṅga country), *Karnāṭaka Dēśa Rājāṅkaḥ Savistāra charitram* (Detailed history of the kings of the Karnāṭaka country), *Taṅjāvūri Āndhra Rājula charitram*, (History of the Āndhra kings of Taṅjāvūr), *Madurai-t-tala-varalāru* (History of the city of Madurai) and so forth.

Col. Mackenzie was not spared to deal with them critically. But they were examined and catalogued by scholars, like William Taylor and H. H. Wilson in the last century. The former scholar summarised many of these chronicles in his two volumes of the *Oriental Historical Manuscripts* in 1835. Scholars who worked on these chronicles in the earlier days did not take serious notice of

them; Even persons like Bishop Caldwell brushed them aside with the sweeping condemnation that they 'fall beneath the level of even tradition' and are 'little better than pure inventions.'<sup>1</sup>

But that was long ago. At that time, Indian studies were not far advanced and the scholars who engaged themselves in this work were mostly foreigners and were not fully conversant with our traditions and the outlook of our ancients. Further they compared these with the materials found in Europe and passed their judgment.

But recent studies have shown that these chronicles deserve better treatment and that such condemnation has to be modified to a very great extent. 'An impartial and collated study of these native records is the only substantial basis for the reconstruction of this history' writes Prof. R. Sathyanatha Aiyar in his *History of the Nayaks of Madura* (p. 33). Prof. K. A. Nilakanta Sastri, whose monumental work on *The Cōlas* is well-known, says that "certain statements regarding early Chōla history in the *Kōṅgudēśarājakkal* have been strikingly confirmed by authentic epigraphical evidence" and adds: "We still know little of the process by which these chronicles came into existence. They deserve careful and critical study too."<sup>2</sup> The fault of treating the contemporaneous dynasties as successive in the order of their attaining the paramount power over the area which has been found in the *Purāṇas* is also seen committed in the *Kōṅgudēśarājakkal*. There is also in this library another work *Konkanadēśa rājula vrittāntamu* in Telugu, evidently a version of this.

There is in this library a manuscript of *Gaṅgavamśānu charitam* giving the history of the Eastern Gaṅgas of Orissa<sup>3</sup>, written by Vasudēvaratha Sōmayājin who is described therein as the *Rāja guru*. The work which has got ten *parichchhēdas* appears to have been composed in the fourteenth century A.D. The author who was holding an official position in the Gaṅga court would certainly have had access to authentic information about the history of the family of his sovereign. Still, the work is treated more in the *kāvya* fashion;

1. *History of Tinnevely*, p. 55.

2. *Historical Method in relation to Indian History* by K.A. Nilakanta Sastri and H. S. Ramanna, p. 46.

3. Manuscript R. No. 3030, *A Triennial Catalogue of the Manuscripts collected during the years 1919-20 to 1921-22 for the Government Oriental Manuscripts Library, Madras*,

Just as we have histories of the several dynasties which ruled over different parts of India, there are also histories of individual kings. The *Harsha-charita* of Baṇa and the *Vikramāṅkadēva charita* of Bilhaṇa are typical examples. The former narrates the achievements of the Vardhana ruler Harsha of Kanyākubja in the first half of the seventh century A.D. (606-648), while the latter of the Western Chalukya monarch Vikramāditya VI (1076-1126 A.D.) The authors of these compositions were the court-poets of the respective monarchs. These two works are very popular among scholars and students of Sanskrit for their literary beauty.

We have similar works on the Nayaka rulers of Tañjavūr in the sixteenth and seventeenth centuries A.D. The *Sāhitya-ratnākaram* by Yajña Nārāyaṇa Dikshitar, son of the famous Gōvinda Dikshitar the minister, and the *Raghunāthābhyudayam* by Rāmabhadraṁbā, the poetess queen, both of them Sanskrit *kāvya*s, are on the life of Raghunātha Nāyaka (1614-33 A. D.). Two other works, one having the same name *Raghunāthābhyudayam*, a drama of the *yakshagāna* type and the other having the name *Raghunātha nāyakābhyudayamu*, a *kāvya*, both in Telugu, were written by his son, the royal poet Vijayarāghava Nāyaka.

About the Vijayanagara emperors, there are the *Śāluvaābhyudayam* by Diṇḍima Kavi on Śāluva Narasimha, and *Achyutarāyābhyudayam* on Achyutadēvarāya written in Sanskrit. There is also *Krishṇarāya vijayam* in Telugu by Kumāra Dhūrjaṭi in praise of the famous Vijayanagara monarch Krishṇadēvarāya.

All these works are *kāvya*s or dramas of some literary merit. They were written by the authors in praise of the good qualities and virtue of their patrons in an attempt to exhibit their poetic skill and not with a view to give an authentic and correct history of their reigns in the sense in which we expect them. We can at best take these works as giving out a pen-picture of and the guiding principle of the lives of these monarchs. We may quote the narration of Bilhaṇa of the birth of his patron Vikramāditya. He simply says that when the child was born, "flowers fell from the sky, Indra's drum resounded, and the gods rejoiced in heaven" (*IA*, vol. V, p. 318), in the conventional manner. But he does not even name the month and day or the year of the birth.

Similarly Baṇa writes that Harshavardhana was born 'in the month Jaishṭha, on the twelfth day of the dark fortnight, when the moon was standing in the Pleiades, just after the twilight time



when the young night had begun to climb'; but he has not stated the year.

"Neither author has given us even his own date. And so, if Harshavardhana and Vikramāditya were not known from more exact sources of a different kind, we should not even know to what period to refer the poets and their patrons" writes an eminent authority while estimating the value of these works for historical purposes. But this defect is found not in literature alone. Even inscriptions do not escape this charge. Many of the copper-plate grants of the early Pallavas before the time of Simhavishṇu would also come under this charge. Even though they give the names of the ancestors of the donor-king for three generations the dates are not given in any specified era. The regnal years of the kings are given and sometimes even that is not found. We have therefore to depend mainly on palaeography and occasionally on external evidences to fix their age.

It appears that similar works were also written in Tamil. Though the works are not now available, their names are preserved casually in inscriptions. A fragmentary record from Tiruppūndurutti in the Tañjavūr District of the time of Rajendra Chōla I mentions the provision made for the reading of a work *Śrī Rājarāja vijayam* (No. 120 of 1931), while an inscription from Tañjavūr of the time of Rajendra Chōla II records the provision made for performance of the drama *Rājarājēśvara nāṭaka* in the temple during the grand festival of *Vaikāśi* (SII, vol. II, No. 67). It is not certain if these works were in Tamil or Sanskrit. Very likely they were in Tamil. Rājarājēśvara, being the name of the god enshrined in the great temple there, it seems probable that the *nāṭakam* was not a drama based on Rājarāja's life, but rather a dramatic representation of the construction of the great temple itself. The other work might have been a quasi-historical poem treating of the monarch's reign. Anyhow, both of them must have contained information about some of the important episodes in the life of the monarch Rājarāja I.

Similarly a record of the time of Kulōttuṅga Chōla I from Tribhuvani near Pondicherry (No. 198 of 1919) mentions a *kāvya* composed in praise of the king and called *Kulōttuṅga-Chōla-charitai* by a certain Tirunarāyaṇabhaṭṭa alias Kavi Kumudachandra of the Manakulaśanichchēri and the gift of land as reward for the composition by the *sabhā* of the village. The reward was made by the *sabhā* in accordance with an order of the king requiring them to adjudge the *kāvya* and reward the author suitably.

Another Chōla king, whose name is not given, is reported to have ordered, while witnessing a dance performance in the Śiva temple at Tiruvārūr, the gift of some tax-free land to a person Pūṅkōyil Nambi who had celebrated a feudatory of the king by name Viraśōla Aṇukkan by composing a poem called *Viranukka-vijayam* (No. 548 of 1904).

The non-availability of these works is certainly a loss to the cause of our history.

There are also histories of important places and sacred temples. We have already referred to the *Madurai-t-tala-varalāru*. It deals with the history of the Madurai temple as its name indicates. It does not pretend to give the whole of the history and is naturally more detailed on the modern side.

The *Kōyil-olugu* is another book of the same type. It gives the history of the development of and the various benefactions made to the temple of Viṣṇu at Śrīraṅgam, known as *Kōyil* or the temple *par-excellence* among the Vaiṣṇavas. The many incidents recorded in this work are attested as correct by epigraphical and other data that are now accessible to us. There is the *Mādalā-Pāṇji*, a chronicle of the temple of Jagannatha at Puri. Similar chronicles for the famous temple at Tirupati, known as *Tirumalai-y-olugu*, and for the temple of Kaḷahastī are also said to be in existence.

### 3. INSCRIPTIONS AS THE MAIN SOURCE FOR HISTORY

In Tamil we have a class of literature which may be designated as 'war-poems.' The *Kalavali-Nāṇpadu*, a poem in forty verses, giving a picturesque account of the battle-field (*kaḷam*) at Kaḷumalam in which the Chōla king Śeṅgaṇan defeated his Chēra adversary Kanaikkal Irumporai by the poet Poygai is perhaps the earliest work of this class. But the *Kalīngattu-p-parani* composed by the poet laureate Jayaṅkoṇḍar towards the close of the reign of Kulōt-tuṅga I, depicting not only the pomp and circumstance of the Kalinga war of the monarch but all the gruesome details of the field is the most famous. A similar work on the victory of Vikrama Chōla in the Kalinga war is said to have been composed by Oṭṭak-kūṭṭan, the poet laureate in the court of Vikrama. The poet himself refers to this *parani* in his other works; but the work is not available. These works though purporting to describe historic events are more conventional and are poetry.

A *kāvya* in Sanskrit called the *Madhura-vijayam* by Gaṅgādevī, one of the wives of the Vijayanagara prince Kumāra Kampaṇa, describes the military expedition led by the prince to free the Tamil country from the Muslim occupation in the middle of the fourteenth century A.D. This work is an important source for correcting the inaccuracies found in the Muslim sources for the same.

There are many other works in Tamil, all of them in the class of minor *prabandhas*. The *Mūvar-ulā*, composed of three *ulās*, one on each of the three Chōla kings, Vikrama Chōla, Kulōttuṅga II and Rajarāja II by Oṭṭakkūttan who was in the courts of all these three and the *Śaṅkara Śōlan ulā*, by an unknown author on Śaṅkara Śōlan, younger brother of Kulōttuṅga III, are typical instances of the variety called *ulā*.

Of the type of *kōvai*, perhaps the earliest historical work is the *Pāṇḍi-k-kōvai*, which furnishes most of the illustrative verses in the commentary to the *Iraiyānār Ahapporūl*. The *Kulōttuṅgan-kōvai*, the authorship of which is not known, has been composed on the Chōla king Kulōttuṅga who is generally taken as the third of that name. There is also the *Taṇjai-vāṇan-kōvai* by Poyyāmolī-Pulavar on the Bāṇa chief of Taṇjai identified with Poṭṭai Taṇjai a place near Madurai.

Oṭṭakkūttan, who was also the tutor to the Chōla monarch Kulōttuṅga II in his early years in addition to his being the court-poet, has composed *Kulōttuṅgan-piḷḷai-t-tamiḷ* on the king.

And in the variety of *kalambakam*, we have the *Nandi-k-kalambakam* on the Pallava monarch Nandivarman, the Victor at Tellāru, supposed to have been written by his dissatisfied younger brother bearing a grudge against the elder.

All these works are composed in the conventional manner. Jayaṅkoṇḍar, like Bilhaṇa, when narrating the birth of his patron, the hero of the *Kalīṅattu-p-parani* mentions simply, that "the drum (*duṇḍhubi*) of the celestials resounded rejoicing that the evil days of the four *vēdas* on the earth had come to an end." Similarly when describing the condition of the Chōla dominion immediately following the death of Virarājēndra and preceding the advent of Kulōttuṅga there, the poet draws a vivid picture of the anarchy that prevailed in the country. "Brahmanical sacrifices were given up; the path of Manu was totally deserted, the six sciences were forgotten and

the chanting of the Vēdas ceased." This will show that the above is only a conventional picture of the conditions.

Even when historical events are actually mentioned, they are only indicated as passing references. The *Nandi-k-kalambakam* says that its patron 'won a victory at Palaiyāru defeating the river-like army of the enemies' (*paḍaiyāru-śāya-p-Palaiyāru venṇān*). Neither the name of the person whom he conquered nor the circumstance that lead to the war is anywhere mentioned.

The poems of the *ulā* and *parani* classes when composed on historical personages have a chapter *tiru-muḍi-y-aḍaiṇu* (the order of succession to the crown) in which the genealogy of the hero-king is given in detail. Mostly, they do not mention the ancestors by name, but refer to them by the specific deeds by which the respective monarchs attained fame, occasionally combining their names to such narration. Thus Karikāla, one of the ancestors of the Chōḷas, is always referred to by his construction of the embankment to the river Kavēri, sometimes adding his name also. But Śēṅgaṇan and Vijayalaya are referred to respectively as the king who had the composition of the poem *Kaḷavali* and as the king who was adorned with the scars of ninety-six wounds on his chest. Similarly, where a king is simply mentioned 'as the conqueror of Madurai and Iḷam' or as 'the Śēmbiyan (Chōḷa) who sat on the throne having captured the Ganges and the Kaḍāram with his army', we know that the poet refers to Parāntaka I or Rajēndra Chōḷa I, as these kings are sometimes referred to likewise in inscriptions also.

There is another class of rustic literature, the Ballads, which has not been considered critically so far. The value of Ballads can hardly be under-estimated for study of the past history of the land. These are simple poems devoid of high poetic ambition for popular and oral circulation. The *Rāmaḥṇayyan Ammāṇai* and the *Dēśinga Rājan kathai* are typical instances of this class. As regards the latter, this library has among those collected by Col. Mackenzie a manuscript quite different from the popular one, but more historical.

All these classes of works contain a great deal of charming reading much of interest and are invaluable for the study of various other branches than chronology.

Again, the introductions and colophons of literary works, romances or even religious works and the *sthala purāṇas* in the local languages often help us as they contain sometimes the dates of their

composition and other useful information about their royal patrons. But it should be borne in mind that the historical information about their patrons is introduced only incidentally to show the status and importance of the authors rather than of their patrons.

The introduction to the *Avantisundarikathā* by Daṇḍin makes its author a great-grandson of Dāmōdara who was a friend of the great poet Bhāravi and from the account given therein it is seen that Bhāravi visited the courts of the Chālukya king Vishṇuvardhana, the Gaṅga ruler Durvīṇa and the Pallava monarch Simhavishṇu, thus making these three monarchs contemporary.

The *Lōkavibhāgam* is a work of Jaina cosmology in eleven *prakaraṇas*. (*Mysore Arch. Report* for 1911.) It is said that the subject matter of work was explained by the last *Tīrthāṅkara* Varddhamaṇa Mahāvīra to Sudharma and others. It was transmitted to posterity orally in the *guru-śishya* manner, i.e., from teacher to disciple and after a long time was reduced to writing by *Rishi* Simhasūri. All the available manuscripts of the work state that it was copied by Sarvanandi at Pāṭalikā in the Pāṇarashṭra on a certain day, the astronomical details of which are given. It is further stated therein it was in Śaka 380, corresponding to the twenty-second year in the reign of the Pallava king Simhavarman of Kāñchīpuram. Pāṭalikā is the same as Pāṭalipuram, the other name of Tiruppadirippuliyūr where according to the *Periya-purāṇam*, there was a Jaina monastery over which the Śaiva saint Appar or Tirunāvukkarasu presided for some time when he was a Jaina. The astronomical details given therein are said to be regular and yield a date in 457 A.D. This clearly shows that the Pallava ruler Simhavarman was ruling at Kāñchīpuram in that year which was his twenty-second regnal year. That there was a king of that name at Kāñchī about this period is evident from the Penukoṇḍa plates.

Sōmadēva Sūri tells us, in the colophon to his work *Yaśastilaka-champū*, that he finished the work in the month of *Chaitra*, in Śaka year 881 expired, falling in 959 A.D., during the rule of a Chālukya prince who was the eldest son of Arikēsarin and was a feudatory of a king Krishṇarāja. He does not give us any further details of his patron or his family or the territory over which he ruled. It is stated therein that Krishṇarāja was then ruling from Mēlpaḍi after having subjugated the Pāṇḍya, Simhala and Chēra. The Karhād plates (*EI*, vol. IV, p. 280) of the Bāshṭrakūṭa king Krishṇa III dated the 9th March 959 A.D. show that Krishṇa was then at his

camp at Mēlpaḍi, in the Chittoor District, at the end of his southern campaign and it is stated therein that in the course of his *digvijaya* in the south, 'he uprooted the family of the Chōḷas and extorted tributes from several kings including the king of Ceylon.' It will thus be apparent that the son of Arikēśarin who was the patron of the poet, was a feudatory of Rāshtrakūṭa Kṛishṇa III. More particulars of this Arikēśarin are found in the Kannaḍa *Bhārata*, also known as *Vikramārjuna-vijaya* by the famous poet Pampa written in 941-42 A.D., where the pedigree of the monarch is given for seven preceding generations with a fairly sufficient account of the family. The history of the Lēmulaṇḍa branch of the Chālūkyas has to be reconstructed with the above as the chief source supplemented by epi-graphs.

The introductory portion to the *Vratakhanda* by Hemādri in the sixties of the thirteenth century A.D. is another instance. The author who held the post *Śrikaraṇādhīpa* or the chief of the department for drafting documents under the Yādava ruler Mahādēva as also under his successor Rāmachandra, has given therein the full pedigree of that branch of the Yādavas to which his patron belonged from even Purāṇic times. He must have had, by the very nature of his official position, free access to the official records and other materials to give a connected account of the family. Still, the exact relationships of the successive members of the family are not given and we have to presume the same as that of a father to a son.

Many literary works give such pedigrees not only of the patrons but also of the authors. Nadiṇḍa Gōpamantrin, in the introductory portion of his work *Kṛishṇārjuna-samvādam* gives the details not only of his own ancestry, but also of his uncle Appaji, otherwise known as Śaḷuva Timma, the famous minister of the Vijayanagara monarch Kṛishṇadēvarāya.

These pedigrees used to astonish foreign scholars in the earlier days and they did not give much credence to them, as they were not accustomed to such material. But the maintenance of such lists is a regular feature in almost every big and important family of our country and this will not be considered astonishing if we remember that the *Dharma śāstras* prescribe regulations for certain religious observances like pollution, etc. in a family extending over fourteen generations. Such lists were being maintained in many families till very recently.

Every *maṭha* preserves a *paṭṭāvali* or succession list of pontiffs running from its founder, which sometimes goes back for long periods. Some of the Jaina *paṭṭāvalis* have been critically noticed by scholars. (*IA*, vols. XX, XXI, etc.) In this collection we have an inscription (No. 1107) copied by the assistants of Mackenzie from the temple of Virarāghava at Tiruvalḷūr registering a gift of gold to the temple by Virarāghava Śaṭhakōpa Jiyar in Śaka 1552 or 1630 A.D. This Jiyar was, evidently of the Ahōbala-maṭha which manages the temple, the thirteenth member in succession of the line who is said to have occupied the pontifical seat from 1630 to 1675 A.D.

The Kuḍiyāntaṇḍal copper-plate grant of the Vijayanagara ruler Vīra Narasimha (*EI*, vol. XIV) dated Śaka 1429 (or 1506 A.D.) registers a land-grant to Mahādēva Sarasvatī, disciple of Sadaśiva Sarasvatī and the then occupant of the *Kāmakōṭi pīṭha* at Kāñchī. This succession is vouched for by the *Gururājaratna-mālikā* of the *maṭha*, which also says that Chandrachūḍa Sarasvatī was the disciple of the above Mahādēva Sarasvatī. A copper-plate grant dated Śaka 1444 (or 1521 A.D.) registers the gift of the village Krishṇarāyapuram to this Chandrachūḍa Sarasvatī by Krishṇadēvarāya. (*Ibid*). He was also known as Chandraśēkhara Sarasvatī. We have a record of this Chandraśēkhara Sarasvatī at Ambi near Kāñchīpuram dated Śaka 1436 (or 1513 A.D.) in the reign of Krishṇadēvarāya. And the Udayambakkam grant of this king dated Śaka 1450 (or 1527 A.D.) registers the gift of the village to Sadaśiva Sarasvatī, disciple of Chandraśēkhara (*EI*, vol. XIII). The *Guruparamparās* say that Chandrachūḍa Sarasvatī was honoured by the king of Nēpāl. Curiously enough, the Nēpāl Chronicles record the visit of a teacher named Sōmaśēkharananda to that country in 1503 A.D. The names Chandrachūḍa, Chandraśēkhara and Sōmaśēkhara are synonymous. We may very well believe the statement of his visit to Nēpāl. The above will clearly testify to the trustworthiness of these succession lists.

From Nēpāl we have a *vamśāvali* giving a list of successive rulers of that country purporting to go to the commencement of the Kali Age in 3102 B.C. (*IA*, vol. XIII, p. 411). It contains, as is inevitable in such cases, gross mistakes in chronology. But it is not entirely devoid of value. The succession list contained therein is found correct, as also the chronology and the dates, for later periods. For instance, from Vṛishadēva of the Śūryavamśi dynasty who is placed as the 18th to Vasantadēva, the 23rd ruler of that line, the list gives a succession of six names which have been verified from epigraphical records.

Such *vamsāvalis* or *Rājāvalis* as they are known, lists of the lineal succession of kings, appear to have been maintained in those days among royal families. This will become clear from the introductory passages found in the copper-plate grants of the Eastern Chālukyas of Vēṅgī. These grants name the successive kings beginning with the founder Kubja-Vishṇuvardhana, the younger brother of Pulikēśin II, of the (Western) Chālukyas of Vatapi in the first half of the seventh century A.D. and also give the length of the reign of each of them. The particulars found in the grants are almost identical, though occasionally some differences are found which probably were mainly due to the existence of varying recensions because of the interruptions of the collateral branches. The records of the Eastern Gaṅgas of Kalinga also contain similar particulars for the monarchs of that dynasty.

Such lists were also being maintained by the Pallavas, the Chōlas and other dynasties of the Tamil country. The Vaikunṭhap-perumāḷ temple inscription from Kañchipuram (SII, vol. IV, No. 147) states that after the death of Paramēśvaravarman II in the first half of the eighth century A.D. there was no direct heir in the line of pure blood on both the sides to ascend the Pallava throne and so the ministers and other leaders selected Nandivarman Pallavamalla of the collateral branch as their sovereign. The Kaśākkṛṇḍi plates of Pallavamalla giving the pedigree of the monarch (SII, vol. II, No. 120) state that he was the son of Hiranyavarman, who was the grandson's grandson of Bhimavarman, who in turn was the younger brother of Simhaviṣṇu through whom descended the other line.

The Chālukyas of Vatapi were ruling over the Kuntala and the Karnaṭaka countries for nearly two hundred years from the middle of the sixth century A.D., at the end of which period they lost power, and the Rāshtrakūṭas who rose in their stead occupied the country. The Chālukyas again rose and retrieved their former position from the Rāshtrakūṭas in the latter half of the tenth century A.D. In the grants of the members of the later branch who are known as the Western Chālukyas of Kalyānapura, their descent from the earlier family of Vatapi is clearly recorded and the names of the members in the intervening period are also given. Not only that; the heroic exploits of the earlier members of the family and other historical matters relating to them are also given. The Kauthēm grant (IA, vol. XVI) of Vikramāditya V, grandson of Taila II the re-establisher of the fortunes of the family, mentions Maṅgalēśa who was not in the direct line of descent and therefore might have been easily lost sight of in a mere *vamsāvali*. It further records his conquest of



the territory of Rēvatidvīpa and also represents him as simply a regent during the minority of his nephew Pulikēśin II, to whom, it says, he eventually restored the throne in pious accordance with the custom and laws of the Chālukya kings, thus seeking in a way to obliterate his attempt to break the direct and rightful senior line of succession in favour of transmitting the crown to his own son.

Some of the feudatory families seem to have maintained similar records of their paramount sovereigns as well. This will become clear from the records of the Śilāhāras of the Southern Kōṅkaṇa. The Kṣārēpaṭaṇ plates (*EI*, vol. III) of Śilāhāra king Raṭṭarāja dated 1008 A.D. in the time of the Western Chālukya monarch Satyāśraya, give the genealogical tree of the donor's family in addition to a list of the Rāṣṭrakūṭa kings from Dantidurga, the founder to Kakka II, the last of the dynasty and also the first two kings of the Western Chālukyas who succeeded them.

It will be evident that dynastic chronicles were maintained in those days by the ruling families, probably as distinct from official records. That probably was responsible for the survival of such records for a considerable time even after the disappearance of the dynasties. It is not improbable under favourable conditions that documents written on even frail materials can be preserved for long periods.<sup>1</sup> It was probably these materials that served as sources for the later members of the several ruling families to give an account of their forefathers.

Kings of old, whether paramount sovereigns or petty chieftains, used to maintain documents known as *granthavāris* of their day-to-day transactions and activities, on many occasions written by their court officials specially entrusted with this work. Col. Mackenzie was able to collect in the beginning of the last century some of these *granthavāris* relating to late periods. Such records have also been secured from different parts of the country for the Moghul and Mahratta periods. But no such document relating to the early periods of the Hindu kings has been traced so far.

---

1. The mathematical work known as the 'Bower Manuscript' and written in the characters of the fifth century A.D. on birch-bark has been secured during the later days of the last century from Kashgaria, on the north of Kashmir through excavations at "the foot of one of the curious old erections, of which several are to be found in the Kuchar district."

From this it is not to be taken that no such records were maintained in earlier days. The several *meykkīrttis* and the *prāśastis* of those kings clearly indicate that some such records were in existence then. Among the Imperial Chōlas of Tañjāvūr and the Paṇḍyas of Madurai, each king had separate *meykkīrtti*, and occasionally some of them had even more than one, each with variant forms. But all of them narrated only the achievements of the respective monarchs. These *meykkīrttis* grew in length with each year and additional information about the victories and other noble acts of the sovereigns included as and when they occurred.

But the *prāśastis* of the kings of some dynasties like the Chālukyas and of the Vijayanagara empire given at the beginning of their copper-plate grants are found almost in a standard form, new verses being added with the succession of each king, the earlier portions being retained as they were.

The Hāthigumphā cave inscription of Khāravēla who ruled over Kāliṅga in the second century B.C. (*EI*, vol. XX) giving a succinct account of the career of the king from his birth to the thirteenth year of his reign is on the model of the *meykkīrtti* and a *kāvya*. It tells us that the king who belonged to the original stock of *Aila*, spent the first fifteen years in princely sports and the next nine years as *Yuvarāja* learning the different branches of administration. He was crowned at the end of his twenty-fourth year of age, after narrating which the record briefly enumerates, year by year, the principal events of his reign, upto the thirteenth year.

These narrations would have been possible only with the help of official records.

The numerous inscriptions of the Chōla monarchs clearly point to the careful and detailed system of administration that was prevalent in those days and its elaborate routine with a fairly extensive method of keeping official records. We find that the administration was then divided into several departments as at present, each managed by several high ranking officers and a large number of officials. Copies of important orders and communications issued by the several departments to the local assemblies and provincial officers would certainly have been maintained at the offices of issue to verify at some later date whether those orders had been executed. Similarly copies of treaties and alliances entered into with the neighbouring states and chiefs would have been kept by both the parties to regulate the proper performance of the same. Some such records existed

on stone have been recovered. During the later years of the Imperial Chōlas of Tañjavūr when the central authority had weakened, and the local chieftains gained importance, we find those chiefs entering into mutual compacts among themselves and recording them on stone.

That some sort of a day-to-day record of events was maintained in those days will be evident from the fact that the Tiruvalaṅgaḍu plates of Rajēndra Chōla I registers that the grant recorded in the charter was orally ordered by the king on the eighty-eighth day in the sixth year of his reign but was reduced to writing thirty two days later, i.e., on the one hundred and twentieth day of the same year (*SII*, vol. II). Similarly an inscription of Rājādhiraja I from Enṇāyiram in the South Arcot District (No. 330 of 1917) states that the order issued by the king on the one hundred and thirty-seventh day of the twenty-seventh year in the reign of the king reached the *sabhā* of the village three years and hundred and three days later, i.e., on the two hundred and fortieth day of the thirtieth year in the reign of the same king. The Tiruppūvanam grant of the Pāṇḍya monarch Kulaśēkhara mentions the thirteenth year and the four-thousand three hundred and sixtieth day in the reign of the monarch. (*EI*, vol. XXV),

We also learn from epigraphy that land was surveyed on many occasions, sometimes even going upto very small fractions and elaborate accounts kept for the several items of revenue therefrom. But unfortunately, except for occasional references to them in the inscriptions, those records have been completely lost to us.

But inscriptions to a certain extent serve as substitutes to these records and we have to depend on them mainly to reconstruct the history of our past.

#### 4. LITERARY AND HISTORICAL INSCRIPTIONS

The ancient inscriptions may be broadly divided into two classes: (1) royal or official and (2) private or individual. Basing on their contents they may be classified broadly into two in a different way, (1) donative and (2) other transactions.

But there are a few records which do not fall within the above classifications and stand separately. Such records also may be divided into two groups: (1) purely literary pieces and (2) inscriptions recording plain statements of a historical nature.

### Literary Inscriptions.

The old commentary (*circa* 8th century A.D.) on the *Ahapporul* of Iraiyaṇār in Tamil narrates a tradition how the original work was composed. Once there was a severe famine extending for twelve years in the Pāṇḍya country, as a consequence of which poets and scholars left their homes for foreign lands. Many of them came back to their homeland with the return of prosperity. But there was no scholar among them well versed in the theme *poruḷ*. The Pāṇḍya monarch was greatly grieved at this. He therefore repaired to the temple of Śiva and prayed to the lord there. The god enshrined therein, who was considered as one of the forty-nine poets constituting the Tamil Academy (*saṅgha*), on hearing the prayer of the king composed the work, had it incised on copper-plates and left it underneath his *piṭṭha* in the night. It was discovered the next morning by the temple priest.

This story would show that the practice of writing books on copper-plates to preserve them for posterity was very old. There are similar traditions in other parts of the country also. Yuan Chwang, the Chinese pilgrim, who visited India in the middle of the seventh century A.D., mentions that king Kanishka convened a Buddhist assembly which prepared commentaries on the *Tripitaka* and that he had them engraved on copper-plates and kept in stone caskets placed in the *stūpas* built over them. A similar story is preserved regarding the commentary of Sayaṇa on the Vēdas being engraved on copper as recorded by Max-Muller in his edition of the *Rig Vēda* (vol. I, p. xvii).

A.D. Campbell, the noted Telugu scholar, wrote in his *Telugu Grammar* (2nd ed. of 1820, p. xiii): "Having heard that a number of poems, engraved on some thousand sheets of copper, had been preserved by the pious care of a family of Brahmins in the temple on the sacred hill at Tripatty, I deputed a native for the purpose of examining them; but, with the exception of a treatise on grammar of which a copy was taken, the whole collection was found to contain nothing but voluminous hymns in praise of deity." They are even now preserved in the *Saṅkīrtana-Bhaṇḍāraṁ* of the temple at Tirupati. These are the compositions of three poets of the Tāḷlapākkam family who flourished in the fifteenth and sixteenth centuries under the patronage of the Vijayanagara kings. It is learnt that there are about three-thousand copper-plates (on one occasion referred to as cart-loads) containing on the aggregate about nine thousand devotional songs in the *saṅkīrtana* style and other literary pieces. (*Tirumalai Tirupati Devasthanam Epigraphical Report*, p. 297). These are now being published by the Tirumalai-Tirupati Dēvasthanam.

From the Chidambaram inscription of Naraṅkavīra (Nos. 1271-73 of the Mackenzie collection) we may infer that he caused the sacred hymns of the *Tēvāram* to be incised on copper-plates and preserved in that temple.

It will be evident from the above that in olden days even literary compositions were written on some enduring material to preserve them for posterity without perishing. Such works are also found incised on stone.

The musical inscription at Kuḍumiyamalai in the former Pudukkōṭṭai State is a typical example of this variety (*EI*, vol. XII). Engraved in the Pallava-Grantha characters of the seventh century on the slope of the rock behind the temple, covering a wide space, the record opens with *Siddham, Namaḥ Śivāya*. It is arranged in seven sections; each section has several sub-sections and each sub-section throughout has sixteen sets of four *svaras* each. There is a colophon at the end stating, "*Svarāgamas* made for the benefit of the disciples by the king, a *Mahēśvara* and a disciple of Rudrāchārya" in Sanskrit and "these (evidently the musical notes) are intended for the eight and seven (stringed *vīṇās*)" in Tamil. (*ivai eṭṭirkum ēlir-kum uriyaṇa*.) It is generally considered that the Pallava monarch Mahēndravarmān I, who prides himself with the title, *Saṅkirṇa-jātiḥ*, giving us to know that he was the inventor of the variety of musical-time going by that name, was the author of this composition.

A similar inscription in similar characters recording another like composition is found at Tirumeyyam near that place. But unfortunately a late Paṇḍya king Māravarman SundaraPaṇḍyaII has erased the inscription stating that "it is in an unintelligible script" (*bhāṣhai puriyāda kalveṭṭu*) and engraved on the space thus obtained an inscription registering some settlement of a dispute. (*PSI*, Nos. 340, 341). Some of the words like *Shadja, Gāndhāra*, etc. are still traceable. Serious damage has thus been wrought to an invaluable inscription.

On the walls of the Puṇyanāthēśvara temple at Tiruvīdaivayil in the Tañjāvūr District there is an inscription in Tamil registering eleven verses by Saint Tirujñānasambandha in characters of the twelfth century (No. 8 of 1918). According to the *Tirumurai-kaṇḍa-purāṇam* of Umāpati Śivachārya, Jñānasambandha composed sixteen thousand *padikams* in praise of Śiva, but that only three hundred and eighty-four were recovered and arranged in three *Tirumurais*. But the printed editions contained three hundred

eighty-three only, thus short by one *padikam*, that found in the inscription not being one of them. Considering that similar records containing the *padikam* of the respective temples are not found elsewhere, it is possible that the loss of one *padikam* of the saint in the collection after its codification occurred even earlier and that there was not unanimity of opinion among the scholars even then, about the one relating to Tiruviḍaiyāil. Anyhow, the discovery of this is highly important as it brings to light an otherwise unknown decade of verses of the saint.

At Tiruchirappalli there is a long inscription (*SII*, vol. IV, No. 167) in Tamil containing one hundred and four verses in the *kaṭṭalai-k-kalitturai* metre of the *antādi* type, in which each verse begins with the last syllable or syllables of the previous verse, in praise of Śiva enshrined there in characters of *circa* eleventh century A.D. This work, composed in beautiful verses by a certain Nārāyaṇan of Vēmbai, has been recently edited separately by Pandit M. Raghava Aiyangar.

A small work in Sanskrit, entitled the *Hanumad-vimśati* in praise of the god Hanumān consecrated in the temple on the banks of the Tātasamudram (Aiyāṅgarkuḷam), a tank dug by and named after *Kōṭikanyādānam* Lakshmi Kumāra Tātachārya, the royal preceptor of the Vijayanagara monarch Vēṅkaṭa I, is found engraved on the walls of the temple of Hanumān at Aiyāṅgarkuḷam (No. 92 of 1923). This is also re-engraved on the east and north walls of 'rock' of the central shrine and also on the walls of the Tayār (goddess) shrine (No. 651 of 1919) and on the outer *gōpura* of the Varadarājasvāmi temple at Kāñchīpuram. The copy of this found in the Mackenzie collection has been edited in the *JOR*, vol. XVIII.

The east and west *gopuras* of the famous temple of Naṭarāja at Chidambaram are very richly decorated and bear on their inner walls fine specimens of images of which a large number illustrate the various dancing postures. These figures contain above them engrossed in the Grantha characters, Sanskrit verses describing the one hundred and eight postures from the *Nāṭya-śāstra* of Bharata. These appear to have been executed in the time of Kōpperuñjiṅga in the middle of the thirteenth century A.D. (*ARSIE*, 1914). This inscription contains some important variant readings. This has been separately edited as the *Tāṇḍva-lakṣhaṇa* by Dr. B. V. Narayanaswāmi Nayudu and two others.

On a pillar in the *maṇḍapa* in front of the Durgā shrine in the temple of Kachchappēśvara at Kāñchīpuram are found incised the first six verses of the Sanskrit poem *Sūryaśatakam* by Mayūra Kavi in characters of the eleventh century A.D. (No. 81 of 1921). Probably it was a votive pillar.

Such literary inscriptions are also found in other parts of India. The first two acts of a drama of the variety of *nāṭikā*, called *Pārijāta-mañjarī* or *Vijayaśrī*, of which the hero is the Paramāra king Arjunavarman, composed by Madana, the royal preceptor, is found engraved on stone in the Bhōjaśāla at Dhārā (*EI*, vol. VIII). From Ajmer, we have fragments of two otherwise unknown plays. One of these plays, entitled *Lalitavigraharāja-nāṭaka*, was composed by a poet Sōmadēva, in honour of the Chāhamāna king Vighraharāja. The other, entitled *Harakēlināṭaka*, was composed by the king Vighraharāja himself. (*IA*, vol. XX). These dramas contain allusions to historical events.

From Dhārā itself have been recovered two Prakrit poems, *Avanī-kūrma-śatakam*, odes to the tortoise incarnation of Viṣṇu, written in honour of the Paramāra king Bhōja (*EI*, vol. VIII). These two poems contain one hundred and nine stanzas each. The first poem states that nobody has carried the earth so well as the tortoise and that no mother is happier and worthy of praise as the mother of the tortoise. The second *śatakam* states that even the tortoise has been surpassed by king Bhōja who carries the earth. "Even to the tortoise rest has been granted by king Bhōja alone. By him the *Kūrma śatakam* has been composed after he had taken away all hope to the enemies."

We have also obtained from the same place two grammatical serpentine inscriptions. Inscribed in the form of *śarpa-bandhas* or *nāga-bandhas*, one gives the letters of the Sanskrit alphabet and the other gives the roots of the *dhātū*, representing the initial grammatical teaching imparted in the Bhōjaśāla or the Sarasvatī temple there in those days. The system followed therein is of the Kātantra school of Sanskrit Grammar. At the top of the *nāga-bandhas*, there is a verse praising Udayāditya and his son Naravarman. Probably the inscriptions were engraved in the time of Naravarman of the same Paramāra family and as such they were slightly later than the time of Bhōja.

A fragmentary inscription found in the Vaidyanāthasvāmī temple at Deoghar in the Santal Pargānas, in characters of the seventh century A.D. ends with the words, *iti Mandaragiri-prakaranam*,

(Thus runs the chapter on the Mandaragiri—*GI*, p. 213). It will be seen therefrom that it forms portion of a larger work, evidently some *purāṇa*, the other details of which are unknown.

It is also said that a large Jaina *sthalapurāṇa*, containing a number of *sargas* incised on stone, exists at Bijholli in the Rājputāna (*IA*, vol. XXXIII, App. p. 97).

The copper-plate containing thirteen lines of writing and recording the *Udāna-sutta* of Buddha, discovered in the Mahānirvāṇa-Stūpa at Kuśinagara in the Uttara Pradesh also belongs to the same class (*ASI.AR*, 1907, p. 46).

There are many other inscriptions giving stray verses instead of complete works. A Tamil verse inscribed in the Śikhānāthasvāmī temple at Kuḍumiyamalai contains an interesting poetic imagery with a play on the name of the god (No. 361 of 1930). It says that the goddess Umā who has given birth to the seven worlds is always laughing at her Lord as to where he would hereafter hide Gaṅga, now that he is wearing only a tuft discarding his matted hair wherein he was hiding her previously.

### Historical Inscriptions

There are a few records which contain only plain statement of events or purely historical narrative.

The stone inscription from Tiruvēndipuram in the South Arcot district dated the year opposite to the 15th year in the reign of the Chōḷa king Rājārāja III is a typical record of this class (*EI*, vol. VII). The inscription opens with the statement that the Hoysaḷa king Vīra Narasimha having heard that Kōp-Peruñjīṅga had imprisoned the Chōḷa emperor, i.e., Rājārāja III, at Śēndamaṅgalam and had devastated the kingdom with his troops and desecrated the temples, started from his capital Dōrasamudra, saying that he would not blow his trumpet (*kāḷam*) until after he had re-established his name *Chōḷamaṇḍala-pratishṭhāchārya* (Establisher of the Chōḷa kingdom). Two of his *daṇḍanāyakas*, Appaṇṇa and Samudra Gōppayya, with orders to carry destruction to the country of Kōp-Peruñjīṅga and re-install the Chōḷa emperor, killed some of the *mudalis* of the king including Parākrama-bāhu, king of Ceylon, and struck terror in the hearts of the people. When finally they made preparations to invest Śēndamaṅgalam, Kōp-Peruñjīṅga sent word to the Hoysaḷa monarch that he was ready to restore the Chōḷa emperor to liberty and his throne. This offer



having been transmitted by Narasimha to his officers, the *daṇḍa-nāyakas* received the Chōḷa emperor with honour and accompanied him back to his country.

Another record of this type is the Mahratti inscription in the Brihadīśvara temple at Tañjavūr (No. 424 of 1924). This long inscription incised in Śaka 1725 or 1803 A.D. by Maharāja Serfoji gives in chronological order the history of the Bhonsle family describing in detail the achievements of Shahji and his son Śivaji the Great, and continues the family history down to Śarabhōji who had the document engraved. It contains interesting information not found in the historical works written previously and a long genealogy of nearly twenty generations. The record gives a fairly comprehensive history of the Mahratta kings of Tañjavūr. This, along with the other Mahratti inscriptions incised in the same temple by the same ruler, has been published in a book form by Sri T. Sambamurti Rao wherein it occupies nearly one hundred and twenty pages of the *royal octavo* size.

The Hathigumpha inscription of Khāravēla, the ruler of Kaliṅga in the first or second century B.C., already referred to, is another of this type. It gives a succinct account of the career of the king from his birth to the thirteenth year of his reign which commenced at the end of his twenty-fourth year of age (*EI*, vol. XX).

The eulogy of the Gupta monarch Samudragupta, incised on the Aśoka pillar at Allahabad (*GI*, p. 1), is another typical instance: It recites his pedigree, describes his conquests in Northern India, mentions some of the foreign tribes with which he had relations, and gives a considerable insight into the political divisions of the eastern portion of the Dakṣiṇ in those days.

There are many inscriptions which merely register the *nilaimai-tittus* or the political compacts entered into between local chieftains. Such records are found only when the central authority had become weak and the local chiefs had risen to prominence more or less claiming independence, owning nominal allegiance to the suzerain power.

An inscription (No. 440 of 1913) from Āraḡaḷūr in the Salem district dated in the thirteenth year in the reign of Kulōttuṅga III registers the terms of a compact between Rajarajadēvan Ponparappinan *alias* Kulōttuṅgasōḷa Vāṇakōvaraiyan and Kīḷiyūr Malaiyamān of Tirukōvalūr. According to the compact, the territory lying to the south

of the river Alivinaiyāru must go to the former and that to the north of the river to the latter. It also includes a defensive alliance in general coupled with the stipulation that they were to act together in the service of the king. Another record from the same place and dated in the thirty-fifth regnal year of the same monarch (No. 435 of 1913) registers a mutual compact between Śengēṇi Ammaiappan Alagiyaśōlan *alias* Ediriliśōla Śambuvarāyan on one side and the chiefs (*aiyar*) Ponparappina Vāṇakōvaraiyar Kulōttuṅgaśōla Vāṇakōvaraiyar and his *maichchunanār* Kāḍavarāyar on the other side. Sometimes interesting imprecations are found at the end of these records.

Stray records registering the oaths of fealty taken by subordinates or officials to serve their patrons faithfully also belong to this class. There are about half a dozen undated inscriptions of the Choḷa ruler Parāntaka III at Drakshārāma registering such declarations by some persons to serve Parāntakadēva faithfully (*SII*, vol. IV, Nos. 1270-1274 and 1275-A). These records also denote that there was opposition either internal or from outside to the suzerain in those days.

The pillars of victory erected by the ancient monarchs to commemorate the victories gained by them should also be considered as belonging to this class. The fragmentary inscription engraved in beautiful Grantha characters dated in the thirteenth regnal year of the Pallava king Narasimha mentioning Vātapi and found on the rock behind the temple of Mallikārjuna at Badami (Vātapi) mentions a *Jayashambha*. (*SII*, vol. XI). Evidently the record mentions his victory over the Chālukya ruler Pulikēśi II, as the Pallava monarch, according to the Vēlūrpaḷaiyam plates (*SII*, vol. II); is said to have gained at Vātapi a pillar of victory.

Śarabhōji, the last Mahratta ruler of Tañjavūr, erected in 1814 a tower *Manōra*, at Śaḷuvanāyakanppaṭṭinam near the sea coast to commemorate the victory of the British forces against Napoleon in Europe and recorded the same thereon in inscriptions in five languages, English, Tamil, Telugu, Mahratti and Persian. (Nos. 343 and 344 of 1925).

An inscription in the Sanskrit, Tamil and Telugu languages engraved on four broken pieces of stone built in different places in the Kailāsanātha temple at Kāñchīpuram and dated in Śaka 923 (or 1102-03 A.D.) mentions the victory of the Chōḷa monarch Rajaraja I over the Telugu Chōḍa chief Jaṭāchōḍa Bhīma and the capture of the latter as a prisoner (*EI*, vol. XXI). The Tiruvālaṅgaḍu plates of

Rajendra Chōla I (*SII*, vol. III) contains the following verse relating to Rājārāja I. "Because Bhima, skilled in battle, killed with a club my namesake Rājārāja, therefore shall I go and fall upon this strong Āndhra ruler Bhima by name. And saying this Rājārāja fell upon him." The poet has introduced a play upon the proper names. It states that Rājārāja attacked him because of his name Bhima. In the *Mahābhārata*, Bhima is depicted as having killed Duryōdhana who was also called Rājārāja. Thus the poet simply wants to convey that both Bhima and Rājārāja were born enemies and that both of them belonged to the same family, i.e., the Chōlas, though of different branches.

A short poem, in grand diction, given in duplicate on the two pillars of victory at Mandasor (*GI*, pp. 142, 149) describes the triumphs of Yaśōdharman, including the humbling of the great foreign invader Mihirakula, 'who had never before that bowed his head in obeisance to any save the god Śiva.'

The Bhumarā pillar inscription (*GI*, p. 110) states that the pillar was set up as a boundary mark between the territories of the Mahārāja Hastin and the Mahārāja Sarvanātha and thus enables us to synchronize the families to which these two princes belonged.

The copper-plate charter consisting of only four lines of writing in the Brāhmī script of *circa* 3rd century B.C. recovered from Sohgaūrā in the Uttar Pradesh (*EI*, vol. XXII) contains a public notification of the establishment of two store-houses of fodder and grains for being used in times of urgent need, probably on the advent of drought or famine.

At one time it was thought that records of this type were very few. But it is not so. It may be true that when compared with the other inscriptions of donative and other varieties, such records are small in number; still there are many. The Vayalūr pillar inscription of the time Rājasimha giving a complete list of the Pallava kings upto that time (*EI*, vol. XVIII), the Gwalior *prāśasti* of the Paramāra king, Bhōja (*Ibid.*), the Nagpur *prāśasti* of the Paramāras of Malava (*Ibid.*, vol. I), the Kalachūri stone record from Kasia (*Ibid.*, vol. XVIII) are but a few to mention.

## 5. VARIETIES OF INSCRIPTIONS

The *Dharmaśāstras* classify the records into two (1) *rājakiyam* (royal or official) and (2) *jānapadam* (pertaining to the people). The latter is also sometimes termed as *laukikam*. Royal records are those issued by the kings themselves or by their subordinate chiefs or ministers. The other variety *jānapadam* are the private records of the common people.

The royal records are further divided, according to the *Dharmaśāstras*, into four classes, *śāsanam*, *jayapatram*, *aiṇāpatram* and *prajñāpanam*.

(1) We have already noted that the word *Śāsanam*, means a writ, edict, charter or instruction generally issued by a king or person in authority and that in mediaeval times it was used in the sense of a land grant.

The *Yājñavalkya Smṛiti* defines a *śāsanam* as follows :

“Having given a plot of land or made a permanent endowment the king should cause a record to be prepared for the information of the future good kings. The king should further cause a permanent writ to be made on a piece of cloth or copper-plate impressed with his seal and autograph and containing his genealogy, personal eulogy, the name of the donee, the quantity of the gift, the boundaries of the plot and the date of the deed.”

Accordingly all the charters registering land grants made by the rulers in olden days will come under this class. There is one main difference in the inscriptions registering such land grants between the earlier and later ones. The later ones, especially those of the Vijayanagara period, simply record the gifts straightway and are couched in the tenor of the gift-deeds of modern days thus becoming more or less the title deeds of the donees to the properties. But the earlier ones, especially those of the early Pallavas, are not so. They contain the orders issued by the king to the provincial governor or the local assembly of the province or other territorial division intimating him of the grant made by the king. The Tamil portion of the copper-plate grants of the later Pallava and the Chōla monarchs contains further details of the action taken by the assemblies on receipt of the royal orders. The members of the assembly on receipt of the orders went round the gifted land fixing its boundaries and put the same in

possession of the donee. The gift deed on copper seems to have been executed thereafter after approval by the officers of the departments concerned and issued affixing the royal seal. It will thus be seen that elaborate administrative details had to be observed in issuing the land grants of the kings incised on copper-plates.

(2) The second is *jayapatram* which is defined as follows : "Having himself gone through the legal procedure and listened to the expounder of law, the king should issue a legal decision for public information."

There are many inscriptions which refer to the disputes preferred by disputants and the decision by the king or his officers or by the assemblies on them. These disputes cover a wide range from the right of private enjoyment of a property to the social rights of a whole community.

A record from Paṭṭiśvaram in the Tañjāvūr district (No. 257 of 1927) dated in 1634 A.D. refers to a *valakku-muri* (dispute) among the weavers (*paṭṭunūlkkārār*) and the *ṣeṭṭis* (*ṣeṇiyar*) of the place regarding the order of precedence in the distribution of betel leaves and arecanut during marriages which was decided by the famous minister Gōvinda Dikshita.

Sometimes disputes, especially over civil rights, appeared to have dragged on without a final settlement. The *sabhā* of Śrīkaṇṭha-chaturvēdimaṅgalam and the *ṇr* of Tiruverumbiyūr had a boundary dispute of rather long standing duration. The solution was found ultimately by a local chieftain buying up the rights of both the parties in the disputed area paying prices that satisfied both and then handing over the land to the local temple as an endowment (No. 129 of 1914).

The various processes through which a dispute had to pass before a final decision was arrived at are not explicitly found mentioned in the records. But these can be pieced together from the references found here and there. It appears that both the parties to a dispute should deposit in advance with the authorities the amount of expenses to be incurred in hearing the dispute and deciding the same. This information which is gathered from literary sources is confirmed by a copper-plate record of the time of the Vijayanagara ruler Sadāśiva Mahārāya obtained from Kunrattūr in the Chingleput District, dated in Kali 4463 Parābhava, referring to a dispute between the temple *paṇḍāram* and the villagers on one side and the *mudanmaiyaṛ*

of the temple on the other side and the decision thereon wherein it is stated as follows : *samasthānam gajāṇāḱku kappamkaṭṭi jayāpajayam pannivārā nirukkura-kālattil*, (having paid the tribute into the state treasury and having preferred the dispute awaiting the success or failure in the same).

A record from Kīlaiyūr in the Tañjavūr district (No. 80 of 1925) dated in the reign of Kulōttuṅga Chōla III gives another instance. Two persons of the village were a public nuisance and a source of trouble to the inhabitants of the place. They were tried for rioting (*kalaham*) and incendiarism and together fined one thousand *kāśus* in accordance with a royal order of a general nature that in similar cases of rioting, incendiarism and so on, the amount of fine may go up to twenty-thousand *kāśus*. No one helped these two persons. So as ordered by the king the lands of these persons were confiscated and sold to the temple for one thousand and sixty *kāśus*, the extra amount of the sixty *kāśus* being treated as the penalty for the default in payment of the fine.

From the above we may have an idea of the procedure adopted in those days of administering justice and issuing judgments. Even copies of such judgments are not available to us in many cases.

A dispute between two priests, each of whom claimed the ownership of a particular plot of land for his god, is recorded in an inscription from Kitṭūr in the Karnataka country (*JBBRAS*, vol. IX). It contains interesting information about the trial by ordeal.

Another record from Śravaṇa Belgoḷa (*EC*, vol. II, *SB*. 344) mentions the settlement of a sectarian dispute in the days of the Vijayanagara king Bukkarāya, between the Jainas and the Vaishṇavas of the place. The record narrates how the ruler brought about a reconciliation between them and embodies a compact under which the Jainas were to enjoy equal freedom and protection with the Vaishṇavas in respect of their rites and processions.

(3) *Ājñāpatram* : "The document through which order is sent to the *sāmantas* (vassals), high officials of the state, provincial governors, etc. is the *ājñāpatram*."

Most of the early copper-plate inscriptions found both in the north and in the south mentioning the land grants made by the kings and called *śāsanas* are in fact orders issued by the king

to the provincial governors or local authorities. The Banskhera grant of Śrī Harsha (*EI*, vol. IV) runs as follows: "Harsha...issues commands to the vassal kings, police officers, officer in charge of land survey, the representative of the king, the prince councillor, the overseer, the district magistrate and the collector, the regular and the irregular soldiery, servants and others and the inhabitants that have assembled at Markaṭasagara, situated in the western *Paṭhaka* of the Āṅgadiya district in the Ahichchatra province."

Similarly the Hirahadagalli grant of the Pallava king Śivaskandavarman (*Ibid.*, vol. I) registering the gift of land to some Brāhmaṇas is an order issued to "our lords of provinces, *vatthas*, royal princes, generals, rulers of districts, custom-house officers, prefects of countries and others, to the free-holders of various villages, to herdsmen, cow-herds, ministers, foresters, *gumikas*, *tūthikas*, *neyikas*, and all others employed in our service, to roaming (spies) and warriors."

In fact almost all the grants made by kings of the Tamil country are recorded only as orders issued to local administrative assemblies on receipt of which such assemblies took action on them and executed the orders. Many of the Tamil inscriptions recording these transactions give at the beginning the royal order received *in extenso* and then proceed to narrate the action taken by the authorities to put them into effect, thereby repeating the main purpose of the grant or order two or three times in the same document, thus helping us sometimes to restore fairly accurately any portion of the epigraph that might have become damaged.

Occasionally, the copy of the royal order and the action taken thereon by the assembly are recorded as separate inscriptions.

(4) *Prajñāpanam* : "The deed which is proclaimed to the *ṛitvik* (sacrificial priest), the *purōhita* (minister in charge of the religious department of the state), the *āchārya* (preceptor), the *mānyas* (respectable persons) and the *abhyarhitas* (persons entitled or concerned) is the *prajñāpanam*."

This kind of document is very rare, not being intended for public information, but addressed only to some selected persons in consideration of their learning and the religious or social position they occupy.

Another variety of document, *prasādalekhyā*, is mentioned in the category of *rājakiya*. This is defined as "where the king, having

been satisfied with the service or heroic deed of a person, makes territorial or some other kind of gift through writing, that is *prasādālēkhyā*."

The supplementary inscription on the Ātakūr stone, dated 949-50 A.D. (*EI*, vol. VI) states that the Rashtrakūṭa king Krishṇa III gave to his brother-in-law and subordinate, the Western Gaṅga prince Bhūtuga II, the Banavase twelve-thousand province and the districts known as the Belgoḷa three-hundred, the Purigere three-hundred, the Kisukāḍ seventy, and the Bagenāḍ seventy, as a reward for his daring bravery in the fight on the *howdah* of the elephant with the Chōḷa prince Rajāditya which resulted in the slaughter of the Chōḷa in the battle-field at Takkōlam.

A second clause in the same gives another instance of a grant of villages in recognition of bravery in the battle-field to a hero who fought and survived.

And we also learn from this last record that grants of this kind were sometimes accompanied by the ceremony of washing the warrior's sword, just as religious grants were usually accompanied by the ceremony of laving the feet of the priest into whose hands the donation was actually given.

The Halsi copper-plate grant (*IA*, vol. VI) of the Kadamba king Kakusthavarmaṇ issued when he was *Yuvaraja* and in the eightieth victorious year, registers the gift of a field in the village named Khēṭagrāma, by the prince to the *sēnāpati* Śrutakīrti, as a reward for saving his life. This record incidentally states that the Kadamba kingdom had been established for eighty years then.

The *Jānapadam* or private records are described by Vyāsa in the *Smṛiti-chandrikā* in the following words. "The writer of a well-known place should write a private document, mentioning the royal genealogy, year, month, fortnight and day." Private documents were concerned with various kinds of transactions. The *Smṛiti* authorities required fixed forms for contractual and monetary transactions. Yājñavalkya lays down: "Whatever matter is decided by mutual consent that should be recorded with the names of the witnesses and that of the *dhanika* (monied or wealthy man.)"

It is these prescriptions which make even the private documents of historical importance and helpful in the reconstruction of dynastic history.



The *Arthaśāstra* of Kauṭilya distinguishes the following seven kinds of royal writs (*śāsanāni*): (1) *prajñāpana-lēkha* (public notification or writ of information); (2) *ājñā-lēkha* (writ of command, orders, official instructions); (3) *paridāna-lēkha* (writ of remission); (4) *niśrīṣṭi-lēkha* (writ of licence); (5) *prāvṛttika-lēkha* (writ of guidance); (6) *prati-lēkha* (writ of reply) and (7) *sarvatraga-lēkha* (writ for wide circulation).

The 'writ of information' is defined as an epistolary form of writing by which the person or persons concerned are informed of the contents of a message to be faithfully delivered with the words, 'Thus saith the king.'

The 'writ of command' is a form, which contains the king's orders, either for rewards or punishments particularly, meant for the officers and servants.

The third is meant for 'the bestowal of honour for deserving merit', either in the manner of a specific relief or as gifts.

The fourth denotes a form to be adopted in announcing to the classes of people or to the localities concerned certain special privilege (*anugraha*) by way of remission, granted in obedience to the king's orders.

This denotes rather a form meant for granting licence or permission by word or deed, which deserves therefore to be treated rather as a verbal order (*vāchika-lēkha*).

The fifth is a form meant for timely giving guidance as to how to provide against or ward off possible or impending calamities.

The sixth is to be adopted in sending a suitable reply to a letter in accordance with the king's orders.

The seventh and the last represents a form to be adopted in issuing general directions to all classes of official agents concerned in matters of general welfare and public safety.

It will be seen that this list of Kauṭilya is slightly different from that of the *Smṛiti* authorities referred to above. The definition of the variety *prajñāpana-lēkha* in these two sets do not agree. Evidently the classification of Kauṭilya was more practical and was in use in the administration in those days.

All the inscriptions found in the Tamil country can be satisfactorily grouped according to these classes. The *vāchika-lēkha*

mentioned above probably corresponds to the *tirumukha* or the *alai* issued by the officer *tiruvāy-k-kēlvi* after receiving the oral orders of the king during the days of the Chōla empire.

## 6. RELIGIOUS RECORDS

The great bulk of the epigraphic materials that have come down to us, it should be noted, was not prompted by any desire to record the past history, but by the religious side of the character of our fore-fathers. The *Dharmaśāstras* have come to lay down that in this Kali yuga, *dāna* or gift should be preferred to the *yajña* or sacrifice for merit. This has been mainly responsible for the desire of the people to make gifts and endowments on every possible occasion. That is how we have a large number of inscriptions registering such gifts and endowments.

In addition we have a few inscriptions issued mainly with a religious motive, but not making any endowment or gift. Some of the records of Aśoka were mainly directed to the propagation of religion and morality.

The rock and pillar edicts of Aśoka are found scattered about at various places of importance in his dominions and in other territories that were more or less subject to his influence. These have been recovered from Shahbāzgarhī near Peshawar (in Pakistan) on the north to Siddhapuram in Mysore, and Yerragudi and Rajula-Mandigiri near Karnul in the Andhra Pradesh on the south, and from Dhauli (near Cuttack) and Jaugada (near Ganjam) in the Orissa on the east to Girnar in the Saurashtra on the west. The object of them was to proclaim the firm determination of the king to govern his realm [righteously and kindly in accordance with the duty of pious kings and with considerateness for every religious belief even other than his own, and to acquaint his subjects with certain measures that he had taken to that end, and to explain to them how they might co-operate with him in his objects.

It is generally taken that the find-spots of his distant inscriptions mark the frontiers of his kingdom and those of the friendly kings of the neighbouring States mentioned by him including the traditional kingdoms of the Tamil country, and to whom he has commended his pious wish, thus establishing that even in those days, South India was independent.

One of his rock inscriptions which is available in various recensions in the North India as well as in the South states that the

record was framed when he was living in religious retirement as a fully admitted member of the Buddhist order at Suvannagiri, identifiable either with Kanakagiri, south of Māski and north of the ruins of Vijayanagara or with Jonnagiri in the Kurnul district. This record was issued to proclaim Buddhism as the true religion.

The several inscriptions found on the sacrificial posts or *yūpa-stambhas* recording the performance of sacrifices by kings in olden days also belong to the same category. Such records have not been recovered so far in the Tamiḷ-nāḍu; but they have been found in the other parts of the country, e.g., in the Andra - Pradesh and in the North.

In this connection it is worth noticing that similar inscriptions are also found in the islands of the South - East Asia, of which the Yupa Inscriptions of Mūlavarman of Borneo are well-known. These, written in the early Pallava script of the close of the fourth or early fifth century A.D., show that a king Mūlavarman by name performed Vedic sacrifices, made *gō-dānas* and gave *dakṣhiṇās* to Brāhmaṇas and bear an unmistakable testimony to the early spread of South Indian colonies in the east. (*JRASB. L*, vol. I)

The desire of Aśōka to honour the memory of the dead teacher Buddha prompted him to erect the Rummindēi Pillar in the Nēpal with his inscription. This record is of great interest as it localises the Lumbinivana garden, the place of Buddha's birth. The record states that the king visited the place in person when he was twenty years anointed and that because 'the Sakya saint' was born there, he built a stone enclosing and screening wall round the place, and set up a stone column (the one on which the inscription is written), and made the village Lumminigama free of certain taxes.

The desire to honour the memory of saints and teachers by enshrining relics of them in the *stūpas* and other edifices built specially for the purpose was also prompted by the religious motive. The records on the relic-caskets, of Kōtīputta Kassapa Gotta and Koḍinīputta-Majjhima and Gotīputta Dundubhissara from Sāñchī and Sōnarī (*JRAS*, 1905) strikingly confirm the account given in the *Dīpavamsa*, the Ceylon chronicle, of the missions that were sent out by the great priest Moggaliputta-Tissa, in the time of Aśōka, to establish the Buddhist faith in the border-lands.

The famous temple known as *Daladāya-p-perumpalli* 'the Great Temple of the Tooth Relic' of Buddha constructed at Polonnaruwa in Ceylon in the closing years of the reign of Vijayabahu at the beginning of the twelfth century A.D. was placed under the protection of the Tamil army known as the *Vēlaikkārar*, naming the temple after them. The construction of this temple to house the relic, the possession of which had in the meantime become the symbol of sovereignty of the island, and the Tamil inscription recording the above were also prompted by the same motive. (*EI*, vol. XVIII)

To religious motive alone, in the form of the desire to create new temples for worship by the devout, we owe the several inscriptions of the Pallava and Chōla monarchs. The earliest of them, the Maṇḍagappaṭṭu inscription of the Pallava king Mahēndravarman, comprising one Sanskrit verse in four lines of writing, mentions the creation of the temple for Brahma, Īśvara and Viṣṇu, without brick, without timber, without metal and without mortar (*EI*, vol. XVII). The joy experienced by the monarch on the completion of the first rock-cut temple in the Tamil country is clearly manifest in this short record. Incidentally this record also informs us that temples were previously built with brick, mortar timber and metal. As these were perishable in course of time, they came later on to be erected of stone.

There are many inscriptions recording such reconstructions. A record from Tirukkōdikkaval in the Tañjavūr district mentions the reconstruction with stone of the temple there by Śembiyan Mahādēvī, the mother of the Chōla monarch Madhurāntaka Uttama-Chōla (No. 36 of 1931) in the eleventh year of her son's reign and the re-engraving on the walls of the temple of the older inscriptions on loose stones found there. She has thus preserved to posterity as many as twenty-six inscriptions. This record incidentally informs us that previously when temples had been constructed of perishable materials, inscriptions were incised on loose stones and left or planted in the premises.

We have already noticed that the majority of the inscriptions registers donation made by the kings and his officers or by private persons to temples, *maṭhas*, educational institutions and to religious communities.

Endowments made to the temples are generally in the shape of lands, money or cattle for the purposes of burning lamps, conducting worship inclusive of specified services and festivals, feeding of ascetics

and others and for the upkeep of the premises including periodical repairs.

The cattle endowed to the temples included both sheep and cows and also bulls. Ninety-six sheep were considered as the unit required to furnish the ghee necessary for burning one perpetual lamp while in the case of cows, it was counted at thirty-two with the occasional addition of one bull to the same. These cattle were known as *śāvā-mūvā-p-ṭēr-āḍu*, having no death or senility, thereby implying that the specified number was regularly maintained replacing the dead and old ones with the young.

Special services were instituted in the temples by kings on the days having the natal stars of themselves as also of their spouses. Sometimes we find the subordinates making such endowments in the names of their sovereigns.

The chanting of the *Tiruppadiyam* or the sacred hymns to the accompaniment of musical instruments before gods Śiva and Viṣṇu during worship formed a regular feature in the worship. We find endowments for this service from the days of Parāntaka I. (Nos. 129 of 1914, 199 of 1915, 349 of 1918, 176 of 1923, etc.) There are also similar endowments for the recitation of the *Vēdas* and other sacred works in the temple during worship. (No. 123 of 1926).

Feeding of the *tapasvins* and other pilgrims who visit the temple for worship formed a regular feature in the management of a temple in those days and we thus find specific endowments, mostly in the nature of lands, made to the temples to meet this item of expenditure from the proceeds thereof.

A record from Kaḍattur in the Coimbatore District (No. 286 of this collection) dated in the 21st regnal year of the Koṅgu king Vikrama Chōḷadēva registers the gift of some lands to the Śiva temple there by Vikrama Chōḷa Tribhuvana Śiṅgadēva, an officer of the king, as his offering the god having cured him of the *meha* disease.

These endowments were generally placed under the control of the temple authorities and occasionally with private persons connected with or serving under the authorities of the temple. Sometimes they were also placed in charge of the *maṭhas* attached to such temples. An inscription from Kāvērippākkam in the North Arcot District (SII, vol. XII, No. 79) dated in the twentyfifth regnal

year of the Pallava ruler Nripatungavarman states that the gift of gold for lamps in the temple was placed in charge of the *maḍattu-saṭṭa-p-perumakkal*.

We have also records registering the endowments made to the *maṭhas* and other religious institutions.

The earliest inscriptions in the Tamil country found incised in the Brāhmī characters on the caves or caverns in hills have been interpreted as registering the donation of such caves to some religious recluses of either the Buddhist or Jaina faith.

The inscriptions of Aśoka and his grandson Daśaratha which are found in the caves on the Barabar and Nāgarjuni Hills in the Bihar (*IA*, vol. XX), were engraved to record the presentation of the caves to a community of the Ājīvika ascetics.

We have already referred (above p. 177) to the grants made by the Vijayanagara rulers to the *maṭha* of Śaṅkarācārya of the *Kāmakōṭi pīṭha* at Kañchipuram. There are many inscriptions registering gifts to the Śaiva *ācāryas* of the Lakshādhyaya *santāna* of the Gōlāki *maṭha*. Other *maṭhas* affiliated to Banaras, Kāshmir and other places also figure as the recipients of gifts and endowments.

We obtain an insight into the early history of the Vīra Śaiva faith, popularly known as the Līṅgāyat, prominent in the Karnaṭaka country, from an inscription from Ablūr in the Dhārwar District there (*EI*, vol. V; *IA*, vol. XXX) dated in the reign of Mahāmaṇḍalēśvara Kamaḍēva, the Kadamba ruler of Haṅgal (circa 1181-1203 A.D.). The record of the villages that were granted to Ekāntada-Rāmayya for the purposes of the Śiva Temple of Sōmanātha which he built there, narrates the great services rendered by him to the faith and discloses the real originator of the movement.

The Līṅgāyats, as also the Arādhyā-Brahmaṇas who more or less follow the same faith, worship at commencement of all important religious ceremonies the four *ārādhyas* invoking them in four-vessels filled with ceremonial water. The word *ārādhyā* would mean a 'person to be worshipped'. These four are Rēvaṇa, Marula, Ekō-Rāma and Paṇḍitarādhyā and they are said to have lived before the time of Basava. It is very likely that Ekāntada-Rāmayya of the Ablūr record is the name as Ekō-Rāma, the third of the four *ārādhyas*.

All the religious faiths are represented in the epigraphs as the recipients of the donations and endowments made by several persons. Of course the temples of Śiva and Viṣṇu figure largely in these; but the temples of other faiths also receive their share. The Leiden grants relate to the Buddhist temple Chūḍamañivarmavihāra built at Nāgapattinam by a king of the Śrī Vijaya kingdom of the Java islands and the gift of villages to the same by the Chōḷa monarchs on the representation of the foreign rulers. (*EI*, vol. XXII). These grants bear testimony to the relations between South India and Indonesian Islands in those days. Similarly the Jaina temples are endowed with lands for their upkeep. This becomes clear from the inscriptions copied at Chittamūr, Tirupparuttikkunram, and other places by the assistants of Col. Mackenzie and included in this collection. Recently an inscription dated in the eighteenth regnal year of the Pallava monarch Narasimhapōtavarman in characters of the eighth century A.D. copied from Kañchīpuram mentions the *Ājivaka-darśana* and the temple of *Arivar* (the All-knowing). (*Indian Archaeology, A Review*, 1954-55).

The desire of pilgrims to commemorate their visits to sacred and other important places has given us a number of records. Such votive inscriptions found at Sāñchī (*EI*, vol. II), and at Bharaut (*IA*, vol. XXI) are of considerable value in the geographical line of inquiry. This practice is even now observed at places like Tirupati and other hill stations of religious importance where devotees have their names and the dates of their visits incised on stone. From Tirukkalukkuṇram, the famous *Pakshi-tīrtha* in the Chingleput District, we get the names of some Dutch officers, together with the dates of their visit to the place in the seventeenth century A.D. (*ARSIE*, 1908, para. 79).

The memorials to the dead persons raised by their devotees or descendants should also be classified as votive records.

The earliest Tamil inscription from Tirunātharkunru (No. 239 of 1904) referring to the *niśīdhikai* of the Jaina *āchārya* Chandra-nandi who died fasting for fifty-seven days may be cited as a typical instance of this class. There are many inscriptions in the Kar-nāṭaka country referring to the death by *sallēkanā* of Jaina *āchāryas* and the erection of the *niśīdhikas* for them.

There are many *virgals* or hero-stones erected in memory of dead heroes, with inscriptions on them containing the names of the dead persons and the particulars of the raid or battle in which they lost

their lives. One record from Sennivaykkal, near Lalgudi, on a hero-stone bearing figure of a brahmana being pierced by an arrow near the neck, mentions the death of a brahmana-hero fighting in a raid by a Baṇa chieftain with the Sēvaṇa horses causing the destruction of a *maṭha* in the 21st regnal year of Nandivarman, 'who obtained the kingdom after defeating (his enemies at) Tellaru.' (*SII*, vol. XII, No. 56) This record is very important for the history of the Tamil country during the tenth century A.D. as the names of the Chōla king Parāntaka I and his son Ariṇjaya occur in it.

Inscriptions registering the self-immolation of a woman on the funeral pyre of her husband also belong to this class. In 1057 A.D. a man killed a relative of the king in a wrestling contest, and was sentenced to death; his wife, Dekabbe, the daughter of a chieftain of Nunganād, followed him in spite of violent opposition from her parents, and the whole story is recorded in the form of a pathetic Kanarese poem in the *kāvya* style. (*EI*, vol. VI, pp. 213-9; *EC*, Vol. IV, Hg. 18). In another inscription of the time of Virarājendra from Elavanāśūr in the South Arcot District (No. 156 of 1906) a woman committing *sati* was said to have averred that if she lived after the death of her husband, she should become the slave of the other wives of her husband and uttered imprecations against those who sought to persuade her to refrain from immolating herself, nay even against people who did not come forward to bind and throw her into the fire. These records on the *sati*-stones, known also as *māsattikkal*, were incised by the descendants or followers of the women as votive offerings to the brave women whose acts were viewed as very pious, acquiring great merit.

From Śrīraṅgam comes an interesting record (No. 788 of this collection; also No. 87 of 1937) mentioning that a devotee of the god fell from the gōpura and sacrificed his life as a protest against lapses in worship in the temple, and that when worship was restored certain temple honours were shown to (the effigy of) this person.

## 7. SECULAR RECORDS

There are a large number of inscriptions bearing on the corporate life and worldly aspects of the society, economic and social life of the people and also on the person and property of the individual.

Two Tamil inscriptions of the time of the Chōla ruler Parāntaka I from Uttaramērūr in the Chingleput District (*ASIAR*, 1905) contain detailed instructions adopted for the election of members to the *sabhā*



and its *vāriyams* or committees by the method of ballot (*kudavōlai*) and the qualifications prescribed necessary for such contestants. Similar inscriptions are found in many other places and these throw a flood of light on the constitution and working of these institutions. A like record from Sittamalli near Muttuppēṭṭai in the Tañjavūr District (No. 5 of 1946) registering the regulations (*vyavasthai*) framed by the *sabhā* of the Śuddhamalli chaturvēdi-maṅgalam, in the time of the Chōla ruler Adhirājendra, contains astronomical details of the day when the above resolution was made.<sup>1</sup> This casual mention of the date is very important for the Chōla history as, it elucidates some crucial problems.

The existence of similar assemblies called *ūr* for agricultural or ryotwari villages and *nagaram* for mercantile cities is also brought to light from the epigraphs. Sometimes, we also find, two or all the three assemblies co-exist in the same village, looking after the interests of each.

The organisations known as the *Chitramēli-p-Periya-nāṭṭavar* composed mainly of agriculturists, the *Nānādēsi* or *Tisai Āyirattu-aiññūrruvar* composed of merchants or traders in many lands and the *Rathakāras* composed of artisans like the carpenters, stone-masons, smiths, etc. also existed embracing the areas of more than one realm.

A perusal of the epigraphic materials obtained so far will reveal the large extent to which religion had permeated in the life of the people, both individually and socially. Thus many acts which we now consider as purely within the orbit of the society and its welfare were in those days treated as pious ones bringing in merit in the after-life. It is very difficult to separate religion from the everyday life of the people.

There are a large number of records referring to the carrying out of public works. The famous Tālagunda inscription of the time of the Kadamba king Kakusthavarman is primarily intended to record the construction of the great tank there. Incidentally the eulogy contained therein in grand *kāvya* style by way of introduction, recites the origin and rise to power of the early Kadambas of Banavase (*EI*, vol. VIII). The fine rock inscription

---

1. This is being edited for the *Epigraphia Indica* and will appear in one of its forthcoming issues.

at Junāgadh (*Ibid*) of the Kshatrapa ruler Rudradāman also belongs to this variety. It records the repairing of the embankment of the great lake Sudarśana. Incidentally it narrates how the lake was originally made by a governor of the Maurya ruler Chandragupta and had been embellished by a governor of Aśoka. Another inscription there records similar repairs carried out to the same tank in the days of the Gupta ruler Skandagupta (*GI*, p. 56).

A record in Tamil verse from Erukkaṅguḍi in the Ramanāthapuram District (No 334 of 1930) dated in the reign of the early Paṇḍya monarch Neḍumaraṇ Śrīvallabha refers to the various benefactions to the public of the Paṇḍya country, in the shape of digging new tanks and repairing the existing ones, made by Eṭṭi Śāttan on whom the title Iruppaikkūḍi-k-kiḷavan, was bestowed by the king. There are many similar inscriptions throughout the country.

A few inscriptions mention the establishment of water-sheds (*tannir-p-pandal*) to serve cool water to wayfarers and the thirsty in the hot season and the endowment made for meeting the expenses thereof including the wages for the persons employed to serve the water.

These acts, though in the nature of public welfare ones, were mainly prompted by the religious fervour of the donors.

A Tamil inscription (No. 333 of 1917) of the time of Rājendra Chōḷa I from Eṇṇayiram in the South Arcot District mentions that the *sabhā* of Rājaraḷachaturvēdimangalam (Eṇṇayiram) resolved in the presence of an officer of the king's government to arrange for the feeding of pupils and the remuneration of the teachers of a college, in accordance with the terms of an order made by the king himself. Provision was made for 270 junior and 70 senior students with a teaching staff of fourteen persons. That a similar college with 260 students and twelve teachers existed at Tribhuvani, near Pondicherry, is evident from another record (No. 176 of 1919).

At Tirumukkūdal near Kāñchipuram, there existed during the days of Virarājendra Chōḷa a college and a hospital, the expenses of which were met from the revenues of the local temple of Mahaviṣṇu. The inscription (*EI*, vol. XXI) dated 1067 A.D. containing this information gives a very detailed account of the entire budget of receipts and expenses of the temple.

The gifts made to individual persons like the learned brāhmaṇas were also prompted by the religious fervour of the donors. Most of the copper-plate grants belong to this class.

A Prakrit inscription on a pillar at Maḷavalli in the Shikarpur taluk of Mysore (EC, vol. VII, SK. 263) registers the gift of a group of villages to a Brahmana by the king Hāritiputa-Vinhukaḍa Chuṭukulananda Śatakamni of Vaijayanti. Another Prakrit document written in continuation of the above on the same pillar, (*Ibid.*, No. 264) of the Kadamba ruler Siva[kadha]varman of Vaijayanti renews the grant confirming the gift of the above villages to the descendant of the original grantee. This inscription in a way is useful in fixing the upper limit for establishment of the rule of the Kadambas at Vaijayanti.

The functions of the several component parts or classes of the society as a whole were strictly regulated according to the *Dharmaśāstras* and there are many inscriptions testifying to the same. A record from Uyyakkonḍān-Tirumalai in the Tiruchirappalli District (No 479 of 1908) of the time of the Chōla rule registers the decision of the *bhaṭṭas* of Rājāśraya-chaturvēdimāṅgalam in accordance with the *śāstras* on the professions to be followed by the members of the *anulōma* caste of Rathakāras.

An inscription from Viriñchipuram in the North Arcot District (*SII*, vol. I, 82) embodies an agreement stating that the brāhmanas of the Paḍai-vidu-rāja should perform the marriage of their daughters only as *kanyādāna* and that any father accepting money and any bridegroom paying money for his bride should be subject to punishment by the king and excommunication from caste.

The social status of the several classes and the privileges to which they were entitled figure prominently in some of the records. It will be seen therefrom that almost all classes clamoured for higher status and to gain this end even fabricated mythical origins for them. A record from Uṭṭattūr in the Tiruchirappalli District dated in the fortieth regnal year of Kulōttuṅga III (No. 489 of 1912) gives the earliest account so far known of the beliefs of the *Iḍaṅgai* classes regarding their origin. They claimed to have been created from the *agni-kunḍa* for the protection of the sacrifice of Kaśyapa, and to have settled in the Chōla country having come as bearers of umbrellas and sandals in the train of large colony of the Brahmins imported from the *Antarvēdi* region by the monarch. They got lands in five villages (now in the Tiruchirappalli District) and lost the memory of their origin which they claimed to have recovered with the aid of the *śrutimāns*. (*ARSIE* 1913, para. 89).

From Karuvūr in the Tiruchirapalli District and Pērūr in the Coimbatore District were obtained records of the time of a Koṅgu Chōḷa ruler registering the privileges accorded to the *kaṇmāḷars* of Veṅgala-naḍu and Ten-Koṅgu and to other artisans elsewhere. These privileges included the blowing of two conches, the beating of drums and so on at the domestic occurrences good or bad, the use of shoes when they went out, and plastering the walls of their residences with lime plaster. The construction of houses with two storeys and with double doors is also mentioned together with the right to decorate the front of their houses with garlands of water-lilies. Inscriptions of 1623 A.D. from Ambāsamudram and Brahmadēśam in the Tirunelvēli District (Nos. 309 and 378 of 1936) record the orders of Muttu Virappa, the Nāyaka ruler of Madurai, prohibiting the five such divisions of the Kammaḷar (artisan castes) from communal fellowship (*uḍan-kūṭṭam-vēṇḍam*). Maṅgammāl, the queen regent of the same place, is said to have granted a *cadjan śāsanam* in 1705 A.D. authorising the Paṭṭunūlkārars, i.e., the Saurāshṭras of Madurai to follow the rites prescribed for the brāhmaṇas in regard to *upākarma* (the ceremony of the renewal of the Sacred Thread). (R. Sathyanatha Aiyar, *History of the Nayakas of Madura*, p. 256)

We have already referred (above, p. 191) to the settlement of a dispute among certain classes of weavers at Paṭṭiśvaram in the Tañjavūr District about the order of precedence for receiving betels in marriages.

The endowments made to temples for the burning of lamps, twilight or perpetual, either voluntarily or forced by the authorities in expiation of sins committed should also be treated as belonging to this variety.

A record from Śīyamaṅgalam in the North Arcot District recites how a certain individual by mistake shot with an arrow a man belonging to his own village; whereupon the *nāṭṭavar* and the Sambuvarāyar assembled together, and decided that the culprit should not die for the offence committed by him through inadvertence, but should burn a lamp in the temple of Tūṇaṇḍar there; and accordingly he provided sixteen cows, from the milk of which ghee was to be prepared, to be used in burning the lamp. (SII, vol. VII, No. 68).

Another record from Tiruvotūr in the same District states that a man went hunting, and missed his aim, and shot

another man whereupon, the people of the several *nāḍus* assembled (*pannāṭṭār tiranḍu*) and decided that the culprit should make over sixteen cows to the temple for burning a lamp. (*SII*, vol. VII, No.85)

There are also records registering the sale of persons as *aḍimai* or slaves. Most of the sales recorded in inscriptions are in favour of temples or *maṭhas*. An inscription from the Tañjavūr District (No.218 of 1925) registers the sale of two ladies and their dependants and relatives to the temple. Sometimes the religious motive must have been the cause in some of the transactions recorded. An inscription of the time of Kulōttuṅga I dated in 1088 A.D. states that some *dēvaraḍiyār* of the temple of Kaḷahasti who had been wrongly appropriated to the palace service were ordered by the king to be restored to the temple; these persons had been stamped with the royal seal which was erased and the trident stamped on their bodies in token of their servitude to the temple (No.230 of 1921). In times of famine, destitute persons escaped death by literally selling themselves and sometimes their unborn descendants for their upkeep.

Many records relate to the transactions pertaining to the ownership of private properties.

An undated record (No. 309 of 1927) from Uḍaiyālūr in the Tañjavūr District mentions that the title-deeds of persons in the village relating to their properties were lost in a commotion (*kshōbam*) which took place in the fifth year in the reign of the Chōla monarch Rājarāja III and that in consequence the rights had to be regulated in accordance with the position that obtained up to the fourth year of the reign. Another record from Talaich-chaṅgaḍu (No. 213 of 1925) in the same District dated in the 19th regnal year of the Rājarāja III states that the title-deeds had to be issued to the residents who were in the enjoyment of the lands (*anubhōga-p-parroḷugu*) as the old registers had been lost in the disturbed state (*duritaṅgal*) of the country in the fifth year of his reign. These clearly show that in the fifth regnal year of Rājarāja III (1220-21 A.D.) there was a serious commotion in the Chōla country which caused damage both to men and properties.

A stone record (No. 42 of this collection) from the temple of Virāṭṭānēśvara at Kīlur in the South Arcot District dated in the 24th regnal year of Kulōttuṅga III registers the exchange of lands belonging to the temples of Viṣṇu and Śiva at Tirukkōvalūr, effected in the names of Sēnapati-ālvār and Chaṇḍēśvara on behalf of the gods respectively. It will be clear therefrom that the affairs of the Śiva temple

came to be conducted in those days in the name of Chaṇḍēśvara while those of the Viṣṇu temple were transacted in the name of Sēnāpati āḷvar or Viṣhvakṣēna.

An inscription from Tirumālpuram in the North Arcot District (SII, vol. III, No. 142) dated in the 14th regnal year of Madhurāntaka Uttama Chōḷa contains the course of a transaction during the period of nearly one century. The village Śīrriyārūr had been granted as a *dēvadāna* and *brahmadēya* in the 21st regnal year of Āditya I to the *sabhā* of Puduppakkam. Though a *śāsana* was drawn up in the next year, the village was not entered in the accounts as such. This mistake was rectified in the 4th regnal year of Parāntaka I and the *sabhā* of Puduppakkam was remitting the produce and the gold due from them to the temple authorities. In the 36th regnal year of Parāntaka I the dues from Puduppakkam were increased as the result of a fresh grant; but the village assembly did not remit the new items properly. The temple authorities lodged a complaint to the king Uttama Chōḷa when he was at Kāñchipuram, who after due enquiry fined the village assembly and restored the grant to the temple.

An inscription from Śīraṅgam (No. 31 of 1937) dated in the 11th regnal year of Kulōttuṅga I registering the decision of the *sabhā* of Rajamahēndra-chaturvēdimāṅgalam remitting the taxes on certain lands belonging to the temple of Mummuḍi-Śōḷa-Viṇṇagar Āḷvar of their village for the consideration of a lump sum of seventy *kalañju* of gold contains an interesting piece of information. It mentions "that in the second regnal year of the king there was a clash between the Right-hand and Left-hand communities, in which the village was burnt down, the sacred places destroyed, and the images of the deities and treasury in the temple looted. Hence as the village had to be rehabilitated, the temple renovated and reconsecrated and new walls had to be constructed for the *prākāra*, the *sabhā* took a loan of fifty *kalañju* of gold which is stated to have been half a carat less in fineness than the *Rājarāia-Śōlan-māḍai*, from the temple. The interest on this accumulated to twentyfive *kalañju* in one year and out of the total seventyfive *kalañju*, five *kalañju* was spent towards the renovation and reconsecration of the temple in third regnal year and the balance of seventy *kalañju* was utilised in purchasing and making tax-free some specified lands for the upkeep of the temple." This shows that the temple acted in times of need as the bank for meeting the expenses of a public nature.

On the margin of this record on stone, it is inscribed that 'this *Kalvēṭṭu* (epigraph) belongs to Rajamahēndra-chaturvēdi māṅgalam'

which village is to be identified with a place some forty miles away. This is one of the instances where the inscription relating to one village is found engraved in another village.

### 8. SPURIOUS RECORDS

We have already seen that the bulk of the inscriptions recovered so far are in the nature of title-deeds to persons or institutions for the enjoyment of certain privileges or properties and as such they are very valuable to the holders of these rights or privileges for enjoying them. Thus the very nature of those records makes it possible for some persons in irregular enjoyment of rights to which they are not legally entitled to forge and create such documents in support of their claim. It should not therefore be taken that all inscriptions are genuine and therefore quite dependable for the reconstruction of our history. In fact we have some spurious documents.

It is usual for kings of old whenever they conquer and annex new territories to their own, to appropriate all grants made by the previous rulers and re-issue them in their own names. On such occasions the new king would not renew all existing grants automatically. The case of every one of them would be gone into individually or in groups and orders for re-grant issued only for the cases thought fit or necessary in his view. At that time every holder of some right or privilege which he wanted to renew would have to prove his title for the same by documentary and other evidences as required. Where a person does not have any much document in support of his claim, but wants that his enjoyment should not be interrupted, might have recourse to the creation of such documents.

There are many inscriptions which clearly state that the grants made by previous rulers had been expropriated in the middle by foreign rulers when they occupied the country and were later on restored or granted afresh by later kings.

The Vēlvikkudī grant (*EI*, vol. XVII) of the Pāṇḍya monarch Parāntaka Neḍuñjaḍaiyan issued in the latter half of the eighth century A.D. states that the grant village was originally gifted to an ancestor of the donee by a previous monarch, Palyagaśalai Mudra kuḍumi-p-Peruvaludi. The village was in the enjoyment of the family for a long period when it was expropriated by the Kaḷabhras who occupied the country in the meanwhile. Long after the restoration of the Pāṇḍyan monarchy a descendant of the original donee petitioned to the then reigning monarch and on his proving his contention with the necessary documentary and other evidences, the

king bestowed once again the village on the petitioner tax-free and issued the copper-plate charter for the same. It will appear from this that the grant contains the history of the village for a period of five or six centuries.

The Nausāri plates dated in 915 A.D. (*JBBRAS*, vol. XVIII) of the Rāshtrakūṭa king Indra III state that on his accession to the throne, he not only performed the *tulābhāra* ceremony, but also gave away four-hundred villages which had been expropriated by previous kings. Similarly the grants of the Western Chālukya ruler Vikramāditya I mention that he renewed the grants to the *brāhmaṇas* and the temples which had been interrupted in the days of the Pallava occupation of country by Narasimhavarman I after defeating the former's father Pulikēśin II.

Whenever a king makes a grant he always wishes that the donee should enjoy the gift for all time to come irrespective of any political change that might happen in the country. As such it is usual to find in every grant the statement added that the grant has been granted '*chandrādityavat*', i.e., 'for so long as the moon and the sun endure' and also, set verses requesting future kings to honour the grants made by him; but this sometimes does not appear to have been respected, especially when there was a dynastic revolution.

We find the creation of spurious documents from very early times. The Madhuban plates of Śrī Harsha of Kanauj dated in 631-2 A.D. mention that a Brahmana had been enjoying the village Sōmakunḍika on the authority of a *gudha-śāsana* (spurious deed) and that the king removed the village from his enjoyment and gifted it to some other Brāhmaṇas (*EI*, vol. IV). Similarly another stone inscription from Tarachandī states that some Brahmanas were enjoying some lands on the authority of a *gudhāmbara* obtained from one of the officials of Vijayachandra, king of Kanauj, and that Mahānāyaka Pratāpa issued instructions that credence should not be given to such a spurious record and that the rents and taxes due for the lands should be collected as usual.

These *gudha-lēkhas* are also mentioned in the *Dharmaśāstras* which prescribe the maximum penalty of death on the perpetrators. Detailed instructions for the *Lēkhya-parīkshā*, examination of such documents, are also found there. But it should be noted that strictly applying the above canons many of the available epigraphs may not satisfy these rules. This is probably due to the fact that conditions of drafting such records varied from place to place and from time to time,



But one thing has to be remembered. Spurious documents are very small in number and negligible when compared with the great bulk of genuine documents obtained. Still they attract the special attention of scholars by their very nature.

These spurious documents, small in number, are mostly copper-plates. They are very rare on stone. We may even say that no spurious record incised on stone has been recovered so far. An inscription on copper or any other metal can be prepared secretly very easily. But a forged document cannot be incised on stone likewise. Stone inscriptions are generally engraved on the walls of temples or on some public places and it will be very difficult to incise a forged one there without drawing public attention.

A Tamil inscription (No. 127 of 1908) engraved on the walls of the Śiva temple at Tirupputtūr in the Rāmanāthapuram District contains interesting information in this respect. Dated in Śaka 1309 (1387 A.D.) it registers the sale by the assembly *mūlaparishad mahā-sabhā* of the hereditary right of the accountant of the village under the following circumstances. The previous accountant who was not entitled to certain specified rights and properties in the village conspired with a goldsmith and with the help of a stone-mason stealthily got engraved on the walls of the temple a spurious document for such rights as having been assigned to him by the *sabhā*. But this became known and the accountant ran away. The goldsmith and the stone-mason were handed over to the *kaṇmālar* who 'destroyed' (*aliya-ch-cheydu*) the two culprits and made suitable amends to the *sabhā*. The rights of the absconding accountant together with the privileges due for the post were then (confiscated by the *sabhā*) and sold to some others.

A close examination will easily expose spurious documents as such. An elaborate technique has been evolved in the drafting and execution of these documents and any false step in these details is sure to betray the spuriousness of the same. The experience gained by the examination of the epigraphs so far has also set some specific tests to determine the genuineness of a grant.

The size of the plate and the shape of the characters employed therein varied according to the place and the period of the issue of the grant. The *Dharmaśāstras* have prescribed that the genealogy of the donor should be given for three generations and in later grants it is found given for the entire family with the full *praśasti*. The date on which the grant was made is expressed sometimes in

the regnal years and sometimes in some wellknown specific eras, occasionally coupled with other astronomical details. Generally the grants are made on some auspicious or important occasions like the eclipses, etc. And finally there is the phraseology of the document which varied with the locality and period of its issue.

The creators of spurious grants would generally imitate the model of a famous king wellknown for his munificent gifts. So, they would adopt the *praśasti* of the king as found in his genuine grants and then record the particular gift for which they claimed a right. In such documents it is only the grant portion that is spurious, while the *praśasti* portion, though clearly a forgery, does not happen to be a new creation, but only a copy of some other existing document.

We have a few copper-plate characters of the Western Chālukyas of Vatapi which are clearly spurious and written on copper nearly six-hundred years later than the period to which they purport to belong. Still they are not discarded completely, but are treated as of some value.

Occasionally we also find inscriptions which purport to be later copies of originals and not the originals themselves. It is possible that in taking copies of the originals and re-engraving them, some mistakes might have happened either through inadvertence or ignorance. This is best explained by the Konnur inscription from Dharwar District (*EI*, vol. VI) which purports to be the reproduction of a charter dated 860 A.D., of the Rāshtrakūṭa king Amoghavarsha I. The record on stone states that it was embodied in that shape in accordance with a copper-plate grant that was read and explained by a certain Jaina teacher Viranandin, son of Mēghachandra in the twelfth century A.D. But it is clear that either he did not read it correctly or interpreted it wrongly as there are glaring mistakes in the genealogical portion of the record.

It is possible that these mistakes are either intentional or due to ignorance and other causes. I have got the ink-impression of a copper-plate inscription obtained from Kunrattūr in the Chingleput District. The plate is shaped like those of the Vijayanagara period, but contains an eye-copy of three Tamiḷ records of the time of the Rāshtrakūṭa king Kṛishṇa III and also disjointed portions of a Chōḷa *meṃkīrtti*. Still it looks suspicious.

It is seen that such spurious documents have come into existence even in recent times. The Suradhēnupura copper-plate grant pur-

ported to have been issued in 807 A.D. in the days of the Western Ganga monarch Sivamāra II, was according to L. Rice the Director of Archaeological Researches in the Mysore State, created in the last century for production before the Inam Commissioner.

The Asiatic Society of Bengal has got a curious copper-plate document in its library. It does not mention any land or other grant, but narrates a battle said to have taken place in North India with a Muslim power in 1317 A.D. The document is written in the Brāhmī characters prevalent during the days of Aśoka in the third century B.C., described therein as the *Pālī* script. We know that Pālī is not the name of a script, but of a language. The document is composed in the Sanskrit language which was not used in the inscriptions in the days of Aśoka. The numerals used therein are modern and the proper names are found mentioned in the corrupt form which came into popular usage after the advent of the Europeans.

## 9. WRITING MATERIALS.

The materials on which inscriptions have been recorded are many and varied, their selection depending mainly on two factors, the nature of the documents and the availability of suitable materials. Copper and stone are the most common; but they are not the only ones. These materials are of two categories, metals and other substances than metal.

### A. Metals

Among metals, apart from copper which is largely used, gold, silver, brass, bronze and iron have been used as writing materials.

1. *Gold*: The Buddhist *Jātakas*, e.g., *Ruru-jātaka*, *Kurudhamma-jātaka*, etc., mention that important family records of wealthy merchants, royal edicts, poetic verses and moral maxims were incised on gold. Evidently stories give an idealised picture of society; gold, being costly, was rarely used for writing, except for ceremonial or religious purposes. We find charms and amulets with *yantras* or magical designs and letters written on gold plates even today. A gold plate with a votive inscription in *Kharōṣṭhī* has been discovered in the Buddhist Stūpa at Gangu near Taxila. (C. ASR, vol.II, 130). Two leaves of gold inscribed with a Buddhist formula and a Pālī verse in characters of the 4th or 5th century A.D. have been found at the village Hmazwa in Burma, (*EL*, vol.V). A treaty between the king of Ava in Burma and the Portuguese was written on a leaf or plate of gold enclosed in an

ivory box. (*ESIP*, p.93). It is also recorded, that the king of Vijayanagara (Krishnadēvarāya) sent in 1514 A.D. to the Portuguese chief at Goa a letter written on a plate of gold. (*Ibid*, p. 90).

2. *Silver*: This metal, not so costly as gold, may be said to be somewhat more popular than gold. A short record on silver has been recovered from the Buddhist Stūpa at Bhaṭṭiprōlu in the Krishna District. (*ASSI*, vol. VI). Another has been discovered at Taxila. (*JRAS*, 1914, p. 975; 1915, p. 192). There is also a record, apparently dedicatory, on a small disc recovered from a Stūpa at Manikiāla near Rawalpiṇḍi. (*C. ASR*, vol. II, 160). Burnell mentions a small Pali manuscript of recent date from Ceylon, written on silver plates in the British Museum. It is also said that the British Museum has manuscripts written on gilt and silver-plated palm-leaves.

The grant of Nagapaṭṭinam (Negapatam) to the Dutch by Vijayarāghava, the last Nāyaka ruler of Tañjavūr, written on a single plate of silver in Telugu and another grant of Ekōji, the first Mahrāṭṭa ruler of the same place, confirming the above in 1676 A.D. written likewise on silver in Tamil are reported to be in the Museum at Batavia. There is also a document written on plates of silver granting certain privileges and making some gifts to the queen and sons of Śīraṅga, the last Vijayanagara ruler, by Shivaji, the founder of the Mahratta empire.

3. *Brass*: This was seldom used for writing independent inscriptions, even though we have small records on the pedestals of big brass statues or on the back of small ones. From the neighbourhood of Gaya, we have a brass image of the Buddha, with an inscription on its pedestal mentioning the image as a votive gift. This is of special interest as it presents a specimen of the 'nail-headed' alphabet. (*IA*, vol. XIX, p. 77). From the former Chambā state were obtained some brass images bearing inscriptions which give the names both of the kings who caused them to be made and of the workmen who made them. (*C. ASR*, vol. XIV, pl. 28; *ASIAR*, 1902-3, p. 242.)

An inscribed seal-ring in brass, apparently of the Gupta period, has been obtained from Kōsam near Allahābād. (*C. ASR*, vol. X, pl. 2). A brass relic-vase with an inscription of Huvishka, was recovered from a Stūpa at Wardak in Afgānistān. (*CII*, vol. II). In some of the Jaina temples on the Abu mountains, are still found brass plates with religious formulas inscribed thereon.

4. *Bronze*: This also like brass was rarely used for independent writing. We have some fine specimens of bronze stamps or dies for making seals and one of them is of particular interest as it has its legends in three scripts, Brahmi, Kharōṣṭhī and Greek. (*JRAS*, 1901; 1905, p. 814, pl. No. 20.) A bronze head obtained at Peshāwar, bears round its base a record probably marking it as a votive offering. (*JASB*, 1836, 484). From Nagapaṭṭinam were obtained several bronze images of the Buddha having inscriptions on their pedestals in Tamil.

It is considered that the majority of the seals attached to the copper-plate grants should be held to be of bronze instead of copper, as casting in the latter would hardly have bought out the details of the devices and legends.

5. *Copper*: By far, the largest number of inscriptions incised on metal are on sheets of copper of varying sizes and number. They range in size from about  $2\frac{1}{2}$  inches by  $1\frac{7}{8}$  inches in the case of a small and very early record obtained from Sōhgaurā (*JRAS*, 1907) to as much as about 2 feet 6 inches square in the case of a record of the time of Kanishka obtained at Sui-Vihar (*CII*, vol. II).

Some of the earlier records on copper were commemorative or dedicatory, and were deposited inside the mounds or erections. But the more common and later ones were, as already pointed out, donative charters becoming the title-deeds of the property and thus passed, as soon as they were issued, into private personal custody.

These vary greatly in the number of leaves, in the size and shape of them, and in the arrangement of the records on them, according to the length of the individual records and also according to the custom or fashion prevalent: The plates were fashioned on the size of the writing material commonly used in the area. In South India we find they were shaped on the model of palm-leaves and imitated the length and narrowness of those leaves. In North where the birch-bark was the model, the breadth of the copper-plates increased and they were made almost square in size. Even in the South, the records of the Vijayanagara rulers were generally fashioned on the northern models.

The number of plates required depended on the content of the document. In some cases a single plate was used; and it was inscribed sometimes on only one side of it, sometimes on both. More often, however, more plates than one were used; and the majority of the multi-plate documents come from the South. The biggest copper-plate records so far discovered belong to the rulers of the Tamil country. The

Larger Leiden grant of Rajaraja I has twentyone plates with four hundred and fortythree lines of writing (*EI*, vol. XXII). The Tiruvalaṅgaḍu plates of Rajendra I comprise thirtyone sheets which, together with the massive ring, weigh 7,980 *tōlas*, containing eight hundred and sixteen lines of writing (*SII*, vol. III). But the biggest copper-plate grant so far discovered is the Karandai plates of the same monarch having fiftyfive sheets with more than two-thousand five hundred lines of writing. These plates measure  $16\frac{1}{2}$  inches by  $9\frac{1}{2}$  inches each and together weigh, even without the seal ring, 8645 *tōlas*, (*Ancient India*, No. 9, p. 219).

Where a grant contains more plates than one, they are used to be strung, passed through holes made in the middle of each plate generally at the left with a ring, the ends of which are soldered and affixed with the royal seal. In cases like the Karandai grant where the plates are too many to be strung with a single ring, sometimes additional rings are used and occasionally we also find the royal seal attached to a separate ring.

In the grants having more plates, the outer sides of the first and last plates are usually blank and the inscription commences only on the inner side of the first plate and ends on the inner side of the last plate. Occasionally where the inscription ends on the outer side of the plate, an additional plate blank on both the sides is added at the end. These are probably intended to protect the writing. Further, the rims of the plates are usually thick and raised to ensure the same.

The writing generally runs parallel to the broadest side of the plate where the grant is modelled like the palm-leaf and through the breadth where it is shaped like the birch-bark. Usually the plates are first hammered into the required shape and then the writing incised with a sharp instrument. Normally the inscription is traced on the plate with some legible material and then chiselled or incised on the same. Where mistakes are found after incision of the writing such portion is hammered out to obliterate the previous writing and written afresh. Sometimes the earlier writing is not completely erased and is visible in places. Such palimpsest plates are even now available.

There are instances where the letters are formed by puncturing a row of dots instead of lines. (*EI*, vol. IV, p. 56). There is also a single instance in the Sohgaūrā plate, of the plate being cast in a mould of earth into which the letters together with the emblem had been previously scratched with a stilus. Thus on that plate both the letters and the emblem appear in relief.

A poet, while describing the boundless liberality of the king, his patron, mentions the dearth of copper that resulted from the issue of innumerable copper-plate grants by the king. (Ballala's *Bhōjaprabandha*). Considering the great bulk of the copper-plate grants of the Chōla monarchs, we have to admit that the above statement is not entirely without foundation. This is further confirmed by the fact that we have some inscriptions on copper-plates which had contained earlier records. In a copper-plate grant of the time of the Vijayanagara ruler Dēvarāya II obtained from Nūtimadugu, one of the sheets contains a portion of the Eastern Chālukya *prasaṣti* written in the Telugu characters of the 10th century A.D. (*EI*, vol. XXV).

Such records were very valuable to the donee, as their loss made the tax-free gift lands in his possession liable for taxation unless fresh grants could be secured from the authorities in respect of the land in question. The copper-plates were therefore preserved carefully, sometimes in cells built of brick and mortar, or stone coffers or earthen jars hidden underground. Photographs of an earthen pot containing some copper-plates buried underground and recovered from Andhāvaram are illustrated in *Ancient India*, No. 9, plate CV.

Though inscriptions on copper are more common in the shape of plates or leaves, they are found in other shapes in the nature of a souvenir such as plough, battle-axe and the like. I have seen a Tamil record relating to the organisation known as the *Chitramēli-p-Periyanāṭṭavar* inscribed in characters of the 13th or 14th century A.D. on a miniature copper-plough, the emblem of that organisation.

A casket in the form of a miniature *stūpa* with its *harmikā* and umbrellas of the conventional shape and almost perfect in every detail, made of copper with an inscription in the Kharōṣṭhī script punctured on the four sides of the square base recording the enshrinement of the bodily relics of Holy Śākya-muni has been recovered from Kurram near Peshawar (*EI*, vol. XVIII).

7. *Iron*: Though iron was used commonly for weapons, implements and other human needs, it was very rarely used as a writing material. The best example is the iron pillar at Meharauli (near the QutubMinar, Delhi) with an inscription in verse about a king Chandra (*GI*, p. 139). This column measuring 23 feet 8 inches is estimated to weigh more than six tons. There is another, of nearly twice the above height, now in fragments, at Dhār. It contains a Persian inscription of Akbar and

a few names and letters in Nāgarī as well as Persian characters. Small inscriptions are also found on the tridents of Śiva and canons made of iron. But these are all late belonging to the fifteenth and the subsequent centuries.

### B. Substances other than metal.

Just as copper is the most common among the metals, stone is the most common among materials other than metals to be used for writing inscriptions. But epigraphs incised on various other substances like crystal, wooden pillars and tablets, earthenware, brick and terra-cotta, conch, tortoise shell, and even ivory plaques are also found.

1. *Crystal*: Inscriptions on crystals are very rare, evidently due to the material being too hard and also not easily available. In the remains of the *stūpa* at Bhaṭṭiprōlu in the Krishna District was found a hexagonal piece of crystal, each face about  $\frac{3}{8}$  inch in breadth, with a record scratched, rather than engraved, on all the six faces (*EI*, vol. II). It is pierced by a hole through its axis. Probably it was originally used as an amulet to be worn suspended round the neck. It is considered as a votive offering, made by a woman from Nandapura, for her recovery from an illness.

Other crystal articles, such as phials, caskets and the like have been recovered from Bhaṭṭiprōlu, Sōnārī and Kōlhāpūr. They bear no inscriptions on them; but other devices have been employed to record their dedication. At Sōnārī, a piece of stone, about  $\frac{3}{4}$  inch long and  $\frac{1}{2}$  inch broad written on both the sides was found inside the casket (*JRAS*, 1905), while, at Kōlhāpūr, the casket was found inside a stone box, with an inscription on its lid. (*ASWI*, No. 10, plate 1).

2. *Bricks*: Bricks inscribed with religious texts are occasionally found in different parts of the country, though not in the South. In Mesopotamia and other countries of Western Asia, bricks were commonly used for writing purposes in ancient days; but its use in India was sporadic. Specimens of inscribed bricks, containing single or a few letters and originally set up in the walls or the niches of temples have been found. At Bhitārī, in the Ghāzīpūr District (U.P.), bricks bearing the inscription 'Śrī Kumāraguptasya' have been found (*C.ASR*, vol. I, p. 94). At Gōpālpūr in the Gōrakhpūr District some brick-tablets have been found bearing Buddhist *sūtras*, one of which is a version in Sanskrit of the short sermon preached by the Buddha at Śrāvastī (*JASB*, 1896, Proceedings, p. 99). There is also a brick-



tablet, found in a field in the Jaunpur District (U.P.), bearing a record dated in 1217 A.D. which registers a mortgage of some lands as security for a loan (*JASB*, 1850, p. 454).

The excavations at Jagaṅgam, in the narrow valley of the Yamunā, not far from its source have brought to light a large number of bricks inscribed in characters ascribed palaeographically to the third century A.D. with a recurring couplet in Sanskrit, from which we learn that it was the scene of the fourth *aśvamēdha* sacrifice performed by a king Śilavarman surmised to be a Yaudhēya prince (*JOR*, vol. XXI).

3. *Clay and Terra-cotta*: Just like bricks, small inscribed tablets of clay, sometimes baked into terra-cotta and sometimes left to harden naturally are also found in large numbers. These tablets, mostly of a votive nature of the Buddhist faith are of several varieties. Some of them present the verse only, while others exhibit, as an accompaniment, one or more *stūpas*, and perhaps the figure of the Buddha. Occasionally, such votive offerings to other faiths are also found. At Sunet in the Ludhiāna District of the Panjab, tablets bearing dedication, 'To Śaṅkara and Narayaṇa' are also found (*JRAS*, 1901). Some of them give the names of the dedicator on one side with the dedication, like *Śrī Viṣṇudāsasya*, '(an offering) of the illustrious Viṣṇudāsa' on the other.

Among the other articles found in clay, the most interesting is the collection of clay-seals. At Basār in the Muzaffarpūr District of Bengal while excavating, were found more than one thousand and one hundred seal-impressions exhibiting approximately one hundred and twenty varieties having about seven hundred and twenty specimens. The bulk consists of seals of officials, guilds, corporations; of seals of private individuals; of seals of temples, and of seals with religious legends on them. One of them bears the legend, 'of the illustrious Ghaṭōtkacha-gupta' while three others mention Dhruvasvāminī, called Dhruvadēvī wife of the Gupta monarch Chandragupta II in inscriptions (*ASIAR*, 1903-04).

The damaged clay seal of Budhagupta, discovered at Nalanda in the Patna District, Bihar, (*Ind. Hist. Quart.*, vol. XIX) gives the ancestry of the monarch for four generations and settles his position in the family which was unknown for the period of over a century since the time when the stone inscription mentioning Surāśmi-chandra, a viceroy of king Budhagupta, was discovered at Eran in Sagar District of Madhya Bharat in 1838 (*GI*, p. 88).

Terra-cotta seals are also recovered and that found at Bulandshahr in the Uttar Pradesh may be mentioned as the typical example of the same (*IA*, vol. XVIII). An inscribed terra-cotta image of Buddha which is assigned to the fifth century A.D. has been found near Kasia in the Gōrakhpūr District (*Arch. Sur. Report*, Panjab and U.P. circle, 1904-5).

The seals in terra-cotta of the Maukhari king Śarvavarman found at Nālandā (*EI*, vol. XXIV) and of his son Avantivarman from Sohnag in the Gōrakhpūr District (*Ibid*, vol. XXVII) are important for the history of that line of kings.

4. *Earthenware*: Inscribed earthenware pots and jars are also recovered occasionally. The find of an inscribed pot from Nandūru in the Andhra Pradesh may be mentioned as a typical instance. A similar pot has been recovered from the Buddhist remains at Sālihuṇḍam (*ASIAR*, 1920; also *EI*, vol. XXVIII).

Fragments of inscribed potsherds have also been recovered from Arikamēḍu, near Pondicherry, written in the Brahmi characters of the first or second century A.D. These are of special interest as the excavations have shown that there was an ancient settlement there having a brisk contact with the Roman world. (*Ancient India*, No. 2).

One of the earthen relic-receptacles found at Bhōjpūr near Sañchi is of some interest, because the inscription, recorded on its lid which was coated with whitewash, was written in ink. (*The Bhilsa Topes* by Cunningham, p. 331) though only traces of the letters remain and no part of the record is decipherable. Similarly three earthenware jars bearing inscriptions in Kharōṣṭhī characters written in ink, have been recovered at the Palātu-dherī hillock in the neighbourhood of Chārsada (North-West Frontier Province, now in Pakistan). The inscriptions record the gift of the jars to the local community of Buddhist monks (*ASIAR*, 1903).

A fragment of a big earthen pot bearing an incised inscription giving the date equivalent to 566-7 A.D. and the name of Śrī Guhasēna, one of the Maitraka princes of Valabhī has been recovered from Kāthiawar (*IA*, vol. XIV).

5. *Wood*: Even though wood is not considered as enduring material, yet inscriptions are occasionally found incised thereon. From Kirari in the Chhattisgarh Division was obtained a wooden pillar buried in the bed of an old tank with an inscription in Brahmi characters of

the second century A.D. (*EI*, vol. XVIII). Unfortunately when it began to dry a good deal of its surface peeled off carrying with it the major portion of the record. It is not possible to ascertain the exact nature of the record incised thereon; but the available portion seems to consist of high official designations and the names of the dignitaries who must have held them.

Recently another record incised on wood has been recovered (*Indian Archaeology*, A Review, 1955-56). One of the wooden ribs in the ceiling of the *chaitya* cave at Bhāja near Poona, contains an inscription in the Brāhmī characters of the second century B.C. thus fixing the date of the excavation of the cave. (p.29, Plate XLIV)

The earliest mention of wood as a writing material occurs in the Buddhist literature. The *Vinayapīṭaka* contains a prohibition that the Buddhist monks should not incise the formula as to how men may gain heaven or riches and fame in the next life, through particular modes of suicide. The *Jātakas* mention the wooden boards (*phalaka*) used for writing alphabets by beginners in learning. It is also said that bamboo chips (*śalākas*) with some marks or letters, or with the names of the bearers, served as pass-ports for Buddhist monks. An inscription of the time of the Kshatrapa ruler Nahapāna (*ASWI*, vol. IV; Nāsik Ins. No. 7) refers to the use of *phalakas* in the guild halls for recording agreements regarding loans. The *Kātyāyana-smṛiti*, a work on legal procedure, prescribes that plaints should be entered on board with chalk (*pāṇḍulēkha*). In Burma, religious manuscripts are found written on slips of wood covered with gold or silver lacquer, the letters being black, and specimens of these are in the British Museum. No such examples are found in India, though it is learnt from Buhler that, according to Winternitz, the Bodleian Library has a manuscript from Assam written on wooden boards.

I have also seen an inscribed bamboo from the former Cochin State area in the Kerala. It was written on the outer enamel of the bamboo in the space between two joints. The writing running lengthwise from joint to joint was incised with a stylus or some sharp instrument. It is learnt that such inscribed bamboos were common in Malabar until very recently and that permanent documents or records were written on bamboos.

7. *Stone* : Lithic records form the bulk of inscriptions obtained so far, and in South India, the major portion of them is found incised on the walls of temples. The selection of temple walls for recording these inscriptions was evidently due to the fact that such epigraphs

mostly registered donations to the respective temples. But the earlier inscriptions, especially those recovered from the rock-cut temples, are found incised on the pillars or beams and lintels. This is best seen in the inscriptions of the Pallava monarch Mahēndravarman found in the several rock-cut temples scooped out by him. We have already referred (above, p. 198) to the custom of inscribing donations to temples on loose stones and leaving them in the premises where the constructions were of brick and other perishable materials. Such stones are even now found planted in or near the temples and sometimes in villages.

Sometimes records are found on stones embedded in the floor and pavement of temples. It is true that these stones got there without any consideration for the records incised on them, when the temples were renovated or rebuilt in mediaeval times. But I have seen in the rock-cut Śiva temple at Kunrakkudi in the Ramanathapuram District, an inscription engraved on the floor of the verandah and continued in the coping and the vertical face of the platform below. That portion on the floor of the verandah has become very much worn out probably by constant treading of the devotees going there, and it is very difficult to decipher the writing.

Next to temples, rocks are much used to record these inscriptions. Boulders or slopes of rocks conspicuous in their presence and by their proximity to human habitation were probably the reason for their selection.

The rock edicts of Aśoka found in different parts of India are the best examples of this variety. The musical inscription at Kuṇḍumiyāmalai already referred to (above, p. 183) also belongs to this class.

In some places rock inscriptions are not single or stray records. Successive generations have incised their records alongside or in continuation of earlier ones. The most notable example of this is probably the inscribed rock at Girnar in Saurāshtra which contains in addition to the edicts of Aśoka, a record of the Mahākshatrapa ruler Rudradāman (*EI*, vol. VIII) bearing date in 150 A.D. and another record of the Gupta king Skandagupta with dates in 455 to 457-8 A.D. (*GI*, p. 56) already referred to (above, p. 204).

At Kaḷugumalai in the Tirunelveli District, there are more than one hundred short descriptive labels in the Vaṭṭeḷuttu characters of *circa* eighth century A.D. underneath portrait sculptures giving out the

names of persons responsible for having made them and also of those whom the portraits represent (*SII*, vol. VII); The various inscriptions on the Chandragiri hill at Śravaṇa Belgōla in Mysore, including the epitaph of the Jaina teacher Prabhāchandra, which commemorates also the migration of the Digambaras to Southern India and their settlement at Śravaṇa Belgōla also belong this class.

The inscriptions below the niches containing representations of Śaiva devotees explaining the incidents or the names of persons illustrated in the niches, on the walls of the Airāvātēśvara temple at Dārāsūram in the Tañjāvūr District also belong to this type.

We have also inscriptions on pedestals and other parts of images and statues. The colossal statue of the Jaina saint Gommaṭa or Gommaṭēśvara, otherwise known as Bāhubalin, at Śravaṇa-Belgōla in Mysore with an inscription recording the erection of the statue in the period 977 to 984 A.D. is a typical example (*EI*, vol. VII). Similar statues, though not so big, are found at Kārkaṭa and Vēṇūr in the South Kanara District having inscriptions with dates 1432 A.D. and 1604 A.D. respectively are also known.

At Kasiā in the Gōrakhpūr District (U.P.) is found a colossal statue (*C. ASR*, vol. XVIII), representing the dying Buddha with an inscription of the end of the fifth century A.D. on a part of its pedestal (*GI*, p. 272).

A seated image of Bōdhisattva bearing an inscription on its pedestal, and dedicated by two nuns in the reign of the Kushana ruler Huvishka and a statue of the Kushana king Kanishka with an inscription incised on the folds of the dress below the knee have been recovered from Mathura near Delhi (*ASIAR*, 1912).

Of the inscribed stone pillars, the most notable one is that found at Allahābad. In addition to Nos. 1 to 6 of the 'Pillar Edicts' of Aśōka, it bears two short records of Āśōka, which are known as the Queen's Edict and the Kōsambi Edict, and also the famous record of the Gupta monarch Samudragupta, incised sometime about 375 A.D. (*GI*, p. 1)

The inscription at Tālaguṇḍa in Mysore primarily recording the repairs carried out to the local tank and which incidentally gives the origin and early history of the Kūḍanbas of Banavase is also incised on a pillar. (*EI*, vol. VII). From the pillar at Mahākūṭa in the Bijāpūr District we obtain the record of the Western Chalukya monarch Maṅgalēśa dated in 602 A.D. (*IA*, vol. XIX).

The circular rim of a stone vessel found in a field at Kailvan in the Patna District bears an inscription in characters of the second century A.D. referring to the year 108 of an unspecified era and a king, evidently a hitherto unknown member of the Maitraka dynasty of Magadha (*Ind. Arch.*, 1955-56).

Lithic records are found on all varieties of stone, like the granite, soap-stone or steatite, sand-stone, etc. Such a situation is mostly due to the materials used.

Some of the best specimens of moulds or stamps for making seals are found in soap-stone or steatite. From Sankīsa or more fully Sankīsa-Vasantpur in the Farrukhābad District (U.P.) we have such a stamp with the name of Utarasēna, incised in reverse with some emblem above and, below it, a *svastikā* (C. *ASR*, vol. XII). From the same place we have another goldsmith's mould with Kharōshthī letters. Here the letters are not reversed, and they stand in the flat surface surrounding the hollow containing the pattern which was to be reproduced from the mould.

The rock-cut seal-matrix of about the commencement of the seventh century A.D. at Rōhtāsgarh in the Shahābad District, Bengal, is indeed, a curiosity. The matrix contains a couchant bull, and below it a legend *Śrī Mahāsāmanta Śaśāṅkadēvasya*, in reverse (GI, p.283) and the whole surrounded by a cricle, about  $4\frac{1}{2}$  inches in diameter, marking the size of any impression to be produced from it. The whole device is carved on the rock, not carved in relief. It is considered as a matrix or mould for making seal. But considering that the friable substance of the rock would not stand the pouring of molten metal on it, it is thought that the mould was made for the purpose of producing a clay, lac or wax seal.

The inscriptions of the Muslim rulers, especially those in the Perso-Arabic script are generally not engraved, but are formed by scooping out the space around them. This method appears to have been followed by others also in Northern India in certain late mediaeval records.

8. *Conch, ivory, etc.*: Inscriptions on conch-shell, ivory plaques etc., are very rare. A white conch with a Brāhmī record has been recovered from Sālihūṇḍam, (EI, vol. XXVIII). At Rupar, sixty miles north of Ambālā on the Sutlej, was found in the recent excavations, an ivory seal inscribed in Mauryan Brāhmī characters (*Ancient India*, No. 9, plate XLVIII-A).

### Note on other Writing Materials

Writing, however old, on materials as the palm-leaf, birch-bark and the like are not generally treated as inscriptions. Still such writings can be properly deciphered only by persons having a knowledge of the palaeography of the scripts used and well-versed in epigraphy also. Further any study of the writing materials will be incomplete without an account of such materials.

1. *Palm-leaf*: The most common material widely used for writing in Ancient India was the *Tāla-patra* or *Tāḍa-patra* and this continued in vogue till very recently. These large-leaved palm-trees (known botanically as *Borassus flabelliformis*, *Corypha umbraculifera* and *C. taliera*) originally indigenous to Southern India, are found even in the Panjab. In Kashmir and other north-western areas of India, birch-bark was more popular. However it appears that palm-leaves were used even in those regions in the earlier period and this will be evident as the birch-bark was cut into sizes corresponding to the shape of the palm-leaves. The Taxila copper-plate (*EI*, vol. XXI) belonging to the first century A.D., is also fashioned after a palm-leaf. The Buddhist Jātakas also refer to *panna* (leaves) as a writing material and these were most probably palm-leaves. A Buddhist tradition, preserved in the biography of Yuan Chwang asserts, that in the first Buddhist council held immediately after the death of the Buddha, their Canons, the *Tripitakas*, were written on palm-leaves.

Palm-leaf manuscripts found in South India generally do not belong to a date earlier than the fifteenth century A.D. due to the hot and humid climate prevailing here. But in the cold and dry climate prevailing in some parts of North India and beyond, early manuscripts on palm-leaves have been found. The earliest specimen recovered so far contains fragments of a Sanskrit drama written in characters of the second century A.D. and this has been obtained from Central Asia. The manuscripts discovered by Macartna in Kashgar are assigned to the fourth century A.D. (*JASB*, vol. LXVI). The manuscripts of the *Prajñā-pāramita-hridayasūtra* and of the *Ushniśa-vijayadhārīnī* now preserved in the Hōri-uzie monastery in Japan appears to have been written in Central India in the sixth century A.D., while the manuscript of the *Skanda-purāṇa* in the Durbar Library at Kathmāṇḍu in Nepal belongs to the seventh century A.D. The Cambridge manuscript of the *Paramēśvara-tantra* is dated in the Harsha era 252 (or 858 A.D.) while that of the Buddhist work *Laṅkāvatāra* is dated in the Newar era 28

(i.e., 906-7 A.D.). South Indian manuscripts written in the Grantha script of the eleventh century and in the Tamil script of the thirteenth century A.D. have also been recovered from the monasteries in Tibet, the photostat copies of which are now preserved in the K. P. Jayaswal Research Institute at Patna.

For writing books and permanent documents, palm-leaves are specially prepared to ensure flexibility and longevity. The leaves are first dried, next boiled or soaked in water, then dried again and finally polished with a smooth stone or conch-shell and cut into the proper sizes. Ancient manuscripts frequently exhibit traces of an artificial preparation. Their lengths vary from one to three feet while in breadth they range from one to four inches. In Northern India, ink was used in writing on palm-leaves. But in the South, they were written with a stylus and then the leaves were besmeared with soot or powder of charcoal. The leaves are punched with a hole, usually in the middle and occasionally on the left, through which strings, (*sūtra* or *śarayantraka*) are passed in order to keep them together. Those of considerable length have two holes, both on the left and right.

The leaves in their natural form without any preparation and sometimes even without trimming the ribs are found used for the ordinary and daily purposes.

Its use, even after the introduction of cheaper paper, continued till about a quarter of a century ago and is at present confined to the primary schools, temples, and the like for its sanctity.

2. *Bhūrjapatra* (Birch-bark) : Another material commonly used for writing in ancient times was birch-bark. This was prepared from the inner bark of the tree called *bhūrja* (*Baetula bhojpatra*) abundantly found in the Himalayan region. Originally it was used in the north-western parts; but later on it travelled to other parts of India and to Central Asia. The earliest mention of it is found in the accounts of the Greek writer, Q. Curtis, who writes that at the time of Alexander's invasion of India, the Indians wrote on bark. The northern Buddhist works frequently mention this as a writing material. A full and detailed account of the same is given by Āl-Berūnī (*India* by Sachau, vol. I, p. 171) : "In Central and Northern India, people use the bark of the *puz* tree, one kind of which is used as a cover for the bows. It is called *Bhūrja*." For writing, pieces one yard in length and one span in width were selected and prepared for use by rubbing oil on them and then polished. The writing was done with a reed pen and ink of special kind,



The middle portion was left blank so that holes might be punched and the leaves bound together with strings passed through such holes. 'The whole book was then wrapped in a piece of cloth and fastened between two (wooden) tablets of the same size.' For ordinary and daily use, the bark was not treated so elaborately and sometimes the bark of the *tuz* tree also was used.

Just like the palm-leaves, the use of birch-bark as a writing material declined with the introduction of cheap paper during the Moghul rule. Still it lingers on, like the palm-leaves, in North India for writing amulets, etc. on account of its sanctity. Its use did not extend to the South.

The earliest manuscript on birch-bark is that of the Buddhist work *Dhammapadam* discovered in Khotan and written in the Kharōshthī characters of the second or third century A.D. The manuscript of *Samyuktāgama* belongs to the fourth century. The inscribed 'twists' tied up with thread discovered in the Stūpas of Afghanistan come next. Those of the Bower and Godfrey collection of *circa* the sixth century A.D. and of the Bakhshali arithmetic of the eighth century A.D. are wellknown. The latest ones of fifteenth and subsequent centuries have been obtained from Kashmir.

3. *Paper*: It is generally believed that paper was first prepared in China in 105 A.D. and first introduced to this country by the Muslims (Barnett : *Antiquities of India*, p. 223). But Nearchos, the Greek writer who accompanied Alexander to India, mentions that the Indians were then preparing writing paper out of cotton (cloth) by pounding (*Strabo*, XV, 717). The earliest manuscript on paper was that obtained in Central Asia at Kashgar (*JASB*, vol. LXVI). written in the characters of the Gupta period of the fifth century A.D. But those obtained in this country do not go to a time earlier than the fourteenth century A.D.

Writing on paper in earlier days imitated writing with ink on palm-leaves or birch-bark and for this purpose the paper was coated with a thin layer of rice or wheat pulp and then polished with conch-shells or stones so that the ink might not penetrate. The paper was then cut into pieces of convenient size. Books of paper were bound with wooden planks on both the sides and sometimes even punched in the middle with holes, strings passing through them.

4. *Cotton cloth*: In Ancient India cotton cloth, variously mentioned as *paṭa*, *paṭikā* or *kārpāsika-paṭa* also served as a writing

material. We have already referred to its mention in the *Dharmaśāstras* (above, p. 190). The earliest epigraphical reference to *paṭa* as a writing material is found in the Nāsik records of the Śātavāhana period (*ASWI*, vol. IV, Nos. 11 A, B). Like paper, cotton cloth also is not enduring and easily becomes affected by moths and moisture. Peterson found at Añhilvād-Pāṭaṇ a manuscript of the Jaina work *Dharmavidhi* of Śrīprabhāsūrī dated Vikrama-Samvat 1418 (or 1361-62 A.D.) In the library *Brhajjñānakōśa* at Jasalmir, Buhler found a silk-band with a list of the Jaina sūtras written with ink. Accounts, two to three hundred years old, written on cotton cloth are also reported to be preserved in the Śrīngēri-maṭha. It is said that in Rajputana there is a class of people who prepare almanacs on long pieces of cloth (Ojha, *Bhāratiya Prāchīna Lipimālā*, p. 140). According to Burnell and Rice, traders in the Kannaḍa area were using for their books of business a kind of cloth, called *kaḍḍatam*, which was covered with a paste of tamarind-seed. Even in Tamiḷ-naḍu, some of the Mārvaṛi merchants were using similar cloth for keeping their accounts.

Cloth, like paper, was made smooth and non-porous by applying a thin layer of pulp on it and polished with a conch-shell or stone after it got dried. They were then written with a special kind of black ink. Sometimes the cloths were used to be blackened with charcoal powder when applying the pulp and in such cases they were written with chalk or steatite pencils.

5. *Leather* : In ancient times leather was used as a writing material in Western Asia, Egypt and Europe. It is said that some Buddhist works include skin among writing materials and that the *Vāsavadattā* of Subandhu also implies to the same. But Indians treat the skins, except those of deer and tiger which are used for religious purposes, as impure and no manuscript written on this material has been recovered so far. However, in the Petersburg collection there are some pieces of leather obtained from Kashgar and inscribed with Indian characters.

6. *Ink* : The statements of the Greek writers already referred to that Indians were writing in those days on birch-bark, cotton cloth and paper obviously suggest that some kind of ink or dye was used for writing in those days. The word *mashī*, *maśi* or *masi* used for ink occurs in the *Grihyasūtras* written before the Christian era. The earliest specimen of writing with ink is that found on the inner side of the lid of the relic-vessel from Stūpa No. III at Andher which is

assigned to the third or second century B.C. (*The Bhilsa Topes*, p. 349). It is taken that the substitution of loops for dots in the formation of certain letters sometimes noticed in the Aśōkan edicts as suggesting that ink was used when those edicts were engraved. The Kharōshthī *Dhammapada* from Khōtān, 'twists' and stone-vessels from the Stūpas of Afghānistan are all written in ink. A few specimens of painted inscriptions are found in the caves of Ajanta.

Different kinds of inks were used; still black was the most common. There were two varieties of black ink. The ordinary or delible one used for temporary purposes was prepared with some kind of pulverised charcoal mixed with water, gum, sugar or some other sticky substance. The other, permanent or indelible ink used for writing manuscripts and documents, was prepared from lac mixed with water, borax, *lōdhra* (a tree with white flowers) and lamp-soots of sesamum oil, all boiled into a strong solution. This kind of ink is said to be not affected by water and damp. In Kashmir the ink required for writing on the birch-bark was prepared by using the char made from almonds and boiling in cow's urine. It is said that ink so manufactured is absolutely free from damage even when the manuscripts were periodically washed in water-tubes.

Coloured inks also were used; red was the most common while yellow also was sometimes used in writing manuscripts. Hemādri refers in his *Dānakāṇḍa* to the donation of manuscripts written with coloured inks. Red ink was made either from *alaktaka* (red dye) or *hingula* (lead or minium), by dissolving them in water with resin or some sticky substance. This was mostly used for making the medial signs and margins on both sides of the text. Sometimes the ends of chapters, or *ślōkas* were also marked with this ink. Green and yellow inks were preferred by some Jaina writers for denoting the ends of chapters.

Gold and silver inks were also used for artistic writing on paintings or the preparation of manuscripts of religious works, etc. for use by royal patrons. References to such usage are found in ancient times; but the available specimens all belong to late periods.

## 10. EPIGRAPHICAL FORMS AND CONTENTS

The *Dharmaśāstras*, we have already seen, have prescribed the form in which an inscription should be written. Generally it is composed of five principal items, *viz.*, the auspicious opening, particulars of the donor, of the donee and of the gift made and the

concluding portion. The earlier records were short and simple and with the passing of time elaborate conventions came to be established which varied from time to time and place to place. Still they observed the above essentials.

*Maṅgala*: There is practically no composition, literary or philosophical or of any other kind, without a *maṅgala* or auspicious mark at the beginning. It may be a verse or symbol or in one of the approved ways. The *maṅgalas* may be of three kinds : *āśīḥ* or benediction, *namaskriyā* or salutation (to the deity), or *vastunirddēśa* or suggestion of *maṅgala* while abruptly beginning the topic, with some auspicious word or letter.

In many of the early inscriptions we find a number of auspicious symbols in addition to the salutation. Generally these symbols are given first and then only the salutations follow. In the Tamil inscriptions, especially of the late mediaeval period the occurrence of the symbol known as *Pillaiyār-śūli* is very common. This symbol has got various forms and is also seen commonly in the inscriptions of the Kāṇṇāṭaka country in the form of a spiral. This is generally taken as the symbol to represent the word *Siddham* and sometimes the *praṇava* or *Oṃkāra*. Occasionally this symbol is also found used in addition to the word *Siddham* or *Om* actually written as such.

The Hathigumpha inscription of Khāravēla has the symbols of a crown and a *Svastikā* on the left margin at the top. These are sometimes taken as representing *svastikā* and *śrīvatsa* suggesting *Svasti śrī* a form which in actual writing marks the beginning of certain grants as *Svasti śrīmatām*, etc. This is in addition to the salutation to the Jinas with which the inscription commences. The symbols of a Drum and *Bōdhi* tree occur in some records. Of these, the former probably represents *praṇava* or Bhagavān and the latter Nārāyaṇa. Occasionally the symbol referred to as the Wheel on the *trīśūla* is found and this is taken as representing the expression *namō* or salutation.

Many of the records, whether they have these symbols or not, begin with the word *Svasti* and occasionally with *Siddham*. In all earlier grants these are written not at the beginning of the first line, but in the margin almost pushing in one of the central lines. In addition, salutation to the respective deities of the donors occurs in forms like *Jitam Bhagavatā* in the early Pallava and Western Gaṅgā grants, *Namaḥ Śivāya* (*EI*, vol. II, pp. 10, 410), *Namō Budhāya* (*Ibid*, vol. VI, p. 287), *Namō Bhagavatē Vāsudēvāya* (*Ibid*, vol. II, p. 350), *Namō Arhatō Vardhamānasya* (*EI*, vol. II) and *Namō Śarasvatyai* or *Bhāratiyai* (*Ibid*, vol. II, pp. 182, 333). All the later Vijayanagara grants begin with *Gaṇādhipataye namaḥ*.

Beautiful verses expressing salutation to the patron deities are found as invocation in several records. These are addressed variously to Viṣṇu under the numerous names of his incarnations, Śiva, Dēvī, Kārttikēya, Brahmā and Sarasvatī. The Jaina inscriptions which abound in the Karṇāṭaka country begin with the invocation to the Jinas or the verse in praise of the *Jinaśāsana*. Similarly, in addition to the Bhagavan Buddha, Mañjuhōśha, Mañjuśrī and other deities are invoked in the records of the Buddhist faith. Very often these verses contain details which help iconographic study.

**Donor :** The name of the donor is mentioned in the record immediately after the invocation. The *Dharmaśāstras* prescribe that the names of at least three generations of the donor, i.e., great grandfather, grandfather and father of the donor should be mentioned. This rule is scrupulously observed in the earlier grants generally and the Sanskrit charters of the Pallavas are the best examples for this. Sometimes the military exploits and other eulogistic information regarding them are also given. In some grants this genealogy is not limited to three generations, but is given for the entire ruling family from its founder. The copper-plate grants of the Chālukyas, both the Eastern and Western branches, give the *praśasti* of their family in set verses which are added on with the accession of each new king. But in the Tamiḷ inscriptions an entirely different method has been adopted. In the inscriptions of the Imperial Chōḷas from the time of Rājarāja I, and also of their successors, the Pāṇḍyas, the *praśasti* of only the reigning monarch is given in metrical form. This eulogy known as *meykkīrtti* in Tamiḷ is more precise and historical, and consequently more reliable than the exaggerated poetical compositions of the Sanskrit forms. This *meykkīrtti* is different for each king and would increase in length as the reign progresses, new victories being added as they are gained. Even grammatical works on Tamiḷ prosody, known as *pāṭṭiyal*, define the form of *meykkīrtti*. The name of the reigning monarch is given at the end of the *meykkīrtti*.

The date of the grant is mentioned at the end of the *meykkīrtti* immediately following the name of the king. In some of the Tamiḷ inscriptions the *meykkīrtti* is not given. Occasionally it is indicated with the opening word like *Puyal vāyttu* and then left off, or simply referred to and passed on like *Śrī-meykkīrttikku-mēl* (after or in continuation of the illustrious *meykkīrtti*). In such cases also the date is given immediately following the name of the monarch and expressed in his regnal year.

Some inscriptions, which appear to be mere copies of the executive order issued, do not contain the *meykkīrtti* as also the name of the

reigning monarch who is simply referred to as His Majesty with the expression like *Tribhuvana chakravartigaḥ* or *Kōṇērinmaikōṇḍān* in its various forms. In such records it is usual to find the date given at the end.

**Donee:** The person who was the recipient of the grant is clearly mentioned in the grants. In the case of a land grant to a Brāhmaṇa, the particulars of the *śākhā*, *sūtra* and the *gōtra* of the recipient together with the name of the village wherein he was residing as also that of his father are given. In the case of other grants to institutions like temples, *maṭhas*, etc., the names of the recipients are mentioned explicitly and clearly.

**Gifts:** This is the important part of the document. The nature of the gift and other particulars regarding the same are specified here. Where the gift represents land the boundaries of the gift land and the exemptions in the taxes to be enjoyed by the donee are also detailed. In the case of other transactions their nature is fully described. This portion varies with each record depending on the contents.

**Conclusion:** This portion also varies very much. But usually the imprecation forms the concluding portion of all gift deeds. This is given in set verses in Sanskrit at the end of almost all the inscriptions. These verses generally vary in number, sometimes long and occasionally restricted to a single verse. In the records of the Tamil, Telugu and other local languages there are short imprecatory prose passages in the language of the inscription. Sometimes the Sanskrit verses also are found added.

The imprecation found in earlier inscriptions is rather simple. The sin of killing a cow on the banks of the river Gaṅgā as also some others like the five heinous sins are pronounced on those who hinder or violate the *dharma*. Similarly the merit of performing a sacrifice, sometimes mentioned as thousand, on the banks of the Gaṅgā or the consecration of a *Linga* is stated to accrue to anyone who protects the *dharma*. Earlier inscriptions in Tamil simply state: "The illustrious feet of those who protect the *dharma* are (ever borne) on my head."

In the early Prakrit charter from Mayidavōlu, the Pallava king Śivaskandavarman (*EI*, vol. VI) threatens corporal punishment to any one who causes trouble or annoyance to the donee by transgressing his orders. This is possible only so long as the king is alive

and ruling. But this will not be possible for all time. So divine wrath is invoked for assuring protection to the gift. There is also a prayer put forth to all future kings to take care of gifts of former kings. While so doing they repeat with one accord the evanescence of wealth and the fleeting nature of glory and request with folded hands their successors in power for all time to protect their gifts. Here they cite the mighty king Rāmabhadra of Ayōdhyā as requesting all future kings to protect the grants of former kings. And one or two verses said to have been composed by Vyasa are also introduced in support of their prayer for the protection of gifts.

The imprecatory verses grew in length in the later charters and we have all forms of curses heaped on the head of a wrong-doer. This is found even in the records in Tamil and other languages. (The popular verses more commonly found in the Sanskrit records have been given in an appendix to the Second volume of this collection).

Some of the inscriptions, especially those on copper-plates, give the names of the engravers. The Paṭṭattāmaṅgalam plates of Nandivarman Pallavamalla mention that they were engraved by Śrī Daṇḍi, son of Viḍēlviḍugu-Pallava-p-perumtachchan of Aimpunaichchēri in Kachchippēḍu (*EI*, vol. XVIII). Occasionally the names of the poets who composed the *prāsaṣṭi* as also those who copied the records on copper for the smith to engrave on are also given. We thus find for one inscription (*EI*, vol. I, p. 49) the author was one Dēvaḡaṇa, the copyist *kshattriya* Kumārapāla and the engraver Sampula. Another inscription (*Ibid*, p. 45) mentions the poet as Ratnasimha, while the copyist and the engraver are the same persons mentioned above.

*Scribe* : The scribe was a prominent figure in ancient days. This was probably rendered necessary by the peculiar conditions then obtaining and the legibility of writing required. Śūdraka, author of the Sanskrit drama *Mudrārākṣha*, has made Chāṇakya, one of the characters, remark that "even though written with care the letters of a *śrōtriya* (Vedic scholar) like himself would be far from clear" and that he prefers the services of a scribe. The lay public though well educated sought to avoid writing themselves and preferred scribes whose hand-writing was distinctly superior. We know that every Government office, till recently, had good scribes to fair-copy outgoing letters and other documents and this went into disuse only with the advent of type-writers.

In early days it was very often the expert craftsmen that undertook the task of inscribing. But official documents on less permanent materials like palm-leaf, bark and cloth were executed by trained scribes. Ornamental writing required the greatest care and dexterity of the scribes.

Scribes were termed as *lēkhakas* in early times and sometimes also designated as *lipikāras*. One of the donative inscriptions from Amarāvati in the Krishna District mentions *rājalekhaka*, a king's scribe, as a donor. This will show that scribes of extraordinary ability and artistic hand were chosen to work in the royal palace or government offices. The earliest mention of a *lēkhaka* in royal service is found mentioned in the versions of Aśoka's edicts recovered from Brahmagiri and Siddhapura where he is styled as *lipikara* with the name Capada. A *rājālipikara* named Subahita Gōtiputa is mentioned in an inscription from Sāñchi (EI, vol. II).

The name of the scribe is not usually mentioned in the stone inscriptions of Tamiḻ-ṇāḍu and is found only occasionally in the copper-plate grants. But in the records of the Telugu country, the name of the scribe is mentioned on many occasions even in stone inscriptions. In two Tamiḻ inscriptions of the time of Kulōttuṅga Chōḷa I recovered from Draksharāma in the West Godavari District it is mentioned at the end in Telugu that they were incised by Virarājendra chōḍa ācharya *alias* Surāchāri of Dakarēmi. (SII, vol. IV, No 1245). The name of the person clearly indicates that he was the official scribe. Even in Tamiḻ-ṇāḍu we find the existence of such official scribes. One of the Tamiḻ inscriptions from Tiruvaiyāru in the Tañjāvūr District mentions that Lōkamahādēvi, queen of Rajarāja Chōḷa I, ordered that the right of incising inscriptions on the walls of the shrine of Dakṣhiṇa-kailāsam that she constructed there should be exercised only by the particular stone-mason who held the *kāṇi* of the office (No. 610 of this collection). And there are also many references to official stone masons attached to temples with the right and authority to incise inscriptions on the walls of such temples.

*Composer* : We have already seen that many of the inscriptions are couched in poetical form having a grand diction and beautiful verses of intrinsic literary merit. Some of the compositions compare very favourably with standard works in the languages in which such records are written. But the names of the poets who were the authors of such compositions are not usually found mentioned. Still a few names are given here and there. The Tāḷagunḍa inscription,



narrating the early history of the Kadambas of Vanavāsi, mentions that it was composed by Kubja who was also the scribe : *Kubjaḥ svakāvyaṃ idam asmatalē lilēkha* (EI, vol. VIII).

These official composers of *praśasti* and the official scribes appear to have occupied their positions in some cases hereditarily. The Udayēndiram plates of the Pallava monarch Nandivarman Pallavamalla (SII, vol. II) mention at the end that the grant was composed by the poet Paramēśvara, son of Śrīchandra who describes himself as a member born of the family of Mēdhāvi (*mēdhāvi kulōdbhavaḥ*). Another Pallava grant of a former monarch Simhavarman recently discovered mentions that it was composed by the poet Mēdhāvi, evidently of the family to which the composer of the Udayēndiram plates belonged.

Occasionally we find the composers of the *praśastis* of land grants and the scribes who incised them on copper-plates getting shares in the villages thus gifted. The poet who composed the Udayēndiram grant mentioned above, is said to have obtained, according to the grant, one share in the gift-village. Similarly, Yuddhakēsari-p-Perumbaṇaik-kāran, who wrote the Vēlvikkūḍi grant of the Pāṇḍya monarch Neḍuṇ-jaḍaiyan, got a house-site, two *mā* of wet land and a dry field in the village (EI, vol. XVII).

**Signature :** The affixation of the signature and seal give the final stamp of authority to any document. The classical example of the royal signature affixed to a grant is that of the Vardhana ruler Śrī Harsha of Kanauj. This is usually found in a highly florid and most artistically drawn form with the words *Svasto mama Mahārājādhirāja Śrī Harshasya* [My own hand (writing) of Mahārājādhirāja Śrī Harsha—EI, vol. IV, p. 288]. Similar instances are also found in the grant of the Paramāra ruler Bhōja of Dhārā : *Svastōyam Śrī Bhōja dēvasya* (Ibid, vol. XI, p. 192). Sometimes the expression of 'my own hand' is omitted and written with only the king's name like *Śrī Mūlarājasya* (Ibid, vol. X) or sometimes merely as *svastō mama* (my own hand—Ibid, vol. I, p. 83) without the name, probably as it was felt that this was sufficient since the royal seal also was attached to it.

In the South, the royal signature or sign-manual is found only at the end of the inscriptions of chieftains of the Telugu country and of the rulers of the Vijayanagara empire. In the earlier records of the Vijayanagara empire, the name of the king is found at the end like *Śrī Harihara* without the addition of the *vrāṇu* or signature. (as found

in some of the inscriptions of the chiefs in Telugu country as *Śingana-yani-vrālu*). Later on the signature was changed over to the name of the principal deity, in the great temple at their capital, *Śrī Virūpākṣha* and once again when the monarchs became staunch followers of the Śrī Vaiṣṇava religion to the sign-manual of *Śrī Vēṅkaṭeśa*.

But this practice was not followed by the kings of the Tamil country, like the Pallavas, the Chōḷas, the Pāṇḍyas as also by their subordinates. But their inscriptions are not entirely wanting in signatures stamping authority. Many of the Chōḷa inscriptions contain the signatures of the administrative officers holding important positions in the official hierarchy. Sometimes we find the signatures of a large body of such officers, thus clearly indicating the several departments in the administration through which a particular document had to pass before final approval and issue.

In many of the Tamil records, these signatures of the state officials were not the final ones. The local assemblies, to which the orders of the king were communicated under the signatures of the several officers, took necessary action on them and finally instructed their official-scribes to record these orders on stone, incorporating the king's orders. Thus we have also at the end the signature of the accountant of the local assembly.

*Seal:* Next to the signature, the royal seal affixed to a document was considered the most important requirement to proclaim its validity. It is sometimes considered that this was not a legal requisite in earlier days and that the earliest law books do not insist on the use of seals in grants. The *Yājñavalkya-smṛiti*, which is assigned to the first or second century A.D., refers to the use of a seal on a grant charter as a legal requisite. But the use of royal seals as authentication of the grants has been restricted to copper-plate charters.

The use of the royal signet as a mark of authenticity has been known from very early times. The earliest mention of the same is that found in the *Rāmāyaṇa* where Hanumān is made to present Sītā when he met her in Laṅkā with the signet-ring of Rāma in support of his mission. The famous play of *Śākuntalam* by Kālidāsa has been woven round the signet-ring of king Duṣhyanta. The *Mudrārākṣha* is another drama in which the signet-ring of the fugitive minister, with his name engraved upon it, plays an important part.

There is also an allusion to the royal seal in the *Harsha-charita* of Baṇa. In the march of Harshavardhana leading an expedition

against Gauda he halted at a place on the banks of the Sarasvati river. There the local officer presented himself before the king with a newly made golden stamp (*mudrā*) with a request to issue orders for the day and authenticating it with the seal. However, when the clay was produced for the purpose, the stamp slipped from the king's hand and fell face downwards on the black-mire which served as an inking-pad and then rolled on to a soft spot. The letters of the legend on the stamp were thus distinctly marked on the bank of the river. The bystanders saw a bad omen in that. But the king deduced from it the auspicious augury, that 'the whole earth should be stamped with the single seal of his sole command'. That balls or tablets of clay were used to be held in palms for impressing them with the seal is borne out by the traces of palm-marks found on the backs of the some of clay seals recovered. (*JRAS*, 1901).

The *Life* of the Chinese pilgrim Yuan Chwang mentions that when he finally took leave of Harsha, the king furnished him with letters, written on fine cotton stuff and certified by impressions of his seal made in red wax, which the officers of his escort were to present in all the countries through which they travelled and on seeing which the pilgrims were to be provided with carriages or other means of conveyance and other facilities by those countries.

A specimen of this signet-ring (made of copper or bronze) has also been found. The diameter is  $1\frac{1}{2}$  inches while the face of the signet is slightly oval in shape, about  $1\frac{7}{8}$  by  $1\frac{5}{8}$  inches. It bears a legend in two lines in characters of the fourth century A.D. and mentions the name of Mahārāja Mahēśvaranaga, son of Nāgabhaṭṭa. (*GI*, p. 282). Above the legend and separated from it by a line is the figure of a couchant bull with a crescent moon, and below the legend, there is a snake.

We have already referred to the use of royal seals in the case of copper-plate grants. The seal is attached to the plate itself where the grant consists of a single plate as in the Mungir plate of Dēvapāla (*EI*, vol. XVIII), and to the ring passing through the holes made in the plates where a grant contains more than one plate. The two ends of the ring are soldered into the base of the flat surface on which the seal is impressed. This prevents removal of any existing sheet or the addition of any new one in the grant without tampering with the ring and thus acts as a safeguard against malpractices. Sometimes the seals attached to single plates have become separated from the plates. The Bhitari seal of Kumaragupta (*JASB*, 1889) and the Aṅgarh seal of Śarvavarman (*GI*, p. 230) are the best examples.

The seals generally contain the emblem of the ruling family to which the king who issues the charter belongs. Thus we find a couchant bull in the seals of the Pallava grants or a boar on those of the Vijayanagara monarchs.

Sometimes several figures are found in the seal; but the principal one is always the *lāñchhana* or crest of the ruling family. This is best seen in the seals of the Chōla monarchs. Even though, in addition to the tiger which was the crest of the Chōlas, we find the double-fish of the Pāṇdyas, the bow of Chēras and other symbols, the tiger is always the prominent figure.

The name of the king whose grant the charter contains is also given in the seal. Sometimes, only the name is found; but usually in the seals of the kings of the Tamil country, a Sanskrit verse which appears as a sort of *praśasti* of the particular king is written circularly near the rim of the seal and this verse is occasionally found at the opening of some of his inscriptions. In some of the North Indian inscriptions, the seal gives not only the name of the monarch who issued the grant, but also the entire genealogy of the family from its founder. The Bhitari seal of Kumāragupta and damaged Nālanda clay seal of Budhagupta already referred to (above p. 219) are the best examples of them.

Another form of authentication adopted for some of the copper-plate grants is the word *drishṭam* or 'seen' implying that the document was seen and approved by the king or the royal authority. The Mayidavōlu (*EI*, vol. VI) and the Hīrahaḍagalli (*Ibid*, vol. I) grants of the Pallava king Śivaskandavarman have the word in its Prakrit form *diṭham* written on the left margin of the blank side of the first plate while it is in its Sanskrit form *drishṭam* in the Basim plates of the Vākāṭaka ruler Vindhyaśakti II (*Proc. Ind. Hist. Congress, Calcutta*, 1939).

Similar form of authentication is found even in some of the stone inscriptions in Tamil, especially those of the Pāṇḍya monarchs, with the word *tulyam* meaning 'equal' either at the beginning or at the end of such records. This stands in the place of 'True Copy' in modern connotation and implies that the record incised in stone was compared with the original and found to be a correct or equal copy of the same. Evidently the Pāṇḍyas exercised strict control over the incision of documents on stone. Occasionally we find the *māṅgala* or the auspicious symbols and words given also at the end of some documents.

## 11. DATING OF THE INSCRIPTIONS

We have already mentioned that the *Dharma-śāstras* prescribe that all documents should contain particulars of the dates on which the respective documents were written. The majority of the inscriptions faithfully follow the rule. It is because of these dates that even private documents become important and historically useful helping in the reconstruction of the past history.

But there is no uniformity in the manner in which these dates are found given. Different methods have been adopted. Some inscriptions are dated in the regnal years of the monarchs then ruling while others are dated in the well-known eras. There are also few which are dated in both these ways and also contain additional particulars of the month, *paksha*, *tiṭhi*, day and the *nakshatra*. Sometimes we also find mention of *sankrāntis*, eclipses, and the like on which occasions the grants were made. These particulars are very helpful in exactly fixing the dates of those grants. Earlier inscriptions, those in Prakrit and Sanskrit languages, give particulars of the dates in the seasons and the *pakshas* in the seasons, as the year was then reckoned as divided into three seasons.

The earlier inscriptions of the South, especially those in Tamil, are generally dated in the regnal years of the kings. In the records of the earlier period these regnal years are expressed in words like *Kō Vijaya Nandivikkiramaparumarku yāṇḍu aruṇpattonrāvadu*—In the Sixty first year (in the reign) of king Vijaya Nandivikramavarman. (*EI*, vol. XVIII, p. 121). These dates are sometimes expressed in numeral figures in the records recovered from Vēṅgi and other areas. In the Tamil inscriptions of the ninth and tenth centuries A.D., the date is expressed in both the words and figures like *Kō Rājakēsari parma[r\*]kku yāṇḍu 8 Eṭṭāvadu*—In the year 8 Eight (in the reign) of king Rājakēsarivarman. (*SII*, vol. XIII, No. 187). It was only in later times that the dates were denoted entirely by figures.

Many of the Pāṇḍyan inscriptions contain double dates which are expressed as *yāṇḍu iraṇḍāvaḍin eḍir nārpaṭtiraṇḍu* (in the year forty-second opposite to the second year—*Sen Tamil*, vol. IV, p. 114) or as *paḍin mūṇrāvaṭin eḍir panniraṇḍāvadu* (in the year twelve opposite to the year thirteen—*IA*, vol. XX, p. 288). This method of dating the inscriptions with two dates had long been a puzzle and it was not even known which of the two dates should be taken as that of the grant. The clue to this was found in the Larger Śīnnamanūr plates of the Pāṇḍya king Rājasimha (*SII*, vol. III). The date of the grant is mentioned as *iraṇḍāvaḍin eḍir paḍināṅkāvadu* (in the

year second opposite to the fourteenth) in the Tamil portion while it is given as *shōḍaśe rājya varshē* (in the sixteenth regnal year) in the Sanskrit portion. It is therefore taken that the total of both these years ( $x+y$  years) represents the date of the grant.

But why this system has been adopted especially by the Pāṇdyas has not been satisfactorily decided. Various explanations have been offered; but none of them appears acceptable answering all the difficulties encountered. This has been discussed at some length by Paṇḍit S. Subrahmanya Sastri who was the Epigraphist to the Tirupati Dēvasthānam in an article in the *Journal of Śrī Venkateśvara Oriental Institute*, Tirupati. (vols. VI and VII).

An inscription of the Chōla king Rajadhiraja I from Eṇṇayiram in the South Arcot District (No. 330 of 1917) states that an order issued by the king took three years and one hundred and three days to reach the *sabhā* of the village (above, p. 181). The Tiruvālaṅgaḍu plates of Rajendra Chōla I (*SII*, vol. II) registering an order made by the king in his sixth year was written on copper after the twelfth year of the monarch, as will be evident from the Sanskrit portion of *prasaṣti* in the grant mentioning his expedition to the Gaṅgā which took place in the twelfth year of his reign. It is therefore likely that of the two dates found in the Pāṇḍyan inscriptions, the first one represents the year in which the order was made by the king and the second represents the interval which elapsed in executing the same after it was made.

It is true that some inscriptions, though rarely, instead of two dates give more opposite years even going upto five (as  $4+1+1+1+1$  year—No. 358 of 1907). But generally these additional dates are always of the first year. Probably these additional dates represent the various stages through which the matter has to pass.

*Eras* : The most common of the eras used in South Indian inscriptions and especially those from the Tamil country is the Śaka era commencing in 78 A.D. The earliest epigraphical reference to this era is that contained in the Bādāmi inscription of Chalukya Vallabheśvara who has been identified with Pulikēśin I, dated in Śaka 465 (*EI*, vol. XXVII), while the next one is that of Kīrttivarman I in the Vaishṇava cave there and dated in Śaka 500 (*IA*, vol. X). But reference to the era in literature goes to still earlier times. The Digambara Jaina work in Sanskrit *Lōkavibhāga* of Śimhasūri is stated to have been completed in the 'year 80 beyond 300, (i.e., 380) of the Śaka years' (*MAR*, 1922).

Two ways are adopted in citing this era in the inscriptions of Tamil country. One is expressing it in the number of 'expired' years like *Śakābdam* 1665-*n mēl sellāninra* (in the year current after Śaka year 1665—No. 947 of this collection). The other way is to express it as 'current'. Citing the era as current in inscriptions is rare and this can be determined only on verification and from the cyclic year named therein. This can best be shown by the analogy of the Śaka year for the cyclic year Hēvilambi according to National Calendar in India is 1879 (which is expressed in the expired year) while according to the Tamil *pañchāṅgams* it is 1880 (expressed as current).

Similarly, in the inscriptions of the extreme South and the West Coast or the Kēraḷa region, the most common era used is the Kollam-aṇḍu which commenced in 824 A.D. This is referred to in the records, especially those of the earlier period, as *Kollam-tōṇri*, (after the appearance—or emergence—of Kollam) which is generally taken as counted from the creation of the Kollam town.

A stray reference to another Kollam era, counted from the destruction of Kollam in 1096 A.D. has been referred to elsewhere in this book (pp. 77-8 of the Historical Survey).

The Kali era counted from the vernal equinox of 3101 B.C. is sometimes mentioned in inscriptions. One of the two related stone inscriptions from Ānaimalai in the Madurai District (*EI*, vol. VII) of the reign Parāntaka, which gives the earliest definite date in the Early Paṇḍyan chronology, is dated in the Kali era 3871 yielding A.D. 770. In some of the later records the date in this era is mentioned along with that of the Śaka era.

Sometimes the Tamil inscriptions from the West Coast are found dated in the Jupiter Cycle, otherwise known as *Viyāḷa-vaṭṭam*. The planet Jupiter stays in each house of the Zodiac for roughly one year and the year is named after that house, thus *Mēsha-viyāḷam*, etc. The Tamil inscriptions of Bhāskara Ravivarman (*TAS*, vol. II) dated in this twelve year cycle are typical examples.

We have also recovered so far three Tamil inscriptions dated in the Hijri era. Two of them are published by Dr. S. Krishnaswami Aiyangar in his *South India and her Muhammadan Invaders* and the third has been obtained from Alañgiyam in the Coimbatore District, (No. 160 of 1920). All these three refer to the period in the fourteenth century A.D. when the Sultāns of Madurai were ruling over that part of the country.

The Western Chalukya ruler Vikramāditya VI started an era of his own, named the Chalukya Vikrama era, with 1075-76 A.D. as the initial year. This continued in use even in the early part of the reign of his son, but subsequently fell into disuse. Another of his successors also started an era likewise; but it was also short-lived. Inscriptions in these eras are found only in portions of the Karṇāṭaka and Telugu countries.

There are also references, mostly in the epigraphs obtained from the West Coast, to other eras which were mainly of local origin and were in use only for short periods :

*Tirukkulaśēkharapurattu-t-talikkku-ch-chellāninra-yāṇḍu nūrru-t-tonṇūttāṇju : ivvāṇḍu makara-nāyarru.* (In the month of Makara in the year one hundred and ninety-five after the consecration of the temple at Tirukkulaśēkharapuram—TAS, vol. VI, p. 193.)

*Tirukkaṇḍiyūr Mahādēvarkku sarvādityain śeyd-arūḷi-ch-chellāninra yāṇḍu munnūrru-t-tonṇūrru nālām āṇḍai mēḍa viyālattil.* (In the year three hundred and ninety-four counted from the consecration (sarvādityam) of Mahādēva at Tirukkaṇḍiyūr, when the Jupiter stood in the mēsha or Aries—TAS, vol. I, p. 290.)

The Paliyam plates registering the agreement between the king of Cochin and the Dutch East India Company (*Lēnda-kummaṇji*) in 1663 A.D. is dated in the year 322 of the Pudu-Vaippu era, which is said to have commenced with the throwing up of the island 'Vaipen' by the sea. (TAS, vol. I).

There are also other records giving dates reckoned from some important local events (vide : *Kāndaḷṇṇr Sālai* by S. Desikavinayakam Pillai, pp. 18—20).

The Vikrama-Samvat, commencing with 57 B.C. and one hundred and thirty-five years earlier than the Śaka era, is another well-known era largely used in inscriptions. But its use has been mostly in Northern India. Inscriptions dated in this era are found in South India only sparingly. This era has been referred to variously as the *Krita*, *Mālava-abda* or merely as *Samvat* and occasionally as *Vikrama Samvat* in the records.

In the north Indian inscriptions various other eras are found used. The Gupta era with the starting point fixed in 319 A.D., the Valabhī era, also said to commence from the same time, the Kala-ḥūrī or Chēḍī era starting in 248 A.D., the Harsha era commencing



in 606-7 A.D., the Newar era of 879 A.D. the Traikūṭa-Abhira era, (248 A.D.) the Lakshmaṇa-Sēna era of 1179 A.D., and the Gaṅga era of the Eastern Gaṅgas of Kalinga with 496 A.D. as its initial year are some of the well-known eras largely used as such.

But there are many more. The Mahāvīra era or Vīra-Nirvāṇa era with the day of *nirvāṇa* of the Jaina tīrthaṅkara Mahāvīra as its starting point is used mostly in Jaina manuscripts. Another one, similarly with the date of *nirvāṇa* of the Buddha as its starting point, is used by the Buddhist not only in this country, but also in other countries like Ceylon and Burma.

The initial dates of some of these eras have been fixed only tentatively and the study of the various eras by itself is an interesting subject deserving separate and special treatment.

### Numeral Notation

Sometimes the date is not given in numerical figures, but in other ways with some letters of the alphabet or words having fixed numerical values.

There are two systems of numeral notation by letters known respectively as the *Kaṭapayādi* and the *Siddhamātrikā*. Both of them, according to Burnell, are originally South Indian (*ESIP*, p. 79).

In the *Kaṭapayādi* system each letter of the vowelless consonants of the Sanskrit alphabet beginning with *ka*, *ṭa*, *pa* and *ya* is assigned the number consecutively from 1 to 9 and 0 as follows.

1	2	3	4	5	6	7	8	9	0
ka	kha	ga	gha	ṇa	cha	chha	ja	jha	ṇa
ṭa	ṭha	ḍa	ḍha	ṇa	ta	tha	da	dha	na
pa	pha	ba	bha	ma	...	...	...	...	...
ya	ra	la	va	śa	sha	sa	ḥa	ḷa	...

This system is generally applied in expressing dates in chronograms, when these letters would be insufficient and additional ones have to be introduced. As such, all vowels and compound consonants thus added have no value; only the final consonant of a ligature will have the numerical value.

Usually these chronograms are given in Sanskrit verses and are so introduced that the words employed in expressing them verbally also have meanings connected with them.

A record in the Varadarāja temple at Kāñchīpuram (No. 1290 of this collection) registering the consecration of the *Kalyāṇakōṭi-vimāna* of the temple erected by Lakshmikumāra Tātachārya gives its date Śaka 1536 in chronogram as follows :

*tallakshmīdye*

6 3 5 1

which when read in the reverse way gives the required figure.

In this system as well as in the other, *Bhūṭasamkhyā*, the unit is mentioned first, then the tenth place and so on progressively. As such to express the figure in the decimal notation, the whole sum has to be turned round, *i.e.*, read from right to left.

The other system, *Siddha-mātrikā*, is also known as *Bārākhadi* and *dvādaśāksharī*. In this each of the vowels, with the exception of *r*, *ṛ*, *ḷ* and *ḹ*, is assigned the number consecutively from one to twelve as follows :

a	ā	i	ī	u	ū	e	ai	o	au	aṁ	aḥ
1	2	3	4	5	6	7	8	9	10	11	12

This system is found used only in the pagination of manuscripts. It is still used in Ceylon, Siam and Burma. When the vowels are exhausted, the consonants are used : thus *ka* to *kaḥ* = 13 to 24; *kha* to *khaḥ* = 25 to 36. In a manuscript from Burma, the pagination commences not with the vowels but with vowelised consonants, without eliminating the four special vowels *r*, *ṛ*, *ḷ* and *ḹ* mentioned above; thus *ka* to *kaḥ* = 1 to 16. When the whole cycle is exhausted, it is begun again with 2 *ka*, 2 *kā*, and so on. It is said that the pagination of the Siamese manuscripts agrees exactly with that of Burma.

One other way also is mentioned by Burnell. In this the letters *ka* to *ḷa* of the Sanskrit alphabet are equivalent to 1 to 34; *kā* to *ḷā* = 35 to 68 and so on. But this system is very rare.

### Bhuta-samkhyā (The word-numerals)

Sometimes, numerals are expressed by significant words which connote a fixed number of things, beings or ideas. It is well-known that the Vēdas are four in number and there are three worlds, the nether world, the earth and the celestial world. So, the words *vēda* and *lōka* are found used to express the numerals four and three respectively. The earliest traces of this system are found in the

*Śrautasūtras* of Katyāyana and Laṭyāyana. It is also seen in the Vēdic Jyōtisha, Varāhamihira's *Pañcha-siddhāntikā* and in the arithmetic of the Bakshālī manuscript. Al Berūnī gives a full list of such words used then to denote the numbers from cipher to forty-nine.

This system is found used in inscriptions also in expressing the dates. The Śrīraṅgam Tamil inscription of the Vijayanagara monarch Achyutadēva Mahārāya dated in Śaka 1461 recording the performance of a *tulābhāra* ceremony by the king, evidently at Hampi, contains two Sanskrit verses by his queen Tirumalambā wherein the date is expressed (*EI*, XXIV, p. 290) as follows : *Śākē chandra-ras-āmarēndra-gaṇitē* [in (the) Śaka (year) counted by *chandra* (1) *rasa* (6) and *amarēndra* (14) thus 1461].

In this system also, the numerals are mentioned first, then the tens and so on and in computing the intended figure these have to read in the reverse direction.

The most important words used to express the numerals up to twelve are given below. On many occasions the numerous synonyms of these words are also used.

0 (cipher) : *śūnya* (a void); *ambara*, *ākāśa* (the empty space of the sky); *ananta*

1 : *indu*, *śaśi* (the moon); *bhū*, *mahī* (the earth); *ādi* (the beginning); *pitāmaha* (Brahmā); *rūpa*, *tanu* (the body); *nāyaka* (the hero)

2 : *nayana* (the eyes); *karṇa* (the ears); *bāhu* (the arms); *kara* (the hands); *paksha*, (the fortnight or the two halves of a lunar month, the two wings or the halves of the body); *yama*, *yamala* (the twins); *aśvin*, *dasra* (the two Aśvins); *ravi-chandrau* (the sun and the moon); *kuṭumba* (the family)

3 : *agni*, *hōtr* (the three sacrificial fires); *rāmāḥ* (the three Rāmas); *guṇa*, *triguṇa* (the three qualities of matter); *lōka*, *trijagat* (the three worlds); *trikāla* (the three times, past, present, and the future); *sahōdara* (brother)

4 : *vēda*, *śruti* (the four Vēdas); *diś* (the four cardinal points); *varṇa* (the four principal castes); *abdhī*, *jaladhi* (the oceans); *aya*, *kṛita* (the four dice); *bandhu* (the relatives); *kōshīha*

5 : *Pāṇḍava* (the five Pāṇḍava heroes); *indriya* (organs of sense); *artha*, *vishaya* (the objects of the senses); *bhūta* (the elements); *ishu*, *bāṇa* (the five arrows of Kāma, the god of Love) *prāṇa*; (the five vital airs); *ratna* (the five jewels); *suta*, *putra* (son)

6 : *rasa* (the six flavours); *ritu* (the seasons); *aṅga* (the auxiliary sciences of the Vēdic study); *darsana* (the six philosophical systems); *kāya*; *rāga* (the principal tunes); *ari*, *śatru* (enemy)

7 : *rishi* (the seven seers) or by *atri*, the first among them; *svara* (the musical notes); *aśva* (the horses of the sun); *aga* (the primeval mountains); *dhātu* (the elements); *chandas* (the classes of the metres); *kalatra* (wife)

8 : *vasu* (the Vasu gods); *ahi* (the eight classes of snakes); *gaja* (the elephants guarding the eight points); *siddhi* (the eight super-natural powers); *māṅgala* (the auspicious things)

9 : *aṅka* (the final of the decimal figures); *nanda* (the nine Nandas); *gō*, *graha* (the planets); *chidra*, *dvāra* (the cavities of the body); *nidhi* (the treasures of Kubēra); *pavana*; *bhāgya*

10 : *avatāra* (the incarnations of Viṣṇu); *rāvaṇaśīras* (the ten heads of Rāvaṇa); *karma* (the ceremonies); *khēṇḍu* (*kha*+*indu* or cypher 0 and the moon 1 or 10)

11 : *rudra* (the eleven Rudras) or sometimes by *īśa* or *Śiva*, the first of the *Rudras*; *akshauhini* (the regiment of the army); *lābha* (income, profit)

12 : *āditya*, *arka* (the twelve Ādityas or sun-gods); *vyaya* (expenditure; loss).

It is well known that the words *tanu* for 1, *kuṭumba* for 2, *sahōdara* for 3, *bandhu* for 4, *putra* for 5, *śatru* for 6, *kalatra* for 7, *māṅgala* for 8, *bhāgya* for 9, *karma* for 10, *lābha* for 11 and *vyaya* for 12 are used to express the respective Zodiacal houses in the science of Horoscopolical Astrology.

Occasionally we find the date expressed combining one or two of the above methods. Thus in one inscription the figure three thousand and eight hundred is expressed as *sahasra tritaya-vasu-śataih*.

## 12. SOME EPIGRAPHICAL CONVENTIONS

The early inscriptions, both on stone and copper, discovered so far are characterised by their simplicity. They had no set phraseology or style in their form and contents. In course of time conventions grew up and set phraseology was evolved. This differed from place to place and from time to time. Thus to express 'inclusive of all land, high and low, together with the cultivation and usufructs thereof'

we find the term *uḍumbōḍi āmai tavaḷḍa-v-ellām* (wherever the iguana runs and the tortoise crawls) used at one time and *mēl-nōkkiya-maramum kiḷ-nōkkiya kiṇarum* (with the tree pointing upwards and the well pointing downwards) or *puṇṇum terriyum* (with the mound and ant-hill) at other times. In the inscriptions of the Koṅgu country the regnal year of the reigning monarch is expressed invariably as *tiru-v-eḷutt-iṭṭu-ch-chellānina tiru-nal-li-yāṇḍu* [in the prosperous and illustrious year running current after affixing the illustrious signature (proclaiming him as the king)]. In the earlier Tamil inscriptions, we find the word *murruṭṭu* used in the sense of *sarvamānya* of the later records. The study of this inscriptional phraseology is an interesting subject.

During the mediaeval days, a convention came to be recognised in certain temples, whereby donations and gifts made to temples by individuals or chieftains were recorded as having been made by the god himself. This is best illustrated by an inscription (Nos. 138, 139 of this collection) from Śrīvilliputtūr in the Rāmanāthapuram District registering the gift of the village Tīḍiyan *alias* Tiruvaraṅganallūr by the Bāṇa chieftain Uraṅgavillidāsan *alias* Mahābali Vāṇadharāyan for the expenses of the kitchen (*aḍukkaḷai-p-puram*) of the temple in Ś'aka 1375 or 1454 A.D. The record is drawn up in the form of a *pranayapatrikā* or love letter which god Rāṅganātha sent to Kōḍai, daughter of Viṣṇuchitta of Pudevai (i.e., the Vaiṣṇava lady saint Āṇḍaḷ, daughter of Saint Periyālvār of Śrīvilliputtūr). It commences with a long preamble relating to the story of the divine love of Śuḍik-kodutta Nāchchiyār towards god wherein many expressions from the *Tirupṇāvai* and the *Nāchchiyār-Tirumōḷi* of the *Nālāyirapprabandham* have been introduced incorporating half and full verses so as to make a connected description, in her own words, of the love-lorn maid Āṇḍaḷ towards her divine lover. This closes with the idea that "pleased with the devotion by the lady-saint, god Rāṅganātha ordered that several honours equal to those shown to him should also be bestowed on her," and that for that purpose, granted the village Tīḍiyan belonging to Uraṅgavillidāsan on the date specified.

This convention seems to have come into use much earlier. A record from Tiruvārūr in the Tañjāvūr District (*SII*, vol. V, No. 456) dated in the 5th regnal year of Vikrama Chōḷa appears as if ordered by god Śiva enshrined in the temple there. The record which registers the grant of a *māḷigai* to a certain Chandraśēkharan Ādiviṭaṅkan *alias* Kulōttuṅgachōḷa Mahābali-vāṇa[dhirayan] of Pālaiyūr. The preamble commences with the well-known story of

the mythical king Manu-nīti-Chōla who was ruling from Tiruvārūr, to whom Ubhaya Kulāmalan, the *udaiyān* of Palaiyūr, an ancestor of the above Bāṇa, was the minister. The story says that unwilling to execute the order of the king to crush the prince under the wheels of the chariot, the minister plucked out his ear which heard the royal order and died; but he was restored to life by the god, pleased with his devotion, along with the prince who was crushed by the king himself. The *māligai* presented to the minister by the king then had long fallen into disuse and even changed hands. The god now is said to have ordered restoration of the same to a descendant of the minister.

*Artistic Writing:* As already stated special scribes were employed to incise epigraphs with the main object of making such records clear to read and also pleasing to look at. Sometimes the scribes were really skilful at their work and naturally took great pride in their execution. In an inscription of the Eastern Chālukya ruler Narēndramrigarāja the scribe is called *akshara-lalitāchārya* (expert writer of beautiful letters—*SII*, vol. I, p. 36). Another record from Bhuvanēśvara in Orissa compares clear and distinct letters to pearls and gems set (*EI*, vol. VI, p. 202) while another compares them to stars in the sky (*Ibid*, vol. II, p. 13). One scribe compares himself to Chitrāgupta, the divine scribe, (*Ibid*, vol. VIII, p. 153) while another describes his well-cut letters as resembling Sarasvatī. (*Ibid*, vol. IX, p. 254). The scribes thus took great pains in executing their work. This is clearly manifest when one scribe compares himself to a lover painting intently with different colours a picture of his beloved one (*Ibid*, vol. XIII, p. 292).

These were not empty boasts. The available examples fully portray the dexterity with which they were executed. To make the writing appear beautiful, the scribes even introduced floral and other artistic designs in their writing. A Kannaḍa record actually praises the skill of one such scribe in the following words: 'when he can entwine forms of elephant, lion, parrot and many other forms so as to shine among letters, will you madly compete with such a sculptor, Sōvaraśi?' (*EC*, vol. XI, Cd. 47).

Such florid and ornamental scripts actually used in the inscriptions of the Tamil country are best seen in an inscription of the Pallava monarch Rajasimha, repeated four times and engraved in different varieties of the script round the base of the Kailāṣanātha temple at Kāñchīpuram erected by him.

The name of Śrī Pūrṇādītya, incised on a pillar in the temple of Rajivalōchana at Rajim, is in a highly ornamental type of letters (C. ASR, vol. XVII, plate X). The letters are so obscured by the peculiar decorative pattern added that it is rather difficult to make them out ; but they can be easily made out by comparing them with the same name in plain letters given with it by Cunningham.

In the Kurgod inscription of the Western Chālukya ruler Śōmēśvara IV, the *anusvāras* are represented by stars arranged above the letters and the letters are shaped like animals and birds. Thus one of them is shaped like a swan and another like a peacock (IA, vol. XV, p. 364).

The so called shell characters from Central India offer another variety of ornamental type producing amusing letter-shapes, sometimes presenting great difficulty in decipherment (JBORS, vol. XX, p. 10-12). Similar shell characters occur even in distant Java (EI, vol. XXII).

*Pagination* : Numbering of pages was necessary to ensure the sequence of the contents of a document, where it contained more than one sheet. There was no necessity to number in the case of lithic records and single-plate documents. The practice was to number only the sheets (*pattra*) and not the pages as is obtaining now. This was followed not only in the case of the palm-leaf manuscripts, but also of copper-plates, though not quite regularly in the case of the latter. In the South, the usual practice was to place the number in the first page of the sheet on the left margin or very near the hole through which the ring or the string holding the leaves together passes. But in some of the north Indian manuscripts the pagination is found on the second page (*śāṅka-prishṭha*). Occasionally, in some of the stone inscriptions we find the lines of the record also are numbered.

*Language* : Inscriptions also form an important link in the study of the growth of the various languages in this country. We have already mentioned that many of the composers of inscriptions were poets of great merit. The Aihole inscription of Pulikēśin II was composed by Ravikīrti, " who by his poetic skill has attained to the fame of Kalidāsa and Bhaṛavi." (EI, vol. VI). Many of the inscriptions, sometimes, contain quotations from classical literature. An inscription of the Western Chālukya monarch Vikramādītya VI at Huli contains the opening verse of the *Raghuvamśa* of Kalidāsa as its invocation. (EI, vol. XVIII). Similarly the *maṅgalaślōka* of the *Abhijñāna-Śākuntalam* occurs as an invocatory verse in an inscription from Rājaputana (*Ibid*, vol. XI, p. 65).

An inscription in Tamil from Śrīvilliputtūr in the Ramanāthapuram District (No. 138 of this collection) of the time of the Bāṇa chief Uṇṅavillidāsan contains, as already mentioned, extracts from the *Nālāyira-p-prabandham*. Another copper-plate grant from Tirumaḷuvaḍi in the Tiruchirapalli District dated Śaka 1662 contains similarly extracts from the *Tēvāram* (No. 693 of this collection).

We have already mentioned that the inscriptions of a locality are generally found in the local language or in Sanskrit or in both the languages. Occasionally we have records in other foreign languages also. From Śrīraṅgam has been obtained an inscription (No. 204 of 1942) in the Kannaḍa language and script dated the 29th regnal year Kulōttuṅga Chōla I registering the gift of two lamps by an officer of the Western Chālukya king Vikramāditya VI, the *Kannaḍa-Sandhivigrahin* and *Danḍanāyaka*, who seems to have constructed of brick and mortar the shrine of Vishvaksēna in the temple. After the advent of rule of the Vijayanagara empire this practice seems to have increased and inscriptions in the Telugu and Kannaḍa languages seem to have increased in number. We have already referred to the Mahratti inscription of Māharāja Śarabhōji in the Brihadīśvara temple at Tañjavūr. Such instances show the languages of the donors or authors of these records as also the high position they occupied.

Sometimes inscriptions in one language are found engraved in quite a different script. An inscription of the time of the Vijayanagara ruler Krishṇadēvaraya from Tirupparuttikkunṅam near Kañchīpuram (No 458 of this collection) in the Kannaḍa language is found engraved in the Tamil script. Another record of the time of Rajēndra Chōla I mentioning his general Araiyan Rajarajan *alias* Vikrama Chōla Śōliyavaraiyan (*SII*, vol. IX, No. 300) from Kottasivaram in the Anantapur District in the Tamil language is incised in the Kannaḍa script. At Śrīraṅgam we have a Tamil inscription written in the Nagari characters. There is also a Telugu record of the Kakatiya king Gaṇapatidēva inscribed in the Grantha characters. Similarly, an epigraph dated in the Kali year 4068 equivalent to 968 A.D. of the Aḷupa king Kundavarma of the Tuḷu country written in the Grantha characters is found engraved on the pedestal of the image of Lōkēśvara in the Mañjunātha temple at Kadiri near Mangalore. (*Ibid*, vol. VII, No. 191). Similar instances are also available in other parts of the country.

When Tamil kings were powerful, we find Tamil records in far distant places and this fact clearly testifies to the influence of the



Tamiḷs in those lands. At Bhuvanēśvara in Orissa, we have a Tamil inscription dated in the twelfth regnal year of Narasimha (IV), the Gajapati ruler of the place. (*JRASB*, 1924. The text given there is very faulty. A revised reading of it was given by me four years ago in the *Amudhasurabhi*).

A Tamil inscription (*JRAS*, 1913 ; *EI*, vol. XVIII) in characters of the tenth century has been recovered even from Siam.

The above study will clearly show how important the inscriptions, whether official or private and whatever may be their contents, are for the reconstruction of our past history in all its phases. But many of them have been irretrievably lost due to vandalism and occasionally due to good and pious intentions. When the Śiva temple at Tiruviḍaimarudūr in the Tañjavūr District was renovated fifty years ago, all the inscriptions on the outer walls of the temple were lost and only those engraved on the central shrine were copied. Even they have been lost since. A typical case as to how an inscription was damaged, its value not being known, is the inscribed Eran pillar which was transformed into a Śiva *līṅga* by a pious devotee.

An inscription on a stone slab at Pandharpur called *Chōraśi Śilā* has almost disappeared being constantly rubbed away by pilgrims rubbing their back on the slab, supposing that thereby they would be free from the eighty-four lakhs of rebirths. This is a typical instance of how inscriptions are damaged by actions done quite innocently or sometimes made in good faith.

---

### List of Abbreviations

<i>ABORI</i>	Annals of the Bhandarkar Oriental Research Institute, Poona
<i>ARSIE</i>	Annual Report on South Indian Epigraphy
<i>ASIAR</i>	Archaeological Survey of India, Annual Report
<i>ASSI</i>	Reports of the Archaeological Survey of Southern India
<i>ASWI</i>	Reports of the Archaeological Survey of Western India
<i>C. ASR</i>	Reports of the Archaeological Survey of India, Cunningham's Series
<i>CII</i>	Corpus Inscriptionum Indicarum
<i>EC</i>	Epigraphia Carnatica
<i>EI</i>	Epigraphia Indica
<i>ESIP</i>	Elements of South Indian Palaeography by Dr. A. C. Burnell, 2nd Edition, 1878
<i>GI</i>	Gupta Inscriptions, edited by J. F. Fleet, being vol. III of the <i>Corpus Inscriptionum Indicarum</i>
<i>IA</i>	Indian Antiquary
<i>JASB</i>	Journal of the Asiatic Society of Bengal
<i>JBBRAS</i>	Journal of the Bombay Branch of the Royal Asiatic Society
<i>JOR</i>	Journal of Oriental Research, Madras
<i>JRAS</i>	Journal of the Royal Asiatic Society, London
<i>JRASB. L</i>	Journal of the Royal Asiatic Society of Bengal, Letters
<i>MAR</i>	Mysore Archaeological Survey Reports
<i>PSI</i>	Inscriptions of the Pudukkottai State
<i>SII</i>	South Indian Inscriptions
<i>TAS</i>	Travancore Archaeological Series

## சரித்திரக் குறிப்புகள்

(முதற் பகுதியின் clxxxviii - ஆம் பக்கத் தொடர்ச்சி)

சோழர்களுடைய சரித்திரம் முதலாம் இராஜராஜ சோழனுடைய ஆட்சிக் காலத்திலிருந்து தெளிவாக இருக்கிற தெனக் கொள்ளலாம். எனினும், இன்னும் நன்கு விளங்காத பகுதி பல இருக்கத்தான் செய்கின்றன.

### முதலாம் இராஜராஜன்

இந்தத் தொகுப்பிலே முதலாம் இராஜராஜ சோழனுடைய சாசனங்கள் சுமார் பதினைந்து உள்ளன. அவை அவனுடைய ஆட்சியின் இருபத்தேழாம் ஆண்டுவரையில் உள்ள காலத்தைச் சார்ந்தவை.

இம் மன்னனுடைய சாசனங்களில் பெரும்பாலானவை 'திருமகள்போல' என்று தொடங்கும் மெய்க்கீர்த்தியுடனே காணப்படும். அவ்விதம் மெய்க்கீர்த்தி இல்லாதனவற்றுள் அரசனுடைய பெயர் 'காந்தனூர்ச்சாலைக் கலமறுத்தருளிய இராஜகேசரிவர்மன்' என்றோ 'சாலைக் கலமறுத்தருளிய இராஜகேசரிவர்மன்' என்றோ சுருக்கமான அடைமொழியுடன் காணப்படும். 'திருமகள்போல' என்னும் மெய்க்கீர்த்தி அவனுடைய ஆட்சியின் எட்டாம் ஆண்டிலிருந்தே காணப்படுவதாயினும் 'காந்தனூர்ச் சாலைக் கலமறுத்தருளிய' என்னும் அடைமொழி இம் மன்னனுடைய நான்காம் ஆண்டுச் சாசனங்களிலேயே உள்ளன. இதுவே அவனுடைய ஆட்சியில் கிடைத்த முதல் வெற்றிபோலும். அன்றி, இவன் இந்த நிகழ்ச்சியைத் தன்னுடைய வெற்றிகளுள் முக்கியமானதாகவும் கருதியிருத்தல் வேண்டும்.

இந் நிகழ்ச்சி எதைக் குறிப்பதாகும் என்பதைப்பற்றி ஆசிரியர்களுக்கிடையே பலத்த விவாதம் நடந்திருக்கிறது. ஆரம்பத்திலே இந்தத் தொடர், 'அரசன் காந்தனூரிலே

மணிமண்டபம் ஒன்றை எழுப்பினான்' என்பதைத் தெரிவிப்பதாகக்கொண்டு மொழிபெயர்க்கப்பட்டது. (தேன் இந்திய சாசனங்கள், முதல் வால்டும், பக்கம் 65). அப்பால் இது, 'மன்னன் காந்தனூரிலே ஒரு கலத்தைத் துண்டாக்கினான்' என்ற பொருள்பட மொழிபெயர்க்கப்பட்டது. (ஷே இரண்டாம் வால்டும், பக்கங்கள் 35, 47). கடைசியாக, இத் தொடர் 'அரசன் காந்தனூர்த் துறைமுகத்துச் சாலையில் கப்பல்(மரக் கலங்)களை அழித்தான்' என்று திருத்தப்பெற்றது. (ஷே பக்கங்கள் 241, 247). இந்தப் பொருளே இப்போது பொதுவாக ஏற்றுக்கொள்ளப்பட்டு வருகிறது.

காந்தனூரிலே இருந்த அறச்சாலை, அதாவது போஜன சாலையைப் பற்றியதாகவே இந்தத் தொடரைக் கொள்ள வேண்டுமென்ற மற்றோர் அபிப்பிராயமும் உள்ளது. காந்தனூர் அறச்சாலையில் சோறு அட்டுவதை அரசன் நிறுத்திய செய்தியைக் குறிப்பதாகவே இதைக் கொண்டார் காலஞ்சென்ற ஆராய்ச்சியாளர் து. அ. கோபிநாதராவ் (திருவாங்கூர் ஆர்க்கியலாஜிகல் ஸீரீஸ், இரண்டாம் வால்டும், பக்கங்கள் 3, 4). கவிமணி தேசிக விநாயகம் பிள்ளை அவர்களோ 'அரசன் காந்தனூர்ச் சோற்றுச்சாலையில் உணவு அளிக்கவேண்டியமுறையை நிர்ணயித்துத் திட்டம் செய்தான்' என்று கூறுவர். (கேரளா ஸோலைட்டி பேப்பர்கள், இரண்டாம் தொகுதி, பக்கம் 100-க்கு மேல்; காந்தனூர்ச்சாலை என்று அவர் தனியாக வெளியிட்ட சிறு நூலையும் பார்க்க). போஜனசாலையைக் குறிப்பதாகக் கொண்ட இந்தக் கொள்கையை அதீதமான கற்பனை யென்று ஆராய்ச்சியாளர்கள் ஒதுக்கிவிட்டார்கள்.

காந்தனூரிலே சோழமன்னன் மேற்கொண்ட நடவடிக்கை எதுவாக இருப்பினும் அதன் புகழை முதலாம் இராஜராஜ சோழன்மட்டுமே கொண்டான் என்பதில்லை. தொடர்ந்து, அவன் மகன் முதலாம் இராஜேந்தின், பெயரன் முதலாம் இராஜாதிராஜன், இன்னும் முதலாம் குலோத்துங்க சோழன், பாண்டியர்களிலே ஜடாவர்மன் பரந்தக பாண்டியன் ஆகியவர்களும் இந்தப் புகழைத் தங்களுக்கு ஏற்றிக் கூறிக்கொள்ளுகிறார்கள். புதுச்சேரிக்குப் பக்கத்தில் உள்ள திருவாண்டார்கோயிலிலிருந்து முதலாம் இராஜேந்

திர சோழனுடைய ஆட்சியின் பத்தாம் ஆண்டு கொண்ட கல்வெட்டு ஒன்று கிடைத்திருக்கிறது. (1917-ஆம் ஆண்டின் 363 நெ. சாசனம்). 'திருமன்னிவளர' என்று தொடங்கும் அவனுடைய மெய்க்கீர்த்தியோடு ஆரம்பமாகும் அந்தச் சாசனத்தில் அரசன் பெயர் தண்டாற் சாலைக் கலமறுத்த கோப் பரகேசரி வர்மன் என்று குறிக்கப்பெற்றிருக்கிறது. 'பாரது நிகழப் பாண்டியமண்டலத்து மதுரையில் மாவிகை எடுப் பித்து, தன் மகன் சோழபாண்டியன் என்றபிஷேகம் செய்து' என்று காணப்படுவதைத் தொடர்ந்து சாலைக் கலமறுத்த செய்தி காணப்படுகிறது. (சாசன இலக்காவின் 1918-ஆம் ஆண்டு அறிக்கை, பக்கம் 144; க. அ. நீலகண்ட சாஸ்திரிகள் எழுதிய சோழர்கள், முதல் வால்பூம், பக்கம் 552).

'திங்ளேர் தரு' என்று தொடங்கும் முதலாம் இராஜாதி ராஜனுடைய மெய்க்கீர்த்தியில் மன்னன் 'வேலைகெழு காந்த னார்ச் சாலைக் கலமறுத்த' செய்தியும் இடம்பெற்றிருக்கிறது. (தே. இ. சாசனங்கள், மூன்றாம் வால்பூம், பக்கம். 56).

"லிக்கிரமன்சோழன் உலா"விலே முதற் குலோத்துங்க னைப்பற்றிக் கூறுமிடத்தில்,

"—மேவலர்தம்  
சேலைத் துரந்து சிலையைத் தடிந்திருகால்  
சாலைக் கலமறுத்த தண்டினன்"

(கண்ணீ 24)

என்று கூறப்பட்டுள்ளது. இதே செய்தி கலிங்கத்துப்பரணியில் கலிங்க மன்னனான அனந்தவர்மனிடம் அவனுடைய மந்திரி ஒருவன் கூறுவதாக,

'வேலை கொண்ட விழிஞ மழித்ததும்  
சாலை கொண்டதும் தண்டுகொண் டல்லவோ'

(தாழிசை 370)

என்று முதற் குலோத்துங்க சோழனுடைய பெருமை எடுத்த துரைக்குமிடத்தில் காண்கிறது.

‘திருவளரச் செயம்வளர’ என்று தொடங்கும் மெய்க் கீர்த்தியையுடைய பாண்டிய மன்னனான ஜடாவர்மன் பாரந்தக பாண்டியனுடைய கன்னியாகுமரிக் கல்வெட்டில் அவன் ‘கன்னிப்போர் செய்து காந்தனூர்க்கலைக் கலமறுத்த’ செய்தியும் குறிக்கப்பட்டுள்ளது. (திருவாங்கூர் ஆர்க்கியலாலிகல் ஸீரீஸ், முதல் வால்பூம், பக்கம் 18 முதல்). அவன் விக்கிரம சோழனுடைய ஆட்சிக் காலத்தில் சோழர்களுடைய ஆட்சிக்கு உட்பட்டவனாக அரசு புரிந்தான் என்று கருதப்படுகிறது. ஆதலின், அவன் கொண்ட வெற்றியும் பேரரசர்களான சோழர்களுடைய சார்பில் கொண்டதாகவே இருத்தல் வேண்டும்.

மேலே எடுத்துக் காட்டியவற்றைக் கவனிக்கும்போது காந்தனூர்ச் சாலைக் கலமறுத்த சம்பவம் எதைக் குறிப்பதாக இருப்பினும், சுமார் ஒன்றரை நூற்றாண்டுக் காலத்துக்கு ஒருவர் பின் ஒருவராகச் சோழ மன்னர்கள் பலராலும் மேற்கொள்ளப்பட்ட தென்பதும், ஒவ்வொரு தடவையும் படைவலிகொண்டே அவர்கள் அதைச் செய்து முடிக்க வேண்டியிருந்தது என்பதும் விளங்கும்.

தஞ்சைச் சோழ மன்னர்களின் ஆட்சி ஆரம்பமாவதற்கு முற்பட்ட காலத்திலிருந்தே காந்தனூர் ஒரு முக்கியமான இடமாக விளங்கி வந்திருக்கிறது. கி. பி. எட்டாம் நூற்றாண்டில் பல்லவ அரசனான நந்திவர்மன் பல்லவமல்லனுக்குச் சம காலத்தவனாகவும் (அவனுக்குக் கீழ்ப்பட்ட சிற்றரசனாகவும்) விளங்கிய முத்தரைய மன்னன் சுவரன் மாறன் என்பான் காந்தனூரில் நடத்திய போரில் பெருவெற்றி கொண்டான் என்பதை,

“செருவ[ல ரா]னதனற் சிந்தியார் போலும்  
மருவலராய் வாண்மாறன் சீறக்—கருவளை  
கண்டோற்ற வண்டரவங் கார்தோற்றுங் காந்தனூர்  
மண்தோற்ற வேந்தர் மனம்”

என்று அவனுடைய செந்தலைக் கல்வெட்டுப் பாடல் கூறுகிறது. (அபிகிராயியா இந்திகா, பதினமூன்றாம் வால்பூம், பக்கம் 146.)

‘காந்தனூர்ச் சாலைக் கலமறுத்தருளி’ என்ற சிறு தொடரில் காந்தனூர், சாலை, கலம், அறுத்தல் ஆகிய நான்கு சொற்கள் உள்ளன. எனினும், காந்தனூர் என்ற இடத்தைக் குறிக்கும் முதற் சொல்லைத் தவிர மற்ற மூன்றில் ஒவ்வொன்றும் தனித்தனியே ஒன்றுக்கு மேற்பட்ட பொருளைக் கொடுக்க வல்லது. ஆயினும் ஒரு விஷயத்தை நாம் நினைவில் கொள்ள வேண்டும். அந்தக் காலத்துச் சாசனங்களில், ‘சாலை’ என்பதும் ‘கலம்’ என்பதும் முறையே உணவுச் சாலையையும் உண் கலத்தையுமே குறிப்பனவாகக் காணப்படுகின்றன; ‘துறைமுகப் பெருவழி’ என்ற பொருளிலே சாலை என்னும் சொல் ஆளப்பட்டிருப்பதாக வேறு எந்த இடத்திலும் காணவில்லை. காந்தனூர் என்பது இப்போது திருவனந்தபுரம் என்று வழங்கப்பெறும் நகரத்தின் ஒரு பகுதியான ‘வலிய சாலை’யே ஆகும் என்று ஆராய்ச்சியாளர்கள் நிர்ணயித்து முடிவுகட்டி யிருக்கிறார்கள்.

இந்தச் சிறுதொடர் குறிக்கும் சம்பவம் எதுவாக இருக்கலாம் என்பதை யறிய வேறு ஒரு சாசனம் உதவிபுரிவதாக உள்ளது. கி. பி. 863-ஆம் ஆண்டில் வேணாட்டு ஆய்குல வேந்தனான கருந்தடக்கன் என்பான் காந்தனூரில் உள்ள சாலையை மாதிரியாகக் கொண்டு அதைப் பின்பற்றிப் பார்த்திவசேகரபுரம் என்னும் இடத்தில் ஒரு சாலை நிறுவி யதைத் தெரிவிக்கும் செப்பேட்டுச் சாசனமே அது. (ஹூஸூர் ஆபீஸ்ச் செப்பேடுகள், திருவா. ஆர்க்கி. ஸீரீஸ், முதல் வால்யூம், பக்கங்கள் 1-14). அந்தச் சாசனம் பொறிக்கப்பட்டிருந்த செப்பேடுகளிலே நடுநடுவே சில ஏடுகள் காணமல்போய் இப்போது ஐந்து செப்பேடுகளே கிடைத்துள்ளன. சாசனம் பூர்த்தியாகக் கிடைக்காமையாலும், சாசன வாசகம் பரிபாஷைச் சொற்கள் நிரம்பிக் கடினமான நடையில் அமைந்திருப்பதாலும், அதன் முக்கியத்துவத்தை இதுகாறும் சரிவர மதிப்பிட முடியவில்லை.

காந்தனூரில் உள்ள சாலையை மாதிரியாகக்கொண்டு அதைப் பின்பற்றிப் பார்த்திவசேகரபுரத்தில் ஒரு சாலை அமைக்கப்பட்டது என்று கூறப்பட்டிருப்பதிலிருந்தே காந்த

னூரில் ஒரு சாலை இருந்ததென்பதும், அந்தக் காலத்தில் அது மிகவும் பிரசித்திபெற்று விளங்கியது என்பதும், அதை இலட்சியமாகக்கொண்டு வேறு ஊர்களிலும் சாலைகளை அமைத்து வந்தார்கள் என்பதும் பெறப்படும். இன்னும், காந்தனூரில் இருந்த சாலையைப்பற்றிய விவரங்கள் நமக்குக் கிடைக்கா விட்டாலும், அதைப்போல் அமைக்கப்பெற்ற வேறு ஒரு சாலையைப்பற்றிய விவரங்கள் நமக்குக் கிடைத்துள்ளனவென்பதும் முக்கியமானது.

பார்த்திவசேகரபுரம் சாசனத்தில் பின்வரும் விஷயம் காணப்படுகிறது: அரசன் சிறிது சிறிதாக மின்சிறை என்னும் ஊர்ச் சபையாரிடமிருந்து வேறு நிலங்களைக் கொடுத்து விளை நிலங்களைப் பரிவர்த்தனை மூலம் பெற்று அவற்றின் எல்லைகளை நிர்ணயித்துப் பார்த்திவசேகரபுரம் என்ற பெயருடன் ஓர் ஊரை நிர்மாணித்தான். அதிலே விஷ்ணு பட்டாரகருக்கு ஒரு கோயிலை எழுப்பினான். அப்பால் 'காந்தனூர் மர்யாதியால் தொண்ணூற்று ஐவர் சட்டர்க்கு ஒரு சாலையுஞ் செய்தான் கோக் கருந்தடக்கன்.' அவ்விதம் அவன் ஏற்படுத்திய சாலையைப்பற்றி அந்தச் சாசனத்திலே காணப்பெறும் விவரங்களே நமக்கு முக்கியமானவை.

“இச்சாலைக்குப் பெய்த கலத்தில் பவிழிய சரணத்தார் உடைய கலம் நாற்பத்தைந்து; தயித்திரியச் சரணத்தார் உடைய கலம் முப்பத்தாறு; தலவகார சரணத்தார் உடைய கலம் பதினான்கு. இனி வருங்கலம்\*] மூன்று சரணத்தார்க்கும் ஒப்பது.” சாலைக்கு நிர்ணயிக்கப் பெற்ற தொண்ணூற்றைந்து சட்டர் ஸ்தானங்களில் எந்த எந்தச் சரணத்தாருக்கு எத்தனை எத்தனை அளிக்கப்பெறவேண்டும் என்பதைக் கூறுகிறது.

“பூவெஸ்க்கஞ் செய்யும் பரிசு. ‘வையாகரண மீமாயப் புரோஹிதப் புண்பாய்ப் புவினும் இலன். நெசுராஜ வஜ்ஹாரத்துக்கு வேண்டும் ஒத்துடையன். இது ஸத்யம்’ என்று ஐவர் சட்டரைக் கொண்டு பஞ்சக்கஞ் செய்தான் புகவு பெறுவான்.



“வாரம் ஒதும் பரிசு. சூத்திரத்திலுஞ் சூத்திராரணத்திலுந் துருச்சொல்லி ஒன்பது புகவினில் இரண்டு கிரம வாரம் அடுத் தோதுவது. சாகையிலும் கற்பத்திலும் கணத்திலுந் துருச் சொல்லி ஒன்பது புகவினில் இரண்டு வாரம் அடுத்தோதுவது. நாலு பாதத்திலுந் துருச்சொல்லி ஒன்பது புகவினில் அகத் தூஹத்தில் இரண்டு வாரம் அடுத்தோதுவது.” இவ்விதம் சட்டர்கள் தாங்கள் கற்றது மறந்துபோகாமல் வாரம் சொல்லி அதை நினைப்பில்கொண்டு வரவேண்டும் என்பதையும் நிர்ணயிக்கிறது சாசனம்.

“முக்கால் வட்டத்து வைத்து ஒரு சட்டனை ஒரு சட்டன் பிழைக்கப் பேசுவானாயில் பெருமக்களுக்கு அஞ்சு காணம் பொன் தண்டம் இட்டுச் சாலை உண்பது. குட்டுவானாயில் ஒரு காசு தண்டம் இட்டு சாலை உண்பது. குட்டுண்டானும் அஞ்சுகாணம் பொன்றண்டம் இட்டு சாலை உண்பது. படைக் கலத்தால் புண்செய்தான் அறத்துக்குப் புறத்தவைது. சட்டர் படைக்கலம் பிடித்துக் கூட்டத்துக்குச் செல்லப் பெரூர்....

“.....யிலகப்பட்ட எச்சுது முக்கால் வட்டத்திலிருந்து பொரப் பெரூர். பொருவார் அற்றைக்கலம் இழப்பது. சட்டர் வெள்ளாட்டிகளை மடத்தில் வைத்துக்கொள்ளப் பெரூர். சாலாபோகமுந் தேவதானமும் சத்திமுகம் இன்றி விலக்கப் பெரூர். விலக்குவார் மெய்வெற்று வகை ஐங்கழைந்து பொன் தண்டம் இட்டன்றிச் சாலை உண்ணப்பெரூர். சாலாபோகத் திலும் தேவதானத்திலும் குடியை வலியக்கொண்ட முதல் ஒன்றுக்குப் பத்தாகக் குடுப்பது. சபைக் கடமை கடவார் பக்கல் மூன்று சரணத்திலும் மூவர் சென்று புக்கது பாடா வது. பாடுப்போகில் ஐம்பத்துநாலு காணம் பொன் தண்ட மும் பட்டு, கடமையும் குடுப்பது. தேவர் சென்னடையும் பதினாழிச் சாலையும் எவ்வழக்குச் சொல்லியும் விலக்கப் பெரூர். விலக்குவார் நியதி கழஞ்சு பொன் தண்டம் இட்டன்றிச் சாலை உண்ணப்பெரூர். பணி மக்கள் சட்டரைப் பிழைக்கப்பேசுவார் ஒரு காசு தண்டப்படுவது.”

இதிலிருந்து பார்த்திவசேகரபுரத்தில் நிறுவிய சாலை— அதற்கு முன்மாதிரியாக அமைந்திருந்த கார்த்தனூர்ச்சாலையும் கூட—ஒரு வகையான பாடசாலை தான் என்பது தெரியவரும். மாணவர்கள் அவ்விடத்திலேயே தங்கி உணவு கொண்டு படித்து வந்திருக்கிறார்கள். அந்தச் சாலைக்கெனத் தனியாக வேண்டிய சொத்து இருந்திருக்கிறது. அதன் நிர்வாகம் முழுவதும் அந்தச் சாலைக்கென நிர்ணயிக்கப்பட்ட சட்டர்கள் வசம். இருந்தது. பிறர் யாருடைய தலையீடும் இல்லாமல் சுயேச்சை வாய்ந்த ஸ்தாபனமாக அது விளங்கியது. தற்காலத்துப் பல்கலைக் கழகங்களை அவற்றுக்கு ஓரளவு ஒப்பாகக் காட்டலாம்.

சட்டர் என்னும் சொல்லைச் சாத்ரர் என்னும் ஸம்ஸ்கிருதச் சொல்லிலிருந்து பெறப்பட்டதாகக் கொண்டு மாணவனைக் குறிப்பதாகவே கொள்ளுவர். (தமிழ் லெக்ஸிகனில் சட்டன் என்ற சொல்லைப் பார்க்க.) ஆயினும் நாம் மேலே காட்டிய சாசன வாசகத்தைக் கவனிக்கும்போது வெறும் மாணவனை மட்டுமே அந்தச் சொல் குறிப்பதாகத் தோற்றவில்லை. இந்தச் சாலையின் சட்டர் அவர் அவர்களுக்கு உரிய வேதத்தில் மட்டுமல்லாமல் மீமாம்சை, வியாகரணம், பௌரோஹித்தியம் ஆகிய பிரிவுகளிலும் பூர்ணமான பாண்டித்தியம் பெற்றிருக்கக் காண்கிறோம்; அன்றி, சாலாபோகத்துக்கு விடப் பெற்ற சொத்துக்களே யன்றி, அந்தச் சாலையோடு சேர்ந்ததாக இருந்த கோயிலுக்குச் சொந்தமான தேவதான நிலங்களும், கோயில் நிர்வாகமும் அவர்கள் வசமே இருந்திருக்கின்றன. ஆதலின், சட்டரை வெறும் மாணவர்களாகக் கொள்வதற்குப் பதிலாகப் பாடசாலையின் நிர்வாகத்தை வகித்துவந்த ஆசிரியர்களாகவே கொள்ள வேண்டும் என்று தோற்றும்.

தென்ஆர்க்ககாடு ஜில்லா எண்ணுயிரம் என்னுமிடத்திலிருந்து கிடைக்கும் முதலாம் இராஜேந்திர சோழனுடைய காலத்துக் கல்வெட்டு ஒன்று இதே போன்ற பொருளைக் கொடுப்பதாகக் காண்கிறது. (1917-ஆம் ஆண்டு 333-நெ.) சாசனம் அரசனே திட்டம் வகுத்து அளித்த உத்தரவை ஒட்டி இராஜராஜச் சதுர்வேதிமங்கலத்துச் சபையார் அந்த

இடத்தில் இருந்த பெரிய கலாசாலையில் பயிலும் மாணவர்களுக்கும் பாடம் சொல்லும் உபாத்தியாயர்களுக்கும் உணவு அளிக்கச் செய்த ஏற்பாடுகளைத் தெரிவிக்கிறது. அந்தக் கலாசாலை இருநூற்று எழுபது பிரம்மசாரிகளையும், எழுபது சாத்திரர்களையும், பதினான்கு ஆசிரியர்களையும் கொண்டிருந்தது. ஒவ்வொரு பிரம்மசாரிக்கும் நாள் ஒன்றுக்கு ஆறு நாழி வீதம் நெல் அளிக்கப்பட்டது. ஆனால் சாத்திரருக்கோ நாள் ஒன்றுக்குப் பத்து நாழி வீதம் நெல் நிர்ணயிக்கப்பட்டது. (பார்த்திவசேகரபுரம் சாசனத்திலும் ஒவ்வொரு சட்டருக்கும் நாள்தோறும் பத்து நாழி வீதம் கணக்கிடப்பட்டிருப்பது கவனிக்கத் தக்கது; 'பதினாழிச் சாலை' என்றே குறிக்கவும் படுகிறது.) பாடம் சொல்லும் ஆசிரியர்களிலே வேதாந்தபாடம் சொல்பவருக்கே நாள் ஒன்றுக்கு ஒரு கலம் முக்குருணி நெல் அளிக்கப்பட்டது. அந்தத் திட்டத்திலே மிகவும் அதிகப்படியாகத் தானியமாகக் கொடுக்கப்படுவது அவருக்குத்தான். மீமாம்ஸை, வியாகரணம் ஆகியவற்றைப் பாடம் சொல்லும் நம்பிகளில் ஒவ்வொருவரும் நாள் ஒன்றுக்கு ஒரு கலம் வீதம் பெற்றுவந்தனர். மற்றவர்களுக்கு நாள்தோறும் முக்குருணி நெல் வீதம் கணக்கிடப்பட்டது. இவ்விதம் நாள்தோறும் அளிக்கப்பெறும் தானியத்தைத் தவிர, பாடம் சொல்லுவதற்குப் பிரதிப் பிரயோஜனமாக ஆசிரியர்களுக்கும் சாத்திரர்களுக்கும் பொன்னும் தனியாக அளிக்கப்பட்டு வந்தது. வேதாந்த பாடம் சொல்லும் ஆசிரியருக்கு மட்டும் அவ்விதம் பொன் அளிக்கப்படவில்லை. (பணம் வாங்கிக்கொண்டு வேதாந்த பாடம் சொல்லக் கூடாது என்பது மரபு. அதனாலே போலும் அவருக்குப் பொன் அளிக்கப்படவில்லை. மற்றவர்களைக் காட்டிலும் அவருக்கு அதிகமாக நெல் கொடுக்க ஏற்பாடு செய்யப்பட்டிருந்ததற்கும் அதுவே காரணமாகும்போலும்.) வியாகரணம், மீமாம்ஸை ஆகிய இரண்டிலும் பாடம் சொல்லும் ஒவ்வொரு அத்தியாயத்துக்கும் ஒரு கழஞ்சு வீதம் பொன் அளிக்கப்பட்டு வந்தது. அதனால், அந்த அந்தச் சாஸ்திரங்களை ஒருதரம் முழுவதும் பாடம் சொன்னால் வியாகரண ஆசிரியர் எட்டுக் கழஞ்சும் மீமாம்ஸை ஆசிரியர் பன்னிரு கழஞ்சும் பெறுவர். மற்றவர்களுக்குத் தலைக்கு ஆண்டுதோறும் அரைக் கழஞ்சு

பொன் என்ற திட்டம். (சாசன இலாக்காவின் 1918-ஆம் ஆண்டு அறிக்கை, பாரா 23). இதனால் சாத்திரரும் பாடசாலையில் பாடம் சொல்லி அதற்கான பொன்னைப் பெற்றுவந்தனர் என்பது விளங்கும்.

சற்றேறக்குறையப் பார்த்திவசேகரபுரம் சாசனத்தின் காலத்தையே சார்ந்த மற்றொரு சாசனமும் இதனையே வலியுறுத்துவதாகக் காண்கிறது. வட ஆர்க்காடு ஜில்லாவில் உள்ள காவேரிப்பாக்கம் என்னுமிடத்திலிருந்து கிடைக்கும் அக் கல்வெட்டு பல்லவ அரசனான நிருபதுங்கவர்மனுடைய ஆட்சியின் இருபத்தைந்தாம் ஆண்டு (சுமார் கி. பி. 886) கொண்டது. அவ்வூர்க் கோயிலிலே விளக்கு எரிக்க எண்ணெய் அட்டுவதற்குப் பொன் அளித்து அந்தத் தர்மத்தை மடத்துச் சட்டப் பேருமக்கள் பொறுப்பிலே விட்ட செய்தியைக் கூறுகிறது அந்தக்கல்வெட்டு. (தே.இ. சாசனங்கள், பன்னிரண்டாம் வால்யூம், 79 நெ.) இதிலிருந்து சட்டர்களுடைய நிலை ஒரு வகையில் தெரியவரும். அவர்கள் சாதாரணமான மாணவர்களாக மட்டும் இருத்தற்கில்லை. அவர்கள் மடத்தில் வசித்து வந்தார்கள். பார்த்திவசேகரபுரம் சாசனமும் இவ்விதமே தான் எடுத்துக் கூறுகிறது. வடமொழி நிகண்டான அமர கோசத்திலும், 'மடஸ் சாத்ராதி நிலய:' அதாவது 'மடம் என்பது சாத்திரர் போன்றோர் இருக்குமிடம்' என்று காணப்படுகிறது. ஆகவே, சட்டர் என்பாரை ஆசிரியராகவே கொள்ளவேண்டும் போலும்.

இவற்றைக் கவனிக்கும்போது சட்டர் என்பார் உலக பந்தம் வேறு ஏதும் இல்லாமல் வித்தை ஒன்றையே பிரதானமாகக்கொண்டு அதைக் கற்பதிலும் பிறருக்குக் கற்பிப்பதிலும் ஆயுட்காலத்தைச் செலவிடும் நைஷ்டிகப் பிரம்ம சாரியாவார் என்று கருதலாம். மகாகவி காளிதாசன் தன்னுடைய நாடகமான சாகுந்தலத்தில் சித்திரித்திருக்கும் கண்வ மகரிஷியின் குண சித்திரம் சட்டருடைய நிலையை எடுத்துக் காட்டுவதாகக் கொள்ளலாம். கண்வர் ஒரு குலபதி. அவருடைய ஆசிரமத்திலே மாணவர்கள் அநேகர் தங்கி அவரிடம் கல்விகற்று வந்தனர். அங்கேதான் துஷ்யந்தன் சகுந்தலையைக் கண்டது. அவள் யார் என்று அவன் விசாரித்த

போது அவளுடைய தோழி அவளைக் கண்வ மகரிஷியின் மகள் என்று கூறி அரசனுக்குப் பதில் உரைத்தாள். இந்தப் பதில் மன்னனை வியப்புக்குள்ளாக்கியது. ஆயுள்முடியப் பிரம்மசரிய விரதத்தை மேற் கொண்டிருந்த கண்வ முனிவருக்கு அவள் எவ்விதம் மகளாக இருக்க முடியும் என்றே அரசன் ஆச்சரியத் துடன் வினவுகிறான்.

அந்நாளிலே தமிழ் நாட்டில் இவ்விதம் பல துறைகளிலும் உயர்தரக் கல்வி பயிலுவதற்கென ஆசிரியர்களும் மாணவர்களும் ஒரே கட்டிடத்தில் தங்கி வாசித்துவந்த பெரிய கலாசாலைகளைத் தவிர, சிறுபாடசாலைகளும் அங்கங்கே ஏராளமாக இருந்து வந்தன. தனிப்பட்ட ஆசிரியர்களிடம் குருகுல வாசம் செய்து தங்கள் தகுதிக்கு ஏற்ப விரும்பிய துறைகளில் பயின்றுவந்த மாணவர்கள் மிகுதியாக இருந்தனர். அத்தகையவர்களுக்கு உணவு அளிப்பதற்கான இறையிலி நிலங்களும் அங்கங்கே ஏராளமாக இருந்துவந்திருக்கின்றன. கல்வெட்டுக்களை ஊன்றிக் கவனித்தால், அவற்றுள் சாலை, சாலா போகம் என்று வரும் இடங்களிலே அந்தச் சொற்கள் முறையே சாதாரண அன்னசத்திரங்களையும் அவற்றுக்கு விடப்பெற்ற நிலங்களையும் குறிப்பனவாகக் காணமாட்டா; மாணவர்கள் கல்விபயிலுவதற்கு ஏற்பட்ட பாடசாலைகளைச் சேர்ந்தனவாகவே இருக்கும்.

பார்த்திவசேகரபுரம் சாசனத்திலிருந்து பல அரிய விவரங்கள் நமக்குத் தெரியவருகின்றன. (உண்மையில் அந்தச் சாசனம் நல்லமுறையில் விளக்கத்தோடு மறுபடியும் பதிப்பிக்கப்பெறுதல் அவசியம்.) ஆயினும் நாம் இவ்விடத்திலே இரு விஷயங்களை முக்கியமாகக் கருதவேண்டும்: (1) சட்டர்கள் திரைராஜ்ய விவஹாரத்துக்கு, அதாவது (தமிழக வழக்குப்படி முடியுடை வேந்தர் மூவரான சேர சோழ பாண்டியர் ஆகிய மன்னர்களின்) மூன்று ராஜ்யங்களது விவகாரங்களை நிர்வகிப்பதற்கு வேண்டிய பயிற்சியும் அறிவும் (ஓத்து) உடையவராக இருத்தல் வேண்டும். (2) குறிப்பிட்ட கட்டுப்பாடுகள் சிலவற்றுக்கு உட்பட்டு அவர்கள் படைக்கலம் தாங்குவதற்கும் கையாளுவதற்கும் அனுமதிக்கப்பட்டிருந்தனர். வேதங்களையும் அவற்றின் அங்கங்களான வியாக்கரணம்,

பௌரோஹித்யம் முதலிய சாத்திரங்களையும் நன்கு கற்றுத் தேர்ச்சிபெற்ற அந்தணன், ராஜ்ய நிர்வாக விஷயங்களை அறிந்திருந்ததோடு தர்ப்பைப் புல் ஏந்தவேண்டிய கரத்தில் படைக்கலம் பிடிக்கவேண்டி யிருந்ததையும் நாம் கவனிக்க வேண்டும். இவற்றிலிருந்து, நாட்டின் நிர்வாகம், போர் முறை ஆகிய இரண்டையும் புத்தக வாயிலாக மட்டுமல்லாமல் நடை முறை வழியாகவும் கற்பித்து வந்த ஒரு கலாசாலையாகவே அது இருத்தல் வேண்டும் என்பதை எளிதில் உணரலாம். இப் போது உள்ளதைப்போல அந்நாளிலே நாட்டின் அரசிய லமைப்பில் அன்றாட நிர்வாகப் பகுதி (ஹிஸில் இலாகாக் கள்), ராணுவப் பகுதி ஆகிய இரண்டும் தனித் தனியாகத் தலைவர்களைக்கொண்டு தனிப் பிரிவுகளாக இருக்கவில்லை; இந்த இருவகைப் பொறுப்புக்களையும் ஒரே நிர்வாகியே ஏற்று வந்திருக்கிறார். அதுமட்டுமல்ல; ராணுவ விஷயமான அறிவும் அனுபவமும் பெருத நிர்வாக அதிகாரி எவருமே அந்தக் காலத்தில் இல்லையென்று சொல்லலாம். அதனால் பார்த்திவ சேகரபுரம் சாலையும், அதேபோலக் காந்தனூரிலே இருந்த சாலையும், நாட்டு நிர்வாகத்தின் பல துறைகளிலும் புத்தகப் படிப்புடன் நடைமுறைவழியிலும் பாடம் போதித்து வந்தன வென்பது போதரும். இப்போது நடைபெற்றுவரும் அதி காரிகள் கல்லூரி, நிர்வாகப் பயிற்சி நிலயம் என்பன போன்ற வற்றை ஒப்ப அந்தச் சாலைகளைக் கொள்ளலாம். ஆனால் அந்தச் சாலைகள் எந்த அரசாங்கத்தின் கட்டுப்பாட்டுக்கு உட் பட்டோ உதவியை எதிர்பார்த்தோ நடந்தனவாகத் தோன்ற வில்லை; வேண்டிய அளவுக்குச் செல்வநிலையையும் பூமிகளையும் பெற்றுப் பிறருடைய தலையீடு ஏதுமின்றிச் சுயேச்சையாக நடந்துவந்தனவென்றே தெரிகிறது.

காஞ்சீபுரத்திலே கடிகை ஒன்று இருந்தது. அதைப் பற்றிய குறிப்புகள் கி.பி. ஒன்பதாம் நூற்றாண்டின் மத்தி வரையில் கிடைக்கின்றன. அங்கேயும் இதேபோலப் படைக் கலங்கள் உள்படப் பலதுறைகளிலும் பயிற்சி அளிக்கப்பட்டு வந்ததென்று தெரிகிறது. கதம்ப ராஜவமிசத்தை ஸ்தா பித்த மபூரசர்மன் பிரவசனம் முழுவதையும் பயில்வதற் காகத் தார்க்குகனாகத் தன் ஆசிரியன் வீரசர்மனோடு அந்தக் கடிகையை அடைந்து அதில் சேர்ந்தான், பல்லவர்களுடைய

‘குதிரை வீரன்’ ஒருவனோடு விரோதித்துக் கொண்டதால் நிகழ்ந்த கலகத்திலே, அவன் தர்ப்பைப் புல்லையும் இதர வேள்விப் பொருள்களையும் ஏந்திய கையிலே வாள்போன்ற படைக் கலங்களை ஏந்திப் போரிட்டுத் தனக்கெனத் தனி ராஜ்யம் ஒன்றையும் அமைத்துக் கொண்டான். இதிலிருந்து கடிகையும் அதேபோல உயர்தரப் படிப்பும் போர்ப் பயிற்சியும் அளித்து வந்ததென்பது நன்கு விளங்கும். (எபிகிராபியா கர்நாடிகா, ஏழாம் வால்பூம், ஷிகார்பூர் 176 நெ. சாசனம்; எபிகிராபியா இந்திகா, எட்டாம் வால்பூம், நெ. 5.)

நாம் மேலே எடுத்துக் காட்டிய விதமே பொருள் கொள்ள வேண்டும் என்பதை வலியுறுத்தும் வேறு ஆதாரங்களும் உண்டு. அனந்தபுரம் என்னும் திருவனந்தபுரத்தின் பழம் பெருமையையும் புனிதத் தன்மையையும் விவரித்துக் கூறுவதாக அனந்தபுர வர்ணனம் என்னும் மலையாள நூல் ஒன்று உண்டு. கி. பி. பதினான்காம் நூற்றாண்டில் எழுதப்பட்டதாகக் கருதப்படும் அந்நூலிலே அனந்தபுரத்தின் ஒரு பகுதியான காந்தனூரில் வேதங்களில் பாண்டித்தியம் பெற்றவர்களுடைய பாடசாலை இருந்துவந்த தென்பதும் அந்தப் பாடசாலையில் இருந்தவர்கள் படைக்கலப் பயிற்சியிலே திறமைவாய்ந்தவர்கள் என்பதும் குறிக்கப் பட்டுள்ளன.<sup>1</sup> (திருவாங்கூர்ப் பல்கலைக் கழகம் பாஷா பிரசுரம், 81 நெ. 106 பாடல் முதல்).

கேரளத்திலே இன்றைக்கும் சாத்திரக்களி என்ற பெயருடன் ஓர் ஆட்டம் நடைபெற்று வருகிறது. அதிலே நடிகர்கள் கத்திகேடயம் கொண்டு தங்கள் வாள்வீச்சுத் திறமையைக் காட்டுவது பிரதான அம்சம். குறிப்பிட்ட சில நம்பூத்திரிக் குடும்பத்தவர்களே அதில் ஈடுபடுவார்களாம். நிகழ்ச்சியின் ஆரம்பப் பகுதியிலே அந்தக் களியை நடத்திக் காட்டுவோர் நாலுபாதம் என்ற பெயருடன் சில பாடல்களை ஸாமவேதம் ஒதும் முறையிலே பாடுவார்களாம். பார்த்திவசேகரபுரம் சாசனத்திலும் சட்டர்கள் வாரம் ஒதும் பரிசைக் கூறுமிடத்

1. சென்னைப் பல்கலைக் கழகத்து மலையாளத் துறையில் உள்ள பூதி கே. என். எழுத்தச்சன் அவர்கள் இதை எனக்கு அறிவித்தார்கள்.

தில் நாலுபாதம், ஸாமவேதத்தின் அஹத்தாஹம் ஆகிய பெயர்கள் காணப்படுகின்றன<sup>2</sup>

இதுகாறும் நாம் கூறியவாற்றால், காந்தனூரில் இருந்த சாலையை ஒருவகைப் பாடசாலை யென்றும், முன்னதாகவே சில குறிப்பிட்ட துறைகளில் பாண்டித்தியம் பெற்றிருந்தவர்களே அதிலே இடம் பெற்றனர் என்றும், அங்கே பல்வேறு விஷயங்களோடு அரசியல் நிர்வாகம், போர் முறை ஆகியவை போதிக்கப் பெற்று வந்தன வென்றும் கொள்வது தவறுகாது. அரசியல் நிர்வாகம், போர் முறை ஆகியவற்றைப் போதித்து வந்த கலாசாலையாகவே அதைக் கொள்ளலாம். சாசனங்களிலே திரை ராஜ்ய கடிக மத்தியஸ்தர் என்பது போன்ற பெயரையுடையவர்களைப் பற்றிய குறிப்புகள் காணப்படுவது (சாசன இலாகாவின் 1916-ஆம் ஆண்டு அறிக்கை, பாரா 8) இத்தகைய கலாசாலைகள் இருந்துவந்தன வென்பதை நன்கு எடுத்துக் காட்டும்.

அப்படியானால் காந்தனூரில் சோழ மன்னன் கொண்ட வெற்றி எத்தன்மையது என்பதை யறியவேண்டும். இந்தச் சந்தர்ப்பத்தில், ஏறக்குறைய இதே காலத்தைச் சேர்ந்த ஒரு கல்வெட்டில் வேறு ஒரு சந்தர்ப்பத்தில் கலமறுத்த என்னும் சொல் ஆளப்பட்டிருப்பதையும் கவனிக்கவேண்டும். தஞ்சாவூர் ஜில்லாவில் கோயில் தேவராயன்பேட்டை என்னுமிடத்திலிருந்து கிடைக்கும் அந்தச் சாசனம் இராஜகேசரிவர்மன் என்பானுடைய ஆட்சியின் பதினான்காம் ஆண்டுகொண்டது. (தே. இ. சாசனங்கள், பதின்மூன்றாம் வால்யூம், நெ. 250.) ஒவ்வொரு வருஷமும் மார்கழி மாதம் திருவாதிரை நாள் இரவு திருச்சேலூர் மகாதேவர் முன்பு 'ஜைமினிகள் சாமவேதத்து மேற்பாதத்து ஒரு துருவும் கீழ்ப்பாதத்து ஒரு துருவும் கரைப்

---

2. சென்னைப் பல்கலைக் கழகத்து மலையாளத் துறைத் தலைவர் டாக்டர் எஸ். கே. நாயர் அவர்கள் இதை எனக்கு அறிவித்தார்கள். கேரளத்தின் கிராமிய நாடகங்கள் என்ற பெயரில் அவர் எழுதியுள்ள நூலின் பிரதியையும் நான் படித்துப் பார்க்கக் கெட்டுத்தார்கள். அது இன்றும் வெளியாகவில்லை. அதிலே இந்த ஆட்டம் நன்கு விவரிக்கப்பட்டுள்ளது.



பறிச்சு பட்டம் கடத்துப் பிழையாமே சொன்னார்க்குப் பரிசு அளிக்க ஒருவன் இருபது காசு பொன் அளித்த செய்தியைத் தெரிவிக்கிறது அந்தக் கல்வெட்டு. அவன் வைத்த அந்த இருபது காசு முதலுக்கு ஆண்டுதோறும் கிடைக்கும் பலிசை மூன்று காலையும் 'ஒருகாற் கொண்டார் அல்லாதாரை மெய்க் காட்டுத் தீட்டினார் எல்லாரும் தம்மில் அஞ்சுபுரியிலுஞ் சொல்லிக் கலமறுத்து நல்லாரானார் ஒருவர்க்கு' எம்பெருமானே அருளவேண்டும் என்பது ஏற்பாடு. இதனால் முன் ஆண்டுகளில் பரிசு பெற்றவர் பின் ஆண்டுகளில் போட்டியிட முடியாது என்பது தெளிவு. போட்டியில் வெற்றி பெற்றவர் 'கலமறுத்து நல்லார் ஆனார் ஒருவர்' என்று சாசனத்திலே குறிக்கப் பெற்றிருக்கிறார். இவ்விடத்திலே கலமறுத்து என்ற சொல்லுக்குச் 'சாசனத்தால் அல்லது ஒலையால் நிர்ணயிக்கப் பெற்ற' என்ற பொருளே கொள்ளவேண்டும்.

இதைக் கொண்டு, இராஜராஜ சோழனும் காந்தனூரில் இருந்த பாடசாலையிலே நடந்த சாஸ்திரப் போட்டியிலே ஈடுபட்டுத் தன் திறமையை வெளிப்படுத்தி வெற்றிகொண்டு பரிசையும் அடைந்தான் என்று பொருள் கொள்ளத் தோன்றுவது சகலமே. இது நடக்க முடியாததும் அல்ல; கூடாததும் அல்ல. சோழர்கள் தங்களைச் சூரிய வமிசத்தைச் சேர்ந்த க்ஷத்திரியர்கள் என்று கூறிவந்திருக்கிறார்கள். இராஜராஜனுடைய பெயரான முதலாம் இராஜாதிராஜன் அசுவமேத யாகமும் செய்திருக்கிறான். அதனால் அவர்கள் வேதாத்தியயனம் செய்ய உரிமை பூண்டவர்களே. ஆயினும், கல்வெட்டுக்களிலே காந்தனூரில் சோழர்கள் படை வலிமை கொண்டே வெற்றி யடைந்தனர் என்று காணப்படுவதை நாம் முன்னரே எடுத்துக் காட்டியிருக்கிறோம். அதனால் அவ்விதம் பொருள்கொள்வது தவறாகும்.

அவ்விதமாயின் சோழமன்னன் படைவலிமைகொண்டு காந்தனூரிலே இருந்த சாலையில்கொண்ட வெற்றி எத்தன்மையது என்பதை அறியவேண்டுவது அவசியமாகிறது. சாலையின் தன்மையே அந்த வெற்றி எவ்விதம் இருந்திருக்க வேண்டுமென்பதை எடுத்துக் காட்டுவதாகக் கொள்ளலாம்.

இராஜராஜன் தன் ஆட்சியின் துவக்கத்திலேயே சோழ நாட்டின் எல்லையை விஸ்தரித்துப் பரந்த ஒரு ஸாம்ராஜ்யத்தை நிறுவவேண்டும் என்று திட்டமிட்டு அதற்கான செயல்களை நடைமுறைப்படுத்தவும் முற்பட்டான் என்று தெரிகிறது. ஆரம்பம் முதலே மன்னனுக்கும் காந்தளூர்ச்சாலை நிர்வாகிகளுக்கும் கருத்து வேற்றுமை ஏற்பட்டிருத்தல் கூடும். அந்தச் சாலை தன்னுடைய ஆதிக்கியத்தில் இருந்து, தன்னுடைய கட்டுத்திட்டங்களை நிறைவேற்றிவைக்கக் கூடியதாக இருந்தால்தான் தன் கனவு நனவாகும் என்று அவன் எண்ணியிருத்தல் சாத்தியமே. பிறருடைய தயவை எதிர்பார்க்காமல் சுயேச்சையாக விளங்கக்கூடிய செல்வநிலை யிருந்தபடியால் அது சுலபத்தில் அரசனுக்கு அடங்கிப்போயிருக்காது. அதற்கு மாறாகத் தன்னுடைய சொந்த நிர்வாகத்தில் பிறர் தலையிட முடியாதபடி அது மிகத் தீவிரமாக எதிர்த்தே வந்திருக்கும். அதனாலேயே மன்னன் அதன் நிர்வாகத்தைத் தன் ஆதிக்கியத்தில் கொண்டுவதற்குப் படைவலியை உபயோகிக்கவேண்டி வந்தது போலும்.

காஞ்சீபுரத்திலிருந்த கடிகையின் நிர்வாகத்திலும் பல்லவ மன்னர்கள் இதேபோல் சில சமயங்களில் தலையிட்டுத் தங்கள் இஷ்டப்படிக் காரியங்களைச் சாதித்துக்கொண்டிருக்கிறார்கள் என்று தெரிகிறது. காஞ்சீபுரத்துப் பல்லவ அரச பரம்பரையை நிறுவிய முதல் அரசனான வீரகூர்ச்சனுடைய பெயரான ஸ்கந்தசிஷ்யன் என்பான் ஸத்யஸேனனிடமிருந்து கடிகையைக் கைப்பற்றினான் என்று வேலூர்ப் பாளைம் செப்பேடுகளில் கூறப்பட்டிருக்கிறது. 'ஸ்கந்த சிஷ்யஸ் ததோ பவத் த்விஜாநாம் கடிகாம் ராஜ்ஞீ ஸத்யஸேநீ ஜஹார யீ' (தே. இ. சாசனங்கள், இரண்டாம் வால்யூம், பக்கம் 508, வரிகள் 11-13.) என்று வரும் அந்தப்பகுதியில் ஜஹார என்னும் வினைச்சொல்லைக் கொண்டு பல்லவ மன்னன் கடிகையைப் படை வலி கொண்டே கைப்பற்றினான் எனக் கொள்ளலாம். அதே சாசனத்தில் மேலும் ராஜஸிம்ஹன் என்பான் 'இரு பிறப்பாளரின் கடிகையைச் சீர்திருத்திப் புனர் நிர்மாணம் செய்தான்' (தத்புத்ர ஸூத்ர நரஸிம்மவர்ம்மா புனர்வ்யாதாத்யோ கடிகாம் த்விஜாநாம்) என்று கூறப்பட்டிருக்கிறது. (மே. வரிகள்

19. 20). தாளகுண்டாக் கல்வெட்டிலிருந்து மயூரசர்மன் தனக்கு நேரிட்ட கஷ்டத்துக்குப் பல்லவ மன்னனையே பொறுப்பாக்கி அவன்மீதே கோபப்பட்டான் என்று தெரிகிறது. அதைக்கொண்டு கவனிக்கும்போதும் காஞ்சிபுரத்துக் கடிகையின் நிர்வாகத்தில் பல்லவமன்னனுக்கும் ஏதோ ஒரு விதமான ஆதிக்கியம் இருந்துவந்த தென்பது பெறப்படும்.

தவிர, கடிகையாருக்கும் நாட்டின் நிர்வாகத்தோடு ஏதோ ஒருவகையில் தொடர்பு இருந்துவந்ததாகவும் தெரிகிறது. காஞ்சிபுரம் வைகுண்டப் பெருமாள் கோயிலில் உள்ள கல்வெட்டிலிருந்து இது தெரிய வருகிறது. இரண்டாம் பரமேசுவரவர்மன் இறந்துபோன பிறகு பல்லவ சிங்காதனம் ஏறுவதற்குத் தகுதியான இராஜகுமாரன் யாரும் இல்லாததால் இளைய பரம்பரையைச் சேர்ந்த ஹிரண்யவர்மனை அணுகி அவன் மகனான நந்திவர்மன் பல்லவ மன்னனை முடிசூட்டிக்கொள்ள அனுமதிக்க வேண்டுமென்று வேண்டிக்கொள்ளச் சென்ற கோஷ்டியில் கடிகையாரும் சேர்ந்திருந்தனர் என்று அந்தக் கல்வெட்டுக் கூறுகிறது. (தே. இ. சாசனங்கள், நாலாம் வால்யூம், பக்கம் 10. இன்னும் டாக்டர் ஸி. மீனாட்சி எழுதிய வைகுண்டப்பெருமாள் கோயிலின் சரித்திர சிற்பங்கள், பக்கம். 33 பார்க்க).

இது சம்பந்தமாக மற்றொரு விஷயத்தையும் நாம் நினைவில் கொள்ளவேண்டும். வேண்டுமே ஆய்குல மன்னன் கருநந்தடக்கன் பார்த்திவசேகரபுரத்தில் சாலை நிறுவியது கி. பி. 868-ஆம் ஆண்டு என்று அந்தச் செப்பேடு கூறுகிறது. அந்தச் செய்தியையும் அந்தச் சாலையின் நிர்வாகத் திட்டங்களையும் தெரிவிப்பனவாக உள்ள செப்பேடுகள் பொறிக்கப்பட்டுள்ள எழுத்துக்கள் கி. பி. 868-க்குப் பிற்பட்ட காலத்தைச் சார்ந்தனவாக உள்ளன. எழுத்துக்களின் வடிவம் சோழ மன்னனான முதலாம் இராஜராஜ சோழன் காலத்து வடிவத்தை ஒத்திருக்கிறது. அன்றி, அந்தச் சாசனம் தமிழ் எழுத்துக்களிலே பொறிக்கப்பட்டிருக்கிறது. அவ்வகை எழுத்துக்கள் அந்தப் பகுதியில் சோழர்களுடைய ஆதிக்கியம் ஏற்பட்டபிறகே வழக்கில் வந்தன. அதற்கு முன்பு வட்டெழுத்து வடிவமே வழக்கில் இருந்தது. அதனால் ஆய்குல வேந்தனை

கருந்தடக்கன் காலத்திலே பொறிக்கப்பட்ட சாசனமாக இருக்குமானால் அது வட்டெழுத்திலே பொறிக்கப்பட்டிருக்க வேண்டும். இன்னும் சாசனத்தின் ஆரம்பத்தில் சாலையை நிறுவிய மன்னன் சபையாரிடமிருந்து நிலங்களைப் பரிவர்த்தனை பெற்று ஊரை நிர்மாணித்து, கோயிலை எழுப்பிச் சாலையை அமைத்துச் சாலையும் கோயிலும் சரிவர நடப்பதற்கு ஏற்ற திட்டங்கள் வகுத்ததைக் கூறுமிடத்தில் தான புருஷனாகிய அரசன் பெயர், மற்றச் சாசனங்களில் காணப்படுவதுபோல், 'செய்தானேன் கோக் கருந்தடக்கன்' என்று தன்மையில் காணப்படவில்லை; 'செய்தான் கோக் கருந்தடக்கன்' என்று பாடர்க்கையில் காணப்படுகிறது. சாசன வாசகமும் ஏதோ பழைய சம்பவத்தை எடுத்துக் கூறுவது போலவே தோன்றுகிறது.

சாலையை நிறுவிய வேண்டுமேனென்ற வேந்தனுக்கு ஸ்ரீவல்லபன் என்ற பெயரும் இருந்ததாகத் தெரிகிறது. அந்நாளில் அதே பெயரைக்கொண்டு ஆண்டுவந்த பாண்டிய மன்னன் கீழ்ச்சிற்றரசனாக அரசு செலுத்திய ஆய் மன்னன் தன் பேரரசன் பெயரையும் தரித்துவந்தான். ஆய் மன்னனுக்கு ஸ்ரீவல்லபன் என்ற பெயர் இருந்ததென்பது, அரசனுக்கும் விஷ்ணுவுக்கும் சிலேடையாக அமைந்து சாசனத்தின் கடைசியில் உள்ள மங்கள சுலோகத்திலிருந்து தெளிவாகும். அன்றி, அதே மன்னனுடைய திருப்பரப்புச் செப்பேட்டை எழுதியவன் பெயர் 'ஸ்ரீ கோக் கருந்தடக்கற்கு ஆயுதங்கள் செய்வான் விழிஞத்து ஸ்ரீவல்லபப் பெரும்பனைகனையின அவியலன் றடக்கன்' என்று காணப்படுவதிலிருந்து அரசனுக்கு ஸ்ரீவல்லபன் என்ற பெயர் இருந்தது தெரியவரும்.

கன்யாகுமரியிலிருந்து கிடைக்கும் சோழ மன்னனான முதலாம் இராஜாதிராஜனுடைய ஆட்சியின் முப்பதாம் ஆண்டு கொண்ட கல்வெட்டு ஒன்று, ஸ்ரீவல்லபப் பெருஞ் சாலையைப் பற்றிக் கூறுகிறது. பார்த்திவசேகரபுரத்தில் ஸ்ரீவல்லபன் ஏற்படுத்திய சாலையையே அது குறிக்கிறது போலும். பெருஞ் சாலை என்பது மஹாசாலை என்பதன் வேறு வடிவமேயாகும். வேத சாஸ்திரங்களில் ஓர் அளவு பரண்டித்தியம் பெற்றவர்களுக்கு மேலும் பாடம் சொல்லும்

பாடசாலையே மஹாசாலையாகும். (இந்திய இலக்கியத்தில் சீராவஸ்தி நகரம் என்னும் நூல் - இந்தியப் புதைபொருள் இலாகா மெமாயர் வெளியீடு - பக்கங்கள் 14-15.) அந்தக் கல்வெட்டிலேயே அச்சாலை 'ஸ்ரீவல்லபப் பெருஞ் சாலையான ராஜராஜப் பெருஞ்சாலை' என்று குறிக்கப்பட்டிருக்கிறது. முதலில் ஸ்ரீவல்லபன் பெயரைப் பெற்றிருந்த அந்தச் சாலை பின்னால் இராஜராஜன் பெயரைக் கொண்டும் வழங்கலாயிற்று. அதனால் இராஜராஜனுக்கும் அந்தச் சாலைக்கும் ஏதோ ஒரு வகையான தொடர்பு இருந்திருக்கவேண்டும். இவ்விடம் குறிக்கப்பட்ட இராஜராஜன் சோழ மன்னனே போலும். மன்னன் அந்தச் சாலையைத் தன் ஆதிக்கியத்தில் ஏற்றுச் சீர்திருத்திப் புதிய சாசனம் வழங்கினான் என்று கொள்ளலாம்.

பார்த்திவசேகரபுரத்திலிருந்த சாலையைப் போலவே, அதற்கு முன் மாதிரியாக நின்ற கார்த்தனூர்ச் சாலையையும் இராஜ ராஜ சோழன் தன்னுடைய ஆதிக்கியத்தின் கீழ்க் கொண்டு அதன் நிர்வாகிகள் வகித்திருந்த ராணுவச் செல்வாக்கைக் குறைத்துச் சாலையின் நடைமுறையிலே பெருத்த மாறுதல்களைச் செய்து புனர் நிர்மாணம் செய்திருத்தல் வேண்டும். இதுவே அவனுடைய மெய்க்கீர்த்தியில் 'கார்த்தனூர்ச் சாலைக் கலமறுத்தருளிய' என்று குறிக்கப்பட்டிருப்பது போலும். <sup>1</sup>

1. 'கலம்' என்ற சொல்லுக்கு எத்தனையோ பொருள்கள் உள்ளன வென்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். 'சாலை' என்ற சொல் துறைமுகத்துப் பெருவழி என்ற பொருளில் அந்நாளில் வழங்கிவரவில்லையாயினும், 'கலம்' என்ற சொல் கப்பல், அதாவது மரக்கலம் என்ற பொருளில் வழங்கிவந்திருக்கிறது. முதலாம் இராஜேந்திர சோழனுடைய மெய்க்கீர்த்தியிலே அவனுடைய கடாரப்படையெடுப்பின்போது அவன் கடலிலே படைகளை ஏற்றிச் சென்று கடலைக் கடக்கக் கப்பல்களை உபயோகித்தது அலேகடல் நடுவுள் பலகலம் செலுத்தி என்று குறிக்கப்பட்டுள்ளது. அவ்விடத்திலே 'கலம்' என்பது மரக்கலத்தையே குறிக்கும். சோழமன்னர்கள் திறமை வாய்ந்த கடற்படை ஒன்றை அமைத்திருந்தனர் என்பதும் அதைக்கொண்டு அவர்கள் கடல்கடந்த பிரதேசங்கள் பலவற்றைக் கைப்பற்றி ஆண்டுவந்திருக்கிறார்கள் என்பதும் பிரசித்தமானவை. தஞ்சாவூர் ஜில்லாவிலே திருத்துறைப்பூண்டித் தாலுகாவில் மரக்கலக்கோரையாறு என்ற பெயருடன் ஒரு கால்

திருக்கோவலூர்க்குப் பக்கத்தில் கீழூரில் உள்ள வீரட்  
டானேசுவரர் கோயிலிலிருந்து முதலாம் இராஜராஜ சோழ  
னுடைய ஆட்சியின் இருபத்தேழாம் ஆண்டு கொண்ட கல்  
வெட்டு ஒன்று கிடைத்திருக்கிறது. (தே. இ. சாசனங்கள், ஏழாம்  
வாஸ்பூம், 863 நெ.; சேந்தமிழ், நாலாம் தொகுதி, பக்கம் 231.)  
அதிலே அவன் நரபதி, அசுவபதி, கஜபதி ஆகிய விருதுகளைக்  
கொண்டிருக்கிறான். கஜபதி என்பது கலிங்கநாட்டு மன்னர்  
களுக்கே உரித்தான விருதாகும். பிற்காலத்திலே விஜயநகர

வாய் இருக்கிறது. கடற்கரையை ஒட்டி நிலப்பகுதியிலே அமைந்திருக்கும்  
கடல்நீர்த் தேக்கத்திலிருந்து உள்நாட்டிலே சுமார் பத்துமைல் தூரம் சென்று  
நின்றுவிடுகிறது அந்தக் கால்வாய். அதன் பெயரிலிருந்து அந்நாளிலே  
அக்கால்வாய் மரக்கலங்களை நிறுத்திவைப்பதற்காக உபயோகப்பட்டுவந்த  
துறைமுகப்பகுதி யென்பது தெரியவரும்.

தலோத்துங்கசோழன் பிள்ளைத்தமிழில் காண்பதைக்கொண்டு அந்  
நாளிலே காந்தளூரில் முத்துக்குளித்து வந்தார்கள் என்றும் எண்ணவேண்டி  
யிருக்கிறது.

“தண்டில் விழிஞத் தெயில் தகர்த்துடைய முத்துச்  
சலாபமுழுதும் பொறையன் சாலையொடு கொண்டாய்”

(பாடல் 91)

இதிலிருந்து மேலைக்கடற்கரையிலும் அந்நாளில் முத்துக்குளித்துவந்தார்கள்  
என்பது தெரியவரும். இந்தப் பழக்கம் கி. பி. பதினேழாம் நூற்றாண்டு  
வரையிலும் நீடித்திருப்பதாக, நம் நாட்டுக்கு வந்துபோன ஆங்கிலப் பிரயாணி  
யான ஜான் பிரையர் என்பார் எழுதிவைத்திருப்பதிலிருந்து தெரிகிறது.

“அவை (அதாவது முத்துக்கள்) நான் முன்னரே சொல்லியிருக்கிற  
பிரகாரம் குமரிமுனைக்கும் சிலோனு(இலங்கை)க்கும் இடையிலும் இருக்கின்  
றன. ஆனாலும் அவற்றைப் பாரசீக முத்துக்களுடன் ஒப்பிட முடியாது.  
பாரசீக முத்துக்களே உண்மையான கீழை நாட்டு முத்துக்கள். சுமத்திராத்  
தீவுகளிலும் அவை கிடைக்கின்றன. பொன்மயமான செரோநீஸை ஜாவா  
வில் உள்ளதாகவே கொள்ளுவர். வேறு சிலர் பழைய தாப்பிரோபேன் என்பர்.  
இவ்விதம் விசால ஜாவாவுக்கும் இந்தியாவுக்கும் இடையில் அதிகம் உள்ளன.  
பனுவலுக்கும் கொச்சிக்கும் இடையில் வேண்டிய அளவு உள்ளது. இன்னும்

மன்னர்கள் நரபதி என்ற விருதைத் தரித்து வந்திருப்பதை நாம் அறிவோம். அவர்களுக்கு முன், கல்யாணபுரத்திலிருந்து அரசு செலுத்திய மேலைச் சாளுக்கிய மன்னர்கள் அந்த விருதைத் தரித்து வந்திருக்கிறார்கள் என்று தெரிகிறது. (நாகாய் கல்வெட்டுகள் - ஹைதராபாத் ஆர்க்கியலாலிகல் ஸீரீஸ், நெ. 8 - பக்கம் 6.) மூன்றாவதான அசுவபதி என்னும் விருதைத் தேவகிரியிலிருந்து அரசு செலுத்திய சேவுணர்கள் தரித்து வந்தனர் என்பதை நாம் முன்னரே (முதற்பகுதி, பக்கம் lii) எடுத்துக்காட்டியிருக்கிறோம்.

இராஜராஜ சோழன் நரபதி, கஜபதி ஆகிய இரண்டு விருதுகளையும் தரித்துக் கொள்வதற்கு உரிமைபெற, அந்த விருதுகளை முன்னம் தங்கள் உரிமையாகப் பெற்றிருந்த மேலைச் சாளுக்கிய மன்னர்களையும் கலிங்க வேந்தர்களையும் வெற்றி கொண்டிருக்கிறான் என்பதை நாம் அறிவோம்.

மலையாளக் கரையோரமாக நெடுகிலும் கொஞ்சமாகக் கிடைக்கிறது.' (ஹக் லுயத் ஸொஸைட்டி வெளியிட்ட ஜான் பிரையரின் கிழக்கிந்திய, பாரசீக யாத்திரைகள். இரண்டாம் பாகம், இரண்டாம் ஸீரீஸ், இருபதாம் வால் யூம் - பக்கம் 355).

மேலைக் கடற்கரையோரமாகச் சேர மன்னர்கள் முத்துக்குளித்தலை இராஜராஜ சோழன் விரும்பவில்லைபோலும். பாண்டியர்களே கிழக்குக்கரையில்தான் அதை நடத்தவேண்டும் என்று தீர்மானித்திருக்கலாம். அல்லது மேலைக் கடற்கரையிலே முத்துக்குளிப்பதற்கு உபயோகப்பட்டு வந்த மரக்கலங்கள் மிகப் பெருகி அரபுக்கடல்வழியாக நடந்துவந்த வியாபாரத்தைப் பெரிதும் பாதித்திருத்தலும் கூடும். அந்நாளிலே அந்தப் பகுதியில் கடற்கொள்ளைக் காரர்கள் நிறைந்திருந்தனர் என்பதையும் நாம் அறிவோம். ஆயினும் சாலை என்ற சொல் காணப்படுவதிலிருந்து இத்தகைய நிலையாக இருக்குமென்று நாம் சொல்லமுடியாது. எவ்விதமாயினும், இராஜராஜசோழன் ஆட்சிக் காலத்திலே அவ்விதம் இருத்தற்கில்லை. ஒருகால் பிற்காலத்தில் அத்தகைய நிலை ஏற்பட்டிருத்தல் கூடும். ஏனெனில், அந்தச் சந்தர்ப்பங்களில் கலம் என்ற சொல் காணப்பெறவில்லை; அதனோடு காந்தளூர்ச்சாலை என்பதற்குப் பதிலாகச் சாலை என்றும்மட்டுமே காணப்படுகிறது. இதைக்கொண்டு காந்தளூர்ச் சாலையையே யல்லாமல் காந்தளூரையும் சாலை என்ற சொல் குறித்து வந்தது எனவும் கொள்ளலாம். அதனாலேதான் போலும் 'சாலைகொண்டது' என்று பொதுவாகக் குறிக்கப்பட்டிருக்கிறது.

அசுவப்தி என்ற விருதையும் அவன் தரித்துக் கொண்டிருப் தால் அவ்விதமே அந்த விருதுக்கு உரியவர்களான மாளவ அரசர்களை அவன் வென்றே அல்லது அவர்கள்மீது ஆதிக்கி யம் செலுத்தியோ இருத்தல் வேண்டும் என்று கொள்வது தவறுகாது. மாளவ தேசத்துப் பரமார மன்னர்களின் புகழை எடுத்துக்கூறும் உதயபூர்ப் பிரசஸ்தியில் போஜ ராஜனுடைய பெரியப்பனும் இரண்டாம் வாஃபதியுமான முஞ்சராஜன் சோழ மன்னனை வெற்றிகொண்டான் என்ற செய்தி கூறப்பட்டிருக்கிறது.

கர்ணாட லாட கேரள சோள சிரோ ரத்ந ராகி பத கமலஃ  
யஸ் ச ப்ரணயி கணூர்த்தித தாதா கல்பத்ரும ப்ரக்யஃ

“கர்நாடர், லாடர், கேரளர், சோழர் ஆகிய மன்னர்கள் சதா வணங்குவதால் அவர்களுடைய தலையில் உள்ள மணிகளால் அலங்கரிக்கப் பெற்ற பாதங்களையுடைய அவன் யாசித்து வந்தவர்களுக்கு அவர்கள் விரும்பிய பொருளை யளிப்பதால் கற்பக விருகூழ் என்னும் கீர்த்தியைப் பெற்றிருந்தான்”.

(எபிகிராபியா இந்திகா, முதல் வால்பூம், பக்கம் 237, சுலோகம் 14.)

வாஃபதி மன்னன் சுமார் கி.பி. 975-ஆம் ஆண்டில் சிங்காதனம் ஏறினான். அவன் மேலைச் சாளுக்கிய அரசனான தைலபனை ஆறு தடவைகள் தோற்கடித்தானாம். ஆனால், ஏழாம் முறையில் அவனைத் தைலபன் சிறைப்படுத்திச் சிரச் சேதம் செய்தானாம். சோழ வேந்தனை இராஜராஜனுக்கும் மேலைச் சாளுக்கியர்கள் பரம விரோதிகள். ஆகவே, அவர்களை இருபுறங்களிலும் தாக்கி முறியடிக்க இம் மன்னன் மாளவ தேசத்து அரசனுடன் நட்புக்கொண்டு ஒத்துழைத் திருப்பது சகஜமே. இராஜராஜசோழன் நர்மதைக் கரையிலே வெற்றி கொண்டான் என்று கோங்கு தேச ராஜாக்கள் சரித்திரம் கூறுவது இதனை இன்னும் வலியுறுத்தும்.

“அதின் பிறகு சோழ ராசா சேனாதிபதியானவன் தங்கள் துரை உத்தாரப்படிக்கு அங்கே அகப்பட்ட திரவியங் களை சிவாலயத்தோடே கூடியிருக்கிற கணவாய் ஸ்தலத்திலே நிக்ஷேபம் பண்ணி பச்சிம திக்கு செயஸ்தம்பம் நட்டு லோகத் திலே வெகு கீர்த்திவைத்தான்.



“அதின் பிறகு, பீமராயனென்கிறவன் இந்த சமா சாரங் கேட்டு சண்டைக்கு வந்தவனை யுத்தம் பண்ணி செயித்து அவன் மகனையுங் கொன்றுபோட்டு அதற்குமேல் கலிங்க தேசத்துக்கு யுத்தத்துக்குப்போய் அவனிடத்திலே கப்பம் வாங்கிக்கொண்டு அங்கேயிருந்து நிற்மதா (நர்மதா) தடத்துக்குப்போய் அந்த தேசங்களிலே அநேக ராசாக்களை செயம்பண்ணி, (நிற்மதா) நர்மதா தடத்திலே செயஸ்தம்பம் நட்டு தெக்ஷிண திக்குக்கும் மஹேந்திரகிரி பர்வதத்திலே வியாக்கிர அடையாளத்துடனே செயஸ்தம்பம் நட்டு அப் போது வைதும்பராயன், காமாற்றணவராயன், தானபால்லிய பீமராயன், அம்மராயன் முதலான இராசாக்களை செயித்து அநேகம் ஆபரணம் திரவியம் அந்தப்புர ஸ்திரீ முதலானதும் கப்பம் வாங்கிக்கொண்டு சுவற்றாத்துமமா யிருக்கிற பீமராய னுடைய பாவபிரதிமை வாங்கிக்கொண்டு சேனைகளுடனே கூட வந்து இராசாவைக் கண்டு.....”

(கோங்கு தேச ராசாக்கள்-சென்னை சர்க்கார் ஓரியண்டல் ஸீரீஸ்,

நெ. 6, பக்கங்கள் 12-13).

இவ்விடம் குறிக்கப்பட்ட பீமராயன் என்பான் தெலுங் குச் சோட. வேந்தனான ஜடா சோட பீமனாகவே இருத்தல் வேண்டும். அதேபோலக் காமாற்றணவன் என்பான் கலிங்க நாட்டை ஆண்டுவந்த கீழைக்கங்க குலத்து மன்னனாவான்.

இராஜராஜ சோழனுக்குப் பின் சிங்காதனம் ஏறிய அவன் மகன் முதலாம் இராஜேந்திர சோழனும் மேலைச் சாளுக்கியர்களோடு நிகழ்த்திய போரில் மாளவ தேசத்து அரசனான போஜராஜனோடு நட்புரிமை பாராட்டிக் கூட்டாகப் போரை நடத்தினான் என்று தெரிகிறது. அதைப் பின்னால் விளக்குவோம்.

### முதலாம் இராஜேந்திர சோழன்

இந்தத் தொகுப்பிலே இம்மன்னனுடைய சாசனங்கள் சுமார் இருபது உள்ளன. அவை அரசனுடைய ஆட்சியின் மூன்றாம் ஆண்டிலிருந்து முப்பத்தொன்றாம் ஆண்டு வரையில்

உள்ள காலத்தைச் சார்ந்தவை. அவனுடைய கல்வெட்டுகளில் சில 'திருமன்னி வளர' என்று தொடங்கும் மெய்க்கீர்த்தியுடன் ஆரம்பமாகின்றன. அத்தகைய மெய்க்கீர்த்திகள் இல்லாதவற்றுள் சில பூர்வ தேசமும் கங்கையும் கடாரமும் கொண்ட கோப் பரகேசரிவர்மன் என்று தொடங்கும். இவ்விதம் சிறு அடைமொழி கொண்ட சாசனங்கள் இந்தத் தொகுப்பில் ஒன்றும் இல்லை.

எனினும், மன்னனுடைய இந்த விருதிலிருந்து அவன் தண்டு எடுத்து வடநாடு சென்று கங்காவிஜயம் செய்து வெற்றி கொண்டது அவனுடைய ஆட்சியின் முக்கியமான சம்பவம் என்பது விளங்கும். இச்செய்தி முதல் முதல் அவனுடைய ஆட்சியின் பதினேராம் ஆண்டுக் கல்வெட்டிலேதான் குறிக் கப்படுகிறது. எனினும், அவ்வெற்றியின் முழு விவரம் பன்னிரண்டாம் ஆண்டுச் சாசனங்களில்தான் காணப்படுகிறது. இவ்வெற்றியைக் கூறும் கல்வெட்டுக்களைக் கவனிக்கும்போது இந்தப் படையெடுப்பு முடிய இரண்டு ஆண்டுகளாவது பிடித் திருக்கும் எனத் தோன்றுகிறது. இவ்விஜயத்தைப் பற்றித் திருவாலங்காட்டுச் செப்பேடுகள் பின்வருமாறு கூறுகின்றன :

“சோழ குல விளக்கான இம்மன்னன் இராஜேந்திரன், தன் தவ வலியால் கங்கையைப் பூமிக்குக் கொணர்ந்த பகீர தனைப் பரிகசிப்பதேபோலத் தன் தோள் வலியால் அந்நதியின் நீரை இவ்விடம் கொணர்ந்து நாட்டைப் புனிதமாக்க முற்பட்டான்.” (தே. இ. சாசனங்கள், மூன்றாம் வால்பூம், நெ. 205, சுலோகம் 109).

இந்தப் படையெடுப்பின் முடிவில் அவன் தன் தலைநகரிலே சோழ கங்கை என்ற பெயரில் 'ஜலமயமான ஜயஸ்தம்பம்' ஒன்றை நிறுவினான் என்றும் அதே சாசனம் கூறுகிறது. இன்னும் அவன் கங்கை கொண்ட சோழன் என்ற பட்டத்தைத் தரித்துக் கொண்டதோடு கங்கை கொண்ட சோழ புரம் என்ற ஒரு நகரையும் புதிதாக நிர்மாணித்தான். அதற்குப் பிறகு சுமார் இரு நூற்றாண்டுகளுக்கு அந்நகரம்தான் சோழ மன்னர்களுக்குத் தலைநகராக விளங்கியிருக்கிறது.

இராஜேந்திர சோழனுடைய இந்தப் படையெடுப்பு வெறும் தீர்த்த யாத்திரையாக மட்டும் அமையவில்லை ; பழைய காலத்து மன்னர்கள் நிகழ்த்திய திக்குவிஜயத்தைப்போலவும், வடநாட்டு மன்னர்களுக்குத் தமிழ் நாட்டு அரசின் வலிமையையும் சோழ ஸாம்ராஜ்யத்தின் பெருமையையும் எடுத்துக் காட்டுவதே போலவும் அமைந்தது என்று பொதுவாகக் கருதப்பட்டு வருகிறது.

ஆனால் இம்மன்னன் வெற்றி அவ்வளவோடு நின்று விடவில்லை. அதன் உண்மையான பெருமையையும் அதனால் ஏற்பட்ட சாதனைகளையும் நன்றாக அறியவேண்டுமானால் அந்தப் படையெடுப்பு நடத்தப்பெற்ற காலம், அதை மேற்கொண்ட முறை ஆகியவற்றையும், ராஜேந்திர சோழனுடைய மெய்க்கீர்த்தியிலே யன்றி அவனுக்குப் பின் சிங்காதானம் ஏறி நாட்டை ஆண்ட அவனுடைய குமாரர்களின் மெய்க்கீர்த்திகளிலும் வடநாட்டு வெற்றிகளைப் பற்றிக் காணப் பெறும் குறிப்புகளையும் நாம் கவனிக்க வேண்டுவது அவசியம்.

இதே சமயத்தில்தான் வடநாட்டில், அப்கானிஸ்தானத்து முஸ்லிம் மன்னனான மம்மூத் அடிக்கடி, ஏன் வருஷந்தோறும், படையெடுத்து வந்து சூரையாடிக் கொண்டிருந்தான். அவனுடைய பிரம்மாண்டமான படைகள், நூறுயிரம் குதிரைகள், ஏராளமான யானைகள், கணக்கற்ற காலாட்படைகள் கொண்டு காட்டாறுபோல ஹிந்துஸ்தானத்தின் மீது ஆண்டுதோறும் பாய்ந்துவந்தன. ‘காபிரிகளை வென்று’ இஸ்லாம் மதத்தைப் பரப்புவது அவனுடைய நோக்கம் அல்ல. நாட்டைக் கொள்ளைகொண்டு எவ்வளவு தூரம் முடியுமோ அவ்வளவு பொன்னையும் மணியையும் திரட்டி எடுத்துச் செல்வதிலேயே அவன் கண்ணை இருந்தான். வடநாட்டு மன்னர்களிலே அவன் படையெடுப்பினால் நேரடியாகப் பாதிக்கப்பட்டவர்களும், படையெடுத்து வரக்கூடும் என்று அஞ்சியவர்களும் ஒன்று சேர்ந்து அவனை எதிர்த்துப் போரில் முறியடித்து மீண்டும் அவன் படையெடுத்து வராமல் தடுத்து நிறுத்த முயன்றார்கள். ஆனால் அவர்களுடைய எதிர்ப்பு போதிய பலம் வாய்ந்ததாக இல்லை. அவர்களால் அவனைத் தடுத்து நிறுத்தமுடியவில்லை. அன்றி அவன் ஒவ்

வொரு வருஷமும் வெவ்வேறு பகுதியைக் குறிவைத்துப் படைகளை நடத்தி வந்தான். முக்கியமாக முன் படையெடுப்புகளில் அவனை எதிர்த்த வேற்று நாடுகளையே அவன் அவ்விதம் குறிவைத்தான் என்றும் சொல்லலாம்.

கன்னேசி என்றும் கன்யாகுப்ஜம் என்றும் வழங்கப் பெற்று வந்த பிரதேசத்தை அந் நாளிலே ராஜ்யபாலன் என்பான் ஆண்டு வந்தான். அவனும் பக்கத்து நாட்டு அரசர்களோடு சேர்ந்துகொண்டு முஸ்லிம் படையெடுப்பை எதிர்த்துப் போராடியிருந்தான் என்று தெரிகிறது. அதனால் கி. பி. 1018-ஆம் ஆண்டில் அவனுடைய நாட்டை மம்மூது தன் படையுடன் தாக்கினான். முஸ்லிம் சேனை கன்யாகுப்ஜ நகரத்தின் தலைவாசலுக்கு வந்தவுடனே ராஜ்யபாலன் பீதியடைந்தான். அவன் தலைநகரம் நல்ல அரண்வலி கொண்டதாக இருந்தாலும் அதைப் பொருட்படுத்தாமல் பயத்தால் செத்துத் தீவிரமாகப் போர்புரியாமல் நகரத்தைக் கைவிட்டுக் கங்கையைக் கடந்து பாரி என்னும் இடத்துக்கு ஓடிவிட்டான். அதன்மீது எதிர்ப்பு ஏதும் இல்லாதபடியால், முஸ்லிம் மன்னன் ராஜ்யம் முழுவதையும் ஒரே நாளில் கைக்கொண்டு நாட்டைச் சூரையாடுவதற்கும் தன் சேனைக்கு அனுமதி அளித்தான். கோயில்கள் இடித்துத் தரைமட்டமாக்கப்பட்டன. குடிமக்கள் பலர் கொன்று குவிக்கப்பெற்றனர். படையெடுப்பின் முடிவில் மம்மூது கஜ்னி(கஜ்ன)க்குத் திரும்பும்போது ஏராளமான பொன்னும் மணியும் கொள்ளைப் பொருள்களும் கொண்டு போனான்.

ராஜ்யபாலன் இவ்விதம் கோழைத்தனமாக நடந்து கொண்டது பக்கத்து நாட்டு மன்னர்களுக்குப் பெரிதும் ஆத்திரம் மூட்டியது. அதனால் படையெடுத்துவந்தவன் திரும்பிப் போனவுடன் அவர்கள் ஒன்று சேர்ந்து ராஜ்யபாலனைத் தண்டிக்க முற்பட்டனர். அந்தக் கோஷ்டிக்குத் தலைவனாக இருந்தவன் பெயர் முஸ்லிம் சரித்திரங்களில் எழுதியிருப்பதைக் கண்டன், நந்தன் அல்லது விதன் என்று பலவிதமாகப் படிக்க முடியும். அவன் காலஞ்சர நகரத்தைத் தலைநகராகக் கொண்டு ஆண்டுவந்த சந்தெல்லர் என்னும் சந்த்ராத்ரேய

வமிசத்து மன்னனான வித்தியாதரன் ஆவன் என ஆராய்ச்சி யாளர் நிர்ணயித்திருக்கிறார்கள். (டாக்டர் எச். ஸி. ராய் எழு திய வட இந்தியாவின் ராஜ வமிச சரித்திரம், இரண்டாம் வால்யூம், பக்கம் 688). அந்தக் கூட்டில் இன்னும் யார் யார் சேர்ந்திருந் தார்கள் என்பது எந்த இடத்திலும் குறிக்கப்பெறவில்லை.

இந்தக் கூட்டுக்குத் தலைமை தாங்கிய வித்தியாதரன் தன் னிடம் ஒப்படைக்கப்பெற்ற காரியத்தைச் செய்து முடிப்ப திலே வெற்றி பெற்றான். ராஜ்யபாலன் போரிலே உயிர் இழந் தான். அவன் மகன் திரிலோசன பாலனைச் சிங்காதனத்தில் அவர்கள் அமர்த்தினர். இந்தச் செய்தியைக் கேள்வியுற்ற மம்மூது கனல் பறக்கக் கோபித்தான். தன்னை அவமதிக்கத் துணிந்த அம் மன்னர்களுக்குப் புத்தி கற்பிக்கத் தீர்மானித் தான். அதனால் அவன் அடுத்த வருஷம், அதாவது கி.பி. 1019-ஆம் ஆண்டு, கன்னோசியின்மீது படையெடுத்து வந் தான். திரிலோசனபாலன் தன் தந்தையைப் போல எதிரிக் குப் பணிந்து போய்விடவில்லை; எதிர்த்து நின்று போராடி னான். ஆனாலும் வெற்றி கொள்ளமுடியவில்லை. ஒரு சமயம் திடீரெனத் தாக்குண்டதால் அவன் தோல்வியுற நேரிட்டது. ஆகவே அவன் அதுகாறும் தலைநகராக விளங்கிய பாரி யையம் துறந்து ஓடிவிட்டான்.

அதன்மீது மம்மூது தன் பெரும் படையுடன் இவ்வள வுக்கும் காரணமாகக் கருதப்பட்ட வித்தியாதரனைத் தாக்கப் போர்க்கோலம் பூண்டு வந்தான். வித்தியாதரன் பயந்து போய், “தன்னுடைய மூட்டை முடிச்சுகளையெல்லாம் போட் டவை போட்டபடியே விட்டுவிட்டு, உடன் கூட்டத்தாரான பரிவாரத்தோடு” ஓடிவிட்டான் என்று முஸ்லிம் சரித்திரங்கள் கூறுகின்றன.

ஆனால் அந்தப் போர் யாருக்கும் வெற்றி தோல்வி கிட்டா மல் முடிவடைந்ததென்றே எண்ணவேண்டியிருக்கிறது. கி.பி. 1021-22-ஆம் ஆண்டில் மம்மூது மறுபடியும் காலஞ்சர நகரத் தின் மீது படையெடுத்து வந்தான். வித்தியாதரன் “அதன் மீது சுல்தானைப் புகழ்ந்து ஹிந்து மொழியில் சில பாடல்களை

இயற்றி அவற்றைச் சுல்தானுக்கு அனுப்பிவைத்தான். சுல்தான் அவற்றை ஹிந்துஸ்தானத்தின் பெரிய வித்துவான்களிடமும் தன் சபையிலிருந்த வேறு புலவர்களிடமும் காண்பித்தான். அவர்கள் எல்லோரும் அந்தக் கவிதைகளைப் பெரிதும் பாராட்டினார்கள். அதன்மீது சுல்தான் தன்னுடைய பாராட்டுதலைத் தெரிவித்து, பதிலாகப் பதினைந்து கோட்டைகளின் அதிபதிப் பதவியையும் வேறு பல பரிசுகளையும் அனுப்பிவைத்தான். நந்தாவும் (அதாவது வித்தியாதரனும்) சுல்தானுக்குப் பொன்னும் மணியும் காணிக்கை அனுப்பிவைத்தான்.” (பிப்ளியோதகா இந்திகா தொகுதியில் பி. டே என் பார்மொழி பெயர்த்து வெளியிட்ட நபகத்-ஈ-அக்பரீ, பக்கம் 14.)

முஸ்லிம் ஆசிரியர்கள் பலபடியாகப் புகழ்ந்து கூறும் அவர்களுடைய சரித்திரங்களை ஊன்றிக் கவனித்தால், எவ்வளவுதான் முயன்றும் மம்மூதினால் காலஞ்சர நகரத்தைக் கைப்பற்ற முடியவில்லை யென்றும் கடைசியில் யாருக்கும் வெற்றி தோல்வி இல்லாமல் பரஸ்பரம் பரிசுகளைப் பரிமாறிக் கொண்டதோடு போர் முடிவடைந்தது என்றும் எண்ண வேண்டியிருக்கிறது. (கூர்ஜ்ஜர தேசத்தின் பழம் பேருமை என்ற பெயரில் ஸ்ரீ கே. எம். முன்ஷி எழுதிய நூலின் மூன்றாம் பாகமான கூர்ஜ்ஜர ஸாம்ராஜ்யம், பக்கங்கள் 134-5). இந்தச் சம்பவத் தோடு முஸ்லிம் மன்னன் கங்கைச் சமவெளியைக் கைக் கொள்ள வேண்டுமென்ற தன் ஆசையை அறவே ஒழித்து விட்டு, வேறு பகுதிகளில் தன் கவனத்தைச் செலுத்த நேர்ந்தது. (இந்தியன் ஆண்டிசுவரி, முப்பத்தேழாம் வால்பூம், பக்கம் 142.) இவ்விதம் கிழக்குப் பகுதியில் தன் எண்ணம் ஈடேற முடியாமல் போனதால் மம்மூது கூர்ஜ்ஜரத்தின் மீது படை யெடுத்துச் சென்றான். அதன் முடிவுதான் சோமநாதபுர ஆலயக் கொள்ளை.

இந்த நிலையில், வடக்கே வித்தியாதரனைத் தண்டிப்பதற்காக மம்மூது காலஞ்சர நகரத்தின்மீது படையெடுத்து வந்து வெற்றி காணாமல் திரும்பிச் சென்ற அதே ஆண்டுதான் இராஜேந்திரசோழனுடைய கங்கா விஜயமும் நிகழ்ந்தது. அந்தப் படையெடுப்பைப்பற்றி அவன் மெய்க்கீர்த்தி கூறுவது :

“விக்கிரம வீரர் சக்கரக் கோட்டமு  
முதிர்பட வல்லை மதுரை மண்டலமும்  
காமிடை வளைஇய நாமனைக் கோணமும்  
வெஞ்சின வீரர் பஞ்சப் பள்ளியும்  
பாசடைப் பழன மாசணி தேசமும்  
அயர்வில்வண் கீர்த்தி யாதிநக ரகவையிற்  
சந்திரன் தொல்குலத் திந்திர ரதனை  
வினையமர்க் களத்துக் கிளையொடும் பிடித்தும்  
பலதனத் தொடுநிறை குலதனக் குவையும்  
கிட்டருஞ் செறிமினை ஒட்ட விஷயமும்  
பூசரர் சேருநற் கோசலை நாடும்  
தன்ம பாலனை வெம்முனை யழித்து  
வண்டுறை சோலத் தண்ட புத்தியும்  
இரண சூரனை முரணறத் தாக்கித்  
திக்கனை கீர்த்தித் தக்கண லாடமும்  
கேர்விந்த சந்தன் மாவிழிந் தோடத்  
தங்காத சாரல் வங்காள தேசமும்  
தொடுகழற் சங்குகொ டடல்மகி பாலனை  
வெஞ்சமர் வளாகத் தஞ்சவித் தருளி  
ஒண்டிறல் யானையும் பெண்டிர் பண் டாரமும்  
நித்தில நெடுங்கட லுத்தர லாடமும்  
வெறிமலர்த் தீர்த்தத் தெறிபுனற் கங்கையும்”

தாரா நகரத்திலிருந்து அரசு செலுத்திய பரமார குல மன்னனான போஜராஜன் இந்திரரதன் என்பான் ஒருவனை வெற்றிக் கொண்டான் என்று உதயபூர்ச் சாசனம் கூறு கிறது. (எபி. இந்திகா, முதல் வால்பூம், பக்கங்கள் 223-38). இராஜேந்திரசோழன் ஆதி நகரில் முறியடித்தான் என்று கூறப்பெறும் சந்திர குலத்து இந்திரரதனும் அவனே போலும். மேலைச் சாளுக்கிய மன்னனான ஜயஸிம்ஹனு டைய காலத்தில், கி. பி. 1028-ஆம் கொண்டதாகக் குலேநார் என்னுமிடத்திலிருந்து கிடைக்கும் கல்வெட்டு ஒன்றிலிருந்து அவன் சோழ மன்னன், காங்கேயன், போஜராஜன் ஆகியோர்களுடைய யானைப் படையை அழித்தான் என்பது தெரியவருகிறது. ஜயஸிம்ஹனுடைய படைத் தலைவனான

சூந்திகன் என்பாளைப் புகழ்ந்துரைக்கும் பின்வரும் கன்னடச் செய்யுள் அந்தச் சாசனத்திலே உள்ளது.

மொநெயொள் சூந்திக நின்நெந்து பெற  
 நின்நெ வண்ணிபர்த்தா தூர்த்  
 திற மத்தேபதிநட்டு பெத்து ரணதோள்  
 பெந்நித்து தந்தாஹவக்  
 கிநிசந்நில்லதெ தூழ்து போத பயதம்  
 பெந்நித்து பாய்விட்டு சோ  
 முந காங்கேயந போஜராஜந கஜா  
 நீகங்களெம் பேலவே.

“ஏ சூந்திகா! போர் முனையில் காட்டும் செளரியத்துக்கு உதாரணமாக உன்னை அவர்கள் குறிக்கும்போது, மற்றவர்கள் உனக்கு அதிகப்படியாக வேறு என்ன புகழை அளிக்க முடியும்? சோழ மன்னன், காங்கேயன், போஜராஜன் ஆகியவர்களுடைய யானைப் படையைச் சேர்ந்தவர்கள், உன்னுடைய யானைகள் கன்னங்களில் வழியும் மதத்துடன் போரிலே அவர்களைத் தாக்கியபோது, பயங்கொண்டு தாங்கள் திருப்பித் தாக்குவதற்கும் காத்திருக்காமல், திறந்த வாயை மூடாமல் ஓடும்போது இதைத்தானே சொன்னார்கள்!” (ஷெ-பதினைந்தாம் வால்பூம், பக்கம் 333).

கி.பி. 1019-ஆம் ஆண்டு கொண்ட அம் மன்னனுடைய மற்றொரு சாசனம் அவனைப் ‘போஜராஜனாகிய தாமரைக்குச் சந்திரன் போன்றவன்’ என்று வருணிக்கிறது. (இந்தியன் ஆண்டிகுவரி, ஐந்தாம் வால்பூம், பக்கம் 17). இன்னும் அவன் ‘மாளவ அரசனுடன் கூடியிருந்தவர்களையும் தேடிப் பிடித்துப் பின்தொடர்ந்து முறியடித்துத் தூரத்தினன்’ என்று அதே சாசனம் கூறுகிறது. இவ்விதம் போஜராஜனோடும் காங்கேயனோடும் சேர்ந்துகொண்டு மேலைச் சாளுக்கிய மன்னனான ஜயஸிம்ஹனுடன் போரிட்டிருக்கக் கூடிய சோழ வேந்தன் முதலாம் இராஜேந்திரனாகவே இருத்தல் வேண்டும். கி. பி. 1020-ஆம் ஆண்டு கொண்ட போஜராஜனுடைய பன்ஸ்வாராச் செப்பேடுகள் (எபி. இந்திகா, பதினேராம் வால்



யும், பக்கம் 182) பேத்மாச் செப்பேடுகள் (ஷெ. பதினெட்டாம் வால்யூம், பக்கம் 320) ஆகிய இரண்டிலிருந்தும் அவன் கொங்கணத்தை அடிப்படுத்தி அந்த வெற்றி (கொங்கண கிரஹண விஜய பர்வணி)யைப் பெரியதொரு விழாவாகக் கொண்டாடினான் என்பது தெரியவருகிறது. இராஜேந்திர சோழனுடைய மெய்க்கீர்த்தியிலிருந்து அவன் முயங்கியில் போர் நடத்தியதும் இரட்டபாடி ஏழரை யிலக்கம் கைக் கொண்டதும் அதே சமயத்தில் நிகழ்ந்தவை என்பது தெரிய வரும்.

அவர்கள் கூட்டிலே சேர்ந்திருந்த மூன்றும் அரசன் சேதி நாட்டுத் திரிபுரீ நகரத்திலிருந்து அரசு செலுத்தி வந்த ஹைஹயர் எனப்பெறும் கலசூரி வமிசத்தைச் சேர்ந்த காங்கேய விக்ரமாதித்தியன் ஆவான்.

போஜராஜன், காங்கேயன் ஆகிய இருவரும் முஸ்லிம்களை எதிர்த்துப் போர் நிகழ்த்தியிருக்கிறார்கள். மாளவ தேசத்து மன்னர்களுடைய புகழைக் கூறும் உதயபூர்ப் பிரசஸ்தி என்னும் சாசனத்திலே போஜனைப் பற்றிப் பின்வரும் சுலோகம் காணப்படுகிறது.

சேதீச்வ ரேந்திரரத[தொக்க]ல [பீமமு]க்யான்  
கர்ணனாட லாடபதி கூர்ஜ்ஜர ராட் துருஷ்க்கான்  
யத்ப்ருத்ய மாத்ர விஜிதாந் அவலோ[க்ய]மௌலா  
தோஷ்ணம் வ(ப)லாநி. கலயம்தி ந[யோத்தர்]லோ[காந்]

“கர்நாடர், லாடபதி, கூர்ஜ்ஜர அரசன், துருஷ்க்கர்கள் இன்னும், சேதீச்வரன், இந்திரரதன், தொக்கலன், பீமன் ஆகியவர்களை முக்கியமாகக் கொண்ட மன்னர்களை இவ்வரசனுடைய வேலைக்காரர்களான கூலிப் படையே தோற்கடித்ததைக் கண்டு இவனுடைய நிலைப்படையான சேனை போர்ப் படையின் தொகைப் பெருக்கத்தைக் கருதாமல் தங்கள் தோள் வலிமையையே கொண்டு பெருமிதம் அடைந்தார்கள்.” (எபி. இந்திகா, முதல் வால்யூம், பக்கம் 235, சுலோகம் 19).

முஸ்லிம் சரித்திர ஆசிரியரான பிரிஷ்டா பின்வருமாறு எழுதியிருக்கிறார்: “ஹிஜ்ரி 399 (கி. பி. 1008)-ஆம் ஆண்டில்

மம்முது மறுபடியும் ஹிந்துஸ்தானத்தின்மீது படையெடுத்து, முன் மூல்தான்மீது படையெடுத்துச் சென்ற காலத்தில் தன்னிடம் மிகுந்த அலட்சிய புத்தியைக் காண்பித்து அகம் பாவமாக நடந்துகொண்ட அனந்தபாலனைத் தண்டிக்க வேண்டுமென்று தீர்மானித்துப் படைகளைத் திரட்டினான். இவன் அவ்விதம் செய்வதைக் கேள்வியுற்ற அனந்தபாலன் தன்னுடைய தூதர்களைப் பலதிசைகளிலும் அனுப்பி ஹிந்துஸ்தானத்து மற்ற அரசர்களைத் தனக்குத் துணைபுரிய வேண்டினான். முகம்மதியர்களை இந்தியாவிலிருந்து துரத்துவதைத் தர்மமாக, புரித கைங்கரியமாக, ஹிந்துஸ்தான மன்னர்கள் இப்போது கருதினார்கள். அவ்விதமே உஜ்ஜைன், குவாலியர், காலிஞ்சர், கன்னௌஜ், தில்லி, அஜ்மீர் அரசர்கள் ஒன்றாகச் சேர்ந்து தங்கள் படையைத் திரட்டிப் பஞ்சாபை நோக்கி முன்னேறினார்கள்.” (எல்லியட் என்பவர் மொழிபெயர்த்து டௌஸன் என்பார் பதிப்பித்த ‘இந்திய சரித்திரம்—மூல ஆசிரியர்கள் கூறியவிதம்’ என்ற நூலின் இரண்டாம் வால்பூம், 406 பக்கம் முதல்). அந்நாளிலே மாளவ தேசத்துக்கு உஜ்ஜயினியே தலைநகரமாக இருந்தது. அதனால் பிரிஷ்டா குறிப்பிட்ட உஜ்ஜைன் அரசன் போஜராஜனாகவே இருத்தல் வேண்டும்.

போஜராஜன், இராஜேந்திர சோழன் ஆகிய இருவருடன் சேர்ந்திருந்த மூன்றாம் மன்னனை சேதி நாட்டுக் கலசூரி அரசன் காங்கேய விக்கிரமதித்தியனும் வலிமை வாய்ந்தவனே: அவனுடைய ஆட்சி கி. பி. 1019-ஆம் ஆண்டிலே நடைபெற்று வந்திருக்கிறதென்று தெரிகிறது. (வங்காளத்து ஏஷ்யாடிக் ஸோஸைட்டி ஜர்னல், 1903-ஆம் ஆண்டு, முதல்பாகம், பக்கம் 18). அது கி. பி. 1042-ஆம் ஆண்டுக்குச் சற்று முன்னதாக முடிவடைந்திருக்க வேண்டும். (எபி. இந்திகா, இரண்டாம் வால்பூம், பக்கம் 297). சந்தெல்லர் அல்லது சந்திராத்ரேயர்களுடைய புகழைக் கூறுவதாக மஹோபா என்னுமிடத்திலிருந்து கிடைத்துள்ள கல்வெட்டில், கன்னோசி வேந்தனை ராஜ்யபாலனைப் பழிவாங்கிய வித்தியாதரனைப் பற்றிப் பின்வருவது காணப்படுகிறது :

“விஹீத கர்யாகுப்ஜ பூபால பங்கம்  
ஸமரகூரும் உபாஸத ப்ரௌடபீஸ் தல்ப பாஜம்  
ஸஹ கலசூரி சந்தர்ஃ சிஷ்யவத் போஜ தேவஃ”

“கன்யாகுப்ஜத்துப் பூபாலனைப் பங்கப்படுத்தியவனும் போர்க்கலை அரசனுமான [வித்தியாதரனைப்] போஜராஜனும் கலசூரி சந்திரனும் ஆசிரியனாகக் கொண்டு பயபக்தியோடு தொழுது நின்றார்கள்.” (ஷு. முதல் வால்பூம், பக்கங்கள் 221-22, சுலோகம் 22). இதிலிருந்து கி.பி. 1019-ஆம் ஆண்டில் கன்யாகுப்ஜத்து அரசனான ராஜ்யபாலனுக்கு விரோதமாக வித்தியாதரனோடு ஒன்று சேர்ந்திருந்த மன்னர்களில் போஜராஜனும் காங்கேய விக்ரமதித்தியனும் கூடியிருந்து வித்தியாதரனைப் பின்பற்றிச் சென்றனர் என்பது விளங்கும்.

இதுகாறும் கூறியவற்றைக் கவனிக்கும்போது, குலே நூர்க் கல்வெட்டின்படிச் சற்றேறக்குறைய இதே காலத்தில் போஜராஜனோடும் காங்கேயனோடும் நடப்புக்கொண்டு கூட்டாகப் போர்களை நிகழ்த்திய இராஜேந்திர சோழனும் கி.பி. 1021-22-ஆம் ஆண்டிலே காலஞ்சர நகரத்தின்மீது முஸ்லிம் படையெடுப்பு நடந்த காலத்தில் சந்தெல்ல மன்னனான வித்தியாதரனுக்கு உதவுவதற்காக அவர்களோடு சேர்ந்துகொண்டிருத்தல் கூடும் என்று எண்ணுவது இயற்கையே.

இராஜேந்திரன் வெற்றி கொண்டனவாக அவனுடைய மெய்க்கீர்த்தியில் காணப்படும் ஊர்ப் பெயர்களைக் கவனித்தாலும் இது ஓர் அளவு ஊர்ஜிதமாகும்.

சக்கரக்கோட்டத்தைக் கைப்பற்றிய பிறகு இராஜேந்திர சோழன் மதுரை மண்டலம், நாமணைக்கோணம், பஞ்சப் பள்ளி, மாசுணி தேசம் ஆகிய இடங்களைக் கைப்பற்றினான் என்று மெய்க்கீர்த்தி கூறுகிறது. சக்கரக்கோட்டம் என்பது மத்தியப் பிரதேசத்தைச் சேர்ந்த பஸ்தர் ராஜ்யத்தில் உள்ள சித்ரகூட் என்னும் ஊராகும். கி.பி. 1065-ஆம் ஆண்டு கொண்டதாக ராஜாபுரத்திலிருந்து கிடைத்த நாகவம்ச அரசனான மதுராந்தகனுடைய செப்பேட்டுச் சாசனத்தில் இது சக்ரகோட்யம் என்று காணப்படுகிறது. (எபி. இந்திகா, ஒன்பதாம் வால்பூம், பக்கம் 178-9).

ராஜாபுரம் செப்பேடுகளை வழங்கிய சிந்தகர்கள் நாகவழி சத்தைச் சேர்ந்தவர்கள்; தங்களை நாகவம்சோத்பவர்கள் என்றும் போகவதீபுவரேச்வரர்கள் என்றும் கூறிக்கொள்ளுகிறார்கள். மாசணிதேசம் என்றால் 'பாம்புகளின் நாடு' எனப் பொருள் படும்; அதனால் அது சிந்தகர்களுடைய ஆட்சிப் பிரதேசமே யாகும் எனக் கொண்டுள்ளார்கள். இந்த முடிவிற்படி 'மதுரை மண்டலம், நாமனைக்கோணம், பஞ்சப்பள்ளி ஆகியவை மாசணி தேசத்தின் பகுதிகளாகின்றன.' மாசணி தேசமே சக்கரக்கோட்டப் பகுதியில் சேர்ந்திருத்தல் வேண்டும். இவ்விதம் மேலே குறிக்கப்பட்ட பிரதேசங்கள் எல்லாம் ஒரு சிறு பகுதியிலே அடங்கியிருந்தனவென்று கொண்டிருக்கிறார்கள். (க. அ. நீலகண்ட சாஸ்திரிகள் எழுதிய சோழர்கள், முதல் வால்பூம், பக்கம் 250).

ஆனால் ஒரு விஷயத்தை நாம் கவனிக்கவேண்டும். மெய்க் கீர்த்தியில் காணும் ஊர்ப் பெயர்களை அதே பொருளைத் தரக் கூடிய வேறு இரண்டு மூன்று சொற்களால் மொழிபெயர்த்துக் கொடுப்பது இல்லை. இதேபோல நடந்திருப்பதாக வேறு உதாரணம் எதுவும் காட்டமுடியாது. அதனால் மாசணி தேசம் நாக நாடாக, அதாவது நாகர்கள் ஆட்சிக்குப்பட்டிருந்த பகுதியாக, இருந்திருக்கமுடியாது. அதே பெயரைக் கொண்ட ஒரு பிரதேசமாகவே இருத்தல் வேண்டும்.

அத்தகைய பிரதேசம் ஒன்று விந்துவின் வட பகுதியிலே இருந்திருக்கிறது. கிரேக்க அரசனான அலெக்சாண்டருடைய படையெடுப்பைப்பற்றி எழுதும் கிரேக்க சரித்திர ஆசிரியரான டயடோரஸ், அம்மன்னன் பஞ்சாபில் நதிசங்கமங்களைக் கடந்து சிந்து நதியின் வழியே படகில் வந்ததை விவரிக்கும்போது பின்வருமாறு எழுதுகிறார்: "ஆற்றிலே நீரோட்டத்தின் வழியே படகைச் செலுத்திச் செல்லுகையில் மன்னன் நதியின் இருகரையிலும் எதிர் எதிராக வாழ்ந்த ஸோத்ரே; (அல்லது சோத்ரி) மாசணி (அல்லது மாசணே) ஆகிய இரண்டு வகுப்பாருடைய சரணாகதியை ஏற்றுக்கொண்டான்." (கன்னிங்ஹாம் எழுதிய புராதான இந்தியாவின் பூகோளம், சுரேந்திரநாத் மஜும்தார் சாஸ்திரியின் பதிப்பு, பக்கம் 290)

இந்த ஓர் இடத்தைத் தவிர இந்தியா முழுவதிலும் இதே போன்ற பெயரையுடைய பிரதேசம் வேறு எங்கும் இல்லை; இது ஒன்றுதான். சோழர்களுக்குத் துணைவனாக இருந்த பரமார மன்னனான போஜராஜன் ஸிந்து நாட்டிலே முஸ்லிம் களை வெற்றி கொண்டதாகப் புகழ்ப்பெறுகிறான். (கே. எம். முன்ஷி எழுதிய கூர்ஜூர ஸாம்ராஜ்யம், பக்கம் 139; அனுபந்தம் எப், பக்கங்கள் 280-81; டி. ஸி. கங்கூலி எழுதிய பரமார வமிச சரித்திரம், பக்கங்கள் 99-101). ஆகவே, இராஜேந்திரன் கைக் கொண்டதாக அவனுடைய மெய்க்கீர்த்தியிலே குறிக்கப் பெறும் மாசணி தேசம் ஸிந்துநதி தீரப் பிரதேசமே யாகும் எனக் கொள்வது தவறாகாது.

மதுரை மண்டலம் என்பது யமுனை நதிக்கரையில் உள்ள மதுரா நகரத்தைச் சுற்றிய பிரதேசமே போலும். தமிழ் நாட்டிலே இரண்டு மதுரைகள் மட்டுமே பிரசித்தம். ஒன்று பாண்டியர்களின் தலைநகரான தென் மதுரை. மற்றொன்று கிருஷ்ண பகவான் பிறந்து விளையாடியதாகப் புராணப் பிரசித்திபெற்ற வட மதுரை. இராஜேந்திர சோழன் காலத்திலும் வட மதுரை புகழ்பெற்று விளங்கியது. கஜ்னியின் சுல்தானான மம்பூது கொள்ளையிட்ட நகரங்களின் பெயர்களிலே இந்நகரின் பெயரும் முக்கியமானதாகக் காணப்படுகிறது. அன்றி, நதூல தேசத்து அரசன் மஹேந்திர ராஜனுடைய சகோதரியான தூர்லபதேவியை அனஹில பாடக நகரத்து அரசனான தூர்லபராஜன் (கி. பி. 1010-முதல் 1022-வரையில் அரசு செலுத்தியவன்) மணந்து கொண்ட சமயம் நடந்த சுயம்வரத்துக்கு அங்கதேசம், காசீதேசம், அவந்தி (உஜ்ஜயினி), சேதிதேசம், குருதேசம், ஹுண தேசம், மதுராதேசம், விந்தியதேசம் போன்ற நாட்டு மன்னர்களும் வந்திருந்தார்கள் என்று ஹேமசந்திரர் தம் முடைய துவயாசர்யம் என்னும் நூலில் எழுதியிருக்கிறார். (ஏழாம் சர்க்கம், 547-பக்கம் முதல்.) குலோத்துங்க சோழன் பிள்ளைத் தமிழும் வடமதுரை, அதாவது யமுனைக் கரையில் உள்ள மதுரா நகரம், சோழர்களைச் சேர்ந்ததென்றும் அவர்களுடைய ஆட்சி அங்கே நிலவியிருந்தது என்றும் பொருள் படுமாறு,

“ வட மது ரையிலொரு புடையிடை வனிதையர்  
மெய்க்கவின் மைக்காவின்  
வயிறற மணியுத வரிவளை யுடனணி  
பொற்றொடி சிற்றுடை  
கொடிமறு கடையவு மொளிபெற வருமுகில்  
கொட்டுக சப்பாணி ”

(பாடல் 34)

எனவும்,

“ மருக்கமமும் வடமதுரை வளநகர்க்கும் பழையோம் ”

(சிறுதேர்ப்பருவம்-பாடல் 95)

எனவும், கூறுகிறது.

இவ்விதம் கொண்டு மெய்க்கீர்த்தியை மேலெழுந்தவாரி யாகக் கவனித்தாலும் அரசன் சக்கரக் கோட்டத்தை விட்டுக் கிளம்பிக் கங்கைக் கரையை அடைவதற்கு முன்னதாக, இடைப்பட்டுள்ள பிரதேசத்து நாடுகளைப்பற்றிய பிரஸ்தாபமே இல்லை யென்பதை அறியலாம். இதிலே வியப்புறுவதற்கு ஏதும் இல்லை. இடைப்பட்ட நாடுகள் அவனுடைய நேசக் கட்சியைச் சேர்ந்த போஜன், காங்கேயன், வித்தியாதரன் ஆகியவர்களுடைய ஆளுகைக்கு உட்பட்டவை. அவற்றின் வழியாக அவன் தன் படைகளை நடத்திச் சென்றானே ஒழிய, போரிட்டு அந்தப் பகுதிகளைக் கைக்கொள்ளவில்லை. அதனாலேயே அந்த இடைப்பிரதேசத்தை அவன் தன்னுடைய வெற்றியாக மெய்க்கீர்த்தியில் குறிப்பிடவில்லை.

சோழ மன்னன் வென்று அடிப்படுத்தியதாகக் கூறிக் கொள்ளும் பிரதேசங்களையே போஜராஜன், காங்கேயன் ஆகிய இருவரும் வெற்றி கொண்டதாகக் குறிப்பிடுவதையும் நாம் கவனிக்கவேண்டும். போஜராஜன் கௌட தேசம், தக்ஷிணபதம் உள்படப் பரந்த பிரதேசத்தை ஆண்டு வந்தான் என்பதை,

பஞ்சாசத் பஞ்ச வர்ஷாணி மாஸாஸ்ப்த திந த்ரயம்

போக்தவ்யம் போஜராஜேந ஸ கௌடம் தக்ஷிணபதம்

என மேருதுங்கர் தம்முடைய பிரபந்த சிந்தாமணியில் முஞ்சப் பிரபந்தத்தில் (பக்கம் 57) கூறுகிறார். இந்திரதனைப் போஜ

ராஜன், இராஜேந்திர சோழன் ஆகிய இருவரும் அடிப்படுத்தி யிருக்கிறார்கள். சேதி மன்னனான காங்கேயன் அங்க நாட்டு அரசனை ஜயித்திருக்கிறான். (லக்தம்-கர்ணனுடைய கோஹர் வாச் செப்பேடுகள், எபி. இந்திகா, பதினேராம் வால்பூம், பக்கம் 143, சுலோகம் 17.) கி. பி. 1033-ஆம் ஆண்டு கொண்ட அவனு டைய பியாவன் மலைக் கல்வெட்டிலிருந்து அவனுடைய ஆட்சி மேற்கே ரேவா வரையிலும் பரவியிருந்ததென்று தெரியவரு கிறது. (இந்தச் சாசனம் கன்னிங்ஹாம் அவர்களால் ஆர்க்கிய லாஜிகல் ஸர்வே ரிபோர்ட், இருபத்தேராம் வால்பூம், 112-13-ஆம் பக்கங்களில் பதிப்பிக்கப்பட்டிருக்கிறது).

காசி நகரமும் காங்கேயனுடைய ஆட்சிக்கு உட்பட்டிருந் ததாகத் தெரிகிறது. கி. பி. 1033-ஆம் ஆண்டு அளவில் அந் நகரம் காங்கேயனுடைய ராஜ்யத்தில் சேர்ந்திருந்ததாகப் பைஹகி என்னும் முஸ்லிம் சரித்திர ஆசிரியர் கூறுகிறார். (எல்லியட்டும் டௌஸனும் வெளியிட்ட 'இந்திய சரித்திரம்-அந் நாட்டுச் சரித்திர ஆசிரியர்கள் கூறியபடியே', இரண்டாம் வால் பூம், தரீக்-ஈ-பைஹகி, பக்கம் 213).

அப்போது பஞ்சாபிலே அஹ்மத் நியால்தகின் என் னும் முஸ்லிம் கவர்னராக இருந்தான். அவன் யமிநீ அரச னான முதலாம் மஸூதின தளகர்த்தனுமாவன். தன்னுடைய அரசனான கஜ்னி சுல்தான் பிடிப்பிலிருந்து தன்னை விடு விடுத்துக் கொள்வதற்காகத் தான் திட்டமிட்ட சூழ்ச்சிகளை நிறைவேற்றுவதற்கு வேண்டிய பொன்னையும் மணியையும் பெறுவதற்காக அவன் கன்யாகுப்ஜத்தின்மீது படையெடுத்து வந்து காசியையும் அடைந்தானாம். அதற்கு முன் அந் நக ரத்துக்கு முஸ்லிம் அரசன் யாரும் வந்ததில்லை. ஆகவே அவ னுக்கு அங்கே ஏராளமான கொள்ளை கிட்டியது. அவற்றைத் திரட்டிக்கொண்டு அவன் திரும்பவும் கன்னோசி வழியாகவே தன் நாட்டை அடைந்தான்.

தாரா நகரத்துப் போஜராஜன் மகா வித்துவான் என் றும், வித்துவான்களை ஆதரித்தவன் என்றும் கூறுவார்கள். அதேபோல இராஜேந்திர சோழனும் விளங்கினான் என்பது பண்டித சோழன் என்னும் அவனுடைய விருதிலிருந்து தெரிய

வரும். இன்னும் அவன் கொண்டிருந்த மற்றொரு விருதான கங்கைகோண்ட சோழன் என்பதைப்போன்றதே சேதி நாட்டு மன்னனான விக்கிரமதித்தியனுடைய காங்கேயன் என்னும் விருதுமாகும்.

[இந்த நிலையில் ஒரு விஷயத்தை நாம் மறக்கக்கூடாது. காங்கேயனுடைய ஆட்சிக்காலம் கி. பி. 1019-ஆம் ஆண்டிலிருந்தே நடந்துவந்ததாக நாம் மேலே குறிப்பிட்டிருக்கிறோம். அவ்விதமாயின் கங்காவிஜயத்து வெற்றியின் பயனாக அவன் அந்த விருதைத் தரித்துக்கொண்டான் என்று கூறுவது பொருந்தாததாகும். நேபாளத்திலிருந்து கிடைத்த ஒரு ராமாயணப் பிரதியின் முடிவில் அது பிரதி செய்யப்பெற்ற காலம் பின் வருமாறு எழுதப்பட்டிருக்கிறது. “ஸம்வத் 1076 ஆஷாட வதி 4 மஹா ராஜாதி ராஜ புண்யாவலோக ஸோம வம்சோத் பவ கௌட (கருட)த்வஜ ஸ்ரீமத் கங்காய தேவ பூஜ்யமானே தீரபுக்தௌ கல்யாண விஜயராஜ்யே....” அதில் குறிக்கப்பட்ட வருஷத்தை விக்கிரம ஆண்டாகக் கொண்டு கி.பி. 1019 எனக் கணக்கிட்டிருக்கிறார்கள். அந்த வருஷம் சகாப்தத்தையே குறிப்பதாகும் என்றும், அதனால் அதன் காலம் கி. பி. 1154 ஆகும் என்றும், அதிலே குறிக்கப்பட்டவன் மிதிலையில் ஆண்டு வந்த கர்நாட வமிசத்தரசனான கங்காதேவன் என்றும், அவன் காலத்துக்கு அது சரியாக வருகிறதென்றும் (பண்டார்க்கர் ஓரியண்டல் ரிஸர்ச் இன்ஸ்டிடியூட் பத்திரிகையின் வெள்ளிவிழா மலரில் 299-301-ஆம் பக்கங்கள்) மகா மகோபாத்யாய வி. வி. மிராஷி கருதுகிறார். (அதே ஸ்தாபனத்துப் பத்திரிகையின் முப்பத்தைந்தாம் வால்யூம், (1954) 102-106-ஆம் பக்கங்களையும் பார்க்க).]

உதயபூர்ப் பிரசஸ்தியிலே பரமார மன்னனான போஜனுடைய ஆட்சி “கைலாசம் வரையிலும், மலயபர்வதம் வரையிலும் உதயகிரி, அஸ்தமயகிரி ஆகிய இரு மலை வரையிலும் உள்ள பூமியில் பரந்து நிலவியது” என்று புகழ்ந்து கூறப்பட்டுள்ளது. (எபி. இந்திகா, முதல் வால்யூம், 233-38 பக்கங்கள், சுலோகம் 17). மலய பர்வதம் சோழ மன்னனான இராஜேந்திரனுடைய ஆளுகைக்கு உட்பட்டிருந்தது. ஆகவே அதை அவன் கைக்கொண்டிருத்தற்கில்லை. நேச மன்னனான சோழ



னுடைய நாட்டிலும் அவனுடைய ஆதிக்கியம் இருந்து வந்தது எனக் கொண்டே பிரசஸ்திகாரர் இவ்விதம் புகழ்ந்திருத்தல் வேண்டும். [சோழ மெய்க்கீர்த்தி அவ்விதம் வீண் புகழ்ச்சி கொள்ளாமல் உள்ள நிலையையே எடுத்துக் கூறுவது இங்கே கவனிக்கத்தக்கது.]

இவற்றையெல்லாம் கவனிக்கும்போது இராஜேந்திர சோழன் தன் படையை வடக்கே நடத்திச்சென்று கங்கா விஜயம் செய்தது, போஜராஜன், காங்கேயன், மற்றும் வட நாட்டு மன்னர்கள் ஆகியவர்களோடு கூடிக் கஜ்னியின் முஸ்லிம் அரசனை மம்முது நடத்திய படையெடுப்புகளைத் தடுப்பதற்காகவே யாகும் என்று எண்ணத் தோன்றுவது இயற்கையே. இவனுக்குப்பின் சோழ சிங்காதனம் ஏறிய இவனுடைய குமாரர்கள் தமிழ் நாட்டுக்கு வெகுதூரம் வடக்கே யுள்ள கங்கைக் கரைப் பிரதேசங்களுக்குச் சோழ இராஜ குமாரர்களைச் சக்கரவர்த்தியின் பிரதிநிதிகளாகவும் அனுப்பி வந்திருப்பது இதனை மேலும் வலிபுறுத்தும்.

### இராஜேந்திரனை யடுத்துப் பட்டம் பெற்றவர்கள்

முதலாம் இராஜேந்திரன் காலத்திலேயே முடிசூட்டப் பெற்ற அவனுடைய மகன் முதலாம் இராஜாதிராஜனுடைய 'திங்களேர் தரு' என்று தொடங்கும் மெய்க்கீர்த்தியில் இராஜகுமாரர்களை நாட்டின் பல பகுதிகளுக்கும் பிரதிநிதிகளாக அனுப்பிய செய்தி பின்வருமாறு காணப்படுகிறது :

“ தன்சிறிய தாதை யுந்திருத் தமையனுங்  
குறிகொள்தன் இளங்கோக் கிளையு நெறியுணர்  
தன்திருப் புதல்வர் தம்மையுந் துன்றெழில்  
வானவன் வில்லவன் மீனவன் கங்கன்  
இலங்கையர்க் கிறைவன் பொலங்கழற் பல்லவன்  
கன்னகுச் சியர்கா வலலெனப் பொன்னணி  
சுடர்மணி மகுடஞ் சூட்டிப் படர்புகழ்  
ஆங்கவர்க் கவர்நா டருளி ”

இந்தச் செய்தி மெய்க்கீர்த்தியின் ஆரம்பப் பகுதியிலே கூறப் பட்டுள்ளது. ஆயினும் அம் மன்னனுடைய மெய்க்கீர்த்திகள்

அவனுடைய இருபத்தாரும் ஆண்டுச் சாசனங்களிலிருந்து தான் காணப்படுகின்றன. 'திங்களேர் தரு' என்று தொடங்கும் மெய்க்கீர்த்தியோ இருபத்தேழாம் ஆண்டுச் சாசனத்தில் தான் முதல்முதலாகக் கிடைத்துள்ளது.

சோழ ஸாம்ராஜ்யத்தின் வெவ்வேறு பகுதிகளை ஆண்டு வருவதற்காக இராஜகுமாரர்களைப் பிரதிநிதிகளாக நியமிக்கும் பழக்கம் முதலாம் இராஜேந்திரனுடைய ஆட்சிக் காலத்திலேயே ஆரம்பமாகிவிட்டது. பாண்டிய நாட்டுக்கும் சேர நாட்டுக்கும் அவ்விதம் பிரதிநிதிகளாக அனுப்பப் பெற்றிருந்த இராஜகுமாரர்கள் முறையே சோழ பாண்டியன், சோழ கேரளன் என்ற விருதுகளுடன் ஆண்டுவந்திருக்கிறார்கள். அந்நாட்களில் அவர்கள் அளித்த சாசனங்களும் கிடைத்துள்ளன. அம்மாதிரியே முதலாம் இராஜாதிராஜனும் பல பகுதிகளுக்கும் ராஜப் பிரதிநிதிகளை நியமித்திருக்கிறான். அவ்விதம் நியமிக்கப்பட்டவர்களுள் கன்யாகுபஜ நாட்டை ஆளுவதற்காக நியமிக்கப்பட்ட இராஜகுமாரன் ஒருவனும் காணப்படுவதை நாம் கவனிக்கவேண்டும்.

இராஜாதிராஜனைப் போலவே அவனுக்குப் பின் சோழ சிங்காதனம் ஏறிய அவன் தம்பி இரண்டாம் இராஜேந்திரனும் இம்மாதிரியே இராஜ குமாரர்களைப் பிரதிநிதிகளாக நியமித்திருக்கிறான். இந்தச் செய்தியும் 'திருமாதா புவியெனும்' என்று தொடங்கும் அவனுடைய மெய்க்கீர்த்தியில் கூறப்பட்டிருக்கிறது.

“தன்

சிறிய தாதை யாகிய வெறுழ்வலிக்  
கங்கை கொண்ட சோழனைப் பொங்கிகல்  
இருமுடிச் சோழ னென்றும் பெருமுரட்  
டன்திருத் தம்பியர் தம்முள் வென்றிகொள்  
மும்முடிச் சோழனைத் தெம்முனை யடுதிறற்  
சோழ பாண்டிய னென்றுங் கோழிமன்  
தொடுகழல் வீரசோழனைப் படிப்புகழ்  
கரிகால் சோழ னென்றும் பொருதொழில்  
வாள்வலித் தடக்கை மதுராந் தகனைச்  
சோழ கங்க னென்றுந் தோள்வலி

மேனிகல் பரார்தக தேவனைச் சோழ  
 அயோத்திய ராச னென்றும்  
 இருதயத் தன்பொடு கருது காதலருள்  
 இத்த லம்புக ழிராசசேந்திர சோழனை  
 உத்தம சோழ னென்றும் தொத்தணி  
 முகையவி ழலங்கன் முடிகொண்ட சோழனை  
 இகல்விச யாலய னென்றும் புகர்முகத்  
 தேமுயர் களிற்றுச் சோழ கேரளனை  
 வார்சிலைச் சோழ கேரள னென்றும்  
 திண்டிறற் கடாரங் கொண்ட சோழனைத்  
 தினகரன் குலத்துச் சிறப்பமர் சோழ  
 சனக ராச னென்றும் கனைகடற்  
 படிகொண்ட பல்புகழ் முடிகொண்ட சோழனைச்  
 சுந்தர சோழ னென்றுஞ் செந்தமிழ்ப்  
 பிடிகளிற் றிரட்ட பாடி கொண்ட  
 சோழனைத் தொல்புவி யாளுடைச் சோழ  
 கன்னகுச் சியராச னென்றும் பின்னுந்தன்  
 காதலர் காதலர் தம்முள் மேதகு  
 கதிராங் கனைகழல் மதுராந் தகனை  
 வெல்படைச் சோழ வல்லப னென்றும்  
 மானச் சிலைக்கையோ ரானைச்சே வகனை  
 நிருபேந்திர சோழ னென்றும் பருமணிச்  
 சுடர்மணி மகுடஞ் சூட்டி.”

மேலே கொடுக்கப்பட்டுள்ள மெய்க்கீர்த்திப் பகுதி இம்  
 மன்னனுடைய நான்காம் ஆண்டு கொண்டதாக மணிமங்  
 கலத்திலிருந்து கிடைக்கப்பெறும் கல்வெட்டில் காண்ப  
 தாகும். இதிலே அவன் தன்னுடைய சிறிய தாதை ஒருவர்,  
 நான்கு தம்பிகள், ஆறு பிள்ளைகள், இரண்டு பேரப் பிள்ளை  
 கள் ஆகப் பதின்மூன்று பேர்களை இவ்விதம் பிரதிநிதிகளாக  
 அனுப்பினான் என்று கூறப்படுகிறது. ஆனால் ஆட்சியின் பிற  
 பகுதியில் காணும் மெய்க்கீர்த்தியில் இந்தப் பட்டியல் குறுகி  
 விடுகிறது;

“திருக்காதலனை ஓதலர் தருங்கால்  
 கங்கை கொண்ட சோழனையும்

ஆங்கவன் திருமகனான இருநிலங் காவலன்  
ஆளவந்த பெருமானையும்  
வென்றிகொள் தன்திருத் தம்பியர் தம்முள்  
வன்றிறல் வளவன் முடிமுடிச் சோழனையும்  
களப்படை வீர சோழனையும்

வெல்படை மதுராந்த கனையும்

பார்அணி திரள்தோள் தன்திரு மகன்  
இராஜேந்திர சோழனையும் தராபதி  
இருமுடிச் சோழன் ராஜாதிராஜன்  
சுருதிமென் குணருஞ் சோழ பாண்டியன் [கங்கன்  
வார்சிலைத் தாணக் கரிகால சோழனென்றும் சோழ  
தொடுகழல் உத்தம சோழனென்றும்  
சுடர்நறு மணிபுனைத் திருமுடி சூட்டித்  
தென்னவர் முதலியர் நிருபரைத் தாங்கவர்  
இருநில மான நிலம்அவர்க் கருளி"]

அதிலே ஆறு பெயர்களே காணப்படுகின்றன. அவர்கள் மேலே குறித்த சிறிய தாதை, அந்தச் சிறிய தாதையின் மகன் (இவன் பெயர் புதியதாகச் சேர்க்கப்பெற்றிருப்பது), நான்கு தம்பிகளில் மூன்று தம்பிகள், இன்னும் அரசனுடைய மகன் ஆக அறுவர். இவற்றை நோக்கும்போது இவ்விதம் இராஜ குமாரர்களை வெளி நாடுகளுக்குப் பிரதிநிதிகளாக அனுப்பியதில், அவர்கள் அந்த அந்த இடங்களிலேயே கிரந்தரமாக இருந்து ஆண்டு வரவில்லை யென்பதும், சந்தர்ப்பத்துக்கு ஏற்றபடி அவர்களை அடிக்கடி மாற்றி வந்திருக்கிறார்கள் என்பதும் தெளிவாகும். [மெய்க்கீர்த்தியில் அளிக்கப்பெற்றனவாகக் காணப்பெறும் இந்தப் பதவிகளை வெறும் பட்டப் பெயர்களாகவே கொள்ள வேண்டுமென்று ஓர் ஆசிரியர் கருதுவர். அவ்விதம் அல்லவென்பதை இது எடுத்துக் காட்டுகிறது. அன்றி, இம் மெய்க்கீர்த்தியிலே அதற்குமுன் சோழ கேரளாக இருந்தவனை இம் மன்னன் திரும்பவும் அதே பதவியில் அமர்த்தினான் என்றும் கூறப்பட்டுள்ளது. இன்னும் 'ஆங்கு அவர்க்கு அவர் நாடு அருளி' என்று இராஜாதிராஜன் மெய்க்கீர்த்தியில் காணப்படுவதையும் கவனிக்க.]

இரண்டாம் இராஜேந்திரனுக்குப் பிறகு சோழ சிங்காதனம் ஏறிய அவன் தம்பி வீரராஜேந்திரனும் 'திருவளர் திரள்

புயத்து' என்று ஆரம்பிக்கும் தன்னுடைய மெய்க்கீர்த்தியிலே இவ்விதம் இராஜ குமாரர்கள் சிலருக்குப் பதவி யளித்ததைப் பற்றிக் கூறிக்கொள்கிறான்.

“முறைமையில்

அரும்பெறல் தமையன் ஆளவந் தானை  
இரும்புவி புகழி ராஜாதி ராஜனென்றும்  
ஒளிமணி முடிசூட்டித் தன் திருப்  
புதல்வனாகிய மதுராந்தகனை  
வாளேந்து தானைச் சோழேந்திர னென்று  
எண்டிசை நிகழ வெழில்முடி சூட்டித்  
தொண்டை மண்டலம் கொடுத்தருளித்  
திண்டிவல் மைந்தனாகிய கங்கைகொண்ட சோழன்  
ஏழுயரி யானைச் சோழ பாண்டிய னெனத்  
திண்டியர் மணிமுடி இசைபெறச் சூட்டிப்  
பாண்டி மண்டலங் கொடுத்தருளி ஆண்டகை  
வடிகொண்ட கதிர்வேல் முடிகொண்ட சோழனைச்  
சுந்தர சோழனென்று சுடர்முடி சூட்டி  
அந்தமில் பெருஞ்சிறப் பருளித் தன்கிளை  
எவ்வெ ருலகத்த வர்க்குரிய வகலிடம்  
வேறு வேறு அருளி ”

இது அவனுடைய ஆட்சியின் ஆரம்ப காலத்திலேதான் காணப்படுகிறது. ஆட்சியின் பிற்பகுதியில் காணும் மெய்க்கீர்த்தியில் இந்தச் செய்தி குறிக்கப்பெறவில்லை. அன்றி, அதிலே வடஇந்தியப் பிரதேசங்களுக்கு அவன் அவ்விதம் பிரதிநிதிகளை அனுப்பினான் என்பதைப் பற்றிய பிரஸ்தாபமும் இல்லை. ஆயினும், ‘வீரமே துணையாகவும்’ என்று தொடங்கும் அவனுடைய மற்றொரு மெய்க்கீர்த்தியில் கன்ன குச்சி மீட்டு என்பது காணப்படுகிறது. (தே. இ. சாசனங்கள், மூன்றாம் வால்யூம், நெ. 83, பக்கங்கள் 201-4.)

இவ்விதம் மெய்க்கீர்த்திகளிலே தெளிவாகச் சொல்லப் பட்டிருப்பனவற்றை அந்த மெய்க்கீர்த்திகளை இயற்றிய கவி களின் கற்பனையென்றே மிகைப்படக் கூறப்பட்டவை யென்றே ஒதுக்கித் தள்ளிவிடமுடியாது. சோழ மன்னர்

களையும் அவ்விதம் வீண் பெருமையிலே திளைத்திருந்தவர்கள் என்று நாம் கொள்ளமுடியாது. அவர்கள் இராஜகுமாரர்களுக்கு உண்மையிலே அத்தகைய பதவிகளை அளித்திருக்காவிட்டால் இவ்விதம் அவைகளைப்பற்றிப் பெருமையாக மெய்க்கீர்த்திகளில் கூறிக்கொண்டிருக்கமாட்டார்கள். அன்றி, அந்த அந்த நாடுகள் சோழர்களுடைய ஆதிக்கியத்துக்கு உட்பட்டிருக்காவிட்டால் மன்னர்கள் அவ்விதம் அந்நாடுகளுக்குத் தங்கள் பிரதிரிதிகளை நியமித்திருக்கமாட்டார்கள்.

மற்றொரு விஷயத்தையும் நாம் கவனிக்கவேண்டும். இந்த மன்னர்கள் எந்த இடத்திலும் தாங்கள் வடநாட்டை வெற்றி கொண்டதாகக் கூறிக்கொள்ளவில்லை. எனினும், முதலாம் இராஜாதிராஜனுடைய 'திங்களேர் தரு' என்று ஆரம்பிக்கும் மெய்க்கீர்த்தியில் அவன்,

“ இளக்கமில்

வில்லவர் மீனவர் வேள்குலச் சளுக்கியர்  
வல்லவர் கொளசலர் வங்கணர் கொங்கணர்  
சிந்துரர் ஐயணர் சிங்களர் பங்களர்  
அந்திரர் முதலிய வரைசரிடு திறைகளும் ”

பெற்றுக்கொண்டான் என்ற செய்தி காணப்படுகிறது. அவன் தனியரசு செலுத்த ஆரம்பித்த காலத்திலிருந்தே மெய்க்கீர்த்தியில் இந்தச் செய்தி காணப்படுவதால், இவ்விடம் குறிக்கப்பெற்ற மன்னர்கள் யாவரும் இவன் தந்தையான இராஜேந்திர சோழன் ஆட்சிக் காலத்திலேயே வெற்றி கொள்ளப் பெற்றுச் சோழர்களுடைய ஆதிக்கியத்தை ஏற்றுக் கொண்டிருத்தல் வேண்டும்.

வித்தியாதரனும் மற்றவர்களுமாகச் சேர்ந்து கி. பி. 1019-ஆம் ஆண்டில் கன்யாகுப்ஜ சிங்காதனத்தில் அமர்த்திய திரலோசனபாலன் முஸ்லிம் படையெடுப்பினால் நாடிழந்து போய்விடவில்லை யென்றே தெரிகிறது. அதற்குப் பிறகும் அவன் அல்லஹாபாத் உட்பட்ட பிரதேசத்தை ஆண்டு வந்திருக்கிறான். இது அல்லஹாபாத் நகரத்துக்கு எதிராகக் கங்கையின் மறு கரையில் உள்ள ஜூனரி என்னுமிடத்தி

விருந்து கிடைத்துள்ள அவனுடைய சாசனத்திவிருந்து தெரியவருகிறது. (இந்தியன் ஆண்டிகுவரி, பதினெட்டாம் வால்பூம், 33-35 பக்கங்கள்.) கி.பி. 1027-ஆம் ஆண்டு கொண்ட அந்தச் சாசனம் அரசன் தக்தினையன் ஸங்கிராந்தி தினத்தில் கங்கையில் நீராடி ஒரு கிராமத்தைப் பிராமணர் சிலருக்குத் தானம் அளித்த செய்தியைக் கூறுகிறது. ஆயினும் சிறிது காலத்துக்குப் பிறகு இதே பிரதேசம் கலசூரி மன்னனான காங்கேயதேவனுடைய ஆளுகைக்கு உட்பட்டிருந்தது. கி. பி. 1038-ஆம் ஆண்டில் பொறிக்கப்பட்ட அவனுடைய சாசனம்கொண்ட பியாவன் மலை அந்நகரத்துக்கு ஐம்பது மைல் தொலைவில்தான் உள்ளது. (ஆர்க்கி. ஸர்வே ரிபோர்ட், இருபத்தோராம் வால்பூம், 112-13 பக்கங்கள்). கலசூரி வமிசத்துச் சாசனங்களிலே அம்மன்னன் பிரயாகையிலே புனிதமான வட விருகத்தின் அடியில் தன் வாசஸ்தலத்தை அமைத்துக் கொண்டான் என்று கூறப்பட்டுள்ளது. அவனுடைய மகனான லக்ஷ்மீ-கர்ணனுடைய கோஹர்வாச் செப்பேடுகளிலே காங்கேயன் கங்கரா பள்ளத்தாக்கில் உள்ள கீரா என்னும் இடத்து அரசனைச் சிறைப்படுத்தினான் என்று புகழப்பட்டுள்ளான். (எச்.ஸி. ராய் எழுதிய வட இந்தியாவின் ராஜ வமிச சரித்திரம், இரண்டாம் பாகம், 775 பக்கம்). [கீரா என்னும் வடமொழிச் சொல் கிளியைக் குறிக்கும். கீரா மன்னனைச் சிறைப்படுத்தினான் என்பதைச் சிலேடையாகக் கிளியைக் கூட்டிலே அடைத்தான் எனச் சாசனங்களில் மொழிவது சகஜம்.] அன்றி அவன் “பிரயாகையிலே தன்னுடைய மனைவிகள் (கிருஹினிகள்) நூறு பேர்களுடன் முக்தி அடைந்தான்” என்றும் தெரிகிறது. (எபி. இந்திகா, இரண்டாம் வால்பூம், பக்கம் 4, சுலோகம் 12).

கன்யாகுப்ஜப் பிரதேசத்தைக் காங்கேயன் அடைந்தது காலஞ்சர நகரத்தின்மீது முஸ்லிம்கள் படையெடுத்து வந்த தன் முடிவாகவும் விளைவாகவும் இருக்கலாம். கஜ்னி சுல்தான் மம்முதுக்கு எதிராக நின்ற ஹிந்துஸ்தானத்து மன்னர்களில் பிரதானமாக விளங்கிய சந்தெல்ல மன்னனான வித்தியாதரன் புகழ் அந்தப் படையெடுப்புக்குப் பிறகு ஒளி வீசவில்லை; மங்கிப்போய் விட்டதாகவே காண்கிறது. அந்தப் படையெடுப்பிலே வித்தியாதரன் முழுதும் தோற்று

விடவில்லை. ஆயினும், அது அவனுடைய வலிமையையும் செல்வாக்கையும் பெரிதும் பாதித்தே இருக்கும். அதற்குப் பிறகு சுமார் ஒரு நூறு வருஷங்களுக்குச் சந்தெல்லர்கள் மறுபடியும் தலைதாக்கவில்லை.

போஜராஜனும் கன்யாகுப்ஜத்தை ஆண்டு வந்தான் என்று கூறப்படுகிறது. கி. பி. 1104-ஆம் ஆண்டு கொண்ட தான், கன்னேசி நாட்டுக் காகடவால வமிசத்து அரசனான கோவிந்த சந்திரனுடைய பஸஹிச் செப்பேடுகளிலே பின் வரும் சுலோகங்கள் காணப்படுகின்றன.

யாதே ஸ்ரீபோஜ பூபே விவு(பு)த வர வதா  
நேத்ர ஸீமா திதித்வம்  
ஸ்ரீகர்ணணே கீர்த்தி சேஷம் கதவதி ச ந்ருபே  
க்ஷமாத்யயே ஜாயமானே  
பர்த்தாரம் யம் வ[த]ரித்ரீ த்ரிதிவ விபுநிபம்  
ப்ரீதி யோகாத் உபேதா  
த்ராதா விச்வாஸ பூர்வ்வம் ஸமபவதிஹ ஸ  
க்ஷமாப திஸ் சந்த்ரதேவே॥

த்விஷத் க்ஷிதிப்ருதஃ ஸர்வ்வான் விதாய விவசாந் வஸே  
கன்யாகுப்ஜே'கரோத் ராஜா ராஜதாநீம் அநிந்திதாம்॥

“போஜன், கர்ணன் ஆகியவர்கள் இறந்த பிறகு பூமி பலவித சங்கடங்களுக்கு உட்பட்டபோது காகடவால வமிசத்தைச் சேர்ந்த மஹியாலன் என்னும் அரசனுடைய மகனான சந்திர தேவன் பூமியை மீட்டு அரசனாகிக் கன்யாகுப்ஜத்தைத் தன் தலைநகராக்கிக் கொண்டான்” என்று அது தெரிவிக்கிறது. (இந்தியன் ஆண்டிகுவரி, பதினான்காம் வால்யூம், பக்கம் 103). மேருதுங்கரும் தம்முடைய பிரபந்த சிந்தாமணியில், போஜன் திக்குவிஜயத்துக்குக் கிளம்பியபோது, அதை யறிந்த கன்யாகுப்ஜ மன்னன் குனிந்து வணங்கினான் என்று கூறியிருப்பதும் (பக்கம் 44) இதனையே வலியுறுத்துகிறது.

தாரா நகரத்துப் போஜ சாலையில் உள்ள கற்களில் பொறிக்கப்பட்ட ஒரு நாடகத்தின் பகுதிகள் கிடைத் துள்ளன. அர்ஜுனவர்மன் என்னும் அரசனுடைய ஆசிரிய



ரான மதனன் எழுதிய அந் நாடகத்துக்குப் பாரிஜாதமஞ்சரீ அல்லது விஜயபுரீ என்று பெயர். அதிலே, “காங்கேயனைத் தோற்கடித்ததைப் போஜன் தன் மனோரதம் பூர்த்தியான வெற்றி விழாவாகக் கண்டான்” என்பது,

“தூர்ணணம் பூர்ணமனோரதஸ் சிரமபூத்  
காங்கேய பங்கோத்ஸவே”

எனக் காணப்படுகிறது. (எபி. இந்திகா, எட்டாம் வால்பூம், பக்கம் 101, சுலோகம் 3.) ஆரம்ப முதல் போஜன் கன்யா குப்ஜப் பிரதேசம் தனக்கு வேண்டுமென்று விரும்பினான் போலும். அந்நாளிலே உத்தராபதத்திற்கு (பின்னால் ஹிந்துஸ்தான் என்று பொதுவாக வழங்கப்பட்டு வந்த பகுதி) கன்யாகுப்ஜமே கேந்திர ஸ்தானமாகக் கருதப்பட்டு வந்தது. அதன் அரசனாக இருப்பவனுக்குச் சார்வபௌமப் பதவி அளிக்கப்பட்டது. அதன் பெருமைகளை அவன் அடைந்து அனுபவித்தான். அதனால் போஜன் அதைப் பெரிதும் விரும்பினான் போலும். ஆனால் முஸ்லிம்கள் திரும்பிச் சென்றவுடன் அந்தப் பிரதேசத்தைக் காங்கேயன் கைப்பற்றிக் கொண்டான். இது போஜனுக்குப் பொறுக்க வில்லை. அதைத் தான் கைப்பற்றித் தன்னுடைய ஆட்சியின் கீழ்க் கொணர்வதற்குப் போஜன் சமயம் பார்த்துக்கொண்டிருந்தான். அத்தகைய சந்தர்ப்பம் அவர்களுடைய வாழ்க்கையின் இறுதியிலேதான் கிட்டியது.

காங்கேயன் கி.பி. 1041-ஆம் ஆண்டில் இறந்துபோனான் என்று தெரிகிறது. (எபி. இந்திகா, இரண்டாம் வால்பூம், 297-310 பக்கங்கள்.) அவன் இறந்தது அவ்வாண்டு ஜனவரி மாதம் 22-ஆம் தேதியாகும் என்று டாக்டர் பிளீட் கணக்கிட்டுருக்கிறார். (ஷெ. பன்னிரண்டாம் வால்பூம், 206-ஆம் பக்கத்தின் கீழ்க்குறிப்பு). அவனுக்குப்பின் பட்ட மெய்திய கர்ணன் அல்லது லக்ஷ்மீ - கர்ணனுடைய சாசனங்களுள் காலத்தால் முற்பட்ட காசிச் செப்பேடுகள் கி. பி. 1042-ஆம் கொண்டவை. அதிலே இறந்த மன்னனுடைய ஸம்வத்ஸர ச்ராத்தம் அப்போது நடந்ததாகக் குறிக்கப்பட்டுள்ளது. சேதி மன்னனான காங்கேயன் பிரயாகை கேஷத்திரத்தில் தன் தேவிகள் தூறுபேர்களோடு முக்தியடைந்தான் என்று

சாசனங்களில் கூறப்பட்டிருக்கிறது. அவனுடைய நண்பனும் கூட்டாளியுமான மேலைச் சாளுக்கிய அரசன் சோமேச் வரன் சில வருஷங்களுக்குப் பிறகு துங்கபத்திரை நதியில் ஜல சமாதி கொண்டதைப்போலே இவனும் கங்கை நதியில் ஜல சமாதி அடைந்து உயிரைவிட்டான் போலும்.

சற்றேறக்குறைய இதே சமயம் கன்யாகுப்ஜப் பிரதேசம் போஜராஜனுடைய ஆளுகைக்கு வந்திருந்ததென்பதை மற்றோர் ஆதாரத்திலிருந்தும் அறியலாகும். பிரிஷ்டா பின்வருமாறு எழுதுகிறார்: ' ஹிஜ்ரி 435 (கி. பி. 1043)-ஆம் ஆண்டில் தில்லி அரசன் மற்றரசர்களோடு கூடிக்கொண்டு ஹன்ஸி, தானேசர், அவற்றுக்கு அடங்கிய மற்றப் பிரதேசங்கள் ஆகிய வற்றை மதாத் நியமித்து ஒப்படைத்திருந்த கவர்னரிடமிருந்து திரும்பவும் கைப்பற்றிக் கொண்டான். அங்கிருந்து ஹிந்துக்கள் புறப்பட்டு நக்ர கோட்டே என்னுமிடத்தை யடைந்து அதை நான்கு மாத காலம் முற்றுகையிட்டார்கள். கோட்டைக்குள் இருந்தவர்களுக்கு உணவுப் பொருள்கள் கிடைக்கவில்லை. கையிருப்பு செலவாகிவிட்டது. லாஹூரி விருந்து வரவேண்டியவை வரவில்லை. அதனால் அவர்கள் சரணாகதியடையவேண்டிய நிலைமை ஏற்பட்டுவிட்டது.' (' இந்தியாவில் முகம்மதிய ஆட்சி எழுந்த வரலாறு' என்ற பெயரில் பிரிக்ஸ் மொழி பெயர்த்து வெளியிட்ட தரீக்-ஈ-பிரிஷ்டா, முதல் பாகம், பக்கம் 118.) நாகர்கோட் என்பது இப்போது பஞ்சாபிலே ராவி, பியாஸ் ஆகிய இரு நதிகளுக்குமிடையில் கங்கரா ஜில்லாவின் பிரதான நகரான கோட்-கங்கரா என்பதாகும். மத்தியக் காலத்திலே சம்பா என்றும், திரிகர்த்தம் என்றும் வழங்கப்பெற்ற பிரதேசங்கள் அடங்கிய பகுதி அதுதான். கி. பி. 1047-ஆம் ஆண்டு கொண்டதான போஜராஜனுடைய திலக் வாடாச் செப்பேடுகள், அவனுடைய சேனாதிபதியான சுராதத்தியன் என்பான் ஸாஹவாஹனையும் மற்றவர்களையும் போரில் வென்று போஜராஜனுடைய ராஜ்யபூரீயை நிலைநிறுத்தினான் என்று கூறுகின்றன.

ஸாஹவாஹந ஸங்க்ராமே

அந்யேஷாமபி பூபுஜாம்

ஹத்வா யோதாம்(ந்)ஸ்திரம் லக்ஷ்மீம்

போஜதேவே சகார யுஃ

(1919-ஆம் ஆண்டில் பூநாகரத்தில் நடந்த(முதல்) கீழ்த்திசை ஆராய்ச்சியாளர் மகாநாட்டு நடவடிக்கைகளும் முடிவுகளும், பக்கம் 324). இவ்விடம் குறிக்கப்பட்ட ஸாஹவாஹனன் என்பான் சம்பா நாட்டில் அரசு செலுத்திய ஸாலவாஹன தேவனேயாவன் (இந்தியன் ஆண்டிகுவரி, பதினேழாம் வால்பூம், 8-9 பக்கங்கள்) என்று நிர்ணயித்திருக்கிறார்கள். அவன் ஸாஹில்லதேவன் என்றும் ஸாஹஸாங்கன் என்றும் குறிக்கப்பெறுவான். கீரா நாட்டுச் சேனை, தூர்கா நாட்டு மன்னன், துருஷ்கர்கள் ஆகியோர்களை அவன் வெற்றிகொண்டான் என்றும், குலாத மன்னன் அடிபணிந்து அளித்த காணிக்கையை ஏற்றுக்கொண்டான் என்றும், அவனுடைய தோழமையைத் திரிகர்த்த நாட்டு மன்னனும் விழைந்தான் என்றும் கூறப்படுகிறது. (டி. எஸ். கங்குலி எழுதியபரமார வம்ச சரித்திரம், பக்கம் 110).

கல்ஹணர் எழுதிய ராஜதரங்கினியிலிருந்து காஷ்மீர தேசத்துக்கும் போஜராஜனுக்கும் ஒருவகையில் தொடர்பு இருந்து வந்ததென்று தெரிகிறது. அந்நாளிலே காஷ்மீரத்தை அநந்தன் என்பான் ஆண்டுவந்தான். பத்மராஜன் என்ற வெளிநாட்டு வியாபாரி ஒருவன் அம்மன்னனுக்கு ஏராளமான பொன்னைக் கடனாகக் கொடுத்திருந்தான். அரசனுடைய முடியே ஒரு சமயம் கடனுக்கு அடைமானமாக இருந்ததாம். அந்த வியாபாரி மூலம் போஜராஜன் தினந்தோறும் காஷ்மீரத்துக் கபோடச்வரத்தில் உள்ள ஊற்றிலிருந்து ஒரு குடம் புனித நீரை மாவவ தேசத்துக்கு அனுப்ப ஏற்பாடு செய்தாலாம். அந்நாளில் போஜராஜனுக்குக் காஷ்மீரத்திலே ஓர் அளவு செல்வாக்கு இருந்ததென்பதையே இது குறிக்கும்.

இவற்றைக் கொண்டு கி. பி. 1040-41-ஆம் ஆண்டுக்கு அணித்ததாகப் போஜன் கன்யாகுப்ஜத்தைக் கைக்கொண்டிருத்தல்வேண்டும் என்று எண்ணுவது தவறுகாது.

இந்தச் சமயத்திலும் போஜனுக்குச் சோழ மன்னர்கள் உதவியாகச் சென்று போர்புரிந்திருக்கிறார்கள் என்றே தெரிகிறது. அவனுக்கு எதிரியான சேதிமன்னனுக்கும் வழக்கம் போல மேலைச் சாளுக்கிய அரசனுடைய உதவி கிட்டியது.

இராஜாதிராஜனுடைய மெய்க்கீர்த்தியில் மேலைச் சாளுக்கியர் களுடன் நடந்ததாகக் கூறப்படும் முதற் போர் இந்தக் காலத்திலேதான் நடந்திருக்கவேண்டும் என்பதை ஓர் அளவு குறிப்பாகத் தெரிவிக்கும் ஆதாரங்களும் உள்ளன. (க.அ. நீலகண்ட சாஸ்திரிகள் எழுதிய சோழர்கள், முதல் வால்பூம், 273-77 பக்கங்கள்; டாக்டர் என். வேங்கடரமணய்யா எழுதிய வேங்கீ நாட்டுக் கீழைச் சாளுக்கியர்கள், 230-31 பக்கங்கள்.) இராஜாதிராஜனுடைய தனியாட்சியின் ஆரம்பகாலமான கி. பி. 1044-க்கு முன்னதாக வடதிசையில் அவன் கொண்டனவாகக் குறிக் கப்பெறும் வெற்றிகளும், கன்யாகுப்ஜம் போன்ற நாடுகளை ஆள அவன் பிரதிநிதிகளை நியமித்ததும் இந்தப் படையெடுப்பின் விளைவுகளே போலும்.

இன்னும், இதே காலத்தில் கன்யாகுப்ஜத்து அரச பரம்பரையைச் சேர்ந்தவர்கள் சிலரும் தென்னாட்டில் இருந்திருக்கிறார்கள். இராஜாதிராஜனுடைய ஆட்சியின் ஆரம்ப காலச் சாசனங்கள் சிலவற்றில் பின்வருவது காணப்படுகிறது:

“இலங்கைக் கரைசையும் அலங்கல் வல்லவனையும்  
கன்னக் குச்சியர் காவலனையும் பொன்னணி  
முடிதலைத் தடிந்து.”

இதே சம்பவம் பிற்பட்ட ஆண்டுச் சாசனங்களில் விரிவாகக் கூறப்பட்டுள்ளது.

“ஒருதனித் தண்டாற் பொருகட விங்கையர்  
கோமான் விக்கிரம பாகுவின் மகுடமும்  
முன்றனக் குடைந்த தென்தமிழ் மண்டலம்  
முழுவது மிழந்து எழுகட லீழம்  
புக்கவிலங்கேச னுகிய விக்கிரம  
பாண்டியன் பருமணி மகுடமும் காண்டகு  
தன்ன வாக்கித்தன் கன்னக்குச் சியிலும்  
ஆர்கலி ஈழந் சீரிதென் றெண்ணி  
உளங்கொளந் நாடுதன் னுறவொடும் புகுந்து  
விளங்குமுடி கவித்த வீரசலா மேகன்  
போர்க்களத் தஞ்சித்தன் கார்க்களி றிழந்து  
கலவையுற் றோடக்.காதலி யொடுந்தன்

தவ்வையைப் பிடித்துத் தாயை மூக்கரிய  
ஆங்கவ மானம் நீங்குதற் காக  
மீட்டும் வந்து வாள்தொழில் புரிந்து  
வெங்களத் துலந்தவச் சிங்களத் தரைசன்  
பொன்னணி முடியுங் கன்னரன் வழிவந்  
துரைகொ ளீழத் தரைச னுகியசீர்  
வல்லவன் மகன ராஜன் மெல்லொளித்  
தடமணி முடியுங் கொண்டு ”

மெய்க்கீர்த்தியிலே கூறப்பட்டுள்ள இவ்வரலாறு இலங்கைச் சரித்திரமான மகாவமிசத்திலிருந்தும் ஊர்ஜிதம் பெறுகிறது. (சூளவமிசம், ஐம்பத்தாராம் அத்தியாயம்). முதலாம் இராஜேந்திர சோழன் தன்னுடைய ஆட்சியின் ஐந்தாம் ஆண்டிலே (கி.பி. 1017-ஆம் ஆண்டு) ஈழ மண்டலம் முழுவதையும் கைக்கொண்ட செய்தி அவனுடைய மெய்க்கீர்த்தியிலே காணப்படுகிறது. இலங்கை மன்னனான ஐந்தாம் மஹிந்தனைச் சிறைப்படுத்தி அவனைச் சோழ நாட்டுக்கு அனுப்பிவைத்தான். அவன் இங்கே பன்னிரண்டு ஆண்டுகள் இருந்து பின் இறந்தான். அப்பால், அவனுடைய மகனான கஸ்ஸபன் இலங்கையைச் சோழர்கள் ஆளுவதைப் பொறுமல் அவர்களுக்கு விரோதமாகக் கிளம்பி இலங்கையின் தென் கிழக்குப் பகுதியான ரோஹண நாட்டை, விக்கிரம பாஹு என்ற அபிஷேக நாமத்துடன், அரசாளத் துவங்கினான். இது சுமார் கி.பி. 1029-ஆம் ஆண்டில் நிகழ்ந்ததாகும். அவன் திரும்பவும் சோழர்களோடு போர் நடத்துவதற்கான ஏற்பாடுகளைப் பெருத்த அளவில் செய்து கொண்டிருக்கையில் திடீரென்று தன்னுடைய ஆட்சியின் பன்னிரண்டாம் ஆண்டில் (சுமார் கி.பி.1040)நோய்வாய்ப்பட்டு இறந்துபோனான். அரசாங்கத்தில் அதிகாரியாக இருந்த கீத்தி என்பான் எட்டு நாள் ஆண்டபிறகு, ‘பலவானான மஹாலானகீத்தி’ என்பான் அரசனானான். மூன்றாம் ஆண்டிலே அவன் சோழர்களுடன் நிகழ்த்திய போரில் உயிர் இழந்தான். மஹாலானகீத்தியின் ஒரே மகனான விக்கம பண்டு பயத்தினால் நாட்டைத் துறந்து துளுதேசத்திலே சிறிது காலம் வசித்திருந்தான். தந்தைக்கு நேரிட்ட கதியைக் கேள்வியுற்ற அவன் ரோஹணத்துக்குத்

திரும்பி வந்து அரசியலை மேற்கொண்டான். சிறிது காலத்துக்கெல்லாம் ஜகதீபாலனுடன் நிகழ்த்திய போரில் அவன் கொல்லப்பட்டான். ஜகதீபாலன் மகாவமிசத்திலே 'ராமனுடைய வழியில் தோன்றிய வீரம் மிகுந்த ராஜகுமாரன்' என்றும், 'அயொஜ்ஜ (அயோத்யா) நகரத்திலிருந்து வந்த அரசனுடைய மகன்' என்றும் குறிக்கப்பட்டிருக்கிறான். "அவனையும் சோழர்கள் போரிலே கொன்றுபோட்டு அவனுடைய மஹேசியையும் மகளையும் சிறைப்பிடித்து விலையுயர்ந்த பொருள்களுடன் சோழ நாட்டுக்கு அனுப்பிவைத்தார்கள். (ஜகதீபாலனுடைய மனைவியும் மகள் லீலாவதியும் பின்னால் தாங்கள் இருந்த சிறையிலிருந்து தப்பிச் சோழ நாட்டை விட்டு இலங்கைக்குத் திரும்பவும் ஓடிவிட்டார்கள். லீலாவதி அங்கே முதலாம் விஜயபாஹு மன்னனை மணந்து அவனுடைய மஹேசி, அதாவது பட்டத்தரசியாக விளங்கியிருக்கிறாள்). பண்டு மன்னனுடைய மகனான பராக்கம வேந்தன் இரண்டு ஆண்டுகள் அரசு புரிந்தான். சோழர்கள் அவனோடும் போரிட்டுச் சண்டையில் அவனைக் கொன்றார்கள்." அதற்குப் பிறகு லோகன் அல்லது லோகேச்வரன் எனப் பெறும் சேனைத் தலைவன் அரசைக் கைக்கொண்டான். அவன் ஆறு வருஷ காலம் நிர்வாகம் நடத்தினான். அப்பால், 'கேஸதாது'க்களின் தலைவனான மற்றோர் அதிகாரி, கஸ்ஸபன் என்ற பெயரையுடையவன், அதிகாரத்தை மேற்கொண்டான். அவன் ஆதிக்கியம் அதிக நாள் நீடிக்கவில்லை; ஆறு மாத காலமே ஓடியது. விக்கிரமபாஹுவின் பெயரான கித்தி என்னும் அரசிளங்குமரன், பதினேழு வயது உடைய வனேயாயினும், இலங்கைத் தீவைச் சோழர்களுடைய ஆதிக்கியத்தினின்றும் விடுவித்துப் பிதிரார்ஜித நாட்டை அடைவதற்கு உரிய முயற்சிகளை மேற்கொண்டான். விஜயபாஹு என்ற அபிஷேக நாமத்துடன் அவன் ரோஹண நாட்டுக்கு அரசனாக முடிசூட்டப் பெற்றான். இது நடந்தது கி. பி. 1055-ஆம் ஆண்டு என்று கணக்கிட்டிருக்கிறார்கள்.

விக்கிரம பாஹுவுக்கும் அவன் பெயரான விஜய பாஹுவுக்கும் இடைப்பட்ட காலத்தில் இலங்கையை ஆண்ட ஷர்களை யெல்லாம் மஹாவமிசம் இலங்கை அரசுக்கு உரிமை

யில்லாமல் அதைக் கைப்பற்றியவர்கள் என்று தெளிவாகக் கூறுகிறது. சோழ மெய்க்கீர்த்தியில் குறிக்கப்பெறும் விக்கிரம பாண்டியன் மஹாவமிசத்தில் குறிக்கப்பெற்ற விக்கிரம பண்டுவே ஆகவேண்டும். மஹாவமிசத்தில் அவன் மஹாலானகித்தியின் ஒரே மகன் என்றும், தந்தை யிறந்த காலத்தில் அவன் பயத்தினால் நாட்டைத் துறந்து துளு தேசத்தில் வாழ்ந்து வந்தான் என்றும் காணப்படுகிறது. சோழ மெய்க்கீர்த்தியிலோ அவன்,

“முன்றனக் குடைந்த தென்றமிழ் மண்டல  
முழுவது மிழந்து எழுகடல் ஈழம்  
புக்கவிலங் கேச னாகிய விக்கிரம  
பாண்டியன்”

என்று குறிக்கப்படுவதிலிருந்து அவன் முதலில் பாண்டிய நாடு முழுவதையும் ஆண்டு வந்தான் என்பதும், அப்பால் அவன் இராஜாதிராஜனால் தென் தமிழ் நாட்டிலிருந்து துரத்தப்பட்டு இலங்கையை அடைந்து அங்கே அரசரிமையை ஏற்றான் என்பதும் தெரியவரும். இதிலிருந்து அவன் பாண்டிய ராஜகுமாரனே யாவன் என்பது பெறப்படும். துளு தேசம் என்று மகாவமிசத்தில் குறிக்கப்பட்டிருப்பது மேலைக் கடற்கரையோரமாக ஆளுபர்களுடைய ஆட்சிக்கு உட்பட்டிருந்த துளுநாடே ஆகும்போலும். பாண்டிய மன்னர்களுக்கு இலங்கை அரச வமிசத்தோடு நெருங்கிய மணவினை உறவு இருந்ததுபோல, ஆளுபர்களோடும் உறவு இருந்து வந்தது. சிங்கள மன்னர்கள் தந்தைக்குப் பின் மகன் என்ற வழியையே பின்பற்றி நாட்டை ஆண்டுவந்திருக்கிறார்கள். எனினும், மாமனுக்குப் பின் மருமகன் என்ற தாய் வழித் தாயமுறையையும் பின்பற்றி இருக்கிறார்கள். அந்த வழியிலேயும் சில மன்னர்கள் அரசரிமை ஏற்றிருக்கிறார்கள். அதேபோல ஆளுபர்களும் சில சமயங்களில் தாய் வழித் தாயமுறையை அனுசரித்திருக்கிறார்கள். ஆளுப அரசர்களில் பலர் ‘பாண்டியன்’ என்ற பட்டப்பெயரைத் தரித்திருக்கிறார்கள். இதனால் விக்கிரம பாண்டியன் மேலைக் கடற்கரையில் உள்ள துளு நாட்டிலே தான் தங்கியிருந்தான் என்று கொள்வது தவறுகாது. (தமிழ் நாட்டுப் பாண்டியர்களுக்கும்

துளு நாட்டுப் பாண்டியர்களுக்கும் உள்ள தொடர்பைப் பற்றிப் பின்னால் விவரித்திருக்கிறோம்.)

சோழ மெய்க்கீர்த்தியில் குறிக்கப்பெற்ற வீரசலாமேகனும் இலங்கைச் சரித்திரத்தில் காணும் ஜகதீபாலனும் ஒருவரே யாவர். இவர்கள் இருவருக்கும் சொந்தமான ஊர் வெவ்வேறுகக் கூறப்பட்டிருப்பதால் அவர்கள் வேறு வேறுனவர்களாகவே இருக்கவேண்டும் என்று கருதப்படுவது உண்டு. சோழ சாசனங்களில் கன்னகூச்சி அவனுக்கு உரியதென்று கூறப்பட்டுள்ளது. அதனால் அவன் கன்யாகுப்ஜ அரச பரம்பரையைச் சேர்ந்தவனென்று ஆகும். மகாவமிசத்தில் அவன் ராமபிரானுடைய வமிசத்தைச் சேர்ந்தவன் என்றும், அயோத்தியிலிருந்து வந்தவன் என்றும் கூறப்பட்டிருக்கிறது. ஆயினும், பின்னால் அவர்களுக்கு நேரிட்டதாகக் கூறப்பெறும் பரிபவம் இரண்டிலும் ஒன்று போலவே உள்ளது. சோழ மன்னர்கள் இராஜகேசரி வர்மன், பரகேசரிவர்மன் ஆகிய விருதுகளை மாறிமாறித் தரித்து வந்ததுபோல இலங்கை மன்னர்கள் சலாமேகன் அல்லது சிலாமேக வண்ணன் (சாசனங்களில் பொதுவாக இது சலமேவன் என்றே காணப்படும்), சங்கபோதி (சாசனங்களில் ஸிரி ஸங்க்போ என்றே காணப்படும்) ஆகிய இரண்டு விருதுகளையும் மாறிமாறித் தரித்து வந்திருக்கிறார்கள். (சூளவமிசம்: வில்லியம் கீசர் என்பாருடைய மொழிபெயர்ப்பு, முதல் பாகம், பக்கம் 185, கீழ்க்குறிப்பு 5). அதனால், சோழ மெய்க்கீர்த்தியில் காணப்பெறும் சலாமேகன் என்பதை அரசனுடைய உண்மைப் பெயராக நாம் கொள்ளமுடியாது. அவனுடைய அரச விருதே அது. அதனால் ஜகதீபாலன் என்பதை அவன் உண்மைப் பெயராகவும் சலாமேகன் என்பதை அவனுடைய பட்டப் பெயராகவும் கொள்வதில் தவறு ஒன்றுமில்லை. ஜகதீபாலன் ரோஹண நாட்டுச் சிங்காதனத்தில் கி. பி. 1045-ஆம் ஆண்டு அரசனாக அமர்ந்தான் என்று இலங்கைச் சரித்திர ஆசிரியர்கள் கருதுகிறார்கள். (ஜி. ஸி. மெண்டிஸ் எழுதிய இலங்கையின் பழைய சரித்திரம், 1940-இல் வெளியான நான்காம் பதிப்பு, பக்கங்கள் 153-54). சோழ சாசனங்களிலே வீரசலாமேகனுடைய முடிவைபற்றிக் கி. பி. 1046-ஆம் ஆண்டின் கடைசியிலேதான் (டி.ஸம்பர் 3-ஆம்



தேதி) காணப்படுகிறது. (தே. இ. சாசனங்கள், மூன்றாம் வால்பூம், பக்கம் 53).

மற்றொரு விஷயத்தையும் நாம் கவனிக்கவேண்டும். அந் நாளிலே கன்யாகுப்ஜ நாட்டை ஆண்டுவந்த பிரதிஹார வமிசத்து மன்னர்களும் தங்களை ரகுவின் வம்சத்தவர்கள் என்று கூறிக் கொண்டிருக்கிறார்கள். கஜ்னி மம்முதுக்குப் பணிந்துபோன ராஜ்யபாலனுடைய பாட்டனான மஹீபாலனை அவனுடைய ஆஸ்தான கவியான இராஜசேகரர் தம்முடைய பாலபாரதத்தில் 'தேந (மஹிபாலேந) ச ரகுவம்ச முக்தாமணிநா' (பக்கம் 2) என்று குறிப்பிடுகிறார். அந்த மஹீபாலனுடைய தந்தையான மஹேந்திரபாலனை அதே நூலில், 'தேவோ யஸ்ய மஹேந்திரபால ந்ருபதி: சிஷ்யோ ரகுராமணி:' (௨௨) என்று குறிப்பிடுகிறார். அன்றி அதே கவி வித்தசாலபஞ்சிகா என்னும் மற்றொரு நூலில் 'ரகுசுல திலகோ மஹேந்திரபால:' (I. 6) என்று அவனைப் புகழ்கிறார். இம் மஹேந்திரபாலனுடைய தந்தையான (கன்னேசி அரசன்) முதலாம் போஜராஜனுடைய குவாலியர்ச் சாசனத்தில் அவர்கள் ராமபிரானுடைய தம்பியான லக்ஷ்மணனுடைய வழி வந்தவர்கள் என்று இவ் விஷயம் இன்னும் நெளிவாகக் காணப்படுகிறது. "இந்திரனுடைய செருக்கை அழித்த மேகநாதனோடு நடத்திய போரில் எதிரிகளை ஒடுக்கி, வாயிற்காப்போன் (ப்ரதீஹாரன்) ஆக விளங்கியவனும் அவனுடைய (அதாவது இராமனுடைய) தம்பியுமான ஸௌமித்ரீ (அதாவது ஸுமித்திரையின் மகன் லக்ஷ்மணன்)" அவர்களுடைய குல முதல்வன் என்று கூறுகிறது அச் சாசனம். (எபி. இந்திகா, பதினெட்டாம் வால்பூம், பக்கம் 106, சுலோகம் 3). ஆகவே இரண்டு இடங்களிலும் இரு வேறு பெயர்களால் குறிக்கப்பட்டிருப்பினும் அவன் ஒருவனே யாவன் என்று கொள்வதில் தவறில்லை.<sup>1</sup>

1. முஸ்லிம் படையெடுப்பின்போது கன்யாகுப்ஜத்தைத் துறந்து அரசன் பாரி என்னும் நகரத்துக்கு ஓடிவிட்டான். அதுவே பின்னால் தலைநகராக விளங்கியது. அப்பால் அதையும் துறந்து வெளியேற நேர்ந்துவிட்டது. அதற்குப் பிறகு எந்த நகரம் தலைநகராக விளங்கியது என்பதை நிச்சயமாகக் கூறமுடியாது. அவர்கள் அயோத்திக்குச் சென்றிருத்தலும் கூடும். அயோத்தியிலிருந்து அந்நாளிலே ஆண்டுவந்த அரசவமிசத்தைப் பற்றி எதுவும் தெரியவில்லை.

மெய்க்கீர்த்தியில் காணும் கடைசிப் பெயரான ஸ்ரீவல்லபன் மதனராஜன், அதாவது கன்னரன் வழிவந்த வல்லபனான மதனராஜன் என்பான், மஹாவமிசத்தில் காணும் பண்டு அரசன் மகனான பராக்கிரமனே யாவான் என்று டாக்டர் ஹூல்ஷ் முடிவு செய்திருக்கிறார். (ராயல் ஏஷ்யாடிக் ஸோஸைட்டி ஜர்னல், 1913-ஆம் ஆண்டு, 519-21 பக்கங்கள்.) ஒருகால் அவன் பெண் வழியாக அரசரிமை பெற்று வந்த துளு பாண்டிய இராஜ பரம்பரையைச் சேர்ந்தவனாக இருத்தல்கூடும். மஹாவமிசம் அவ்விதம் குறிக்கச் சோழ சாசனங்களில் அவன் தகப்பன் வழியைக் கொண்டவனாகக் கன்னரன் வழிவந்தவன் என்று குறிப்பிட்டிருத்தல் கூடும்.

மேலே கூறியதிலிருந்து வட நாட்டிலே முஸ்லிம் படை யெடுப்பின் பயனாக அவ்விடத்தின் நிலை சீர்குலைந்திருந்த சமயம் கன்யாகுப்துஜத்திலிருந்து அரச வமிசத்தைச் சேர்ந்த ராஜ குமாரர்கள் சிலர் சோழ நாட்டுக்கு வந்திருந்தார்கள் என்பதும் அவ்விதம் வந்தவர்களுக்குச் சோழ மன்னர்கள் புகலிடம் அளித்திருந்தார்கள் என்பதும் தெளிவாகும்.

1. இராஜாதிராஜனுக்குப் பிறகு சோழ சிங்களனம் ஏறிய இரண்டாம் இராஜேந்திரனுடைய 'திருமாத புவியேனும்' என்று தொடங்கும் மெய்க்கீர்த்தியில் அவன் இலங்கை யரசனான வீரசலாமேகன் என்பானுடன் போரிட்டான் என்பது பின்வருமாறு கூறப்பட்டுள்ளது :

“தென் றிசைவயிற்  
பேர்ப்படை நடாத்திக் கார்க்கட லிங்கையில்  
விறற்படைக் கலிங்கர்மன் வீரசலா மேகனைக்  
கடற்களிற் ரெடுபடக் கதிர்முடி கடிவித்  
திலங்கையர்க் கிறைவன் மாளு பரணன்  
காதல ரிருவரைக் களத்திடைப் பிடித்து”

இந்தச் செய்தி முதன் முதலாக அவனுடைய ஆட்சியின் நான்காம் ஆண்டிலே (கி.பி. 1055-ஆம் ஆண்டு) தான் காணப்படுகிறது. பிற்பட்ட ஆண்டுகளில் வரும் மெய்க்கீர்த்தியோ (உதாரணமாக, ஒன்பதாம் ஆண்டு கொண்ட 1895-ஆம் ஆண்டு 87 நெ. சாசனம்) வீரசலாமேகன் பெயரை மட்டுமே கொடுக்கிறது. இவன் 'விறற்படைக் கலிங்கர்மன்' என்று குறிக்கப்பட்டிருப்பினும், இராஜாதிராஜனுடைய மெய்க்கீர்த்தியில் காணும் கன்னகுச்சியர் காவ லணினின்றும் இவனை வேறுக எண்ணவேண்டிய அவசியம் இல்லையென்று

ஐக்கிபாலனும் அவர்களிலே ஒருவன் போலும். அவனுக்கு ஏதேனும் பதவி அளிக்க வேண்டுமென்பதற்காகச் சோழர்கள் அவனை இலங்கைக்குத் தங்கள் பிரதிரிதியாக அனுப்பி வைத்திருக்கலாம்.

இவ்விதம் போலும் இராஜாதிராஜனும் சேர்ந்து வட நாட்டில் கொண்ட வெற்றிகளை நீண்ட காலம் அனுபவிக்க முடியவில்லை. காங்கேயனுக்குப் பிறகு சேதி நாட்டு அரசனாகக் கி.பி. 1041-ஆம் ஆண்டில் சிங்காதனம் ஏறிய அவன் மகன் கர்ணன் சும்மா இருக்கவில்லை. தங்களைத் தோற்கடித்துத் தந்தையின் மரணத்துக்குக் காரணமாக இருந்த போலன்மீது வஞ்சம் தீர்த்துக்கொள்ள விரும்பினான். பெரு முயற்சியால் அவன் தாங்கள் இழந்த நாடுகளைத் திரும்பவும் அடைந்ததோடு போலனையும் தாக்கி அவன் செருக்கை ஒழித்தான். இதிலே அவனுக்கு மேலைச் சாளுக்கிய மன்னனான ஆஹவமல்ல சோமேச்வரனும், அணஹிலபாடக நகரத்துச் சௌலுக்கிய வேந்தனான பீமனும் துணையாக நின்றார்கள். ஆஹவமல்லன் மாளவ தேசத்திலே பரமார வமிசத்து மன்னர்களின் தலைநகரான 'தாரா நகரத்தைத் தாக்கிப் போலனை அவ்விடத்திலிருந்து ஓடச் செய்தான்' என்று விக்கிரமாங்க தேவ சரிதம் கூறுகிறது. (முதல் சர்க்கம், 91-96 சுலோகங்கள்; இன்னும் இந்தி. ஆண்டிசுவரி, ஐந்தாம் வால்பூம், 319 பக்கம்). சோமேச்வரன் அந் நகரத்தைக் கைப்பற்றிச் சூரையாடிக் கொள்ளையடித்தான். இந்தச் செய்தி அவனுடைய சாசனங்களிலும் காணப்படுகிறது. 'பூர்வ அரசர்களால் அணுக முடியாதபடிச்

கருதி இருவரையும் ஒருவராகவே கொள்ளுவர்சிலர். வீரசலாமேகன் என்பது இலங்கை மன்னர்களுடைய பட்டப்பெயர்களுள் ஒன்று என்பதையும் அதை அரசனுடைய பெயராகக் கொள்ளமுடியாதென்பதையும் நாம் மேலே காட்டியுள்ளோம். மெய்க்கீர்த்திகளும் ஒருவனைக் கன்யாகுப்ஜத்து அரசுக்கு உரியவென்றும், மற்றவனைக் கலிங்க தேசத்து அரசன் என்றும் வேறுபடுத்தியே கூறுகின்றன. ஆகவே அவர்களை வேறு வேறுபாடுகளாகவே கொள்ளவேண்டும். இரண்டாம் இராஜேந்திர சோழனுடைய மெய்க்கீர்த்தியில் குறிக்கப்பட்ட வீரசலாமேகன் கி.பி. 1055-ஆம் ஆண்டு இலங்கைச் சிங்காதனம் ஏறிய முதலாம் விஜயபாஹுவாசுக்கு முன்னதாக அரசு செலுத்தியவனாக இருத்தல்வேண்டும் போலும்.

தம்பிரமாக நின்ற' தாரா நகரத்தையும் அவன் தாக்கி அடிப் படுத்தினான் என்று ஒரு சாசனம் (மைசூர் ஆர்க்கியலாஜிகல் இலாகாவின் 1928-ஆம் ஆண்டு அறிக்கை, 72 பக்கம்) தெரிவிக்கிறது. கி.பி. 1058-ஆம் ஆண்டு கொண்டதாக ஹைதராபாத் ராஜ்யத்தில் நாகை என்னுமிடத்திலிருந்து கிடைத்துள்ள அவனுடைய சாசனம் ஒன்று மன்னன் தாராநகரத்தையும் உஜ்ஜயினியையும் செந்தழல் கொளுத்தியதாகக் கூறுகிறது. (நாகாய்லிருந்து கிடைத்த சாசனங்கள், ஹைதராபாத் ஆர்க்கியலாஜிகல் ஸீரிஸ், 8 நெ). அவன்கீழ் அதிகாரியாக இருந்த மாதுவன் என்பான் இந்தப் படையெடுப்பிலே ஈடுபட்டிருந்தான் என்றும் தாரா நகரத்தைக் கைவிடப் போஜனைத் துரத்தியவன் அவனே என்றும் அது கூறுகிறது. கி.பி. 1060-ஆம் ஆண்டு கொண்ட மற்றொரு சாசனம் (மைசூர் ஆர்க்கியலாஜிகல் இலாகாவின் 1929-ஆம் ஆண்டு அறிக்கை, 68-69 பக்கங்கள்) மன்னனை 'நர்மதையின் இரு கரைகளிலும் விளையாடிய ராஜஹம்ஸம்' என்றும், 'மாளவ தேசத்து மக்களுக்குத் தாமகேது போன்றவன்' என்றும், 'மண்டேவ (மாண்டு என்று இப்போது வழங்கப்பெறும்) கோட்டையைக் கைப்பற்றியவன்' என்றும், தாரா நகரத்தில் அவன் கௌரவிக்கப்பட்டு வந்தான் என்றும் கூறுகிறது. பிரபந்த சிந்தாமணி (பக்கங்கள் 36-37) பின்வருமாறு கூறுகிறது: டாஹல வேந்தன் (அதாவது சேதி நாட்டு அரசனான) கர்ணன் நூற்றுமுப்பத்தாறு மன்னர்களையும் தன்னுடன் சேர்த்துக்கொண்டு போஜராஜன் மீது படையெடுத்து வந்தான். "அதே சமயம் மாளவத்தைப் பின்புறத்திலிருந்து தாக்கும்படி அவன் பீமனையும் அழைத்தான்; அவ்விதம் செய்தால் போஜனுடைய நாட்டின் ஒரு பாதியை அவனுக்கு அளித்துவிடுவதாகவும் ஆசை காட்டினான். இவ்விதம் இருவராலும் தாக்குண்ட போஜராஜன் மந்திரத்தால் கட்டுண்ட பாம்பு தன் விஷத்தை இழப்பதுபோலத் தன்னுடைய கீர்த்தியை இழந்தான். அப்பால் திடீரென்று அவனுக்கு ஏதோ ஒரு தேக உபாதி கண்டு போஜன் உயிர்துறந்தான். அதன்மீது கர்ணன் கோட்டையைப் பிளந்து உள்ளே புகுந்து போஜனுடைய செல்வம் அனைத்தையும் கைக்கொண்டான்." மாளவத்திலே வெற்றி கிட்டிய பிறகு, கைப்பற்றிய நாட்டைத் தங்களுக்குள் கூறுபோட்டுக் கொள்வதிலே

கர்ணனுக்கும் பீமனுக்கு மிடையே தகராறு ஏற்பட்டது என்று மேருதுங்கர் கூறுகிறார். (பிரபந்த சிந்தாமணி, பக்கங்கள் 74-75). இதையே ஹேமசந்திரரும் தம்முடைய துவயாச்சரயத்தில் குறிப்பிடுகிறார் (ஒன்பதாம் சர்க்கம், சுலோகம் 57, பக்கம் 692).

“போஜன் இந்திரனுடைய தோழனாகச் சென்றதும் அவனுடைய ராஜ்யம் (குல்யாகுலம்-பிரமுகர்கள் நிரம்பிய) வெள்ளத்திலே மிதந்து, அதன் அரசனும் அவ்வெள்ளத்திலே மூழ்கியபோது, போஜனுடைய (பந்து) உறவினனான உதயாதித்தியன் தோன்றி அரசனான். கர்நாடர்களால் கைக்கொள்ளப்பட்டு, பல அரசர்களால் துன்புறுத்தப்பட்ட பூமியைச் சமுத்திரம்போல விளங்கிய அதிலிருந்து அம்மன்னன் வராஹம்போல் தோன்றி மீட்டான்” என்று விஷ்ணு வராஹ அவதாரம் எடுத்துப் பூமியை அசுரர்களிடமிருந்து மீட்டதற்கு ஒப்பிட்டுக் கூறுகிறது, மாளவ தேசத்துப் பரமார மன்னர்களின் புகழைக்கூறுவதாகக் கி.பி. 1104-ஆம் ஆண்டுகொண்ட நாகபூர்ப் பிரசஸ்தி (எபி. இந்திகா, இரண்டாம் வால்பூம், 192 பக்கம், சுலோகம் 32). ஒரு சமயம் போஜன் தாரா நகரத்தின் நகர்ப்புறத்திலே இருந்த தன் குலதேவதையை வழிப்படுவதற்காகப் போனபோது அவனைக் கூர்ஜ்ஜர வீரர்கள் சிறைப் பிடிக்கும் தறுவாயில் இருந்தார்கள் என்றும், அவ்விதம் ஆபத்தில் சிக்கிக்கொண்ட அவன் மயிரிழையில் உயிர் தப்பினான் என்றும் ஒரு சம்பவத்தை மேருதுங்கர் பிரபந்த சிந்தாமணியில் (பக்கங்கள் 73-75) கூறுகிறார்.

போஜராஜன் எதிரிகளைத் துரத்தித் தன்னாட்டை மீட்டுக் கொள்வதற்காகப் படை திரட்டி ஏற்பாடுகளைச் செய்துவந்த சமயம் திடீரென்று நோய்வாய்ப்பட்டு இறந்து போனான் என்று கூறப்படுகிறது. இது கி.பி. 1050-51-ஆம் ஆண்டு நிகழ்ந்ததாகச் சோழ சாசனங்களிலிருந்து தெரிகிறது. ‘திங்களேர் தரு’ என்று தொடங்கும் முதலாம் இராஜாதி ராஜனுடைய மெய்க்கீர்த்தியிலே பின்வரும் பகுதி காணப்படுகிறது.

“கூர்ச்சரன் உப்பலன் கொய்மலர்ப் பசுந்தலைத்  
தார்தலைபன் தடிந்துமுன் கொண்டு தகைவன்

தப்பைமுன் தைப்ப அப்பகை செகுத்து  
உப்பலன் வழியிற் தப்பியபல் லரைசர்  
ஆங்கது மீட்கமாட் டாதுதன் பூங்கழல்  
சரணெனப் புகுந்த வரணவர்க் கருளித்  
தடமுடி மீட்டுக் கொடுத்துத் ,  
தடமுடிக் கிடங்கொடுத் திருந்த தகைவன்  
தப்பையைப் பறித்துக் கொண்டு போந்தபின் ”

இது முதல் முதலாக அவனுடைய ஆட்சியின் முப்பத்து மூன்றாம் ஆண்டுச் சாசனங்களிலேதான் (கி. பி. 1050-51) காணப்படுகிறது. மெய்க்கீர்த்தியிலே குறிக்கப் பெற்ற கூர்ஜ்ஜர உப்பலன் என்பான் போஜனுடைய பெரியப்பனான இரண்டாம் வாக்கபதி முஞ்சனான உத்பலனே யாவன்.

இதிலிருந்து போஜனுக்கு எதிராக மேலைச் சாளுக்கிய வேந்தன் சோமேச்வரன், கலசூரி மன்னன் கர்ணன், அணஹிலபாடக நகரத்துச் சௌலுக்கிய அரசன் பீமன் ஆகியவர்கள் ஒன்று சேர்ந்து நடத்திய போரில் தஞ்சைச் சோழ மன்னனும் போஜனுக்கு உதவியாக நின்றிருந்தான் என்று தெரிகிறது. சண்டையின் போக்கும் மற்ற விவரங்களும் இப்போது நமக்குக் கிடைக்கவில்லை. எதிரிகளின் கூட்டுப் படைக்குமுன் நிற்கமுடியாமல் போஜன் தோல்வியுற்று நாட்டையும் இழந்தான் ; அதைத் திரும்பக் கைப்பற்ற அவன் படை திரட்டிய காலத்தில் திடீரென்று நோய்வாய்ப்பட்டு இறந்தான் என்ற அளவுதான் தெரிகிறது. எதிரிகளின் கை மிகவும் ஓங்கியிருந்தபடியால் மாளவ சிங்காதனத்துக்கு உரியவர்கள் சோழர்களிடம் அடைக்கலம் புகுந்தனர் போலும். சோழர்களுடைய உதவியோடு அவர்கள் மறுபடியும் படைதிரட்டித் தங்கள் பிதிரார்ஜிதத்தை அடையும் வரையில் அவர்கள் சோழர்களின் ஆதரவிலே தங்கியிருந்தார்கள் போலும்.

இந்தக் காலத்து மாளவ தேச சரித்திரமும் தெளிவாக இல்லை. போஜனுக்குப் பின் அவனுடைய மகன் ஜயஸிம் ஹன் மாளவ தேசத்தை ஆண்டு வந்திருக்கிறான். அவன் கி. பி. 1055-ஆம் ஆண்டில் அரசனாக இருந்தான் என்று அவ்

வாண்டில் அளிக்கப்பெற்ற மாந்தாதாச் செப்பேடுகளினின்றுத் தெரிகிறது. கி.பி. 1059-ஆம் ஆண்டுகொண்ட பன்ஹேராச் சாசனத்திலிருந்தும் அப்போது ஜயஸிம்ஹன் அரசனாக இருந்தது விளங்குகிறது. பரமார வமிசத்து வேறொரு கிளையைச் சேர்ந்த மண்டலிகன் என்பான் வாகடப் பகுதியை ஜயஸிம்ஹன் கீழ்ச் சிற்றரசனாக ஆண்டுவந்தான். அவன் போரிலே கன்ஹன் என்னும் சேனாதிபதியை யானை குதிரைகளோடு பிடித்துத் தன் பேரரசன் ஜயஸிம்ஹனிடம் ஒப்படைத்ததாக அந்தச் சாசனம் கூறுகிறது. கன்ஹன் யார் என்பது விளங்கவில்லை. ஆயினும் ஜயஸிம்ஹனுடைய ஆட்சி அமைதியாக நடைபெறவில்லை யென்றும், எதிரிகள் இருந்தனர் என்றும் அந்தச் சாசனத்திலிருந்து தெரியவருகிறது.

ஆஹவமல்ல சோமேச்வரனுடைய ஆட்சிக் காலத்தில் அவன் மகன் விக்கிரமாதித்தன், 'புகலிடம் வேண்டித் தன்னை யண்டின மாவை அரசனுக்குத் தன் உதவி அளித்து அவனுடைய நாட்டை அவன் அடையச் செய்தான்' என்பதைப் பில்ஹணர் விக்கிரமாங்கதேவ சரிதத்தில்,

ஸ மாலவேந்தரம் சரணம் ப்ரவிஷ்டம்  
அகண்டகே ஸ்தாபயிதி ஸம் ராஜ்யே |  
கர்யா ப்ரதாநச் சலதஃ க்ஷதீசஃ  
ஸர்வஸ்வ தானம் பஹுவோ 'ஸ்ய சக்ருஃ ||

(மூன்றாம் சர்க்கம், 67 சுலோகம்)

எனக் கூறுகிறார். சாளுக்கிய மன்னனால் உதவியளிக்கப் பெற்ற மாவை அரசனுடைய பெயர் தெரியவில்லை. மாவை தேசத்துப் பரமாரர்களும் மேலைச்சாளுக்கியர்களும் பரம்பரை விரோதிகள் என்பதையும், ஆரம்பம் முதலே தலைமுறை தலை முறையாக அவர்கள் சதா தங்களுக்குள் போரிட்டு வந்திருக்கிறார்கள் என்பதையும் நாம் அறிவோம். அவ்விதம் இருக்க, குடும்ப கௌரவம், பழைய விரோதம் ஆகியவற்றை அறவே புறக்கணித்துத் தங்கள் குல விரோதியான சோமேச்வரனுடைய உதவியையே நாடிய மாவை ராஜகுமாரன், சோழர்களுடைய உதவியை நாடி அவர்களால் சிங்காதனத்தில் அமர்த்தப்பெற்றவனாக இருக்கமுடியாது. அவன் சோழர்

களுக்கு விரோதமாக, அவர்களால் முடிசூட்டப் பெற்றவனுக்குப் போட்டியாகச் சாளுக்கியர்களுடைய உதவியால் அரசைக் கைப்பற்ற முயன்றவன் போலும்.

கி.பி.1011-ஆம் ஆண்டு கொண்ட போஜனுடைய ஸோடாஸாச் செப்பேட்டிலிருந்து அந்தத் தானம் வழங்கிய மஹாராஜபுத்ர வத்ஸராஜன் என்பான் மோஹுடவாஸக எழுதாற்றைம்பதுப் பகுதியை ஆண்டு வந்ததாகத் தெரிகிறது. (பாரதீய வித்யா, ஆங்கிலப் பத்திரிகை, ஆறாம் வால்பூம், பிற்சேர்க்கை, பக்கங்கள் 37-40). அவன் போஜனுடைய மகனேபோலும்.<sup>1</sup> ஆயினும் அவன் போஜனுக்குப் பின் சிங்காதனம் ஏறியவனாகக் கருதப்படும் ஜயஸிம்ஹன் அல்லது வேறு ஒருவன் என்பது தெரியாது. நாகபூர்ப் பிரசஸ்தியில் போஜராஜனுக்குப் பிறகு “நாட்டிலே ராஜகுலத்தைச் சேர்ந்த பலர் வெள்ளம் போல் திரண்டு அரசுப் பதவியை மூழ்கடித்து விட்டனர்” என்று காணப்படுவதனின்றும், சிங்காதனத்துக்கு உரியவர்களாகப் பலர் போட்டியிட்டு வந்தனர் என்பதை யறியலாம். (எபி. இந்திகா, இரண்டாம் வால்பூம், பக்கம் 192). அவ்விதம் போட்டியிட்டவர்களுள் ஒருவனுக்குச் சோழர்கள் உதவிபுரிந்தனர் என்பதையும் நாம் மேலே கண்டோம்.

நாகபூர்ப் பிரசஸ்தியில் ஜயஸிம்ஹன் பெயரே காணப்பெறவில்லை. சீர்குலைந்திருந்த நிலைமையின் முடிவில் உதயாதித்தன் தோன்றி அரசை நிலை நிறுத்தினான் என்று பொதுவாகக் கூறப்பட்டுள்ளது. இந்த உதயாதித்தியனே சோழர்களுடைய உதவியைப் பெற்றவன் என்றும் (ஜர்னல் ஆப் ஓரியண்டல் ரிஸர்ச், பதினாறாம் வால்பூம், 147-48 பக்கங்கள்), அவனுக்குப் போட்டியாக இருந்த ஜயஸிம்ஹனே மேலைச் சாளுக்கியர்களால் உதவப்பெற்றவன் என்றும் (பரமார வமிச சரித்திரம், 123-ஆம் பக்கம்) கருதப்படுகிறது. ஆனால் நிலையைக் கவனித்தால் இதற்கு நேர்மாறாகத் தோன்றுகிறது.

1. மஹாராஜபுத்ர என்னும் சொல்லை அரசாங்க அதிகாரியின் பட்டப் பெயராகவும் கொள்வர் சிலர். (இந்தியன் ஆண்டிதலரி, பதினெட்டாம் வால்பூம், 212-ஆம் பக்கம், கீழ்க்குறிப்பு 3).



உதயாதித்தன் கி.பி. 1030-81-ஆம் ஆண்டு ஆட்சிபுரிந்து வந்தான் என்பது அவனுடைய உதயபூர்க் கல்வெட்டாலும் (இந்தியன் ஆண்டிசுவரி, இருபதாம் வால்பூம், பக்கம் 83) கி.பி. 1086-87-ஆம் ஆண்டிலே அரசுபுரிந்திருக்கிறான் என்பது ஜலரபடன் கல்வெட்டாலும் (வங்காளத்து ஏஷியாடிக் ஸோஸைட்டியின் ஜர்னலும் புரோஸ்டிங்க்ஸும், பத்தாம் வால்பூம், 241-ஆம் பக்கம் முதல்) தெளிவாகத் தெரிகிறது. அன்றி, குவாலியரில் உள்ள உதயபூரிலிருந்து கிடைத்துள்ளதும் பிரதேச மொழியில் உள்ளதுமான சமீப காலத்து (கி.பி. 1560-ஆம் ஆண்டு கொண்ட) சாசனம் ஒன்று உதயாதித்தியன் (விக்கிரம) ஸம்வத் 1116, சகாப்தம் 981 (அதாவது கி.பி. 1059-60) கொண்ட ஆண்டில் அங்கே சிவபெருமானுக்கு ஒரு கோயில் எழுப்பினான் என்ற செய்தியைத் தெரிவிக்கிறது. (வங்காளத்து ஏஷியாடிக் ஸோஸைட்டி ஜர்னல், ஒன்பதாம் வால்பூம், 545-50 பக்கங்கள்.) இவற்றைக் கவனிக்கும்போது மாவை சிங்காதனத்திலிருந்து ஜயஸிம்ஹனைத் துரத்தியவன் உதயாதித்தியனே என்பது போதரும்.

மேலேச் சாளுக்கிய மன்னன் தன்னிடம் அடைக்கலம் புகுந்த மாவை தேசத்து ராஜகுமாரனுக்கு அந்த நாட்டு அரசுப் பதவியை அளித்ததோடு மட்டுமல்லாமல், கன்யாதானம் என்னும் சாக்கைக்கொண்டு எல்லாப் பரிசுகளையும் வழங்கினான் என்று பில்ஹணர் கூறுகிறார். இதனால் அந்த மாவை இராஜகுமாரன் சாளுக்கிய இராஜகுமாரி ஒருத்தியை மணந்து கொண்டான் என்பது தெரியவரும். கூர்ஜ்ஜர தேசத்துக் கர்ண பரம்பரைச் சரித்திரமான ராஸ் மாலாவிலும் உதயாதித்தியனைப் பற்றிக் கூறப்பட்டிருப்பது இதனை வலியுறுத்துவதாகக் காணப்படுகிறது. ராஸ் மாலா என்பது சென்ற நூற்றாண்டின் மத்தியில் ஸர் கின்லக் போர்ப்ஸ் என்பவரால் அவருக்குக் கிடைத்த சில ஹைனப் பிரபந்தங்களையும், கவி தல்பத்ராம் என்பார் நாடோடியாக வழங்கிய பாடல்களைத் திரட்டித் தொகுத்ததையும் கொண்டு எழுதப்பட்டது. உதயாதித்தியனைப் பற்றி அது பின்வருமாறு கூறுகிறது :

“உதயாதித்தியனுக்கு இரண்டு மனைவிகள் இருந்தனர். ஒருத்தி ஸோலங்கி குலத்தைச் சேர்ந்தவள். மற்றொருத்தி

வாகேல வமிசத்தில் வந்தவள். ஸோலங்கி குலத்து அரசியிடம் அவனுக்கு ஜக்தேவ் (ஜகத்தேவன்) என்ற பிள்ளை பிறந்தான். வாகேல வமிசத்து அரசியிடம் ரிந்துவால் (ரணதவளன்) என்ற பிள்ளை பிறந்தான். வாகேல வமிசத்து அரசியே உதயாதித்தியனுக்குப் பிரியமானவள். அதனால் அவளுடைய பேச்சைக்கேட்டு அவன் தன் மகன் ரிந்துவாலை இளவரசனாக முடிசூட்டினான். மாற்றூந் தாயின் கொடுமையால் ஜக்தேவ் செல்வத்தை இழந்து ஏழையானான். ஆகவே அவன் ஜீவனத்துக்கு வழிதேடி மாளவத்தை விட்டு வெளியேறி, குஜராத் மன்னனான ஸித்ராஜனுடைய சேனையில் சேவகம் ஏற்றான்." (போர்ப்ஸ் எழுதிய ராஸ் மாலா, 1924-ஆம் ஆண்டில், எச். ஜி. ராவின்ஸன் வெளியிட்ட பதிப்பு, முதல் வால்யூம், 117-ஆம் பக்கம் முதல்). ஜகத்தேவன் குந்தள நாட்டு மன்னனான பரமர்த்தி (பெருமானடிகள் என்ற தமிழ்ச் சொல்லின் திரிபே இது; மேலைச் சாளுக்கிய அரசனான ஆறாம் விக்கிரமாதித்தியனுடைய விருதுகள் ஒன்று) என்பானுடைய சேனையில் உத்தியோகம் வகித்து வந்தான் என்றும், கூர்ஜ்ஜர நாட்டுச் சௌலுக்கிய வேந்தனான ஸித்தராஜ-ஜயஸிம்ஹன் அவனைப் பெரிதும் கௌரவித்துப் போற்றி வந்தான் என்றும் மேருதுங்கர் கூறுகிறார். (பிரபந்த சிந்தாமணி, 186 பக்கம்; இன்னும் சோமேச்வரனுடைய கீர்த்தி கௌமுதி, இரண்டாம் சர்க்கம், 99 சுலோகம் பார்க்க). சாளுக்கியர் என்பதே சௌலுக்கியர் என மாறியது. சௌலுக்கியர்களே பின்னால் ஸோலங்கிகள் எனப் பெயர்பெற்றவர். அதனால் ராஸ் மாலாவில் உதயாதித்தியன் ஸோலங்கி குலத்து அரசியை மணந்தான் என்று கூறப்பட்டிருப்பது, அவன் பில்ஹணர் தெரிவித்திருக்கிறபடி மேலைச் சாளுக்கிய இராஜகுமாரி ஒருத்தியை மணந்ததையே குறிக்கிறது போலும். அவ்விதமானால் அவர்களுக்குப் பிறந்த ஜகத்தேவன் தன் தாய் மாமனான விக்கிரமாதித்தியனுடைய ராஜ சபையில் இடம் பெற்றதும், அவனுடைய போர்ப் படையில் உத்தியோகம் வகித்துப் போர்புரிந்ததும் இயற்கையே. அன்றி ஜகத்தேவன் நீண்ட காலம் ஆறாம் விக்கிரமாதித்தியன்கீழ்க் கொள்ளிப்பாக்கை (இப்போது ஹைதராபாத் ராஜ்யத்தில் உள்ள கூல்பாக்)ப் பிரதேசத்தை ஆண்டு வந்தான்

என்பதைத் தெலுங்கானாவில் கிடைக்கும் சாசனங்கள் தெரிவிக்கின்றன.

தவிர, உதயாதித்தியன் பரமார வமிசத்தின் இளைய பரம்பரையைச் சேர்ந்தவன்; வாக்பதி, போஜராஜன் ஆகியோர்கள் வந்த மூத்த பரம்பரையைச் சேர்ந்தவனல்லன். அவனுடைய பரம்பரையைப் பற்றிய விவரங்கள் பில்ஸாவில் உள்ள உதயபூரில் கிடைக்கும் ஒரு சாசனத்திலிருந்து நமக்குக் கிடைத்துள்ளன. (வங்காளத்து எஷ்யாடிக் ஸோஸைட்டியின் ஜர்னல், ஒன்பதாம் வால்டூம், 547-ஆம் பக்கம்). அதிலே அவன் பாவர அதாவது பரமார குலத்து ஸௌரவீரன் (சூரவீரன்) என்பானுடைய கொள்பெயரன் என்றும் கோந்தலன் என்பானுடைய பெயரன் என்றும் குறிக்கப்படுகிறான். அவன் தந்தையின் பெயர் க்யாதா (ஜ்ஞாதா) என்பதாகும். அவன் முதலில் மாளவதேசத்தின் கீழைப் பகுதியில் அரசு புரிந்துவந்தானாம். அதற்குப்பிறகு அவனுடைய முன்னோர்கள் அரசு செலுத்தி வந்த நடுப்பகுதியை அடைந்தானாம். ('மாலவ மத்ய தேசம் கத்வா ஸ்தாநம் ப்ரஸித்தி' என்று அந்தச் சாசனம் கூறுகிறது). ஆகவே அவன் சோழ மெய்க்கீர்த்தியில் அவர்களால் உதவப்பெற்று மாளவ சிங்காதனத்தில் அமர்த்தப்பட்டவன் என்று குறிக்கப்பட்ட உத்பலன் வழி வந்தவர்களுள் ஒருவனாக இருக்கமுடியாது.

இவ்விதம் சோழர்களால் அரசுரிமை அடைந்த ராஜகுமாரன் ஒருவனையல்லாமல் வேறு சில மாளவ இராஜகுமாரர்களும் சோழர்களின் கீழ் அதிகாரிகளாகப் பதவியேற்று அமர்ந்திருக்கிறார்கள் என்று தெரிகிறது. இதேபோல வேறு சிலர் மேலைச் சாளுக்கியர்களின் கீழும் அதிகாரிகளாக இருந்து வந்திருக்கிறார்கள். திருவளர் திரள்புயத்து என்று தொடங்கும் வீரராஜேந்திரனுடைய மெய்க்கீர்த்தியில் பின்வரும் பகுதி காணப்படுகிறது :

“வீரசிங் காதனம் பார்தொழ வேறி  
எழிறர வுலக முழுதுடை யாளொடும்  
விசையமணி மகுட மேய்ந்து எழில்கொள்  
தத்துமாப் புரவிப் பொத்தப்பி வேந்தனை

வாரணை<sup>1</sup> வன்கழற் கேரளன் றன்னைத்  
தார்சன நாதன் தம்பியைப் போர்க்களத்  
தலங்கல்கூழ் பசுந்தலை யரிந்து "

இது முதல் முதலாக அவனுடைய ஆட்சியின் மூன்றாம் ஆண்டுக்கு எதிராம் ஆண்டான நான்காம் ஆண்டு கொண்ட கருவூர்ப் பசுபதிச்வரர் கோயில் கல்வெட்டிலே தான் காணப்படுகிறது. (தே. இ. சாசனங்கள், மூன்றாம் வால்பூம், 20 நெ.) ஜனநாதன் என்ற பெயர் சில பாடங்களிலே 'தாரா ஜனநாதன்' அதாவது தாரா நகரத்துப் பரமார குலத்தைச் சேர்ந்த ஜனநாதன் என்று காணப்படுகிறது. வீரராஜேந்திரன் தன்னுடைய ஆட்சியின் ஐந்தாம் ஆண்டிலே வேங்கியின்மீது இரண்டாம் முறையாகப் படையெடுத்துச் சென்றான். அப்போது விஜயவாடைக் கடுத்த பேராறு (கிருஷ்ண வின்) கரையில் நிகழ்ந்த பெரும் போரில் அவன் ஜனநாதன், ராஜமய்யன் முதலியோர் நடத்தி வந்த மேலைச் சாளுக்கியப் படையைத் தோற்கடித்து அவர்களைக் காட்டுக்கு ஓடச்செய்தான். இந்தச் செய்தியும் அதே மெய்க்கிர்த்தியில் பின்வருமாறு காணப்படுகிறது:

“எல்லையங்

கடுத்தவத் தானை எழில் விசய வாதையோ  
டடுத்த பேராற்றில் வந்து தடுத்த  
சனநா தனையுந் தண்டநா யகனும்  
இனமார் கடக்களிற் றிராசமய் யனையும்  
திப்பர சனையு முதலாக வுடைய  
வப்பெருஞ் சேனையை அடவியிற் பாய்ச்சி”

இரண்டு இடங்களிலும் குறிக்கப்பெற்ற ஜனநாதன் ஒருவனே போலும். அவ்விதமானால் ஜனநாதன், அவன் தம்பி

1. 'வாரணை' என்னும் பாடம் கொண்டு இந்தப் பகுதி, 'பெரிய கழல் களைப்பூண்ட கேரள அரசனான வாரணை வென்றான்' என்று மொழி பெயர்க்கப்பட்டுள்ளது. 'வாரணை' என்பதே பாடம். ஆகவே 'வார் அணைந்த பெரிய கழல்' என்றே பொருள்படும். வாரன் என்ற பெயருள்ள அரசன் யாரும் இல்லை.

ஆகிய இருவரும் மாளவ நாட்டுப் பரமார குலத்து இராஜ குமாரர்களே யாவர். அவர்கள் மேலைச் சாளுக்கியர்களோடு சேர்ந்துகொண்டு சோழர்களுக்கு விரோதமாகப் போர் புரிந்தார்கள் என்பது தெளிவாகும். ஆயினும், ஜனநாதன் என்ற பெயர் முதலாம் இராஜராஜ சோழனுடைய விருது களுள் ஒன்றாகும். பின்னால் வந்த மன்னர்கள் சிலரும் அதை விருதாகச் சூட்டிக் கொண்டிருந்தார்கள் என்று தெரிகிறது. அதனால் அந்தப் பெயரைக் கவனித்தால் அதைத் தரித்திருந் தவன் அதைச் சோழர்களிடமிருந்தே பெற்றிருக்க வேண்டும் என்பது தெளிவாகும். அதனால் அவன் முதலில் சோழர் களின் கீழ் அதிகாரியாகக் கிருஷ்ண நதிக்கரைப் பிரதேசத் தில் இருந்துவந்தான் என்றும், பின்னால் அந்தப் பகுதியை மேலைச் சாளுக்கியர்கள் கைக்கொண்டவுடனே அவனும் அவர்களுக்கு அடங்கியவனாகச் சேவகம் பார்த்துவந்தான் என்றும், அதனாலேயே தனக்கு முன்னர் எஜமானராக இருந்த சோழர்களோடு அவன் போர் நிகழ்த்த வேண்டி யிருந்ததென்றும் கொள்ளலாம்.

பேரரசனான மேலைச் சாளுக்கிய மன்னன் ஆஹவமல்ல சோமேச்வரன், அவன் மகன் பெருவீரன் விக்கிரமாதித்தி யன் ஆகியோர்களுடைய முயற்சியால் அவர்களுடைய வலிமை யும் செல்வாக்கும் பெருகி வந்தன. அவற்றால் விரிந்து பரந்த சோழ ஸாம்ராஜ்யத்துக்கு நெருக்கடி தோன்றி அங்கங்கே தொல்லைகள் கிளம்பின. இவ்விரு ராஜ்யங்களுக் கும் இடையில் ஏற்பட்ட போட்டி தக்திணத்தோடு நின்று விடவில்லை. இன்னும் வடக்கேயும் பரவியது. மாளவ தேசத்துச் சிங்காதனத்துக்குப் போட்டி அரசர்களை நியமித்து அவரவர்க்கு அரசை அளிக்கமுற்பட்ட அதே நாடகம் சக்கரக் கோட்டப் பகுதியிலும் நடைபெற்றதாகத் தெரிகிறது.

இப்போது மத்தியப் பிரதேசம் என வழங்கப்பெறும் ராஜ்யத்தில் முன்னாள் பஸ்தர் ஸம்ஸ்தானப் பகுதியான சக்கரக் கோட்டத்தைச் சிந்தகர் எனப்பெறும் நாக வமிச மன்னர்கள் ஆண்டு வந்தனர் என்பதை முன்னரே குறிப் பிட்டிருக்கிறோம். அவர்கள் அனந்தப்பூர், பெல்லாரி, ராய்ச் சூர் ஆகிய ஜில்லாக்களின் பகுதிகள் அடங்கிய ஸிந்தவாடிப்

பிரதேசத்தை ஆண்டு வந்த ஸிந்தர்கள் வகுப்பைச் சேர்ந்த வர்களே. சிந்தக-நாக வமிச அரசர்களுடைய சாசனங்களிலே கிடைப்பவற்றுள் காலத்தால் முற்பட்டது பஸ்தர் ஸம்ஸ்தானத் தலைநகரான ஜகதால்பூருக்குப் பத்து மைல் தூரத்தில் உள்ள எர்ரகாட் என்னுமிடத்திலிருந்து கிடைப்பதாகும். கி.பி. 1023-ஆம் ஆண்டுக்குச் சரியான சகாப்தம் 945 கொண்ட அந்தச் சாசனம் பூர்த்தியாக இல்லை. அரசன் பெயரும் சிதைந்து காணப்படுகிறது. அதிலே 'திபூஷண' என்ற பகுதியே வாசிக்க முடிகிறது. அதை 'நிருபதி பூஷண' அல்லது 'ஹிதிபூஷண' என்று பூர்த்தி செய்யலாம். (தே. இ. சாசனங்கள், (மூலம் மட்டும்), பத்தாம் வால்பூம், 643 நெ; இன்னும் ஹிராலால் தொகுத்த மத்திய மாகாணங்களிலும் பீராரிலும் உள்ள சாசனங்களின் பட்டியல் (இரண்டாம் பதிப்பு) நெ. 285.) இந்தச் சாசனத்தின் காலத்தைக் கொண்டு, சிந்தக-நாகர்கள், கி.பி. 1023-ஆம் ஆண்டுக்குச் சிறிது முன்னதாக நடைபெற்ற இராஜேந்திர சோழனுடைய கங்கா விஜயத்தின் போது அவனுடைய படையோடு பஸ்தர்ப் பகுதிக்கு வந்து தங்கியவர்களாகவே இருக்கவேண்டும் என்று கருதப்படுகிறது. (குவார்டர்லி ஜர்னல் ஆப் தி மிதிக் ஸோஸைட்டி, நாற்பத்து நான்காம் வால்பூம், பக்கம் 2, டாக்டர் திரேஷ் சந்திர சர்க்கார் எழுதிய கட்டுரை). அதே பகுதியில் நாகர்களுக்கு அடங்கியவர்களாகத் தெலுங்குச் சோழரின் ஒரு கிளையினரும் காணப்படுகிறார்கள். அந்நாளிலே அந்தப் பகுதிக்குத் தலைநகராக விளங்கிப் பாரஸுலுரு (இப்போது பார்ஸுலர் என்று வழங்கப் பெறுவது) என்னுமிடத்திலிருந்து கிடைத்த கி. பி. 1060-ஆம் ஆண்டு கொண்ட சாசனம் ஒன்றிலிருந்து அப்போது தாராவர்ஷன் என்று மறுபெயரைப் பெற்றிருந்த மஹாராஜா ஜகதேகபூஷணன் என்ற சிந்தக-நாக அரசன் அந்நாட்டை ஆண்டு வந்தான் என்று தெரிகிறது. அப்போது அவனுடைய சிற்றரசனும் அம்மகாம் என்னும் ஊரின் அதிபதியுமான தெலுங்குச் சோட மஹாமண்டலேச்வரன் சந்திராதித்திய மஹாராஜா என்பான் பாரஸுலுருவில் தான் தோண்டிய குளக்கரையில் சிவனுக்கு ஒரு கோயில் எழுப்பிய செய்தியைத் தெரிவிக்கிறது அந்தச் சாசனம். (ஹிராலால் தொகுத்த ஷேர் சாசனப் பட்டியல், நெ 269).

‘திருமன்னி விளங்கும்’ என்று தொடங்கும் முதற் குலோத்துங்க சோழனுடைய மெய்க்கீர்த்தியிலே பின்வருவது காணப்படுகிறது :

“கேளலர்

வஞ்சனை கடந்து வயிரா கரத்துக்  
குஞ்சரக் குழாம்பல வாரி யெஞ்சலில்  
சக்கரக் கோட்டத்துத் தாரா வரசனைத்  
திக்கு நிகழத் திறைகொண் டருளி ”

இதிலிருந்து அவன் சக்கரக் கோட்டத்து அரசனான தாரா வர்ஷனை வெற்றிகொண்ட செய்தி தெரியவரும். இந்நிகழ்ச்சி அவன் அரசனாக முடிசூட்டப் பெறுவதற்கு முன், அதாவது அவனுடைய இளங்கோப் பருவத்தில், நிகழ்ந்ததென்பது அதே அரசனுடைய ‘புகழ்சூழ்ந்த புணரி’ என்று தொடங்கும் மெய்க்கீர்த்தியில்,

“விளங்குசய மகளை யிளங்கோப் பருவத்துச்  
சக்கரக் கோட்டத்து விக்ரமத் தொழிலாற்  
புதுமணம் புணர்ந்து மதவரை யீட்டம்  
வயிரா கரத்து வாரி அயிர்முனைக்  
கொந்தள வரசர் தந்தள மிரிய  
வாளுறை கழித்துத் தோள்வலி காட்டிப்  
போர்ப்பரி நடாத்திக் கீர்த்தியை நிறுத்தி  
வடதிசை வாகை சூடி ”

எனக் காணப்படுவதிலிருந்து தெளிவாகும். இவ்விதம் குலோத்துங்கனால் வெற்றி கொள்ளப்பட்ட தாராவர்ஷனும், சிந்தக-நாக மஹாராஜனான ஜகதேகபூஷண தாராவர்ஷனும் ஒருவனே போலும். சில வருஷங்களுக்குள்ளாகவே, அதாவது கி.பி. 1065-ஆம் ஆண்டில், அந்தப் பிரதேசம் அவ் வமிசத்தைச் சேர்ந்த மதுராந்தகன் என்பவனுடைய ஆட்சியில் இருக்கக் காணப்பெறுகிறது. (மதுராந்தகனுடைய ராஜாபுரச் செப்பேடுகள், எபி. இந்திகா, ஒன்பதாம் வால்பூம், 174 பக்கம் முதல்). ஆயினும் மறுபடியும் வெகு சீக்கிரம் அதே பிரதேசம் தாராவர்ஷ ஜகதேகபூஷணனுடைய மகன் சோமேச்வரனுடைய ஆளுகைக்கு மாறி யிருக்கிறது. இந்தச்

சோமேச்வரனுடைய சாசனங்கள் பல கிடைத்துள்ளன. கி. பி. 1069-ஆம் ஆண்டு கொண்டதாகக் குருஸ்பால் என்னு மிடத்திலிருந்து கிடைத்ததே அவனுடைய சாசனங்களில் காலத்தால் முற்பட்டது. (எபி. இந்திகா, பத்தாம் வால்பூம், பக்கம் 31.) அதே இடத்திலிருந்து கிடைக்கும் அவனுடைய மற்றொரு கல்வெட்டில், அவன் சக்கரக்கோட்டத்து அரசுக்கு உரிமை பெற்றவன் என்றும், பலம் பொருந்திய மதுராந்த கனைக் கொண்டு வெற்றிகொண்டவன் என்றும் குறிக்கப் பெற்றிருக்கிறான் (ஹெ. பக்கம் 25). அவன் வெற்றிகொண்ட மதுராந்தகனும், ராஜாபுரச் செப்பேடுகளை அளித்த மதுராந் தகனும் ஒருவனே போலும். இவ்விதம் குலோத்துங்க சோழன் வெற்றிகொண்ட தாராவர்ஷன் அரசாண்டதாகக் காணும் கி. பி. 1060-ஆம் ஆண்டுக்கும், அவன் மகன் சோமேச்வரன் அரசுபுரிந்ததாகக் காணும் கி. பி. 1069-ஆண் டுக்கும் இடைப்பட்ட காலத்தில், கி. பி. 1065-ஆம் ஆண்டில் மதுராந்தகன் என்பான் ஒருவன் அந்த நாட்டை ஆட்சி புரிந்திருக்கிறான். அவனைக் கொண்டு வெற்றிகொண்ட தாலேயே சோமேச்வரன் தன் பிஜிரார்ஜிதமான நாட்டை அடையவேண்டி யிருந்தது. இவ்விதம் சக்கரக் கோட்டப் பிரதேச அரசுக்குப் போட்டியிட்ட சிந்தக நாகர்களான மதுராந்தகன், சோமேச்வரன் ஆகியோருடைய பெயர்களி லிருந்து மதுராந்தகனைச் சோழர்களுடைய உதவியைப் பெற்று அவர்களுக்கு அடங்கியவனாகவும், சோமேச்வரனை அதேபோல மேலைச் சாளுக்கியர்களுடைய உதவிபெற்றவ னாகவும் கொள்ளலாம்.

இவ்விதம் சோழர்களும், சாளுக்கியர்களும் தக்திணத் திலே கடுமையாகப் போட்டியிட்டு வந்த சமயத்திலே சாளுக் கியர்களுக்கு முன்னாலில் துணைவனாக நின்ற கலசூரி வேந்த னான கர்ணன் வடக்கே தன்னுடைய நிலைமையை ஸ்திரப் படுத்திக் கொள்வதில் முனைந்திருந்தான். அதில் அவன் ஓர் அளவு வெற்றியும் கண்டான். அவனுடைய சாசனங்கள் கிடைக்கும்டங்கனையும் அவன் தரித்துக்கொண்ட திரிகலிங் காதிபதி (ஹெ. இரண்டாம் வால்பூம், 297-310 பக்கங்கள்) என்னும் விருதையும் கொண்டு, “அவன் ஆட்சி மேற்கே பனாஸ், மஹி ஆகிய நதிகளின் உற்பத்தி ஸ்தானங்களி



வீருந்து கிழக்கே ஹூக்ளி சங்கமம் வரையிலும், வடக்கே கங்கை - யமுனைப் பள்ளத்தாக்கிலிருந்து தெற்கே மஹாநதி, வைன்கங்கா, வர்தா, தப்தி நதிகளின் மேல் பகுதி வரையிலும்" பரந்திருந்ததென்று கொள்ளலாம். (எச். வி. ராய் எழுதிய வட இந்தியாவின் ராஜ வமிச சரித்திரம், இரண்டாம் வால்பூம், பக்கம் 779). அவன் காசி கேஷத்திரத்திலே கர்ண மேரு என்ற பெயருடன் மேரு எனப்படும் வகையிலே ஒரு கோயிலை எழுப்பி யிருக்கிறான். (மேரு எனப்படுவது நான்கு வாசல்களையும், வித விதமான பலகணிகளையும் கொண்டு பன்னிரண்டு அடுக்குகளுடன் ஆறு பட்டையாக அமைந்துள்ள கோயிற் கட்டட வகை என்று பிரஹதஸ்ம்ஹிதை தெரிவிக்கிறது. கர்ணனுடைய தகப்பனான காங்கேயனும் காசியிலே மேரு வகையில் ஒரு கோயில் எழுப்பியுள்ளான். அதனின்றும் வேறுபடுத்திக் காட்டவே இதற்குத் தன் பெயரால் கர்ணமேரு என்று பெயரிட்டான் போலும். எபி. இந்திகா, இரண்டாம் வால்பூம், பக்கம் 4, சுலோகம் 14). இன்னும் அவனுடைய கொள்பெயரான ஜயஸிம்ஹனுடைய சாசனத்தில், சோழ, குங்க, ஹூண, கௌட, கூர்ஜ்ஜர, கீர தேசத்து மன்னர்கள் கர்ணனுடைய தயவுக்குக் காத்திருந்தார்கள் என்ற செய்தி காணப்படுகிறது. (இந்தியன் ஆண்டிகுவரி, பதினெட்டாம் வால்பூம், பக்கங்கள் 215-17). அதே போல அவனுடைய பெயரான கயா-கர்ணனுடைய மஹிஷி அல்ஹணதேவியின் பேராகட் சாசனத்தில், "ஒப்புவமையில்லாத புகழையுடைய இம் மன்னன் (லக்ஷ்மீ-கர்ணன்) தன் பராக்கிரமம் முழுவதையும் காண்பித்தபோது, பாண்டியன் சண்டையைத் துறந்தான்; முரளன் தன் அகம் பாவத்தை ஒழித்தான்; குங்கன் நல்ல மார்க்கத்தில் செல்ல ஆரம்பித்தான்; கலிங்கனோடு வங்கன் நடுங்கினான்; கூண்டுக்கிளிபோலக் கீரன் தன் நாட்டிலே தங்கினான்; ஹூணன் தன்னுடைய உல்லாஸத்தைத் துறந்தான்" என்று கூறப்பட்டுள்ளது. (எபி. இந்திகா, இரண்டாம் வால்பூம், பக்கம் 11.) முரளர் என்பார் வட கொங்கணத்தில் உள்ள முரள என்னும் ஆற்றங்கரைப் பிரதேசத்திலே வாழும் மக்கள் என்பர். (டாக்டர் என். வேங்கடரமணய்யா எழுதிய லேமூலவாடாச் சாஸ்திரிகள், பக்கம் 67). குங்கர் என்பாரைக் கொங்கு

நரீட்டார்கள் என்றே கொள்வர். (எச். ஸி. ராய், எழுதிய வட இந்திய ராஜ வமிச சரித்திரம், இரண்டாம் வால்யூம், பக்கம் 778). இவர்களோடு சோழ பாண்டியர்களுடைய பெயர்களும் காணப்படுவதிலிருந்து லக்ஷ்மீ - கர்ணன் தென்னாட்டிற்கும் வந்து போர்புரிந்திருக்கிறான் என்றே கொள்வர். மேலைச் சாளுக்கியர்களுடன் சேர்ந்துகொண்டு அவன் சோழர்களோடு நடத்திய போர்களின் விளைவுகளே இப் புகழ்ச்சிபோலும். ஆயினும் ஒன்று மட்டில் நிச்சயமாகத் தெரிகிறது. கர்ணன் வடக்கிலே தன்னுடைய பிடிப்பை இறுக்கிக் கொண்டான். கன்யாகுப்ஜமும் அவனுடைய ஆளுகைக்குள் வந்தது. இது கன்யாகுப்ஜத்துக் காஹடவால அரசனான கோவிந்த சந்திரனுடைய பஸஹிச் செப்பேடுகளிலிருந்து தெளிவாகிறது. அதிலே, அவனுடைய வமிசத்தவர்கள் அரசை ஏற்பதற்கு முன் போஜன், கர்ணன் ஆகியோர் கன்யாகுப்ஜத்தை ஆண்டு வந்தனர் என்று கூறப்பட்டுள்ளது.

எனினும் சோழர்கள் தங்களுக்கு வடக்கே செல்வாக்குக்குறைவு நேரிட்டதைப் பார்த்துக்கொண்டு சுமமா இருந்திருக்கமாட்டார்கள். தங்களுடைய பழைய நிலையை மீண்டும் அடைவதற்கு நிச்சயம் பெரிதும் முயன்றிருப்பர். 'வீரமே துணையாகவும்' என்று தொடங்கும் வீரராஜேந்திரனுடைய மெய்க்கீர்த்தியிலே அவன் கன்னகூச்சியை மீட்ட செய்தி காணப்படுகிறது. (தே. இ. சாசனங்கள், மூன்றாம் வால்யூம், நெ. 83). மெய்க்கீர்த்தியின்படி, இவ் வெற்றி இரண்டாம் சோமேசுவரன் தன் கண்டிகை அவிழ்ப்பதன் முன்னதாகவே (அதாவது அவன் தந்தை இறந்த கி. பி. 1068-ஆம் ஆண்டு மார்ச்சு மாதம் 30-ஆம் தேதிக்குப் பிறகு அதே ஆண்டு ஏப்ரல் மாதம் 11-ஆம் தேதி முடிசூட்டிக் கொள்வதற்குமுன்) அடைந்த வெற்றிக்குப் பிறகு, சக்கரக் கோட்டத்துக்குத் தன் படைகளை நடத்திச் சென்றதன் விளைவாகவே ஏற்பட்டிருத்தல் வேண்டும். அதன் முடிவில் அவன் 'எல்லே கெடாது நிலையிட்டு', 'வடதிசை இமயத்தொடுங் கிடந்த சேது வாம்பாகச் செங்கோல் செலுத்தி'னான் என்று கூறப்பட்டிருக்கிறது. ('எல்லே கடந்து நிலையிட்டு' என்ற பாடமும் உண்டு.)

இந்தப் போர்களிலே வீரராஜேந்திரனுக்கு முதற் குலோத்துங்கன் உதவியாக இருந்திருக்கிறான் என்றே

தெரிகிறது. அப்போது குலோத்துங்கன் அரசனாகவில்லை. அவனுடைய பிதிரார்ஜிதமான வேங்கி நாடு அவன் சிற்றப்பன் விஜயாதித்தியன் ஆட்சியில் இருந்தது. கீழைச் சாளுக்கிய வமிசத்தைச் சேர்ந்த அவன் நாட்டை இழந்தபடியால் தன் மாமனான வீரராஜேந்திரனோடு சோழ நாட்டில் தங்கிவந்தான். இராஜேந்திரன் என்றே பெயர் பெற்றிருந்தான். அரசனாக முடி சூடுவதற்குமுன் அவன் நிகழ்த்திய வெற்றிகளை அவன் இளங்கோப் பருவத்தில் கொண்டனவாக அவனுடைய மெய்க் கீர்த்திகள் கூறுகின்றன. அவற்றின் சில பகுதிகளையும் நாம் முன்னரே கொடுத்திருக்கிறோம். சக்கரக் கோட்டப் பகுதியில் அவன் கொண்ட வெற்றிகள் மிகவும் சுருக்கமாகவே காணப்படுகின்றன. கலிங்கத்துப் பரணியிலே,

கடித ழிந்துபோர் மிதிலை யிற்படும்

கரிம ரூப்பினைத் திரள்து லாமெனும்

படிப ரப்பியப் பரும யானையின்

பழுவெ லும்பினில் பாவ டுக்கியே

(பண்டித அ. கோபாலையர் பதிப்பு, தாழிசை 87)

என்று காணப்படுவதிலிருந்து அவன் மிதிலையில் நடந்த போரில் அநேகம் யானைகளைக் கொன்று வெற்றிகொண்டான் என்பது தெரிகிறது. அவனுக்கு ஏழெட்டு மெய்க் கீர்த்திகளும் ஒவ்வொன்றிலும் பல பாடங்களும் காணப்படுகின்றன. (க. அ. நீலகண்ட சாஸ்திரிகள் எழுதிய சோழர்கள், இரண்டாம் வால்பூம், பக்கம் 2.) எனினும் அவற்றுள்ளே இம் மிதிலைப் போர் எங்கும் குறிக்கப் பெறவில்லை. அதனாலே இதுவும் அவனுடைய இளங்கோப் பருவத்தில், வீரராஜேந்திரன் ஆட்சிக் காலத்திலே, நடந்த நிகழ்ச்சிகளுள் ஒன்றாகும் போலும்.

மேலைச் சாளுக்கிய மன்னனான ஆஹவமல்லனுடைய ஆட்சிக் காலத்தின் கடைசியில் அவன் மகன் விக்கிரமாதித்தியன் திக்குவிஜயம் செய்து கொண்டிருந்தான் என்றும் அந்தச் சமயம் அவனுடைய சேனை கௌட காமரூப தேசங்களையும் வெற்றிகொண்டது என்றும் பில்ஹணருடைய விக்கிரமங்க தேவ சரிதம் கூறுகிறது. (இந்தியன் ஆண்டிக்குவரி

ஐந்தாம் வால்பூம், பக்கம் 319). அவனுடைய தந்தை இறந்த செய்தி அவனுக்கு எட்டிய சமயம் அவன் வெற்றிவீரனாகத் திரும்பிவரும் வழியில் கிருஷ்ண நதிக்கரையில் தங்கியிருந்தான். (விக்கிரமாங்க தேவ சரித்திரம், ஆறாம் சர்க்கம், 36 சுலோகம்.) அப்பால் தந்தை இறந்ததால் ஏற்பட்ட நிலைமையைக் கவனிப்பதில், இரண்டாம் சோமேசுவரன், விக்கிரமாதித்தியன் ஆகிய சகோதரர்கள் இருவரும் ஈடுபட்டிருக்கும்போது, வீரராஜேந்திரன் வடக்கே தன் படைகளை நடத்திச் சென்று, அதற்குமுன் விக்கிரமாதித்தியன் திக்கு விஜயத்தால் சோழர்கள் இழந்த பகுதிகளை மீட்டுக்கொண்டான் போலும். கன்யாகுப்ஜத்தை அவன் மீட்டுக்கொண்டதும் அதே சமயம்தான் போலும்.

இதுகாறும் கூறியவற்றால், முதலாம் இராஜேந்திர சோழன் போர்ப்படை நடாத்திக் கங்காவிஜயம் செய்த காலத்தில் வடநாட்டிலே சோழர்களுக்கு ஏற்பட்ட ஆதிக்கியத்தையும் செல்வாக்கையும், நடுவிலே அவர்களுக்கும் மேலைச் சாளுக்கியர்களுக்கும் ஏற்பட்ட கடும் போட்டியின் விளைவாக அவை சிறிது மங்கியிருந்தாலும், வீரராஜேந்திரன் ஆட்சியின் முடிவு வரையில் கொஞ்சமும் குறைய விடாமல் அவர்கள் காப்பாற்றி வந்திருக்கிறார்கள் என்பது விளங்கும்.

இவ்விரண்டு பேரரசுகளுக்கும் இடையில் இருந்த விரோதபாவத்திலே ஆஹவமல்ல சோமேசுவரன் இறந்ததிலிருந்து ஒரு மாறுதல் ஏற்பட்டது. இரண்டு ஆண்டுகள் கழித்து வீரராஜேந்திரன் இறந்த பிறகு மற்றும் ஒரு மாறுதல் நேர்ந்தது.

ஆஹவமல்லன் இறந்து அவன் மூத்தமகனான இரண்டாம் சோமேசுவரன் மேலைச் சாளுக்கிய அரசனாக முடிசூட்டிக் கொண்டதன்பின் அவனுக்கும் அவன் தம்பி விக்கிரமாதித்தனுக்கும் இடையில் பிளவு ஏற்பட்டது. அந்தப் பிளவு சிறிது நாளிலே முற்றியதால் விக்கிரமாதித்தியன் தன் தம்பி ஜயஸிம்ஹனையும் உடன் அழைத்துக்கொண்டு கல்யாண புரத்திலிருந்து வெளியேறிவிட்டான். அவர்களால் தனக்குக் கெடுதல் ஏற்படக் கூடும் என்று தீர்மானித்த சோமேசுவரன்

அவர்களைச் சும்மா விட்டுவிடவில்லை; அவர்களைத் தொடர்ந்து தன் படைகளை ஏவினான். எனினும், விக்கிரமாதித்தியன் அந்தப் படைகளை முறியடித்து, துங்கபத்திரை நதிக்கரையை அடைந்து, அவ்விடத்திலே சிறிது காலம் தங்கியிருந்தான். (விக்கிரமாங்க தேவ சரித்தரம், நான்காம் சர்க்கம், 67-ஆம் சுலோகம் முதல் ஐந்தாம் சர்க்கம், பத்தாம் சுலோகம் வரை.) வீரராஜேந்திரனுடைய மெய்க்கிர்த்தியிலே பின்வருவது காணப்படுகிறது:

“ சோமேச்வரனைக்

கன்னட தேசங் கைவிடத் துரத்தித்  
தன்னடிபுயடைந்த சளுக்கி விக்கிரமாதித்தனை  
எண்டிசை நிகழக் கண்டிகை கட்டி  
இரட்ட பாடி ஏழரை இலக்கமும்  
எறிந்து கொடுத்தருளி ”

இதிலிருந்து விக்கிரமாதித்தியன் தன் தமையனுக்கு எதிராகச் சோழ மன்னன் வீரராஜேந்திரனுடைய உதவியை வேண்டினான் என்பதும், சோழனும் அவனுக்கு உதவியளித்தான் என்பதும் தெரியவரும். இதே சமயம் மேலைக் கடற்கரையில் உள்ள (கோவா) கோபகா பட்டினத்தை ஆண்டு வந்த கதம்ப குல மன்னனான ஜயகேசி என்பான், மேலைச் சாளுக்கிய அரசனை அவனுடைய ஸ்திர சிம்மாசனத்தில் இருத்தியவன் என்றும், சாளுக்கியர்களையும் சோழர்களையும் காஞ்சி மாநகரத்தில் ஒன்று சேர்த்து நட்புரிமை கொள்ளச் செய்தவன் என்றும் கதம்ப சாசனங்களில் புகழப்படுகிறான். (ராயல் ஏஷியாடிக் ஸோஸைட்டி பம்பாய்க் கிளையின் பத்திரிகை, ஒன்பதாம் வால்பூம், பக்கம் 282; இன்னும் டம்பாய் கேஜட்டியர், முதல் வால்பூம், இரண்டாம் பாகம், பக்கம் 367.) வீரராஜேந்திரன் தன் மகளை விக்கிரமாதித்தியனுக்கு மணம் செய்து இந்தத் தோழமையைப் பலப்படுத்திக் கொண்டான் என்று பில் ஹணர் கூறுகிறார். (விக்கிரமாங்க தேவ சரிதம், ஐந்தாம் சர்க்கம், 28-ஆம் சுலோகம் முதல் ஆறாம் சர்க்கம், மூன்றாம் சுலோகம் வரை.) இவ்விதம் சாளுக்கியர்களுடைய விவகாரத்திலே சோழ மன்னன் தீவிரமாகத் தலையிட நேர்ந்ததால் சோமேச்வரன் அதற்கு மேல் ஏதும் செய்ய வகையில்லாமல் தன்னுடைய

ராஜ்யத்தில் ஒரு பாதியைப் பிரித்து விக்கிரமாதித்தியனுக்கு அளிக்கவேண்டிய நிர்ப்பந்தம் உண்டாகியது. அதுவும் அவன் சிங்காதனம் ஏறியவுடனேயே நடந்தபடியால் அவன் விட்டுக் கொடுக்க நேரிட்டதுபோலும். இவ்விதம் மேலைச் சாளுக்கிய ராஜ்யம் இரண்டாகப் பிரிந்தது. விக்கிரமாதித்தியனுக்குத் தென்பகுதி கிடைத்தது. அதை அவன் திரைலோக்கிய மல்லன் என்ற விருதுடன் அரசாளத் தொடங்கினான். வடபகுதி சோமேச்வரன் ஆட்சியில் அடங்கியிருந்தது. சோழ-சாளுக்கியர்களின் பலப்பரீகைப் போட்டியில் ஒரு கட்டம் இதனோடு முடிந்தது என்று சொல்லலாம். வீரராஜேந்திரன் இந்தச் சமாதானம் ஏற்பட்ட பிறகு நீண்ட நாள் ஜீவித்திருக்கவில்லை. இரண்டு வருஷங்களுக்குள்ளாகவே இறந்து விட்டான். அவன் இன்னும் சிறிதுகாலம் உயிருடன் இருந்திருப்பானாயின் சரித்திரத்தின் போக்கே வேறுவிதமாக மாறியிருக்கக் கூடும்.

**அதிராஜேந்திரனும் முதற் குலோத்துங்கனுடைய முடிதூட்டும்.**

வீரராஜேந்திரனுடைய ஆட்சியின் எட்டாம் ஆண்டைப் பற்றிய குறிப்பு அவனுக்குப் பின் சோழ சிங்காதனம் ஏறிய அவன் மகன் அதிராஜேந்திரனுடைய சாசனத்தில் காணப்படுகிறது. அதனால் அவன் கி. பி. 1070-ஆம் ஆண்டின் முற்பகுதியில் இறந்திருக்கவேண்டும். தஞ்சாவூர் ஜில்லாவில் முத்துப்பேட்டைக்குச் சமீபம் உள்ள சித்தமல்லி என்னும் கிராமத்தில் அதிராஜேந்திரனுடைய கல்வெட்டு ஒன்றை நான் 1944-ஆம் ஆண்டில் கண்டு பிடித்தேன்.<sup>1</sup> அவனுடைய ஆட்சியின் மூன்றாம் ஆண்டு முந்தாற்றிருபத்தொன்பதாம் நாள் கொண்ட அந்தக் கல்வெட்டில், அந்தச் சாசனம் அளிக்கப்பட்ட நாளின் பஞ்சாங்கக் குறிப்புகள் உள்ளன. ரிஷப மாதம் சுக்கிலபக்ஷப் பிரதமையும் செவ்வாய்க்கிழமையும் கொண்ட ரோஹிணி நாளான அது கி. பி. 1071-ஆம் ஆண்டு மே

1. சாசன இலாகாவினரும் இதைப் பின்னால் பிரதி செய்திருக்கிறார்கள். 1945-46-ஆம் ஆண்டின் நெ. 5. கொண்ட இக்கல்வெட்டு எபிகிராபியா இந்திகா பத்திரிகையில் வெளியாவதற்காகப் பேராசிரியர் க. அ. நீலகண்ட சாஸ்திரிகள் அவர்களோடு கூட்டாக என்னால் பதிப்பிக்கப்பட்டு வருகிறது.

மாதம் மூன்றாம் தேதியாகும். இதைக்கொண்டு கணித்தால் அவனது ஆட்சி 1068-ஆம் ஆண்டு ஜூன் மாதம் ஒன்பதாம் தேதி ஆரம்பமாயிற்று என்பது தெரியவரும்.

அதிராஜேந்திரனுடைய ஆட்சிக் காலம் எதோ சில நாட்களோ வாரங்களோ கொண்டதாகவே இருந்தது என்றும், அதன் முடிவில் அவன் இறந்து நாட்டிலே அரசரிமைக்கு உரிய பிள்ளைகள் இல்லாமையாலும் அராஜகம் தாண்டவ மாடியதாலும், குலோத்துங்கன் சோழ சிங்காதனம் அடைந்தான் என்றும், அவ்விதம் அவன் சோழ மன்னனாக முடிசூட்டப்பெற்ற காலம் கி. பி. 1070-ஆம் ஆண்டு ஜூன் மாதம் ஒன்பதாம் தேதியாகும் என்றும் பொதுவாக இதுவரையில் கருதி வந்திருக்கிறார்கள். (தே. இ. சாசனங்கள், மூன்றாம் வால்பூம், பக்கம் 127). ஆயினும் குலோத்துங்கன் சோழ சிங்காதனம் ஏறியதாகக் கருதப்படும் நாளுக்குப் பிறகு பதினொரு மாத காலம் அதிராஜேந்திரன் உயிரோடு வாழ்ந்து நாட்டை ஆண்டு வந்திருக்கிறான் என்பதை நாம் மேலே கண்டோம். ஆகவே முதற் குலோத்துங்க சோழன் சோழநாட்டின் அரசரிமையை அடைய நேர்ந்த சந்தர்ப்பத்தை நாம் மறுபடியும் ஆராயவேண்டிய அவசியம் ஏற்பட்டுவிட்டது.

குலோத்துங்கனுடைய ஆட்சியின் பிற்பகுதியில் அளிக்கப்பட்ட சாசனங்களில் பல—அவற்றுள்ளும் முக்கியமாக ஆட்சியின் ஆண்டு, சகாப்தம் ஆகிய இரண்டையும் கொடுப்பனவாகத் தெலுங்கு நாட்டிலிருந்து கிடைப்பவை—கி. பி. 1070-ஆம் ஆண்டையே அவனுடைய ஆட்சியின் ஆரம்பகாலமாகக் காட்டுகின்றன. வேங்கிநாடு நீண்ட நாளுக்கு முன்னதாகவே அவனுக்குக் கிட்டாமல் அவன் கையிலிருந்து நழுவி விட்ட படியால் அந்தத் தேதியை அவன் வேங்கி நாட்டுக்கு அரசனாக முடிசூட்டப்பெற்ற காலமாகவும் கொள்ள முடியாதென்பர்.

குலோத்துங்கன் தந்தையான இராஜ ராஜ நரேந்திரனுடைய ஆட்சிக் காலத்திலிருந்தே வேங்கிநாடு தாயாதிச் சண்டையின் போர்க்களமாக விளங்கியது. இந்தப் போர் அவன் ஆட்சி முழுவதும் நிகழ்ந்த வண்ணம் இருந்தபடியால் நரேந்திரனால் நாட்டை அமைதியாக ஆளமுடியவில்லை.

அவன் சோழ சக்கரவர்த்தி முதலாம் இராஜராஜன் மகள் குந்தவையக்கும் அவளை மணந்துகொண்ட கீழைச் சாளுக்கிய மன்னன் விமலாதித்தியனுக்கும் பிறந்தவன். கீழைச் சாளுக்கியர்கள் தங்கள் நாட்டை இழந்து சோழநாட்டில் அடைக்கலம் புகுந்திருந்த காலத்தில் அந்தத் திருமணம் நடந்தது. விமலாதித்தியன் கி. பி. 1011-ஆம் ஆண்டு மே மாதம் பத்தாம் தேதி வேங்கிக்கு அரசனாக முடிசூட்டப் பெற்றவன். (எபி. இந்திகா, ஆறாம் வால்பூம், பக்கம் 359.) அவன் ஏழு வருஷ காலம் ஆட்சி புரிந்தான் என்று கூறப்பட்டுள்ளது. (அவன் மகன் இராஜராஜ நரேந்திரனுடைய கோருமெல்லிச் சாசனம்: இந்தியன் ஆண்டிதவரி, பதினான்காம் வால்பூம், பக்கம் 53.) எனினும் ரணஸ்தி பூண்டிச் சாசனம் (எபி. இந்திகா, ஆறாம் வால்பூம், பக்கம் 359) அவனுடைய ஆட்சியின் எட்டாம் ஆண்டில் அளிக் கப்பட்டது. அதனால் அவன் தன்னுடைய ஆட்சியின் எட்டாம் ஆண்டு ஆரம்பத்தில், கி. பி. 1018-ஆம் ஆண்டின் பிற்பகுதியில், காலம் ஆகியிருத்தல் வேண்டும். ராஜ ராஜ நரேந்திரனுடைய ஆட்சியின் ஆண்டோடு சகாப்தத்தையும் சேர்த்துத் தெரிவிக்கும் சாசனங்களில் சில அவனுடைய ஆட்சி இந்தக் காலத்தில் ஆரம்பமாயிற்றென்பதைக் காட்டுகின்றன.<sup>1</sup> ஆனாலும் அவனுடைய மகுடாபிஷேகம் அப்போது நடைபெறவில்லை; நான்கு ஆண்டுகளுக்குப் பிறகே கி.பி. 1022-ஆம் ஆண்டில் நடந்தது. அவனுடைய கோருமெல்லிச் சாசனத்திலிருந்து அந்த மகுடாபிஷேகம் 1022-ஆம் ஆண்டு ஆகஸ்டு மாதம் பதினாறாம் தேதி வியாழக்கிழமை நடந்ததென்று தெரிகிறது. (இந்தியன் ஆண்டிதவரி, பதினான்காம் வால்பூம், பக்கம் 53) இவ்விதம் அவன் அரசுக்கு உரியவன் ஆனதற்கும் முடிசூட்டப் பெற்றதற்கும் நடுவில் நான்கு ஆண்டு இடைவெளி இருந்திருக்கிறது. எதனால் இப்படியாயிற்று என்பது நன்கு விளக்கப்பெறவில்லை.

இராஜராஜ நரேந்திரனுக்குக் குந்தவையைத் தவிர, மேளமா அல்லது மேடமா என்ற பெயரையுடைய தேவி ஒருத்

1. இதே போல இவனுடைய ஆட்சிக் காலத்தைக் கி. பி. 1022-ஆம் ஆண்டு முதலே கணக்கிட்டுக் காட்டும் சாசனங்களும் கிடைக்கின்றன.



தியும் இருந்திருக்கிறாள். அவளும் சோட குலத்தில் பிறந்தவளே. தெலுங்குச் சோடவமிசம் போலும். அவள் வயிற்றில் பிறந்த விஜயாதித்தியன் என்ற இளவரசன் ஒருவனும் உண்டு. தந்தை இறந்ததும் அப்போது வேங்கி நாட்டுச் சிங்காதனத்தை மேலைச் சாளுக்கியர்களுடைய உதவியோடு கைப்பற்றியிருந்தல் வேண்டும் என்று எண்ணவேண்டியிருக்கிறது. அதனாலேயே இந்த இடைவெளி ஏற்பட்டதுபோலும். இந்த இடைவெளிக்காலத்தில் வேங்கி நாட்டை விஜயாதித்தியனே ஆண்டுவந்தான். அதனால் ராஜ ராஜ நரேந்திரன் தன் மாமனான முதலாம் இராஜேந்திர சோழனுடைய உதவியை நாடவேண்டியதாயிற்று. இராஜேந்திரன் அவனுக்குத் தாய் மாமன் மட்டுமல்ல; தன் மகளான அம்மங்க தேவியையும் அவனுக்கு மணம் செய்து கொடுத்திருந்தான்.

இராஜேந்திர சோழனும் தன்னுடைய ஆட்சியின் பத்தாம் ஆண்டில் வேங்கி நாட்டின்மீது படையெடுத்துச் சென்றிருக்கிறான். அனந்தபூர் ஜில்லாவில் மதகசிரா தாலுகாவில் உள்ள மதகசிரா, கொத்தசீவரம் கிராமங்களில் கிடைக்கும் தமிழ்ச் சாசனங்களிலிருந்து இது தெரியவருகிறது. (1917-ஆம் ஆண்டு 23, 24, 30, 31, 751, 752 நெ. சாசனங்கள்.) அரசனுடைய ஆணைப்படி சாமந்தாபரணனும் சேனாதிபதியுமான அரையன் ராஜராஜனை விக்கிரம சோழச் சோழிய வரையன் என்பான் அந்தப் படைகளுக்குத் தலைமை தாங்கிப் போரை நடத்தினான் எனத் தெரிகிறது.

அந்தச் சாசனங்களிலிருந்து அவன் வேங்கி நாட்டு அரசனை அந் நாட்டிலிருந்து வெளியே தூரத்தினான் என்றும், ஜயசிங்கன் குலத்தை அழித்தான் என்றும், கலிங்கர், தெலுங்கர், குலிங்கர், ஓட்டர் ஆகியோரைப் போரில் வென்றான் என்றும் தெரியவருகிறது. இதிலிருந்து சோழனால் வேங்கியிலிருந்து தூரத்தப்பட்டவன், ஜயஸிம்ஹன் குலத்தைச் சேர்ந்த மேலைச் சாளுக்கியர்களோடு நட்புரிமை பூண்டிருந்தான் என்பதும் விளங்கும்.

“போயினான் போர்ச்சளுக்கி பொற்சோழியவரசை  
ஏவினான் கோச்சென்னி என்னவே—வாயினாற்

கொல்வேங்கை பின்தொடரக் கோல்வேங்கை சூழ்  
புறவில்  
தொல்வேங்கை மண்டலமுந் தோற்று "

என்னும் பாடலால் வேங்கியிலிருந்து ஓடிய மன்னன் சாளுக்  
கிய குலத்தைச் சேர்ந்தவனே என்பதும் அந் நாட்டு அரசுக்கு  
உரிமை உள்ளவன்தான் என்பதும் தெளிவாகும். எனினும்  
அவன் ராஜ ராஜ நரேந்திரனாக இருத்தற்கில்லை. சோழர்  
களுக்கும் அவனுக்கும் உள்ள நெருங்கிய உறவு ஒருபுறம்  
இருக்க, இந்தப் படையெடுப்பின் முடிவில்தான் அவன்  
வேங்கி நாட்டு அரசனாக முடிசூட்டப் பெற்றிருக்கிறான் என்ப  
தையும் நாம் கவனிக்கவேண்டும். அவன் ஆட்சி முழுவதிலும்  
அவனுக்குச் சோழர்களோடு சுமுகமான உறவு இருந்திருக்  
கிறது. அன்றி, விஜயாதித்தியனுடைய வாழ்க்கையைப் பார்த்  
தாலும் இது விளங்கும். இராஜேந்திர சோழன் வேங்கி விவ  
காரத்தில் தலையிட்டு விஜயாதித்தியனை அங்கிருந்து துரத்தித்  
தன் மருமகன் ராஜ ராஜ நரேந்திரனுக்கு நாட்டை மீட்டுக்  
கொடுத்து மகுடாபிஷேகமும் செய்துவைத்தான்.

அதற்குப் பிறகும் நரேந்திரன் ஆட்சி அமைதியாக நடை  
பெறவில்லை. மறுபடியும் விஜயாதித்தியன் தன் மாற்றூர்  
தாய்ச் சகோதரனைத் துரத்தி வேங்கியைக் கைக்கொண்டு,  
கி. பி. 1031-ஆம் ஆண்டு ஜூன் மாதம் 27-ஆம் தேதி அரச  
னாக முடிசூட்டிக்கொண்டான். அவனுடைய பாமுலவாகச்  
செப்பேடுகளிலிருந்து இது தெரிகிறது. (ஆந்திர சரித்திர ஆராய்ச்  
சிக் கழகத்தின் பத்திரிகை, இரண்டாம் வால்யூம், பக்கம் 257.)  
அவன் மேலைச் சாளுக்கியர்களுக்கு அடங்கியவனாக அவர்க  
ளின் கீழ் அதிகாரியாக இருந்துவந்தான். அதனால் இந்த  
முயற்சியிலே அவனுக்குப் பேரரசர்களான மேலைச் சாளுக்கி  
யர்களுடைய உதவியும் இருந்து வந்தது. திரும்பவும் சோழர்  
கள் வேங்கி விவகாரத்தில் தலையிட்டு விஜயாதித்தியனை வெளி  
யேற்றி நாட்டை மீட்டு நரேந்திரனுக்கு அளிக்கவேண்டிய  
தாயிற்று. இவ்விதம் வேங்கிநாடு, இரு சகோதரர்களுக்குள்  
ஏற்பட்ட தாயாதிச் சண்டைக்குக் காரணமாக மட்டுமல்லா  
மல், அவரவர்க்கு வேண்டிய அரசர்களை ஆதரித்து நின்றதால்

சோழர்களுக்கும் மேலைச்சாளுக்கியர்களுக்கும் இடையில் சதுரங்கக் காயாக அகப்பட்டுத் திண்டாடியது.

ஆஹவமல்ல சோமேச்வரன் கி. பி. 1042-ஆம் ஆண்டு மேலைச் சாளுக்கிய மன்னனாகச் சிங்காதனம் ஏறினான். அதன்பின் இரண்டு ஆண்டுகளிலே இராஜேந்திர சோழனும் இறந்தானாதலால் அவன் மகன் இராஜாதிராஜன் சக்கரவர்த்தியானான். அப்பால் வேங்கிநாட்டு அரசியலிலும், ராஜராஜ நரேந்திரனுடைய நிலைமையிலும் மறுபடியும் மாறுதல் ஏற்பட்டது. வேங்கியையும், அதனோடு ஒருபாகமாக இணைந்திருந்த கலிங்கத்தையும் சோழர்களிடமிருந்து மேலைச் சாளுக்கியர்கள் கைப்பற்றி, அவ்விடங்களில் தங்கள் அரசை நிலை நிறுத்தினார்கள். இராஜாதிராஜனும் அவனுக்குப் பின் சோழ சிங்காதனம் ஏறிய இரண்டாம் இராஜேந்திர சோழனும் வேங்கியைச் சோமேச்வரன் பிடியிலிருந்து மீட்கச் செய்த முயற்சிகள் அனைத்தும் வீணாயின. (டாக்டர் என். வேங்கடரமணய்யா எழுதிய வேங்கி நாட்டுக் கீழைச் சாளுக்கியர் சரித்திரம், பக்கம் 231 முதல்). இந்த நிலை சோழ சாசனங்களிலிருந்தும் தெளிவாகத் தெரிகிறது. வீர ராஜேந்திரனுடைய சாராலச் செப்பேடுகளில் (எபி. இந்திகா, இருபத்தைந்தாம் வால்யூம், நெ. 15.) பின் வரும் சுலோகம் காணப்படுகிறது.

ப்ராத்ருப்யாம் சமுபேக்ஷிதம் ஜநபதம்

வம்சக்ரமாப்யாகதம்

க்ரான்தம் வைரி மஹீச்வரைரதிபிலைர்-வ்

வேங்கிங் கலிங்காநபி ।

ஜித்வா சத்ரு பரம் பரா மதிபலாம்

பித்வா ச துர்க்கான் பஹுலம்

ஸ்ரீமாந் வல்லப வல்லபஃ க்ஷுதிபதிஃ

கேஷமேண தாம் ஸோந் வஸாத் ॥

(சுலோகம் 77)

இதே பிரசஸ்தியும் சுலோகமும் அவனுடைய கன்யா குமரிக் கல்வெட்டிலும் காணப்படுகின்றன. (திருவாங்கூர் ஆர்க்கியலாஜிகல் ஸீரீஸ், மூன்றாம் வால்யூம்). “சகோதரர்கள் இருவரால் வயிச பரம்பரையாக வந்து அடையப்பெற்றும்

அவர்கள் சரியாகக் கவனிக்காமையால் மிகுந்த பலம் பொருந்திய எதிரிகள் கைப்பற்றிய வேங்கி நாட்டையும் கலிங்க தேசத்தையும் அதிபலம் பொருந்திய அந்த எதிரிகளை வென்று அநேக கோட்டைகளை அழித்து ஸ்ரீமான் வல்லப வல்லபனா (அதாவது வல்லபர்கள் என்று பொதுவாகக் குறிக்கப் பெறும் மலேச் சாளுக்கியர்களுக்கு வல்லவனா) இம் மன்னன் மீட்டு அவற்றுக்கு நன்மை நல்கினான்.”

இம்மீட்சி வீரராஜேந்திரன் காலத்தில்தான் நடந்தது. இடையில் வேங்கிநாடு சுமார் இருபது ஆண்டுகளுக்கு மேலேச் சாளுக்கியர்கள் வசம் இருந்தது. அப்போது இராஜராஜ நரேந்திரன் வேறு வழியில்லாமல் அவர்களுடைய ஆதிக்கியத்தை ஏற்று அவர்களுக்கு அடங்கியவனாக அரசுபுரிய நேர்ந்தது. இல்லாவிட்டால், அவன் தன் நாட்டைத் துறந்து பழைய படியே சோழநாட்டில் அடைக்கலம் புகுந்திருக்க வேண்டும். அதைக் காட்டிலும் இதுவே சந்தர்ப்பத்திற்கு ஏற்றது என அவன் நினைத்தான்.

மேலேச் சாளுக்கியர்களுடைய விருதுகள் சிலவற்றை அவன் தரித்துக்கொண்டான். அன்றி, அவர்களுடைய பிரதிநிதி ஒருவனையும் தன்னுடைய சபையிலே அங்கம் வகிக்க ஒப்புக்கொண்டான். சோமேச்வரனுடைய பிரதானிகளுள் ஒருவரான நாராயண பட்டர் என்பார் அவ்விதம் இருந்திருப்பது தெரிகிறது. “அவர் ராஜராஜநரேந்திரனுடைய ஆஸ்தான கவியும் ஆந்திர மஹாபாரதம் இயற்றிய மகா கவியுமான நன்னய பட்டருடைய சகபாடி. அவரும் சிறந்த கவிஞரே. நன்னயபட்டர் ஆந்திர மஹாபாரதம் இயற்றியதற்கு அவர் பெரிதும் உதவியிருக்கிறார். அதைப் பாராட்டி மன்னன் அவருக்கு நந்தம பூண்டி என்னும் கிராமத்தைக் கி.பி. 1051-52-ஆம் ஆண்டில் தானமாக அளித்திருக்கிறான்.” இன்னும் திராக்ஷாராமத்திலிருந்து கிடைக்கும் கி. பி. 1055-56-ஆம் ஆண்டு கொண்ட ஒரு கல்வெட்டிலும் அவர் பெயர் காணப்படுகிறது. (தே. இ. சாசனங்கள், நான்காம் வால்பூம், பக்கம் 1010).

இராஜ ராஜ நரேந்திரன் நாற்பத்தோராண்டுகள் அரசு புரிந்தான். அதன் முடிவில் அவனுடைய மாற்றாந்தாய் வயிற்றுச் சகோதரனான விஜயாதித்தியன் மறுபடியும் வேங்கியைக்

கைப்பற்றிக்கொண்டான். இது அவனுடைய ரியாலச் செப் பேடுகளால் தெரிகிறது. (ஆந்திர சரித்திர ஆராய்ச்சிக் கழகப் பத்திரிகை, ஒன்பதாம் வால்யூம், பக்கம் 31).

பரோகேசு ராஜராஜஸ்ய ப்ராதூர் த்வைமாதூரஸ்ய ய: |

பர்யக்ரஹீந் மஹாராஜ்ய ஸ்ரியம் வீரஸ்யா யுத: ||

“மாற்றூந்தாய் மகனான ராஜராஜன் காணப்படாத சமயம் [இம்மன்னன்] வீர லக்ஷ்மியுடன் பெரிய ராஜ்யலக்ஷ்மியைக் கைப்பற்றினான்” என்று கூறும் அந்தச் சுலோகத்தில், பரோகேசும் அதாவது ‘காணப்படாதபோது’ என்ற சொல் லாட்சியைக் கவனிக்கவேண்டும். அதனால் இராஜ ராஜ நரேந் திரன் இயற்கை முடிவு எய்தும் வரையில் விஜயாதித்தியன் காத்திருந்தானா அல்லது இடையிலேயே நாட்டைக் கைப்பற்றிக் கொண்டானா என்ற சந்தேகம் உண்டாகிறது. எவ்விதமாயி னும், அவன் இவ்வளவு ஆர்வத்துடன் கைப்பற்றிய நாட்டைத் தானே நேரிடையாக ஆளவில்லை; தன் மகன் இரண்டாம் சக்திவர்மனுக்கு முடிசூட்டி வைத்தான். இம் மகுடரபிஷேகம் கி. பி. 1031-ம் ஆண்டு அக்டோபர் மாதம் 18-ஆம் தேதி வியாழக்கிழமை நடந்ததாகும். அவனும் ஒரு வருஷ காலமே ஆட்சிபுரிந்தான். அதன் முடிவில் அவன் ‘அபிமன்யுபோல்’ சுவர்க்கத்திற்குச் சென்றான். இந்த உபமானத்திலிருந்து சக்திவர்மனும் கரும்போரிட்டுப் போரிலே உயிர் துறந்தான் என்று எண்ணவேண்டியிருக்கிறது. விஜயாதித்தியனையும் அதைப் போலவே சந்திரகுலத்து அர்ஜுனனுக்கு ஒப்பிட்டுக் கூறுகிறது சாசனம். இவ்வளவு கஷ்டங்கள் நேர்ந்தபோதி லும் கடமையையே பிரதானமாகக் கருதிய விஜயாதித்தியன் வேங்கியின் அரசபாரத்தை வகிக்க முற்பட்டான். இது திரா க்ஷாராமத்தில் கிடைக்கும் அவனுடைய மகளான ஸோவல தேவியின் சகாப்தம் 987 (கி. பி. 1065-ஆம் ஆண்டு) கொண்ட சாசனத்திலிருந்து ஊர்ஜிதமாகிறது. (த. இ. சாஸனங்கள், நான்காம் வால்யூம், 1007 நெ.) இவற்றிலிருந்து விஜயாதித்தி யன் ஆரம்பமுதலே தன் மாற்றூந்தாய்வயிற்றுச் சகோதரன் ராஜராஜ நரேந்திரனோடு விரோதம் பாராட்டியதுமட்டுமல்லா மல் அவன் மகனும் குலோத்துங்கன் எனப் பின்னால் பிரசித்தி யான இராஜகுமாரன் இராஜேந்திரனுடன் சுமுகமான உறவு

கொண்டிருக்கவில்லை யென்பதும் விளங்கும். அவன் வேங்கியைப் பதினைந்து ஆண்டுகள் அரசுபுரிந்திருக்கிறான்.

சோழ ஸாம்ராஜ்யத்தின் பகுதிகளாக விளங்கிய வேங்கியையும் கலிங்கத்தையும் திரும்பவும் கைப்பற்றி விடவேண்டுமென்பதை வீரராஜேந்திரன் விரதமாகக் கொண்டிருந்தான். அதற்காக அவன் வேங்கியின்மீது இருமுறை படையெடுத்துச் சென்றான். [முதல் படையெடுப்பு அவன் சோழ சிங்காதனம் ஏறியவுடனே, கி. பி. 1033-ஆம் ஆண்டில், நடைபெற்றதாகத் தெரிகிறது. அதிலே அவன் ஆஹவமல்லனையே முக்கியமாக எதிர்த்துப் போரிட்டான். சாமுண்ட ராஜன் போன்ற சாளுக்கிய தண்ட நாயகர்களைக் கொன்ற தல்லாமல் அந்தப் படையெடுப்பிலே பெரு வெற்றி ஏதும் நிகழ்ந்து விடவில்லை. (எபி. இந்திகா, இருபத்தைந்தாம் வால்பூம், 248, 251-ஆம் பக்கங்கள்). இரண்டாம் சக்திவரமன் உயிர் துறந்ததும் இந்தப் படையெடுப்பின்போதேயாகும் போலும். வீரராஜேந்திரனுடைய ஐந்தாம் ஆண்டிலேயே பொறிக்கப்பட்ட திருமுகூடல் கல் வெட்டிலிருந்து (ஹெ. இருபத்தோராம் வால்பூம், பக்கம் 232) அவன் கி. பி. 1068-ஆம் ஆண்டிலே மூன்றாம் முறையும் வேங்கியைப் படையெடுத்துச் சென்றான் எனவும் கொள்ளலாம். இந்தச் செய்தியைத் தெரிவிக்கும் மெய்க்கீர்த்திப்பகுதி சிதிலமாக இருக்கிறது. முன்தடவையைக் காட்டிலும் இரும்புடங்கு போர்ப் படையுடன் வந்த அச்சுக்கியை எதிர்த்தே மன்னன் போரிட்டான் என்றும், வேங்கியே போர்க்களமாக விளங்கியது என்றும் அதிலிருந்து தெரிகிறது.] இந்த இரண்டாம் படையெடுப்பின் போதுதான் விஜயாதித்தியனைப் பற்றிய குறிப்பு காணப்படுகிறது. (தே. இ. சாசனங்கள், மூன்றாம் வால்பூம், நெ 30, பக்கம் 67). சோழ மன்னன் வேங்கியை வெற்றி கொண்டு தன்னை அடிபணிந்த விஜயாதித்தியனுக்கு அந்த நாட்டைத் திரும்பவும் அளித்தான் என்று அவனுடைய மெய்க்கீர்த்தி கூறுகிறது. அந்நாளிலே இராஜேந்திரன் என்ற பெயரைக் கொண்டிருந்த முதற் குலோத்துங்கனைப் பற்றிய பேச்சே இல்லை.

இதனால் கி. பி. 1070-ஆம் ஆண்டு ஜூன் மாதம் ஒன்பதாம் தேதி முதற் குலோத்துங்க சோழனுக்கு முடிசூட்டப்

பெற்றது வேங்கி நாட்டுக்கு அரசனாக இருந்திருக்க முடியாது என்றும் சோழநாட்டுக்கு அரசனாகவே இருத்தல் வேண்டும் என்றும் பொதுவாகக் கருதப்பட்டு வருகிறது. அதிராஜேந்திரனுடைய சித்தமல்லிக் கல்வெட்டிலிருந்து அம் மகுடாபிஷேகம் சோழ நாட்டுக்கு அரசனாகவும் நடந்திருக்க முடியாதென்பதை நாம் மேலே கண்டோம். குலோத்துங்கனுடைய மகுடாபிஷேகத்துக்குப் பிறகும் அதிராஜேந்திரன் பதினொரு மாதகாலம் அரசுபுரிந்திருப்பதிலிருந்து இது தெளிவாகும்.

அவ்விதமாயின் அவனுக்கு அம் மகுடாபிஷேகம் எந்த நாட்டுக்கு அரசனாக நடைபெற்றது என்ற கேள்வி எழுவது சகஜமே. இதை நிர்ணயிப்பதற்கு வீரராஜேந்திரன் காலமான சமயத்தை ஒட்டியும், குலோத்துங்கனுடைய ஆட்சியின் ஆரம்ப ஆண்டுகளிலும் சோழ நாட்டில் நிகழ்ந்த சம்பவங்களை நாம் தெளிவாக அறிய வேண்டுவது அவசியம்.

பில்ஹணர் தம்முடைய விக்கிரமாங்கதேவ சரித்தர்தில் இதைப் பின்வருமாறு கூறுகிறார்: விக்கிரமாதித்தியனுக்குத் திருமணம் நடந்த சிறிது காலத்துக் கெல்லாம் அவன் மாமனாரான சோழ மன்னன் இறந்தான். அதனால் சோழ நாட்டிலே அராஜகம் ஏற்பட்டது. இதைக் கேள்வியுற்ற மன்னன் இறந்துபோன வேந்தன் மகனான தன்னுடைய மைத்துனனுக்கு உதவியளித்து அவனுடைய அரசை நிலைநிறுத்த வேண்டுமென்ற நோக்கம் ஒன்றையே கொண்டு உடனே புறப்பட்டுக் காஞ்சி புரத்தை விரைந்து அடைந்தான். காஞ்சிபுரத்திலே சில நாட்கள் தங்கித் துஷ்டவர்க்கத்தை அடிபணிய வைத்தான். பிறகு கங்காகுண்ட (அதாவது கங்கை கொண்ட சோழபுர)த் துக்குச்சென்று எதிரியின் பலத்தை அழித்துச் சோழ ராஜ குமாரனுடைய அரசை ஸ்திரமாக்கினான். அப்பால் ஒரு மாத காலம் அவன் அவ்விடத்திலே தங்கியிருந்து நிலைமையை ஒழுங்கு செய்தான். அமைதி ஏற்பட்டு விட்டதென்று திருப்தியடைந்த விக்கிரமாதித்தியன் திரும்பித் துங்கபத்திரைக் கரையை அடைந்தான்.

“சில நாட்களே ஆனபின், சோழமன்னன் (அதிராஜேந்திர சோழன்) அவனுடைய குடிமக்கள் திரும்பவும் செய்த கலகத்தில் கொல்லப்பட்டதும் வேங்கிநாட்டு வேந்தனான ராஜிகன்

என்பான் திருவின் அருளும் கூடியதால் சிங்காதனத்தைக் கைப்பற்றினான். குடிலமனமுள்ள அவன் தனக்கு இவனால் (விக்கிரமாதித்தியனால்) அபாயம் நேரிடக்கூடுமெனச் சந்தேகித்து, பின்புறத்திலிருந்து இவன் கவனத்தை வேறு வழியில் திருப்புவதற்காக இவனுடைய இயற்கை விரோதியான சோமதேவனோடு (இரண்டாம் சோமேசுவரனோடு) நட்புரிமை பூண்டு சீர் செய்துகொண்டான்.....இவனுக்கு (விக்கிரமாதித்தியனுக்கு)த் தீங்கு விளைவிக்கவேண்டும் என்ற நோக்கத்துடனே குலவிரோதியான சோமன் ராஜிகனோடு கூட்டுச் சேரும்படியாகத் தன் அண்ணனுக்கு பரந்த பெருமனம் படைத்த இவன் (விக்கிரமாதித்தன்) என்ன செய்துவிட்டான்? அரசநெறியில்லாத ராஜிகனைக் கடிந்து தண்டிப்பதற்காக ராஜகுமாரன் (விக்கிரமாதித்தியன்) தண்டு எடுத்துக் கிளம்பிய போது சோமதேவன் (இரண்டாம் சோமேசுவரன்) தன் முழுப்பலத்தோடும் வெகுவேகமாக இவன் பின்னாலே துரத்திச் சென்றான். ....திராவிடசேனையின் கூட்டம் தயாளமனம் படைத்த ராஜகுமாரனை (விக்கிரமாதித்தியனை) அணுகியதும் கடைசியாக அவனுக்குக் கெடுதி செய்யும் சந்தர்ப்பம் வாய்த்து அவனை இம்மன்னன் (சோமேசுவரனும்) நெருங்கினான்.” (பேராசிரியர் க. அ. நீலகண்ட சாஸ்திரிகள் எழுதிய சோழர்கள், இரண்டாம் வால்பூம், 8-9-பக்கங்கள்.) போரும் நடந்தது. ஆயினும் விக்கிரமாதித்தியனே வெற்றியடைந்தான். ராஜிகன் ஓடிப்போனான்; சோமேசுவரன் சிறைப்பட்டான். இதன் பயனாகச் சோமேசுவரன் சிங்காதனத்தை இழந்தான். சிறிதுகாலம் சென்றவுடன் விக்கிரமாதித்தியன் தக்கணத்து அரசனாக முடி சூட்டிக்கொண்டு அரசாளத் தொடங்கினான் என்று அந்தக் காவியம் கூறுகிறது. (இந்தியன் ஆண்டிகுவரி, இருபதாம் வால்பூம், 281-ஆம் பக்கம்.)

இவ்வரலாற்றிலே ராஜிகன் என்று பில்ஹணர் குறிப்பிட்டிருப்பது முதற் குலோத்துங்கனுடைய பழம்பெயரான ராஜேந்திரன் என்பதேயாகும். சோழ நாட்டிலே திரும்பவும் ஏற்பட்ட கலகத்தின் விளைவாக அதிராஜேந்திரன் உயிர் இழந்ததால் அவன் சோழ சிங்காதனத்தைக் கைப்பற்றிய செய்தியைக் கூறும் பில்ஹணர் அவனை ‘வேங்கியின் மன்



னன் ' என்றே குறிக்கிறார். அவன் சோழ சிங்காதனம் ஏறுவதற்கு உரிமை இல்லாகவன் என்பதை எடுத்துக் காட்டுவதற்காகவே அவர் அவ்விதம் கூறுவதாக இருக்கலாம். ஆயினும், அந்தச் சமயத்தில் உண்மையாகவே அவன் வேங்கி நாட்டை ஆண்டு வந்தவனாகவும் இருத்தல் கூடும். பில்ஹணர் விக்கிரமாதித்தியனுடைய அவைக்களத்திலே புலவராக இருந்தவர். வேங்கியை ஆண்டு வந்த விஜயாதித்தியனோ மேலேச் சாளுக்கியர்களுக்கு நம்பிக்கை வாய்ந்த சாமந்தன். அதனால், ஆஸ்தானக் கவிஞருக்குத் திட்டமான விவரங்கள் நிச்சயம் தெரிந்திருக்கு மென்று தான் நாம் கொள்ள வேண்டும். ஆகவே அந்தச் சமயத்தில் வாஸ்தவமாகவே ராஜிகன் வேங்கி நாட்டு அரசனாக இருந்திரா விட்டால் அவர் அவனை அவ்விதம் குறித்திருக்க மாட்டார். அன்றி அதே சர்க்கத்தில் சில சுலோகங்களுக்கு அப்பால் கவிஞர் ராஜிகனைச் சோழன் என்று குறிப்பிடுவதையும் அப்போது அவன் உண்மையாகவே சோழ நாட்டை ஆண்டு வந்தான் என்பதையும் நாம் கவனிக்க வேண்டும். ஆகவே, பில்ஹணர் அவனை முதலில் வேங்கி நாட்டு அரசன் என்று குறித்திருப்பதை நாம் சந்தேகப்பட வேண்டிய அவசியமே இல்லை.

சித்தமல்லிக் கல்வெட்டு பொறிக்கப்பட்ட காலத்தில் அதிராஜேந்திரன் உயிருடன் இருக்கிருக்கிறான். அதனால் அவனுடைய மாணம் அந்தக் கல்வெட்டின் காலமான கி. பி. 1071-ஆம் ஆண்டு மே மாதம் மூன்றாம் தேதிக்கு முன்னதாக இருக்கமுடியாது. அவன் மரணமடைந்த காலத்தையும் சற்றேறக் குறைய நிச்சயமாக நிர்ணயித்தலும் கூடும். 'புகழ் சூழ்ந்த புணரி' என்னும் மெய்க்கீர்த்தியுடன் தொடங்கும் இராஜகேசரிவர்மன் சக்கரவர்த்தி (முதலாம்) குலோத்துங்கனுடைய பதினேராம் ஆண்டு கொண்டகாக ஸ்ரீரங்கத்திலிருந்து கிடைக்கும் ஒரு கல்வெட்டு இது பற்றிய முக்கியமான செய்தியைத் தெரிவிக்கிறது. (1937-ஆம் ஆண்டின் 31-நெ.) இராஜமஹேந்திர சதுர்வேதிமங்கலத்துச் சபைபார் அவ்வூர் மும்முடி சோழ விண்ணகர ஆழ்வார் கோயிலுக்குச் சொந்தமான நிலங்களை எழுபது கழஞ்சு பொன் கொண்டு இறைபிஷியாக்கிய செய்தியைக் கூறுவதாகும் அந்தக் கல்வெட்டு.

அவ்விதம் செய்ய வேண்டிய சந்தர்ப்பம் எப்படி ஏற்பட்ட தென்பதும் பின்வருமாறு விளக்கப் பட்டிருக்கிறது. “மன்ன னுடைய ஆட்சியின் இரண்டாம் ஆண்டில் வலங்கை இடங் கைச் சமூகத்தார்களுக்குள் ஒரு பெருங்கலகம் நடந்தது. அதிலே கிராமம் சுட்டு எரிக்கப்பட்டது. கோயில்கள், புண் ணிய ஸ்தலங்கள் பாழாயின. கோயில் விக்ரங்களும் கோயில் பண்டாரமும் கள்வர்களால் சூரையாடப் பட்டன. அவர்களு டைய கொள்ளைக்குத் தப்பிய பொருள்களையும் கோயிலிலே பாதுகாக்க முடிய வில்லை. கிராமத்தைப் புணர் நிர்மாணம் செய்து குடியேற்றி, கோயில்களை ஜீர்னோத்தாரணம் செய்து, பிராகாரங்களுக்குப் புதிய மதில்களை எழுப்பிப் புதிதாய்ப் பிரதிஷ்டை செய்யவேண்டி நேர்ந்தது. அதற்காகச் சபை யினர் கோயில் பண்டாரத்திலிருந்து இராஜேந்திர சோழன் மாடைக்கு அரை மாற்றுக் குறைவாக உள்ள ஐம்பது கழஞ்சு பொன்னைக் கடனைப் பெற்றனர். அதன் வட்டி இருபத் தைந்து கழஞ்சு ஆகியது. மொத்தம் கூடுதலான பொன் எழு பத்தைந்து கழஞ்சில் மூன்றாம் ஆண்டில் கோயில் ஜீர்னோத் தாரணத்துக்கும் புதிய பிரதிஷ்டைக்குமாக ஐந்து கழஞ்சு செலவாகியது. மீதமுள்ள எழுபது கழஞ்சு பொன்னைக் கொண்டு கோயிலின் நித்த நிபந்தங்களுக்காகச் சில நிலங் களை வாங்கி இறையிலியாக்கிவிடச் சபையார் முன்வந்தார் கள். (சாசன இலகாகாவின் 1936-37-ஆம் ஆண்டு அறிக்கை, இரண்டாம் பாகம், 27-ஆம் பாரா.) கல்விலே இந்தக் கல் வெட்டின் (மார்ஜினில்) பக்கத்தில், “இந்தக் கல்வெட்டு இராஜ மஹேந்திர சதுர்வேதிமங்கலத்துக்கு உரியது” என்றும் குறிக்கப்பட்டுள்ளது. இவ்வூர் நித்த விநோத வளநாட்டுக் காந்தார நாட்டைச் சேர்ந்ததென்று கூறப்பட்டிருக்கிறது. இப்போது பாபநாசம், நன்னிலம் தாலுகாக்கள் கொண்ட பிரதேசமே நித்த விநோத வளநாடு என்பது ஆகும். தஞ்சாவூருக்குக் கிழக்கே சுமார் ஐந்து மைல் தூரத்தில் உள்ள நெல்வித் தோப்பு (பாபநாசம் தாலுகா) என்னும் கிராமத் திலிருந்து கிடைத்துள்ள ஒரு கல்வெட்டிலிருந்து (1921-ஆம் ஆண்டு 537-நெ.) இராஜமஹேந்திர சதுர்வேதி மங்கலம் என்பது அதற்குப் பக்கத்திலேயே இருந்திருத்தல் வேண்டும் என்பது விளங்கும். இவ்வூரைப்பற்றிய இந்தக் கல்வெட்டு

உள்ளூர்க் கோயில் சுவர்களில் பொறிக்கப்படாமல் சுமார் நூற்று மைல் தொலைவில் உள்ள ஸ்ரீரங்கம் கோவில் சுவர்களில் பொறிக்கவேண்டிய காரணம் என்ன என்பது விளங்கவில்லை.

ஆயினும் இந்தச் சாசனத்திலிருந்து ஒரு விஷயம் தெளிவாகிறது. முதற் குலோத்துங்க சோழனுடைய ஆட்சியின் இரண்டாம் ஆண்டில் தஞ்சாவூரைச் சுற்றியுள்ள பிரதேசத்திலே பெருங் கலகமும் குழப்பமும் நடைபெற்றன. அதிலே சொத்துக்களுக்கும் பெருஞ்சேதம் ஏற்பட்டது. கோயில் சொத்துக்களும் தப்பவில்லை. கல்வெட்டிலே இந்தக் கலகம் ஆனி மாதம் நடந்ததாகக் குறிக்கப்பட்டுள்ளது.<sup>1</sup> அவ்விதமாயின் அது கி. பி. 1071-ஆம் வருஷம் ஜூன் மாதம் ஆகும்.

‘திருமன்னி விளங்கும்’ என்று தொடங்கும் மெய்க்கீர்த்தியை யுடைய இராஜேசரிவர்மனான இராஜேந்திர சோழனுடைய ஆட்சியின் இரண்டாம் ஆண்டு கொண்ட கல்வெட்டு ஒன்று தென் ஆர்க்காடு ஜில்லாவில் கொள்ளிடத்தின் வடகரையில் உள்ள கண்டமங்கலத்திலிருந்து கிடைத்துள்ளது. (1917-ஆம் ஆண்டு 358-நெ). ‘பூமருவிய திருமடந்தையும்’ என்று தொடங்கும் மெய்க்கீர்த்தியையுடைய சக்கரவர்த்தி இராஜேந்திரனுடைய கல்வெட்டு ஒன்று அதே ஆண்டு கொண்டதாகத் தஞ்சாவூர் ஜில்லாவில் வழுவூரிலிருந்து கிடைக்கிறது. அந்தக் கல்வெட்டில் காணும் பஞ்சாங்கக் குறிப்புகளைக் கொண்டு அது கி. பி. 1071-ஆம் ஆண்டு நவம்பர் மாதம் இருபத்தொன்பதாம் தேதி கொண்டதெனக் கணக்கிடப்பட்டிருக்கிறது. (சாசன இலாகாவின் 1914-ஆம் ஆண்டு அறிக்கை: ‘டி’ அனுபந்தம்.) இவற்றால் 1071-ஆம் ஆண்டு நவம்பர் மாதத்தில் சோழ நாட்டின் முக்கியமான மத்தியபாகம் குலோத்துங்கனுடைய ஆளுகைக்கு உட்பட்டிருந்ததென்பது தெரியவரும். அதனால் அதிராஜேந்திரன் மரணமும் அதற்கு முற்பட்டதாகவே சம்பவித்திருத்தல் வேண்டும். ஆகவே கி. பி. 1071-

1. சாசன இலாகாவின் அறிக்கையில் ஆனிமாதம் என்பது குறிக்கப் பெறவில்லை. கல்வெட்டின் மசிப்படத்திலிருந்தே இதை அறிய முடிந்தது. அதைப் பார்க்க எனக்கு அன்புடன் அனுமதியளித்த சாசன இலாகாவின் தலைவருக்கு என் நன்றி.

ஆம் ஆண்டு ஜூன் மாதம் அதாவது அதிராஜேந்திரனுடைய ஆட்சியின் நான்காம் ஆண்டுத் தொடக்கத்தில் நடைபெற்ற கலகத்தையே அதிராஜேந்திரன் உயிரிழப்பதற்குக் காரணமாக இருந்த கலகமென்று கொள்வதில் தவறு இல்லை.

இன்னும் அந்தக் காலத்தில் குலோத்துங்கன் என்னும் இராஜேந்திரன் வேங்கி நாட்டு அரசனாகவே இருந்திருத்தல் கூடும். கலிங்கதேசத்து அரசனான இராஜராஜ தேவேந்திரவர்மன் என்பான் “முதலில் திரயிளர் (தமிழர்)களுடன் நடத்திய போரில் ஜயமகளை மணந்து பிறகு சோடமன்னன் மகளான இராஜசுந்தரியையும் மணந்துகொண்டான். வேங்கி அரசனான விஜயாதித்தியன் முதுமையடைந்து வானமண்டலத்தை விட்டு வெளியேறும் (அதாவது அஸ்தமனமாகும்) சூரியனைப்போல வெளியேறி, சோடர்களாகிய சமுத்திரத்தில் முழுகிப் போகும் சமயத்தில், கஷ்டப்படுகிறவர்களுக்குப் புகலிடமான இராஜராஜன் அவனைக் கைதூக்கிச் சிறிது காலம் மேற்கு நாடுகளில் ஸௌபாக்கியத்தை அனுபவிக்கச் செய்தான்” என்று அவனுடைய மகன் அநந்தவர்மன் சோடகங்கனுடைய கோர்ணீச் செப்பேடுகளும் (ஆந்திர சரித்திர ஆராய்ச்சிக் கழகத்தின் பத்திரிகை-ஜர்னல் ஆப் தி ஹிஸ்டாரிகல் ஸோஸைட்டி, முதல் வால்யூம், பக்கம் 106-முதல்) விசாகப் பட்டினம் செப்பேடுகளும் (இந்தியன் ஆண்டிகுவரி, பதினெட்டாம் வால்யூம், பக்கங்கள் 166-9) தெரிவிக்கின்றன. கிழைக்கங்க வமிசத்து அரசனான இராஜராஜ தேவேந்திரவர்மன் கி. பி. 1070-ஆம் ஆண்டு மே மாதம் இருபதாம் தேதி கலிங்க நாட்டுச் சிங்காதனம் ஏறியவன். அதனால் அவன் கொண்ட வெற்றிகளும் விஜயாதித்தியனுக்கு உதவியதும் அந்த நாளுக்குப் பிறகே நடந்திருக்கவேண்டும்.

இவ்விதம் வேங்கியிலிருந்து வெளியேறிய விஜயாதித்தியன் திரும்பவும் அந்நாட்டு அரசைப் பெற்றது கி. பி. 1072-ஆம் ஆண்டுக்கு முன்னதாகவே நடத்திருத்தல் வேண்டும். இது அவனுடைய ஆட்சியின் பன்னிரண்டு, பதின்மூன்றாம் ஆண்டுகளைக் கொண்ட கல்வெட்டுகள் கிடைப்பதிலிருந்து தெரியவருகிறது. (1924-25-ஆம் வருஷத்து 8, 9-எண்கள் கொண்ட செப்பேட்டுச் சாசனங்கள் ; தே. இ. சாசனங்கள், ஆறாம் வால்யூம்,

1011-நெ. ஜர்னல் ஆப் தி ஆந்திரா ஹிஸ்டாரிகல் ரிஸர்ச் ஸோஸைட்டி, ஏழாம் வால்பூம், 177-8-பக்கங்கள்). எனினும், அதற்கு முன்னதாக நான்கு ஆண்டுகளுக்கு அவனுடைய சாசனங்கள் கிடைக்க வில்லை யென்பதும் குறிப்பிடத்தக்கது. கி. பி. 1075-ஆம் ஆண்டில் அளிக்கப்பட்டதும் கலிங்க மன்னனான இராஜராஜன் சேனைத்தலைவன் வனபதி என்பவனுடையது மான தீர்காஸிச் சாசனத்தில் அவன் தன் எஜமானனுக்காகச் சோழ சைனியத்தோடு போரிட்டுப் பெருவெற்றிகள் கொண்டான் என்பது விவரமாக எடுத்துரைக்கப்பட்டுள்ளது. (எபி. இந்திகா, ஏழாம் வால்பூம், 317-பக்கம்).

மற்றொரு விஷயமும் கவனிக்கவேண்டும். விஜயாதித்தியன் மேலைச் சாளுக்கியர்களிடம் விசுவாசமாக நீண்டகாலம் சேவை புரிந்தவன். அப்படியிருந்தும் இந்தத் தடவை அவன் வேங்கியிலிருந்து விரட்டப்பட்டபோது அவன் முன் தடவை களைப்போல அவர்களிடம் செல்லவில்லை. அதற்குப் பதிலாகக் கலிங்க நாட்டிலே அடைக்கலம் புகுந்தான். இதிலிருந்து அவன் மேலைச் சாளுக்கிய வேந்தனுடைய ஆதரவை இழந்து விட்டான் என்றே கருதவேண்டியிருக்கிறது. மேலைச் சாளுக்கியர்கள் விஜயாதித்தியனுக்கு விரோதியாக இருந்தவனையே ஆதரித்து நின்றார்கள் எனக் கொள்ளலாம். அவர்கள் நாடே அப்போது இரண்டாகப் பிளவு பட்டிருந்தது. தென்பகுதியை விக்கிரமாதித்தியனும் வடபகுதியைச் சோமேச்வரனும் ஆண்டுவந்தார்கள். ஆகவே விஜயாதித்தியன் அவர்களிடம் அடைக்கலம் புகுவதாக இருந்தால் சோமேச்வரனையே அண்டியிருத்தல் வேண்டும். சோமேச்வரனே விஜயாதித்தியனுக்கு உதவுவதாக இல்லை; பதிலாக அவனை வேங்கியிலிருந்து துரத்தியவனையே ஆதரித்து நின்றான் போலும். அதற்குச் சிறிது காலத்துக்கு முன்னதாக விக்கிரமாதித்தியனும் அவன் மாமனான சோழமன்னன் வீரராஜேந்திரனும் ஒன்றுசேர்ந்து மேலைச் சாளுக்கிய ஸாம்ராஜ்யத்தின் ஒரு பகுதியை அடைவதற்குச் செய்த முயற்சியில், விஜயாதித்தியன் அவர்களுக்கு உதவியாக நின்றான் என எண்ணுவதற்கு இடமிருக்கிறது. அது சோமேச்வரனுக்குப் பெரிதும் ஆத்திரம் மூட்டியிருக்கும். அந்த நிலையிலே வேங்கி நாட்டிலிருந்து விஜயாதித்தியனைத் துரத்தி அதைக் கைப்பற்றக் கூடியவன் குலோத்துங்கன்.

ஒருவனே ஆவன். பின்னால் அதிராஜேந்திர சோழன் இறந்த போது குலோத்துங்கன் சோழநாட்டைக் கைப்பற்றிய வுடனே அவனைக் கடிந்து அவன் எண்ணத்தை முறியடிக்க விக்கிரமதித்தியன் சோழநாட்டின்மீது படையெடுத்துவந்த காலத்தில், இரண்டாம் சோமேச்வரன் குலோத்துங்கனுக்குத் துணையாக நின்று பெரிதும் உதவியிருக்கிறான் என்பதை நாம் அறிவோம். அப்போது அவர்களுக்குள்ளே காணப் பெறும் இந்நட்பு இன்னும் முன்னதாகவே, அதாவது விக்கிரமதித்தியனுக்கும் சோமேச்வரனுக்கும் பிளவு ஏற்பட்ட வுடனேயே, ஆரம்பித்ததுபோலும்.

அப்பொழுதிருந்த சூழ்நிலையும் ஏறக்குறைய அம்மாதிரி யேதான் குலோத்துங்கனுக்குத் தோற்றியதுபோலும். தன் பிதிரார்ஜிதமான வேங்கி அரசை அவன் துணிந்து கைப் பற்ற அப்போது முயலாவிட்டால், ஒருகால் எப்போதுமே அவனுக்கு அது கிட்டாமல் போய்விடுமோ என்ற சந்தேக மும் ஏற்பட்டிருக்க வேண்டும். அத்தகைய முயற்சிக்கும் அதுவே உற்ற காலமாக அவனுக்குப்பட்டது போலும். வீர ராஜேந்திரன் ஒன்றிரண்டு ஆண்டுகளுக்கு முன்னே வேங்கி யை விஜயாதித்தியனிடமிருந்து வெற்றி கொண்டு கைப்பற்றி னான். ஆயினும் அந்த அவன் தன் மருமகனும் வேங்கி நாட்டு அரசுக்கு உரியவனுமான குலோத்துங்கனுக்கு அளிக்க வில்லை. திரும்பவும் விஜயாதித்தியனிடமே கொடுத்துவிட்டான். இவ்விதம் அவன் செய்ததற்கு மேலைச் சாளுக்கியர்களுடைய நிர்ப்பந்தமே முக்கிய காரணமாயிருந்திருக்கலாம். விஜயாதித் தியன் அவர்கள் சாமந்தன் அன்றோ? ஆனால் மேலைச்சாளுக் கிய ஸாம்ராஜ்யமே இப்பொழுது பிளவுபட்டிருந்தது. ஒரு வருக்கு ஒருவர் பரம விரோதிகளான சகோதரர்கள் இரு பகுதிகளைத் தனித்தனியாக ஆண்டுவந்தார்கள். எனினும் வீர ராஜேந்திரன் இப்போது இறந்துவிட்டான். அவனுக்குப் பின் சோழ சிங்காதனம் ஏறிய அதிராஜேந்திரனிடமும் குலோத்துங்கனுக்குச் சுமுகமான உறவு இருந்திருக்கவில்லை. தவிர, அவனுக்கு விக்கிரமதித்தியன் உதவியும் கிட்டுமே.

ஒருகால் குலோத்துங்கனுக்கு ஆரம்ப முதலே சோழ சிங்காதனத்தின் மீது ஒரு கண் இருந்திருக்கவும் கூடும். இந்த ஆசையை மேலும் சோமேச்வரன் தூண்டிவிட்டிருத்தல்

கூடும். அதிராஜேந்திரனும் விக்ரமாதித்தியனும் ஒன்று சேர்ந்துவிட்டால் அந்தக் கூட்டு மிகவும் பலம்பொருந்தியதாக ஆகிவிடும். அவ்விதம் நேராமல் தடுத்துவிடவேண்டும். ஆயினும் அதற்காக வெளிப்படையாகச் சோழர்களிடம் விரோதம் பாராட்டுவதோ அந்நாட்டின் மீது படையெடுத்துச் செல்வதோ முடியாத காரியம். அதனாலே குலோத்துங்கன் இம்முறையைப் பின்பற்றியிருக்கலாம். இதற்காக அவன் உள்நாட்டிலே கலகத்தைக் கிளப்பிவிட்டுக் கிளர்ச்சி செய்ய மக்களைத் தூண்டியிருக்கலாம். இதற்கு ஓர் அளவு சோமேச்வரன் உதவியும் கிட்டியிருக்கல் கூடும்.

மேலே குறிப்பிட்ட ஸ்ரீரங்கம் கல்வெட்டிலிருந்து மற்றொரு விவரமும் தெரியவருகிறது. அப்போது நடைபெற்ற கலகம் வலங்கை-இடங்கையாக நடந்ததென்று காணப்படுகிறது. இவ்விரு பிரிவினருக்கும் இடையில் உள்ள விரோதம் நீண்டகாலமாக இருந்துவந்ததாகத் தெரிகிறது. அதன் ஆணிவேர் மிகவும் ஆழமாக ஓடியிருந்தது. பிற்காலத்தில் அந்தக் கலகங்கள் கோரமான விசுவரூபமெடுத்து ஆடியிருக்கின்றன. கிழக்கிந்தியக் கம்பெனியார் நாளிலே சென்னைத் தெருக்களில் ரத்தப்பெருக் கெடுத்துவிடுமோ என்ற நிலை பல சமயங்களில் ஏற்பட்டிருக்கிறது. காஞ்சிபுரத்திலே இவ்விரு பிரிவினர்களும் ஒரே கோயிலில் வழிபட மாட்டார்களாம். அதே போல, முக்கியமான வைதிகச் சடங்குகள் முதலியவற்றுக்கு ஒரே மண்டபத்தையும் உபயோகிக்கமாட்டார்களாம். (சாகன இலாகாவின் 1921-ஆம் ஆண்டு அறிக்கை, 47 பாரா.) இந்தச் சண்டைகள் எல்லாம் பெரும்பாலும் சமூக வாழ்க்கையில் அவர் அவர்களுக்கு உள்ள சில உரிமைகளைப் பற்றியனவே எனத் தெரிகிறது. சில சமயங்களில் அவர்களுக்குள்ளே சமாதானம் நிலவி ஒப்பந்தங்களும் ஏற்பட்டிருக்கின்றன. அவ்விதம் ஏற்பட்ட விவஸ்தைகள் பெரும்பாலும் எந்த எந்த வகுப்பார் எந்த எந்த உரிமைகளை அனுபவிக்கலாம் என்பதை நிர்ணயிப்பனவாகவே காண்கின்றன.

நாட்டிலே-பலவகைச் சமூகத்தாரிடையிலும் இவ்விதம் இரு பெரும் பிரிவு நீண்டகாலமாக இருந்து வந்திருக்கிறதென்று தெரிகிறது. ஆனால் அந்தப் பிரிவு எதைக் குறிக்க

கிறது என்ற விவரம்தான் தெரியாது. இந்தப் பிரிவு எப்படித் தோன்றியது என்ற விவரம் எழுதாது ஆண்டுகளுக்கு முன்னதாகவே மறந்துபோய்விட்டது. இது திருச்சிராப்பள்ளி ஜில்லா ஊற்றத்தாரிலிருந்து கிடைத்த ஒரு கல்வெட்டிலிருந்து தெரியலாகிறது. (1912-ஆம் ஆண்டு 489-ஆம் செ.) மூன்றாம் குலோத்துங்க சோழனுடைய ஆட்சியின் கார்ப்பதாம் ஆண்டு கொண்ட அக் கல்வெட்டு இடங்கைப் பிரிவினர் தாங்கள் எப்படித் தோன்றினார்கள் என்பதைப்பற்றி அப்போது கொண்டிருந்த வரலாற்றைக் கூறுகிறது. “அவர்கள் கச்யப முனிவரின் யாகத்தை ஸம்ரக்ஷிப்பதற்காக அகலி குண்டலத் திலிருந்து தோன்றியவர்களாம். அவர்கள் அரிந்தம சக்கர வர்த்தியின் நாளில் சோழ நாட்டுக்கு வந்து தங்கினார்களாம். அந்தச் சக்கரவர்த்தி அக்தர்வேதி (கங்கா - யமுனாப் பிரதேசம்) பூமியிலிருந்து அழைத்து வந்த பிராம்மண சிரேஷ்டர் களுடன் அவர்களுடைய பாதரக்ஷையையும் குடையும் தாங்கிக் கொண்டு வந்தார்களாம், இடங்கைச் சாதிபினர். ஐந்து கிராமங்களிலே அவர்களுக்கு நிலம் அளிக்கப்பட்டதாம். அவ் ஐந்து ஊர்களும் இப்போது திருச்சிராப்பள்ளி ஜில்லாவிலே உள்ளன. தங்கள் பூர்வோத்தரத்தைப் பற்றிய விவரங்கள் அவர்களுக்கு கிண்டகாலம் தெரியாமல் மறந்துபோயிருந்தனவாம்.” அப்பால் அதை அவர்கள் கண்டுபிடித்தார்களாம். (சாசன இலாகாவின் 1913-ஆம் ஆண்டு அறிக்கை, பாரா 39). அதன் மேல் அவர்கள் ஒன்றுகூடி ஒரே வயிற்றில் பிறந்த சகோதரர்கள் போல ஒற்றுமையாக வாழவேண்டுமென்று தங்களுக்குள் தீர்மானித்துக்கொண்டார்களாம். இதைக் கவனித்தால் அந்தப் பிரிவுகள் எப்படி ஏற்பட்டது என்ற விவரம் அந்நாளிலேயே அவர்களுக்குத் தெரியவில்லை என்பதும், ஆகவே ஒரு புராணக் கதையைச் சிருஷ்டித்துக்கொள்ள வேண்டிய நிலை அவர்களுக்குள்ளே சுருதிமான்சுக்கு ஏற்பட்டது என்பதும் விளங்கும்.

வலங்கை என்பது சோழ மன்னனான முதலாம் இராஜராஜனுடைய காலத்திலிருந்தே, வலங்கைப் பழம் படைகளிலார், பெருந்தனத்து வலங்கைப் பழம்படைகள், அழகிய சோழத் தெரிந்த வலங்கை வேளைக்காரப்படைகள், இராஜ



ராஜத் தெரிந்த வலங்கை வேளைக்காரர் என்பன போலச் சோழர் படையின் பிரிவுகளிலே காணப்படுகிறது. (தே. இ. சாசனங்கள், இரண்டாம் வால்பூம், முன்னுரை, பக்கம் 9). வலங்கை வேளைக்காரர் என்ற பிரிவைப் பல படைகளிலும் காண்கிறோம். ராஜ சேவகத்தில் நிரந்தரமாகவும் எந்தச் சமயத்திலும் சேவைக்குத் தயாராகவும் இருந்த படையினர் என்று அவர்களைப் பொதுவாகக் கொள்வர்.

எனினும், இடங்கையைப் பற்றி யாதொரு விவரமும் தெரியவில்லை. இடங்கைப் பிரிவின் பெயர் சாசனங்களில் காணப்படாமல் இல்லை. ஏதோ சிற்சில இடங்களிலே தான் காணப்படுகின்றது. ஆனால் அப்படி உள்ள இடங்களில் எல்லாம் பெரும்பாலும் அது வலங்கையுடன் சேர்ந்தே காணப்படுகிறது. தஞ்சாவூர் ஜில்லாவில் உள்ள திருவெண்காட்டிலிருந்து கிடைக்கும் வீரராஜேந்திரனுடைய இரண்டாம் ஆண்டுக் கல்வெட்டு ஒன்று (தே. இ. சாசனங்கள், ஐந்தாம் வால்பூம், 976-நெ.) அவ்வூர்க் கோயிலுக்குப் பல கிராமங்களிலிருந்து வசூலாகும் வரிகள் சிலவற்றை அளித்த செய்தியைக் கூறுகிறது. அந்த வரிகளிலே வலங்கை-இடங்கை மகன்மை என்பதும் ஒன்றாகும். வடஆர்க்காடு ஜில்லாவில் உள்ள திருவல்லத்திலிருந்து கிடைக்கும் அரேராஜேந்திரனுடைய மூன்றாம் ஆண்டும் இருதாரும் நாளும் கொண்ட கல்வெட்டு ஒன்றிலும் (செ. மூன்றாம் வால்பூம், பக்கம் 115) இதே வரி குறிக்கப்பட்டுள்ளது. வலங்கை, இடங்கை ஆகிய இருபிரிவுகளிலும் படைக்கலம் ஏந்திப் போர் புரியும் திறமை வாய்ந்தவர்கள் அனைவரும் செலுத்த வேண்டிய தலைவரி என்றே இதைக் கொள்வர். இதனால் இடங்கையும் போர்ப் படையோடு ஏதோ ஒரு வகையில் தொடர்பு கொண்டதெனக் கொள்ளலாம். ஆயினும் இடங்கைப் பிரிவிலே அடங்கியுள்ள சாதிப் பெயர்களைக் கவனிக்கும்போது அவை யாவும் வாணிகம் செய்வோரையும் தச்சன் கருமான் போன்ற தொழிலாளர்களையுமே கொண்டனவாக உள்ளன.

இலங்கை மன்னன் விஜயபாஹு ஆட்சியின் கடைசிக் காலத்தில் பொறிக்கப்பட்டதாக இலங்கையில் பொலநறு வையிலிருந்து கிடைக்கும் தமிழ்க் கல்வெட்டு ஒன்று இவ்

விஷயத்தில் உதவியாகக் காண்கிறது. புத்த பகவானுடைய புனிதச் சின்னமான பல்லை வைத்து அதன் மீது அம் மன்னன் எழுப்பிய பள்ளிக்கு மூன்றுகைத் திருவேளைக்காரன் தலதாயப் பெரும் பள்ளி என்று பெயரிட்டு வேளைக்காரர் பாதுகாப்பிலே அதை விட்ட செய்தியைத் தெரிவிக்கிறது அந்தக் கல்வெட்டு. (எபி. இந்திகா. பதினெட்டாம் வால்பூம், 338-பக்கம்) வேளைக்காரர்கள் அந்தப் பொறுப்பை ஏற்றுக்கொள்வதற்கு முன் தங்கள் மகாசபையைக் கூட்டி விவாதித்து முடிவு செய்ததைத் தெரிவிக்குமிடத்தில் கல்வெட்டு பின்வருமாறு கூறுகிறது: “மா தந்திரத்தோங் கூடி எங்களுக்கு மூதாதைகளாயுள்ள வளஞ்செயரையும் எங்களோடு கூடிவரும் நகரத்தார் உள்ளிட்டாரையும் கூட்டி மூன்று கைத் திருவேளைக்காரன் தலதாயப் பெரும்பள்ளி யென்று.....” கடைசியிலே அதற்கு ஒப்புக்கொண்டு அந்தக் கல்வெட்டிலே கையொப்பமிட்டவர்களெனக் காணும் பகுதி, “வலங்கை இடங்கை சிறுதனம் பிள்ளைகள் தனம் வருகார் மலையாளர் பரிவாரக் கொந்தம் பலகலையுள்ளிட்ட திருவேளைக்காரரோம்” என்பதாகும்.

மா தந்திரத்தாருக்கு, அதாவது மஹா தந்திரத்தாருக்கு மூதாதையாரான வளஞ்சியரும் மஹா தந்திரத்தாரோடு கூடி உடன் வருகிற நகரத்தாரும் வாணிகம் நடத்துபவர்கள் என்பதை நாம் அறிவோம். ஆனால் வளஞ்சியத்தாருக்கும் நகரத்தாருக்கும் உள்ள வித்தியாசம் தெரியவில்லை. வளஞ்சியத்தாரை அவர்களுடைய மூதாதையர் எனக் குறிப்பதால் அவர்கள் அந்த ஸ்தாபனத்தின் மூலஸ்தானத்தைச் சேர்ந்தவர்களாக இருத்தல் வேண்டும். பம்பாய் ராஜ்யத்தின் பிஜாப் பூர் ஜில்லாவில் இப்போது ஐஹோளே என்று வழங்கப் பெறும் அய்யாவழி அல்லது அய்யபொழிலைத் தலைமை ஸ்தானமாகக் கொண்டு பல நாடுகளிலும் வியாபாரம் செய்த நானாதேசி திசையாயிரத்து ஐந்தாற்றுவரை அது குறிக்கும் போலும். நகரத்தார் என்பது அந்த அந்த இடங்களிலே தங்கி வாணிகம் செய்பவர்களின் ஸ்தாபனத்தைக் குறிப்பதாகக் கொள்ளலாம். தந்திரம் என்ற சொல்லுக்குப் பல பொருள்கள் இருந்தாலும் சந்தர்ப்பத்தை ஒட்டிப் பார்த்தால் இந்த இடத்திலே அது போர்ப்படையைப் பற்றிய பொருளைக் கொடுப்பதாகவே கொள்ள வேண்டும் என்பது விளங்கும்.

ஆகவே மஹாதந்திரத்தார் என்போர் படைத் தலைமையின் நிர்வாகக் குழுவினர் என்றே பொருள்படும். அப்படியானால் இந்தச் சாசனத்திலே குறிக்கப்பட்டுள்ள வேளைக்காரர் என்னும் சேனாவீரர்கள் வாணிபத் துறையோடு ஏதோ ஒரு வசையான சம்பந்தம் கொண்டவர்கள் என்பது தெளிவாகும்.

இன்னும் தாங்கள் ஏற்றுக் கொண்ட காரியம் சரிவர நடைபெறுவதற்காக மஹாதந்திரத்தார் ஒவ்வொரு படையிலிருந்தும் ஒரு சேவகரையும் ஒவ்வொருவருக்கும் ஒரு வேலி வீதம் நிலமும் அளித்துக் கோயில் ஊழியத்துக்கு அளித்திருக்கிறார்கள்.

இவ்விதம் கோயில்களைச் சைனியத்தாரின் பாதுகாப்பிலே ஒப்படைக்கும் பழக்கம் அந்நாளிலே தென்னிந்தியாவிலும் இருந்ததாகத் தெரிகிறது. திருநெல்வேலி ஜில்லாவில் உள்ள சேரன்மாதேவி பக்தவத்சல சுவாமி கோயிலிலிருந்து கிடைத்திருக்கும் முதற் குலோத்துங்க சோழனுடைய காலத்துக் கல்வெட்டு ஒன்று (1895-ஆம் ஆண்டு 189-நெ.) அந்தக் கோயிலுக்கு அளிக்கப்பெற்ற சில தர்மங்களைப் பாதுகாக்கும் பொறுப்பை மூன்றுகை மஹாஸேனையார் ஏற்றுக் கொண்ட செய்தியைத் தெரிவிக்கிறது. அதே ஜில்லாவில் உள்ள திருவாலிச்வரத்திலிருந்து கிடைக்கும் மற்றொரு கல்வெட்டு (1309-ஆம் ஆண்டு 167-நெ.) அவ்வூர்க் கோயிலையும் அதன் ஸ்ரீபண்டாரத்தையும் கோயிலைச் சேர்ந்த தேவகன்மிகளையும் சோழஸாம்ராஜ்யத்தின் படையான மூன்றுகை மஹாசேனையின் பாதுகாப்பிலே விட்ட செய்தியை எடுத்துக் கூறுகிறது. இதே போல, கோயம்புத்தூர் ஜில்லாவில் உள்ள சங்கராம நல்லூரிலிருந்து கிடைத்த சாசனம் ஒன்றும் (1925-ஆம் ஆண்டு 183-நெ.) காணப்படுகிறது. அந்நாளிலே அவ்வூர் கோட்டை கொத்தளங்களுடன் படைநிலையமாக விளங்கியது போலும். அவ்விடத்திலிருந்த படைவீரர்கள் கோயில், அதன் கோபுரம், கோயிலைச் சார்ந்த மற்ற இடங்கள் ஆகியவற்றைப் பாதுகாக்க வேண்டும் என்று அது கூறுகிறது. (1905-ஆம் ஆண்டு 120-நெ; இன்னும் சாசன இலாகாவின் 1936-ஆண்டு அறிக்கை, பக்கம் 71.) தஞ்சாவூர் ஜில்லாவில் உள்ள புஞ்சை என்னும் இடத்திலிருந்து கிடைக்கும் ஒரு சாசனத்திலிருந்து

தேவதான நிலங்களில் சில அவ்வூர்க் கோயிலுக்கே உரியன என்பதை நிரூபிப்பதற்காகத் திருச்சூல வேளைக்காரர் சிலர் தீக் குளித்துத் தங்கள் உயிரைத் தியாகம்செய்து உரிமையை நிலை நிறுத்தினர் என்ற செய்தி தெரியவருகிறது. இதிலிருந்து கோயில்களும் வேளைக்காரர்களைக் கொண்டிருந்தனவென்பது விளங்கும். திருநெல்வேலி ஜில்லாவில் உள்ள உக்கிரன் கோட்டையிலிருந்து, முதற் பரார்தக சோழனோடு சமகாலத் தவன் என்று கருதப்பெறும் ராஜ்ஜிம்ஹன் என்னும் பாண்டிய அரசன் காலத்தைச் சார்ந்த கல்வெட்டு ஒன்று கிடைத்துள்ளது. கரவந்தபுரம் என்று அந்நாளிலே வழங்கப்பட்டு வந்த அவ்வூரின் கோயிலை மதிட்சேவகர் பாதுகாப்பிலே விட்ட செய்தியை உரைக்கிறது அந்தக் கல்வெட்டு. (எபி.இந்திகா, இருபத்துமூன்றாம் வால்பூம், பக்கம் 235.)

இராமநாதபுரம் ஜில்லாவில் உள்ள ஸ்ரீவில்லிபுத்தூரிலிருந்து கிடைக்கும் சாசனம் ஒன்று அவ்வூர் விஷ்ணு கோயிலான வடபெருங் கோயிலுடையான் ஆலயத்தின் திருவாசல் அவ்வூரில் இருப்பவர்களுக்கும் மற்றும் பக்கத்திலே உள்ள வேறு சில ஊர்களில் உள்ளவர்களுக்கும் அபயம் எனக் கருதப் படவேண்டுமென்பதைத் தெரிவிக்கிறது. (1926-ஆம் ஆண்டு நெ. 537; சாசன இலாகாவின் 1927-ஆம் ஆண்டு அறிக்கை, பாரா. 54). அஞ்சினன் புகலிடம் என்று வேறு இடங்களில் குறிக்கப்பட்டிருப்பதே இவ்விடம் அபயம் என்று காணப்படுகிறதேபோலும். துரிதங்கள் நேரிட்ட காலத்தில் எதிரிகளிடமிருந்து தப்புவதற்காகக் கஷ்டத்துக்குள்ளானவர்கள் அடைக்கலம் புகுமிடம் என்பதையே அது தெரிவிப்பது. இன்னும் கோயில் ஊழியர்களில் வீரமுஷ்டி என்றும் வீரபத்திரர் என்றும் பெயர் பெற்ற வீரர்கள் இருந்ததும் தெரியவருகிறது. (சாசன இலாகாவின் 1917-ஆம் ஆண்டு அறிக்கை, பாரா 36.) இவற்றைக் கவனிக்கும்போது அந்நாளிலே சில கோயில்களேனும் தங்களுக்கெனத் தனியாகச் சேனை வீரர்களைக் கொண்டிருந்ததென்று கொள்வதில் தவறு இல்லை.

மேலே குறிப்பிட்ட பொலந்நறுவைச் சாசனம் வேளைக்காரரை 'மூன்றுகை வேளைக்காரர்' என்று கூறுகிறது. இதேபோல மூன்றுகை மஹாசேனை என்று தென்னிந்தியச்

சாசனங்களிலும் போர்ப்படையினர் குறிக்கப்பட்டுள்ளார்கள். வலங்கையும் இடங்கையும் போர்ப் படையின் இரு கைகள் போலும். மூன்றாவது கை என்னவென்பது எவ்விடத்திலும் கூறப்படவில்லை. இவற்றைக் கவனிக்கும்போது வலங்கை என்பது ஸாம்ராஜ்யத்தின் நிலையான படைப் பிரிவையும் இடங்கை என்பது வணிகர்களின் போர்ப்படைப் பிரிவை குறிப்பதாகக் கொள்ளலாம். மூன்றாவது கை கோயில் நிர்வாகத்தினர் நிறுவியிருந்த படைப்பிரிவேபோலும்.<sup>1</sup>

அந்நாளிலே வாணிபத் துறையில் பெருமையோடு விளங்கிய சிலரும் அரசாங்கத்தில் உயர்ந்த பதவி வகித்து வந்திருக்கிறார்கள் என்பது தெளிவாகத் தெரிகிறது. முதற் குலோத்துங்க சோழனுடைய ஆட்சியின் நாற்பத்தொன்பதாம் ஆண்டு எழுபதாம்நாள் கொண்டு திராக்ஷாராமத்தில் கிடைக்கும் தமிழ்க் கல்வெட்டு ஒன்று, இலங்கை மன்னனான விக்கிரம பாஹுவின் பிரதானியான உய்யவந்தான் திருவண்ணாமலை யன் விஜயபாஹு மாசாத்துநாயன் என்பான் தானம் அளித்த செய்தியைத் தெரிவிக்கிறது. (தே. இ. சாசனங்கள், நான்காம் வால்பூம், நெ. 1227.) மதுரை ஜில்லாவில் உள்ள விக்கிரமங்கலத்திலிருந்து கிடைக்கும் மாறவர்மன் பராக்கிரம பாண்டியன் என்னும் பாண்டிய மன்னனுடைய சாசனம் ஒன்றிலே பராக்கிரம பாண்டிய மாசாத்துவாயன் என்னும் அதிகாரி கையெழுத்திட்டிருக்கிறான். (ஜேம்ஸ் பர்ஜஸ், பண்டித நடேச சாஸ்திரி ஆகியோர் பதிப்பித்த தமிழ், ஸமஸ்கிருத சாசனங்கள், பக்கம் 14). மாசாத்துநாயன் என்ற அவர்களுடைய சிறப்புப் பெயரிலிருந்து அவர்களை வாணிபத் துறைத் தலைவர்களாகவே நாம் கொள்ளவேண்டும்.

இதுகாறும் கூறியவற்றால், குலோத்துங்கனுடைய ஆட்சியின் இரண்டாம் ஆண்டிலே வலங்கை-இடங்கையாக நடந்த தென்று ஸ்ரீரங்கம் கல்வெட்டில் குறிக்கப்பட்டுள்ள கலகம் சோழர்களுடைய ஸாம்ராஜ்யப் படைக்கும் வாணிபத் துறை

1. 'மூன்றுகை மஹாசேனை' என்பதை யானைப் படை, குதிரைப் படை, காலாட்படை என்னும் மூன்று பிரிவுகளைத் தன்னுள் அடக்கியசேனையாகக் கொள்ளவும் கூடும்.

யாரின் படைக்கும் இடையே நடந்த கலகம் எனக் கொள்ளலாம். கிழக்கிந்தியக் கம்பெனியார் நாளிலே 'அரசர்படை' என்றும் 'கும்பினிப்படை' என்றும் தனித் தனிப் பிரிவுகள் இருந்துவந்த விவரம் இந்தச் சமயத்திலே குறிப்பிடத் தக்கது.

அந்தக் கலகத்துக்குக் காரணம், அது எவ்விதம் நிகழ்ந்தது என்பன போன்ற விவரங்கள் இப்போது தெரியவில்லை. திருச்சிராப்பள்ளி ஜில்லாவில் உள்ள ஆடுதுறையிலிருந்து கிடைக்கும் கல்வெட்டு ஒன்று, அரசாங்க அதிகாரிகளுடைய ஆதரவுடன் வன்னியக் குடிமக்களும் வேளாளர் பிராமணர் போன்ற நிலச்சொந்தக்காரர்களும் சேர்ந்து இடங்கைப் பிரிவில் அடங்கிய தொண்ணூற்றெட்டுச் சாதியினருக்கு இழைத்த அநீதிகளைக் கூறுகிறது. (1913-ஆம் ஆண்டு 34-நெ. சாசனம்.) இதே போல இடங்கை வகுப்பார் அந்த அந்தக் காலங்களில் பட்ட கஷ்டங்களையும் ஏற்க வேண்டி வந்த வரிச்சுமைகளையும் தெரிவிக்கும் கல்வெட்டுகள் நாட்டின் பல பாகங்களிலிருந்தும் கிடைத்துள்ளன. இந்தச் சந்தர்ப்பத்தில் மைசூர் ராஜ்யத்து ஆவணியிலிருந்து கிடைத்துள்ள முதற்குலோத்துங்க சோழனுடைய ஆட்சியின் மூன்றாம் ஆண்டுக் கல்வெட்டு முக்கியமானது. அரசனுடைய ஆணைக்கிணங்கவே கூடிய பெரிய விஷயத்தாரின் முடிவைத் தெரிவிப்பது அந்தக் கல்வெட்டு. (1911-ஆம் ஆண்டு 461-நெ; எபி. கர்நாடிகா, பத்தாம் வால்பூம், முருபாகல் 49-உ. அன்றி அதே வால்பூம், முன்னுரை, xxviii-ஆம் பக்கமும் பார்க்க). நிகரிவிசோழ மண்டலத்து எழுபத்தெட்டு நாடுகளும் ஜயங்கொண்டசோழ மண்டலத்தின் நாற்பத்தெண்ணாயிரம் பூமியும், பெரும்படை வலங்கை மஹாஸேனைக்கு வழங்கப் பெற்ற இராஜேந்திர சோழப் பதினெண் பூமியும் உள்ளிட்ட நாடுகளில் சோழ வமிசம் தோன்றின நாள் முதலே பசு எருமைகளுக்கு என்றுமே வரி விதிக்கப் பட்டதில்லையென்றும், அதனால் அதிகாரிகள் சோழ மூவேந்தவேளான் புதிதாக விதித்த இவ் வரிகளைக் கொடுக்க வேண்டியதில்லை என்றும் அந்த விஷயத்தார் முடிவு கட்டினார்கள். அன்றி, பதினெட்டு விஷயங்களிலும் உள்ளவர்கள் கொடுக்க வேண்டிய வரி விதிதங்களையும் அவர்கள் நிச்சயத்து நிர்ணயித்தார்கள். இதே சாசனத்தின் பிரதி ஒன்று உத்தனூரிலிருந்தும் கிடைத்

துள்ளது. (1911-ஆம் ஆண்டு 458-நெ. எபி. கர்நாடகா, பத்தாம் வாஸ்யம்; முளுபாகல் 119; இன்னும் கோலார் 42-யும் பார்க்க. மைசூர் ஆர்க்கியலாஜி 3ல் ரிபேர்டு, 1909-10-ஆண்டு, பக்கம் 29).

இடங்கை வகையைச் சேர்ந்த வணிகக் குழுவினரைத் திருப்திசெய்து உற்சாகப்படுத்தவே இம்மன்னன் சுங்கத்தை எடுத்து விட்டான். ‘சுங்கம் தவிர்த்து இருணீக்கி உலகாண்ட வன்’ என்று இம்மன்னன் வடஆர்க்காடு ஜில்லாவில் உள்ள மருதாடு என்னுமிடத்திலிருந்து கிடைத்துள்ள ஒரு சாசனத்தில் குறிக்கப்பட்டிருக்கிறான். (1912-ஆம் ஆண்டு 408-நெ.)

குலோத்துங்கன் சோழ உலாவிலே

“புவிராச ராசர் மதுமுதலோர் நாளில்  
தவிராத சுங்கம் தவிர்த்தோன்”

(கண்ணி—26)

என்று காணப்படுகிறது. இதைக் கவனிக்கும்போது இவன் வணிகர்களுக்கு எவ்வளவு தூரம் சலுகைகள் வழங்கி இருக்கிறான் என்பதும் அவர்களுடைய நல்லெண்ணத்தையும் ஆதரவையும் பெற்று நிலைநிறுத்திக் கொள்ள அவன் எவ்வளவு தூரம் முயன்றிருக்கிறான் என்பதும் தெளிவாகும். சோழநாட்டிலே உள்நாட்டுக் கலகத்தைக் கிளப்பி அதிலே அதிராஜேந்திரன் உயிர்துறக்குமாறு செய்து அராஜகத்தை உண்டாக்கிச் சோழ சிங்காதானத்தைக் குலோத்துங்கன் கைப்பற்றுவதற்கு வழிகோலிய இடங்கை வகுப்பாரான வாணிபச் சுங்கத்தார் செய்த உதவிக்குப் பிரதிப்பிரயோஜனமாக இம்மன்னன் அவ்விதம் வரிகளை நீக்கிக் கொடுக்க வேண்டிய நிர்ப்பந்தம் ஏற்பட்டது போலும்.

குலோத்துங்க மன்னனுடைய ஆஸ்தானக் கவிஞராக இருந்த ஐயங்கொண்டார் தம்முடைய கலிங்கத்துப்பரணியில் அதிராஜேந்திரனைப் பற்றிப் பிரஸ்தாபிக்கவே இல்லை. இராஜேந்திரனுடைய பிள்ளைப்பருவத்தைப் பற்றிய சம்பிரதாய மான் வருணனைக்குப் பிறகு அபயன் அவனுக்கு இளவரசுப் பட்டம் கட்டினான் என்று கூறிவிட்டு அவனுடைய திக்கு விஜயத்தை வருணிக்க ஆரம்பிக்கிறார் கவிஞர். திக்கு விஜயத்திலும் வடநாட்டிலே வயிராகரம் சக்கரக்கோட்டம் ஆகிய

இடங்களிலே கொண்ட வெற்றியே முக்கியமாக இடம் பெற்றுள்ளது. 'சோழமன்னன் இறந்த சமயம் இராஜேந்திரனாகிய குலோத்துங்கன் வடக்கேதான் இருந்தான். அரசன் மரணத்தையொட்டிச் சோழநாட்டிலே அராஜகம் ஏற்பட்டது. குலோத்துங்கன் தென்னாடு போந்து அரசியலை மேற்கொண்டு அராஜகத்தைப் போக்கி நாட்டில் அமைதியைநிலைநாட்டினான். இதைக் கவிஞர் வெகு அழகாகவும் தத்ரூபமாகவும் சித்திரித்திருக்கிறார். ஆனால் வீக்கிரட்சோழன் உலாவிலோ வீரராஜேந்திரனுக்குப் பிறகு குலோத்துங்கன் சிங்காதனம் ஏறியதற்கு முன்னதாக. வேறு ஒரு சோழஅரசன் நாட்டை ஆண்டு வந்திருக்கிறான் என்பது,

—' அங்கவன்பின்

காவல்புரிந் தவனி காத்தோனும் '

(கண்ணி—22)

என்று தெளிவாகக் காணப்படுகிறது. 'வீரமே துணையாகவும்' என்று தொடங்கும் வீரராஜேந்திரன் மெய்க்கீர்த்தியைப் 'புகழ்மாதா விளங்க' என்று ஆரம்பமாகும் தன்னுடைய மெய்க்கீர்த்தியுடன் குலோத்துங்கன் இணைத்து ஒன்றாகியது, ஒருகால் வீரராஜேந்திரனுக்குப் பிறகு தானே உரிமையால் முறைப்படி சோழ சிங்காதானம் ஏறியவன் என்பதைக் காண்பிப்பதற்காகவேபோலும். (சாசன இலாகாவின் 1913-ஆம் ஆண்டு அறிக்கை பாரா 33.)

வேங்கி அரசைக் கைக்கொண்டிருந்தவனும் குலோத்துங்கனுடைய சிற்றப்பனுமான விஜயாதித்தியன் காலமான பிறகு குலோத்துங்கன் அந்நாட்டு அரசை மேற்கொண்டு தன் குமாரர்களை ஒருவன் பின் ஒருவனாக அங்கே பிரதிநிதியாக ஆட்சி நடத்துவதற்கு அனுப்பிவைத்தான். அவ்விதம் முதல் முதலாகத் தன் மகன் மும்முடிச்சோழனை அனுப்பியபோது அவனுக்கு வேங்கி அரசியலைப்பற்றிய பழைய சம்பவங்களை எடுத்துக் கூறியிருக்கிறான். அவ்விதம் பிரதிநிதிகளாகச் சென்றிருந்த ராஜராஜ சோடகங்கனுடைய டேக்கிச் செப்பேடுகள் (குலோத்துங்கன் ஆட்சியின் பதினேழாம் ஆண்டில் அளிக்கப்பட்டவை. எ. டி. இலக்கா, ஆறாம் வால்பூம், நெ. 35, வீர சோடகனுடைய செல்லூர்ச் செப்பேடுகள் (தந்தை ஆட்சி



யின் இருபத்தோராம் ஆண்டு கொண்டவை: தே. இ. சாசனங்கள், முதல் வால்பூம், நெ. 39; இன்னும் இந்தியன் ஆண்டிசுவரி, பத்தொன்பதாம் வால்பூம், பக்கம் 427) பிட்டபுரம் செப்பேடுகள் (இருபத்து மூன்றாம் ஆண்டு கொண்டவை; எபி. இந்திகா, ஐந்தாம் வால்பூம், நெ. 10) ஆகிய சாசனங்களில் இந்த வரலாறு ஒரேவிதமாக உள்ளது.

“இராஜராஜரேந்திரன் நாற்பத்தோராண்டிகள் அரசு செலுத்திய பிறகு இறந்து போனதும் இராஜேந்திரன் முதலில் வேங்கிநாட்டுக்கு அரசனாக முடிசூட்டப் பெற்றுப் பெரும்புகழ் எய்தினான். அப்பால் அவன் தேவேந்திரப் பதவிக்குக் கொஞ்சமும் குறைவில்லாத சோழராஜ்யத்தின் அரசனாக முடிசூட்டப் பெற்றான். சோழவமிச திலகமான இராஜேந்திர தேவனாகிய சமுத்திரத்திலிருந்து தோன்றிய இலக்சுமியான மதுராந்தகியை அவன் மணம் புரிந்து கொண்டான். அவளிடம் அம்மன்னனுக்கு ஏழு குமாரர்கள் பிறந்தார்கள். அவர்களுள் ஒருவனான இராஜராஜனுக்கு மன்னன், ‘குழந்தாய், திக்கு விஜயம் செய்ய வேண்டும் என்ற ஆசையினால் (இந்தப் பகுதி செல்லூர்ச் செப்பேடுகளிலே ‘சோழராஜ்யத்தை அடைய வேண்டும் என்று நான் ஆசைகொண்டதால்’ என்று காணப்படுகிறது.) வேங்கி என்னும் பேரரசை நான் முன்னாளிலே என் சிற்றப்பன் விஜயாதித்திய ராஜாவின் நிர்வாகத்திலே விட்டு வைத்தேன். பலத்திலே சிங்கத்தை நிகர்த்த அவரும் பதினைந்து ஆண்டுகள் ராஜ்யத்தை ஆண்டு தெய்வம்போன்ற அவர் சுவர்க்கத்தை அடைந்தார்’ என்று தெரிவித்தான்.”

வேங்கியைவிட்டு வெளியேறிய விஜயாதித்தியனைக் கீழைக்கலிங்க அரசனான இராஜராஜ தேவேந்திரவர்மன் மீண்டும் சிங்காதானத்தில் அமர்த்திய சமயத்தில் குலோத்துங்கன் சோழநாட்டு விவகாரத்திலே ஈடுபட்டு அதை ஒரு நிலைக்குக் கொணர முயன்று கொண்டிருந்தான். அப்போது விஜயாதித்தியனுக்கு உதவுவதற்காகக் குலோத்துங்கன் மீது கலிங்கமன்னன் நடத்திய படையெடுப்பிலே டாஹல தேசத்து (அதாவது சேதிநாட்டு) வேந்தனான யசக்கர்ணனும் ஈடுபட்டிருந்தான் என்று தெரிகிறது. கலசூரி அப்தம் 823 (அதாவது

கி. பி. 1073-ஆம் ஆண்டு கொண்ட அவனுடைய கைராச் செப்பேடுகளிலே, “யுத்ததந்திரத்திலும் ஆபுதவீச்சிலும் எவ்விதக் குறையும் இல்லாதிருந்தும் ஆந்திர மன்னனை அவன் சுலபமாகவெற்றி கொண்டு, அலைகளையே அழகியபுருவங்களாகவும் தன்னுடைய ஏழுக்கிளைகளில் பாயும் நீரின் சலசலப்பால் கிளம்புவதும் மதங்கொண்ட வண்டுகளின் ரீங்காரத்தொளிபோல இனிமையானதுமான சப்தஸ்வரங்களில் புகழ்ந்துபாடிச் செல்லும் கோதாவரி நதியால் சூழப்பெற்ற பீமேச்வரதேவருக்குப் பல ஆபரணங்களை அளித்து அவரை வழிப்பட்டான்” என்று கூறப்பட்டுள்ளது. (எபி. இந்திகா, பன்னிரண்டாம் வால்யூம், பக்கம் 213, சுலோகம் 23.) இவ்விடம் குறிக் கப்பட்ட பீமேச்வரர் திராக்ஷாராமத்தில் கோயில் கொண்டு எழுந்தருளியிருக்கும் பீமேச்வரரே ஆவர். குலோத்துங்கனுடைய ஆட்சிக் காலத்திலே வேங்கிநாட்டில் அரசு செலுத்தப் பிரதிநிதிகளாக அனுப்பப்பெற்ற சோழ ராஜகுமாரர்கள் திராக்ஷாராமத்திலே தான் தங்கியிருந்திருக்கிறார்கள். ஒரு நூற்றாண்டுக்குப் பிறகு சோழசிங்காதானத்துக்குப் போட்டியிட்டு வெற்றி கொண்ட மூன்றாம் குலோத்துங்கனால் விரட்டப் பட்ட இரண்டாம் இராஜாதிராஜன் வேங்கியில் தஞ்சம் புகுந்த காலத்தில் இவ்வூரிலேதான் தங்கிப் பெயரளவில் அரசனாக விளங்கி அரசமரியாதைகளை அனுபவித்து வந்திருக்கிறான். இவற்றைக் கவனித்தால் விஜயாதித்தியன் ஆட்சிக் காலத்திலும் இவ்வூரே தலைநகராக விளங்கியது எனக் கொள்ளலாம். ஆகவே கீழைக் கலிங்கமன்னன் இராஜராஜ தேவேந்திர வர்மனும் சேதி வேந்தன் யசக்கர்ணனும் சேர்ந்து விஜயாதித் தியனுக்கு உதவ வந்த சமயம் வேங்கியின் தலைநகரை அவர்கள் கைப்பற்றியே தங்கள் காரியத்தை முடித்தார்கள் எனக் கொள்ளலாம். இதிலிருந்து குலேத்துங்கன் அடைந்த தோல்வியின் பரிமாணம் ஓர் அளவு விளங்கும். விஜயாதித்தியனை வேங்கியிலிருந்து வெளியேற்ற முடியாதென்பதை உணர்ந்த குலோத்துங்கன் சமரசத்துக்கு வரவேண்டியதாயிற்று. அந்தச் சமயத்திலே அவன் சோழசிங்காதானத்தைக் கைப்பற்றி அங்கே தன் ஆட்சியை நிறுவிவிட்டபடியாலும், விஜயாதித் தியனுடைய முதுமையை உத்தேசித்தும் தன் சிற்றப்பன் பெயரளவிலாவது சோழர்களுடைய பேரரசை ஏற்று அதற்கு

அடங்கி நடப்பதாக ஒப்புக்கொண்டால் அவனை வேங்கியில் அரசு புரிந்து வருவதை அனுமதித்திருக்கவும் கூடும்.

இதுகாறும் கூறியவற்றால் குலோத்துங்கன் ராஜ்யபாரத்தை ஏற்றது பற்றிக் கல்வெட்டுக்களிலும் இலக்கியத்திலும் கூறப்படுவன எல்லாம் அந்த அந்த அளவுக்கு உண்மை என்பதும், ஆனால் அவை முழுவிவரங்களையும் கொடுக்காமல் அந்த அந்தச் சந்தர்ப்பத்துக்கு வேண்டிய மட்டிலே தெரிவிக்கின்றன என்பதும், அவை எல்லாவற்றையும் ஒருங்கே திரட்டிச் சேர்த்தே முழு உருவம் அளித்துச் சித்திரத்தைப் பூர்த்தி செய்யவேண்டும் என்பதும் நன்கு விளங்கும்.

முதற்குலோத்துங்க சோழன்

சோழராஜ்யத்தை முதற் குலோத்துங்கன் ஆண்டுவந்த காலத்தில் மேலைச் சாளுக்கிய ராஜ்யத்தை ஆறாம் விக்கிரமாதிர்த்தியன் அரசுபுரிந்து வந்தான். இருவரும் பலம்பொருந்தியவர்கள்; நீண்டகாலம், அதாவது ஐம்பதாண்டுகள், ஆட்சி செய்திருக்கிறார்கள். அவர்கள் காலத்திலே சோழ-சாளுக்கியர் உறவு எந்த நிலையில் இருந்தது என்பது கவனிக்கத் தக்கது. ஆரம்பத்தில் அவர்களுக்கிடையே இருந்த விரோதம் நீடித்து நின்றதா என்பதும் ஆராயத்தக்கது.

கங்கை கொண்ட சோழ புரத்துக் கோயிலின் சுவரிலே அகுண்டோத் கண்ட என்று தொடங்கும் காஹடவால வமிசத்துப் பிரசஸ்தியின் பெரும்பகுதி பொறிக்கப்பட்டுள்ளது. (1908-ஆம் ஆண்டு, 29 நெ. சாசனம். அதே ஆண்டின் சாசன இலாகா அறிக்கை, 58-60-ஆம்பாராக்களையும் பார்க்க). சாசனம் முதலிலே குலோத்துங்க சோழனுடைய ஆட்சியின் நாற்பத்தொன்றாம் (கி. பி. 1110-11) ஆண்டைக் கொடுத்து விட்டு மேலே பிரசஸ்தியை எழுத ஆரம்பிக்கிறது. ஆயினும் சந்திரதேவனைப் பற்றிய சுலோகத்தோடு திடீரென்று நின்றுவிடுகிறது. அதனால் சாசனகாலத்தில் அரசு செலுத்திய அரசன் பெயரையோ, சாசனம் கல்வில் வெட்டப்பட வேண்டிய சந்தர்ப்பத்தையோ, அது தெரிவிக்க வேண்டிய விவரத்தையோ காணவில்லை. காஹடவால மன்னர்களான மதனபாலனும் அவன் மகன் கோவிந்த சந்திரனும் அந்நாளிலே சோழமன்னனான குலோத்துங்கனுக்குச் சமகாலத்தவர்களாக ஆட்சி செய்தவர்

கள். இதுகாறும் கிடைத்துள்ள சாசனங்களில் மதனபாலனுடைய ஆட்சியைச் சேர்ந்ததாகக் கி. பி. 1109-ஆம் ஆண்டு கொண்ட ரஹன் செப்பேடுகளே காலத்தால் பிற்பட்டவை. (இந்தியன் ஆண்டிசுவரி, பதினெட்டாம் வால்பூம், 14-9 பக்கங்கள்). அதேபோல அவனுக்குப்பின் சிங்காதனம் ஏறிய கோவிந்த சந்திரனுடைய சாசனங்களிலே காலத்தால் முற்பட்டது கி.பி. 1114-ஆம் ஆண்டு கொண்டதாகும் (எபி. இந்திகா, நான்காம் வால்பூம், 101-103 பக்கங்கள்). எனினும் தந்தையின் ஆட்சிக் காலத்திலேயே மகனும் தந்தையோடு சேர்ந்து ராஜ்ய பாரத்தை வகித்து வந்திருக்கிறான். ஆகவே இந்தச் சாசனத்தை அளித்தவன் கோவிந்த சந்திரன் என்றே கொள்ளலாம்.

கோவிந்த சந்திரன் ஆட்சிக் காலத்திலே கி.பி. 1129-ஆம் ஆண்டு கொண்டதாக உள்ள செப்பேட்டுச் சாசனம் (ஷெ. பதினேராம் வால்பூம், நெ. 3) ஒன்றில் உத்கல தேசத்துச் சாக்கிய ரக்ஷிதர் சிஷ்யரும் சோட (சோழ) தேசத்துவருமான ஸௌகத பரிவ்ராஜக மஹாபண்டிதர் வாசிசுவர ரக்ஷிதர் என்னும் புத்தமதப் பெரியார் குறிக்கப்பட்டுள்ளார். இன்னும் தஞ்சாவூர் ஜில்லாவில் சூரியனார் கோவில் என்னும் ஊரிலே குலோத்துங்கன் தன் பெயரில் குலோத்துங்க சோழ மார்த்தாண்டாலயம் என்று சூரிய பகவானுக்கு ஒரு கோயில் எடுப்பித்திருக்கிறான். (சாசன இலாகாவின் 1927-ஆம் ஆண்டு அறிக்கை, 19-21 பாராக்கள்). காஹடவால மன்னர்கள் சூரிய வழிபாட்டிலே சிறந்து விளங்கியவர்கள். சூரியனார்கோயிலிலே விசுவேசுவர சுவாமி, விசாலாக்ஷி அம்மன் ஆகியோரும் பிரதிஷ்டை செய்யப்பெற்றிருக்கிறார்கள். அவர்கள் இன்றைக்கும் காசி கேஷத்திரத்தில் கோயில் கொண்டு எழுந்தருளி யிருப்பதை யாவரும் அறிவர்.

காசி கேஷத்திரமும் காஹடவாலர்களுடைய ஆட்சியில் அடங்கியிருந்தது. ஆகவே குலோத்துங்கன் மார்த்தாண்டாலயமான சூரியன் கோவில் எழுப்பியது அவனுக்குக் காஹடவாலர்களுடன் இருந்த தொடர்பின் விளைவே எனக் கொள்வதில் தவறு ஒன்றும் இல்லை. இவற்றால் இராஜேந்திர சோழன் காலம் முதலே வடநாட்டில், முக்கியமாகக் கன்யா

குப்ஜ தேசத்தின் மீது, சோழர்களுக்கு இருந்த ஆதிக்கியம் குலோத்துங்கன் காலத்திலும் குறைபாமல் இருந்தது என்பது விளங்கும்

காஹடவாலர்களே கன்யாகுப்ஜப் பிரதேசத்தைச் சமீப காலத்தில் தான் அரசு செலுத்த ஆரம்பித்தார்கள். அந்த வமிசத்தின் முதல் அரசனான சந்திரதேவன் தான் 'தன்னுடைய புஜபல பராக்கிரமத்தால் கன்யாகுப்ஜத்தின் புகழ் பெற்ற அரசரிமையை அடைந்தான்'. (நிஜ புஜோ பார்ஜித் கன்யாகுப்ஜாதிபத்ய ஸ்ரீசந்திரதேவ :- இந்தியன் ஆண்டிசுவரி, பதினெட்டாம் வால்பூம், பக்கம் 18). அவனுடைய சாசனங்களிலே காலத்தில் முற்பட்டது கி.பி. 1090-ஆம் ஆண்டு கொண்டதாகும். (எபி. இந்திகா, ஒன்பதாம் வால்பூம், 302-305 பக்கங்கள்.) பிற்பட்டது கி. பி. 1100-ஆம் ஆண்டு கொண்டதாகும். (ஷெ பதினான்காம் வால்பூம், 197-200 பக்கங்கள்.) அவன் தன்னுடைய வலிமையால் நரபதி, கஜபதி, திரிசங்குபதி, கிரிபதி ஆகியோர்களை வெற்றிகொண்டான்.<sup>1</sup> (ஷெ பக்கம் 193.) அன்றி 'காசி, குசிகம், உத்தரகோசலம், இந்திரஸ்தானம்

1. இந் நான்கு பெயர்களில் திரிசங்குபதி, கிரிபதி ஆகிய இரண்டும் வேறு இடங்களிலே காணப்பெறவில்லை. அவை இரண்டும் யாரைக் குறிப்பிடுவன என்பதும் தெரியவில்லை. கிரிபதி என்பது பெரும்பாலும் மலைப் பிரதேசமாக அமைந்த ஒரு நாட்டு அரசனைக் குறிப்பதாகக் கொள்ளலாம். எனினும் திரிசங்குபதி யாரைக் குறிக்குமென்பது தெரியவில்லை. நேபாளத்தின் மூன்று முக்கிய நகரங்களுள் சங்கு என்பதும் ஒன்று. (மற்ற இரண்டும் கட்மண்டுவும் பட்டணமும் ஆகும்). முதலாம் இராஜேந்திரனுடைய வட நாட்டுப் படையெடுப்பின் போது அவன் 'சங்கோட்டல் மஹிபாலனை வெற்றி' கொண்டான் என்று அவன் மெய்க்கீர்த்தியில் காணப்படுவதிலிருந்து சங்கு என்பான் ஒருவன் பெயர் தெரிகிறது. திரிசங்குபதிக்கும் இந்த இரு பெயர்களிலே ஏதாவது ஒன்றுக்கும் சம்பந்தம் உண்டா என்பது தெரியாது. இன்னும் புராணப் பிரசித்தியுடையவனும் விச்வாமித்திரரால் ஆதரிக்கப்பெற்றவனுமான திரிசங்கு வேறு இருக்கிறான். அவனுக்காக முனிவர் புதிய உலகம் ஒன்றையே சிருஷ்டித்தாரே. ஸி-யு-கீ என்னும் சீன நூலிலே ஜம்பூத்வீபம் முழுவதையும் ஒருகுடைக் கீழ் ஆளும் ஏகசக்கராதிபதி இல்லாத சமயங்களில் அதன் தெற்குப் பகுதியைக் கஜபதியும் மேற்குப் பகுதியைச் சந்திரபதியும், வட்பாகத்தை அசுவபதியும் கிழக்குப் பாகத்தை நரபதியும் ஆண்டுவருவார்கள் என்று குறிக்கப்பட்டுள்ளது. (பீல் என்பாரின் பதிப்பு, முதல் பாகம், பக்கம் 13, குறிப்பு.)

ஆகிய புண்ணிய தீர்த்தங்களைக் கைக்கொண்டு பரிபாலனம் செய்துவந்தான். (இந்தியன் ஆண்டிசுவரி, பதினாண்டுகாம் வால்பூம், பக்கம் 7-8 - தீர்த்தாநி காசி குசி கோத்தர கோச லேந்தரஸ்தாநீயகாநி பரிபாலய தாதிகம்ய). காசி கேஷத் திரம் யாவரும் அறிந்ததே. குசிகம் என்பது கன்யாகுப்ஜத் தையே குறிக்கும். உத்தரகோசலம் என்பது அயோத்தியைச் சுற்றியுள்ள பிரதேசமாகும். இந்திரஸ்தானம் என்பது இந்திரப்ரஸ்தம் அதாவது முற்காலத்திய தில்லி நகரம் ஆகும் எனக் கொள்வார். (ஷே பதினெட்டாம் வால்பூம், பக்கம் 13, கீழ்க் குறிப்பு 33.) இதைக் கவனித்தால், இப்போது உத்தரப்பிரதேசம் என்று வழங்கப்பெறும் பகுதி முழுவதும் சந்திரதேவனுடைய அரசில் அடங்கியிருந்த தென்பது விளங்கும்.

அவனும் முஸ்லிம்களோடு போரிட வேண்டிய சந்தர்ப்பம் நேர்ந்திருக்கின்றதென்றே தெரிகிறது. ஹிந்துஸ்தானத்தின்மீது படையெடுத்துவந்த மம்லுதின் பெயரானும் முதலாம் மஸூதின் மகனுமான இப்ரஹீம் கி. பி. 1059-ஆம் ஆண்டு கஜ்னியிலே சிங்காதனம் ஏறிக் கி.பி. 1099-ஆம் ஆண்டு வரையில் ஆட்சி புரிந்தான். தன் அரசிலே அடங்கியிருந்த இந்தியப் பிரதேசங்களுக்கு அவன் தன் மகன் மம்லுதைக் கி. பி. 1075-ஆம் ஆண்டில் பிரதிரிதியாக நியமித்தான். மம்லுதும் ஹிந்துஸ்தானத்தின் பல பகுதிகளிலும் படைநடத்திச் சென்றான். அவன் படை சென்ற இடமெல்லாம் வெற்றி தாலும். 'அவன் வாள்வீச்சைத் தாங்கமுடியாமல் ஆக்ரா நகரம் கீழ்ப்படிந்தது. ஹிந்து மன்னர்கள் அநேகர் அவனுக்கு அடிபணிந்தனர். சுற்றுப்பிரதேசத்திலிருந்த அரசர்கள் அவனுக்கு அளித்த காணிக்கைகளில் ஏராளமான யானைகளும் இருந்தன. அந்த யானைகளைக் கட்டிவைப்பதற்காகக் கன்யாகுப்ஜ நகரில் யானைச்சாலைகளை அமைத்து அவற்றைப் பராமரிக்கும் பொறுப்பை ஏற்கச் சந்தராய் நியமிக்கப்பட்டான்.' (எல்லியட்டும் டௌஸனும் மொழிபெயர்த்து வெளியிட்ட இந்தியதேச சரித்திரம் மூலநூலாசிரியர்கள் கூறியபடியே; நான்காம் வால்பூம், 524-ஆம் பக்கம்). இந்தச் சந்தராய் என்பாளைக் காஹட்வால் மன்னனான சந்திரதேவன் என்றே ஆராய்ச்சியாளர்கள் கொள்வர்.

கன்யாகுப்ஜத்தை வெற்றிகொண்ட மம்மூது தன் கவனத் தை மாளவத்தின் மீது திருப்பினான். அந்தப் படையெடுப்பைப் பற்றி ஸல்மான் என்னும் பாரசீகக் கவிஞர் குறிப்பிட்டிருக்கிறார். ஸுல்தான் இப்ரஹீம், மம்மூத் ஆகியவர்கள் காலத்தில் இருந்த அந்தக் கவிஞர் மஹுத் இபன் சாத் இபன் ஸல்மான் எனப்படுவார். பொதுவாக ஸல்மான் என்றே குறிக்கப் பெறுவர். மம்மூதுக்கு எழுதிய ஒரு மனுவிலே இந்தப் படையெடுப்பைப் பற்றிக் கவிஞர் பின்வருமாறு எழுதுகிறார்: “நீ-படைபதைக்கும் வெய்யில் கொளுத்தும் கோடைக்காலத்திலே ஒவ்வொரு மாகாணத்திலும் மிக்க மரோம்மமான இடங்களிலே பாடியிறங்கியிருந்தாய். அந்தப் படையெடுப்பிலே உன் சேனை விக்கிர ஆராதனை புரியும் ஆயிரம் கோயில்களை அழித்தது. அரண்வலிகொண்ட நூற்றுக்கு மேற்பட்ட கோட்டை கொத்தளங்களை உன்னுடைய யானைகள் மிதித்து நசுக்கின. உன் படை உஜ்ஜயினுக்குச் சென்றது. உன்னைக் கண்டு நடுங்கி மாளவன் ஓடிப்போனான்” (ஷெ. பக்கம் 525). அந்நாளிலே லக்ஷ்மதேவன் மாளவ நாட்டு அரசனாக இருந்தான் எனத் தெரிகிறது. நாகபூர் பிரசஸ்தியின்படி (எபி. இந்திகா, இரண்டாம் வால்யூம், 185-195 பக்கங்கள்) உதயாதித்தியனுக்குப் பிறகு அவனுடைய குமாரர்களான இம்மன்னனும் இவன் தம்பி நரவர்மனும் ஒருவன் பின் ஒருவனாக நாட்டை ஆண்டுவந்தார்கள். லக்ஷ்மதேவன் ‘துருஷ்கர்களைச் சுலபமாக அழித்தான்’ என்றும் (கங்கையின் ஒரு சிறு கிளை யான) வங்கும் என்னும் நதி தீரத்தில் பாடியிறங்கியிருந்த காலத்தில் துருஷ்கர்கள் அவனுக்குத் துடி துடிப்புள்ள அநேக குதிரைகளைக் காணிக்கை செலுத்தினார்கள் என்றும் அந்தச் சாசனம் கூறுகிறது.

அந்நாளிலே மாளவதேசத்துக்கும் கன்யாகுப்ஜத்துக்கும் ஏதோ ஒருவிதத்தில் தொடர்பு இருந்ததென்று தெரிகிறது. மூன்றாம் மஸூதின் ஆட்சிக் காலத்தில் (சுமார் கி. பி. 1099-1115 ஆண்டு) கங்கை-யமுனைப் பிரதேசத்தில் இதே போன்ற மற்றொரு முஸ்லிம் படையெடுப்பு நடைபெற்றதென்று தபகாத்-நாஷீர் என்னும் நூல் கூறுகிறது. “ஹிந்து ஸ்தானத்திலே புனிதயுத்தம் புரிவதற்காக ஹாஜிப் துஜாதி கீன் கங் நதியைக் கடந்து, ஸுல்தான் மம்மூதைத் தவிர

வேறு யாரும் அதற்குமுன் படையோடு சென்றறியாத ஓர் இடத்தைச் சென்றடைந்தான்.” (ராவெர்ட்டியின் மொழி பெயர்ப்பு, முதல் வால்பூம், பக்கம் 107). இந்தப் படையெடுப்பைப் பற்றிய விவரங்கள் சில மேலே குறிப்பிட்ட கவிஞர் ஸல்மான் இயற்றிய பாடல்களில் காணப்படுகின்றனபோலும். கன்யாகுப்ஜத்தை “இந்தியாவின் தலைநகரம், ஷாமன்களுடைய காபா அல்லது காபிரிகளின் கிப்லா போன்றது” என்று அவர் குறிப்பிடுகிறார். “சிற்றூறுகள் எல்லாம் பெரிய நதியிலே விழுந்து கலப்பதுபோல இந்தியாவின் செல்வம் முழுவதும் இந்நகரத்துக்கு வந்து சேருகின்றன. அங்கே யானைப்படை, போர்க் களங்கள் ஆகியவை சிறைந்து செல்வம் கொழிக்கிறது.” அதன் அரசன் மல்ஹி அல்லது மல்ஹிரா எனப்படுபவன் வலிமை மிக்கவன். ‘கொடும்புலிபோன்ற கோபம் வாய்ந்தவன்.’ இவ்வளவு வீரமும் செல்வமும் பெற்றிருந்தானாயினும் அவனை மூன்றாம் மஸூது வென்று சிறைப்படுத்தி விட்டனாம். பெருந் தொகையை மீட்சி பணமாகக் கொடுத்து அவன் தன்னை மீட்டுக் கொள்ளவேண்டிய தாயிற்றும். (எல்லியட், டௌஸன் ஆகியோர் மொழிபெயர்த்து வெளியிட்ட இந்தியதேச சரித்திரம், நான்காம் வால்பூம், 526-27 பக்கங்கள்).

இவ்விடம் குறிக்கப்பட்டுள்ள அரசன் மல்ஹி அல்லது மல்ஹிரா என்பான் யார் என்பது தெளிவாகத் தெரியவில்லை. கன்யாகுப்ஜத்தை ஆண்ட காலஹடவால மன்னன் மதனபாலனாகவே அவன் இருத்தல் வேண்டும் என்று ஆராச்சியாளர் கருதுவர். (டாக்டர் எச். ஸி. ராய் எழுதிய வடஇந்தியாவின் வம்சவாரி சரித்திரம், முதல் வால்பூம், 515-ஆம் பக்கம்). உதயாதித்தியனுடைய மற்றொரு மகனான ஜகத்தேவனுடைய ஜைனாத் கல்வெட்டிலிருந்து (எபி. இந்திகா, இருபத்திரண்டாம் வால்பூம், நெ.11) அவன் தோரசமுத்திரத்திலே (அதாவது துவாரசமுத்திரத்திலே) மலஹரன் என்னும் அரசனுடைய போர் வீரர்கள் பலரைக் கொன்று வெற்றி கொண்டான் என்ற செய்தி தெரியவருகிறது.

மத்யேதோர ஸமுத்ர மத்ரி சிகரா  
காரம் கபாலவலி



மாலோக்ய த்விரதேந்த்ரத தந்த முஸல  
ப்ரந்தஸ்ப்ரிசம் ப்ரேயஸாம் ।

ஸாத்ரந்தை : ப்ரதி மந்திரம் மலஹர  
கேஷாணீச சித்தோதரே  
சூலம் பல்லவயாந்தி வாவ்ப ஸலிலேர்  
யத்வைரிணம் வல்லபா : ॥

“எதிரிகளுடைய யானைகளின் உலக்கைபோன்ற தந்தங்  
களால் தாக்குண்டு போரில் இறந்தவர்களின் மண்டையோடு  
கள் மலைச்சிகரம் போலக் குவிந்துகிடப்பதைக் கண்டு தோர  
சமுத்திரத்தில் ஒவ்வொரு வீட்டிலும் அழும் விதவைகளின்  
துக்கக்குரல் மலஹர கேஷாணீசன் (அதாவது மலஹர மன்ன)  
னுடைய சித்தத்திலே பெருந்துக்கத்தை உண்டாக்குகிறது.”

“சுலோகத்திலே மலஹரகேஷாணீச என்று வரும் சொல்  
ஹோய்சள மன்னர்கள் தரித்துவந்த மலபரோள் கண்ட என்  
னும் கன்னடவிருதின் மொழிபெயர்ப்பாகவே காண்கிறது.  
மலப அல்லது மலஹ என்பது ஹோய்சளர்களுடைய மூதாதை  
யரான ஏதோ சமூகத்தாரின் பெயர் என்று கருதப்படுகிறது.  
(எபி. கர்நாடிகா, ஆறாம் வால்யூம், முன்னுரை பக்கம்-14). இது  
அவர்களையே குறிக்கும்.” (எபி. இந்திகா, இருபத்திரண்டாம்  
வால்யூம், பக்கம் 58-கீழ்க்குறிப்பு 5). அந்நாளிலே ஹோய்சளர்  
கள் மேலைச்சாளுக்கிய அரசனை ஆறாம் விக்கிரமதித்தியன்  
கீழ்ச் சிற்றரசர்களாக விளங்கியவர்கள். மாளவ தேசமும் அந்  
நாளிலே விக்கிரமதித்தியனுடைய ஆட்சியில் அடங்கியிருந்  
தது. இது நாகபூருக்கு ஆறு மைல் கிழக்கே உள்ள சீதபட்டி  
என்னுமிடத்திலிருந்து கிடைத்துள்ள அவனுடைய கி. பி.  
1087-ஆம் ஆண்டு கொண்ட சாசனத்தால் (ஹெ. மூன்றாம்  
வால்யூம், பக்கம்-304) நன்கு தெரியவரும்.

அந்நாளிலே மாளவதேசத்துக்கும் ஹோய்சள மன்னர்க  
ளுக்கும் ஏதோவொருவகையில் சம்பந்தம் இருந்துவந்ததென்  
பது பின்வருவதால் விளங்கும் அணலிலபாடக நகரத்தைத்  
தலைநகராகக்கொண்டு அரசு செலுத்திய கூர்ஜ்ஜர நாட்டுச்  
சௌலுக்கிய மன்னன் குமாரபாலன் (கி.பி. 1144-ஆம் ஆண்டு

முதல் 1173-ஆண்டு வரையில் அரசு செலுத்தியவன்) மாவை நாட்டு மன்னனான பல்லாளன் என்பாளை வெற்றி கொண்டதாகப் புகழ்ப்பெறுகிறான். ஆன்னன், அதாவது ஸபாதலையும் எனவும் சாகாம்பரீ எனவும் குறிக்கப்படும் பிரதேசத்தை ஆட்சிபுரிந்துவந்த அர்ணோராஜன் என்பாளைக் குமாரபாலன் வெற்றி கொண்டதும், அவன் பல்லாளனையும் வென்று அடிப்படுத்திப் புகழ்பெற வேண்டும் என்று அவனுடைய மந்திரிகள் ஆலோசனை கூறினார்களாம். த்வயாசிரயம் என்னும் நூல் இவ்விதம் கூறுகிறது. அவன் எதற்காகப் பல்லாளன் மீது படையெடுத்துச் செல்ல வேண்டுமென்று அவர்கள் கூறின காரணத்தை ஹேமசந்திரர் மற்றோர் இடத்திலே தெரிவித்திருக்கிறார். அர்ணோராஜன் தான் கூர்ஜ்ஜரத்தின் எல்லையை மீறி உள்ளே நுழைவதற்கு முன்னதாக அவந்தி மன்னனான பல்லாளனுடன் தோழமை பூண்டு ஒப்பந்தம் செய்துகொண்டானாம். அதன்படி இருவரும் சௌலுக்கிய ராஜ்யத்தை வடக்கிலிருந்தும் கிழக்கிலிருந்தும் ஒரே சமயத்தில் தாக்க வேண்டுமாம். (இந்தியன் ஆண்டிதவரி, நான்காம் வால்பூம், பக்கம் 268).

அரசனான குமாரபாலன் பட்டணத்துக்குத் திரும்பிவந்த பிறகு அவனுக்குப் பின்வரும் செய்தி எட்டியது. “அர்ணோராஜன்மீது மன்னன் படைநடத்திச்சென்ற சமயம் பல்லாளனை எதிர்ப்பதற்காக அவன் அனுப்பிய சாமந்தர்களான விஜயன், கிருஷ்ணன் ஆகிய இருவரும் உஜ்ஜயினி அரசனோடு (அதாவது பல்லாளனோடு) சேர்ந்து கொண்டு விட்டனர். அம் மன்னனும் கூர்ஜ்ஜர தேசத்துக்குள்ளே புகுந்து அணலில்ல புரத்தை நோக்கித் தன் படைகளுடன் வந்து கொண்டிருந்தான்.” இதைக் கேள்வியுற்ற குமாரபாலன் தன் படைகளைத் திரட்டிப் பல்லாளனை எதிர்த்துப் போர்புரிந்து அவனைத் தோற்கடித்து யானையின் மீதிருந்து கீழே தள்ளினான். இவ்விடம் குறிக்கப்பட்ட அர்ணோராஜன் என்பவன் கூர்ஜ்ஜர தேசத்தைக் குமாரபாலனுக்கு முன்னதாக அரசாண்ட சித்தராஜ-ஜயஸிம்ஹனுடைய மருமகனும் நம்பிக்கை வாய்ந்த சிற்றரசனும் ஆவான். குமாரபாலனோ சித்தராஜ-ஜய ஸிம்ஹனுடைய மகன் அல்ல; தாயத்தாரில் ஒருவன். அவன் இறந்த அரசனுடைய ஸ்ரீகார குமாரனை விரட்டிவிட்டுச் சிங்கா

தனத்தைக் கைப்பற்றிக் கொண்டான். ஆகவே அர்ஜுன ராஜன்மீது குமாரபாலன் படையெடுத்துச் சென்றது அங்கே ஏற்பட்ட தாயாதிச்சண்டையின் விளைவே என்பது தெளிவாகும்.

குமாரபாலன் தன்னுடைய தண்டநாயகனும் கூர்ஜ்ஜர பிரம்ம சேநானி என்று புகழப் பெற்றவனுமான கர்க்கன் அல்லது காகன் என்பவன் வசம் பெரும் படையை மாளவத்துக்கு அனுப்பினான். கர்க்கன் அப்போது நந்தபுரியிலே லாட தேசத்துப் படையை நிர்வகித்து வந்தவன். அபு மலைப் பிரதேசமான அத்து மண்டலத்துப் பரமாரவமிசக் கிளையைச் சேர்ந்த அரசன் யசோதவளனும் அந்தப் படையெடுப்பிலே முக்கியமான தண்ட நாயகனாக விளங்கியிருக்கிறான். இது அபு மலையிலிருந்து கிடைக்கும் தேஜப்பாலனுடைய பிரசஸ்தியிலிருந்து தெரியவரும்:

ரோத : கம்தரவார்த்தி கீர்த்தி லஹரீ  
விப்தாம்ரிதாம்ச த்யுதேர்  
அப்ரத்யும்ந வசோ யசோதவல இத  
யாஸீத் தநூஜஸ் தத : |  
யச் செளலுக்ய குமாரபால ந்ரிபதி  
ப்ரத்யார்த்திதா மாகதம்  
மத்வா ஸத்வர மேவ மாலவபதிம்  
பல்லாஸ மாலப்தவான் ||

மாலவ பதியான பல்லாஸன் “செளலுக்கிய மன்னனான குமாரபாலனுக்கு விரோதமாகப் போய்விட்டான் என்ற செய்தியைக் கேட்டவுடனே அவனை யசோதவளன் விரைவில் கொன்றான்” என்று அது கூறுகிறது. (எபி. இந்திகா, எட்டாம் வால்யூம், 210-16-ஆம் பக்கங்கள் சுலோகம் 35.) பல்லாஸனுக்கு எதிராக இந்தப் படையெடுப்புக்குத் தலைமை தாங்கிச் சென்ற கர்க்கனுக்கும் வெற்றி சலபத்தில் கிட்டுவதாக இல்லை. குமாரபாலனுடைய சாமந்தர்களான விஜயன், கிருஷ்ணன் ஆகிய இருவரும் பகிரங்கமாகவே பல்லாஸனுடன் சேர்ந்துகொண்டனர். “சேனைத் தலைவர்கள் எவ்வளவோ தூண்டியும் ஒரு சமயம் கூர்ஜ்ஜர சேனை பின்வாங்கத் தொடங்கியது. எனினும் தலை

வன் மிகுந்த உற்சாகத்துடன் ஊக்கியதால் உணர்ச்சி யெழுந்த படையினர் மும்முரமாகத் தாக்கி, பல்லாளனை அவன் ஏறியிருந்த யானையின் மீதிருந்து கீழே இறக்கிக் கூர்ஜ்ஜர பிரம்ம சேநானியின் முன்னதாகக் கொன்றார்கள்.' (இந்தியன் ஆண்டி குவரி, நான்காம் வால்பூம், பக்கம் 268); த்வயாச்ரயம், பதினான்காம் அத்தியாயம், 22-23 சுலோகங்கள்; பிரபந்த சிந்தாமணி, பக்கம் 95; வஸந்தவிலாசம், மூன்றாம் அங்கம், 29 சுலோகம்).

இவ்விதம் மாலவதேசமன்னனை பல்லாளன்மீது குமாரபாலன் கொண்ட வெற்றி பாவபிரஹஸ்பதியின் வேராவல் (வீரதவளபட்டணம்) பிரசஸ்தியினின்றும் தெரியவருகிறது. அதிலே பாவபிரஹஸ்பதியின் தலைவனான குமாரபாலன் "தாரா அரசனான பல்லாளன்போன்ற மத்தகஜங்களின் தலையிலே தாவிக்குதிக்கும் சிங்கம்" என்று புகழப்பட்டிருக்கிறான். (ராயல் ஏஷியாடிக் ஸோஸைட்டி, பஃபாய்க் கிளையின் பத்திரிகை, எட்டாம் வால்பூம், 59-ஆம் பக்கம் முதல்). அதேபோல வாடநகர் பிரசஸ்தியிலும் அவன் மாலவமன்னன் தலையைவெட்டிக் கொணர்ந்து தொங்கவிட்டுச் சண்டிதேவியை வழிபட்டு அவள் உள்ளத்தைக் குளிர்வித்தான் என்று கூறப்பட்டுள்ளது. (எபி. இந்திகா, முதல் வால்பூம், பக்கம் 302, சுலோகம் 15.)

இவ்விதம் பல்லாளன் எல்லா இடங்களிலும் தாரா நகரத்தைத் தலைநகராகக் கொண்டு அரசு செலுத்திய மாலவதேசத்து அரசன் என்றே குறிக்கப்பட்டுள்ளான். அந்தப் பெயர் ஹொய்சளர்களிடையே தான் சகஜமாகக் காணப்படுவது. அவர்கள் கல்யாணபுரத்தைத் தலைநகராகக் கொண்டு ஆண்டுவந்த மேலைச்சாளுக்கியர்களுக்கு அடங்கிய சிற்றரசர்களாக ஆட்சி புரிந்தவர்கள். மாலவதேசத்துப் பரமாரர்களும் அவ்விதம் இருந்தவர்களே. சுமார் கி. பி. 1100-ஆம் ஆண்டு முதல் 1150-ஆம் ஆண்டு வரையில் அரசு செலுத்திய ஹொய்சள மன்னனான விஷ்ணுவர்த்தனனுக்குப் பல்லாளன் என்ற மகன் ஒருவன் இருந்திருக்கிறான். கி. பி. 1130-ஆம் ஆண்டு கொண்ட ஒரு சாசனத்திலே அவன் ஸ்ரீமத் திரிபுவனமல்ல குமார' பல்லாள தேவன் என்றும், விஷ்ணுவர்த்தனனுடைய (அக்ரதனுஜ) மூத்தகுமாரன் என்றும், அப்போது ராஜ்ய பாரத்தை கிரிவகித்து வந்தான் என்றும் கூறப்பட்டுள்ளது,

(எபி. கர்நாடிகா, ஆறாம் வால்பூம், முத்தெரெ 22). குமார பாலன் வெற்றிகொண்ட மாலவாதிபதியான பல்லாளன் இவனே போலும்.

இவற்றைக் கொண்டு கவனித்தால், அந்நாளிலே மேலைச் சாளுக்கிய மன்னர்கள் தங்களுடைய ஸாம்ராஜ்யத்தின் வட பகுதியிலே மாளவம்போன்ற தேசங்களை நிர்வகிப்பதற்காக ஹொய்சள இராஜகுமாரர்கள் சிலரைப் பிரதிரிதிகளாக அனுப்பிவைத்திருந்தார்கள் என்பதும், பல்லாளன் அவர்களிலே ஒருவன் என்பதும், அவ்விதம் அனுப்பப்பெற்ற பிரதிரிதிகள் கன்யாகுப்ஜப் பிரதேசத்தையும் தங்கள் மேற்பார்வையிலே கொண்டிருந்தார்கள் என்பதும் பெறப்படும்.

அதே சமயம் கன்யாகுப்ஜப் பிரதேசத்திலே ராஷ்டிரகூட வமிசத்தைச் சேர்ந்த இராஜகுமாரர்கள் சிலரும் ஆண்டு வந்திருக்கிறார்களெனத் தெரிகிறது. விக்கிரம சம்வத்ஸரம் 1176, அதாவது கி. பி. 1119-20 ஆம் ஆண்டு கொண்ட ஸைத்-மாஹேத் புத்தமதக் கல்வெட்டு ஒன்றிலே காதீபுராதிபர்களான கோபாலன், அவன் மகன் மதனன் ஆகியோர்களுடைய பெயர்கள் காணப்படுகின்றன. (இந்தியன் ஆண்டி குவரி, பதினேழாம் வால்பூம், பக்கங்கள் 61-64). காதீபுரம் என்பது கன்யாகுப்ஜத்தின் மறுபெயரே. லக்கணபாலனுடைய புதாவன் செப்பேடுகளிலே (எபி. இந்திகா, முதல் வால்பூம், 61-66 பக்கங்கள்) காணும் ராஷ்டிரகூட அரசர்களுடைய வமிசாவளியிலே அதே பெயர்களைக் கொண்டு வரும் அரசர்களே யாவர் போலும், அவர்கள். (ஜர்னல் ஆப் தி ஏஷ்யாடிக் ஸோஸைட்டி ஆப் பேங்கால், 1925, பக்கம் 105 முதல்). சோழர், சாளுக்கியர் ஆகிய இருவரும் வடநாட்டிலே தங்களுக்கிருந்த ஆதிக்கியத்தை நிலைநிறுத்திக் கொள்வதற்காகப் பெரிதும் முயன்று வந்தார்கள் என்றும், அதன் பயனாக ஒவ்வொருவரும் தங்கள் தங்கள் பிரதிரிதிகளை அங்கே நிறுவியிருந்தார்கள் என்றும் கொள்ளக்கூடும்.

ஆனால் இது சாத்தியமாவதற்கு அந்தப் பேரரசுகள் இரண்டும் தங்களுக்குள் இருந்த நீண்டகாலப் பகையை மறந்து ஏதோவொருவகையான சமாதானத்துக்குத் தற்காலிகமாக

வாவது வந்திருக்கவேண்டும். ஸ்ரீரங்கம் ரங்கநாதர் ஆலயத் திலிருந்து கிடைக்கும் ஒரு கல்வெட்டிலிருந்து (1942-ஆம் ஆண்டு 204 நெ.) இவ்வித நிலை அப்போது இருந்து வந்த தென்று தெரிகிறது. முதற் குலோத்துங்க சோழனுடைய ஆட்சியின் இருபத்தொன்பதாம் ஆண்டிலே மேலைச் சாளுக் கிய மன்னனை ஆறாம் விக்கிரமாதித்தியனுடைய கன்னட ஸந்தி விக்கிரஹியும் தண்டநாயகனுமான அதிகாரி ஒருவன் இரண்டு விளக்கு எரிப்பதற்கான கிபந்தங்களை அளித்த செய்தியைக் கூறுகிறது அந்தக் கல்வெட்டு. இன்னும், அவன் அந்த ஆலயத்திலே ஸௌநபதிக்கு அதாவது விஷ்வக்ஸேன ருக்குச் செங்கல்லும் சுண்ணாம்பும் கொண்டு ஒரு கோயில் எழுப்பினான் என்றும் தெரியவருகிறது. அந்த இரண்டு அரசர்களுக்கிடையிலும் ஒரு விதமான சமாதானம் நிலவி யிருந்ததென்பதை இது தெரிவிக்கிறது.

பழம் பகையை மறந்து சமாதானமாகப் போவதே நல்லது என்று எண்ணவேண்டிய சந்தர்ப்பமும் சோழமன்னனுக்கு இப்போது ஏற்பட்டிருத்தல் வேண்டும்.

கர்னல் மக்கென்ஸி சேகரித்து வைத்துள்ள நூல்களில் பாண்டியர் வரலாறு என்பதும் ஒன்று. அதிலே கி. பி. 1323-ஆம் ஆண்டு மே-ஜூன் மாதகாலத்தில் முஸ்லிம்கள் மதுரையைப் பிடித்துக்கொண்டு அவ்விடம் ஒரு படையை நிலையாக வைத்த செய்தி பின்வருமாறு குறிக்கப்பட்டுள்ளது: “பிறகு, சாலி வாகன சகாப்தம் ஆயிரத்து இருநூற்று நாற்பத்தாறுக்குச் சரியான கொல்லம் அழிந்த ஆண்டு இருநூற்று இருபத்தேழு ருதிரோத்காரி வருஷம் ஆனி மாதம் பராக்கிரம பாண்டியன் ஆண்டுவந்த நாளையிற் தில்லியிலிருந்து ஆதி சுல்தான் முல்க் கும் நேயி என்பவனும் வந்து”, நாட்டைப் பிடித்துக்கொண் டார்கள். (ஹிஸ்டாரிகல் மானுஸ்க்ரிப்டஸ் - சரித்திர சம்பந்தமான ஏட்டுச் சுவடி நூல்கள்-என்ற பெயரில் டெய்லர் ஆங்கிலத்தில் மொழிபெயர்த்து வெளியிட்ட நூல், முதல் பாகம், பக்கம் 203).

மதுரையை முஸ்லிம்கள் கைப்பற்றிய தேதி அந்நூலிலே இரண்டுவிதமாகக் குறிக்கப்பட்டுள்ளது. ஒன்று சகாப்தம்

1246, ருதிரோத்தகாரி வருஷம் ஆனிமாதம். இது கி. பி. 1323, மே-ஜூன் ஆகும். மற்றொன்று கொல்லம் அழிந்தது முதல் கணக்கிடப்படும் வேறு ஓர் அப்தத்தின் 227-ஆம் ஆண்டு. கி. பி. 824-ஆம் ஆண்டு முதல் கணக்கிடப்பட்டுப் பொதுவாக வழக்கில் உள்ள கொல்லம் தோன்றிய காலத்தினின்றும் இது வேறுனது. கொல்லம் தோன்றியது முதல் ஆரம்பித்த ஆண்டுக்கு சுமார் இருநூற்று எழுபது ஆண்டுகளுக்குப் பிறகு, கி. பி. 1096-ஆம் ஆண்டில், கொல்லம் அழிந்த நாளி லிருந்து தோன்றிய புது அப்தமாகும் (டாக்டர் என். வேங்கட ரமணய்யா எழுதிய தேன் இந்தியாவிலே முஸ்லிம் ஆட்சி பரவியதன் ஆரம்பகால வரலாறு, 71-3 பக்கங்கள்).

புதிய அப்தம் தோன்றிய காலத்திலே மேலைக் கடற்கரை யோரப் பிரதேசத்திலே வேண்டில் ஏதோ குழப்பம் இருந்த தென்றும், அதற்காகக் குலோத்துங்கன் தன் சேனைத் தலை வன் நரலோக வீரனை அனுப்பினான் என்றும் தெரிய வரு கிறது. அப்போது நரலோகவீரன் கொல்லத்தை அழித்திருக் கிறான். நரலோகவீரன் புகழ்ச்சியைப் பலபடியும் விதந்து ஓதும் சாசனங்களிலே இவ்வெற்றி கூறப்பட்டுள்ளது. (சோழர் சரித்திரம், ஆட்சிமுறை ஆகியவற்றில் சிற்றராய்ச்சி என்ற தலைப்பில் ஸ்ரீ க. அ. நீலகண்ட சாஸ்திரி எழுதிய நூல், பக்கம் 191. இன்னும் இந்தத் தொகுப்பிலே உள்ள 1271-3 நெ. சாசனங் கள்).

இந்த ஆண்டுக்கணக்கு வேறு எந்த இடத்திலும் குறிக்கப் பெறவில்லை. அவ்விதம் இருக்க, இவ்வரலாற்றிலே இந்த ஆண் டைக் குறிக்கவேண்டிய சந்தர்ப்பம் என்ன என்பது நோக் கற்குரியது. கி. பி. 824-ஆம் ஆண்டு முதல் கணக்கிடப்படும் முதல் கொல்லம் ஆண்டே பாண்டி நாட்டில் வழக்கில் இல்லை. ஆகவே மதுரையை முஸ்லிம்கள் கைப்பற்றிய செய்தியைக் கூறுமிடத்தில் புதியதானதும் கொல்லம் அழிவுநாள் முதல் தோன்றியதுமான ஆண்டுக்கணக்கை உபயோகித் திருப்ப தைக் கவனிக்கவேண்டும். ஆயினும் ஒரு விஷயத்தை நாம் மறக் கலாகாது. இவ்வரலாற்றை எழுதிய ஆசிரியர் கொல்லம் அழிவு ஆண்டுக் கணக்கை மட்டும் கூறினால் போதாது, விபரம் தெரி

யாது என்று நினைத்தே சகாப்தத்தையும் சேர்த்துக் காட்டியிருக்கிறார். சகாப்தக் கணக்கு இல்லாவிட்டால் முஸ்லிம்கள் மதுரையைக் கைப்பற்றிய ஆண்டை நாம் நிச்சயமாக நிர்ணயிக்க முடியாது. ஆகவே அவர் கொல்லம் அழிவு ஆண்டுக் கணக்கை வேண்டுமென்றே ஏதோ ஒரு காரணத்தால் இவ்விடம் சேர்த்திருத்தல் வேண்டும்.

ஒருகால் கி. பி. 1096-ஆம் ஆண்டு நடந்த கொல்லம் அழிவுக்கும் முஸ்லிம்களுக்கும் ஏதாவது தொடர்பு இருக்கவேண்டும் போலும். ஆனால் அதைப்பற்றிய விவரம் ஒன்றும் இப்போது தெரியவில்லை. சிதம்பரத்திலே கிடைக்கும் முதற்குலோத்துங்கனுடைய வடமொழிக் கல்வெட்டு ஒன்று, அவன் மேலைக் கடற்கரை ஓரமாக ஸஹ்ய மலையிலே ஜயஸ்தம்பம் நிறுவினான் என்றும், சமுத்திரத்தின் மறுகரையில் உள்ள பாரதீக நாட்டு யுவதிகள் அவன் புகழைப் பாடினார்கள் என்றும் கூறுகிறது. (எபி. இந்தகா, ஐந்தாம் வால்யூம், 103-4 பக்கங்கள்; இன்னும் இந்தத் தொகுதியில் உள்ள 1270 நெ. சாசனம்.) அது எதைக் குறிக்கிறதென்பது தெரியவில்லை. ஆயினும் அதைக்கொண்டு முதற் குலோத்துங்கன் முஸ்லிம்கள்மீது ஏதோ பொரு வெற்றி கொண்டான் என்று எண்ண இடம் ஏற்படுகிறது.

இதே சமயம் ஆண்டுவந்த மேலைச் சாளுக்கிய அரசன் ஆறாம் விக்கிரமாதித்தியனும் ஹொய்சள மன்னன் விஷ்ணுவர்த்தனனும் துருக்கர்களை வெற்றி கொண்டதாகக் கூறிக் கொள்ளுகிறார்கள். தங்களுக்குப் பொதுவான எதிரியை முறியடிக்கச் சவண்டிக் குலோத்துங்கனும் விக்கிரமாதித்தியனும் தங்களுக்குள்ளே இருந்த பகையையைத் துறந்து முஸ்லிம்களை வெற்றி கொள்ள ஒன்று சேர்ந்திருக்கக் கூடும்.

**இலங்கை விவகாரம்**

முதற் குலோத்துங்க சோழன் தன் ஆட்சியின் ஆரம்பத்திலே இலங்கையின் ஆதிபத்தியத்தை இழந்துவிட்டான் என்றும், அதற்குப்பிறகு அதைத் திரும்பவும் அடைய அவன் செய்த முயற்சிகள் கைகூடவில்லை யென்றும் பொதுவாகக் கொள்ளப்பட்டிருக்கிறது.



சிங்கள ராஜவமிசத்து அரசகுமாரனான கித்தி என்பான் விஜயபாஹு என்னும் அபிஷேக நாமத்துடன் கி. பி. 1055-ஆம் ஆண்டில் தன்னுடைய பதினேழாம் வயதிலேயே இலங்கையின் தென்கிழக்குப் பகுதியான மலைநாட்டில் அரசரிமையை ஏற்றான். (சுளவமிசம், ஐம்பத்தேழாம் அத்தியாயம், சுலோகங்கள் 65-66; எபிகிராபியா ஸைலாநிகா, இரண்டாம் வாஸ்யும், பக்கம் 507.) இதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். அவன் ஐம்பத்தைந்து வருஷகாலம், அதாவது தன்னுடைய எழுபத்துமூன்றாம் வயது வரையில், அரசு புரிந்திருக்கிறான். அவன் தன்னுடைய ஆட்சியின் பதினைந்தாம் ஆண்டு (சுமார் கி. பி. 1070-ஆம் ஆண்டு) அநுராதபுரத்தை யடைந்து அகில இலங்கைக்கும் அரசன் ஆனான். இரண்டு ஆண்டுகளுக்குப் பிறகு அதற்குரிய அபிஷேகமும் நடந்தது. (டாக்டர் மெண்டிஸ் எழுதிய இலங்கையின் பழைய வரலாறு என்னும் ஆங்கில நூலின் நான்காம் பதிப்பு, 86-90. 154 பக்கங்களில் அனுஷ்டித்த கால முறையே இவ்விடம் கொள்ளப்பட்டுள்ளது. எபிகிராபியா ஸைலாநிகா, ஐந்தாம் வாஸ்யும். முதல் பாகத்தில் காணும் திருத்தங்களையும் கவனிக்க). இதனால் அந்தத் தீவிலே அதுகாறும் நிலைத்திருந்த சோழர்களுடைய ஆதிக்கியம் முடிவடைந்தது. கி. பி. 991-ஆம் ஆண்டு முதல், முதலாம் இராஜராஜ சோழன் காலத்திலிருந்தே அந்தத் தீவின் வடபகுதியிலே சோழர்கள் ஆட்சி நிலவி வந்தது. கி. பி. 1017-18-ஆம் ஆண்டிலிருந்து, ஏதோ மூலை முடுக்குகளிலே உள்ள சிற்சில பிரதேசங்கள் நீங்கலாகத் தீவு முழுவதுமே சோழர்களுடைய ஆளுகைக்கு உட்பட்டிருந்தது. இவ்வளவுதூரம் வேரூன்றியிருந்த அந்த ஆதிக்கியத்தைத் தகர்த்தெறிவதற்கு விஜயபாஹு முயற்சி எடுத்துக்கொண்டதற்கான சமயமும் ஏற்றதாக இருந்தது. சோழநாட்டிலே அப்போதுதான் வீரராஜேந்திரன் இறந்துபோயிருந்தான். அவனுக்குப்பின் சிங்காதனம் ஏறிய அதிராஜேந்திரனே அமைதியாக நாட்டை ஆளமுடியவில்லை. அவனுக்குக் கடுமையான எதிர்ப்பு இருந்தது. உள்நாட்டுக் கலகத்தில் அதிராஜேந்திரன் இறந்துபோகவே முதற் குலோத்துங்கன் அரசியலைக் கைப்பற்றி ஆளத் துவங்கினான். இந்தச் சமயம்தான் விஜயபாஹு தன்னுடைய சுதந்திரத்தை நிலை நிறுத்த

திக் கொண்டது. மற்றொரு விஷயத்தையும் நாம் கவனிக்க வேண்டும். அதிராஜேந்திரதேவனுடைய மூன்றாம் ஆண்டுக் கல்வெட்டும் இலங்கையில் கிடைத்துள்ளது. (தே.இ. சாசனங்கள், நான்காம் வரல்தும், நெ. 1389). ஆனால் அப்பால் குலோத்தங்க சோழனுடைய சாசனங்களோர் அவனுக்குப் பின் வந்த வர்களுடைய சாசனங்களோர் இலங்கையில் கிடைக்கவில்லை.

இவ்விதம் விஜயபாஹு அடைந்த வெற்றி குலோத்தங்கனுடைய உள்ளத்தைச் சதா உறுத்திக்கொண்டே இருத்தல் வேண்டும்! அதற்காக அவன் உற்ற சமயத்தை எதிர்பார்த்துக் காத்திருந்தான் போலும். குலோத்தங்கன் இலங்கையைத் திரும்பவும் கைப்பற்ற எடுத்துக் கொண்ட நடவடிக்கைகளைப் பற்றியோ அவற்றின் விளைவுகளைப்பற்றியோ சோழ சாசனங்கள் ஏதும் தெரிவிக்கவில்லை. எனினும், இலங்கைச் சரித்திரமான மஹாவிசத்திலே இரண்டு சம்பவங்கள் குறிக்கப்பட்டுள்ளன. முதற் சம்பவம் விஜயபாஹுவின் ஆட்சியிலே முப்பதாம் ஆண்டு, அதாவது சுமார் கி. பி. 1085-ஆம் ஆண்டு, நடந்தது.

—கண்ணாட (கர்நாடக) வேந்தனும் சோழமன்னனும் அனுப்பிவைத்த தூதுவர்கள் விலையுயர்ந்த பரிசுகளைக் கொண்டு இவ்விடம் வந்தார்கள். அவர்கள் அரசனைப் பேட்டிகண்டார்கள். மன்னனும் பெரிதும் மகிழ்வுற்று இரண்டு தூதுகோஷ்டிகளுக்கும் அவர் அவர்க்கு உரிய மரியாதைகளை வழங்கினான். அப்பால் முதலில் கண்ணாட நாட்டுத் தூதுவர்களோடு தன் தூதுவர்களையும் சேர்த்துப் பொறுக்கி எடுத்த பரிசுகளுடன் கண்ணாட தேசத்துக்கு அனுப்பி வைத்தான். ஆனால் அவர்கள் சோழ நாட்டு எல்லையில் நுழைந்தபோது ஸிம்ஹளர்களுடைய காதையும் மூக்கையும் சோழர்கள் கொரோமாக அரிந்துவிட்டார்கள். இவ்விதம் உருக்குலேந்த தூதுவர்கள் சென்ற வழியே திரும்பி இவ்விடம் வந்து தங்களுக்குச் சோழமன்னன் இழைத்த பரிபவம் எல்லாவற்றையும் அரசனிடம் முறையிட்டார்கள். கனன்று எரியும் கோபம் கொண்ட விஜயபாஹு வேந்தனும் (மந்திரி பிரதானிகள்) புடை சூழ்ந்திருக்கும் சபை நடுவே தமிழ்த் தூதுவர்களை அழைப்பித்துச் சோழ அரசனிடம் பின்வரும் செய்தியைத் தெரிவிக்குமாறு

கூறியான். “நடுச் சமுத்திரத்திலே ஒற்றைத் தீவிலே நாம் இருவரும் நம்முடைய புலவலிமையைப் போட்டியிட்டுப் பரீக்ஷித்துக் கொள்ளலாம். இல்லை, நீயே தேர்ந்தெடுக்கும் ஓர் இடத்தில் உன்னுடைய படைப்பலம் முழுவதையும் திரட்டி என் படைகளோடு போரிட்டு வெற்றி கொள்ளலாம்.” நான் கூறியது போலவே இதை உன் யஜமானனிடம் தெரிவி.” இதைக் கூறிய மன்னன் அந்தத்தூதுவனுக்குப் பெண்ணுடை அணிவித்துச் சோழ அரசனிடம் அனுப்பி வைத்தான்.<sup>1</sup> அவனும் அதுராதபுரத்தை அடைந்து அங்கே தன் படையுடன் தங்கியிருந்தான். சோழநாட்டை அடைந்து போர்ரைத் துவக்கும்படி அவன் தன்னுடைய படைத்தலைவர்கள் இருவரை மத்திகாவாடதித்த, மஹாதித்த ஆகிய துறைமுகங்களுக்கு அனுப்பிவைத்தான். சோழநாட்டுக்குப் படைகளை அனுப்புவதற்காகக் கப்பல்களையும் இதரத் தளவாடங்களையும் அவர்கள் சேகரித்துவைத்தார்கள். அப்போது (மன்னனுடைய ஆட்சியின்) முப்பதாம் வருஷத்திலே வேளைக்காரப் படைப்பிரிவினர் அவ்விடம் செல்ல இஷ்டப்படாமல் கலகம் செய்தார்கள். தண்டநாயகர்கள் இருவரையும் அவர்கள் கொன்று, கட்டுக் கடங்காமல் செல்லும் மதயானைகளைப்போலப் புலத்திகரத்தைச் சுற்றியுள்ள பிரதேசங்களைச் சூறையாடினார்கள். அரசனுடைய தங்கையையும் அவளுடைய மூன்று பிள்ளைகளோடு சிறைப்பிடித்து, அரசனுடைய அரண்மனையையும் மூர்க்கமாக எரியூட்டினார்கள். அரசனும் நகரத்தை விடுத்துத் தக்கிண தேசத்துக்கு விரைந்தான். விலையுயர்ந்த பொருள்களை வாதகிரிக்குகையில் ஒளித்துவைத்துவிட்டு, சிங்கத்தின் வீறு கொண்ட உபராஜ வீரபாஹுவோடுகூடப் பெரும்படை நடத்திப் புலத்தி நகரத்தை அடைந்தான். அங்கே தீரமான சண்டையின் முடிவில் படைகளைப் புறமுதுகு காட்டி ஓடச்செய்தான்.

1. இதுவும் இந்தப் போர் நிகழ்ச்சிபற்றி மகாவயிசத்திலே காணும் இதர சம்பவங்களும் அதற்குச் சில ஆண்டுகளுக்கு முன்னதாக நடந்த சோழ-சாளுக்கிய யுத்தசமயத்தில் நடந்த சம்பவங்கள் சிலவற்றை நினைப்பூட்டுவனவாக உள்ளன. சாளுக்கியர்களுக்குச் சோழர்கள் இழைத்த அவமானங்களுக்குப் பிரதியாக இலங்கை வேந்தன் சோழர்களை இவ்வாறு அவமானம் செய்தானு அல்லது இவையெல்லாம் அந்தக் காலத்துப் போர்முறையிலே சகஜமாகக் காணப்படுபவைகளா என்பது நிச்சயமாகத் தெரியாது.

கொலையுண்ட தன்னுடைய தண்டநாயகர்கள் இருவருடைய உடலையும் வைத்துக் கட்டிய பாடையைச் சுற்றி அவர்களை நிறுத்தி, கலகப்படைத் தலைவர்களின் கைகளைப் பின்புறம் இழுத்துக் கட்டியபடியே கழுமரங்களோடு பிணைத்துவைத்துத் தீயிட்டு எரிக்கச் செய்தான். இவ்விதம் அரசன் அங்கே கலகத்தலைவர்களை அழித்து இலங்கை மண் முழுவதிலும் (கலகப்) பூண்டு இல்லாமல் செய்தான்."

இவ்விடம் குறிக்கப்பட்ட வேளைக்காரப் படைப்பிரிவு தமிழ் நாட்டு வீரர்களால் அமைக்கப்பட்டது போலும். இந்தக் கலகம் அடக்கப்பட்டதற்குச் சில ஆண்டுகளுக்குப் பிறகு, கி. பி. 1114-ஆம் வருஷம், இந்த விஜயபாஹுவிற்குப் பின் சிங்காதனம் ஏறிய அவன் தம்பி ஜயபாஹுவின் வேளைக்காரனாகச் சேதராயன மலைமண்டல நாயகன் என்பான் இருந்த செய்தி அவ்வாண்டு கொண்ட ஒரு கல்வெட்டிலிருந்து தெரிகிறது. (இலங்கைச் சாசனம் 509 நெ., ஸிலோன் ஜர்னல் ஆப் ஸயன்ஸ், ஜி பிரிவு, இரண்டாம் வால்பூம், பக்கம் 122). தமிழ் நாட்டுச் சாசனங்களிலே வேளைக்காரர் பெயர் அதிகமாகக் காணப்படுகிறது. சேனையிலே அவர்கள் நம்பிக்கை வாய்ந்த நிலையான பிரிவினர் என்று கருதப்படுகிறது. இலங்கைத் தீவிலே சோழர்களுடைய ஆட்சி நிலவியிருந்த காலத்தில் அவர்கள் அவ்விடம் சேர்ந்தவர்கள், சோழர்களது ஆட்சி மறைந்தபிறகும் அங்கே தங்கியிருந்தனர் போலும்.

மஹாவமிசத்திலே கண்ணுடர் என்று குறிக்கப்பட்டவர் கல்யாண புரத்தைத் தலைநகராகக் கொண்டு ஆண்டுவந்த மேலைச் சாளுக்கியர்களே யாவர். அந்நாளிலே அவர்களுக்கும் இலங்கைத் தீவுக்கும் ஏதோ ஒருவகைத் தொடர்பு இருந்த தென்று கொள்ளலாம். பரமாவமிசத்துப் புகழ்பாடும் நாக பூர்ப் பிரசஸ்தியில் உதயாதித்தியனுக்குப் பின் பட்டத்துக்கு வந்த அவன் மகன் லக்ஷ்மதேவனைப் பற்றி இருபது சுலோகங்கள் (35-முதல் 54-வரையில்) உள்ளன. (எபி. இந்திகா, இரண்டாம் வால்பூம், 193-4 பக்கங்கள்.) அந்தப் பிரசஸ்தியிலேயே அவன் புகழைக் கூறும் பகுதிதான் மிகப் பெரியது. அவன் கௌட, திரிபுர (சேதி தேசம்), அங்க, கலிங்க நாடுகளை வெற்றி கொண்டாலும், இன்னும்;

“கும்பத்திற் பிறந்த முனிவரான அகஸ்தியரைப்போல அவன் தென் திசையை நோக்கிக் கிளம்பியபோது சோழர்களும் மற்றைக் குலத்தாரும் அவனைத் தாழ்ந்து வணங்கி வந்திய மலையாக மாறினார்கள். (46)

“தாயிரவருணி நதியிலே அவனுடைய படையில் இருந்த சாமந்த அரசர்களின் மனைவிகள் விளையாடிக் குளித்த சமயம் அவர்களுடைய இடையிலிருந்த ஒட்டியாணத்திலிருந்து தெறித்து ஆற்றில் சிதறி விழுந்த முத்துக்கள் உலகப்பிரசித்தி பெற்று இன்றைக்கும் பாண்டிய மன்னனுக்கு ஜீவனோபாயத்துக்கு வழிசெய்கின்றன. (47)

“விந்தியபர்வதம் வளர்ந்ததுபோல அவன் எதிரே தோன்றிய அணை, மாருதி கொணர்ந்த மலைச்சிகரங்கள் பலவற்றைக் கொண்டு இராமன் கட்டிய சேது என்று மக்கள் பணிவுடன் கூறியதை அவன் கவனமாகக் கேட்டான். ஆயினும், அலட்சியமாக அவன் தன் படையின் யானைகளமீதே ஏறி அதைக் கடந்து எதிர்க்கரையை அடைந்தான்.” (48)

இதற்குமேல் விவரம் ஏதும் கிடைக்கவில்லை. வேளைக்காரப் படையின் கலகம் சோழர்களுடைய தூண்டுதலாலே நிகழ்ந்ததுபோலும். குலோத்துங்கனுக்கு அதில் ஓர் அளவு சம்பந்தம் இருக்க வேண்டும். ஆனால் முயற்சி பலிக்கவில்லை.

மற்ற முயற்சி பதினைந்து வருடங்களுக்குப் பிறகு, அதாவது விஜயபாஹு ஆட்சியின் நாற்பத்தைந்தாம் ஆண்டு (கி. பி. 1100-ஆம் ஆண்டு) நடந்தது. மஹாவமிசம் அதைப் பின்வருமாறு வருணிக்கிறது. “சோழ (வேந்த)னோடு போர் தொடுக்க வேண்டுமென்று தான் கொண்ட தீர்மானத்தை அரசன் மறக்கவே இல்லை. (தன் ஆட்சியின்) நாற்பத்தைந்தாம் ஆண்டு அவன் யுத்தசனாகமாகப் படையுடன் கடற்கரைத் துறைமுகப் பட்டினத்தை அடைந்து எதிரியின் வரவை எதிர்பார்த்து அங்கே காத்திருத்தான். ஆனால் சோழ(மன்னன்) வரவில்லை. ஆகவே அரசன் அவனுடைய (அதாவது சோழனுடைய) தூதுவர்களைத் திருப்பி அனுப்பிவிட்டுப் புலத்தி நகரத்துக்குத் திரும்பி அங்கே நீண்ட காலம் வதிந்தான்.”

மேலேகூறிய இரண்டு சம்பவங்களும் நிகழ்வதற்கான சந்தர்ப்பம், அவற்றின் போக்கு ஆகிய விவரங்கள் நமக்கு இப்போது கிடைக்கவில்லை. ஆயினும் ஒரு விஷயம் மட்டும் தெளிவாகத் தெரிகிறது. சோழர்கள் தங்களுக்கு ஏற்பட்ட தோல்வியையும் அதனால் நாடு இழந்ததையும் கண்டு சும்மா இருந்து விடவில்லை. பழைய நிலையை மீண்டும் அடைவதற்கு அவர்கள் அவ்வப்போது சந்தர்ப்பம் கிட்டிய போதெல்லாம் முயன்றிருக்கிறார்கள். எனினும், விஜயபாஹு உயிருடன் இருந்த வரையில் அவர்கள் முயற்சி கைகூடி லக்ஷ்யம் சித்திக்க வில்லை. ஆனால் சுமார் கி. பி. 1110-11 ஆம் ஆண்டிலே விஜய பாஹு இறந்ததும் சிங்கள நாட்டுச் சிங்காதனத்தை அடைவதில் போட்டி ஏற்பட்டுத் தாயாதிச் சண்டை உண்டாயிற்று. அப்போது தான் குலோத்துங்கன் எண்ணம் ஈடேறிற்று போலும்.

மஹாவமிசத்தில் காணும் வரலாற்றின்படி, விஜய பாஹு ஐம்பத்தைந்து ஆண்டு ராஜ்யபாரம் தாங்கிய பிறகு இறந்துபோனான். அப்போது அவன் மகன் விக்கிரமபாஹு தந்தையின் பக்கத்தில் இல்லை. வெகுதூரத்துக்கு அப்பால், தென்கிழக்கில் உள்ள ரோகண நாட்டை ஆண்டு வந்தான். தந்தை இறந்த செய்தி மகனுக்கு எட்டவில்லை. அதை ரகசியமாகவே வைத்துவிட்டு இறந்த மன்னன் தம்பியான ஜய பாஹு தானே அரசனென்று முடிசூட்டிக் கொண்டான். தன் சகோதரி மகனும் பாண்டிய குலத்தைச் சேர்ந்தவனுமான மாலபரணன் என்பவனை இளவரசனாகவும் நியமித்தான். விக்கிரமபாஹு இந்த நிலையை ஏற்றுக் கொள்ளவில்லை. சிங்காதானத்தைக் கைப்பற்றத் தன் சிற்றப்பன் ஜய பாஹுவோடு போர்புரிந்தான். இரண்டு ஆண்டுகள் கழித்து அவன் வெற்றி கொண்டு அரசனானான் எனப்படுகிறது.

விக்கிரமபாஹுவோ தந்தை உயிருடன் இருந்த காலத்திலேயே ராஜ்யத்தின் ஒரு பகுதியை ஆண்டு வந்திருக்கிறான். அன்றி, பட்டத்துக்குரிய இளவரசன் எனவும் அங்கீகரிக்கப் பட்டிருக்கிறான். இது இலங்கையிலே திருக்கோணமலை ஜில்லாவில் கந்தளாய்க்குப் பக்கத்தில் உள்ள பாலமோட்டை என்னுமிடத்திலிருந்து கிடைத்த ஒரு தமிழ்க் கல்வெட்டால் விளங்கு

கிறது. அரசர் விஜயபாஹு ஆட்சியின் நாற்பத்திரண்டாம் ஆண்டு கொண்ட அக் கல்வெட்டு கந்தளாயான விஜயராஜ சதுர்வேதி மங்கலத்து விஜயராஜ ஈசுவரம் என்னும் சிவன் கோயிலுக்குப் பிராமணஸ்திரீ ஒருத்தி இறந்துபோன தன் கணவன் ஞாபகார்த்தமாகச் செய்த நிவந்தங்களைத் தெரி விக்கிறது. அதை ஸ்ரீவிக்கிரம சலாமேகத் தெரிந்த வேளைக் காரர் என்ற பெயரால் அவர்கள் பாதுகாப்பிலே விட்டதாக அந்தக் கல்வெட்டு கூறுகிறது. (எபி. ஸைலாபிகா, நான்காம் வால்யூம், நெ. 24). சலாமேகன் என்பது அரசனது பட்டப் பெயரைக் குறிப்பது என்பதை நாம் அறிவோம். ஆகவே, அப் போதே விக்கிரமபாஹு இளவரசனாக நியமிக்கப்பட்டு விட்டான். இதனால் தந்தைக்குப் பிறகு அவன் சிங்காதனத்தை அடைவதற்காக எடுத்துக் கொண்ட முயற்சியிலே அவனுக்கு நாட்டு மக்களிடையிலும் பெருத்த ஆதரவு இருந்திருத்தல் வேண்டும்.

அதேசமயம் ஜயபாஹுவுக்கும் தன்னுடைய நிலைமையை ஸ்திரப்படுத்திக் கொள்வதற்கு வேண்டிய ஆதரவும் இருந்திருக்கும். அவனோடு வீரதேவன் என்பான் ஒருவன் இலங்கைக்குத் தன் படைகளோடு வந்து போர்புரிந்திருக்கிறான். மகாவரிசத்திலே அவன் ஆர்யதேசீச (ஆர்யதேசத்து ஈசன், அதாவது ஆர்யதேசம் எனப்படும் இந்தியாவிலிருந்து வந்த அரசன் ஒருவன்) என்றும், பலந்தீபம் என்னும் பிரதேசத்தின் ஏகசத்திராதிபதி என்றும் குறிக்கப்பட்டிருக்கிறான். பலந்தீபம் என்பது முதலாம் இராஜராஜன் வெற்றி கொண்டதாக அவனுடைய மெய்க்கீர்த்தியில் காணும் 'முன்னீர்ப் பழந்தீவு பன்னீராயிரம்' அதாவது மாந்தீவு என்னும் மலையத்தீவுகளை நமக்கு ஞாபகமுட்டுகின்றன. இதே பிரதேசம் முதலாம் இராஜேந்திர சோழனுடைய மெய்க்கீர்த்தியிலே 'சங்கதிர் வேலைத் தொல் பெருங்காவல் பல்பழந்தீவு' என்று காணப்படுகிறது. இந்தத் தீவுகள் அந்நாளிலே ஒரு தனிப்பிரதேசமாகக் கருதப்பட்டு வந்திருக்கிறது. கொடுந்தமிழ் பேசப்படும் பிரதேசங்களைத் தெரிவிக்கும் பழம் பாடல் ஒன்று நன்னூல் மயிலை நாதர் உரையில் மேற்கோளாக எடுத்துக் காட்டப்பட்டுள்ளது. அதில் 'கன்னித் தென்கரைக்கட் பழந்தீவம்' என்று இந்தப் பிரதேசம் குறிக்கப்பட்டுள்ளது. இலங்கை

யிலே புதமுத்தாவா என்னும் இடத்திலிருந்து கிடைத்த மற் றொரு தமிழ்க் கல்வெட்டு (எபி. ஸைலாங்கா, மூன்றாம் வால்பூம், 302-12 பக்கங்கள்) ஒன்றிலிருந்து ஜயபாஹு ஆட்சியின் எட்டாம் ஆண்டில் மஹாகலா ஆன விக்கிரம சலாமேகபுரத் திலே கோயில் கொண்டு எழுந்தருளியிருக்கும் விக்கிரம சிலா மேக ஈச்வரமுடையார் கோயிலிலே ஒரு விளக்கு எரிக்கக் குலோத்துங்க சோழன் திருமகளும் பாண்டியன் வீரப்பெரு மாள் தேவியுமான சுத்தமல்லியார் நிவந்தம் அளித்த செய்தி தெரியவருகிறது.

முதற் குலோத்துங்க சோழனுடைய ஆட்சியின் நாற்பத் தொன்பதாம் ஆண்டு எழுபதாம் நாள் கொண்ட தமிழ்ச் சாசனம் ஒன்று மேற்கு கோதாவரி ஜில்லா திராக்ஷாரா மத்திலிருந்து கிடைத்துள்ளது. (தே. இ. சாசனங்கள், நான் காம் வால்பூம், 1227, 1225 நெ. ஆகிய இரண்டும் சேர்ந்தது). இலங்கை அரசனான விக்கிரமபாஹுவின் பிரதானியான உய்யவந்தான் திருவண்ணாமலையன் விஜயபாஹு மாசாத்து நாயன் என்பான் திராக்ஷாராமத்திலே தான் எடுபித்த மஹேச்வரமடத்தில் நாள்தோறும் பதினைந்து தபஸ்விகள் உண்ணுவதற்கு வேண்டிய நிவந்தங்களைச் சூரியகிரகண கால த்தில் அளித்த செய்தியைக் கூறுகிறது, அந்தக் கல்வெட்டு. அதிலே குறிக்கப்பட்ட மடம் அவனால் குலோத்துங்க சோழ னுடைய ஆட்சியின் நாற்பத்து மூன்றாம் ஆண்டிலே அவ்வூரில் நிர்மாணிக்கப்பட்டது. (ஹெ. 1246 நெ. சாசனம்). அப்போது அவன் அம்மடத்திலே நாள்தோறும் முப்பது தபஸ்விகள் உண்ண வேண்டும் என்று நிர்ணயித்துப் பதினைந்து பேர் உணவுக்கு வேண்டிய நிலங்களை அளித்தான். பாக்கியிருந்த பதினைந்து பேர் உணவுக்கு வேண்டியவற்றை இப்போது அவன் அளித்தான். இந்தத் தர்மத்தைச் செய்தவன் தமிழ் நாட்டைச் சேர்ந்த ஒரு தமிழன். இலங்கை அரசனுடைய பிரதானி. அப்போது இலங்கையில் அரசனாயிருந்தவனுடைய தந்தையின் காலம் முதலே அவன் இலங்கை அரசியலில் ஈடுபட் டிருந்தான். அவன் தெலுங்கு நாட்டுத் திராக்ஷாராமத்திலே சிவதர்மங்கள் பலவற்றைச் செய்திருக்கிறான். அந்நாளிலே திராக்ஷாராமம் வேங்கியை ஆண்டு வந்த சோழமன்னருடைய



பிரதிரிதிகளுக்குத் தலைநகராக இருந்ததென்பதையும் நாம் மறக்கலாகாது. அந்த நிலையில் இலங்கை அதிகாரி அங்கே வந்து தங்கியிருந்த சம்பவம் முக்கியத்துவம் பெறும்.

அவன் அங்கே தங்கியிருந்த சமயத்தையும் நாம் கவனிக்க வேண்டும். முதற் குலோத்துங்கனுடைய குமாரர்களான விக் கிரம சோழனும் பரார்தகனும் அப்போது சோழசிங்கா தனத்துக்காகத் தங்களுக்குள் சண்டைபோட்டுக் கொண்டிருந்தார்கள். (இதை விவரமாகப் பின்னால் கூறுவோம்). ஹொய் சளர், மேலேச்சாளுக்கியர் ஆகியவர்களுடைய ஆதரவோடு போர் புரிந்து வந்த விக் கிரம சோழனுக்கு எதிராகப் போரை நடத்தி வந்த முதற் குலோத்துங்கனுக்கும் அவன் மகன் பரார்தகனுக்கும் உதவுவதற்காகவே அவன் அவ்விடம் வந்திருந்தான் போலும். இலங்கை வேந்தன் சோழமன்னனுக்கு அப் போது அடங்கியவரை இருந்தால்தான் இந்த நிலை சாத்தியமாகும். அந்தத் தீவின் ஆட்சியை அன்னியரின் ஆதிக்கியத்திலிருந்து விடுவித்த விஜயபாஹுவின் மரணத்துக்குப் பிறகு அவ்விடம் ஏற்பட்ட தாயாதிப்பூசலைக் கவனித்தால் அப் போது சோழர்கள் மறுபடியும் இலங்கை விவகாரத்தில் தலையிட்டு அதனைத் தங்கள் ஆளுகைக்குள் கொண்டுவந்து விட்டார்கள் என்று கொள்வது தவறாகாது.

விஜயபாஹுவின் மரணத்துக்குப் பிறகு, கொஞ்சகாலம் இலங்கைத் தீவு அன்னிய ஆதிக்கியத்தின் கீழ் இருந்ததென்பது பராக்கிரமபாஹுவின் தேவனகலக் கல்வெட்டால் விளங்குகிறது. “என் பாட்டனார் விஜயபாஹு மன்னர் சுவர்க்கலோகவாசி யானதன் பிறகு நாற்பத்திரண்டு வருஷகாலம் அழிவுற்றுக் கிடந்த அரசையும் மதத்தையும் மறுபடியும் மலரச் செய்வதென்று நான் உறுதிபூண்டிருக்கிறேன்.” (எபி. லைலாநிகா, மூன்றாம் வால்பூம், பக்கம் 324). இதிலிருந்து விஜயபாஹுவின் காலத்துக்குப் பிறகு நாற்பத்திரண்டு ஆண்டுகள் இலங்கைத்தீவின் அரசியலும் புத்தமதமும் இலங்கை மக்களுக்கு அனுகூலமாக நடைபெறவில்லை என்று பராக்கிரமபாஹு கருதினான் என்பது தெளிவாகும்.

இதே பராக்கிரமபாஹு தான் சில வருஷங்களுக்குப் பிறகு பாண்டியர்களுக்குள்ளே ஏற்பட்ட தாயாதிச் சண்டையில் பராக்கிரம பாண்டியனுடைய கட்சியை ஆதரித்துத்

தமிழ் நாட்டின்மீது படையெடுத்து வந்தவன். தேவனகலச் சாசனத்தில் குறிப்பாகக் காண்பதைக் கொண்டு சோழர்கள் திரும்பவும் இலங்கை அரசியலைக் கைப்பற்றியிருந்தனர் என்று தீர்மானிக்கலாம்போலும். 'பூமருவிய பொழிலேழும்' என்று தொடங்கும் இரண்டாம் குலோத்துங்க சோழன் மெய்க்கீர்த்தியில் அவன் வீணைக்கொடிச் சிங்களவரிடமிருந்து திறை பெற்று வந்தான் என்று காணப்படுகிறது. (தே. இ. சாசனங்கள், ஐந்தாம் வால்பூம், நெ. 645). அவனுடைய ஆசிரியரும் ஆஸ்தான கவிஞருமான ஒட்டக்கூத்தர் அவன்மீது இயற்றிய குலோத்துங்கன் பிள்ளைத்தமிழிலும் இதேசெய்தி(64-ஆம் பாடலில்) குறிக்கப்பட்டுள்ளது. இராமாயணகாலத்துத் தென் இலங்கை வேந்தனான இராவணன் வீணைக்கொடியைக் கொண்டிருந்தான் என்றும், அவனை வீணைக்கொடியோன் என்றும் கம்பநாடர் தம் இராமாயணத்தில் கூறிச் செல்கிறார். இராவணனுக்கு வீணைக்கொடி என்னும் விவரம் வால்மீகி எழுதிய ராமாயணத்தில் காணப்பெறவில்லை என்பதும் இவ்விடம் குறிப்பிடத்தக்கது. தன்னுடைய காலத்திலே சிங்களவர்களுக்கு வீணைக்கொடியிருந்ததை மனத்தில் கொண்டே கம்பர் தம்முடைய காவியத்தில் அவ்விதம் கூறிச் சென்றார்போலும்.

மூன்றாம் பராந்தகனும் விக்கிரம சோழனும்

முதற் குலோத்துங்க சோழன் பஞ்சத் திராவிடங்களோடு ஆந்திர தேசத்தையும் சேர்த்து ஐம்பது ஆண்டுகள் அரசு புரிந்துவந்தான் என்று பிற்காலத்துச் சாசனங்கள் கூறுகின்றன. (மல்லபதேவனுடைய பிட்டாபுரம் சாசனம்: எபி.இந்தீக், நான்காம் வால்பூம், 33 நெ. 22-24 சுலோகங்கள்). அவனுடைய ஆட்சியின் நாற்பத்தொன்பதாம் ஆண்டு முந்தூற்று முப்பத்து மூன்றாம் நாள் கொண்ட கல்வெட்டும், ஐம்பதாம் ஆண்டு கொண்ட கல்வெட்டுகளும் கிடைத்துள்ளன. (1923-ஆம் ஆண்டு 284 நெ, 1920-ஆம் ஆண்டு 520 நெ : தே. இ. சாசனங்கள், ஏழாம் வால்பூம், 763 நெ.) பழைய புதுக்கோட்டை ஸம்ஸ்தானத்தில் உள்ள இடையாத்தாரிலிருந்து அவனுடைய ஆட்சியின் ஐம்பத்திரண்டாம் ஆண்டு கொண்ட கல்வெட்டு ஒன்றும் (புதுக்கோட்டை ஸம்ஸ்தானத்துச் சாசனங்கள், நெ. 127) கிடைத்துள்ளது. சோழ சிங்காதனத்துக்குப் போட்டியிட்டு அரசைக்

கைப்பற்றிய அவனுடைய ஆட்சியின் முடிவிலும் அதே போன்ற மற்றொரு போட்டி நடைபெற்றது. ஆனால், இந்தத் தடவை அவ்விதம் போட்டி யிட்டவர்கள் அவனுடைய குமாரர்களேயாவர்.

அவன் சோழமன்னனை இரண்டாம் இராஜேந்திர சோழனுடைய மகள் மதுராங்கியை மணந்திருந்தான். அவளே பட்டமகிஷிகளுள் மூத்தவள். அவள்மூலம் அவனுக்கு ஏழு பிள்ளைகள் பிறந்தனர். (எ.பி. இந்திகா, ஆறாம் வால்பூம், 335-ஆம் பக்கம்.) கி.பி. 1076-77-ஆம் ஆண்டில் விஜயாதித்தியன் இறந்த பிறகு அந்த இராஜகுமாரர்கள் ஒருவன் பின் மற்றொருவனை வேங்கி நாட்டிலே தந்தைக்குப் பிரதிநிதியாக அரசு செலுத்திவந்திருக்கிறார்கள். அவர்களுள் பராந்தகன் எனப்பட்டவனும் ஒருவன். சகாப்தம் 1033, அதாவது கி.பி. 1111-12-ஆம் ஆண்டில் குலோத்துங்கன் அவனைப் பட்டத்துக்கு உரியவனைக் கருதிப் பரகேசரிவர்மன் என்ற விருதுடன் அவனுக்கு முடிசூட்டி நாட்டின் நிர்வாகத்திலும் அவனை ஈடுபடுத்தினான். பூமங்கலளர அல்லது புலிமங்கலளர என்று தொடங்கும் மெய்க்கீர்த்தியையுடைய அவன் சாசனங்கள் கிடைத்துள்ளன. அவை அவனுடைய ஆட்சியின் ஒன்பதாம் ஆண்டு வரையில் கிடைக்கின்றன. தமிழ்நாட்டில் கிடைப்பன அதிகம் இல்லை. ஆயினும், தெலுங்கு நாட்டிலே அதிகமாக உள்ளன. இதனால் அவனும் தன் தந்தை முதற் குலோத்துங்கனுடைய ஆட்சியின் கடைசி ஆண்டான கி.பி. 1119-20 ஆம் ஆண்டு வரையில் அரசு புரிந்திருக்கிறான் என்பது தெளிவாகும். (இந்த விஷயங்கள் சோழ பராந்தகதேவனுடைய ஒன்பதாம் ஆண்டு கோண்ட இரண்டு கல்வெட்டுகள் என்ற கட்டுரையில் விரிவாக ஆராயப்பட்டுள்ளன. ஸ்ரீ. க. அ. நீலகண்ட சாஸ்திரிகளோடு கூட்டாக எழுதப்பெற்ற அக்கட்டுரை எபிகிராபியா இந்திகாவில் வெளியாகும்).

ஆனால் குலோத்துங்கனுக்குப் பிறகு சோழ சிங்காதனத்திலே அவனுடைய மற்றொரு மகனை விக்கிரம சோழனே அமர்ந்து அரசாண்டான். இந்தப் பராந்தகன் அரசாளவில்லை. விக்கிரம சோழன் கி.பி. 1118-ஆம் ஆண்டு ஜூன் மாதம் இருபத்தொன்பதாம் தேதியை ஒட்டிச் சோழ

சிங்காதனம் ஏறியதாகக் கொண்டு தன் ஆட்சியின் ஆண்டு களைக் கணக்கிட்டிருக்கிறான். ஆனால் சகாப்தம் 1033, அதாவது கி. பி. 1111-12-ஆம் ஆண்டில் சோழ சிங்காதனம் ஏறிய பரந்தகனோ விக்கிரமசோழன் சிங்காதனம் ஏறியதாகக் கணக்கிடும் கி. பி. 1118-ஆம் ஆண்டுக்குப் பின்னும், ராஜ்யத் தைத் தன்னுடைய ஆட்சியின் ஒன்பதாம் ஆண்டிலே, அதாவது கி. பி. 1119-20-ஆம் வருஷத்திலே, அரசு புரிந்திருக்கிறான். இவ்விதம் குலோத்துங்கனுடைய ஆட்சியின் கடைசி இரண்டு வருஷங்களிலே அவனுடைய குமாரர்களான விக் கிரம சோழனும் பரந்தகனும் பரகேசரிவர்மன் என்ற பட் டப் பெயருடன் சோழ ராஜ்யத்தை அரசுபுரிந்தனர் என்ப பதைக் காண்கிறோம்.

இந் நிலை அசாதாரணமானது. அதை ஒரே ஒரு வழியில் தான் விளக்கிக் கூறமுடியும். பரந்தகனைப் பட்டத்துக்கு உரியவனாகக் கொண்டு தந்தை முடிசூட்டியதை விக் கிரம சோழன் ஒப்புக்கொள்ளவில்லை. முறைப்படி அந்த உரிமை தனக்கேயாகும் என்று அவன் கொண்டான். அவ்விதமாயின் அவன் தன் உரிமையைச் சுலபமாக ஸ்தாபித்துச் சமாதான மான வழிகளில் தன் லட்சியத்தை அடைந்து வெற்றி கொண்டிருக்க முடியாது. சகோதரர்கள் இருவருக்கிடையே கிச்சயம் சோழ சிங்காதனத்துக்காகத் தாயாதிச் சண்டை நிகழ்ந்திருத்தல் வேண்டும்.

இந்தச் சண்டையின் பயனாக நாட்டின் அமைதியான வாழ்க்கை நிலை குலைந்ததென்பது கொங்கு நாட்டுத் தலைநகரங் களுள் ஒன்றான கருவூரிலிருந்து கிடைக்கும் சாசனத்திலிருந்து தெளிவாகிறது. விக் கிரம சோழனுடைய ஆட்சியின் மூன்றாம் ஆண்டு, அதாவது கி. பி. 1120-21-ஆம் வருஷம், கொண்ட அக் கல்வெட்டு, வீர சோழ மண்டலத்து வெங்கால நாட்டுக் கருவூர் திருவானிலை யாளுடைய நாயனார் கோயிலிலிருந்த கூத்தர் (அதாவது நடராசர்). திருமேனி (விக் கிரகம்) கலகத்தில் சேமந் தப்பினமையில் அக்கோயில் காணியுடைய சிவப்பிராமணர் கள் ஆராய்ந்து தேடி அத் திருமேனியைத் திரும்பவும் கண்டு பிடித்துக் கோயிலில் பிரதிஷ்டை செய்து அதன் வழிபாட்டுக் குரிய ஏற்பாடுகளைச் செய்த விவரத்தைத் தெரிவிப்பதாகும்.

(தே. இ. சாசனங்கள், நான்காம் வால்பூம், 387-நெ. இந்தத் தொகுதியின் 703-நெ. சாசனம்). இன்னும் தஞ்சாவூர் ஜில்லாவிலே முதற் குலோத்துங்கனுடைய ஆட்சியின் நாற்பத்தேழு, நாற்பத்தொன்பதாம் ஆண்டுகள் கொண்ட கல்வெட்டுகள் சில வற்றிலிருந்து (உதாரணமாகத் திருச்சேறை, கோநேரிராஜபுரம் ஆகிய இடங்களிலிருந்து கிடைத்து முறையே 1909-ஆம் ஆண்டு 620, 647 நெ. கொண்ட சாசனங்கள். ஸ்ரீ. வி. ரங்கா சாரியார் தொகுத்த சேன்னை ராஜதானியில் கிடைத்த சாசனங்களின் கிராமவாரி அட்டவணையில் தஞ்சாவூர் நெ. 74, 1219-ஆகிய வற்றையும் காண்க) இரண்டு வருஷங்களுக்கு மேலாக வரி செலுத்த முடியாமல் கிராமங்களைத் துறந்து வெளியேறிய குடிமக்களின் நிலங்களைக் கைப்பற்றிக் கோயில்களுக்கு விற்றுக் கொடுத்த செய்தியும் தெரியவருகிறது.

இத்தச் சந்தர்ப்பத்தில் திருச்சிராப்பள்ளி ஜில்லாவில் உள்ள பெரம்பலூர் தாலுகா ஆடுதுறைபிலிருந்து கிடைக்கும் ஒரு கல்வெட்டு முக்கியமானது (1913-ஆம் ஆண்டு நெ. 35). பராக்கிரம பாண்டியன் என்பானுடைய ஆட்சியின் நான்காம் ஆண்டு கொண்ட அக் கல்வெட்டு, விக்கிரம சோழனுடைய ஆட்சியின் நான்காம் ஆண்டில் அந்தக் கிராமத்துக் குடிமக்களான பள்ளிகளுக்கு விசேஷ சந்தர்ப்பம் ஒன்றில் அளிக்கப்பட்ட சில உரிமைகளோடு வேறு சிலவற்றையும் சேர்த்து ஊர்ஜிதம் செய்த விவரத்தை எடுத்துக் கூறுகிறது.

‘பெரியவடுகன் போர் நடந்த சமயம் தேவதைகள், நாயன்மார் ஆகியோர்களுடைய திருமேனிகளை (விக்கிரகங்களை)த் தோரசமுத்திரத்துக்கு (அதாவது மைசூர் ராஜ்யத்தில் உள்ள ஹளேபீடு என்னும் துவாரசமுத்திரத்துக்கு)க் கொண்டு போகும் போது (பள்ளிகள்) இடைமறித்து அந்த விக்கிரகங்களை மீட்டுக் கோயிலிலே திரும்பவும் பிரதிஷ்டைசெய்து அவற்றின் வழிபாட்டுக்கு வேண்டிய செலவுகளை ஏற்றுக் கொண்டு ஏற்பாடுகளைச் செய்தார்கள். தங்கள் சமூகப்பொறுப்பாக அதை மேற்கொண்ட அவர்களுக்குக் கைம்மாறாக அந்தச் சமூகத்தைச் சேர்ந்தவர்களுக்குச் சந்திதியிலே பட்டுப்பரிவட்டம் சாத்தி அருளப்பாடு செய்து மரியாதை வழங்கவேண்டும் என்று நிர்ணயிக்கப்பட்டதாம்.’ (சாசன இலாகாவின் 1913-ஆம்

ஆண்டு அறிக்கை, 45-7 பாராக்கள்.) இந்த ஏற்பாட்டைப் பெருமான் குலோத்துங்க சோழதேவர் அங்கீகரித்து அனுமதித்தார் என்ற செய்தியும் காணப்படுகிறது. இதனால் விக்கிரகங்கள் அகற்றப் பெற்றதற்குப் பிறகு வெகு சீக்கிரமாகவே குலோத்துங்க சோழனுடைய ஆட்சிக் காலத்துக்கு உள்ளாகவே மீட்கப்பட்டனவென்பது தெரியவரும்.

சோழநாட்டிலே வந்து போர் புரிந்த பெரியவடுகன் யார் என்பது சாசனத்திலிருந்து தெளிவாகத் தெரியவில்லை. ஆயினும் தோரசமுத்திரத்தின் பெயர் காணப்படுவதிலிருந்து ஹொய்சளர்களும் அந்தப் படையெடுப்பிலே சம்பந்தப் பட்டிருந்தார்கள் என்பது தெரிகிறது. அப்போது ஹொய்சள மன்னனாக இருந்த பிட்டிக தேவன் விஷ்ணுவர்த்தன் 'தளைக்காடு கொண்டவன்' என்ற விருதைப் பெற்றிருந்தான். முதல் முதலாக அது அவனுடைய சாசனங்களில் கி. பி. 1117-ஆம் ஆண்டுதான் காணப்படுகிறது. (எ. பி. 38 நாடிகா, மூன்றாம் வால்பூம், மளவல்லி 31; நான்காம் வால்பூம், எடதொரே 6-சாசனங்கள்). அதே ஆண்டில் அவன் கொங்குவரையில் கங்கவாடி தொண்ணூற்றாறுபிரத்தையும் தளைக்காடு, குவலாலம் (கோலார்) ஆகிய இடங்களிலிருந்து அரசு செலுத்தி வந்தான் என்றும் வருணிக்கப்படுகிறான் (ஹெ-நான்காம் வால்பூம், சாம்ராஜ் நகர் 83). கங்கவாடி அதற்கு முன்னதாகச் சோழர்களுடைய ஆட்சியில் அடங்கிச் சோழஸாம்ராஜ்யத்தின் ஒரு மண்டலமாக நிர்வகிக்கப்பட்டு வந்திருக்கிறது. அதை ஹொய்சளருக்காக அவர்களுடைய தண்டநாயகனான கங்கராஜன் என்பான் தாக்கி வெற்றி கொண்டு கைப்பற்றியிருக்கிறான். இது ஹொய்சள சாசனங்களிலே விரிவாக வருணிக்கப்பட்டுள்ளது. (ஹெ-மூன்றாம் வால்பூம், சிரவணபெளகொள 240 - பழைய எண் 90.)

கங்கவாடியில் அடைந்த வெற்றியோடு ஹொய்சளர்கள் நின்று விடவில்லை. அதன் எல்லையைத் தாண்டி அப்பாலும் படைநடத்திச் சென்றார்கள். அந்தக் காலத்து ஹொய்சள சாசனங்களிலே விஷ்ணுவர்த்தன் ஆட்சிக்குட்பட்ட பிரதேசத்தின் தென்பகுதி கொங்கு, சேரம், ஆனைமலை ஆகியவைகளை உள்ளடக்கியிருந்ததெனக் கூறப்பட்டுள்ளது. விஷ்ணு

வர்த்தனன் மதுரையைத் தன் உள்ளங்கையிலே வைத்துக் கசக்கினான். (மே. ஆறாம் வால்பூம், சிம்மகநூர் 160.) அவனுடைய வெற்றிப்படை இராமேசுவரம் வரையில் கூடச் சென்ற தாம். (சாசன இலாகாவின் 1913-ஆம் ஆண்டு அறிக்கை, 47 பாரா.)

இவ்விதம் ஹொய்சளர்கள் சோழநாட்டுள் புகுந்து போரிட்டுச் குறையிட்டது தென்பகுதியோடு நின்று விடவில்லை. கிழக்கு முகமாகவும் அவர்கள் தங்கள் போர்ப்படையை நடத்திச் சென்றிருக்கிறார்கள். அதன் பயனாகத் தேரேயூர், கோயத்தூர் (இப்போது சித்தூர் ஜில்லாவில் உள்ள லட்டிகம் ஆகும்) ஆகிய இடங்கள் விஷ்ணுவர்த்தனன் ஆட்சிக்குட்பட்டன. அவன் காஞ்சிபுரத்தையும் கைப்பற்றி அதைக் கொண்டாடுவதற்காகக் காஞ்சிகோண்டவன் என்ற விருதையும் தரித்துக் கொண்டான். அவன் 'காஞ்சிபுரத்தையும் மதுரையையும் கைப்பற்றிய பிறகு ஜனநாதபுரத்தையும் சுட்டு எரித்தான்' என்று அவனுடைய சாசனங்கள் கூறுகின்றன. (எபி. கருட்டிசா, ஆறாம் வால்பூம், சிம்மகநூர் 160). அன்றி, அவன் ஆந்திர அரசன் ஒருவனைக் கொன்றதாகவும் புகழப்படுகிறான். (மைசூர் சாசனங்கள், பக்கம் 123). அவன் எரியூட்டிய ஜனநாதபுரம் என்பது வேங்கி நாட்டின் தலைநகராக விளங்கிய திராக்ஷாராமத்தின் மறுபெயரேயாகும்.

திராக்ஷாராமத்திலிருந்து பரார்த்தகனுடைய ஆட்சியைச் சேர்ந்தனவாகச் சுமார் அரை டஜன் சாசனங்கள் கிடைத்துள்ளன. (தே. இ. சாசனங்கள், நான்காம் வால்பூம், நெ. 1270-1274. இன்னும் 1275-A). அவற்றிலே இவனுடைய ஆட்சியின் ஆண்டு குறிக்கப்படவில்லை. பரார்த்தக தேவனுக்கு விசுவாசமாக இருப்பதாகச் சிலர் ஆணையிட்டு உறுதி கூறிய விவரத்தை எடுத்துரைக்கின்றன, அந்தக் கல்வெட்டுகள். அவர்கள் அவ்விதம் ஆணையிட்டுச் சபதம் எடுத்துக் கொள்ளவேண்டிய சந்தர்ப்பம் என்னவென்பது குறிக்கப்பெறவில்லை. எனினும், அவற்றில் ஒரு விஷயம் கவனிக்கத்தக்கது. அவர்கள் பரார்த்தக தேவனுக்கு விசுவாசமாக இருப்பதாகக் கூறுகிறார்களேயல்லாமல் சோழ ஸாம்ராஜ்யத்துக்கோ சிங்காதனத்துக்கோ அல்லது சாளுக்கிய ராஜ்யத்துக்கோ சிங்காதனத்துக்கோ அவ்விதம் விசுவாசமாக இருப்பதாகத் தெரிவிக்கவில்லை.

இவற்றைக் கவனிக்கும்போது அந்நாளிலே பராந்தகனுக்கு உள்ள உரிமைகளைப்போன்ற சம உரிமைகள் பெற்ற வேறு ஒருவன் இருந்தானென்றும், ஆயினும் இவ்விதம் விசுவாசப் பிரதிஜ்ஞை எடுத்துக்கொண்டவர்கள் அவனுக்கு எதிராகப் பராந்தகனையே ஆதரித்து நின்றவர்கள் என்றும் கொள்ளக் கூடும்.

இன்னும், காஞ்சீபுரத்தைக் கைப்பற்றி ஜனநாதபுரத் தைச் செந்தழல் கொளுத்திய புகழை ஹொய்சள மன்னனான விஷ்ணுவர்த்தனனுடைய தண்டநாயகர்களே யன்றி, அதே காலத்தில் கல்யாணபுரத்திலிருந்து அரசு செலுத்திய அரச னான ஆறும் விக்கிரமாதித்தியனுடைய தண்டநாயகர்களும் பகிர்ந்து கொள்ளுகிறார்கள். ஆரம்ப காலத்திலிருந்தே ஹொய்சளர்கள் மேலைச்சாளுக்கியர்களுடைய ஆதிக்கியத்துக்கு அடங்கிய சிற்றரசர்களாக இருந்துவந்தார்கள். இப்போதும் அப் படியேதான் இருந்தார்கள். ஆகவே அவர்கள் நடத்திய போர் தங்களுடைய பேரரசர்களான மேலைச் சாளுக்கியர்களுடைய ஆதரவிலும் மேற்பார்வையிலும் நடைபெற்றதாக இருத்தல் வேண்டும்.

இதைக்கொண்டு கவனித்தால் தமிழ் நாட்டின் மத்திய பாகத்திலே போர் புரிந்ததாக ஆடுதுறைக் கல்வெட்டில் குறிக்கப் பெற்றிருக்கும் பெரியவடுகன் மேலைச் சாளுக்கிய மன்ன னான ஆறும் விக்கிரமாதித்தியனாகவே இருத்தல் வேண்டும் என்பது தெளிவாகும்.

இந்தக் காலத்திலே சோழ ஸாம்ராஜ்யத்தின் வட பகுதியில் நடந்த போரின் விவரம் நமக்குக் கிடைக்கவில்லை. ஆயினும் ஒன்று தெரிகிறது. அந்தப் போரின் பயனாக அதன் முடிவில் தெலுங்கு நாடு முழுவதும் விக்கிரமாதித்தியன் வசம் ஆகியது. இது அந்நாட்டிலே கிடைக்கும் அவனுடைய கல் வெட்டுக்களினின்றும் தெளிவாகிறது.

இவ்விதம் சாளுக்கிய விக்கிரமாதித்தியனும் அவன் சிற்றரசனான ஹொய்சள விஷ்ணுவர்த்தனனும் தங்களுக்குள்ளாகவே நிர்ணயித்துக் கொண்டு வடக்கிலிருந்தும் மேற்கிலிருந்தும் படையெடுத்து வந்து சோழ நாடு முழுவதையும் விஜயம் செய்தார்கள்.



இதே சமயத்தில் தான் விக்கிரம சோழன் சிங்காதனம் தனக்கே உரியதென்று கூறி அதை அடைவதற்காகத் தன் சகோதரனோ மாற்றாந்தாய் வயிற்றில் பிறந்தவனோ ஆன பராதகனோடு போரிட்டுக் கொண்டிருந்தான். தானே பட்டத்துக்கு வாரிசு என்று அவன் அறிவித்த பிறகே இந்தப் படையெடுப்பு கள் நடந்தனவென்றும் கூறலாம். குண்டுர் ஜில்லாவில் உள்ள நிடுப்ரோலுவில் சோழேச்வர ஆலயத்தின் முன்னே காணும் ஒரு தூணில் விக்கிரம சோழனுடைய கல்வெட்டு ஒன்று (தே. இ. சாஸனங்கள், ஆறாம் வால்பூம், 123 நெ.) பொறிக்கப் பட்டுள்ளது. திரிபுவன சக்கரவர்த்தி விக்கிரம சோழனுடைய ஆட்சியின் பதினேழாம் ஆண்டுக்குச் சரியான சகாப்தம் 1054-ல் வெலநாண்டி கோங்காவின் மாதூலனும் தண்டாதி பனுமான மாராய பண்டன் என்பான் இக்ஷாப்பள்ளியில் எழுந்தருளியிருக்கும் கோங்கேச்வரர் ஆலயத்துக்கு விளக்கு எரிக்கவும் வேறு நிவந்தங்களுக்கும் தானம் அளித்த செய்தியைக் கூறுகிறது. அதன்படி விக்கிரம சோழன் சகாப்தம் 1038 அதாவது கி.பி. 1115-16-ஆம் ஆண்டு பட்டத்துக்கு வந்தவன் என்பது ஆகும். இது அவன் ஆட்சியின் ஆரம்பகாலமாகப் பொதுவாகக் கொள்ளப்பட்டுவரும் 1118-ஆம் வருஷத்துக்கு மூன்று ஆண்டுகள் முற்பட்டதாகும்.

சோழ சிங்காதனத்துக்காக இவ்விதம் பிள்ளைகள் இருவரும் சண்டை போட்டு வந்த சமயம் குலோத்துங்கனும் உயிரோடு இருந்திருக்கிறான். இரு குமாரர்களுள் அவன் யாரை ஆதரித்தான் என்பது வெளிப்படையாகத் தெரியவில்லை. ஆயினும் அவன் ஏற்கெனவே இளவரசுப் பட்டம் கட்டி இராஜ்யபாரத்தில் ஈடுபடுத்திய பராதகனை ஆதரித்து நின்றிருப்பான் என்று கொள்வதே இயற்கை. பராதகனுடைய சாசனங்களும் இங்கிலேயையே தெளிவாக எடுத்துணர்த்துகின்றன. அவ்விதமாயின் விக்கிரம சோழன் தன் லட்சியம் பூர்த்திபெறுவதற்குச் சகோதரன் பராதகனோடு மட்டுமல்லாமல் தந்தையான குலோத்துங்க சோழனோடும் போரிட்டிருத்தல் வேண்டும். தந்தையின் ஜீவதசையிலேயே அவன் வெற்றி கொண்டதை நோக்கினால் அவனுக்கு நாட்டிலே பலம் பொருந்தியவர்களும் நல்ல செல்வாக்குள்ளவர்களுமான ஒரு

சாராரின் ஆதரவோடு மட்டுமல்லாமல் சோழர்களுக்குச் சமமான அல்லது அவர்களைக் காட்டிலும் அதிகப்பலம் வாய்ந்த வேற்றரசு ஒன்றன் ஆதரவும் கிட்டியிருத்தல் அவசியம் எனக் கொள்ளலாம். அவன் குலோத்துங்கனுக்குச் சோழ ராஜ குமாரியான மதுராந்தகியின் வயிற்றில் பிறந்த மகன் அல்ல; ஹொய்சள அரசிளங்குமரி ஒருத்தியின் வயிற்றில் பிறந்தவன். இது குலோத்துங்கசோழன் உலாவிவிருந்து தெரிகிறது. (இரண்டாம் இராஜாதிராஜனுடைய பல்லவராயன்பேட்டைக் கல்வெட்டைப் பற்றிய ஒரு குறிப்பு என்ற கட்டுரையில் விவரமாக ஆராயப்பட்டுள்ளது. ஸ்ரீ க. அ. நீலகண்ட சாஸ்திரிகளுடன் கூட்டாக எழுதப்பெற்ற அக்கட்டுரை எபி. இந்திகாவில் வெளிவரும்.)

“வேற்றார்

விரும்பரணில் வெங்களத்தீ வேட்டுக் கலிங்கப்  
பெரும்பரணி கொண்ட பெருமான்—தரும் புதல்வன்  
கொற்றக் குலோத்துங்க சோழன் குவலயங்கள்  
முற்றப் புரக்கு முகில்வண்ணன்—போற்றவரை  
இந்து மரபில் இருக்குந் திருக்குலத்து  
வந்து மனுகுலத்தை வாழ்வித்த—பைந்தளிர்க்கை  
மாதர்ப் பிடிபெற்ற வாரணம்அவ் வாரணத்தின்  
காதற் பெயரன் களகளபன் ”

(கண்ணிகள் 28-31)

அதனால் விக்கிரம சோழன் சிங்காதனம் ஏறியதாகக் கணக்கிடப்படும் நாளுக்குச் சிறிது முன்னதாக, ஹொய்சள மன்னனை விஷ்ணுவர்த்தனன் தன் பேரரசனும் முதற் குலோத்துங்க சோழனுடைய பரம வையியுமான மேலைச் சாளுக்கிய வேந்தன் ஆறாம் விக்கிரமாதித்தியனுடைய ஆதரவும் உதவியும் பெற்றுச் சோழநாட்டின் தென்பகுதி வடபகுதி போன்ற பல இடங்களிலும் பிரதானமாக நின்று போரிட்டு வெற்றி கொண்டது, விக்கிரம சோழனைச் சிங்காதனத்தில் அமர்த்துவதற்காகவே போலும். அதுவும் உறவு முறையால் உந்தப்பட்டதாக இருக்கலாம். இன்னும், இந்தப் போரின் பயனாகச் சோழர்கள் மேற்கே கங்கவாடியையும் வடக்கே வேங்கியையும் இழந்தனர். அவற்றை முறையே ஹொய்சளர்களுக்கும் மேலைச்சாளுக்கியர்களுக்கும் அவர்கள் தனக்கு

உதவியதற்காக விக்கிரம சோழன் கொடுக்க வேண்டி நேர்ந்தது போலும்.

தென்திருவாங்கூர்ப் பகுதியில் பின்வரும் தமிழ்ப் பாடல் ஒன்று சாதாரணமாக வழங்கிவருகிறது.

எத்திசையும் புகழ்ப்படைத்த கொல்லம் தோன்றி  
இருதூற்றுத் தொண்ணூற்றிரண்டாம் ஆண்டு

தத்திவிழும் பறளியாறு அணையும் தள்ளித்  
தமிழ்ப்பாண்டி ராஜசிங்கம் தனையும் வென்று  
கொத்தவரும் பூஞ்சோலை நாஞ்சில் நாகும்  
கோட்டாறும் கூபகர்கோன் கொண்டநாளே ”

(டாக்டர் கே.கே. பிள்ளை, எழுதிய சூசீந்திரம்கோயில், பக்கம் 30)

கொல்லம் இருதூற்றுத் தொண்ணூற்றிரண்டாம் ஆண்டில் கூபக அரசன் ஒருவன் பாண்டிய ராஜஸிம்ஹனை வெற்றி கொண்டு நாஞ்சில் நாட்டையும் கோட்டாற்றையும் கைப் பற்றினான் என்று கூறுகிறது இந்தப் பாடல். கோட்டாற்றுக் கோட்டையைக் குலோத்துங்கன் பலப்படுத்தி அவ்விடத்திலே ஒரு நிலைப்படையை நிறுவினான் என்பதை நாம் அறிவோம். பாண்டிய மன்னனான ஜடாவர்மன் பரார்தக பாண்டியன் என்பான் விக்கிரம சோழனோடு தெலுங்கவீமனுடைய குளம் (அதாவது இப்போது கொல்லேறு ஏரிக்குப் பக்கத்தில் ஏலாரு என்று வழங்கப்பெறும் கொலனு) என்னும் இடத்தையும் தென்கலிங்கத்தையும் வென்று அடிப்படுத்தினான் என்று அவனுடைய மெய்க்கீர்த்தி தெரிவிக்கிறது. (திருவாங்கூர் ஆர்க்கியலாஜிகல் ஸீரீஸ், முதல் வால்யூம், 15-பக்கம்). அவன் கூபகர்கோன் மகளை மணந்து கொண்டவன் என்பதும் அம்மெய்க்கீர்த்தியிலிருந்தே தெரியவருகிறது. குலோத்துங்கன் அமைத்த வலிமையான பாதுகாப்பையும் மீறிக் கூபகர்கோன் சுதந்திரத்தை நிலைநிறுத்த முயன்றது விக்கிரம சோழனுடைய கிளர்ச்சியின் ஒரு பகுதியே போலும்.

இரண்டாம் குலோத்துங்கனும் இரண்டாம் இராஜராஜனும்

விக்கிரம சோழனுக்குப் பிறகு இரண்டாம் குலோத்துங்கன் சிங்காதனம் ஏறினான். பொதுவாக அவனை விக்கிரம

சோழன் மகன் என்றே கொள்வார். அவனுடைய செல்லூர்ச் செப்பேடுகளும் அப்படியே கூறுகின்றன. (தே.இ. சாசனங்கள், முதல் வால்பூம், 39௩௭; இந்தியன் ஆண்டிசுவரி, பத்தொன்பதாம் வால்பூம், பக்கம் 427). ஆயினும் உண்மையில் அவன் விக்கிரம சோழனுடைய பெயரே. பெண் வயிற்றுப் பேரன். 'புத்திரிகா புத்திரன்' என்றபடி பின்னால் மகனாக ஸ்வீகரிக்கப்பட்டவன் போலும். இது இரண்டாம் இராஜாதிராஜன் காலத்தைச் சார்ந்த பல்லவராயன்பேட்டைக் கல்வெட்டிலிருந்து நன்கு விளங்குகிறது. (இக் கல்வெட்டு பற்றி மேலே குறித்துள்ள கட்டுரையில் இது விவாதிக்கப்பட்டுள்ளது). 'விக்கிரம சோழன் பெயரால் நெறியுடைப் பெருமாள் திருமகனார் எதிரிலிப் பெருமாள்' என்று சாசனத்தில் குறிக்கப்பட்டிருப்பவன் இரண்டாம் குலோத்துங்கனே யாவன். அவன் மகுடாபிஷேகமே இராஜாதிராஜன் முடிசூட்டுக்கு ஓர் உதாரணமாக அமைந்திருந்தது என்பது 'முன்னாளிலே காரியம் இருந்தபடி வி[சாரண] செய்து' என்று சாசனத்தில் வரும் பகுதியால் விளங்கும்.

குமார குலோத்துங்கன் என்று தமிழ் இலக்கியங்களில் குறிக்கப்படுபவனும் இரண்டாம் குலோத்துங்கனே போலும். அவன் தன் இளமைப்பருவம் முதல் பாட்டன் விக்கிரம சோழனிடத்திலேயே வளர்ந்து, ஆஸ்தானக் கவிஞரான ஒட்டக்கூத்தரிடம் மாணவனாக இருந்துவந்தான்.

“ ஆடுங் கடைமணி நாவசை  
யாமல் அகிலமெல்லாம்  
நீடுங் குடையிற் றரித்த  
பிரானென்று நித்தநவம்  
பாடுங் கவிப்பெருமா னெட்டக்  
கூத்தன் பதாம்புயத்தைச்  
குடுங் குலோத்துங்க சோழனென்  
றேயெனைச் சொல்லுவரே”

என்று முற்பகுதி கவிஞராலும் பிற்பகுதி அரசனாலும் பாடப் பெற்றதாகத் தமிழ் நாவலர் சரிதையில் உள்ள பாடல் (132) இதை நன்கு விளக்கும்.

தஞ்சாவூர் ஜில்லாவிலே திருமயானத்திலிருந்து கிடைக்கும் மூன்றாம் குலோத்துங்க சோழனுடைய ஆட்சியின் ஒன்பதாம் ஆண்டு கொண்ட கல்வெட்டு ஒன்று (1925-ஆம் ஆண்டு 259 நெ.) பெரியதேவர் நாளையிலே மூன்றாம் ஆண்டு கொமர குலோத்துங்க சோழச்சதூர்வேதி மங்கலத்திலே விலை கொண்டு திருக்கடவூர்த் திருமயானம் உடையாருக்கு விட்ட நிலத்தின் மீது உள்ள கடமை குடிமை வரிகளை நீக்கி மணல்குடியான உத்தம சோழச் சதூர்வேதி மங்கலத்துப் பெருங்குறிப் பெருமக்கள் அளித்த உத்தரவைத் தெரிவிப்பது. அதிலே பெரிய தேவர் என்று குறிக்கப்பெற்றிருப்பவன் அவனுக்கு முன் அரசாண்ட இரண்டாம் இராஜாதிராஜனாகவே இருந்தல் வேண்டும். அதே ஜில்லா திருவிழிமிழலையில் கிடைக்கும் இராஜகேசரிவர்மனான திரிபுவன சக்கரவர்த்திகள் என்பானுடைய சிதிலமான கல்வெட்டு (1908-ஆம் ஆண்டு 420 நெ.) ஒன்று கொமரன் குலோத்துங்க சோழச் சதூர்வேதி மங்கலத்தைப் பற்றிக் குறிக்கிறது. அந்தச் சாசனத்தை அளித்த இராஜகேசரிவர்மனும் இரண்டாம் இராஜாதிராஜனே என்பார். இவற்றால் இரண்டாம் இராஜாதிராஜன் ஆட்சியிலேயே குமார குலோத்துங்க சோழச் சதூர்வேதி மங்கலம் என்னும் கிராமம் இருந்து வந்ததென்பதும், அதனால் அந்தக் கிராமத்துக்குப் பெயரை அளித்த குமார குலோத்துங்கனும் அதற்கு முற்பட்டவனாக இருந்தல் வேண்டுமென்பதும் தெளிவாகும்.

இரண்டாம் குலோத்துங்கன், அவனுக்குப் பின் பட்டத்துக்கு வந்த அவன் மகன் இரண்டாம் இராஜராஜன் ஆகியோருடைய ஆட்சிக்காலம் சண்டை சச்சரவு எதுவும் இல்லாமல் அமைதியாகவும் சுபிக்ஷமாகவும் நடைபெற்றதெனவே கொள்வார். அவர்களுடைய மெய்க்கீர்த்திகள் பல கிடைத்துள்ளன. எனினும் அவற்றிலே அவர்களுடைய வெற்றிச் செய்திகள் ஏதும் காணப்பெறவில்லை.

ஆயினும் இலக்கியங்களிலே இரண்டு வெற்றிகள் இரண்டாம் இராஜராஜனுக்கு ஏற்றிக் கூறப்படுகின்றன. ஒன்று காவிரியாற்றுக்கு நடுவே ஏற்பட்ட அடைப்பை நீக்கி வழி

கண்டது. இச்செய்தி அவன் ஆஸ்தானப் புலவரும் ஆசிரியப் பெருமானுமான ஒட்டக்கூத்தராலே தக்க யாகப் பரணியில்,

“அலைகொன்று வருகங்கை வாராமன் மேன்மேல்  
அடைகின்ற குன்று டறுக்கின்ற பூதம்  
மலைகொன்று போன்னிக்கு வழிகண்ட கண்டன்  
வரராசன் ராசன்கை வாளென்ன வந்தே”

(தாழிசை-549)

என்றும், இராஜராஜ சோழன் உலாகிலே,

“சுழியிட்ட காவிரிக்குச் சோணடு வாழ  
வழியிட்ட வாள்காண வாரீர்”

(கண்ணி-85)

என்றும் குறிக்கப்பட்டிருக்கிறது. நோல்காப்பியம் நச்சினூர்க் கினியர் உரையில் மேற்கோளாக எடுத்துக் காட்டப்பெற்ற பழம் பாடல் ஒன்றிலும்,

—“சைய

மலைச்சிறைதீர் வாட்கண்டன் வெள்ளணிநாள் வாழ்த்திக்  
கொலைச்சிறைதீர் வேந்துக் குழாம்”

(பொருள், புறத்திணை, சூத்திரம் 36.)

என்று இது குறிக்கப்பெற்றுள்ளது. காவிரியின் குறுக்கே அணைபோட்டு நீரை வேறு வழியில் திருப்பியதைப் பற்றிச் சரித்திர பூர்வமாக நமக்குக் கிடைக்கும் முதற் குறிப்பு இதுவே யாகும். இவ்விதம் அணைபோட்டு நீரைத் திருப்பியவன் ஹொய் சள மன்னனாகவே இருத்தல் வேண்டும். அதனால் சோழனும் ஹொய்சளர்மீது போர்தொடுத்தே அணையை உடைத்து நீரைச் சோழநாட்டுக்குக் கொணர்ந்திருத்தல் வேண்டும். இரண்டாம் குலோத்துங்கன் காலத்திலே இயற்றப்பெற்ற பெரியபுராணத்திலே அதன் ஆசிரியர் சேக்கிழார் தம்மை ஆதரித்த சோழன் அநபாயணப் பற்றி,

“பொன்மலைப் புலிகின் ரோங்கப்

புதுமலை யிடித்துப் போற்றும்

அந்நெறி வழியே யாக

அயல்வழி யடைத்த சோழன்

மன்னிய அனபா யன்சீர்

மரபின்மா நகர மாகும்

தொன்னெடுங் கருவு ரென்னுந்  
சுடர்மணி வீதி மூதார்”

(எறிபத்த நாய்னார் புராணம், பாடல் 2)

என்று பாடியிருக்கிறார். இந்தப் பாடலும் இதே செய்தியைக் குறிப்பதுபோலும். அவ்விதமானால் ஒட்டக்கூத்தர் இப்புகழை இரண்டாம் இராஜராஜனுக்கு ஏற்றிக் கூறும்போது அதையே சேக்கிழார் அவன் தந்தையான இரண்டாம் குலோத்துங்கன் புகழாகக் கொள்கிறார். இவற்றால், இவ்விருவரும் இதே புகழுக்கு உரியர் என்பது பெறப்படும். கி. பி. 1145-ஆம் ஆண்டு முதல் கி. பி. 1150-ஆம் ஆண்டு வரையில் தந்தை, மகன் ஆகிய இருவரும் சேர்ந்து அரசு புரிந்திருக்கிறார்கள் என்பதை நாம் அறிவோம். ஆகவே இந் நிகழ்ச்சி இந்த இடைக் காலத்தில், அதாவது தந்தை குலோத்துங்கனுடைய ஜீவதசையிலே மகன் இராஜராஜன் தலைமையில் நடந்தது எனக் கொள்ளலாம்.

மற்றொன்று, அவன் கல்யாண புரத்துச் சிங்காதனத்திலே மேலைச் சாளுக்கிய அரசன் ஒருவனை அமர்த்தியது. தக்க யாக பரணியின் கடைசியில் உள்ளதான வாழ்த்துப் பகுதியிலே ஆசிரியர் ஒட்டக்கூத்தர் இரண்டாம் இராஜராஜனைப் பின் வருமாறு வாழ்த்துகிறார்.

“பிரட்டனை யேபட்டங் கட்டழித்துப்

பேரே முரையிலக் கம்புரக்க

இரட்டனை யேபட்டங் கட்டிவிட்ட

இராசகம் பிரனை வாழ்த்தினவே”

(தாழிசை—774)

இவ்விடத்தில் இரட்டன் என்று குறிப்பிடப் பெறுபவன் இரட்டபாடி ஏழரையிலக்கம் என்னும் பூமிக்கு உரியவனான மேலைச் சாளுக்கியனே ஆவன். தமிழ் நாவலர் சரிதையில் இச்சோழ மன்னனைப் பற்றிப் பின் வரும் பாடல் காண்கிறது.

“கரத்துஞ் சிரத்துங் களிக்குங்

களிறுடைக் கண்டன் வந்தான்

இரத்துங் கபாட மினித்திறப்

பரப்பண் டிவன் ணங்கே

உரத்துஞ் சிரத்துங் கபாடந்  
திறந்திட்ட துண்டி லங்கா  
புரத்துங் கபாட புரத்துங்கல்  
யாண புரத்தி னுமே ”

(பாடல்-128)

பாண்டியர் தலைநகரான மதுரை, இலங்கைத் தலைநகரான லங்காபுரம் ஆகியவற்றைப்போல மேலைச் சாளுக்கியர் தலைநகரான கல்யாணபுரம் அவனுக்கு எப்போதும் வாயில் திறந்திருந்ததாம், அதாவது அவன் ஆணைக்கு அடங்கியிருந்தது என்று கூறுகிறது இந்தப் பாடல்.

அந்நாளிலே மேலைச் சாளுக்கிய நாட்டிலே பெருத்த மாறுதல்கள் நடைபெற்று வந்தன வென்பதை நாம் அறிவோம். சாளுக்கிய அரசனாக இருந்த மூன்றாம் தைலபனுக்குக் கீழ்ப்பட்டிருந்த கலகூரி வமிசத்துப் பிஜ்ஜலன் கொஞ்சம் கொஞ்சமாக அதிகாரத்தைக் கைப்பற்றிச் சிறிது காலத்திலே அரசு முழுவதையும் கைக்கொண்டு தன் பேரரசனையே துரத்திவிட்டான். அரசையும் சிங்காதனத்தையும் இழந்த தைலபன் எல்லைப்புற மாகாணங்களை அடைந்து அவ்விடங்களிலிருந்த விசுவாசமான சிற்றரசர்கள் ஆதரவோடும் உதவியோடும் அரசு புரிந்துவந்தான். சுமார் கி. பி. 1163-ஆம் ஆண்டில் அவன் இறந்ததாகத் தெரிகிறது. அதேசமயம் (மூன்றாம்) ஜகதேகமல்லன் மேலைச் சாளுக்கிய விருதுகள் எல்லாவற்றையும் தாங்கி அரசு புரிய ஆரம்பித்திருக்கிறான். இந்த ஜகதேகமல்லனைச் சிங்காதனத்தில் அமர்த்துவதற்காக வே இரண்டாம் இராஜராஜன் மேலைச் சாளுக்கிய ராஜ்ய விவகாரத்தில் தலையிட நேர்ந்தது போலும். இப்போது உள்ள நிலையிலே நமக்கு முழு விவரங்கள் கிடைக்க வில்லை. ஆகவே அது எந்த வகையில் கைகூடியது என்பதை நாம் நிச்சயமாகக் கூறமுடியாது.

இந்த இரு சம்பவங்களும் மெய்க்கீர்த்திகளில் காணப்பட வில்லையென்பதை நாம் முன்னரே கூறியிருக்கிறோம். எனினும் மெய்க்கீர்த்திகளிலிருந்தும் சில விவரங்கள் நமக்குத் தெரியவருகின்றன.



‘பூமன்னு பதுமம்’ என்று தொடங்கும் இரண்டாம் குலோத்துங்கனுடைய மெய்க்கீர்த்தியிலே பின்வரும் பகுதியும் உள்ளது:

—“ பல்லவர்

தெலுங்கர் மாளுவர் கலிங்கர் கோசலர்  
கன்னடர் கடாரர் தென்னவர் சேரலர்  
சிங்கணர் கொங்கணர் சேதிபர் திரிகர்த்தர்  
வங்கர் அங்கர் வத்தவர் மத்திரர்  
கங்கர் சோனகர் கைகையர் சீனரென்  
றறைகழல் வேந்தரும் எல்லா வரைசரும்  
முறைமையில் வருந்தித் திறைகொணர்ந் திறைஞ்சு”

குலோத்துங்கன் பிள்ளைத்தமிழிலே பாட்டுடைத் தலைவனான இரண்டாம் குலோத்துங்கன் மகரக் கொடியை யுடைய அரசன் ஒருவனிடம் திறைகொண்டான் என்ற செய்தி காணப்படுகிறது (பாடல் 56). கடாரம் எனப்படும் ஸ்ரீவிஜய நாட்டு மன்னர்களான சைலேந்திரர்களுக்கு மகரக் கொடி இருந்த தென்பது லீடன் (பெரிய) பட்டயங்களிலிருந்து தெரிகிறது. (எபி. இந்திகா, இருபத்திரண்டாம் வால்பூம், 242-257 பக்கங்கள்.) அதிலே அவன் மகரத்வஜம் கொண்டவன் என்று குறிக்கப் பெறுகிறான். இதைக்கொண்டு கவனித்தால் மெய்க்கீர்த்தியிலே கடாரர் என்று குறிக்கப்பெறுபவர் ஸ்ரீவிஜய நாட்டுச் சைலேந்திர மன்னர்களே என்பதும் இரண்டாம் குலோத்துங்கன் காலத்திலும் அவர்கள் சோழர்களுக்கு அடங்கியிருந்தனர் என்பதும் தெளிவாகும். இதிலிருந்து கடல் கடந்த பிரதேசங்களில் சோழர்களுக்கு ஆதிக்கியம் இப்போதும் குறையாமல் பழையபடியே இருந்து வந்ததென்று கொள்ளலாம்.

இன்னும் மெய்க்கீர்த்தியிலே திரிகர்த்தர், மத்திரர் ஆகியோர் பெயர்களும் காணப்படுகின்றன. திரிகர்த்தர் என்பார் பஞ்சாபிலே காங்கரா பள்ளத்தாக்கு என்னும் பிரதேசத்தில் அரசுபுரிந்தவர்கள். இதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். மத்திரர் என்பாரும் பஞ்சாப் பிரதேசத்தில் இருந்தவர்களே. லிக்கிரம சோழன் உலாவிலே அம்மன்னனுடைய தண்டநாயகர்களுள் திகத்தன் என்பான் ஒருவனும் இருந்தான் என்று கூறப்பட்டுள்ளது.

—“கோட்டரணக்

கொங்கைக் குலைத்துக் குடகக் குவடடித்த  
செங்கைக் களிற்றுத் திகத்தனும்”

(கண்ணி-88)

அவன் திரிகர்த்த தேசத்திலிருந்து வந்தவனாகவோ அந்  
நாட்டு அரசுக்கும்பத்தைச் சேர்ந்தவனாகவோ இருத்தல்  
வேண்டும். அவ்விதம் இல்லாமல், சோழ மன்னனால் வெறும்  
பட்டம் அளிக்கப்பெற்றவனே அவன் என்று கொள்வதாக  
இருந்தாலும், வெகுதொலைவுக்கு அப்பால் உள்ள அந்நாட்  
டுக்கும் சோழர்களுக்கும் அந்நாளிலே ஏதாவது ஒருவகையில்  
தொடர்பு இருந்திருத்தல் வேண்டும்.

இதேபோல், ‘பூமருவிய பொழிலேழும்’ என்று தொடங்  
கும் இரண்டாம் இராஜராஜனுடைய மெய்க்கீர்த்தியிலும் பின்  
வரும் பகுதி காணப்படுகிறது.

“கன்னடருங் கலிங்கருந் தொற்றவருந் சிங்களருங்  
கைகயருங் கொங்கணருங் கூபகருங் காசிகருங்  
காம்போதருங் கோசலுருங் கொந்தளரும் கப்பளரும்  
பப்பளரும் பாஞ்சாலரும் பொப்பளரும் பூலுவரும்  
மத்திரரும் மாராட்டரும் வத்தவரும் மாகதரும்  
கொடிதுடங்கு கனககோபுரக் கொற்றவாசலில்  
[வந்திண்டி.]”

மெய்க்கீர்த்திகளில் வந்துள்ள இவ்விருபகுதிகளைச் சம்பிரதாய  
மான வெறும் புகழ்ச்சியேயென்றும் அவற்றுக்குப் பிரா  
தான்யம் ஏதும் அளிக்கக் கூடாது என்றும் ஆராய்ச்சியாளர்  
கள் பொதுவாகக் கொள்வர். ஆனாலும் நாடு முழுவதும் ஒவ்  
வொருசாசனத்திலும் காணப்பெறுவதற்காக அரசர்களுடைய  
ஆஸ்தானப்புவர் இயற்றி, அரசாங்க முத்திரையுடன் கூடிய  
மெய்க்கீர்த்திகளில் காணப்பெறுவன இவை என்பதை நாம்  
மறக்கலாகாது. அன்றி, இத்தகைய புகழ்ச்சிகள் இவ்விருவரு  
க்கு முன்னால் ஆண்ட அரசர்கள், பின்னால் வந்த மன்னர்கள்  
ஆகியோருடைய மெய்க்கீர்த்திகளில் காணப்பெறவில்லையென்  
பதையும் நாம் கவனிக்கவேண்டும். இன்னும் இதேபோன்ற  
புகழ்ச்சி அந்தக் காலத்தில் அரசுபுரிந்த மேலைச் சாளுக்கியர்  
களுக்கும் ஏற்றிக் கூறப்படுகிறது.

மேலைச் சாளுக்கிய மன்னனான ஆறாம் விக்கிரமாதித்தியனுக்குப் பின் அவன் மகன் மூன்றாம் சோமேச்வரன் பட்டம் எய்தினான். பூலோகமல்லன், சர்வஜ்ஞ பூபன், சர்வஜ்ஞ சக்கரவர்த்தி என்ற விருதுகளைத் தாங்கிய அவன் “ஆந்திர, திரவிள, மகத, நேபாளர்கள் முடிமேல் அடிவைத்தான் ; அறிஞர்கள் பலராலும் கொண்டாடப் பட்டான்” என்று வருணிக்கப் பெற்றுள்ளான். (ராயல் ஏஷ்யாடிக் ஸோஸைட்டி பம்பாய்க் கிளையின் பத்திரிகை, பதினேராம் வால்பூம், 268 பக்கம்). அவன் மகன் மூன்றாம் தைலபனிடமிருந்து அரசைக் கைப்பற்றியவனும் அதற்குமுன் சாளுக்கியர்களுக்கு அடங்கிய சிற்றரசனாக இருந்தவனுமான பிஜ்ஜலனும் ஒரு சாசனத்திலே, ‘நேபாளத்தை நிலைகுலையச் செய்தவன்’ என்று குறிக்கப்பெறுகிறான். (எபி. இந்திகா, ஐந்தாம் வால்பூம், 29, 149 பக்கங்கள்.) இதே சமயம் நேபாளத்தின் எல்லைப்புறத்திலே, தீர்ஹுத் (தீரபுக்தி), மிதிலா என்னும் இடங்களைக் கர்நாடகத்திலிருந்து சென்ற அரசர்கள் ஆண்டு வந்திருக்கிறார்கள் என்பதையும் நாம் அறிவோம். அந்த வமிசத்தை நிறுவிய முதல் அரசனான நான்யதேவன் என்பான் நேபாளத்தைக் கைப்பற்றினான் என்று நேபாள தேசத்துக் கர்ணபரம்பரையில் கூறப்படுகிறது. இது கி. பி. 1141-ஆம் ஆண்டு நிகழ்ந்ததெனக் கணக்கிட்டிருக்கிறார்கள். (பண்டார்கார் ஓரியண்டல் ரிஸர்ச் இன்ஸ்டிடியூட்டின் பத்திரிகை, 1954-ஆம் ஆண்டு, பக்கம் 18). இதே சமயம் நேபாள இராஜகுமாரன் ஒருவனுக்குச் சோமேச்வரன் என்ற பெயரும் காணப்படுகிறது. நேபாளத்து இராஜ பரம்பரையில் காணும் பெயர்களிலே இந்தப் பெயர் அபூர்வமானது. அன்றி அந்தப்பெயர் அதே காலத்தில் நேபாளத்தை வெற்றி கொண்டதாகக் கூறிக்கொள்ளும் மேலைச் சாளுக்கிய அரசன் பெயராகவும் இருக்கிறது.

மேலைச் சாளுக்கிய அரசனான ஆறாம் விக்கிரமாதித்தியனுடைய ஆதரவு பெற்று விக்கிரமசோழன் சோழ இராஜ்யத்தை அடைந்து சிங்காதனம் ஏறிய பிறகு, அந்த இராண்டு பேரரசுகளுக்கு மிடையில் பெருத்த விரோதம் ஏதும் ஏற்பட்டதாகத் தெரியவில்லை. அதற்கு மாறாக அவ்விருவருக்குமிடையே ஒருவகைச் சமாதானமே நிலவியதெனக் கொள்ளலாம். இன்

னும் இரண்டாம் இராஜராஜன் மேலேச் சாளுக்கியச் சிங்கா  
தனத்திலிருந்து பிரட்டன் ஒருவனை விரட்டியடித்து இரட்  
டனுக்கு முடி சூட்டியிருக்கிறான் என்பதையும் நாம் மேலே  
கண்டோம். இவற்றைக் கவனிக்கும்போது வட நாட்டுப் போரி  
லும் சோழர் சாளுக்கியர் இருவரும் சேர்ந்து ஒன்றாக ஈடு  
பட்டிருத்தல் கூடும் என்று முடிவு செய்யலாம். குலோத்துங்கன்  
பிள்ளைத்தமிழிலே,

“கருநடர் துருக்கர் வடகவுசலர் குகுத்தர்விடு  
கவுரியர்ம கதத்தர் பிறர்கூழ்  
கடலெனவ னைத்தமரர் ககனதல முட்டவொலி  
களிபெருக ளத்தி னிடையே”

(பாடல்-52)

என்று காணப்படுவதிலிருந்து இரண்டாம் குலோத்துங்கன்  
துருக்கர், வட கோசலர் முதலியோருடன் போர் புரிந்தான்  
என்று கொள்ளலாம். அதேபோல, அந்தக் காலத்தில் ஆண்ட  
ஹொய்சள மன்னனை விஷ்ணுவர்த்தனனும் துருக்கர்களை  
வெற்றிகொண்டதாகக் கூறிக்கொள்கிறான். ‘பொய்சள  
தேவன் கைவாள் ஆன பல்ல போர்க்கடேயின் விசுவாசமான  
ஊழியன் கொலேவூர் பீட்டி என்பான் அநேகம் துருக்கர்  
களைக் கொன்று தானும் இறந்தான் என்னும் செய்தியை ஒரு  
கல்வெட்டு (எபி. கர்நாடிகா, ஆறாம் வால்பூம், முத்ரகரெ. 3,)  
எடுத்துக் கூறுகிறது.

இரண்டாம் இராஜாதிராஜனும் மூன்றாம் குலோத்துங்கனும்

அந்தபூர் ஜில்லா மடகசிரா தாலுகாவில் ஹேமவதியி  
லிருந்து கிடைத்துள்ள தமிழ்ச் சாசனம் ஒன்று திரிபுவன  
சக்கரவர்த்தி குலோத்துங்க சோழதேவனுடைய ஆட்சியின்  
இரண்டாம் ஆண்டும் வியய வருஷமும் கொண்டு காணப்படு  
கிறது. வட்டவிவஹாரியும் தேசிமுக்கியருமான சிக்கில் உடைய  
செட்டியார் என்பார், நிகரிவிசோழமண்டலத்துச் சிரை நாட்  
டுப் பெருஞ்செறுவில் எழுந்தருளியிருக்கும் மங்கேசுவர தேவ  
ருக்குச் சில நிவந்தங்களுக்காக நிலம் அளித்த செய்தியைக்  
கூறுகிறது அந்தக் கல்வெட்டு. (தே. இ. சாசனங்கள், ஆறாம்  
வால்பூம், 553 நெ. இந்தச் சாசனம் எபி. இந்திகாவில் வெளி

யிடப் பெறுவதாக ஸ்ரீ க. அ. நீலகண்ட சாஸ்திரிகளுடன் கூட்டாகப்பதிப்பிக்கப்பெற்றுள்ளது.) அவன் அந்தத் தானத் தை அளிக்க ஸ்ரீமான் மகாமண்டலேச்வர உறையூர் புரவராதீச்வர ஸ்ரீமாஹேச்வரன் திரிபுவனமல்ல மல்லிதேவ சோழ மஹாராஜாவின் அங்கீகாரத்தைப் பெற்று அரசர் திருக்கை மலரிலே நீர் வார்த்துக் கொடுத்தான் என்றும் கூறுகிறது அந்தச் சாசனம். சாசனத்தில் காணப்பெறும் திரிபுவனமல்ல மல்லிதேவ சோழ மகாராஜா அந்தப் பகுதியிலே கிடைக்கும் வேறு சாசனங்களிலும் காணப்படுகிறான். ஹெஞ்சேறு (அதாவது பெருஞ்சேறு என்பதன் கன்னடப் பெயரே) நகரைத் தலைமையிடமாகக் கொண்டு சிரைநாட்டுப் பகுதியை ஆண்டு வந்த நிடுகல் சோழர் எனப் பெறும் தெலுங்குச் சோழர் வமிசத்தைச் சேர்ந்தவன். அவனுடைய சாசனங்கள் கி. பி. 1162 முதல் கி. பி. 1179 வரையில் கிடைக்கின்றன. (ஹெ-ஒன்பதாம் வால்பூம், 208, 273. நெ. சாசனங்கள்.) ஆகவே ஹேமவதிச் சாசனத்தில் காணும் வியய வருஷம், சகாப்தம் 1088-க்குச் சரியான கி. பி. 1166-67-ஆம் ஆண்டு வருவதே ஆகும். அது குலோத்துங்கனுடைய ஆட்சியின் இரண்டாம் ஆண்டு ஆகுமானால் அவன் சிங்காதனம் ஏறியது அதற்குமுதல் வருஷமான கி. பி. 1165-66 ஆம் ஆண்டு ஆகும். குலோத்துங்கனுடைய ஆட்சியின் ஆரம்ப காலம் இதுவல்ல. சோழர்களிலே வேறு எந்த அரசனும் இவ்வாண்டிலே சிங்காதனம் ஏறியதாகக் கொள்ளவில்லை. ஆனால், இரண்டாம் இராஜாதிராஜனுடைய ஆட்சி ஆண்டுகளில் ஒருவகைக் கணக்கில் அடங்கியவை கி. பி. 1166-ஆம் ஆண்டு ஏதோ ஒரு தேதியிலிருந்து கணக்கிடப்படுவதை நாம் அறிவோம்.

பல்லவராயன்பேட்டைக் கல்வெட்டிலிருந்து (எபி. இந்திகா, இருபத்தோராம் வால்பூம், பக்கங்கள் 184-93) இரண்டாம் இராஜராஜன் தனக்குப்பின் சிங்காதனம் ஏறப் பட்டதுக்கு உரிய பிள்ளைகள் இல்லாமையைக் கண்டு இராஜாதிராஜன் என்பாளைத் தேர்ந்து எடுத்து முடிசூட்டிய விவரம் தெரியவருகிறது. இதற்காக அவன் கங்கைகொண்ட சோழ புரத்திலிருந்து இராஜ குமாரர்கள் சிலரைப் பிரயாணம் பண்ணுவித்துக் கொணர்ந்தான். அவர்களிலே இராஜாதிராஜன் தேர்ந்தெடுக்கப்பட்டான். அவ்விதம் வந்து தேர்ந்

தெடுக்கப்பெறாமல் ஏமாற்றம் அடைந்து திரும்பியவர்களுள் குலோத்துங்கனும் ஒருவன் போலும். இராஜாதிராஜனைத் தேர்ந்தெடுத்து முடி சூட்டியதில் அரசனுக்கு ஒரேமுகமான ஆதரவு இருக்கவில்லை யென்றும் மிகவும் சிரமப்பட்டே அந்த எதிர்ப்புக்களை ஒரு வழியாக அவன் சமாளிக்க வேண்டியிருந்ததென்றும் சாசன வாசகம் தெளிவாக எடுத்துக் காட்டுகிறது. குலோத்துங்கன் தான் தேர்ந்தெடுக்கப்படாவிட்டாலும் இராஜாதிராஜனைப் பொறுக்கி எடுத்தது. சரியில்லை யென்றும், தனக்கே அந்த உரிமை கிட்டவேண்டுமென்றும் நினைத்திருக்கலாம். அதன் பயனாகவே அவன் தன்னை முறைப்படி அரசனாகப் பிரகடனம் செய்துகொண்டான்.

அதை அவன் சோழநாட்டிலிருந்து செய்யமுடியாது. ஆகவே கன்னடப் பிரதேசத்துக்குப் போய் அவ்விடம் பிரகடனம் செய்துகொண்டான். அதற்குத் தேவையான உதவியை அளிக்கக் கூடியவர்களும் அங்கே தான் இருந்தார்கள். எனினும் இம் முயற்சி அப்போது வெற்றிபெற்றவில்லை. சோழநாட்டிலே ஸ்திரமான, குடிமக்களின் அன்புக்குப் பாத்திரமான அரசு இருந்தது. அன்றி குலோத்துங்கனுக்கும் நாட்டு மக்களிடையே பெருத்த ஆதரவு இருந்ததாகவும் தெரியவில்லை. குலோத்துங்கன் இவ்விதம் தன்னை அரசனாகப் பிரகடனம் செய்துகொண்டதும், பாண்டி நாட்டிலே சிங்காதனத்தை அடைவதாகக் கிளம்பிய தாயாதிச் சண்டையும் ஒன்றுசேர்ந்து, கி.பி. 1163-ம் ஆண்டு மார்ச் மாதம் பட்டத்துக்குரியவனாகத் தேர்ந்தெடுக்கப்பட்ட இரண்டாம் இராஜாதிராஜன்னுடைய முடி சூட்டு விழாவை நாலாம் திருநகைத்திரத்திலே, கி.பி. 1166-ஆம் ஆண்டிலே, செய்யவேண்டிய அவசரத்தை ஏற்படுத்தின போலும்.

அரசன் அதாவது மூன்றாம் குலோத்துங்கன் திருக்கை மலரிலே நீர்வார்த்துத் தானம் வழங்கியதாக ஹேமவதித் தமிழ்க் கல்வெட்டில் குறிக்கப்பட்டுள்ள சிக்கல் உடைய செட்டியார் வட்டவியவஹாரி தேசிமுக்யர் என்று விவரிக்கப்பட்டுள்ளான். கர்நாடக தேசத்துச் சாசனங்களிலே ‘ஸ்ரீமான் மகாபட்டு வியாபாரி உபய நாநாதேசிக்கு முக்கியமான’ என்று தமிழிலும் (பி. கர்நாடிகா, பத்தாம் வால்யூம், கோலார் 71 நெ.சாசனம்)

“ஸ்ரீமன் மஹாபட்டவ்யவஹாரி உபய நானாதேசியரகா மஹா பிரபு முக்யரப்ப’ என்று கன்னடத்திலும் (ஷெ 72, 73 நெ.) காணப்படுவதையே இந்த விருது குறிக்கும். இதிலிருந்து அவன் பம்பாய் ராஜ்யம் அய்யாவழி என்னும் ஐஹோ ளெயைத் தலைநகராகக்கொண்டு நானாதேசிகள் என்றும் ஐந்தூற்றுவர் என்றும் குறிக்கப்பெற்று நாடு முழுவதும் பரவியிருந்த வியாபாரக் குழுவைச் சேர்ந்தவனாகவே இருத்தல் வேண்டும் போலும்.

இராமநாதபுரம் ஜில்லா பிரான்மலையிலிருந்து கிடைக்கும் ஒரு கல்வெட்டிலே (தே. இ. சாசனங்கள், எட்டாம் வால்யூம், 442 நெ.) இந்தக் குழுவினரின் மெய்க்கீர்த்தி காணப்படுகிறது. அதிலிருந்து இவர்களுக்கும் சித்திரமேழிப் பெரிய நாட்டவர் என்னும் மற்றொரு குழுவினருக்கும் ஏதோ ஒரு வகையான தொடர்பு இருந்து வந்தது என்று தெரிகிறது. தென்னார்க்காடு ஜில்லா திருக்கோவலூரிலிருந்து சித்திரமேழிப்பெரிய நாட்டவர் என்பாருடைய தருமங்கள் சிலவற்றைத் தெரிவிப்பதாகக் கிடைக்கும் ஒரு கல்வெட்டிலே (ஷெ ஆறாம் வால்யூம், 129-நெ.) இம் மெய்க்கீர்த்தியின் பெரும்பகுதி காணப்படுகிறது. அதே ஜில்லாவில் திட்டக்குடியிலிருந்து கிடைத்த இரண்டாம் இராஜாதிராஜனுடைய நான்காம் ஆண்டுக் கல்வெட்டு ஒன்று (ஷெ ஏழாம் வால்யூம், 291) எழுபத்தொன்பது நாட்டுச் சித்திர மேழிப் பெரியநாட்டாரும் திசை திசை விளங்கும் திசை ஆயிரத்து ஐந்தூற்றுவரும் சேர்ந்து அவ்வூர்க் கோயிலுக்கு அளித்த சில நிவந்தங்களைக் கூறுகிறது. சித்திரமேழிப் பெரியநாடு, திசை ஆயிரத்து ஐந்தூற்றுவர் ஆகிய இரண்டும் நானாதேசி என்னும் மூலஸ்தாபனத்தின் இரு பிரிவுகளே போலும். கன்னட நாட்டுச் சாசனங்களிலே உபயநானாதேசி என்று காணப்படுவது இந்த இரு பிரிவுகளையே குறிக்கும்.

சித்திரமேழிப் பெரியநாட்டவர் பல சமயங்களிலே பெரிய நாட்டவர் என்றே பொதுவாகச் சாசனங்களில் குறிக்கப்படுவர். ‘அழகிய கலப்பை’ என்ற பெயரை உடைய அந்த ஸ்தாபனம் விவசாயிகளே நிரம்பியது போலும். இந்த ஸ்தாபனம் சற்றேறக்குறைய இந்தக் காலத்தில் தான் தோன்றியிருக்க

வேண்டும். மூன்றாம் குலோத்துங்கன் ஆட்சியிலே அது சோழ-  
ஸாம்ராஜ்யம் முழுவதும் பரவிப் பற்பல கிளைகளுடன் தழைத்து  
விளங்கியது. ஆந்திர ராஜ்யம் நெல்லூரிலே அவன் காலத்தில்  
கட்டப்பட்டதாகக் கருதப்படும் விஷ்ணு ஆலயம் திருப்பார்  
கடல் பள்ளி கொண்ட பெருமாள் சித்திரமேழி விண்ணகரம்  
என்று பெயர் கொண்டது. (இந்தத் தொகுப்பின் 938-939 நெ-  
சாசனங்களைப் பார்க்க. இன்னும் தே. இ. சாசனங்கள், ஐந்-  
தாம் வால்பூம், 496, 493 நெ. நெல்லூர் ஜில்லாச் சாசனங்கள்,  
நெல்லூர் 61, 62 பார்க்க.) கடப்பை ஜில்லா அத்திரால என்னும்  
ஊரில் சித்திரமேழி மண்டபம் ஒன்று இருந்திருக்கிறது. (1914-  
ஆம் ஆண்டு 404 நெ.) கோயம்புத்தூர் ஜில்லாவில் அந்நாளிலே  
கோயிற்பூசை செய்தோன் ஒருவன் சித்திரமேழி பட்டன்  
என்ற பெயரைக் கொண்டிருந்தான். (1920 ஆம் ஆண்டு 258 நெ.  
சாசனம்.) அதே ஜில்லாவில் விஜயமங்கலத்தில் உள்ள கரிய  
மாணிக்கர் என்னும் விஷ்ணுவின் கோயிலுக்குச் சித்திரமேழி  
விண்ணகரம் என்ற பெயர் சாசனங்களிலே காணப்படுகிறது.  
(இந்தத் தொகுப்பின் 270, 271 நெ. சாசனங்கள். 1905-ஆம்  
ஆண்டு 544 நெ. சாசனமும் பார்க்க).

இந்த ஸ்தாபனத்துக்கெனத் தனியாக மெய்க்கீர்த்தியும் இலச்சினையும் இருந்தன. இவர்களுடைய பிற்காலத்துச் சாசனங்களிலே சில புயல் வாய்த்து என்று முதலில் எழுதப் பெற்று அப்பால் அதைத் தொடர்ந்து சாசனங்கள் எழுதப் பெற்றுக் காண்கின்றன. (தே. இ. சாசனங்கள், ஆறாம் வால்யூம்; 40, 41 நெ). புயல் வாய்த்து என்பது மூன்றாம் குலோத்துங்கன் சாசனங்கள் பலவற்றிலே காணப்படும் அவனுடைய மெய்க்கீர்த்தியின் ஆரம்பமாகும். மூன்றாம் குலோத்துங்கனுடைய புயல் வாய்த்து என்று தொடங்கும் மெய்க்கீர்த்திக்கும் சித்திர மேழிப் பெரிய நாட்டவர் மெய்க்கீர்த்திக்கும் சொல்லாட்சியிலே மிகுந்த ஒற்றுமை காணப்படுகிறது. புயல் வாய்த்து என்று ஆரம்பமாகும் மெய்க்கீர்த்தியையே பெரியநாட்டவர் பிற்காலத்தில் தங்களுக்கு ஸ்வீகரித்துக் கொண்டுவிட்டார்கள். ஆகவே அவர்களுடைய பிற்காலத்துச் சாசனங்களிலே காணும் 'புயல் வாய்த்து' என்பது அந்த மெய்க்கீர்த்தி முழுவதையும் கொடுப்பதற்குப் பதிலாக அதன் ஆரம்பத் தொடரை மட்டும் கொடுப்



பதாகும். இதைக் கவனித்தால், இந்த ஸ்தாபனத்தை மூன்றாம் குலோத்துங்கனே சோழ சிங்காதனத்தைக் கைப்பற்றுவதற்குச்செய்த தன்னுடைய முதல் முயற்சித் தோற்றுப்போனவுடன் சிருஷ்டித்தான் என்று சொல்லலாம். நாடுமுழுவதும் பல கிளைகளுடன் பரவி நன்கு வேருன்றிய அந்த ஸ்தாபனத்தின் உதவியாலேயே சிறிது காலத்திற்கெல்லாம் அவன் தன்னுடைய முயற்சியிலே வெற்றி கொள்ளமுடிந்தது.

தஞ்சாவூர் ஜில்லா செம்பொனார் கோயிலிலிருந்து கிடைக்கும் மூன்றாம் குலோத்துங்கனுடைய ஆட்சியின் ஆறாம் ஆண்டு கொண்ட கல்வெட்டு ஒன்றிலிருந்து இரண்டாம் இராஜாதி ராஜனுடைய ஆட்சியின் பதினேராம் ஆண்டிலே சோழ நாட்டின் மீது வேற்றார்படையெடுப்பு ஏதோஒன்று (தூரித காலமாய்ப் படைஏற) நடந்தது என்றும் தெரிகிறது.<sup>1</sup> அந்தப்படையெடுப்பு மூன்றாம் குலோத்துங்கன் நடத்தியதாகவே இருத்தல் வேண்டும்.

பாண்டியர் தாயாதிச் சண்டை

பன்னிரண்டாம் நூற்றாண்டின் பிற்பகுதியில் தென்னிந்திய சரித்திரத்திலேயே முக்கியமான சம்பவம் ஒன்று நிகழ்ந்தது. பாண்டி நாட்டிலே இராஜகுமாரர்களிடையே முப்பது வருஷ காலத்துக்கு அதிகமாக இரண்டு தலைமுறைகளுக்கு இழுத்துச் சென்ற அப்போர் அந்தக் காலத்தில் தென்னாட்டையே ஒரு கலக்குக் கலக்கி விட்டதென்னலாம். இருசாராரிலே ஒருவன் இலங்கை அரசனுடைய உதவியை நாடினான். மற்றவன் சோழ மன்னனை அண்டினான். இவ்விதம் அந்தப் போர் பாண்டியர்களோடு நின்று விடவில்லை. சோழர்களையும் சிங்களர்களையும்

1. 1925-ஆம் ஆண்டு 171 நெ. சாசனம். சாசன இலாகாவின் 1925-ஆம் ஆண்டு அறிக்கையின் 22 பாராவில் இந்தப் படையெடுப்பு பாண்டிய நாட்டில் நடைபெற்றுவந்த தாயாதிச் சண்டையுடன் சம்பந்தப்பட்டதாக இருக்குமோ வென்று கருதப்பட்டுள்ளது. ஆனால் பாண்டி நாட்டுத் தாயாதிச் சண்டையில் சோழர்கள் தீவிரமாக ஈடுபட்டுப் போர் நடத்திவந்தாலும் அந்தப் போர் பாண்டிய நாட்டு எல்லையைக் கடந்து சோழ நாட்டுக்குள் பரவியதாகத் தெரியவில்லை.

போரில் இழுத்து விட்டது. பழைய பகை புது உருவத்தில் கிளம்பிப் போரிட்டது.

இந்தத் தாயாதிச் சண்டையின் ஆரம்பப்பகுதி இலங்கைச் சரித்திரமான மகாவமிசத்தில் விரிவாக வருணிக்கப் பட்டுள்ளது. பின்னால் நடந்ததை மூன்று அல்லது நான்கு சோழசாசனங்களிலிருந்து சிறிது சிறிதாக அறிய வேண்டி வருகிறது. இவ்விதம் இரண்டையும் சேர்த்தால் தான் சித்திரம் பூர்த்தியாகும். அப்படியும் சில விவரங்கள் கிடைக்காமல் தான் இருக்கும்.

மஹாவமிசத்தில் காணும் விவரமே இலங்கை அரசன் உதவியைப் பராக்கிரம பாண்டியன் வேண்டிக் கொள்வதி லிருந்து தான் ஆரம்பமாகிறது.

மதுரையிலே பராக்கிரம பாண்டியன் அரசனாக அமர்ந் திருந்தான். அதைக் கைப்பற்றுவதற்காகக் குலசேகரன் படையெடுத்துவந்து அந்நகரை முற்றுகையிட்டிருந்தான். வந்த எதிரியைத் துரத்தித் தன் நிலையை ஸ்திரமாக்கிக் கொள்ளுவதற்கு வேண்டிய பலம் கிட்டாத பராக்கிரமன் தனக்கு உதவிசெய்ய வேண்டுமென்று இலங்கை மன்னனை பராக்கிரம பாஹுவை வேண்டிக் கொண்டான். இதிலிருந்து தான் ஆரம்பிக்கிறது மஹாவமிசத்திலே காணும் இந்தப் போரைப்பற்றிய விவரம். இலங்கை வேந்தனும் தன் சேனாபதி லங்காபுர தண்டநாயகன் தலைமையில் ஒரு படையை அனுப்பி உதவினான். ஆனால் சிங்களப்படை தமிழ் நாட்டை அடை வதற்கு முன்னதாகவே பாண்டிய நாட்டில் சம்பவங்கள் துரித மாக நடந்து விட்டன. குலசேகரன் மதுரையைக் கைப் பற்றிக் கொண்டு பராக்கிரமன், அவன் மனைவி மக்கள் ஆகியோரைத் திருமலக்கே என்னுமிடத்தில் படுகொலை செய்து விட் டான். இதைக் கேள்வியுற்ற பராக்கிரம பாஹு, குலசேகர னிடமிருந்து மதுரை அரசைத் திரும்பவும் மீட்டுப் பராக்கிர மனின் வமிசத்து அரசகுமாரன் ஒருவன்வசம் அளிக்கப்படும் வரைப் போரைத் தொடர்ந்து நடத்துமாறு உத்தரவு அனுப் பினான். இராமேசுவரத்துக்கு அருகில் மிகுந்த எதிர்ப்பு களுக்கிடையே லங்காபுரன் தன் படைகளுடன் கரையிறங்கி

இராமேசுவரம் செல்லும் வழியில் குண்டுகலா என்னுமிடத்தில் தன் படைகளை ஸ்திரப் படுத்திக் கொண்டான்.

இப்படையெடுப்பிலே நிகழ்ந்த சண்டைகள் பலவற்றையும் பாண்டியர் பக்கத்தில் சேர்ந்து போரிட்ட அதிகாரிகள் தண்டநாயகர்கள் ஆகியோர் பலரின் பெயர்களையும் மகாவம்சம் விரிவாகக் கூறுகிறது.

இந்தப் போரிலே ஈடுபட்டிருந்த அதிகாரிகள் யார் யார் என்பதையும் போர் நடந்த இடங்கள் எவை எவை என்பதையும் நன்றாக நிர்ணயித்து விடமுடியும். ஆனால் அது மிகவும் நீண்டவிடும். அதை இவ்விடம் ஆராய முடியாது. (சாசன இலாகாவின் 1899-ஆம் ஆண்டு அறிக்கையில் 23 முதல் 38-வரையில் உள்ள பாராக்களில் இந்தப் போர் பற்றி விரிவாக ஆராயப்பெற்றுள்ளது.)

மஹாவம்சத்திலே காணும் சிறு விவரங்களை விட்டு விட்டு மேலெழுந்த வாரியாகப் பார்த்தாலே லங்காபுர தண்டநாயகன் நினைத்தபடி சுலபமாக வெற்றி கொள்ள முடியவில்லையென்பது நன்கு விளங்கும். போரின் உக்கிரம் அதிகமாக அதிகமாகக் கொடூரமும் அதிகரித்தது. லங்காபுரன்கையில் சிக்கிய தமிழ் நாட்டுப் படைவீரர்கள் ஒன்று கொல்லப்பட்டார்கள், அல்லது இலங்கைக்குக் கைதிகளாக அனுப்பிவைக்கப் பட்டார்கள். தமிழர்கள் இலங்கையை ஆண்ட நாளிலே சேதமுற்ற புத்த விஹாரங்களைப் புதுப்பிக்கும் புனிதத் திருப்பணியிலே கூலிகளாக வேலை செய்வதற்குத் தான். குலசேகரனும் மூச்சைப் பிடித்துக் கொண்டதான் லங்காபுரனை எதிர்த்து நின்றான்.

லங்காபுரன் உதவிக்காக மேலும் படைகள் இலங்கையிலிருந்து தண்டநாயகன் ஜகத்விஜயன் என்பவன் தலைமையில் அனுப்பப்பட்டன. அவனுடைய பெயர் சோழ சாசனங்களில் ஜயத்ரதன் எனக் காணப்படுகிறது. பராக்கிரம பாண்டியனுடைய குமாரனான வீரபாண்டியன் என்பவன் குலசேகரன் செய்த படுகொலையிலிருந்து தப்பிச் சென்று மலய நாட்டில் வசிப்பதாகக் கேள்விப்பட்ட லங்காபுர தண்டநாயகன் அவனைத் தன்னிடம் வரவழைத்தான். முடிவில் குலசேகரனை ராஜ்யத்திலிருந்து விரட்டிவிட்டு, வீரபாண்டியனை அரசனாக முடி சூட்டிவைத்தான்.

பாண்டிய அரசுக்குப் போட்டியிட்ட குலசேகரனுடைய மாமனே கொங்கு நாட்டுச் சோழ அரசன் முதலாம் குலோத்துங்கன். அவனும் தன் மருமகனுக்கு உதவுவதற்காக இந்தப் போரில் ஈடுபடநேர்ந்தது. இந்த விவரம் மகாவமிசத்திலும் குறிக்கப்பட்டுள்ளது. திருச்சிராப்பள்ளி ஜில்லாவிலே உள்ள நெருர் என்னுமிடத்திலிருந்து கிடைக்கும் இக் கொங்கு மன்னன் குலோத்துங்கனுடைய சாசனம் ஒன்றும் இதை வலியுறுத்துகிறது. (1928-ஆம் ஆண்டு 336 நெ. இந்தத் தொகுப்பின் 716 நெ. சாசனம்.) அவனுடைய பதினேழாம் ஆண்டு கொண்ட அக் கல்வெட்டு, அவன் தன்னுடைய மருமகனார் குலசேகரனுக்கு மதுரை அரசை எறிந்து கொடுக்கக் கிளம்புவதற்கு முன்னதாகத் தன்னுடைய புரோகிதருக்கு ஒரு கிராமத்தை யாத்திரதானமாக அளித்த செய்தியைத் தெரிவிக்கிறது. இம் மன்னன் சக வருஷம் 1072-ல் (கி.பி. 1150-51) சிங்காதனம் ஏறியவன். இது, கோயம்புத்தூர் ஜில்லா விஜயமங்கலத்திலிருந்து கிடைக்கும் அவனுடைய மற்றொரு சாசனம், அவனுடைய ஆட்சியின் பதின்மூன்றாம் ஆண்டுக்கு எதிராம் ஆண்டும் சகவருஷம் 1085-ம் கொண்டிருப்பதிலிருந்து பெறப்படும். (1905-ஆம் ஆண்டு 593 நெ.) இதிலிருந்து நெருர்க் கல்வெட்டின் காலம் கி.பி. 1166-67 எனக் கொள்ளலாம். அப்படியானால் பாண்டிய நாட்டுத் தாயாதிச் சண்டை அதற்கு முன்னதாகவே கிளம்பி இரண்டாம் கட்டத்தை அடைந்துவிட்டது என்றாகும்.

இராமநாதபுரம் ஜில்லாவில் உள்ள திருப்புத்தூரிலிருந்து கிடைக்கும் (1908-ஆம் ஆண்டு 101 நெ.) பாண்டிய மன்னன் திரிபுவன சக்கரவர்த்திகள் குலசேகர தேவனுடைய ஆட்சியின் நான்காம் ஆண்டுக் கெதிராம் ஆண்டு கொண்ட ஒரு சாசனத்தில் காணும் பஞ்சாங்கக் குறிப்புகளைக் கொண்டு அது தொடுக்கப்பட்ட காலம் கி.பி. 1166-ஆம் வருஷம் ஜூலை மாதம் 23-ம் தேதிக்குச் சரியானதாகுமெனக் கொள்ளலாம். (இந்தியன் ஆண்டிடுவரி, நாற்பத்து நான்காம் வால்டும், பக்கம் 255). இதிலிருந்து இந்தக் குலசேகரன் சிங்காதனம் ஏறியது கி.பி. 1161-62-ஆம் ஆண்டாகும் எனக் கொள்ளலாம். அந்தச் சாசனம் மேலும் முக்கியமான செய்திகள் சிலவற்றை அறிவிக்கிறது. 'பெருமாள் குலசேகர தேவரைத் திருவடித்தொழு மதுரை ஏறப்போகைக்கு ஸ்ரீமதுதிரவியம் வேண்டினமையிற்,'

அவ்வூர் மூலபரிஷத் மகாசபையார் கிராமத்தில் திருத்தளி ஆண்ட நாயனார் கோயிலில் ஆயிரத்தெழு நூற்றாவன் திரு மண்டபத்தில் கூடி, கோயிலுக்குச் சொந்தமான சில கிலங்களில் பயிரிடும் உரிமையை இருநூறு சோழிய நற்பழங்காசுக்கு விற்றுக் கொடுத்த செய்தியைத் தெரிவிக்கிறது.<sup>1</sup>

நாட்டிலே புதிய அரசன் முடி சூட்டப்பெற்றால் அதை யொட்டி நாட்டில் உள்ள பிரமுகர்கள் எல்லோரும் அரசனை நேரில் கண்டு காணிக்கை செலுத்தித் தங்கள் விசுவாசத்தைத் தெரிவித்து வருவது வழக்கம். இவ்விதம் குலசேகரனுக்குத் திருப்புத்தூர் மூலபரிஷத் மஹாசபையார் அபிஷேகக் காணிக்கை செலுத்த நேர்ந்த சம்பவத்தையே இக் கல்வெட்டு எடுத்துரைக்கிறது போலும். ஆகவே குலசேகரன் கி. பி. 1166-ஆம் ஆண்டு ஜூலை மாதத்திற்குச் சிறிது காலம் முன்னதாக, அதாவது ஒன்றிரண்டு வருஷங்களுக்குள்ளாக, மதுரையைக் கைப்பற்றித் தன் எதிரியான பராக்கிரம பாண்டியனைக் கொன்றிருத்தல் வேண்டும். ஆதலால் அவன் கி. பி. 1165-ஆம் ஆண்டில் மதுரையைக் கைப்பற்றினான் என்று கொள்ளலாம்.

மதுரையைவிட்டுக் குலசேகரனை வெளியேற்றி, வீரபாண்டியனுக்கு முடிசூட்டிவிட்டுச் சிங்கள படைத்தலைவர்களான இலங்காபுர தண்டநாயகனும் ஜகத்விஜயனும், இலங்கைக்குத் திரும்பியதும் அங்கே அரசன் பராக்கிரமபாஹு இவ் வெற்றியின் ஞாபகார்த்தமாகப் பாண்டுவீஜயம் என்ற பெயரில் ஒரு நகரை நிர்மாணித்து விழாக் கொண்டாடியதோடு மஹா வமிசத்தில் காணப்படும் விபரம் முடிவடைகிறது.

ஆனால் தாயாதிச் சண்டை இதனோடு முடியவில்லை. நாடிழந்த குலசேகரன் தனக்கு உதவும்படி சோழ மன்னன் இரண்டாம் இராஜாதிராஜனை அணுகினான். சோழனும் அவனை வரவேற்று, இவ்விடம் இருக்கும் நாளில் தகுந்த மரியாதையுடன்

1. இராமநாதபுரம் ஜில்லா குன்றக்குடியில் உள்ள திருவண்ணாமலை ஆதினத்தைச்சார்ந்த கோயில்களில் காணும் சாசனங்களைப் பிரதிசெய்வோரை நான் பணியாற்றிய காலம் இந்தச் சாசனமும் பிரதிசெய்யப்பெற்றது. அதிலிருந்தே நான் மேற்கோள் கொடுத்துள்ளேன்.

உபசரித்து அவனை மறுபடியும் பாண்டிய சிங்காதனத்தில் அமர்த்துமாறு தன்னுடைய அதிகாரிகளுக்கு உத்தரவிட்டான். பல்லவராயன் ஆகிய திருச்சிற்றம்பலம் உடையான் பெருமானம்பி என்பவன் இந்தப் பொறுப்பை ஏற்று இலங்கா புர தண்டநாயகன் முதலியோர் தலையைக் கொய்து மதுரைக் கோட்டை வாசலில் ஆணி அடித்து அரசன் ஆணையை நிறைவேற்றினான். குலசேகரன் மறுபடியும் பாண்டிய அரசனானான். இவ்விவரங்கள் செங்கற்பட்டு ஜில்லா ஆர்ப்பாக்கம் கிராமத்திலிருந்து கிடைக்கும் ஒரு சாசனத்தாலும் தஞ்சாவூர் ஜில்லா பல்லவராயன்பேட்டையிலிருந்து கிடைக்கும் மற்றொரு சாசனத்தாலும் அறியப்படுகின்றன. இராஜதிராஜனுடைய ஆட்சியின் ஐந்தாம் ஆண்டு கொண்ட ஆர்ப்பாக்கத்துச் சாசனம் (தே. இ. சாசனங்கள், ஆறாம் வால்பூம், நெ. 456) பாண்டிய நாட்டிலே ஈழத்துப் படை புகுந்து செய்த அக்கிரமங்களையும், சோழ சைன்னியம் அவர்களைத் தோற்கடித்ததையும் கூறுவதோடு நின்றுவிடுகிறது. மற்ற விவரங்கள் எட்டாம் ஆண்டில் பொறிக்கப்பட்ட பல்லவராயன் பேட்டைச் சாசனத்திலிருந்து (எபி. இந்திகா, இருபத்தோராம் வால்பூம், 184-193 பக்கங்கள்) தெரியவருகின்றன.

அப்போதும் சண்டை முடியவில்லை. மேலும் தொடர்ந்து நடந்துவந்தது. இது இராஜதிராஜனுடைய ஆட்சியின் பன்னிரண்டாம் ஆண்டில் பொறிக்கப்பட்ட திருவாலங்காட்டுக் கல்வெட்டிலிருந்து காணப்படுகிறது. இலங்கை வேந்தனை பராக்கிரமபாஹு திரும்பவும் படையெடுத்து வருவதற்கான ஏற்பாடுகளைச் செய்துவந்தான். இதையறிந்த சோழமன்னன் அம் முயற்சியை முனையிலேயே கிள்ளி எறிந்துவிட விரும்பினான். அப்போது பராக்கிரமபாஹுவின் மருமகனும் பாண்டிய மாண்புரணனுடைய மகனுமான ஸ்ரீவல்லபன் என்னும் பாண்டிய இராஜகுமாரன் மரும்க்கள்தாயமுறைப்படி இலங்கை அரசுக்கு உரிமை கொண்டாடிவந்தான். அவன் தன் முயற்சி பலிக்காமல் அப்போது தமிழ் நாட்டிலே தங்கியிருந்தான். அவன் தன் உரிமையை வற்புறுத்தி இலங்கை அரசைக் கைப்பற்றுவதற்காக வேண்டிய உதவியை அளிப்பதற்குச் சோழமன்னன் முன்வந்தான். அவ்விதம் ஸ்ரீவல்லபனை முன்னிட்டுக் கொண்டு இலங்கை சென்ற சோழர் சைன்னியம் அங்கே

பெரு வெற்றிகளை அடைந்து, பராக்கிரம பாஹுவின் எண்ணம் ஈடேறாதபடி செய்துவிட்டது.

சோழர்கள் இவ்விதம் செய்த சூழ்ச்சிக்குப் பதிலாகப் பராக்கிரம பாஹுவும் சூழ்ச்சியில் இறங்கினான். இராஜாதி ராஜனுடைய பிடிப்பிலிருந்து குலசேகரனை விடுவித்து வெளிக்கொணர்ந்துவிடத் தீர்மானித்தான். அதற்காக அவன் குலசேகரனையே பாண்டிய மன்னனாக அங்கீகரித்து அவனோடு சம்பந்தம் செய்யவும் முற்பட்டான். குலசேகரன் ஈழத்தானுடன் சேர்ந்து கொண்டான் என்பதை யறிந்த சோழன் அவனை மதுரையிலிருந்து விரட்டிவிட்டுப் பாண்டி நாட்டுத் தாயாதிச் சண்டையின் ஆரம்பகாலத்திலிருந்த பராக்கிரம பாண்டியன் மகனான வீரபாண்டியனை மறுபடியும் அரசனாக முடி சூட்டிவைத்தான்.

இரண்டாம் இராஜாதிராஜனுடைய ஆட்சியின் பன்னிரண்டாம் ஆண்டில் பொறிக்கப்பட்ட திருவாலங்காட்டுக் கல்வெட்டிலிருந்து அறியப்படுவது இந்த நிலை. (எபி. இந்தியா, இருபத்திரண்டாம் வால்யூம், 86-92 பக்கங்கள்.) இராஜாதிராஜனுடைய ஆட்சிக் காலமும் இறுதிக்கட்டத்தை எட்டிவிட்டது அதற்குப்பிறகு அவன் நீண்ட காலம் சோழ நாட்டை ஆளவில்லை. ஆரம்பக் காலத்திலிருந்தே அவனுடைய விரோதியாக விளங்கிய குலோத்துங்கன் அவனைத் தமிழ் நாட்டிலிருந்து துரத்திவிட்டு அரசைக் கைக்கொண்டான். குலோத்துங்கனுடைய ஆட்சி கி. பி. 1178-ஆம் ஆண்டு ஜூலை மாதம் ஆறாம் தேதிக்கும் எட்டாம் தேதிக்கும் இடைப்பட்ட காலத்தில் ஆரம்பமாயிற்று என்று கணக்கிட்டிருக்கிறார்கள்.

இராஜாதிராஜன் பாண்டிய குலசேகரன்மீது விரோதம் கொண்டதற்கு அவன் ஈழத்தானுடன் சேர்ந்துகொண்டது மட்டுமே காரணமாக இருத்தற்கில்லை. சோழசிங்காதனத்துக்குப் போட்டியிட்ட குலோத்துங்கனுடன் பாண்டிய குலசேகரன் சேர்ந்துவிட்டான் என்று எண்ண வேண்டியிருக்கிறது. அதுவே முக்கிய காரணமாகவும் இருந்ததுபோலும். இராஜாதிராஜனுடைய ஆட்சியின் பதினேராம் ஆண்டிலே, அதாவது திருவாலங்காட்டுக் கல்வெட்டுப்படி குலசேகரனைப் பாண்டிய

சிங்காதனத்திலிருந்து நீக்கியதற்குச் சிறிது முன்னதாக, சோழநாட்டின்மீது வெளியார் படையெடுப்பு ஒன்று நடந்திருந்தது என்று செம்பொனார் கோயிலிலிருந்து கிடைக்கும் ஒரு கல்வெட்டால் விளங்குகிறது என்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். அந்தப் படையெடுப்பும் குலோத்துங்கன் நடத்தியதே ஆகும். குலோத்துங்கனுக்கும் பாண்டிய குல சேகரனுக்கும் ஏதோ ஒருவகைத் தொடர்பு இருந்துவந்திருத்தல் வேண்டும் என்பது குலோத்துங்கன் சோழநாட்டின் அரசரிமையைப் பெற்றவுடனே, திரும்பவும் பாண்டிய நாட்டு அரசுப் பதவியில் மாறுதல் ஏற்பட்டது என்பதிலிருந்து நன்கு விளங்கும்.

குலோத்துங்கனுடைய ஆட்சியின் ஒன்பதாம் ஆண்டிலே பொறிக்கப்பட்ட சிதம்பரம் கல்வெட்டில் பின் வரும் பகுதி காணப்படுகிறது :

“ விக்கிரம பாண்டியன் வேண்ட விட்டதண்டால்  
வீரபாண்டியன் மகன்பட ஏழகம்பட  
மறப்படை படச் சிங்களப்படை  
மூக்கறுப்புண்டு அலைகடல்புக  
வீரபாண்டியன் முதுகிடும்படிதாக்கி  
மதுரையும் அரசும் கைக்கொண்டு ”

இதிலிருந்து விக்கிரம பாண்டியன் வேண்டிக் கொண்டதால் அவன் தன் படையை ஏவி வீரபாண்டியனைத் துரத்தி மதுரையையும் அரசையும் கைப்பற்றி விக்கிரம பாண்டியனுக்கு அளித்தான் என்று தெரிகிறது. விக்கிரம பாண்டியன் என்பான் குலசேகரன் மகனே போலும். இடைக்காலத்தில் குலசேகரன் இறந்துவிட்டான் போலும். அதனாலேயே குலோத்துங்கன் வீரபாண்டியனைத் துரத்திக் குலசேகரன் மகனைப் பாண்டிய சிங்காதனத்தில் அமர்த்தினான் எனக் கொள்ள வேண்டும் போலும்.

இந்த வெற்றியின் முடிவில் அவன் ‘மதுரையும் பாண்டியன் முடித்தலையும் கொண்டருளிய’ என்னும் விருதைத் தரித்துக் கொண்டான். இவ்விருது அவனுடைய சாசனங்களிலே நான்காம் ஆண்டு முதல் காணப்படுவதால் இவ்வெற்றி அவனுடைய ஆட்சியின் ஆரம்பக் காலத்திலேயே அதாவது



அவன் பட்டத்துக்கு வந்த சிறிது காலத்திற்குள்ளாகவே நடந்திருத்தல் வேண்டும் என்று கொள்ளலாம். இந்தக் கட்டத்திலும் ஈழத்துப்படை சண்டையில் ஈடுபட்டிருந்தது என்று தெரிகிறது.

குலோத்துங்கனால் இவ்விதம் தோல்வியுற்ற வீரபாண்டியன் கொல்லத்திலே அடைக்கலம் புகுந்தான். அங்கிருந்து தன் படைகளைத் திரட்டிக் கொண்டு தான் இழந்த நாட்டையும் பதவியையும் மீட்டுக் கொள்வதற்காக மறுமுறையும் சோழனோடு யுத்ததிற்கு வந்தான். ஆனால் திரும்பவும் அவன் தோல்வியுற்றான். சோழ மெய்க்கீர்த்தியிலிருந்து அவன், அப்பால் 'மீனவனும் வீரகேரளனோடு' குலோத்துங்கனிடம் சரணு புகுந்தான் என்றும், சோழ மன்னன் அவனுக்குப் படியும் முடியும் வழங்கினான் என்றும் தெரிகிறது.

இலங்கையில் பராக்கிரம பாஹு இறந்து போனான். அவனுக்குப் பிறகு நாட்கணக்கு மாதக் கணக்கிலே அரசு புரிந்த இருவருக்குப் பிறகு நிஸ்ஸங்க மல்லன் என்பவன் அரசனானான். அவன் முடி சூட்டிக் கொண்டது கி. பி. 1187-ஆம் ஆண்டு ஆகும் எனக் கணக்கிட்டிருக்கிறார்கள். அவன் பாண்டிய நாட்டின்மீது மூன்று தடவைகள் படையெடுத்து வந்ததாகவும் இராமேஸ்வரத்திலே ஒரு கோயிலைப் புதுப் பித்ததாகவும் தன்னுடைய சாசனங்களிலே கூறிக் கொள்ளுகிறான். இராமேஸ்வரத்திலே அவன் புதுப்பித்த கோயில் நிச்சங்கமல்லேஸ்வரம் எனப்படும்.

குலோத்துங்க சோழனுடைய ஆட்சியின் முப்பத்தொன்றாவது, முப்பத்து நான்காவது ஆண்டுகள் கொண்டனவாகப் பழைய புதுக்கோட்டை ஸம்ஸ்தானத்திலிருந்து கிடைக்கும் இரண்டு கல்வெட்டுக்களிலிருந்து அம்மன்னன் மறுபடியும் ஒரு முறை பாண்டிய நாட்டு விவகாரத்திலே தலையிட வேண்டி இருந்ததென்று தெரிகிறது. அதன் முடிவிலே தான் அவன் மதுரையிலே வீரபிஷேகம் செய்து கொண்டது. இந்த அபிஷேக விவரம் அவனுடைய சாசனங்களிலே 29-ஆம் ஆண்டு-அளவில் தான் காணப்படுகிறது. ஆகவே இந்தப் படையெடுப்பு கி. பி. 1205-ம் ஆண்டுக்கு அணித்தாக நடந்திருக்க வேண்டும். அவன் வெற்றிகொண்ட பாண்டிய அரசன் பெயர் எவ்விடத்திலும் காணப்படவில்லை. ஆயினும் கி. பி.

1190-ல் பாண்டிய சிங்காதனம் ஏறிய ஜடாவர்மன் குலசேகர பாண்டியன் என்பவன் அப்போது இருந்திருக்கிறான். ஆகவே இந்தப் படையெடுப்பு அவன்மீதே நடத்திருத்தல் வேண்டும் என்று கொள்வர்.

இந்த படையெடுப்பைப் பற்றிய மற்ற விவரங்கள் கிடைக்க வில்லை. ஆகவே இது தாயாதிச் சண்டையின் தொடர்பாக நடந்த சம்பவமா அல்லது வேறு ஒன்று என்பதையும் நிச்சயமாகக் கூற இயலாது.

இந்தச் சண்டையிலே நாம் ஒரு விஷயத்தைக் கவனிக்க வேண்டும். ஆரம்ப முதலே பாண்டியர்களில் இருசாராரும் வேற்றூர் யாரே ஒருவருடைய தயவை எதிர்பார்த்தே நின்றார்கள். அவ்விதம் உதவி செய்த வெளியாரும் பாண்டிய நாட்டிலே தங்களுடைய உரிமைகளை ஸ்தாபித்துக் கொள்ள முயன்றனர். ஆயினும் சண்டையின் முடிவில் சிறிது காலத்திற்கெல்லாம் புத்தயிர் பெற்ற பாண்டிய அரசாங்கம் ஒன்றை நாம் காண்கிறோம். தாயாதிச் சண்டையில் பாண்டியர்கள் பக்கத்திலே அவ்வப்போது உதவியாகப் போரிட்டு வந்த சோழர், சிங்களவர் ஆகிய இருவரையுமே விழுங்கிவிட்டு அப்புதிய அரசாங்கம் மிகுந்த பலத்துடன் விளங்கியிருக்கிறது. இது எங்ஙனம் சாத்தியமாகும்? தாயாதிச் சண்டைக் காலத்திலும் அதற்குப் பிறகும் பாண்டியர்களுக்கு ஏழகத்தார் என்பார் ஒருவருடைய உதவி இருந்திருக்கிறது. சோழ சாசனங்களிலே ஏழகத்தார் பெயர் எப்போதும் மறவர் பெயருடன் சேர்ந்தே காணப்படுகிறது.

இராஜாதிராஜனுடைய திருவாலங்காட்டுக் கல்வெட்டிலே நான் முதல் முதலாக ஏழகத்தார் பெயர் காணப்படுகிறது. அந்தப் பகுதி பின்வருமாறு: “பாண்டியனார் குலசேகரர் தமக்கு முன்பு செய்த நன்மைகளும் பாராதே ஈழத்தா னுடனே ஸம்பந்தம் பண்ணம் இவனும் இருவருங் கூடா நின்று சோழ ராஜ்யத்துக்கு விரோதமாயிருப்பன செய்யவுங் கடவதாக நிச்சயித்து இதுக்கு உறுப்பாகப் பாண்டி நாட்டு ஏழகத்தாரிலும் மறச்சாமந்தரிலும் நமக்குச் சேர்வுபட்டு நின்று பணி செய்கிற இராஜராஜக் கற்குடியராயனும் இராஜ கும்பீர அஞ்சுகோட்டை நாடாழ்வானும் உள்ளிட்டாரை

அத் துறைகளில் நின்றும் வெள்ளாற்றுக்கு வடகரையிலே போதப் பண்ணி...<sup>1</sup>

அடுத்தபடியாக உள்ளது மூன்றாம் குலோத்துங்கனுடைய சிதம்பரம் கல்வெட்டு. அதன் பகுதி பின்வருமாறு :

“விக்கிரம பாண்டியன் வேண்ட விட்ட தண்டால்  
வீரபாண்டியன் மகன்பட ஏழகம்பட<sup>2</sup>  
மறப்படைப்படச் சிங்களப் படை  
மூக்கறுப் புண்டு அலைகடல் புக”

கடைசியாக உள்ளவை புதுக்கோட்டை ஸம்ஸ்தானத்துச் சாசனங்கள். அவற்றிலே வரும் பகுதி “மறப்படையுடன் ஏழகப்படை சிறைப்பட்டு விழத்தடிந்து.” என்பதாகும்.

இந்தச் சாசனங்களிலே காணப்படும் ஏழகத்தார் யார் என்பது நிர்ணயிக்கப்பட வில்லை. ஏழகத்தார் என்னும் செல் ஏழகத்து மக்கள் எனப் பொருள்படும். ஏழகம் என்பது மதுரை ஜில்லாவில் உள்ள ஏடகம் (திருவேடகம்) என்னும் ஊராக இருக்குமோவென்று டாக்டர் ஹூல்ஷ் சந்தேகப்பட்டார். (தே. இ. சாசனங்கள், மூன்றாம் வால்பூம், பக்கம் 212, கீழ்க்குறிப்பு.) தேவாரத்திலும் அவ்வூர் ஏடகம் என்றேதான் காண்கிறது. ஸ்ரீ கே. ஆர். ஸ்ரீநிவாஸன் அவர்கள் காரைக்குடிக்குப் பக்கத்தில் உள்ள கழனிவாசல் என்பதே ஏழகமாக இருக்க வேண்டும் என்று கருதுகிறார். (புதுக்கோட்டை ஸம்ஸ்தானச் சாசனங்கள், ஆங்கில மொழிபெயர்ப்பு, இரண்டாம் பாகம், பக்கம் 141, கீழ்க்குறிப்பு 62). எனினும், திருவாலங்காட்டுக் கல் வெட்டிலே பாண்டி நாட்டு ஏழகத்தார் என்று காண்பது கவனிக்

1. எய், இந்திகா, இருபத்திரண்டாம் வால்பூம், பக்கம் 90. அதிலே வெளியாகியுள்ள பாடம் ‘சேர்வுபட்டு நின்றுடன் செய்கிற’ என்பதாகும். ஆயினும் அவ்விடம் வெளியாகியிருக்கும் மசிப்படத்தைக் கவனித்தால் ‘சேர்வுபட்டு நின்று பணிசெய்கிற’ என வாசிக்கலாம் [என்றே தோன்று கிறது.

2. இந்தப் பகுதியை ‘ஏழக[ப்]ப[ரை\*]ட மறப்படை புட’ எனவும் கொள்ள முடியும்.

கத்தக்கது. ஏழகத்தார் பாண்டி நாட்டில் மட்டுமல்லாமல் வேறு இடங்களிலும் இருந்து வந்தனர் என்பது அதிலிருந்து நன்கு விளங்கும்.

ஏழகத்தார் ஏதோ ஒரு நாட்டு அரசரிமை பெற்றவர்கள் என்பதும் கல்வெட்டுக்களிலிருந்து தெரிகிறது. புதுக்கோட்டை ஸம்ஸ்தானத்திலிருந்து கிடைக்கும் ஒரு கல்வெட்டில் வீரபாண்டியபுரமான ஏழகச்சக்கரவர்த்திப் பெருந்தெரு என்னும் ஊர் கீழ்க்குண்டாற்றுப் பகுதியிலே அடங்கியதாகக் குறிக்கப்பட்டுள்ளது. (புதுக்கோட்டை ஸம்ஸ்தானச் சாசனங்கள், 450). மற்றொரு சாசனத்தில் வீரபாண்டிய புரமான ஏழகப் பெருந்தெருவில் உள்ள கழனிவாசல் குறிக்கப் பெற்றுள்ளது. (தே. இ. சாசனங்கள், எட்டாம் வால்பூம், 183 நெ). கழனிவாசலை இப்போது காரைக்குடிக்குப் பக்கத்தில் உள்ள ஊராகக் கொள்ளலாம். புதுக்கோட்டை ஸம்ஸ்தானத்து நெய்வாசலிலிருந்து கிடைக்கும் முதலாம் மாறவர்மன் சுந்தர பாண்டியனுடைய ஆட்சியின் ஐந்தாம் ஆண்டு கொண்ட ஒரு கல்வெட்டு அவ்வூர்க் குளத்திலிருந்து நீர் பாய்ச்சிக் கொள்ளும் உரிமையைக் கோயிலுக்கு விற்றுக் கொடுத்த ஊர்ச்சபையார் வரிவிலக்கு அளித்த சந்தர்ப்பதைக் கூறும்போது, “எப் பேற்பட்ட...றவதரங்களிலும் நீரிலும் இராஜ கோயிற்றமத்திலும் ஏழகத்தார் கோயிற்றமத்திலும் இறை குடிமை எச்சோறு...” என்ற பகுதி காணப்படுகிறது. (புதுக்கோட்டைச் சாசனங்கள், 259). இவற்றால் ஏழகத்தாருக்கு அரண்மனை, படை, கஜானா முதலிய ராஜ சின்னங்கள் பலவும் இருந்தமை தெளிவாகும்.

இந்தப் போரைப்பற்றி மஹாவமிசத்தில் காணும் விவரத்திலே பாண்டியர்களுடைய பக்கத்திலே போரிட்ட அதிகாரிகள், தண்டநாயகர்கள் ஆகியவர்களுடைய பெயர்கள் விவரமாகக் கொடுக்கப்பட்டிருப்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். அவர்களிலே நிஷதராஜன் (நிகழ்தராஜன்), மாளவச்சக்கரவர்த்தி ஆகியோர் பெயர்களும் காணப்படுகின்றன. நிஷதராஜன், மாளவச்சக்கரவர்த்தி ஆகிய பெயர்களைத் தாங்கிய சிற்றரசர்கள் இப்போது செட்டிநாட்டுப் பிரதேசம் என்று வழங்கப்படும் பகுதியில் கிடைக்கும் சாசனங்களிலே மிகுதியும் காணப்படுகின்றனர். ஆனால் ஏழகத்தார்

ருடைய பெயர் மஹாவமிசத்திலே காணப்படவில்லை. சோழ சாசனங்களிலே அவர்கள் தனியாகக் குறிக்கப்பட்டிருக்கையில் மஹாவமிசத்திலே அவர்கள் பெயரே காணப்படாமல் இருப்பது ஆச்சரியம் தான். மற்றவர்களைத் தனித்தனியாகப் பிரித்துக் கூறிய மஹாவமிசத்தின் ஆசிரியர் ஏழகத்தாரின் பெயரை அவ்விதம் தனியாகக் கொடுக்க வேண்டும் என்று நினைக்க வில்லை போலும். அவர்களைப் பாண்டியர்களில் ஒரு பிரிவினராகவே அந்தூல் ஆசிரியர் கொண்டிருத்தல் வேண்டும். அதைக் கவனிக்கும்போது ஏழகத்தார் பாண்டியர்களிலே ஒரு பிரிவினர் என்றும், அவர்கள் பாண்டிய நாட்டு எல்லைக்கு அப்பால் உள்ள ஓரிடத்திலே இருந்து வந்தனர் என்றும், பாண்டிய சிங்காதனத்துக்காகத் தாயாதிச் சண்டை நடந்து வந்த இச்சமயத்தில் அவர்களில் சிலர் தங்கள் பூர்வதேசத்துக்கு வந்து தங்கித் தாயாதிகளுக்கு உதவிபுரிந்து வந்தனர் என்றும் கொள்ளலாம்.

அவர்கள் யார் என்பதை அறிவதற்குக் கொங்கு நாட்டுச் சாசனங்கள் சில உதவியாக உள்ளன. மதுரை ஜில்லா பழனிக்குப் பக்கத்தில் உள்ள கீரனூர் என்னும் கொழும்பு கொண்ட சோழ நல்லூர் அந்நாளிலே கொங்கு நாட்டுப் பகுதியில் அடங்கியிருந்தது. அவ்வூரில் வாசிச்சுவரர் கோவிலிலே கொங்கு நாட்டு அரசனான திரிபுவன சக்கரவர்த்தி வீர ராஜேந்திர தேவனுடைய கல்வெட்டுகள் பொறிக்கப்பட்டுள்ளன. அவற்றுள் அவனுடைய ஆட்சியின் பதின்மூன்றாம் ஆண்டு கொண்ட (தே. இ. சாசனங்கள், ஐந்தாம் வால்பூம், 262-நெ.) ஒன்று கோயிலில் ஒரு சந்தி விளக்கு எரிக்க அமரபுஜங்கப் பல்லவரையன் என்பான் ஒரு கழஞ்சு பொன் அளித்த செய்தியைக் கூறுகிறது. அந்தப் பொன்னைக் கொண்டு விளக்கு எரிக்க ஒப்புக் கொண்டவன் அக்கோயிலில் காணி உடைய சிவப்பிராம்மணன் காசிபன் பாண்டிய தனஞ்சய சைவேச்சுவர முடையானான சைவசக்கரவர்த்தி என்றும் அது கூறுகிறது. அதே இடத்தில் அவ்வரசனுடைய பதினேராம் ஆண்டு கொண்ட மற்றொரு கல்வெட்டு (ஷா. நெ. 264), அரையன் சிறியனான வேந்த சூளாமணிப் பல்லவரையன் என்பான் அளித்த பொன்னைக் கோயில் சிவப்பிராம்மணன் பாண்டிய தனஞ்சய சுந்தனான குலோத்துங்க சோழ பட்டன் என்பவன்

கைக் கொண்ட செய்தியைத் தெரிவிக்கிறது. அவ்வரசனுடைய பன்னிரண்டாம் ஆண்டு கொண்ட ஒரு கல்வெட்டு (196 நெ. 265) குருளன் கூத்தன் ஆன உத்தமக்கோன் என்பான் சந்தியாதிபத்துக்காக அளித்தப் பொன்னை அக்கோயில் காணியுடைய சிவப்பிராம்மணர் காசிபன் பாண்டிய தனஞ்சய சைவேச்வர முடையானை சைவ சக்கரவர்த்தியும் பாண்டிய தனஞ்சய சுந்தனை குலோத்துங்க பட்டனும் ஆகிய இருவரும் கைக் கொண்டனர் என்று கூறுகிறது.

இந்தச் சாசனங்களிலே கண்ட கொங்கு மன்னனை வீரராஜேந்திர தேவன் சகாப்தம் 1129 (அதாவது கி.பி. 1207-08) சிங்காதனம் ஏறியான். இது கோயம்பத்தூர் ஜில்லா உடுமலைப் பேட்டைத் தாலாகாவில் உள்ள குமரலிங்கம் என்னும் கிராமத்திலிருந்து கிடைக்கும் அவனுடைய சாசனம் (1909-ஆம் ஆண்டு 135 நெ.) ஒன்றால் விளங்குகிறது. அவ்வூரில் உள்ள கரிவரதராஜப் பெருமாள் கோயிலில் காணும் அந்தச் சாசனம் திரிபுவன சக்கரவர்த்திகள் கோனேரின்மை கொண்டான் வீரராஜேந்திர தேவனுடைய ஆட்சியின் இருபத்து ஐந்தாம் ஆண்டும் சகாப்தம் 1153-ம் கொண்டது. பாண்டி மண்டலத்துக் கீழ் இரணியமுட்ட நாட்டுத் திருமாலிருஞ்சோலை அழகர் கோயிலிலே வீரராஜேந்திரன் சந்திக்கும் பத்து ஆழ்வார்களுக்கு அமுதுபடி சாத்துப்படிக்குமாக நிலம் அளிக்கப்பட்ட செய்தியைத் தெரிவிக்கிறது. இதனால் கீரணூரிலிருந்து கிடைத்த மேற்கண்ட சாசனங்கள் கி. பி. 1217-க்கும் 1220-க்கும் இடைப்பட்ட காலத்தைச் சார்ந்தவை என்பது தெளிவாகும்.

இந்தச் சமயத்திலே தான் கி. பி. 1216-இல் பாண்டிய சிங்காதனம் ஏறிய மாறவர்மன் சுந்தர பாண்டியன் அது காலும் இருந்த நிலையைத் தலைகீழாக மாற்றிச் சோழர்களைத் தோற்கடித்துப் பெருவெற்றி கொண்டு தமிழ் நாடு முழுவதையும் விஜயம் செய்தான். இவ்விதம் பாண்டியர்கள் வெற்றியடைந்த காலத்தில் கொங்கு நாட்டுப் பகுதியிலே அரசரிமை கொண்டிருந்த பாண்டியன் ஒருவனிடமிருந்து சிவப்பிராம்மணர்கள் பாண்டிய தனஞ்சயன் என்ற விருதைப் பெற்றிருந்தல் வேண்டும்.

ஆனால் மாறவார்மன் சூந்தர பாண்டியனோ தனஞ்சயன் என்ற பெயரையோ பட்டத்தையோ கொண்டிருந்ததாகத் தெரியவில்லை. அதுமட்டுமல்ல. மதுரையிலிருந்து அரசுபுரிந்த பாண்டிய மன்னர்களில் எவருமே அதைத் தரித்திருந்ததாகத் தெரியவில்லை.

எனினும், பூர் பாண்டிய தனஞ்ஜய என்று பெயர் பொறிக் கப்பட்ட தங்க நாணயங்கள் சில கிடைத்துள்ளன. இந் நாணயங்கள் ஒரு பக்கத்தில் வலதுபுறத்தைப் பார்க்கும் இரண்டு மீன்களும் இருபுறங்களிலும் பக்கத்துக்கு ஒன்றாகக் குத்து விளக்கும் மேலே ஆலவட்டக் குடையும் கீழே வில்லும் கொண்டு காணப்படுகின்றன. மறுபுறத்திலே அரசன் பெயர் கன்னடத்திலே எழுதப்பட்டுள்ளது. (தேன்னிந்திய ஆர்க்கியலாஜிகல் ஸோஸைட்டியின் டிரான்ஸாக்ஷன்ஸ், முதல் வால்யூம், 1955, பக்கங்கள் 28, 31).

இந்த நாணயத்திலே காணும் கன்னட எழுத்தைக் கொண்டு அது கன்னட மொழியைப் பேசும் பிரதேசத்தை ஆண்டு வந்த அரசன் ஒருவனுடையதாக இருக்க வேண்டும் என்று நிச்சயமாகக் கொள்ளலாம். பாண்டியன் என்றப் பட்டப் பெயர் தரித்து மேலேக் கடற்கரை ஓரமாகத் துளு நாட்டை ஆண்டு வந்த ஆளுப மன்னர்களிலே தனஞ்ஜயன் என்ற பெயர் சகஜமாகக் காணப்படுகிறது. அந்தப் பெயர் கொண்டவன் ஒருவன் அங்கே அந்நாளில் அரசுக்கட்டிலில் வீற்றிருந்திருக்கிறான். தென் கன்னடம் ஜில்லா கர்க்கல் தாலுகாவில் வராங்கா என்னுமிடத்திலிருந்து கிடைக்கும் ஒரு சாசனம் (1929-ஆம் ஆண்டு 526 நெ.) கன்னட சுலோகங்களால் ஆனது. சூலசேகரன் என்னும் ஆளுப அரசன் ஒருவனுடைய தேவியான ஜாக்கலமாதேவி என்பவள் அளித்த தானத்தைத் தெரிவிக்கிறது அந்தக் கல்வெட்டு. அதிலே அவ்வரசனுக்குப் பண்டித பாண்டியன், பாண்டிய தனஞ்ஜயன் என்ற விருதுகள் அளிக்கப்பட்டுள்ளன. இந்தக் குலசேகரன் சகாப்தம் 1127, அதாவது கி. பி. 1205-06 ஆம் ஆண்டு, அரசு புரிந்திருக்கிறான்.

பாண்டியர்களுக்கும் துளு நாட்டுக்கும் உள்ள சம்பந்தத்தைப்பற்றி நாம் ஏற்கெனவே குறிப்பிட்டிருக்கிறோம். (மேலே

௩௩-௩௪ பக்கங்கள்). முதலாம் இராஜாதிராஜன் இலங்கையிலே கொண்ட வெற்றிகளை எடுத்துக் கூறும் மெய்க்கீர்த்திப் பகுதியையும் இலங்கைச் சரித்திரமான மஹாவயிசத்தில் காணும் பகுதியையும் ஒப்பிட்டுப் பார்த்திருக்கிறோம். மஹாலானகித்தி என்பானுடைய ஒரே மகனான விக்கிரம பாண்டியன் இராஜாதிராஜனிடம் அடைந்த பயத்தால் நாட்டைத் துறந்து, துளு தேசத்தில் இருந்துவந்தான் என்பதையும் அவன் தந்தை இறந்த செய்தியைக் கேட்டபிறகே அவன் துளு நாட்டிலிருந்து இலங்கை சென்றான் என்பதையும் குறிப்பிட்டிருக்கிறோம். கி. பி. 13-ஆம் நூற்றாண்டின் பிற்பகுதியில் ஆளுபநாட்டை ஆண்டு வந்த பல்லமஹாதேவி என்பவள் ஸோமகுலத்தில் மாண்புரணேசுவர தேவர் வம்சத்திலே பிறந்தவள் என்று தென் கன்னடம் ஜில்லா உடுப்பித் தாலுகாவில் அம்மஞ்சி என்னும் இடத்திலிருந்து கிடைத்த ஒரு கல்வெட்டு தெரிவிக்கிறது. (1932-ஆம் ஆண்டு 336 நெ.)

கி. பி. 1251-ஆம் ஆண்டு பாண்டிய சிங்காதனம் ஏறிய ஜடாவர்மன் சுந்தர பாண்டியனுடைய சாசனம் ஒன்று ஸ்ரீ ரங்கம் (1939-ஆம் ஆண்டு 81 நெ.) ரங்கநாதருடைய ஆலயத்தில் கிடைத்துள்ளது. அதிலே அவன் கேரள, ஹொய்சள ராஜ்யங்களைத் தோற்கடித்தான் என்றும், தன் தம்பியான வீர பாண்டியனைக் கொங்கண ராஜ்யத்துக்கு அரசுகை முடிசூட்டினான் என்றும் கூறப்பட்டிருக்கிறது. கொங்கண ராஜ்யம் என்று அதிலே குறிக்கப்பட்டிருப்பது துளுநாடே போலும். அப்போது ஆளுப நாட்டை வீர பாண்டிய ஆளுபேந்திரன் என்பான் ஒருவன் ஆண்டுவந்த செய்தி தெரிகிறது. சகாப்தம் 1173, அதாவது கி. பி. 1261-62 கொண்ட அவனுடைய சாசனம் ஒன்று மங்களூரில் கிடைத்திருக்கிறது. (1929-ஆம் ஆண்டு 370 நெ.) அதேபோலக் கொங்கு நாட்டிலும் கி. பி. 1254-ஆம் ஆண்டில் சிங்காதனம் ஏறி, இரு கொங்குகளையும் வெற்றி கொண்ட வீர பாண்டியன் என்பான் ஒருவனும் இருந்திருக்கிறான். கொங்கு நாட்டுக்கும், கொங்கண ராஜ்யத்துக்கும் ஏதாவது தொடர்பு உண்டா என்பதை இப்போது நாம் நிச்சயமாகச் சொல்லமுடியாது. ஆயினும் பாண்டிய தனஞ்சயன் என்ற பட்டப்பெயர் கொண்ட ஆளுப அரசன் ஒருவன் கொங்கு நாட்டை ஆண்டிருப்பது குறிப்பிடத்தக்கது.



இதே சமயம் மதுரைப் பாண்டிய மன்னர்களிலும் ஜடாவர்மன் வீர பாண்டியன் என்பான் ஒருவன் இருந்திருக்கிறான். அவனும் கி.பி. 1253 அல்லது 1254-ஆம் ஆண்டிலே பாண்டிய சிங்காதனம் ஏறியவன். (இந்தியன் ஆண்டிசுவரி, நாற்பத்திரண்டாம் வால்பூம், நாற்பத்து நாலாம் வால்பூம் இரண்டும் பார்க்க). இப்போது உள்ள நிலையிலே மதுரைப் பாண்டியர், கொங்கு நாட்டரசர், துளு நாட்டு ஆளுபர் ஆகிய மூவரிடையிலும் காணப்படும் வீரபாண்டியன் வெவ்வேறானவனல்லது ஒருவனே தானா என்பதை நாம் நிர்ணயிக்கமுடியாது. ஆயினும், மதுரை மன்னனான ஜடாவர்மன் வீர பாண்டியனுடைய ஆட்சியின் பதினேராம் ஆண்டு கொண்ட ஒரு கல் வெட்டில் அவனுடைய சைன்னியத்தில் கன்னட தேசத்துக்குதிரைச் சேவகர்கள் இருந்தனர் என்பது காணப்படுகிறது. (1901 ஆம் ஆண்டு 134 நெ.)

இவற்றால், மதுரைப் பாண்டியர்களுக்கும் துளுநாட்டுப் பாண்டியர்களுக்கும் நெருங்கிய தொடர்பு இருந்துவந்தது தெரியவரும். துளுநாட்டுப் பாண்டியர்கள் மருமக்கள் தாய் முறையைச் சில சமயங்களில் அனுஷ்டித்து இருக்கிறார்கள். அதனால் மதுரைப் பாண்டியர்களில் சிலர் அங்கே அரசரிமை அடைவது சாத்தியமாக இருந்திருக்கலாம்.

இதுவரையில் கூறியதைக் கொண்டு கவனித்தால், சோழ சாசனங்களிலே ஏழகத்தார் என்று குறிக்கப்பட்டிருக்கிறவர்கள் துளுநாட்டுப் பாண்டியர்களாகவே இருத்தல் வேண்டும் எனக் கொள்ளலாம். துளுநாடான கொண்கானமும் ஒருகாலத்திலே தமிழ் நாட்டுப் பகுதியாகத்தான் இருந்துவந்தது. துளுநாட்டுப் பகுதியைப் பற்றியும் கொண்கான மக்களைப் பற்றியும் சங்கநூல்களிலே குறிப்புகள் காணப்படுகின்றன. (அகநானூறு, பாடல் 15; குறுந்தொகை, பாடல் 73). நற்றிணையில் ஒரு பாடலிலே பின்வரும் பகுதி காணப்படுகிறது:

“பொன்படு கொண்கான நன்ன னன்னாட்டு  
ஏழிற் குன்றம் பெறினும் பொருள்வயின்  
யாரோ பிரிகிற பவரே”

—(நற்றிணை, பாடல் 391)

இதிவிருந்து கொண்கானம் பொன் விளையும் பூமி என்றும் நன்னன் என்னும் தலைவனுக்கு உரியது என்றும் ஏழில் குன்றம் என்னும் மலை அங்கே இருந்தது என்றும் தெரிகிறது. மத்திய காலத்திலே சோழ சாசனங்களில் காணப்படும் ஏழகம் என்பது சங்க இலக்கியங்களில் காணும் ஏழில் என்பதே போலும். இரண்டும் ஒரே பொருளைக் கொடுப்பன. கொண்கானம் அல்லது கொங்கணமும் ஏழு பிரிவுகளாக அமைந்தது; அதனாலேயே சப்த-கொங்கணம் என்ற பெயரைப் பெற்றது. ஆகவே ஏழகத்தார் என்பார் துளு நாட்டுப் பாண்டியர்களே என்று கொள்வதில் தவறு ஏதும் இருத்தற்கில்லை.

#### தாயாதிச் சண்டையின் விளைவு

பாண்டிய நாட்டிலும், சோழ நாட்டிலும் சிங்காதனத்துக் காகப் போட்டி ஏற்பட்டு நடந்த சண்டைகள் பக்கத்து அரசர்களுக்கும் சண்டையிலே ஈடுபடச் செய்து தென்னாடு முழுவதையுமே கலக்கிவிட்டன. இதன் பயனாக எதிர்பாராத விளைவுகள் பல தோன்றின. அண்டை அயல் அரசுகளுக்கிடையே இருந்த சுமுகமான உறவிலும் மாறுதல் ஏற்பட்டிருக்கிறது. இந்த நிலை போட்டியிலே சம்பந்தப்பட்ட மூல புருஷர்கள் உயிருடன் இருந்த வரையில் நீடித்திருக்கக் காணலாம்.

மூன்றாம் குலோத்துங்கனுடைய மெய்க்கீர்த்திகளைக் கவனித்தால் அவன் வாழ்நாள் முழுவதையும் ஒரு நாடு இல்லாவிட்டால் மற்றொரு நாடு என்று ஏதாவது ஒரு நாட்டுடன் சதா சண்டை போட்டுக் கொண்டே இருந்தான் என்பது தெரிய வரும். அவன் சோழ சிங்காதனத்திலிருந்து விரட்டிய இராஜாதி ராஜன் சோழ சாம்ராஜ்யத்தின் வடபகுதியாக இருந்த வேங்கிக்குச் சென்று, அங்கே இருந்த சிற்றரசர்களுடைய உதவியோடு அவ்விடத்திலே தங்கிவிட்டான். அது குலோத்துங்கனுக்குத் தீராத தொல்லையாகப் போய்விட்டது போலும். வேங்கியில் இருந்த சிற்றரசர்கள் தங்களிடம் தஞ்சம் புகுந்த அரசனைக் கைவிடவில்லை. அவனையே பேரரசனாக மதித்து ஏற்றுக்கொண்டார்கள். அவ்விதம் செய்வதால் அவர்களுக்குச் சிரமம் ஏதும் இல்லை; பொறுப்பும் இல்லை. அதற்குப் பதிலாக மூன்றாம் குலோத்துங்கனை உள்ளே நுழைய அனுமதித்தால்

நிலைமை அவர்களுக்கு விரோதமாகப் போய்விடும். பலம் பொருந்திய அவன் சிற்றரசர்களை ஒங்கவிடமாட்டான். அதனாலேயே அவர்கள் இராஜாதிராஜனை ஆதரித்துக் குலோத்துங்கனுக்கு விரோதமாக நின்றார்கள் போலும்.

**மூன்றாம் குலோத்துங்கன் வாரங்கல்மீது படையெடுத்துச் சென்றது.**

முன்னாள் புதுக்கோட்டை ஸம்ஸ்தானப் பகுதியிலிருந்து கிடைத்துள்ள இம்மன்னனுடைய இரண்டு கல்வெட்டுக்களைப் பற்றி ஏற்கனவே குறிப்பிட்டுள்ளோம். புயல் வாய்த்து வளம் பேருக என்று தொடங்கும் அம் மெய்க்கீர்த்தி பல புதிய விஷயங்களைக் கூறுகின்றது. அதிலே அவன் தாங்கரும் போர் நடத்தி வடுகரை வெற்றிகொண்டு வேங்கி மண்டலத்தைத் தன்னதாக்கிக் கொண்டபின் பொன் மழை பெய்து உறங்கை என்னும் பொன்னகர் புக்கருளினான் என்று கூறப்பட்டிருக்கிறது (புதுக்கோட்டை ஸம்ஸ்தானச் சாசனங்கள், 163, 166-நெ.). உறங்கை என்று மெய்க்கீர்த்தியில் காண்பது காகதீயவமிசத்து அரசர்களுடைய தலைநகரான ஒருங்கல், அதாவது இப்போது வாரங்கல் என்று வழங்கப்பெறும் இடமாகும். இதிலிருந்து குலோத்துங்கன் காகதீய மன்னர்களோடு போர்புரிந்து வெற்றிகொண்டு பொன் மழை பெய்து அவர்கள் தலைநகரான வாரங்கல் நகரை அடைந்தான் என்று கொள்ளவேண்டும் என்பது தெளிவாகும். ஆனால் ஆராய்ச்சியாளர்கள் இதை மிகைபடக் கூறியதென்று கொள்வர்.

ஆயினும் காகதீயர்களுடைய தலைநகரிலே பொன் மழை பெய்ததென்ற சம்பவம் மற்றொரு சந்தர்ப்பத்திலும் கூறப்பட்டுள்ளது. இப்போது மத்தியப் பிரதேசம் என்று வழங்கப்பெறும் பிரதேசத்தில் பழைய பஸ்தர் ராஜ்யத்தில் உள்ள தந்தாவாரம் என்னும் கிராமத்தில் உள்ள தந்தேசுவரி ஆலயத்தின் ஸ்ரீபண்டாரத்திலே உள்ள கல்லில் பொறிக்கப்பட்டுக் காணும் ஒரு கல்வெட்டில்தான் (எபி. இந்திகா, பன்னிரண்டாம் வால்யூம், நெ. 30, பக்கங்கள் 242-50) அது குறிக்கப்பட்டுள்ளது. ஸம்ஸ்கிருதத்தில் ஒரு பாடமும், ஹிந்தியில் ஒரு பாடமும் கொண்ட அந்தக் கல்வெட்டு, விக்கிரம ஸம்வத்

ஸரம் 1760 (அதாவது கி. பி. 1703)-ல் திக்பாலதேவன் என் பான் தந்தாவாரத்துக்குக் குடும்ப யாத்திரை செய்து தன் குலதெய்வத்தை, அதாவது தந்தேசுவரி தேவியை, வழிபட்ட செய்தியைத் தெரிவிக்கிறது. அதிலே அவனுடைய வமிசாவளி கொடுக்கப்பட்டுள்ளது. பஸ்தர் ராஜ வமிசத்தைச் சேர்ந்த அவர்கள் வாரங்கல் நகரத்துக் காகதீய வமிசத்துப் பிரதாபருத் திரன் சகோதரனான அன்னமராஜன் வழி வந்தவர்களாம். பிரதாபருத்திரன் யவனர்களிடம், அதாவது முஸ்லிம்களிடம், தோல்வியுற்று நாட்டை இழந்தான் என்றும், பொன் மழை (கனகவர்ஷம்) பெய்ததால் உண்டான கலவரத்திலே அவன் உயிரை இழந்தான் என்றும், அதன்மீது பிரதாபருத்திரன் தம்பியான அன்னமராஜன் நாட்டைத் துறந்து வெளியேறி, பஸ்தர்ப் பகுதியை அடைந்து அங்கே தனக்கெனத் தனி ராஜ்யம் ஒன்று அமைத்துக் கொண்டான் என்றும் கூறப் பட்டிருக்கிறது. (சாசன இலாகாவின் 1909-ஆம் ஆண்டு அறிக்கை, பாரா. 66).

இந்தச் சாசனத்தில் காணும் பிரதாபருத்திரன் யார் என்பதைப்பற்றி ஆராய்ச்சியாளர் பற்பல விதமாகக் கருது கிறார்கள். காகதீய அரசை முஸ்லிம்கள் கைப்பற்றிய சமயம் அரசுபுரிந்து வந்த கடைசி அரசனான பிரதாபருத்திரன் என்றே கொள்ளுவர் ஒரு சாரார். தில்லி சுல்தான் கையாஸ்-உத்-தீன் என்பானுடைய மூத்த மகனும் பட்டத்து இளவரசனுமான உலாக்கான் என்பான் நடத்திய இரண்டாவது 'திலிங்' படையெடுப்பில் இந்தப் பிரதாபருத்திரன் முஸ்லிம்களிடம் சிறைப்பட்டான். சிறைப்பிடித்த அவனை உற்றூர் உறவினர்களோடு சேர்த்துத் தக்க காவலுடன் தில்லி நகருக்கு அனுப்பிவைத்தான் உலாக்கான். ஆனால் பிரதாபருத்திரன் தில்லி நகரம் போய்ச் சேரவில்லை. வழியில் விந்திய மலைப் பக்கத்தில் போய்க் கொண்டிருந்தபோது நர்மதா நதி தீரத்தில் அவன் தன் விருப்பப்படி உயிரைத் துறந்தான். இது கி. பி. 1323-ஆம் ஆண்டு நிகழ்ந்தது. (தேன்னிந்தியாவில் முஸ்லிம்கள் ஆட்சி பரவிய ஆரம்பகால வரலாறு, பக்கங்கள் 118-120. இன்னும் டாக்டர் எம். ராமராவ் எழுதிய வாரங்கல் நகரத் துக் காகதீயர்களின் சரித்திரம், பக்கம் 98-பார்க்க). ஆயினும்

இந்தப் போர் சம்பந்தமாக எந்த இடத்திலும் பொன் மழை பெய்ததாகக் குறிக்கப் பெறவில்லை.

சாசனத்தில் கண்டுள்ள பிரதாபருத்திரன் இவனாக இருக்குமானால் அந்த வமிசத்தை நிறுவிய அவன் தம்பி அன்னமராஜனுக்கும் சாசனம் வழங்கிய திக்பாலதேவனுக்கும் இடையே சுமார் நானூறு ஆண்டுகள் இருக்கும். அன்னமராஜனுடைய பத்தாம் தலைமுறையில் வந்தவன் திக்பாலதேவன். அதனால் இந்த இடைவெளி மிகவும் அதிகமானது என்றும், பிரதாபருத்திரன் வேறு அரசனாக இருத்தல்வேண்டும் என்றும் சிலர் கொள்வர். பதினேந்தாம் நூற்றாண்டில் அரசு செலுத்திக் கி. பி. 1422-ஆம் ஆண்டில் அஹமத் ஷா பஹ்மனியால் வெற்றி கொள்ளப்பெற்ற அரசன் ஒருவனாக இருத்தல்வேண்டும் என்று ஓர் ஆசிரியர் கருதினார். (எபி. இந்திகா, பன்னிரண்டாம் வால்பூம், பக்கம் 243). ஓரிஸா, அதாவது உத்கல தேசத்துக் கஜபதி வமிசத்தைச் சேர்ந்த அரசன் ஒருவனாக இருக்கலாமென்று வேறு ஒருவர் நினைத்தார். (ஹெ. பக்கம் 244, கீழ்க்குறிப்பு),

ஆயினும் சாசனத்தின் வடமொழிப் பாடம், ஹிந்திப் பாடம் ஆகிய இரண்டையும் கவனித்தால் அதில் கூறப்பட்டிருக்கும் விவரம் கர்ண பரம்பரையாக வந்த இரண்டு மூன்று சம்பவங்களை ஒன்று சேர்த்து ஓர் உருவம் கொடுத்துப் பொறிக்கப்பட்டிருப்பதென்பது தெரியவரும். அவர்கள் குடும்பத்திலே வழங்கிவந்த கர்ண பரம்பரைச் செய்திகளைக் கொடுக்கும் அளவுக்குத்தான் அந்தச் சாசனம் உபயோகப்படும். முஸ்லிம்கள் காகதீய நாட்டைக் கொண்டது பிரசித்தமான சம்பவம். அப்போது பிரதாபருத்திரன் என்பான் காகதீய நாட்டை ஆண்டு வந்தான். அதேபோலப் பிரதாபருத்திரன் என்பான் ஒருவனுடைய காலத்தில் அவர்கள் தலைநகரிலே 'பொன் மழை' பெய்தது. அதன் பயனாக அப்போதும் அரசு நிலை குலைந்தது. பிரதாபருத்திரன் என்ற பெயர் கொண்ட ஒருவனை அதே பெயர்கொண்ட மற்றொருவனாக எண்ணி மயங்கி, இரண்டு சம்பவங்களையும் ஒன்று சேர்த்து ஒரே சம்பவமாகக் கொள்ளப்பட்ட தென்றே எண்ண வேண்டியிருக்கிறது. பொன் மழை பெய்தது ஒரே ஒரு தடவைதான் நிகழ்ந்

திருத்தல் கூடும். இரண்டு தடவை இருக்காது. ஆகவே, இரண்டு இடங்களில் குறிக்கப்பட்டிருப்பதும் ஒரே சம்பவத்தைக் குறிப்பதாகவே கொள்ளவேண்டும்.

காகதீயர்களிலே ருத்திரன் என்ற பெயர்கொண்டு மூன்று அரசர்கள் இருந்தார்கள். நடுவில் உள்ளவர் பெண். ருத்திரரம்பா என்ற பெயர் கொண்டவள். கடைசியான பிரதாப ருத்திரன் இந்த ருத்திரரம்பாவின் பெயரன். அவளுக்குப் பின் சிங்காதனம் ஏறியவன். ருத்திரன் என்ற பெயரைக் கொண்ட முதல் அரசன் ருத்திரரம்பாவின் தந்தையான கணபதியின் பெரிய தந்தை. கி. பி. 1151-ஆம் ஆண்டு முதல் கி. பி. 1196-ஆம் ஆண்டு வரையில் அவன் காகதீய நாட்டை அரசு புரிந்திருக்கிறான்.

இம்மன்னன் மூன்றாம் குலோத்துங்கன் ஆட்சிக் காலத்தில் அரசுபுரிந்திருக்கிறான். இவன் ஆட்சியின் முடிவிலும் காகதீய ராஜ்யத்துக்குப் பேராபத்து நேர்ந்திருக்கிறது. தேவகிரியைத் தலைநகராகக் கொண்டு ஆண்டுவந்த சேவுணர் எனப் பழம் யாதவ மன்னர்களிலே ஜைத்ரபாலன் என்பான் ருத்திர தேவனை வெற்றிகொண்டு போரிலே கொன்றான். இந்தச் செய்தி யாதவ மன்னர்களுடைய ராஜப் பிரசஸ்தியில் காணப்படுகிறது. ஹேமாத்ரி எழுதிய விரதகண்டத்தில் காணப்பெறும் அந்தப் பிரசஸ்தியில் பின்வரும் சுலோகம் உள்ளது.

தீக்ஷித்வா ரணரங்க தேவ யஜாதே  
ப்ரோதஸ்த சஸ்த ச்ருவஃ  
ச்ரோணீபிர் ஜகதீபதீந் ஹுதவதா  
யேந ப்ரதாபாநலே  
தைலங்காதிபதேஃ பசோர் விச ஸநம்  
ருத்ரஸ்ய ரௌத்ராக்ருதேஃ  
க்ருத்வா பூருஷமேத யஜ்ஞவிதிநா  
லப்த த்ரிலோகீ ஜயஃ

“புத்தபூமியிலே வேள்விக்கான தீக்ஷை செய்துகொண்டு ஆயுதங்களாகிய அகப்பைகளால் தன்னுடைய பிரதாபம் என்னும் நெருப்பிலே அநேக அரசர்களை அவிர்ப்பித்துத் தைலங்காதிபதியும் (அதாவது தெலுங்குதேச அரசனும்) ருத்திரனைப்

போன்ற தோற்றமுடையவனுமான ருத்திரனைப் பசுவாகக் கொண்டு புருஷமேதம் என்னும் வேள்வியைச் செய்து மூன்று உலகத்தையும் வென்றான்.” (பம்பாய் கேஜட்டியர், முதல் வால் யும், இரண்டாம் பாகம், பக்கங்கள் 238-9. இன்னும் 292-ம் பக்கத்தில் உள்ள 41-ஆம் சுலோகம்). அசுவமேதம் செய்வ தால் பூலோகம் முழுவதையும் வென்ற பதவி கிட்டுவதுபோல, புருஷ மேதம் அல்லது நரமேதம் செய்வதால் மூன்று உலகத் தையும் வென்ற பதவி கிட்டுகிறதாம்.

ஐைதுகி என்றும் ஐைத்ரவார்மன் என்றும் வழங்கப் பெறும் ஐைத்ரபாலன் சேவுண தேசத்தைக் கி. பி. 1191-ஆம் ஆண்டுமுதல் கி. பி. 1210-ஆம் ஆண்டுவரையில் அரசு புரிந்திருக் கிறான். அவனுடைய இவ் வெற்றி அவ்வமிசத்தைச் சேர்ந்த ராமசந்திர தேவனுடைய (கி. பி. 1292-ஆம் ஆண்டு கொண்ட) பைட்டான் (அதாவது பிரதிஷ்டானபுரத்துச்) சாசனத்தில் குறிக்கப்பட்டுள்ளது. அதிலே ஐைத்ரபாலன் திரிகலிங்காதி பதியைப் போரில் கொண்டு அவன் நாட்டைக் கைக்கொண் டான் என்று காணப்படுகிறது. இன்னும், “கருணாகர மான அம்மன்னன் கணபதியைச் சிறையிலிருந்து வெளிக் கொணர்ந்து அவனை அரசனாக முடிசூட்டினான்” என்றும் அது கூறுகிறது. (இந்தியன் ஆண்டிசுவரி, பதினான்காம் வால் யும், 316-பக்கம். இன்னும் இருபத்தோராம் வால்யும், 197-பக்கம்). ஐைத்ரபாலன் மகனான சிங்கணனுடைய காலத்துச் சாசனம் ஒன்று பாஹல் என்னுமிடத்திலிருந்து கிடைத் துள்ளது. அதிலே ஐைத்ரபாலன் கணபதியை ஆந்திரநாட் டுக்கு அரசனாக முடிசூட்டிவைத்தான் என்னும் செய்தி காணப் படுகிறது.

கணபதியின் ஆட்சியிலே அவன்கீழ்ச் சிற்றரசனாக ரேசர்லா என்னுமிடத்திலிருந்து ஆண்ட ருத்திரன் என்பா னுடைய பாலம்பேட்டைக் கல்வெட்டிலே பின்வரும் செய்தி காணப்படுகிறது. (ஹைதராபாத் ஆர்க்கியலாலிகல் ஸீரீஸ், நெ. 3, சுலோகங்கள் 21 - 24). கி. பி. 1213-ஆம் ஆண்டுகொண்ட அச் சாசனம், “காகதீய மன்னான ருத்திரதேவன் இறந்தவுடனே காகதீய நாட்டைக் கவர்ந்து கொள்ளும் நோக்கத்துடன் விரோதிகள் பலர் அந்நாட்டின்மீது படையெடுத்து வந்தனர்.

ருத்திரன் அந்த விரோதிகளை எதிர்த்தான். அவர்களிலே ஒருவன் தலையைக் கொய்து ஈட்டியிலே செருகினான். இதைக் கண்ட நாகதி அரசன்போன்ற படையெடுப்பாளர்கள் தங்கள் உயிருக்குப் பயந்து ஓடினார்கள். இவ்விதம் காகதீய ராஜ்ய லக்ஷ்மி முள்ளை மிதித்தவுடன் ருத்திரன் அவளைத் தூக்கி, முள்ளை அகற்றி அவளைத் திரும்பவும் பழைய ஸ்தானத்தில் நிலைநிறுத்தினான்” என்று கூறுகிறது.

காகதீய மன்னனான ருத்திரதேவனுக்குப் பிறகு சிங்காதனம் ஏறுவதற்கு உரியவனாக அவனுக்குப் பிள்ளை யாரும் இல்லை யென்றே தெரிகிறது. உப்பரப்பள்ளிச் சாசனமும், (ஹைதராபாத் ஆர்க்கியலாலிகல் ஸீரீஸ், நெ. 3) கர்ண பரம்பரைச் செய்திகளும் அவனுக்குப் பின் சிங்காதனத்திலமர்ந்த கணபதி தேவனை ருத்திரனுடைய மகன் என்றே குறிக்கின்றன. ஆயினும் சாசன இலக்கிய வழக்காறு முழுவதிலும் ருத்திர தேவனுடைய தம்பியான மகாதேவனுடைய மகனாகவே கணபதி குறிக்கப்பட்டுள்ளான். (டாக்டர் எம். ராமராவ் எழுதிய வாரங்கல் காகதீயர்களின் சரித்திரம், பக்கம் 53). இன்னும், ருத்திரதேவனுடைய ஆட்சியின் கடைசிக் காலத்தில் ருத்திரதேவனுக்கும் அவன் தம்பி மஹாதேவனுக்கும் அரசரிமை விஷயமாக மனவேற்றுமை ஏற்பட்டு இருவரும் சண்டைபோட்டுக் கொண்டார்கள் என்றும் ஒரு கதை உண்டு. (பிரதாப சரித்திரம் என்னும் தெலுங்கு நூல், 29-30-பக்கங்கள்). அவர்களுக்கு வேறு சகோதரர்களும் இருந்தார்கள் என்று தெரிகிறது.

அப்போது என்ன நடந்ததென்ற விவரம் நமக்கு நிச்சயமாகத் தெரியவில்லை. ஆயினும் அந்தச் சந்தர்ப்பத்தில் காகதீய ராஜ்யத்தின்மீது சேவுணர்கள் எனப்பெறும் யாதவர்களுடைய படையெடுப்பு ஒன்று நிகழ்ந்ததென்பது மட்டில் நிச்சயமாகத் தெரிகிறது. குலோத்துங்கனும் ஜைத்ரபாலனும் இந்தப் படையெடுப்பிலே ஈடுபட்டிருந்தான் போலும். காகதீய ருத்திரனிடம் அவன் விரோதம் பாராட்டுவதற்குத் தகுந்த காரணங்களும் இருந்திருக்கவேண்டும்.



காகதீய அரசே மேலைச் சாளுக்கிய மன்னனான ஆறாம் விக்கிரமாதித்தியன் காலத்தில் ஏற்பட்டது. அவன் பேடன் என்பானுக்கு அநுமகொண்டாப் பகுதியை வழங்கினான். அதுவே காகதீய அரசுக்கு அடிகோலியதாகும். அதன் பின் காகதீயர்கள் தங்கள் பேரரசர்களான மேலைச் சாளுக்கியர்களுக்கு விசுவாசமாக நடந்துகொண்டிருக்கிறார்கள். கலசூரியர்கள் சாளுக்கிய ராஜ்யத்தை அபகரித்ததைக் காகதீயர்கள் எதிர்த்திருத்தல் இயற்கையே. ருத்திரதேவனுடைய ஹனுமக் கொண்டாக் கல்வெட்டில் அவன் மைலகிதேவன் என்பானை வெற்றிகொண்டதாகக் குறிக்கப்பட்டுள்ளது. (இந்தியன் ஆண்டி குவரி, பதினொராம் வால்பூம், 59-ம் பக்கம் முதல்). இம் மைலகி தேவனைச் சேவுண அரசனான மல்லுகிதேவன் என்றே சிலர் கருதுவர். அது சரியாகத் தோன்றவில்லை. ருத்திரன் வெற்றிகொண்ட மைலகிதேவன் என்பான் கலசூரி வமிசத்தைச் சேர்ந்தவனாகவே இருத்தல்வேண்டும். அந்தப் பெயர் கொண்ட கலசூரி ராஜகுமாரர்கள் அப்போது நாட்டின் சில பகுதிகளிலே ஆண்டுவந்திருக்கிறார்கள்.

மூன்றாம் குலோத்துங்க சோழனுடைய திரிபுவனம் கல்வெட்டிலிருந்து அவன் ஆட்சி வடக்கே சக்கரம் அதாவது சக்கரக் கோட்டத்திலிருந்து தெற்கே இலங்கையில் உள்ள அநுராதபுரம் வரையில் பரவியிருந்ததென்று தெரிகிறது. (1907-ஆம் ஆண்டு 190-நெ. சாசனம். இதே தொகுப்பில் 1007-நெ. சாசனத்தையும் பார்க்க). அவன் மெய்க்கீர்த்தியிலும் 'ஆழிமண்டலமும் ஈழமண்டலமும்' அவன் ஆட்சியில் அடங்கியிருந்ததாகக் காணப்படுகிறது. ஆழிமண்டலம் என்பது சக்கரக்கோட்டப் பகுதியே போலும். (ஆழி - சக்கரம்). இவற்றால் சக்கரக் கோட்டமும் அந்நாளிலே சோழர்களுடைய ஆதிக்கியத்தில் இருந்து வந்ததென்பது விளங்கும். பஸ்தர்ப் பிரதேசம் சக்கரக் கோட்டத்தில் அடங்கியதாகும். ஆகவே ருத்திரதேவனுடைய தம்பியான அன்னமராஜன் பஸ்தர்ப் பிரதேசத்திலே தனக்கென ஒரு அரசை நிறுவிக்கொண்டதும் மூன்றாம் குலோத்துங்க சோழனுடைய ஆதரவையும், உதவியையும் கொண்டே இருத்தல் வேண்டும்.

## மூன்றாம் குலோத்துங்க சோழனும் இரண்டாம் பல்லவ தேவனும்

இரண்டாம் இராஜராஜன் தனக்குப் பின் சோழ சிங்கா தனம் ஏறுவதற்கு உரிமையுள்ளவனென்று இரண்டாம் இராஜாதிராஜனைத் தேர்ந்தெடுத்ததை ஒப்புக்கொள்ளாமல், தானே அந்த உரிமை பூண்டவன் என்று குலோத்துங்கன் முதல் முதலாகப் பிரகடனம் செய்துகொண்டபோது அவனுக்குக் கர்நாடக தேசத்து அரசுகளில் சில ஆதரவளித்து உதவியாக நின்றனவென்பதை முன்னரே நாம் குறிப்பிட்டிருக்கிறோம். குலோத்துங்கன்கோவையிலிருந்து அவன் தந்தையின் பெயர் சங்கமராஜன் என்பதும் அண்ணன் பெயர் நல்லமன் என்பதும் தெரியவருகின்றன. இந்தப் பெயர்களும் அவன் கர்நாடகப் பிரதேசத்தோடு தொடர்பு உடையவன் என்பதையே உணர்த்துகின்றன. கர்நாடகப் பகுதியில் அரசு செலுத்திய ராஜகுடும்பம் ஏதோ ஒன்றில் மணம் புரிந்துகொண்ட சோழ இராஜகுமாரி ஒருத்தியின் மகனாகவே அவன் இருத்தல்வேண்டும் போலும். இவ்விதம் சோழ சிங்காதனத்துக்குக் குலோத்துங்கன் உரிமை கொண்டாடியதைக் கர்நாடக அரசுகளில் சில ஆதரித்ததை, குந்தள ராஜ்ய விவகாரத்தில் இரண்டாம் இராஜராஜன் தலையிட்டுப் பிரட்டன் ஒருவனைத் துரத்தி மேலைச் சாளுக்கிய மன்னன் ஒருவனைக் கல்யாணபுரத்து அரசனாக முடிசூட்டியதற்கு எதிரிடையான நடவடிக்கையாகவே கருதவேண்டும் போலும். இது கி. பி. 1163-ஆம் ஆண்டுக்கு அணித்தாக நடைபெற்றிருத்தல் வேண்டும்.

கர்நாடக அரசுகள் சில ஒன்றுசேர்ந்து சோழ சிங்கா தனத்துக்குப் போட்டியாக ஒருவனை நிறுத்தி அவனுக்கு ஊக்கம் அளித்ததைக் கண்டு இரண்டாம் இராஜராஜன் சும்மா இருந்திருக்கமாட்டான். அவர்களுக்கு விரோதமாக அவன் ஏதாவது நடவடிக்கை எடுத்திருப்பான். அதற்குச் சிறிதுகாலத்துக்கு முன்பாகத்தான் மேலைச் சாளுக்கிய அரசை அபகரித்த கலசூரி மன்னனை பிஜ்ஜலன் கி. பி. 1167-ஆம் ஆண்டில் பட்டத்தைத் துறந்தான் என்பதையும், அவனுக்குப் பின் அவன் மகன் ஷோவிதேவன் என்றும் ராயமுராரி

என்றும் வழங்கப்பெற்ற சோமேச்வரன் சிங்காதனம் ஏறி  
 னுன்னப்பதையும், பட்டத்தைத் துறந்த சிறிதுகாலத்தின்கெல்  
 லாம் பிஜ்ஜலன் கொலையுண்டு இறந்தான் என்பதையும் நாம்  
 அறிவோம். பிஜ்ஜலன் சிங்காதனத்தைத் துறந்ததற்கு அந்  
 நாட்டு அரசியலிலே சோழமன்னன் தலையிட்டதே காரண  
 மாகவும் இருத்தல் கூடும்.

அவ்விதம் கருதுவதற்கான ஆதாரங்களும் இல்லாமல்  
 இல்லை. அந்நாளிலே நுளம்பபாடியை உச்சங்கி தூக்கத்தைத்  
 தலைநகராகக் கொண்ட பாண்டியவமிசக் கிளையினர் ஆண்டு  
 வந்தார்கள். அவர்களிலே காமதேவன் எனப்பெறும் விஜய  
 பாண்டியன் என்பான் அப்போது அரசுசெலுத்தி வந்தான்.  
 அவன் கலஞரியர்களுக்கு உறுதுணையாக நின்றவர்களில்  
 ஒருவன். அந்த விஜயபாண்டியனோடு இரண்டாம் இராஜராஜ  
 சோழன் போர்புரிந்திருக்கிறான். இது ஹொய்சள வேந்தனான  
 இரண்டாம் பல்லாள தேவனுடைய சாசனங்களிலிருந்து  
 தெளிவாகிறது.

பல்லாளதேவன் கி. பி. 1177-78-ஆம் ஆண்டில் உச்சங்கி  
 தூக்கம் கோட்டையைக் கைப்பற்றியதோடு அதன் அரசு  
 னான விஜய பாண்டியனையும் சிறைப்பிடித்தான் என்று புகழ்ப்  
 பெறுகிறான். (எபி. கர்நாடிகா, ஐந்தாம் வால்யூம், பேலூர் 137,  
 175-நெ. சாசனங்கள்). அந்தக் கோட்டை பிறர் நுழையமுடி  
 யாத அரசன் வலிகொண்டதென்று கருதப்பட்டு வந்தது.  
 “அதன் மதில்கள் மிகவும் உயரமாம். கருடனாலும் அதன் உச்  
 சியை அடையமுடியாதாம். பாதாளம்வரை செல்லும் ஆழ  
 மான அகழி அதனைச் சுற்றியிருந்தது. இவ்விதம் எட்டுத் திக்கு  
 களையும் அடையக்கூடியபடி விசாலமாகவும், வானளாவ உயர்ந்  
 தும் இருபுறங்களிலும் பரந்திருந்த அக்கோட்டை மூவுலகத்தி  
 லும் புகழ் பெற்றிருந்தது,” (ஹெ. பேலூர் 72 நெ. சாசனம்).  
 “சோழ மன்னன் அதைக் கைப்பற்றுவதற்காகப் பன்னி  
 ரண்டு வருஷங்கள் அதை முற்றுகையிட்டும், வெற்றி பெறாமல்  
 கடைசியில் அம் முயற்சியைக் கைவிடவேண்டி நேர்ந்தது”  
 என்று கூறப்படுவதிலிருந்து அந்தக் கோட்டையின் அரசன்  
 வலி நன்கு விளங்கும். எனினும் பல்லாளதேவனோ அந்தக்  
 கோட்டையையும் அதன் மன்னையும் வெகு சுலபமாகக்

கைப்பற்றிவிட்டாலும். அப்பால், அவன் பாண்டிய மன்னனை விடுதலைசெய்து அவனைத் திரும்பவும் சிங்காதனத்தில் அமர்த்தினான். இவ்வெற்றி அவனுக்கு ஒரு சனிக்கிழமையிலே கிட்டியதாம். அதனால் அவன் 'கிரிதூர்க்கமல்லன்', 'சனிவாரசித்தி' என்பனபோன்ற விருதுகளைத் தரித்துக்கொண்டானாம். ஆனால் இந்த விருதுகளை அதற்கு முன்னதாகவே கலசூரி மன்னர்கள் தரித்து வந்திருக்கிறார்கள்.

உச்சங்கி தூர்க்கம் கோட்டையைக் கைப்பற்ற முடியாமல் சோழர்கள் பன்னிரண்டு வருஷகாலம் அதை முற்றுகையிட்டிருந்தது கி.பி.1177-78-ஆம் ஆண்டில்பல்லாளதேவன் அதைக் கைப்பற்றியதற்கு முன்னதாக இருத்தல்வேண்டும். உச்சங்கி தூர்க்கத்து அரசனான விஜய பாண்டியன் அப்போது கலசூரி மன்னர்களின்கீழ்ச் சிற்றரசனாக துளம்பபாடியை ஆண்டுவந்தான். அவன் கி.பி.1171-ஆம் ஆண்டிலேயே ராஜிக சோளமனோபங்கன் என்னும் விருதைத் தரித்துக்கொண்டிருக்கிறான். (எபி. காநாடிகா, பதினேராம் வால்பூம், தாவனகரை 32 நெ. சாசனம்.) இந்த விருதிலே காணப்படும் ராஜிகசோழன் என்னும் பெயர்-இரண்டாம் இராஜராஜனையே குறிக்கும் போலும். விஜய பாண்டியனுக்கு முன்னதாக அந்த வமிசத்து மன்னனான திரிபுவன மல்ல பாண்டியன் என்பான் ஒருவனும் இதே விருதைக் கொண்டிருக்கிறான். (ஷே. ஹோளலகரை 68 நெ. சாசனம்.) அவன் மேலைச் சாளுக்கிய அரசனான ஆளும் விக்ரம மாதத்தியன்கீழ்ச் சிற்றரசனாக ஆட்சி புரிந்தவன். அப்போது ராஜிகன் எனப்படும் இராஜேந்திரனான முதற்குலோத்துங்க சோழனுடைய ஆசை நிறைவேறுதபடி அவன் தடுத்துவிட்டதைக் குறிப்பதாக இந்த விருதை உச்சங்கிப் பாண்டியன் தரித்துக்கொண்டான். ஆயினும் இந்த விருதை அவனுக்குப் பின்னால் வந்தவர்கள் தரித்துக்கொள்ளவில்லை. ஆகவே அதைப் பரம்பரை விருதாகக் கொள்ளமுடியாது. எனினும், விஜய பாண்டியன் இப்போது சந்தர்ப்பம் சரியாக இருந்ததையொட்டிப் புதிய விருது ஒன்று கொள்வதைவிடப் பழைய விருதே ஏற்றது என்று அதனைத் தரித்துக்கொண்டான் போலும். இதனால் இரண்டாம் இராஜராஜனுடைய எண்ணம் நிறைவேறவொட்டாமல் விஜய பாண்டியன் அதை முறியடித்து விட்டதாகப் பெருமைகொள்வது நன்கு விளங்

கும். ஆகவே பன்னிரண்டு வருஷகாலம் உச்சங்கி தூர்க் கத்தை முற்றுகையிட்டவன் இரண்டாம் இராஜராஜனாகவே இருத்தல்வேண்டும். அவனுக்குப் பின் சோழ சிங்காதனம் ஏறிய இரண்டாம் இராஜாதிராஜனும் அந்த முற்றுகையைச் சிறிது காலம் தொடர்ந்து நடத்தியிருத்தலும் கூடும்.

மைசூர் ராஜ்யத்துக் கடுர் ஜில்லாவில் ஆஸந்தி என்னு மிடத்தில் உள்ள ஈசுவரன் கோவில் ரங்க மண்டபத்தில் ஹெய்சள மன்னனான இரண்டாம் பல்லாள தேவனுடைய கல்வெட்டு ஒன்று இருக்கிறது. (ஐடி ஆறாம் வால்பூம், கடுர் 156-நெ. சாசனம்.) அவனிடம் சிற்றரசனாக இருந்த கங்கவமி சத்து நரஸிம்ஹன் என்பான் அளித்த தானங்களைப்பற்றிக் கூறும் அந்தக் கல்வெட்டிலே நரஸிம்ஹன் புகழை எடுத்து உரைக்கும் பின்வரும் கன்னடச் செய்யுள் ஒன்று காணப் படுகிறது.

கரிபதியப்ப மாளவ மஹீபதி  
பண்டன லாள பூமிபம்  
துரக சயங்களிந்தெ ஸெவ கூர்ஜ்ஜர  
பூபதி சோள பூபஜர்ந்  
நெரெ திராந்து தாகே ரணரங்கதோள்  
ஓர்வ்வநே காதி கெல்தான் ஈ  
நரபதி பல்ல பூபன பெஸம் பதேத் ஈ  
நரஸிம்ஹபூபஜம்.

“யானைகளின் தலைவனான மாலவ மன்னன், போர்வீரர் களோடுகூடியலாள (அதாவது லாட) தேசத்தரசன், அநேகம் குதிரைவீரர்களுடன் விளங்கிய கூர்ஜ்ஜரவேந்தன், சோழ அரசன் ஆகியோர் ஒன்றுகூடி எதிர்த்துவந்தார்கள்; ஆயினும் நரஸிம்ஹ பூபஜன் ஆகிய இம்மன்னன் பல்ல (அதாவது பல்லாள) வேந்தனுடைய உத்தரவை ஏற்றுப் போர்க்களத் திலே ஒருவனாக நின்று அவர்களை எதிர்த்துத் தாக்கி வெற்றி கொண்டான்.” இதிலிருந்து ஹெய்சளர்களுக்கு எதிராக மாலவ, லாட, கூர்ஜ்ஜர, சோழ மன்னர்களுடைய கூட்டு ஒன்று இருந்ததென்பதும், பல்லாளன் அவர்களை வெற்றி கொண்டான் என்பதும் பெறப்படும்.

இந்தச் சாசனத்தில் அதன் காலம் குறிக்கப் பெறவில்லை. எனினும் கங்க மன்னனான நரஸிம்ஹனைப்பற்றிய செய்தி ஹொய்சள சாசனங்கள் வேறு பலவற்றிலும் காணலாம். அவை சுமார் கி. பி. 1190-ஆண்டு முதல் நார்பது வருஷங்களுக்குக் காணப்பெறுகின்றன. அதனால் ஆஸந்திக் கல்வெட்டில் குறிக்கப் பெற்றுள்ள இப்போர் கி. பி. 1190 - ஆம் ஆண்டுக்கும் இரண்டாம் பல்லாள தேவனுடைய ஆட்சியின் கடைசி ஆண்டான கி. பி. 1220-ஆம் வருஷத்துக்கும் இடைப்பட்ட காலத்தில் நடைபெற்றிருத்தல் வேண்டும்.

மாளவர்களோடு பல்லாளதேவன் போரிட்டு வெற்றி கொண்டான் என்பது அவனுடைய ஆட்சியின் வேறு சாசனங்களிலும் காணப்படுகிறது. ஹுலியேரக் குறுநில மன்னன் மஹா சாமந்தன் கோவிதேவன் மகனான பல்லேய தேவன் என்பான், “சோழரையும் கலிங்கரையும் மிதித்து, மாலவ சேனையை விழச்செய்து, நேபாள சைனியத்தை அழித்து, பாண்டியர்களைக் கொள்ளை கொண்டு துரத்தினான்” என்று புகழப்படுகிறான். (எபி. கர்நாடகா, பன்னிரண்டாம் வால்பூம், சிக்கநாயகன ஹள்ளி 17-நெ. சாசனம்).

மேலே குறித்த சாசனங்களில் காணும் கூட்டைப்பற்றி அறிந்துகொள்வதற்கு, பல்லாள தேவனுக்கும் சோழமன்னனான குலோத்துங்கனுக்கும் இடையில் இருந்த நட்பு முறையை நாம் தெரிந்துகொள்ளவேண்டியது அவசியம்.

மைசூர் ராஜ்யத்திலே ஆவணியில் பல்லாள தேவனுடைய ஆட்சிக்காலத்தைச் சார்ந்த சாசனம் ஒன்றன் ஆரம்பப்பகுதி மட்டும் கிடைத்துள்ளது. சாசனம் பூர்த்தியாக இல்லாததால் முழு விவரமும் நமக்குக் கிடைக்கவில்லை. எனினும், கிடைத்துள்ளவரையில் அது முக்கியமான விஷயத்தைத் தெரிவிக்கிறது. தமிழில் உள்ள அந்தச் சாசனம் குலோத்துங்க சோழனுடைய ஆட்சியின் பன்னிரண்டாம் ஆண்டான சகாப்தம் 1112, ஸௌம்ய வருஷம் பல்லாளதேவன் அரசுபுரிந்து வந்தான் என்பதை தெரிவிக்கிறது. இதிலிருந்து கி. பி. 1189-90-ஆம் ஆண்டு பல்லாள தேவன் மூன்றாம் குலோத்துங்க சோழனுக்கு அடங்கியவனாக ஆட்சி புரிந்தான் என்பது விளங்கும். (ஷெ. பத்தாம் வால்பூம், முளுபாகஸ் 44-b).

ஆனால் அந்நிலையிலே அவன் நீண்டகாலம் நிலைத்திருந்ததாகத் தெரியவில்லை. அடுத்த ஆண்டிலேயே அவன் ஸார்வபௌமப் பதவி வகிப்பதை எடுத்துக் காட்டுவதான விருதுகளைத் தரித்துக்கொண்டிருப்பதைக் காண்கிறோம். (எபி. கர்நாடிகா, ஏழாம் வால்பூம், சன்னகிரி 64; எட்டாம் வால்பூம், ஸோரப் 140 நெ. சாசனங்கள்; மைசூர் ஆர்க்கியலாஜிகல் ரிபோர்ட், 1913-ஆம் ஆண்டு, பக்கம் 37). தன்னுடைய பேராசுப் பதவியை எடுத்துக் காட்டுவதற்காகவே போலும் அவன் சகாப்தம் 1114, அதாவது கி. பி. 1191-92-ஆம் ஆண்டை ஆரம்ப வருஷமாகக் கொண்டு புதிய அப்தம் ஒன்றையும் நிறுவியிருக்கிறான். (மைசூர் சாசனங்கள், பக்கம் 137). இந்த நிலையை அவன் கி. பி. 1190-ஆம் ஆண்டு தேவகிரி யாதவ மன்னனான பில்லமனை ஸோரத்தூர் என்னும் இடத்தில் தோற்கடித்துப் பெரு வெற்றி கொண்டதாலேயே அடைந்தான். அந்தச் சமயம் கல்யாணபுரத்திலிருந்து அரசுபுரிந்துவந்த மேலைச் சாளுக்கியர்கள் வலிகுன்றித் தங்கள் ஆதிக்கியத்தை இழந்து வந்தனர். பழைய சாளுக்கிய ராஜ்யத்தின் பகுதிகளை, முக்கியமாக அவர்களுடைய பூர்வீகமான குந்தள தேசத்தைக் கைப்பற்றிக் கொள்வதற்கு ஆசைப்பட்டு வடக்கிலிருந்து யாதவர்கள் என்னும் சேஷணர்களும் தெற்கிலிருந்து ஹொய்சளர்களும் முயன்றனர். யாதவர்களுக்கு இடம் கொடுக்காமல் பல்லாள தேவன் வெற்றி கொண்டான். அந்தப் போர் முடிவில் பில்லமனும் இறந்துபோனான். எனினும், பில்லமனுக்குப் பின் சிங்காதனம் ஏறிய அவன் மகன் ஜைத்ரபாலன் தன் தந்தைக்கு நேர்ந்த இழுக்கை மாற்றிப் பல்லாளன் மீது போர் தொடுத்து வெற்றி கொண்டான். குந்தள தேசத்தின் வட பகுதி அவன் வசமாயிற்று. இந்த ஜைத்ரபாலன் சோழ மன்னனான மூன்றாம் குலோத்துங்கனோடு நட்புக்கொண்டிருந்தான் என்பதையும், அவர்கள் இருவரும் சேர்ந்து கி.பி. 1195-ஆம் ஆண்டில் காகதீய நாட்டைத் தாக்கி வெற்றி கொண்டார்கள் என்பதையும் நாம் முன்னரே கண்டோம். ஹொய்சள சாசனங்களிலே, 'பல்லாள தேவனுடைய வீரத்தின் தீப்பிழம்புகளால் சோளிகதேசம் கரியாகியது' என்று குறிக்கப்பட்டுள்ளது. (எபி. கர்நாடிகா, ஐந்தாம் வால்பூம், சென்னராய பட்டணம், 220-நெ. சாசனம்).

மேலே குறிப்பிட்ட ஹூலியேரச் சிற்றரசன் பல்லேயனுடைய சாசனத்திலிருந்து இந்தச் சண்டையிலே கலிங்கர்களும் ஈடுபட்டிருந்தனர் என்று தெரிகிறது. முதலாம் இராஜராஜ சோழன் ஆட்சிக் காலத்திலே சோழர்கள் ஸாம்ராஜ்யமோகம் கொண்டு தங்கள் ஆதிக்கியத்தைப் பரப்ப ஆரம்பித்த நாளிலிருந்து கலிங்கதேசம் சோழ ஸாம்ராஜ்யத்தில் அடங்கிய பகுதியாக இருந்து வந்திருக்கிறது. நடுநடுவே சிற்சில சமயங்களில் அவர்கள் தனியரசாக விளங்க முயன்றது நீடித்துப் பயன் அளிக்கவில்லை. முதற் குலோத்துங்கன் அங்கே தன் ஆதிக்கியத்தை நிலை நிறுத்தியதோடு அல்லாமல் அந்நாட்டு நிர்வாகத்தையும் தன் பிடிப்பிலே கொள்ள முயன்றிருக்கிறான். அதிலிருந்து கலிங்கதேசத்துச் சரித்திரத்தின் போக்கிலே ஒரு மாறுதல் ஏற்பட்டிருக்கிறது. முதற் குலோத்துங்கனுக்குவிரோதமாக விஜயாதித்தியனுக்கு உதவிசெய்த கலிங்க நாட்டு மன்னன் இராஜராஜ தேவேந்திரவர்மனுடைய மகன் அனந்த வர்மன் என்பான் சோடகங்கள் என்னும் விருதைத் தரித்துவந்தான். அவனுடைய சொந்தப் பெயரைக் காட்டிலும் இந்த விருதே பிரபலமானதாக விளங்கியிருக்கிறது. அதே சமயம் முதற் குலோத்துங்கனுடைய பிள்ளைகளுள் ஒருவனான இராஜராஜனும் சோடகங்கள் என்னும் விருதைத் தரித்து வந்திருக்கிறான். அனந்தவர்மன் சிறுவனாக இருந்த காலத்தில் இராஜராஜ சோடகங்கள் கலிங்க தேசத்திலே சோழர்களுடைய பிரதிநிதியாக இருந்து அந்நாட்டு அரசியலை நிர்வகித்துவந்தான் போலும். அதுமுதல் இரண்டு நாடுகளுக்கும் இடையில் நெருங்கிய தொடர்பு இருந்திருக்கிறது.

பாண்டியர்களிடையே தாயாதிச் சண்டை நடந்த காலத்தில் இலங்காபுர தண்டநாதனுக்கு எதிராகச் சோழர்களுடைய ஆதரவோடு குலசேகர பாண்டியன் பக்கத்தில் நின்று போர் புரிந்தவர்களிலே சோழகங்கள் என்பவனும் ஒருவன் என்று மகாவமிசம் கூறுகிறது. (ஸ்ரீ கே. வி. சுப்பிரமணிய ஜயர் எழுதிய தக்காணத்தின் பழைய சரித்திரம், பக்கம் 156). இதற்குப் பிறகு சோடகங்கள் என்பான் ஒருவனும் அணிகங்கள் (அணியங்கள்) என்பான் ஒருவனும் தமிழர்களுடைய சேனையின் உதவிகொண்டு இலங்கை நாட்டைக் கைக் கொண்டு சிறிதுகாலம் ஆண்டு வந்திருக்கிறார்கள். அணிகங்கனுடைய



இலங்கைப் படைமெடுப்பு அந்நாட்டை ஆண்டு வந்த கல்யாண வதி என்னும் அரசியின் ஆட்சியிலே எட்டாம் ஆண்டு நடைபெற்றதாம். அந்நாட்டிலே கிடைக்கும் ஒரு கல்வெட்டிலே இந்தப் படையெடுப்பு பின்வருமாறு வருணிக்கப்பட்டுள்ளது : “தமிழர்களின் பெருங்கூட்டம் இந்த இலங்கையில் வந்து இறங்கி, ஆதி என்னும் மந்திரியை நிர்மூலமாக்கி, மலையரண்கள், காட்டு அரசன்கள் எல்லாவற்றையும் பொருட்படுத்தாமல், யுகத்தின் முடிவில் தோன்றும் பிரளயாக்கினிபோல இலங்கை முழுவதும் பரவிச் சமூக அமைப்பு, சமயநிலை ஆகிய எல்லாவற்றையும் அழித்துவிட்டது.” (எபி. ஸைலானிகா, ஐந்தாம் வால்யூம், பக்கம் 120). இந்தச் சம்பவம் கி.பி. 1210-ஆம் ஆண்டு நிகழ்ந்த தென்று இலங்கைச் சரித்திர ஆசிரியர்கள் கூறுவர். அப்போது மூன்றாம் குலோத்துங்கன் சோழமன்னனாக இருந்தான். ஆகவே அவனுடைய தீவிரமான உதவியுடனேதான் இந்தப் படையெடுப்பு நிகழ்ந்திருத்தல் வேண்டும்.

பழைய புதுக்கோட்டை ஸம்ஸ்தானத்தில் உள்ள பெருமானாடு என்னும் இடத்திலிருந்து பாண்டிய மன்னனான திரிபுவன சக்கரவர்த்திகள் சுந்தரபாண்டிய தேவனுடைய ஆட்சியின் பத்தாம் ஆண்டு கொண்ட சாசனம் ஒன்று கிடைத்துள்ளது. அது ஸ்ரீமது மஹா ப்ரதானி மண்டலிக முராரி அணியெக [கெ] த்தய தண்டநாயகன் என்பான் அவ்வூர்க்கோயில் நித்த நிவந்தங்களுக்குப் பொன் அளித்து, விளக்கெரிக்க நெய் அட்டுவதற்கு ஏற்பாடு செய்த விவரத்தைத் தெரிவிக்கின்றது. (புதுக்கோட்டை, ஸம்ஸ்தானக் கல்வெட்டுகள், 518 நெ. சாசனம்). அது ‘தம் பிராட்டியார் திருக்கைமலரிலே நீர்வார்த்து’ அளிக்கப் பெற்றதென்று கூறுகிறது அந்தச் சாசனம். அதனால் அவ்விதம் தானம் செய்தவன் ஓர் அரச குடும்பத்தைச் சேர்ந்தவன் என்பதும், அவன் தன்னுடைய அரசுப் பதவியை அப்போது வகித்து வந்தான் என்பதும் தெரியவரும். சாசனத்திலே அவன் பெயர் குறிக்கப் பெறும் முறையும் இதையே வலியுறுத்துகிறது. இந்த அரசனுடைய பெயர் அந்த ஸம்ஸ்தானத்திலே கிடைத்துள்ள வேறு இரண்டு சாசனங்களிலும் காணப் பெறுகிறது. பேரையூரிலிருந்து கிடைத்த ஒன்றில் அவன் பெயர் ஸ்ரீமது மஹா சாகனி மெய்சத்ருகண்டன் சாமந்தன் என்றும், (மே. 193-நெ,

சாசனம்) மேலத்தானையத்திலிருந்து கிடைக்கும் மற்றொன்றில் ஸ்ரீமது மஹாச்ராகயானி மண்டலிகமுரா.....ய தண்ணயகன் என்றும் (199-நெ. சாசனம்) காணப்படுகிறது. அந்தப் பெயர் 'ஸ்ரீமந் மஹாப்ரதானி மண்டலிக முராரி அணியங்க ராகுத்தராய தண்டநாயகன்' என்றே இருத்தல் வேண்டும் போலும். அணியங்கன் என்பது கலிங்கமன்னன் பெயராகும். இலங்கைத் தீவிலே திரிகோணமலையிலிருந்து கிடைத்துள்ள ஒரு சாசனத்தில் காணும் வடமொழிச் சுவோகத்தின் குறைப் பகுதியிலிருந்து சோடகங்கன் என்பான் ஒருவன் அந்தத் தீவிலே தன் படைகளுடன் வந்திறங்கிய தேதி தெரியவருகிறது. (எபி. ஸைலாநிகா, ஐந்தாம் வால்பூம், 14-நெ. சாசனம்). அந்நாள் கி. பி. 1223-ஆம் ஆண்டு ஏப்ரல் மாதம் பதினான்காம் தேதியாகும். இவற்றைக் கவனிக்கும் போது கலிங்க மன்னர்கள் தமிழ்நாட்டோடு, முக்கியமாகச் சோழ மன்னர்களோடு, அந்நாளிலே நெருங்கிய தொடர்பு கொண்டிருந்தது விளங்கும்.

மேலே குறிப்பிட்ட ஆஸந்திக் கல்வெட்டில் பல்லாளனுக்கு விரோதமாகச் சேர்ந்திருந்தவர்கள் கூட்டைப்பற்றிக் கூறப்பட்டிருப்பதிலே ஒரு முக்கியமான விஷயத்தையும் நாம் கவனிக்கவேண்டும். சோழ மன்னனோடு மாளவ, லாட, கூர்ஜ்ஜுர தேசத்து அரசர்களும் ஒன்றாகச் சேர்ந்திருந்தார்கள் என்று காணப்படுகிறது. ஆனால் அந்நாளிலே அவர்களுடைய ஆட்சிப் பிரதேசங்கள் சோழ நாட்டோடு ஒட்டியனவாக இல்லை. இடைப்பட்ட பகுதியிலே தேவகிரியைத் தலைநகராகக் கொண்ட யாதவர் எனப்படும் சேவுணர்களும், வாரங்கலைத் தலைநகராகக் கொண்ட காகதீயர்களும் ஆண்டு வந்திருக்கிறார்கள். மாளவ, லாட, கூர்ஜ்ஜுர தேச மன்னர்கள் இவ்விரு தேசங்களையும் கடக்காமலும் அந்நாட்டுமன்னர்களான சேவுணர்களுடனோ, காகதீயர்களுடனோ பொருதாமலும் சோழ மன்னனோடு கூட்டுச் சேரவோ அவனுடன் கூடி ஹொய்சளர் நாட்டைத் தாக்கவோ அந்நாளில் சாத்தியமில்லை. ஆனால் அவ்விருநாட்டு மன்னர்களின் பெயர்கள் இந்தச் சாசனத்தில் காணப்பெறவில்லை.

ஹொய்சள மன்னனான இரண்டாம் பல்லாள தேவன் கலிங்கர்கள் மீது வெற்றிகொண்டான் என்று கூறப்படுவது போலவே அவன் மகன் ஸீரநரசிம்ஹனும் புகழப்படுகிறான்.

(எபி. கர்நாடிகா, ஐந்தாம் வால்பூம், சென்னராய பட்டணம் 203-நெ.சாசனம்). இரண்டும் தனித்தனியான வெற்றிகளைக் குறிப்பனவா அல்லது ஒரே வெற்றிதான வெண்பது தெரியாது. எனினும், இரண்டும் ஒரே வெற்றியைக் குறிக்கின்றனவாகக் கொள்ளலாம். அவ்விதமாயின், அந்த வெற்றி இரண்டாம் பல்லாள தேவனுடைய ஆட்சியின் கடைசி ஆண்டுகளிலே தந்தையும் மகனும் சேர்ந்து போரிட்டு அடைந்ததாகவே இருத்தல்வேண்டும்.

பெரு வெற்றிகள் பலவற்றைக் கண்ட மூன்றாம் குலோத்துங்கனுடைய ஆட்சி கடைசியிலே பெருத்த ஆபத்துக்கு உள்ளாகி நிலைகுலைய நேரிட்டதென்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். கி.பி. 1216-ஆம் ஆண்டில் மதுரைச் சிங்காதனம் ஏறிய மாறவர்மன் சுந்தர பாண்டியன் தன் நாட்டைச் சோழர்களுடைய ஆதிக்கத்திலிருந்து மீட்டுக் கொண்டதோடு நில்லாமல் சோழநாட்டின் மீதும் படையெடுத்துச் சென்று ஒரு காலத்தில் பேரரசு செலுத்திய மன்னனையும் வெற்றிகொண்டு வாகை குடினான். இது அவனுடைய மெய்க்கீர்த்தியிலே விவரமாகக் காணப்படுகிறது. (எபி. இந்திகா, இருபத்திரண்டாம் வால்பூம், 42-ஆம் பக்கம் முதல்).

‘பொன்னிசூழ் நாட்டிற் புலியாணை போயகல’ அவன் சோழநாட்டைக் கைக்கொண்டு, ‘தஞ்சையும் உறந்தையும் செந்தழல் கொளுத்தி’னான். ‘கூடமும் மாமதிலும் கோபுரமும் ஆடரங்கும் மாடமும் மாளிகையும் மண்டபமும் பலவிடித்’ தான். ‘செம்பியனைச் சினமிரியப் பொருது, சுரம்புக வோட்டிப் பைம்பொன் முடிபறித்துப் பாணருக்குக் கொடுத்தருளி’னான். ‘ஆடகப் புரிசை ஆயிரத்தளியிற் சோழவளவன் அபிஷேக மண்டபத்து வீராபிஷேகம் செய்து’ கொண்டான். தெய்வப் புலியூரை அடைந்து பொன்னம்பலத்தில் ஆடுவாரை வணங்கிப் பொன்னமராவதி திரும்பி, ‘சோலைமலிபழனச் சோனாடும் தான் இழந்த மாலை முடியும் தர வருக’ என்று சோழனை அழைத்தான். ‘மானநிலை குலையச் சக்கர)வாள்கிரிக்கப்புறத்துப் போன வளவன் உரிமையோடும் புகுந்து பெற்ற புதல்வனை நின் பேர் என்று முன்காட்டித்’ தொழுதான். பாண்டியன் அவனுக்குப் ‘பண்டிழந்தசோளபதி என்னும் நாமமும் தொன்னகரும் மீள வழங்கித்’ திருமுகமும் கொடுத்தான்.

இவ்விதம் மெய்க் கீர்த்தியில் புகழ்ந்து கூறப்பெற்ற சம்பவங்கள் வேறு சில கல்வெட்டுக்களிலும் குறிக்கப்பட்டு உறுதிபெறுகின்றன. முன்னாளிலே கடிய லூர் உருத்திரங் கண்ணனார் என்னும் புலவர் சோழன்மீது பாடிய பட்டினப் பாலை அரங்கேற்றப்பட்ட பதினாறுகால் மண்டபம் ஒன்றைத் தவிர, சோழன் அரண்மனை முழுதும் சுந்தரபாண்டியனால் இடிக்கப் பெற்றது என்னும் செய்தியைத் திருச்சிராப்பள்ளி ஜில்லா திருவெள்ளறையில் காணும் சாசனப் பாடல் ஒன்று தெரிவிக்கிறது. (1939-ஆம் ஆண்டு 197-நெ. சாசனம்). வீர மாகதன் (அதாவது மகதநாட்டு மன்னன்) என்று குறிக்கப் பட்டுள்ள பாணபதிக்குச் சோழநாட்டைப் பாண்டியன் வழங்கிய செய்தி ஸ்ரீரங்கத்துக்குப் பக்கத்தில் உள்ள திருவாணைக் காவிலிருந்து கிடைக்கும் இரண்டு சாசனங்களில் காணப்படுகிறது. (1908 - ஆம் ஆண்டு 481, 482 - நெ. சாசனங்கள்.) ஸ்ரீரங்கத்திலிருந்து கிடைக்கும் கல்வெட்டு ஒன்றே பாண்டியன் காவிரிநாட்டை வளவனுக்கும் மாகதர்கோனுக்கும் (அதாவது மகதநாட்டுப் பாணனுக்கும்) பிரித்து வழங்கியதைக் கூறுகிறது. (1939-ஆம் ஆண்டு 196-நெ. சாசனம்.) மூன்றாம் குலோத்துங்கனுடைய ஆட்சியின் கடைசி இரண்டு, அதாவது முப்பத்தொன்பது, நாற்பதாம் வருஷத்துச் சாசனங்கள் வட ஆர்க்காடு, தென் ஆர்க்காடு, செங்கற்பட்டு ஜில்லாக்களில் கிடைக்கவில்லை யென்பதையும், காவிரி நாட்டில் மட்டுமே தான் கிடைக்கின்றன வென்பதையும் நாம் கவனித்துப் பார்த்தால், சோழநாடு அப்போது இரண்டாகப் பிரிக்கப்பட்டு ஒரு பகுதி சோழனுக்கும் மற்றொரு பகுதி பாண அரசனுக்கும் கொடுக்கப்பட்டிருந்ததென்பதும் உறுதியாகும்.

சுந்தரபாண்டியன் தன்னுடைய ஆட்சியின் மூன்றாம் ஆண்டிலிருந்தே சோண்டு வழங்கியருளிய என்னும் வீருதைத் தரித்து வந்திருக்கிறான். (1928-ஆம் ஆண்டு 322-நெ. சாசனம்; புதுக்கோட்டை ஸம்ஸ்தானத்துச் சாசனங்கள், 249-நெ. சாசனமும் பார்க்க). அவனுடைய ஆட்சியின் பதினைந்தாம் ஆண்டு கொண்ட மற்றொரு சாசனம் (1926-ஆம் ஆண்டு 9-நெ. கொண்டது) அவன் குலோத்துங்க சோழனுக்கு மணிமுடியையும் முடிகொண்ட சோழபுரம் (அதாவது இராஜராஜபுரம் என்ற பெயர்பெற்று அந்நாளில் தலைநகராக விளங்கிய பழையாறை) என்னும் நகரத்தையும் வழங்கினான் என்று கூறுகிறது.

சுந்தர பாண்டியன் இவ்வெற்றிகளைக் கி. பி. 1216-ஆம் ஆண்டில் மதுரைச் சிங்காதனம் ஏறியதன்பின் சிறிதுகாலத்துக்குள்ளாகவே அடைந்திருத்தல் வேண்டும்.

‘நின் பேர்’ என்று பாண்டியனிடம் குலோத்துங்கன் அளித்த இராஜகுமாரன் யார் என்பது தெரியவில்லை. மெய்க்கீர்த்தியின் வாசகத்திலிருந்து அந்த இராஜகுமாரனும் சுந்தரன் என்ற பெயர் தாங்கி யிருந்தான் எனக் கொள்ளலாம். ஆயினும், அந்தப் பெயர் கொண்ட சோழ மன்னனோ அரசிளங்குமரனோ அப்போது யாரும் இருந்ததாகத் தெரியவில்லை. மூன்றாம் குலோத்துங்கனுக்குப் பின் சோழ சிங்காதனத்தில் அமர்ந்தவன் மூன்றாம் இராஜராஜன் ஆவன். அவர்கள் இருவருக்கும் உள்ள உறவுமுறை என்னவென்பது நிச்சயமாகத் தெரியாது. எனினும், மூன்றாம் இராஜராஜனை அவனுக்கு முன் இருந்த குலோத்துங்கனுடைய மகன் என்றே ஆராய்ச்சியாளர் பொதுவாகக் கொள்வர்.

மூன்றாம் இராஜராஜன் சோழ சிங்காதனம் ஏறியது கி. பி. 1216-ஆம் ஆண்டில் ஜூன் மாதம் இருபத்தேழாம் தேதிக்கும் ஜூலை மாதம் பத்தாம் தேதிக்கும் இடைப்பட்ட நாள் ஒன்றாகும் எனக் கணக்கிட்டிருக்கிறார்கள். (எபி. இந்திகா, எட்டாம் வால்யூம், 260-பக்கம்; இன்னும், 1943-ஆம் வருஷத்து 160-௨௬. சாசனம் அவனுடைய ஆட்சியின் இருபத்துநான்காம் ஆண்டும் சகாப்தம் 1162, அதாவது கி. பி. 1240-ஆம் ஆண்டும் கொண்டிருப்பது கவனிக்கத்தக்கது). அதே வருஷம் தான் சுந்தரபாண்டியனும் மதுரைச் சிங்காதனம் ஏறினான். அதற்குப் பிறகே சுந்தரபாண்டியன் சோழநாட்டின் மீது படையெடுத்து வந்து அதைக் கைப்பற்றியதாகும். குலோத்துங்கனுடைய குமாரனாக இராஜராஜன் இருந்திருப்பானாகில், குலோத்துங்கனால் ‘நின் பேர்’ என்று சுந்தரபாண்டியன் மூன்றாம் கொணர்ந்து நிறுத்தப் பெற்ற அவன் குமாரன் இராஜராஜனாகவே இருத்தல் வேண்டும். ஆகவே குலோத்துங்கனுக்குப் பாண்டிய மன்னனால் திருப்பி அளிக்கப்பெற்ற சோழநாட்டைப் பெற்று அனுபவித்தவனும் அந்த இராஜராஜனாகவே இருத்தல் வேண்டும்.

எனினும், ஹொய்சள சாசனங்களிலிருந்து மூன்றாம் இராஜராஜன் சோழ சிங்காதனத்திலே ஹொய்சள மன்னர்

களான இரண்டாம் பல்லாள தேவன், அவன் மகன் வீர நரஸிம்ஹன் ஆகிய இருவர்களாலும் அமர்த்தப்பட்டவன் என்று தெரிகிறது. கி. பி. 1218-ஆம் ஆண்டு கொண்ட ஒரு சாசனத்திலே பல்லாளன் சோள ராஜ்ய ப்ரதிஷ்டாசாரியம், பாண்டிய கஜகேசரி என்ற விருதுகளைத் தரித்திருப்பதைக் காண்கிறோம். (எபி. கர்நாடிகா, நான்காம் வால்பூம், நெலமங்கலம் 29-நெ. சாசனம்). அதே சாசனத்தில் அவன் மகன் நரஸிம்ஹன் சோளகுல ஏகரக்ஷகன் மகதோர்வீபால நிர்மூலகன் (அதாவது மகதை மண்டலத்து அரசனான பாணனை நிர்மூலமாக்கினவன்) என்றும் புகழப்படுகின்றான். அதிலிருந்து அந்த ஆண்டின் ஆரம்பத்திலேயே பல்லாளன் இந்த விருதுகளைத் தரித்திருத்தல் வேண்டும் என்பது புலனாகும். மற்றொரு சாசனத்திலே பல்லாளன் உயிருடன் இருந்த காலத்திலேயே அவன் மகன் வீர நரஸிம்ஹன் தெற்கே ஸ்ரீரங்கத்தின்மீது படை நடத்திவந்த செய்தி காணப்படுகிறது. (ஹெராய்சன ஸ்ரீ வீர வல்லாளதேவன் மகம் வீர நரஸிம்ஹதேவனு தெங்கலுரங்கன் மேலே நடவந்து - எபி. கர்நாடிகா, ஆறாம் வால்பூம், சிம்மகநூர் 56-நெ. சாசனம்). கன்னடமொழியிலே இயற்றப்பெற்ற சம்பூகாவியமான ஜகந்நாத லீஜயம் என்னும் நூலிலே பல்லாள தேவனால் உதவி செய்யப் பெற்றுச் சோழ சிங்காதனத்திலே அமர்த்தப்பெற்றவன் இராஜராஜனே யாவான் என்று தெளிவாகக் கூறப்பட்டுள்ளது. (ராஜராஜ ப்ரதிஷ்டா நிரத்தம் - ஜர்னல் ஆப் இந்தியன் ஹிஸ்டரி, ஆறாம் வால்பூம், பக்கம்-200). இவற்றிலிருந்து இரண்டாம் பல்லாள தேவன் பாண்டிய மன்னனையும் பாணர் அரசனையும் போரில் வெற்றிகொண்டு இராஜராஜனைச் சோழசிங்காதனத்தில் அமர்த்தினான் என்று நாம் கொள்ளலாம். குலோத்துங்கனுடைய பெயர் ஓர் இடத்திலும் பிரஸ்தாபிக்கப் பெறவில்லை யென்பதும் கவனிக்கத்தக்கது.

ஹெராய்சன சாசனங்களில் கூறப்பட்டுள்ள சம்பவங்களைக் கவனித்தால், சுந்தரபாண்டியன் குலோத்துங்கனுக்கும் அவன் மகனுக்கும் சோழநாட்டைத் திரும்பவும் வழங்கியதாகப் பாண்டிய மெய்க்கீர்த்திகளில் காணும் சம்பவங்களாகத் தோன்றவில்லை; அவற்றினின்றும் வேறான ஒரு சம்பவத்தையே குறிப்பதாகத் தோற்றுகின்றது. இது மற்றோர் ஆதாரத்தாலும் உறுதியாவதாகக் கொள்ளலாம். மூன்றாம் இராஜராஜ சோழ

னுடைய ஆட்சியின் ஐந்தாம் ஆண்டிலே தஞ்சை ஜில்லாப் பகுதியில் பெருத்த கலவரங்கள் நடந்து நிலைமை சீர்குலைந்து விட்டதாகத் தெரிகிறது. திருவிளக்குடியிலிருந்து கிடைக்கும் அவனுடைய ஆட்சியின் பதினொன்றாம் ஆண்டுக்கு எதிராமாண்டு கொண்ட ஒரு கல்வெட்டிலிருந்து, இராஜராஜ சோழனுடைய ஆட்சியின் ஐந்தாம் ஆண்டிலே நடந்த கலவரத்தில் திருவேள் விக்குடிக் கோயிலின் விக்ரகங்களை வாணகோவரையர் பரிவாரத்தார் எடுத்துச் சென்று திருச்சத்திமுற்றம் கோயிலிலே வைத்துச்சென்றார்கள் என்றும், பின்னால் அவ்விக்ரகங்களைத் திருவேள்விக்குடிக் கிராமத்தவர் தேடிக் கண்டுபிடித்துப் பணம் கொடுத்து மீட்டு வந்து தங்கள் கோயிலிலே பழையபடி பிரதிஷ்டை செய்யவேண்டி நேர்ந்தது என்றும் தெரிகிறது. (1926-ஆம் ஆண்டு 141-நெ. சாசனம்) ஆண்டு குறிக்கப்பெறாமல் உடையாளுரிலிருந்து கிடைக்கும் மற்றொரு கல்வெட்டிலிருந்து அம்மன்னன் ஆட்சியின் ஐந்தாம் ஆண்டில் நிலவிய கேஷாபத்திலே நிலங்களில் மூலபத்திரங்கள் அழிந்துபோனமையால் நான்காம் ஆண்டளவில் உள்ள அனுபோக முறைப் படி நிர்ணயிக்கப்பட வேண்டியதாயிற்று என்பது விளங்குகிறது. (1927-ஆம் ஆண்டு 309-நெ. சாசனம்). பத்தொன்பதாம் ஆண்டுகொண்டதாகத் தலைச்சங்காட்டிலிருந்து கிடைக்கும் வேறொரு கல்வெட்டு அம்மன்னனுடைய ஆட்சியின் ஐந்தாம் ஆண்டிலே நாட்டில் நடந்த துரிதங்களிலே பழைய கணக்குகள் அழிந்துபோனமையால், அனுபோகப் பற்றொழுக்கை யொட்டி ஆதரவுச் சீட்டுகளைப் புதுப்பிக்கவேண்டியிருந்தது என்னும் செய்தியைத் தெரிவிக்கிறது. (1925-ஆம் ஆண்டு 213-நெ. சாசனம்).

இவற்றைக் கவனித்தால் இக்கலவரங்கள் ஹொய்சள் வேந்தர்களால் இராஜராஜன் சோழ சிங்காதனத்தில் அமர்த்தப் பெற்றதை ஒட்டியே நடந்திருத்தல் வேண்டும் என்பதும், அவற்றிலே பாண அரசனும் சம்பந்தப்பட்டிருந்தான் என்பதும் தெரியவரும். தான் முன்பு பாண்டியனிடமிருந்து பெற்ற சோழநாட்டுப் பகுதியைத் திரும்பவும் மீட்டுக் கொள்வதற்காகப் பாணன் செய்த இம்முயற்சியிலே பாண்டியனும் ஹொய்சளர்களுக்கு எதிராகப் பாணனுக்கு உதவியிருத்தல் கூடும். இந்தக் காலத்திலே ஹொய்சள் ராஜமீறன் முதலில் வடக்கே



சேவுணர்களோடு போரிட்டு வெற்றிகொண்டு, அப்பால் தெற்கே திரும்பி அதியமன், சேரன், பாண்டியன், மகரன் (மகதை மண்டலத்து வேந்தனான பாணன்), பலம்பொருந்திய காடவன் ஆகியவர்களைக் கைப்பற்றிச் சோழமன்னனைச் சிங்காதனத்தில் இருத்தினான் என்று கல்வெட்டுகளிலே புகழப் படுகிறான். (எபி. கர்நாடிகா, ஐந்தாம் வால்பூம், சென்னையப் பட்டணம் 203-நெ, பேலூர் 74-நெ. சாசனங்கள்). மூன்றாம் இராஜராஜன் இப்போது நாம் கொண்டுள்ளபடி மூன்றாம் குலோத்துங்கன் மகதை இருந்து, சுந்தரபாண்டியன் வழங்கிய சோழநாட்டை ஏற்றுக்கொண்டவனாக இருப்பானாகில் சம்பவங்கள் மேலே குறித்தபடி நடந்திருக்கா. ஆகவே 'நின்பேர்' என்று சுந்தரபாண்டியனிடம் குலோத்துங்கன் அளித்த அரசிளங்குமரனின்றும் இராஜராஜன் வேறுவனாகவே இருத்தல் வேண்டும். குலோத்துங்கனால் சோழநாட்டிலிருந்து தூரத்தப்பட்ட இரண்டாம் இராஜாதிராஜனுடைய கிளையைச் சேர்த்தவர்களுள் ஒருவனாக அவன் இருக்கலாம்.

மூன்றாம் குலோத்துங்கனால் விரட்டியடிக்கப்பட்ட இராஜாதிராஜன் தமிழ்நாட்டைத் துறந்து வடக்கே சென்று வேங்கி நாட்டில் தங்கியவன் சற்றேறக்குறையக் குலோத்துங்கன் ஆட்சிக் காலம் முழுவதும் அங்கே இருந்துவந்தான் என்பதையும் நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். அவனுடைய ஆட்சியின் நாற்பத்தொன்பதாம் ஆண்டுக்குச் சரியான சகாப்தம் 1137, அதாவது கி. பி. 1215-16-ஆம் ஆண்டு கொண்ட சாசனமும் கிடைத்துள்ளது. (தே. இ. சாசனங்கள், நான்காம் வால்பூம், 1330-நெ. சாசனம்). அது குலோத்துங்கன் ஆட்சியின் கடைசிக் காலமாகும். அதற்குப் பிறகு இரண்டாம் இராஜாதிராஜன் எவ்வளவு காலம் அரசுபுரிந்தான் என்பது தெரியாது. ஆயினும் அடுத்த ஆண்டான சகாப்தம் 1138, அதாவது கி. பி. 1216-17-ஆம் வருஷத்திலிருந்து அதே பெயர் கொண்டு திரிபுவன சக்கரவர்த்தி (மூன்றாம்) இராஜாதிராஜன் என்பான் ஒருவன் வேங்கியிலே அரசனாக இருந்துவந்திருக்கிறான். அவனுடைய ஆட்சியின் எழுபத்தாராம் ஆண்டான சகாப்தம் 1215 (அல்லது கி. பி. 1293) வரைக்கும் அவனுடைய சாசனங்கள் கிடைக்கின்றன.



திராசுாராமத்திலிருந்து கிடைத்தனவாகத் தேன் இந்திய சாசனங்களில் நான்காம் வால்பூயில் வெளியாகியுள்ள அவனுடைய சாசனங்கள் பின்வருமாறு :

சாசன எண் ஆட்சி வருஷம் சகாப்தம் கி. பி. ஆண்டு

1043	36	1174	1252-53
1178	36	1174	1252-53
1045	36	1175	1253-54
1371	37	1175	1253-54
1033	37	1175	1253-54
1230	38	1176	1254-55
1032-A	43	1180	1258-59
1163	50	1188	1266-67
1373	59	1197	1275-76
1152	62	1200	1278-79
1019	72	121*	1289 ?
1038	72	1211	1289-90
1307	76	1215	1293-94

அவனுடைய ஆட்சியின் கடைசிக் காலத்திலே தமிழ் நாட்டில் சோழர்களுடைய ஆட்சி நிலை குலைந்துவிட்டது. அவர்களுடைய தனியரசு போய்விட்டது. தமிழ்நாட்டுச் சோழர்களிலே கடைசி வேந்தனான மூன்றாம் இராஜேந்திரனுடைய ஆட்சியில் கடைசியாக நமக்குக் கிடைக்கும் சாசனம் கி. பி. 1279-ஆம் வருஷத்துக்குச் சரியான அவனுடைய ஆட்சியின் முப்பத்து மூன்றாம் ஆண்டு கொண்டதாகும். (1901-ஆம் வருஷத்து 492-நெ. சாசனம்). அதற்குப் பிறகு அவன் எவ்வளவு காலம் அரசு புரிந்தான் என்பதும், அவனுக்குப் பின் யார் சோழ சிங்காதனம் ஏறினான் என்பதும் தெரியாது. ஆயினும், அதற்குப் பிறகும் சுமார் பதினைந்து ஆண்டுகள் சோழ வம்சம் தெலுங்கு நாட்டிலே நிலைத்திருந்த தென்பது தெளிவாகிறது. அந்த இராஜாதி ராஜனுடைய சாசனங்கள் சிலவற்றிலே காகதீய மன்னன் ருத்திரதேவன், அவன் அதிகாரிகள் முதலியோர் தானம் வழங்கிய செய்தியும் காணப்படுகிறது.

தமிழ்நாட்டிலே சோழர்களுடைய ஆதிக்கம் நிலைகுலைய ஆரம்பித்தது முதல் விஜயநகர ஸாம்ராஜ்யத்தின் நிர்வாகம் ஸ்திரமாக ஊன்றிய காலம் வரையில் உள்ள இடைக் காலத்தின் சரித்திரம் நன்றாக ஆராயப் பெறவில்லை. அதை ஆராய்ந்தால் பல புதிய விஷயங்கள் தெரியவரும். விரிவாகவும் ஆராய வேண்டும். ஏற்கெனவே இந்த ஆராய்ச்சிப் பகுதி மிகவும் நீண்டுவிட்டது. ஆகவே இதை வேறொரு சந்தர்ப்பத்தில் தான் செய்யவேண்டும். இதன் முதற்பகுதியிலே கொங்கு நாட்டு மன்னர்களுள் சரித்திரத்தை இவ்விடம் கொடுப்பதாகக் குறிப்பிட்டிருந்தோம். இடமின்மை காரணமாக அதையும் வேறொரு சந்தர்ப்பத்திலே தான் ஆராயவேண்டும்.

# பொருட்குறிப்பகராதி

—(0)—

அ

அகஸ்தியர் 123  
அக்ரிசுண்டம் 94  
அக்ரதனுஜன் 114  
அங்க தேசம் 35, 37, 122  
அசுவபதி (விருது) 20, 21, 22,  
107  
அசுவமேத யாகம் 15  
அணஹிலபாடக நகரம் 35, 57, 60,  
111, 112  
அணை 140  
அதிராஜேந்திரன் 76, 77, 85, 86,  
87, 89, 90, 92, 93, 95, 101,  
119, 120  
அத்புத மண்டலம் 113  
அனந்தவர்மன் சோடகங்கன் 90  
அனந்தன் 49  
அநபாயன் 140  
அநுராதபுரம் 119, 121, 175  
அந்தர்வேதி (கங்கா யமுனாப் பிர  
தேசம்) 94  
அபயன் 101  
அபிமன்பு 83  
அமரகோசம் 10  
அமர புஜங்கப் பல்லவரையன் 163  
அம்மகாம 68  
அம்மங்க தேவி 79  
அம்மராயன் 23  
அயோத்தி 52, 54, 55, 108  
அய்யாவழி (அய்யபொழில்) 95  
அரபுக் கடல் 21  
அராஜகம் 77, 85, 101, 102

Y

அரிந்தமச் சக்கரவர்த்தி 94  
அருளப்பாடு 131  
அரையன் இராஜராஜன் விக்ரம  
சோழச் சோழிய வரையன் 79  
அரையன் சிறியனான வேந்த சூளா  
மணிப் பல்லவரையன் 163  
அர்ணோராஜன் 112, 113  
அர்ஜுனவர்மன் 46  
அர்ஜுனன் 83  
அலெக்சாண்டர் 34  
அல்லஹாபாத் 44  
அல்லஹணதேவி 71  
அவந்தி (உஜ்ஜயினி) 35  
அழகர்கோயில் 164  
அழகிய சோழத் தெரிந்த வலங்கை  
வேளைக்காரப் படைகள் 94  
அறச்சாலை (போஜன சாலை) 2  
அனந்தபாலன் 32  
அனந்தபுரம் (திருவனந்தபுரம்) 13  
அனந்தபுரவர்ணனம் (நூல்) 13  
அனந்தபூர் ஜில்லா 67, 79  
அனந்தவர்மன் (கலிங்க மன்னன்) 3  
அஜ்மீர் 52  
அஹத்தூஹம் 41  
அஹமத் நியாஸ்திகின் 37

ஆ

ஆக்ரா 108  
ஆதி சுல்தான் முல்க் 115  
ஆதிநகர் 29  
ஆந்திர மஹாபாரதம் 82  
ஆந்திரம் 128, 173

ஆப்கானிஸ்தான் 25  
ஆயிரத் தெழுநூற்றுவன் திருமண்  
டபம் 155  
ஆய்குலம் 17, 18  
ஆர்யதேசம் 125  
ஆலவட்டக் குடை 165  
ஆழ்வார் 164  
ஆளுப நாடு 166  
ஆனைமலை 132  
ஆறுவமல்ல சோமேசுவரன் 57, 61,  
67, 74, 81  
ஆறுவமல்லன் 73, 84

இ

இடங்கை 88, 94, 95, 96, 92,  
100, 101  
இந்தியா 20, 125  
இந்திரப்பிரஸ்தம் 108  
இந்திராதன் 29, 31, 36  
இந்திரன் 55, 59  
இந்திரஸ்தானம் 107, 108  
இப்ரஹீம் 108  
இப்ரஹீம், சுல்தான் 109  
இரட்டபாடி ஏழரையிலக்கம் 31,  
141.  
இரட்டன் 141  
இராமநாதபுரம் ஜில்லா 98, 154,  
155  
இராமன் 52, 54  
இராமாயணம் 38, 129  
இராமேசுவரம் 133, 159  
இராவணன் 128  
இராஜ கம்பீர அஞ்சுகோட்டை  
நாடாழ்வான் 160  
இராஜகேசரிவர்மன் 14  
இராஜகேசரிவர்மன் (இராஜாதி  
ராஜன் II) 139  
இராஜகேசரிவர்மன் இராஜேந்திர  
சோழன் 89

இராஜகேசரிவர்மன், காந்தளூர்ச்  
சாலைக் கலமறுத்தருளிய 1  
இராஜகேசரிவர்மன், சக்கரவர்த்தி  
குலோத்துங்க சோழன் (I) 87  
இராஜகேசரிவர்மன் திரிபுவன சக்கர  
வர்த்திகள் 139  
இராஜசுந்தரி 90  
இராஜசேகரர் 55  
இராஜதரங்கினி 49  
இராஜமய்யன் 66  
இராஜமஹேந்திர சதுர்வேதி மங்கலத்  
துச் சபை 87  
இராஜமஹேந்திர சதுர்வேதி மங்கலம்  
88  
இராஜராஜக் கற்குடிய ராயன் 160  
இராஜராஜ சோழன் 15, 16, 17, 19,  
21, 22, 67, 83, 90, 103  
இராஜராஜன் (கலிங்க மன்னன்) 91  
இராஜராஜ சோழன் (I) 1, 2, 20,  
78, 95, 119, 125  
இராஜராஜன் (II) 137, 138, 139,  
141, 142, 144, 176  
இராஜராஜச் சதுர்வேதி மங்கலத்துச்  
சபை 8  
இராஜராஜ சோடகங்கன் 102  
இராஜராஜ சோழன் உலா 140  
இராஜராஜத் தெரிந்த வலங்கை  
வேளைக்காரர் 95  
இராஜராஜ தேவேந்திரவர்மன்  
(கலிங்க மன்னன்) 90, 103, 104  
இராஜராஜ நேரந்திரன் 77, 78, 79,  
80, 81, 82, 83, 103  
இராஜவரீம்ஹன் 16  
இராஜவரீம்ஹன் (பாண்டியன்) 98, 137  
இராஜாதிராஜன் 42, 50, 53, 56,  
57, 81, 138, 156, 157, 160, 168  
இராஜாதிராஜன் (I) 2, 3, 15, 18  
39, 44, 166  
இராஜாதிராஜன் (II) 104, 139,  
155, 157, 169, 176

இராஜேந்திரசோழப்பதினெண் பூமி 100 உத்தர கோசலம் 107, 108  
உத்தரப் பிரதேசம் 108

இராஜேந்திரசோழன் 24, 25, 28, உத்தராபதம் 47  
29, 31, 32, 33, 35, 37, 38, 39, உத்பலன் 65  
68, 73, 80, 81, 103 உபராஜ வீரபாஹு 121

இராஜேந்திரன் (குலோத்துங்க சோ உஜ்ஜயினி 32, 109, 112  
ழன் I) 83, 84, 86, 102

இராஜேந்திரன், சக்கரவர்த்தி 89 ஊ

இராஜேந்திர சோழன் (I) 2, 3, 8, ஊர்ச் சபை 162  
19, 23, 30, 40, 51, 74, 79, 107

இராஜேந்திர சோழன் (II) 40, 42, எ  
56, 57, 81, 129

இராஜேந்திர சோழன் மாடை 88

இராஜ்யபாலன் 33, 55

இலங்காபுர தண்டநாயகன் 153, எண்ணுயிரம் 8  
155, 156 எதிரிலிப்பெருமாள் 138  
எர்ரகாட் 68

இலங்கை 51, 52, 53, 54, 56, 57, ஏ  
95, 99, 119, 120, 122, 124, 125, 126, 127, 128, 142, 153, 155, 159, 166, 175

இலக்ஷ்மி 103

இளங்கோப் பருவம் 69, 73

இறையிலி 87, 88

இஷுப்பள்ளி 135

ஈ

ஈழமண்டலம் 51, 175

ஈழம் 157, 159, 160

உ

உடுப்பி தாலுகா 166

உடுமலைப்பேட்டை தாலுகா 164

உதயபூர் 63, 65

உதயாதித்தியன் 59, 62, 63, 64, 65, 109, 110, 122

உத்கலம் 106

உத்தம சோழச் சதுர்வேதி மங்கலம் (மணல்குடி) 139

உடகம் (திருவேடகம்) 161  
எழகத்தார் 160, 161, 162, 163, 167, 168  
எழகத்தார், பாண்டிநாட்டு 160, 161  
எழகப்படை 161  
எழகம் 161, 168  
எழில்குன்றம் 167

ஐ

ஐதொளே 96

ஓ

ஒட்டக்கத்தர் 128, 138, 140, 141  
ஒட்டர் 79

க

கங்கராஜன் 132  
கங்கரா ஜில்லா 48

கங்கரா பள்ளத்தாக்கு 45, 143  
 கங்கவாடி தொண்ணூற்றாறுயிரம்  
 132, 136  
 கங்கா குண்டம் (கங்கை கொண்ட  
 சோழபுரம்) 85  
 கங்காதேவன் 38  
 கங்கா விஜயம் 24, 28, 38, 68, 74  
 கங்கை 26, 36, 44, 45, 48, 109  
 கங்கைகொண்ட சோழபுரம் 24, 105  
 கங்கைகொண்ட சோழன் (விருது)  
 24, 38  
 கங்கைப் பிரதேசம் 23, 39  
 கங்கை யமுனைப் பிரதேசம் 77, 109  
 கச்யப முனிவர் 94  
 கடாரம் (ஸ்ரீவிஜய நாடு) 143  
 கடிகை 12, 13, 16  
 கடமண்டு 107  
 கண்ணாடர் 122  
 கண்ணாட தேசம் (கர்நாடகம்) 120  
 கண்டிகை 72  
 கண்வர் 10, 11  
 கதம்ப வமிசம் 12  
 கந்தளாய் 124  
 கபோடேச்வரம் 49  
 கம்பநாடர் 128  
 கயாகர்ணன் 71  
 கரவந்தபுரம் 98  
 கரிவரதராஜப் பெருமான் கோயில்  
 164  
 கருந்தடக்கன் (ஆய்குல மன்னன்)  
 5, 17, 18  
 கருமான் 95  
 கருவூர் 66  
 கர்க்கல் தாலுகா 165  
 கர்க்கன் 113, 114  
 கர்ணமேரு 71  
 கர்ணன் 46, 47, 57, 59, 60, 72  
 கர்ணன் (கலஞ்சுரி வமிசம்) 70  
 கர்ணன் (டாஹல மன்னன்) 58  
 கர்நாடர் 31

கர்நாட வமிசம் 38  
 கலஞ்சுரி சந்திரன் 33  
 கலஞ்சுரி வமிசம் 31, 45, 60  
 கலம் 9  
 கலிங்கத்துப்பராணி 3, 73, 101  
 கலிங்கம் 57, 81, 82, 84, 91  
 கலிங்கர் 79  
 கலிங்கன் 71  
 கல்யாணபுரம் 21, 74, 122, 134,  
 141, 142  
 கல்வெட்டுகள்  
 அம்மஞ்சி 166  
 ஆடுதுறை 100, 141, 134  
 ஆர்ப்பாக்கம் 156  
 ஆவணி 100  
 இடையாத்தூர் 128  
 உக்கிரன்கோட்டை 98  
 உதயபூர் 29, 63  
 உத்தனூர் 100  
 ஊற்றத்தூர் 84  
 கண்டமங்கலம் 89  
 கருவூர் 130  
 கன்யாகுமரி 4, 81  
 கீரனூர் 164  
 குமரலிங்கம் 164  
 குருஸ்பால் 70  
 குலேதூர் 29, 33  
 குவாலியர் 55  
 கொத்தசீவரம் 79  
 கோகேரிராஜபுரம் 131  
 கோருமல்லி 78  
 சங்கராமநல்லூர் 97  
 சிதம்பரம் 118, 153, 161  
 சித்தமல்லி 76, 85, 87  
 சீதபல்லி 111  
 செந்தலை 4  
 செம்பொனர்கோயில் 158  
 சேரன்மாதேவி 97  
 திராக்ஷாராமம் 82, 83, 93, 126,

திரிபுவனம் 175  
 திருச்சேறை 131  
 திருப்புத்தூர் 154  
 திருமயானம் 139  
 திருமுக்குடல் 84  
 திருவல்லம் 95  
 திருவாலங்காடு 156  
 திருவாலீச்வரம் 97  
 திருவீழிமிழலை 139  
 திருவெண்காடு 95  
 தேரேயூர் 133  
 தேவனகலா 127, 128  
 நெடுப்போலு 135  
 நெய்வாசல் 162  
 நெருர் 154  
 நெல்லித்தோப்பு 88  
 பசுபதிச்வரன்கோயில் 66  
 பல்லவராயன்பேட்டை 138, 156  
 பன்னேரா 61  
 பாலமோட்டை 124  
 புஞ்சை 97  
 புதமுத்தாவா 125  
 பேராகட் 71  
 பொலந்தறுவை 95  
 மங்கனூர் 166,  
 மதகசிரா 79  
 மருதாடு 101  
 ரணஸ்திபுண்டி 78  
 வராங்கா 165  
 வழுபூர் 89  
 விக்கிரமங்கலம் 99  
 விஜயமங்கலம் 156  
 ஜைனாத் 110  
 ஸேத்மாஜேத் 115  
 ஸ்ரீரங்கம் 87, 93, 116, 166  
 கல்ஹணர் 49  
 கற்பக விருக்சும் 22  
 கழஞ்ச 9, 87, 88, 163  
 கழனிவாசல் 161, 162  
 கன்யாதானம் 63

கன்யா குப்ஜம் 26, 33, 37, 40, 44-  
 48, 49, 50, 54, 55, 56, 57, 72,  
 74, 107, 108, 109, 110, 115  
 கன்யாகுமரி 18  
 கன்னக்குச்சி 54, 72  
 கன்னக்குச்சியர் 56  
 கன்னடம் ஜில்லா 165  
 கன்னட ஸந்திவிக்கிரகி 116  
 கன்னான் 56  
 கன்னிப்போர் 4  
 கன்னோசி 26, 27, 32, 37, 46  
 கன்ஹன் 61  
 கஜபதி (விருது) 20, 21, 107  
 கஜானு 162  
 கஜனி 26, 108  
 கஜனி சுல்தான் 37, 45  
 கஸ்ஸபன் 51, 52

கா

காகன் 113, 114  
 காங்கேயதேவன் 45  
 காங்கேய விக்கிரமாதித்தியன் 31,  
 32, 33  
 காங்கேயன் 21, 30, 31, 36, 37,  
 38, 39, 45, 47, 57, 71  
 காங்கேயன் (விருது) 38  
 காசி 37, 71, 106, 107, 108  
 காசிதேசம் 35  
 காசிபன் பாண்டிய தனஞ்சய சைவே  
 ச்ரமுடையானான சைவ சக்கர  
 வர்த்தி 163, 164  
 காஞ்சிகொண்ட (விருது) 133  
 காஞ்சிபுரம் 12, 15, 16, 75, 93  
 காணி 130  
 காணிபுடைய சிவப்பிராம்மணன் 163  
 காதிபுராதிபர் 115  
 காந்தனூர் 1, 2, 4, 5, 6, 12, 13,  
 14, 15, 202  
 காந்தனூர்ச்சாலை (நூல்) 2

காந்தநூர்ச்சாலை 4, 8, 16, 19, 21  
காந்தநூர் துறைமுகச்சாலை 2  
காந்தாரநாடு 88  
காபா 110  
காபிரிகள் 110  
காமரூபம் 73  
காமார்ணவராயன் 23  
காரைக்குடி 162  
காலஞ்சர நகரம் 26, 27, 28, 32,  
33, 45  
காவிரி 139, 140  
காவேரிப்பாக்கம் 10  
காளிதாசன், மகாகவி 10  
காவ்யமீரம் 49  
காஹடவாலர் 46, 105, 106, 107

கி

கித்தி 51, 52  
கித்தி (விஜயபாஹு) 119  
கிப்லா 110  
கிருஷ்ணபகவான் 35  
கிருஷ்ணன் (சாமந்தன்) 112, 113  
கிருஷ்ண நதி 67, 74  
கிரேக்கர் 34  
கிழக்கிந்தியக் கம்பெனி 93, 100  
கின்லக் போர்ப்ஸ், ஸர் 63

கி

கிரா 45, 71  
கிரா நாடு 49  
கீழர் 20  
கீழ் இரணியமுட்ட நாடு 164  
கீழ்க்குண்டாறு 162

கு

குங்கர் 71  
குசுகம் 107, 108

குண்டுர் ஜில்லா 131  
குந்தவை 78  
குந்திகன் 30  
குமரிமுனை 20  
குமாரபாலன் 112, 113, 114  
குமாரபாலன் (செளலக்கியன்) 111  
கும்பினிப் படை 100  
குரு தேசம் 35  
குருளன் கூத்தனான் உத்தமக்கோன்  
164  
குலசேகர பாண்டியன், ஜடாவர்மன்  
160  
குலசேகரன் 153, 154, 155, 156,  
157, 158  
குலசேகரன் (ஆளுநர் மன்னன்) 165  
குலிங்கர் 79  
குலாத மன்னன் 49  
குலோத்துங்க சோழ தேவன், பெரு  
மான் 132  
குலோத்துங்க சோழ மார்த்தாண்டால  
யம் 106  
குலோத்துங்கசோழன் 69, 70, 85,  
91, 92, 93, 101, 103, 104,  
107, 117, 123, 124, 126, 130,  
132, 135, 136, 137, 157, 158,  
159  
குலோத்துங்க சோழன் (இராஜேந்தி  
ரன்) 90  
குலோத்துங்கசோழன் (I) 2, 3, 72,  
73, 76, 77, 84, 89, 97, 99, 105,  
106, 116, 118, 119, 120, 127,  
129, 131, 169, 174  
குலோத்துங்கசோழன் (II) 128,  
137, 138, 139, 140, 141, 143  
குலோத்துங்க சோழன் (III) 94,  
104, 139, 161, 168, 172, 175  
குலோத்துங்கன் (I) (கொங்கு நாடு)  
154  
குலோத்துங்க சோழன் உலா 136



குலோத்துங்கன், கொமார 138, 139  
 குலோத்துங்கன் கோவை 176  
 குலோத்துங்கன் பிள்ளைத் தமிழ் 20,  
 35, 128, 143  
 குவலாலம் (கோலார்) 132  
 குவாலியர் 32, 63  
 குன்றக்குடி 155  
 குஜரத் 64

**கூ**

கூத்தர் (நடராஜர்) 130  
 கூபகர் கோன் 137  
 கூர்ஜஜர பிரம்ம சேநானி 113, 114  
 கூர்ஜஜரம் 28, 60, 63, 111, 112,  
 கூர்ஜஜர் 71  
 கூல்பாக் 64

**கே**

கேஸதாது 52

**கை**

கையாஸ் உத்தின் 170  
 கைலாசம் 38

**கோ**

கொங்கணம் 31, 166, 167, 168  
 கொங்கு தேச ராஜாக்கள் சரித்திரம்  
 22, 23  
 கொங்கு நாடு 130, 132, 163, 166,  
 167  
 கொங்கு நாட்டார் 71  
 கொச்சி 20  
 கொமார குலோத்துங்க சோழன்  
 சதுர்வேதி மங்கலம் 139  
 கொல்லம் 116, 117, 137, 159  
 கொல்லம் அழிந்தது 116, 117, 118  
 கொல்லேறு ஏரி 137

கொழும்புக் கொண்ட சோழ நல்லூர்  
 (கீரனூர்) 163  
 கொள்ளிடம் 89  
 கொள்ளிப்பாக்கை (கூல்பாக்) 64

**கோ**

கோங்கேஸ்வரர் ஆலயம் 135  
 கோட்-கங்கரா 48  
 கோட்டாறு கோட்டை 137  
 கோதாவரி நதி 104  
 கோந்தவன் 65  
 கோபகா (கோவா) 75  
 கோபாலன் (காதிபுராதிரி) 115  
 கோயத்தூர் (லட்டிகம்) 133  
 கோயம்புத்தூர் ஜில்லா 97, 154,  
 164  
 கோயில் தேவராயன் பேட்டை 14  
 கோயில் பண்டாரம் 88  
 கோவிந்த சந்திரன் 105, 106  
 கோவிந்தசந்திரன் (காஹடவால அர  
 சன்) 72

**கௌ**

கௌட தேசம் 36, 73, 122  
 கௌடர் 71

**கூ**

க்யாதா 65

**ச**

சகுந்தலை 10  
 சக்கரக் கோட்டம் 33, 34, 36, 67,  
 69, 70, 72, 73, 101, 175  
 சக்திவர்மன் II 83, 84  
 சங்கம ராஜன் 176  
 சங்கபோதி (விருது) 54  
 சங்கு 107

சட்டப் பெருமக்கள் (மடம்) 10  
 சட்டர் 6, 7, 8, 9, 10, 11, 13  
 சண்டிதேவி 114  
 சதுரங்கக் காய் 81  
 சத்திரபதி 107  
 சந்திரகுலம் 83  
 சந்திரதேவன் (காஹடவாலன்) 46,  
 105, 107, 108  
 சந்திரன் 30  
 சந்திராதித்திய மஹாராஜா, தெலுங்கு  
 சோட, மஹாமண்டலேச்வரன் 68  
 சந்திராத்ரேயர் 27, 32  
 சந்தி விளக்கு 163, 164  
 சந்தெல்லர் 26, 32, 33, 46  
 சந்த் ராய் 108  
 சப்த கொங்கணம் 168  
 சம்பா நாடு 48, 49  
 சர்வஜ்ஞபுடன் (விருது) 144  
 சலாதேவன் 125  
 சலாமேகன் (விருது) 54

சா

சாகாம்பரீ 112  
 சாகுந்தலம் 10  
 சாக்கிய ரக்ஷிதர் 106

சாசனங்கள்

உப்பரப் பள்ளி 174  
 பாலம்பேட்டை 173  
 பாஹல் 173  
 ஹனுமக்கொண்டா 175  
 சாத்திரக்களி 13  
 சாத்திரர் 9, 10  
 சாமந்தர் 92, 112, 123  
 சாமந்தாபரணன் (விருது) 79  
 சாமுண்டராஜன் 84  
 சாலாபோகம் 8, 11  
 சாலிவாகன சகாப்தம் 116  
 சாலே 11, 17, 18

சி

சிங்கணன் 173  
 சித்தராஜ ஜயசிம்ஹன் 112  
 சித்தூர் ஜில்லா 133  
 சித்ரகோட் 33  
 சிந்தக நாக வமிசம் 68  
 சிந்தகர் 34, 67  
 சிந்து நதி 34  
 சிலாமேக வண்ணன் (விருது) 54  
 சிலோன் (இலங்கை) 20  
 சிவதர்மம் 126  
 சிவப்பிராமணர் 130  
 சிவபெருமான் 63, 68  
 சிவன்கோயில் 125

சு

சுக்கிலபக்ஷம் 76  
 சுத்தமல்லியார் 126  
 சுந்தரபாண்டியன், மாறவர்மன் 162,  
 164, 165  
 சுந்தரபாண்டியன், ஜடாவர்மன் 166  
 சுராதித்தியன் 48  
 சுவரன் மாறன் (முத்தரைய மன்னன்)  
 4

சூ

சூரியகிரகணம் 125  
 சூரிய வமிசம் 15  
 சூரியனார் கோவில் 106  
 சூரியன் 90, 106

செ

செங்கற்பட்டு ஜில்லா 156  
 செட்டிநாட்டுப் பிரதேசம் 162  
 செப்பேடுகள்  
 காசி 47  
 கைரா 104  
 கோர்ணீ 90

## உராக

கோழர்வா 37, 45  
 சாரால 81  
 செல்லூர் 102, 188  
 டேக்கி 102  
 திருப்பரப்பு 18  
 திருவாலங்காடு 24, 157, 160, 161  
 திலக்வாடா 48  
 தீர்காவலி 91  
 பன்ஸ்வரா 30  
 பஸ்தூரி 72  
 பாமுலவாகம் 80  
 பிட்டாபுரம் 103  
 புதாவன் 115  
 பேத்மா 31  
 பைட்டான் 173  
 மாந்தாதா 61  
 ரஹன் 106  
 ராஜாபுரம் 33, 34, 70  
 ரியால 83  
 லீடன் 143  
 விசாகப்பட்டினம் 90  
 வேலூர்ப்பாளையம் 6  
 ஜஹ்வி 44  
 ஸோடாஸா 62  
 செவ்வாய்க்கிழமை 76  
 சென்னை 93

### சே

சேக்கிழார் 140, 141  
 சேதராயன் மலைமண்டல நாயகன் 122  
 சேதிநாடு 31, 32, 35, 38, 57  
 சேதிமன்னன் 37, 49  
 சேதிச்வரன் 31  
 சேது 123  
 சேரம் 132  
 சேவுணர் 21, 172, 174

### சை

சைலேந்திரர் 143

### சோ

சோமநாதபுரம் 28  
 சோமேச்வரன் 60, 69, 70, 82, 91, 93  
 சோமேச்வரன் (II) 72, 74, 75, 76, 86, 92  
 சோமேச்வரன் (III) 144  
 சோழகங்கை 24  
 சோழ கோளன் (விருது) 40  
 சோழ பாண்டியன் (விருது) 3, 40  
 சோழ மூவேந்த வேளான் 100  
 சோழிய நற்பழங்காசு 155  
 சோழேச்வர ஆலயம் 135

### சௌ

சௌலுக்கிய நாடு 112

### ட

டயடோரஸ் 34

### த

தக்காணம் 86  
 தக்கயாக பரணி 140, 141  
 தச்சன் 95  
 தஞ்சாவூர் 88, 89  
 தஞ்சாவூர் ஜில்லா 14, 19, 76, 89, 95, 97, 106, 131, 139  
 தண்டநாயகன் 84, 113, 116, 121, 134, 153, 162  
 தந்தாவாரம் 169, 170  
 தந்தேச்வரி 170  
 தந்தேச்வரி ஆலயம் 169  
 தபகாத்-நாவிளி 109  
 தபஸ்வி 126  
 தப்தி நதி 71  
 தயிழ் நாவலர் சரிதை 138, 141  
 தயித்திரிய சரணத்தார் 6  
 தலவகார சரணத்தார் 6

தலைவரி 95  
தல்பத்ராம், கவி 63  
தலைக்காடு 132  
தலைக்காடு கொண்டவன் (விஷ்ணு  
வர்த்தனன்) 132  
தனஞ்சயன் (விருது) 165  
தக்பிணம் 67, 70  
தக்பிணபதம் 36  
தக்பிணபனம் 45

### தா

தாமரை 30  
தாமிரவருணி நதி 123  
தாரா நகரம் 29, 37, 46, 57, 58,  
59, 114  
தாராவர்ஷன், ஜகதேக பூஷணன்  
(சிந்தக நாக மகாராஜன்) 67,  
68, 69, 70  
தானம் 99  
தானேசுவரம் 48

### தி

திகத்தன், தண்டநாயகன் 143  
திக்கு விஜயம் 101, 103  
திக்காலதேவன் 170, 171  
திரமிளர் (தமிழர்) 90  
திராக்ஷாராமம் 104, 126, 133  
திரிகர்த்த நாடு 48, 49, 144  
திரிகர்த்தர் 143  
திரிகலிங்காதிபதி (விருது) 70  
திரிசங்கு 107  
திரிசங்குபதி (விருது) 107  
திரிபுரி (சேதி) நாடு 122  
திரிபுரீ உகரம் 31  
திரிலோசனபாலன் 27, 44  
திரு 86  
திருக்கடவூர் 139  
திருக்கோணமலை ஜில்லா 124  
திருக்கோவலூர் 20

திருச்சிராப்பள்ளி ஜில்லா 94, 100,  
131, 154  
திருச்சுல வேளேக்காரர் 98  
திருச்சேலூர் மகாதேவர் 14  
திருத்தளி ஆண்ட நாயனார் கோயில்  
154  
திருத்துறைப்பூண்டி தாலுகா 19  
திருநெல்வேலி ஜில்லா 97, 98  
திருப்பணி 153  
திருப்புத்தூர் 155  
திருமயானம் உடையார் 139  
திருமாலிருஞ்சேலை 164  
திருமேனி (விக்கிரகம்) 130, 131  
திருவண்ணாமலை ஆதினம் 155  
திருவனந்தபுரம் 5  
திருவாங்கூர், தென்பகுதி 137  
திருவாசல் 98  
திருவாண்டார் கோயில் 2  
திருவாதிரை நான் 14  
திருவாணிலை யானுடைய நாயனார்  
கோயில் 130  
திரைராஜ்ய கழக மத்தியஸ்தர் 14  
திரைலோக்கிய மல்லன் (விக்கிரமா  
தித்தியன்) 76  
'திலிங்' படையெடுப்பு 170  
தில்லி 32, 48, 108, 116, 170  
திறை 128, 143

### து

துங்கபத்திரை (நதி) 48, 75, 85  
துரு 14  
துருஷ்கர் 31, 49, 109, 118  
துர்கா நாடு 49  
துர்லப தேவி 35  
துவயாசிரயம் 35, 59, 112, 114  
துளு நாடு 53, 54, 165, 161, 167  
துளு பாண்டியர் 168  
துறைமுகப் பெருவழி 5  
துஷ்யந்தன் 10

து

துமகேது 58

தெ

தெலுங்கர் 79

தெலுங்க வீமன் 137

தெலுங்காளு 65

தெலுங்குச் சோடர் 68, 79

தெலுங்கு நாடு 126, 134

தென் ஆர்க்காடு ஜில்லா 8, 89

தென் கன்னடம் ஜில்லா 166

தென் மதுரை 35

தென்னிந்தியா 97

தே

தேவகன்மிகள் 97

தேவகிரி 21, 172

தேவாரம் 161

தேவேந்திரன் 103

தேஜப்பாலன் 113

தை

தைலபன் 22

தைலபன் (III) 142

தொ

தொக்கலன் 4

தொல்காப்பியம் 140

தோ

தோர சமுத்திரம் (துவார சமுத்திரம்) 110, 131, 132

ந

நகரத்தார் 96

நகர கோட்டே 48

நச்சினார்க்கினியர் 140

நந்தபுரி 113

நந்தமபூண்டி 82

நந்திவர்மன் மல்லவ மல்லன் 4

நம்பூதிரி 13

நரபதி (விருது) 20, 21, 107

நரலோக வீரன் 117

நரவர்மன் 109

நர்மதை (நதி) 23, 35, 58, 170

நல்லமன் 176

நன்னய புட்டர் 82

நன்னன் 168

நன்னிலம் தாலுகா 88

நன்னூல் 125

நா

நாக நாடு 34

நாகபூர் 111

நாகதி அரசன் 174

நாக வமிசம் 34, 67

நாக வம்சோத்பவன் 34

நாகை (ஹைதராபாத்) 58

நாஞ்சில் நாடு 137

நாமணைக் கோணம் 33, 34

நாராயண பட்டர் 82

நாலு பாதம் 13, 14

நாழி 9

நானாதேசி திசையாயிரத்து ஐந்தாந்துவர் 96

நி

நிகரிலிசோழமண்டலம் 100

நிச்சங்க மல்லேசுவரம் 159

நித்தவிநோத வளநாடு 88

நிபந்தம் 116, 126, 135

நிருபதுங்கவர்மன் 10

நிஸ்ஸங்க மல்லன் 159

நிஷத்தராஜன் (நிகழ்தராஜன்) 162

நே

நெறியுடைப் பெருமாள் 138

நே

நேபாளம் 88, 107  
நேமி 116

நை

நைஷ்டிக பிரம்மசாரி 10

ப

பகீரதன் 24  
பக்தவத்சல சுவாமி கோயில் 97  
பஞ்சாப் 32, 34, 37, 43, 143  
பஞ்சப்பள்ளி 34, 83  
பட்டை நிலயம் 97  
பண்டித சோழன் (விருது) 37  
பண்டித பாண்டியன் (விருது) 165  
பண்டு 52, 56  
பத்மராஜன் 49  
பம்பாய் ராஜ்யம் 96  
பரகேசரிவர்மன் (விருது) 54, 130  
பரகேசரிவர்மன் (பராந்தகன்) 129  
பரகேசரிவர்மன், தண்டாற்சாலைக்  
கலமறுத்த கோ 3  
பரகேசரி வர்மன், பூர்வதேசமும், கங்  
கையும், கடாரமும் கொண்ட  
கோ 24  
பரணன் 124  
பரமர்த்தி 64  
பரமாரகுலம் 22, 29, 59, 60, 61,  
65, 66, 113, 114, 122  
பராக்கம வேந்தன் 52  
பராக்கிரம பாண்டியன் 116, 127,  
131, 153, 155, 157  
பராக்கிரம பாண்டிய மாசாத்து  
வாயன் 99  
பராக்கிரம பாண்டியன், மாறவர்மன்  
99  
பராக்கிரம பாண்டியன் 127, 155  
156, 157, 159

பராக்கிரமன் 56  
பராந்தகன் 127, 129, 130, 133,  
134, 135,  
பராந்தக பாண்டியன், ஜடாவர்மன்  
2, 4, 137  
பராந்தகன் (I) 98  
பராந்தகன் (III) 128  
பலந்தீபம் 125  
பலிசை 15  
பல்கலைக்கழகம் 6  
பல்லமஹாதேவி 166  
பல்லவராயன், திருச்சிற்றம்பலம்  
உடையான் பெருமானம்பி 156  
பல்லாளன் 113 - 115  
பல்லாளன் (தாரா அரசன்) 112,  
114  
பல்லாள தேவன், ஸ்ரீமத் திரிபுவன  
மல்ல குமார 114  
பலிழிய சரணத்தார் 6  
பழந்தீவு 125  
பழனி 163  
பள்ளி 96  
பள்ளிகள் 131  
பளு 20  
பளுஸ் நதி 76  
பஸ்தர் ஸம்ஸ்தானம் 33, 67, 68,  
169, 170, 175

பா

பாண்டிய தனஞ்சய சுந்தன் குலோத்  
துங்க சோழ பட்டர் 163, 164  
பாண்டிய தனஞ்சயன் (விருது) 165,  
166  
பாண்டிய மண்டலம் 3, 164  
பாண்டியர் வரலாறு 116  
பாண்டியன் வீரப்பெருமான் 126  
பாண்டுவீஜயகம் 155  
பாதரசை 94  
பாபநாசம் தாலுகா 88  
பாம்பு நாடு 84

பாரசீகம் 20

பாரசு-ரு (பார்ஸு-ரு) 63

பாரி 26, 27, 55

பாரிஜாத மஞ்சரி (விஜயபுரி) 47

பார்த்திவசேகரபுரம் 5, 6, 8, 9, 10,

11, 12, 13, 17, 18, 19

பாலபாரதம் 55

பாவபிரஹஸ்பதி 114

பாஹ்மனி, அஹமத் ஷா 171

பி

பிட்டிக தேவன் (விஷ்ணுவர்த்தனன்)  
132

பியாவன் மலை 45

பியாஸ் நதி 48

பிரசுஸ்தி

அபுமலை 113

உதயபூர் 22, 31, 38, 109, 122

நாகபூர் 59, 62

வாட்நகர் 114

வேராவல் (வீரதவளபட்டினம்)

114

பிரட்டன் 176

பிரதமை திதி 76

பிரதாபருத்திரன் 170, 171, 172

பிரதிஷ்டானபுரம் 173

பிரதானி 99, 126

பிரதிஷ்டை 130, 131

பிரதிஹார வமிசம் 55

பிரபந்த சிந்தாமணி 36, 46, 58, 59

பிரயாகை 45, 47

பிரஹத் ஸம்ஹிதை 71

பிரிஷ்டா 31, 48

பிஸ்ஸா 65

பிஸ்ஹணர் 61, 63, 64, 73, 75, 85,

86

பிளீட், டாக்டர் 37

பிள்ளை, டாக்டர் கே. கே. 137

பிஜாபூர் ஜில்லா 96

பிஜ்ஜலன் (கஸூரி-வமிசம்) 142, 176

பி

பீமராயன் 23

பீமன் 31, 57, 58, 59, 60

பீமேச்வரதேவர் 104

பு

புதுக்கோட்டை ஸம்ஸ்தானம் 128,  
159, 161, 162, 169

புதுச்சேரி 2

புத்தபகவான் 96

புத்தவிஹாரம் 153

புலத்தி நகரம் 121, 123

பு

பூபாலன் 33

பூலோக மல்லன் (விருது) 144

பெ

பெரம்பலூர் தாலூகா 141

பெரியதேவர் 139

பெரியபுராணம் 140

பெரிய வடுகன் (விக்கிரமாதித்தியன்)  
134

பெரிய வடுகன் போர் 131

பெரிய விஷயத்தார் 100

பெருங்குறிப் பெருந்தேவர் 139

பெருந்தனத்து வலங்கைப் பழம்படை  
கள் 94

பெரும்படை வலங்கை மஹாஸேனை  
100

பெல்லாரி ஜில்லா 67

பே

பேடன் 175

பை

பைஹகி 37

**பொ**

பொலந்நறுவை 98  
பொன் 10, 15  
பொன் மழை 169, 170, 171

**போ**

போகவதீபுரவரேச்வரர் 34  
போர்க்கலை அரசன் 33  
போஜராஜன் 22, 29, 30, 31, 32,  
33, 35, 36, 37, 38, 39, 46, 47,  
48, 49, 55, 57, 58, 59, 60, 62,  
65, 72

**பெ**

பெளரோஹித்யம் 8, 12

**ம**

மகரக்கொடி 143  
மகாசபை 96  
மகாதேவன் (ருத்திரதேவன் தம்பி)  
174  
மகுடாபிஷேகம் 78, 80, 83, 85  
மக்கென்ஸி, கர்னல் 116  
மணிமங்கலம் 41  
மணிமண்டபம் 2  
மண்டலிகன் 61  
மதகசிரா தாலூகா 79  
மதனபாலன் 105, 106, 110  
மதனராஜன், ஸ்ரீவல்லபன் 56  
மதனன் 47, 115  
மதிட்சேவகர் 98  
மதுரா 35  
மதுராந்தகன் (சிந்தக நாக வமிசம்)  
69, 73  
மதுராந்தகி 103, 129, 136,  
மதுரை 3, 116, 117, 118, 133,  
142, 152, 155, 156, 157, 158,  
165, 167,

மதுரை மண்டலம் 33, 34, 35  
மதுரையும் பாண்டியன் முடித்தலையும்  
கொண்டருளிய (விருது) 158  
மதுரை ஜில்லா 99, 111, 113,  
மதுத் 48  
மத்திகாவாடதித்த 121  
மத்தியப் பிரதேசம் 33, 67  
மத்திரர் 143  
மம்மூது 25, 26, 27, 28, 32, 35,  
39, 45, 55, 108  
மம்மூது (இப்ரஹீம் மகன்) 108,  
109  
மயிலைநாதர் 125  
மயூரசர்மன் 12  
மரக்கலக் கோரையாறு 19  
மரக்கலம் 2  
மருமக்கள் தாயம் 167.  
மலபரோள் கண்ட (விருது) 111  
மலய நாடு 153  
மலயபர்வதம் 38  
மலஹன் 110  
மலஹர கோணீசன் 111  
மலையத்தீவு 125  
மலையாளர் 96  
மல்லுகிதேவன் (சேவுண அரசன்)  
175  
மல்லுரி (மல்லுரி) 110  
மறச்சாமந்தர் 160  
மறப்படை 161  
மறவர் 160  
மஹாகலா விக்கிரம சலாமேகபுரம்  
126  
மஹாதந்திரத்தார் 96, 97  
மஹாதித்த 121  
மஹாநதி 71  
மஹாராஜபுத்ர (விருது) 62  
மஹாலான கித்தி 51, 53, 166  
மஹாவமிசம் 51, 52, 53, 54, 56,  
120, 122, 124, 125, 127, 153,  
154, 155, 162, 163, 166



மஹி நதி 70

மஹிந்தன் V 51

மஹிபாலன் 55, 101

மஹியாலன் 46

மஹேச்வரமடம் 126

மஹேந்திரகிரி 23

மஹேந்திரபாலன் 55

மஹேந்திரராஜன் 35

மஹோபா 32

மஸூத் I 37, 108

மஸூத் III 109, 110

மஸூத் இபன் சாத் இபன் ஸல்மான்  
109

### மா

மாசனி (வகுப்பார்) 34

மாசாத்துநாயன் (விருது) 99

மாசுணி தேசம் 38, 35

மாண்டு கோட்டை 58

மாதம்

மே 76, 78, 116, 117

ஜூன் 77, 80, 84, 89, 90, 116,  
117, 129

ஜூலை 154, 155, 157

ஆகஸ்டு 78

அக்டோபர் 83

நவம்பர் 89

ஆனி 89, 116, 117

மார்ச்சு 14

ரிஷபம் 76

மாதுலன் 58, 135

மாராய பண்டன், தண்டாதிபன் 135

மாருதி 123

மாலத் தீவு 125

மாளவச் சக்கரவர்த்தி 162

மாளவம் 49, 57, 60, 61, 63, 64,  
65, 67, 109, 111, 113, 115

மாணபரணன் 156

மாணபரணேச்வர தேவர் வமிசம்  
166

### மி

மிதிலை 38, 73

மின்சிறை 6

### மீ

மீமாம்ஸை 8, 9

மீனவன் (சேரன்) 159

### மு

முத்துக் குளித்தல் 20

முத்துப்பேட்டை 76

மும்முடி சோழ விண்ணகர ஆழ்வார்  
கோயில் 87

மும்முடிச் சோழன் 102

முயக்கி 31

முரள நதி 71

முரளர 71

முன்னீர்ப் பழந்தீவு பன்னீராயிரம்  
125

### மூ

மூலபரிஷத் மகா சபை 155

மூல்தான் 32

மூன்று கைத் திருவேளைக்காரன்  
தலதாயப் பெரும்பள்ளி 96

மூன்றுகை மகாஸேனை 97, 98

மூன்றுகை வேளைக்காரர் 98

### மே

மேய்க்கீர்த்தி

திங்களேர் தரு 3, 39, 40, 44, 59

திருமகள் போல 1

திருமன்னி வளர 3, 24

திருமன்னி விளங்கும் 69, 89

திருமாதா புவியெனும் 40, 56

திருவளரச் செயல் வளர 4

திருவளர் திரள்புயத்து 42, 65

புகழ்க்குழந்த புணரி 69, 87

புகழ்மாத விளங்க 102  
புயல்வாய்த்து 169  
புலி மங்கை வளர 129  
பூ மங்கை வளர 129  
பூமருவிய திருமடந்தையும் 89  
பூமருவிய பொழிலேழும் 128, 144  
பூமன்னு பதுமம் 193  
வீரமே துணையாகவும் 43, 72, 102

**மே**

மேகநாதன் 55  
மேடமா 78  
மேருதுங்கர் 36, 46, 59  
மேளமா அல்லது மேடமா (இராஜ  
ராஜ நரேந்திரன் தேவி) 78  
மேற்கு கோதாவரி ஜில்லா 126

**மை**

மைசூர் ராஜ்யம் 100, 131  
மைலகித் தேவன் 175

**மோ**

மோஹடவாஸக எழு நூற்றைம்பதுப்  
பகுதி 62

**ய**

யசக்கர்ணன் (சேதிநாட்டு டாஹல  
மன்னன்) 103, 104  
யசோதவளன் 113  
யமிநீ அரசன் 37  
யமுனை நதி 35  
யவனர் 170, 174, 175

**யா**

யாகம்  
அசுவமேதம் 173  
புருஷமேதம் 173

யாத்திரா தானம் 154

**ர**

ரகு 55  
ரங்கநாதர் கோவில் 116, 166  
ரணதவளன் 64

**ரா**

ராமசந்திரதேவன் 173  
ராயமுராரி 176  
ராய்ச்சூர் ஜில்லா 67  
ராவி நதி 48  
ராஜப்பிரசுத்தி 172  
ராஜஹம்சம் 58  
ராஜிகன் 85, 86, 87  
ராஜ்யபாலன் 26, 27, 32  
ராஜ்யபுரீ (அரசு) 48  
ராஸ்மாலா (நூல்) 63, 64

**ரி**

ரிந்துவால் (ரணதவளன்) 64

**ரு**

ருத்திரதேவன் 173, 175  
ருத்திரன் (சிவன்) 172  
ருத்திரன் 172, 173, 174  
ருத்திராம்பா 172  
ருத்திரோத்காரி வருஷம் 116, 117

**ரே**

ரேசர்லா 173  
ரேவா 37

**ரோ**

ரோஹண நாடு 51, 52, 54, 124  
ரோஹிணி நக்சத்திரம் 76

**ல**

லக்கணபாலன் 115  
லங்காபுரம் 142  
லக்ஷ்மணன் 55  
லக்ஷ்மதேவன் 109, 122

ஒக்ஷமீகர்ணன் 37, 41, 42, 45, 47

லா

லாடதேசம் 113

லாடபதி 31

லாஹூர் 48

லீ

லீலாவதி 52

லோ

லோகன் (லோகேச்வரன்) 52

வ

வங்கன் 71

வங்கும (நதி) 109

வட ஆர்க்காடு ஜில்லா 10, 95, 101

வட கொங்கணம் 71

வடபெருங்கோயிலுடையான் கோயில் 98

வடமதுரை 35

வடவிருகும் 45

வடுகர் 96, 169

வட்டெழுத்து 17

வத்ஸராஜன், மஹாராஜபுத்ர 62

வயிராகரம் 101

வர்தா நதி 71

வலங்கை 88, 94, 96, 99

வலங்கை இடங்கை கலகம் 93, 99

வலங்கை இடங்கை மகன்மை 95

வலங்கைப் பழம் படைகள் 94

வலங்கை வேளாக்காரர் 95

வலிய சூலை 5

வளஞ்சியர் 96

வனபதி 91

வன்னியர் 100

வா

வாகட பகுதி 61

வாகேச்வர ரக்ஷிதர், ஸௌகத பரிவரா  
ஜக மஹா பண்டிதர் 106

AA

வாகேச்வரர் கோயில் 168

வாகேல வமிசம் 64

வாக்பதி 65

வாக்பதி முஞ்சன், உப்பலன் (II) 22,  
60

வாதகிரிக் குகை 121

வாரங்கல் (ஒருங்கல் அல்லது உறங்  
கை) 169, 170

வால்மீகி 128

வானமண்டலம் 90

வி

விக்கம பண்டு 51

விக்கிரம ஸம்வத்ஸரம் 115, 169

விக்கிரகங்கள் 132

விக்கிரம வருஷம் 38

விக்கிரம சிலாமேக ஈச்வரமுடையார்  
கோயில் 126

விக்கிரம சோழன் 4, 127, 128,  
129, 130, 131, 135, 136, 137,  
138

விக்கிரம சோழன் (திரிபுவன சக்கர  
வர்த்திகள்) 135

விக்கிரம சோழன் உலா 3, 102,  
143

விக்கிரம பாண்டியன் 53, 158, 160

விக்கிரமபாஹு 51, 52, 124, 126

விக்கிரமாங்க தேவ சரிதம் 57, 61,  
74, 75, 85

விக்கிரமாதித்தியன் 38, 64, 67, 73,  
74, 75, 76, 85, 86, 87, 91, 92,  
93

விக்கிரமாதித்தியன் (VI) 105, 111,  
116, 118, 134, 136, 144, 175

விசாலாக்ஷி அம்மன் 106

விசுவேசுவர சுவாமி 106

விசுவாமித்திரர் 107

வித்தசாலபஞ்சிகா (நூல்) 55

வித்தியாதரன் 27, 28, 32, 33, 36  
44

விந்தியதேசம் 35  
 விந்திய மலை 123, 170  
 விமலாதித்தியன் 78  
 வியாகரணம் 8, 9, 11  
 வியாழக்கிழமை 78, 83  
 விரதகண்டம் 172  
 விருது 132  
 விற்றற்படைக் கலிங்கவர்மன் 56  
 விஜயபாஹு 52, 57, 95, 99, 120,  
 122, 123, 124, 125, 127  
 விஜயபாஹு மாசாத்து நாயன் 99,  
 126  
 விஜயராஜ சதுர்வேதி மங்கலத்து  
 விஜயராஜ ஈசுவரம், கந்தனாய் 125  
 விஜயவாடா 66  
 விஜயன் (சாமந்தன்) 112, 113  
 விஜயஸ்ரீ (பாரிஜாதமஞ்சரி, நூல்) 47  
 விஜயாதித்தியன் 73, 79, 80, 82,  
 83, 84, 87, 90, 91, 102, 103,  
 104, 129  
 விஷ்ணு 18, 59  
 விஷ்ணு கோயில் 98  
 விஷ்ணுபட்டாரகர் 6  
 விஷ்ணு வர்த்தனன் 114, 118, 133,  
 134, 136  
 விஷ்வக்ஸேனார் 116

### வி

விணைக்கொடி 128  
 விணைக்கொடிச் சிங்களர் 128  
 விணைக்கொடியோன் 128  
 வீரகேரளன் 159  
 வீரகடர்ச்சன் 16  
 வீரசலாமேகன் 54, 56, 57  
 வீரசர்மன் 12  
 வீரசோடன் 102  
 வீரசோழ மண்டலம் 130  
 வீரட்டானேசுவரர் கோயில் 20  
 வீரதவளபட்டினம்(வேராவல்) 114  
 வீரதேவன் 125

வீரப்பெருமான், பாண்டியன் 126  
 வீரபத்திரர் 98  
 வீரபாண்டிய ஆளுபேந்திரன் 166  
 வீரபாண்டியபுரம், ஏழகச் சக்கர  
 வர்த்திப் பெருந்தெரு 162  
 வீரபாண்டியன் 152, 155, 157,  
 158, 159, 166  
 வீரபாண்டியன், ஜடாவர்மன்  
 167  
 வீரமுஷ்டி 98  
 வீரராஜேந்திரன் 42, 65, 66, 73,  
 74, 75, 76, 81, 82, 84, 85, 91,  
 92, 95, 119  
 வீரராஜேந்திர தேவன் 164  
 வீரராஜேந்திர தேவன், திரிபுவன  
 சக்கரவர்த்தி 163  
 வீரராஜேந்திர தேவன், திரிபுவன  
 சக்கரவர்த்தி கொணேரின்மை  
 கொண்டான் 164  
 வீரராஜேந்திரன் சந்தி 164  
 வீராபிஷேகம் 159

### வை

வைதும்பராயன் 23  
 வைன் கங்கா(நதி) 71

### வே

வேங்கால நாடு 130

### வே

வேங்கி 66, 73, 77, 78, 79, 80,  
 81, 82, 83, 84, 85, 86, 87, 90,  
 91, 92, 102, 103, 104, 105,  
 126, 129, 133, 136, 168, 169  
 வேனாடு 5, 17, 18, 111  
 வேலநாண்டி கோங்கன் 135  
 வேலி 97  
 வேளாளர் 100  
 வேளைக்காரப் படை 122, 123  
 வேளைக்காரர் 96 - 98

**ஜ**

ஜகதாழ்ப்பூர் 68  
 ஜகதேக பூஷணன், மஹாராஜா 68  
 ஜகதேகமல்லன் (III) 142  
 ஜகதீபாவன் 52, 54, 57  
 ஜகத்தேவன் 110  
 ஜகத் விஜயன் 153, 155  
 ஜடா சோட பீமன் 23  
 ஜம்பூ த்வீபம் 107  
 ஜயகேசி (கதம்பகுலம்) 75  
 ஜயங்கொண்ட சோழமண்டலம் 100  
 ஜயங்கொண்டார் 101  
 ஜயசிங்கன் 79  
 ஜயத்ரதன் 153  
 ஜயபாஹு 122, 124-126  
 ஜயமகள் 90  
 ஜயவிறிம்ஹன் 29, 80, 60, 61, 62, 63, 64, 74  
 ஜயஸ்தம்பம் 118  
 ஜயஸ்தம்பம், ஜலமயமான 24  
 ஜலசமாதி 48  
 ஜனநாதபுரம் 133, 134  
 ஜனநாதன் 66  
 ஜனநாதன் (விருது) 17

**ஜா**

ஜாக்கலமாதேவி 115,  
 ஜாவா 20  
 ஜான் பிரையர் 20

**ஜீ**

ஜீரோனோத்தாரணம் 88

**ஜை**

ஜைதுகி 173  
 ஜைத்ர பாலன் 171, 172, 173, 174  
 ஜையினிகள் 114

**ஷா**

ஷாமன்கள் 110

**ஷு**

ஷுத்திரியர் 15

**ஸ**

ஸங்கிராந்தி 45  
 ஸத்யஸேனன் 16  
 ஸபாதலகும் 112  
 ஸம்வத்ஸர ச்ராததம் 4, 7  
 ஸல்மான் 109  
 ஸஹ்யமலை 118

**ஸா**

ஸாமவேதம் 13, 14  
 ஸாஹவாஹனன் 48, 49  
 ஸாஹஸாங்கன் 49  
 ஸாஹிலில் தேவன் 49

**ஸி**

ஸித்தராஜன் 64  
 ஸிந்தவாடி 67  
 ஸிந்து நதி 34, 35  
 ஸி - யு - கீ (சீன நூல்) 104

**ஸே**

ஸேநாபதி 116

**ஸோ**

ஸோதரே (குலம்) 34  
 ஸோமகுலம் 166  
 ஸோவிதேவன் 176  
 ஸோலங்கி குலம் 63, 64  
 ஸோவலதேவி 83

**ஸௌ**

ஸௌகத பரிவ்ராஜக மஹாபண்டிதர்  
 வாஜீச்வர ரக்ஷிதர் 103  
 ஸௌமித்ரீ 55  
 ஸௌரவீரன் 65

ஸௌலுக்கியன் 64

ஸ்

ஸ்கந்த சிஷ்யன் 16

ஹ

ஹளேபீடு (துவார சமுத்திரம்) 131

ஹனுமகொண்டா 175

ஹன்வரி 48

ஹா

ஹாஜிப் துஜாதிகின் 109

ஹு

ஹுல்வ், டாக்டர் 161

ஹோ

ஹோய்சளர் 111, 114, 132, 133,  
134, 136, 140, 166

ஹி

ஹிந்துஸ்தானம் 25, 28, 32, 45, 47,  
108

ஹிஜ்ரி 31, 48

ஹு

ஹுக்ளி சங்கமம் 71

ஹுணதேசம் 35

ஹுணர் 71

ஹே

ஹேம சந்திரர் 35, 59, 112

ஹேமாத்ரி 172

ஹை

ஹைஹயர் 31

ஹைதராபாத் 58

ஹைதராபாத் ராஜ்யம் 64

ஹீ

ஹீசிவாசன், கே. ஆர். 116

ஹீபண்டாரம் 97, 169

ஹீரங்கம் கோவில் 89

ஹீவல்லப்பப்பெருஞ்சாலை 18, 19

ஹீவல்லபவல்லபன் 82

ஹீவல்லபன் 18, 19, 156

ஹீவிக்கிரம சலாமேகத் தெரிந்த

வேளைக்காரர் 125

## ஸ்ரீ இராமாநுஜர் காலத்தைப்பற்றி ஒரு குறிப்பு.

விசிஷ்டாத்வைத மதத்தை நிறுவின ஆசாரியரான ஸ்ரீ இராமாநுஜருடைய காலத்தைச் சுமார் நாற்பது ஆண்டுகளுக்கு முன் காலஞ்சென்ற து. அ. கோபிநாதராயர் ஆராய்ந்து நிர்ணயித்தார்கள். (சென்னைப் பல்கலைக் கழகத்தில் 1917-ஆம் ஆண்டில் “ஸர். சுப்பிரமணிய ஐயர் பேருரை” யாக அவர் செய்த பிரசங்கங்களின் பதிப்பு ஸ்ரீவைஷ்ணவர்கள் வரலாறு). அதற்குப் பிறகு, பொதுவாக ஆராய்ச்சியாளர்கள் அந்த முடிவுகளைப் புனராலோசனை செய்து மாற்றுவதற்குத் தக்க ஆதாரங்கள் இருந்தும் அவற்றைக் கவனியாமல் புறக்கணித்து அவர் கண்ட முடிவுகளையே ஏற்றுவருகிறார்கள்.

[உதாரணமாகப் பின் வருவதைக் கூறலாம். “சோழர் களுடைய ஆட்சியிலே மதத்துவேஷம் கொண்டு வேற்று மதத்தினரைத் துன்புறுத்தியதற்கு இராமாநுஜரையும் அவரைப் பின்பற்றியவர்களையும் சோழ அரசன் ஒருவன் நடத்திய விதத்தை முக்கியமானதாகக் கொள்ளலாம். அவ்வரசன் யார் என்பது சந்தேகமற முடிந்த முடிவு என்பதாகாது. இந்த மதவெறிச்செயல் நாட்டிலே மக்கள் எழுச்சியை உண்டாக்கியது என்றும், அந்தக் காலத்தில் விஜயாலய வமிசத்து ஆண் வழியின் கடைசி அரசனான அதிராஜேந்திரன் உயிரிழந்தான் என்றும் கருதுவதற்குப் போதிய காரணத்தை நாம் கண்டோம்” என்று பேராசிரியர் க. அ. நீலகண்ட சாஸ்திரிகள் தம் சோழர்கள் சரித்திரத்தில் (இரண்டாம் வால்பூம், பக்கம்-487) கூறுகிறார். இவ்விதம் செய்த மன்னனைக் கிருமிகண்ட சோழன் என்று வைஷ்ணவசம்பிரதாயநூல்கள் குறிக்கின்றன. “அவன் சிதம்பரம் நடராஜர் ஆலயத்தின் எதிரில் இருந்த கோவிந்தராஜர் விக்கிரகத்தைப் பிடுங்கிக் கடலில் எறிந்தான் என்று கூறப்படுகிறது. திவ்ய குரி சரித்திரத்தில் இந்தச் சம்பவம் விஷ்ணு மதத்துக்கு விரோதமாக நடந்த கிளர்ச்சியின் ஆரம்பத்திலேயே கொடுக்கப் பட்டுள்ளது. (பதினெட்டாம் அத்தியாயம், சுலோகம் 72). இந்த விஷயம் மிகவும் பிற்காலத்து நூலான பிரபஞ்ஜமிருத்திலும் சொல்லப்பட்டுள்ளது. (புராதன இந்தியா என்ற தம் நூலில் பக்கம் 320-ல் டாக்டர் எஸ். கிருஷ்ணசாமி ஐயங்கார் இந்தப்பகுதியை மேற்கோளாகக் கொடுத்திருக்கிறார்.)

இந்தச் சம்பவத்தை இரண்டாம் குலோத்துங்க சோழனுக்கு ஏற்றிக் கவிஞர் ஒட்டக்கூத்தர் கூறுகிறார். குலோத்துங்க சோழன் உலா வரிகள் 76-8; இராஜராஜ சோழன் உலா வரிகள் 64-6, இதிலே தெளிவாகக் கூறப்பட்டுள்ளது. தக்கயாகபரணி தாழிசை 777. ஆயினும் அதைக்கொண்டு இராமாநுஜரைத் துன்புறுத்தியவன் இரண்டாம் குலோத்துங்க சோழனே யாவான் என்று யாரும் கூறுவதற்குத் தயாராக இருப்பதாகத் தோன்றவில்லை. எனினும், இம்மன்னன் புதிய கட்டிடங்களை அமைத்து நடராஜர் ஆலயத்தை விஸ்தரித்துப் பொன் மயமாக்கியிருக்கிறான் என்பது தெரிந்த விஷயம். இவ்விவரத்தைக் கூறும் கவிஞர் அவ்வரசனுடைய முன்னோர்களில் ஒருவன் செய்த காரியத்தை அவனுக்கு ஏற்றிக் கூறியிருத்தல் கூடும்” என்று (முதல் வால்பூம், பக்கம் 355.) மேலும் அவர் கூறுகிறார்.]

குருபரம்பரைகளில் காணும் விவரங்களை ஸ்ரீராயர் தம்முடைய நூலில் திரட்டிக் கொடுத்திருக்கிறார். அவற்றின்படி ஸ்ரீ இராமாநுஜர் கலியப்தம் 4118, சகாப்தம் 939, பிங்களவருஷம், சைத்ர மாதம், சுக்கிலபக்ஷத்துப் பஞ்சமி, வியாழக்கிழமை பெற்ற திருவாதிரை நாள் பிறந்தவர். சக வருஷத்தைக் கடபயாதி சங்கியையில் ‘தீர்லப்தா’ (தீர்லப்தா) என்று குறிப்பார்கள். இது கி. பி. 1017-ஆம் ஆண்டு ஏப்ரல் மாதம் நாலாம் தேதி வியாழக்கிழமை ஆகும். அன்றைத்தினம் சுக்கிலபக்ஷத்துப் பஞ்சமி உதயாதி ஒன்பது நாழிகை முப்பத்தாறு விநாடிவரையிலும், திருவாதிரை நக்ஷத்திரம் உதயாதி நாற்பத்தைந்து நாழிகை வரையிலும் இருந்தன. அவர் நூற்றிருபது ஆண்டு உயிர் வாழ்ந்திருந்தாராம். அதனால் அவருடைய மறைவு சகாப்தம்; 1059 அல்லது கி. பி. 1137-38-ஆம் ஆண்டு நிகழ்ந்திருக்க வேண்டும். அவர் மறைந்த வருஷத்தையும் கடபயாதி சங்கியையில் ‘தர்மோநஷ்ட:’ (யலோநஷ்ட:) என்று குறிப்பார்.

குருபரம்பரைகளில் காணும் சம்பிரதாயமான கால நிர்ணயத்துக்கு ஒத்து வருவதற்காக இராமாநுஜர் ஸ்ரீ பாஷியம் எழுதிமுடித்த காலத்தைத் தெரிவிக்கும் தமிழ்ச் செய்யுள் ஒன்றில் காணும் வருஷத்தை முப்பதுவருஷம் குறைத்து ஸ்ரீராயர் கணக்கெடுத்துக் கொடுத்திருக்கிறார். அன்றி, அவ்வாசாரிய



ரைத் துன்புறுத்திய சோழ மன்னன் முதற்குலோத்துங்கனாகவே இருத்தல்வேண்டும் என்று, அவன் வைஷ்ணவ மதத்துக்கு விரோதமாக இருந்தான் எனக் கூறுவதற்கான ஆதாரம் சிறிதும் இல்லாமல் இருந்தும் நிர்ணயித்தார்.

இவ்வாசாரியாருடைய ஜனன நாளைக் குறிக்கும் அவதார சுலோகமும் தமிழ் உரைநடைப் பகுதியும் காஞ்சிபுரத்திலிருந்து கர்னல் மக்கென்ஸியின் உதவியாளர்கள் பிரதி செய்து எழுதி வைத்தவை இந்தத் தொகுப்பிலே தனியாகக் கொடுக்கப்பட்டுள்ளன. (நெ. 1292, 1293). அவற்றின்படி அவர் கலி வருஷம் 4126, சகாப்தம் 947, குரோதன ஆண்டில் பிறந்தார். இது குரு பரம்பரை சம்பிரதாயப்படி காணும் ஆண்டுக்கு எட்டு வருஷம் பிற்பட்டதாக இருக்கிறது. மற்றப் பஞ்சாங்க விவரங்களான சித்திரை மாதம், சுக்கில பக்ஷத்துப் பஞ்சமி, வியாழக்கிழமை, திருவாதிரை நக்ஷத்திரம் ஆகியவை இரண்டுக்கும் பொதுவாக உள்ளன. இவ்விடம் கொடுக்கப்பட்டுள்ள பஞ்சாங்கக் குறிப்பில் சித்திரை மாதத்தின் 14-ஆம் தேதி என்பது அதிகப்படியாகக் காண்பதாகும். இந்த விவரம் எப்படிக் கிடைத்ததென்பது தெரியவில்லை.

இந்தத் தொகுப்பில் காணும் விவரங்களைக் கொண்டு கணக்கிட்டால் அவர் பிறந்த நாள் கி. பி. 1025-ஆம் ஆண்டு ஏப்ரல் மாதம் ஐந்தாம் தேதியாகும். அன்றைக்குப் பஞ்சமி திதி உதயாதி முப்பது நாழிகை வரைபில் இருந்திருக்கிறது. திருவாதிரை நக்ஷத்திரம் உதயாதி மூன்று நாழிகை முப்பத்தாறு விநாடிக்குமேல் வந்திருக்கிறது. ஆனால் அன்றைக்குத் திங்கட்கிழமை; சாசனத்தில் கண்டுள்ளபடி வியாழக்கிழமை அல்ல. இதேபோல, சம்பிரதாயப்படி காணும் பஞ்சாங்கக் குறிப்புகளுக்கு ஒத்து வரும் நாள் கி. பி. 1017-ஆம் ஆண்டு ஏப்ரல் மாதம் நான்காம் தேதி ஆகும். ஆனால் அன்றைக்குச் சித்திரை மாதம் பதின்மூன்றாம் தேதியாகும்; சாசனத்தில் கண்டுள்ளபடி பதினான்காம் தேதியாகாது.

இம்மாதிரியே, வைஷ்ணவ ஆசார்ய பரம்பரையில் இராமாதுஜருக்கு மூத்தவரான ஆளவந்தார் ஜனன காலத் தைப்பற்றியும் வேறுபாடு காணப்படுகிறது. சம்பிரதாயத்தை

ஒட்டி அவர் கலியப்தம் 4017-க்குச் சரியான தாது (கி. பி. 917)வருஷம், ஆடிமாதம், உத்திராட நக்ஷத்திரத்தில் பிறந்தார் எனக் கூறுவர். ஆனால் இவ்விடம் கொடுக்கப்பட்ட கணக்கிலே (சாசனங்கள் 1296-7) அது ஐம்பது ஆண்டு பிற்பட்டதாகக் காண்கிறது. அந்தச் சுலோகத்தின் கடபயாதி சங்கியைப்படி அது கலியப்தம் 4067, சகாப்தம் 888, அக்ஷய வருஷம் (கி. பி. 966-7) ஆகும்.

இன்னும், இராமாநுஜருடைய பெரிய தாயார் குமாரரும், அவருடன் ஒருசாலை மாணவரும், பின்னால் வைஷ்ணவ மதத்தைத் தழுவி, துறவம்பூண்டு எம்பார் என்ற பெயரிலே விளங்கியவருமான கோவிந்த பட்டர் என்பார் இராமாநுஜருக்கு எட்டு வருஷம் இளையவர் என்று குருபரம்பரைகள் கூறும். இராமாநுஜர் கலியப்தம் 4118, பிங்கள வருஷம் பிறந்தார். கோவிந்த பட்டர் கலியப்தம் 4126, குரோதன வருஷம் தைமாதம் புனர்ப்பூச நக்ஷத்திரத்தில் பிறந்தார். இராமாநுஜார் திவ்ய சரிதை என்னும் நூலும் சம்பிரதாயத்தை ஒட்டியே இராமாநுஜர் பிங்கள வருஷம் பிறந்தார் என்று கூறுகிறது. எனினும், கோவிந்தர் அதே ஆண்டு தை மாதம், பூர்ணமி, புனர்ப்பூச நக்ஷத்திரத்தில் பிறந்தார் என்று கூறுகிறது. இவ்விதம் இருவரும் ஒரே ஆண்டில் பிறந்தவர் என்பது அந்த நூலாசிரியர் கருத்து. இதை ஒட்டியே சம்பிரதாயமாகக் கோவிந்தர் பிறந்த வருஷமாகக் கொள்ளும் குரோதன ஆண்டிலேயே இராமாநுஜர் பிறந்தார் என்று இந்தத் தொகுப்பில் கொடுக்கப்பட்டுள்ள சாசனம் தெரிவிக்கிறது.

இவற்றைக் கவனிக்கும்போது குரு பரம்பரைகளும் சம்பிரதாயங்களும் இந்தக் கால முறையை ஒருமுகமாகக் கூறவில்லையென்பதும், அவற்றுள் வேறுபாடுகள் காணப்படுகின்றன வென்பதும் தெளிவாகும். ஆகவே சம்பிரதாய நூல்களில் காணும் காலவிவரத்தைத் தள்ளாமல் அப்படியே ஏற்றுக்கொள்ள வேண்டும் என்ற நிர்ப்பந்தம் இல்லை. உண்மையில் அந்தச் சம்பிரதாயங்களே நீண்ட காலத்துக்குப் பிறகு உருவானவை. ஆதலின் இதர ஆதாரங்களைக் கொண்டு இராமாநுஜருடைய காலத்தைப் புனராலோசனை செட்வது முற்றிலும் பொருத்தமானதே.

இவ்வாசாரியரின் வாழ்க்கையில் நிகழ்ந்த முக்கியமான சம்பவம் சோழ மன்னனுடைய மதத் துவேஷத்தால் அவர் ஸ்ரீரங்கத்தைத் துறந்து மைசூர்ப் பிரதேசத்துக்கு ஓடிப் போனது ஆகும். மதத்துவேஷம் கொண்டு அவரைத் துன்புறுத்திய சோழமன்னன் யார் என்பது ஐயந்திரிபற நிச்சயிக் கப்பெறவில்லை. பொதுவாக அவனை முதலாம் குலோத்துங்கன் என்று கொள்வர். அவனுக்கு முன் அரசாண்ட அதிராஜேந்திர தேவனாகவோ அல்லது அவன் தந்தையான வீர ராஜேந்திரனாகவோ இருத்தல் வேண்டும் என்று கொள்வாரும் உளர். குருபரம்பரை நூல்களிலே அவன் கிருமிகண்டசோழன் என்று குறிக்கப்பெறுகிறான். ஓர் இடத்தில் குலோத்துங்கன் என்ற பெயரும் காணப்படுகிறது. சோழ மன்னன் வைஷ்ணவர் களுக்கு விரோதமாக மதத் துவேஷம் கொண்டிருந்தான் என்பதை எடுத்துக்காட்ட இரண்டு சம்பவங்கள் குறிக்கப்படுகின்றன; ஒன்று அவன் (தில்லைச் சிற்றம்பலத்தே) சித்திர கூடத்தில் எழுந்தருளியிருந்த கோவிந்தராஜப் பெருமான் விக்கிரகத்தைப் பிடுங்கிக் கடலில் எறிந்தது. மற்றொன்று சிவாத் பரதரம் நாஸ்தி (சிவனையன்றி வேறு பரம்பொருள் இல்லை) என்று எழுதிய ஓலையில் இராமாநுஜரைக் கையெழுத்துச் சாற்றவேண்டுமென்று அவன் நிர்ப்பந்தித்தது.

இராமாநுஜரைக் கையெழுத்திடும்படி சோழ மன்னன் நிர்ப்பந்தித்த வரலாற்றைக் குருபரம்பரைகள் பின் வருமாறு கூறுகின்றன.

இராமாநுஜரைக் கங்கைகொண்ட சோழபுரத்திலிருந்த இராஜசபைக்கு அழைத்துச் செல்வதற்காக அரசாங்க ஊழியர்கள் ஸ்ரீரங்கத்துக்கு வந்தார்கள். இதையறிந்ததும், இராமாநுஜருடைய ஆசாரியர்களுள் ஒருவரான பெரியநம்பி என்பவர் தம் வெள்ளை ஆடையைக் களைந்து காஷாயம் பூண்டு தாமே இராமாநுஜர் என்று கூறிக்கொண்டு, கூரத்தாழ்வானுடன் சேவகர்களைப் பின்தொடர்ந்து இராஜசபைக்குச் சென்றார். இதனால் இராமாநுஜரும் காஷாயம் இல்லாமல் வெள்ளை ஆடை அணிந்து சோழநாட்டைத் துறந்து வெளியேறச் சிறிது அவகாசம் ஏற்பட்டது. அவரும் வெள்ளை ஆடை

உடுத்து வெளியேறி வழியிலே பல கஷ்டங்களை அனுபவித்துக் கடைசியாக ஹொய்சள தேசத்தைச் சென்றடைந்தார்.

அவருக்குப் பதிலாக, கூரத்தாழ்வானுடன் சோழராஜ சபைக்குச் சென்ற பெரியநம்பி அங்கே ஓலையில் கையெழுத்து இடவில்லை. அதற்குப் பதிலாகக் கூரத்தாழ்வான், ஓலையில் எழுதியிருந்த வாக்கியத்தின் அடியில் த்ரோணமஸ்தி ததி பரம் (அதற்குமேல் துரோணம் என்பது உண்டு) என்று எழுதினாராம். சிவம், துரோணம் என்ற சொற்கள் இரண்டும் (குறுணி, முக்குறுணி போன்று) முகத்தலுக்கான வெவ்வேறு அளவுகளின் பெயர். இவ்விதம் இருபொருள் கொண்ட சொற்களால் அவர் எழுதியது வேண்டுமென்றே இராஜசபையை அவமானம் செய்ததாகக் கருதப்பட்டது. அதன்மீது பெரிய நம்பி, கூரத்தாழ்வான் ஆகிய இருவரும் தங்கள் கண்களைப் பறிகொடுக்க நேர்ந்ததாம்.

பெரியநம்பி முதுமையை அடைந்திருந்தபடியால் அதைப் பொறுக்காமல் வேதனைப்பட்டு, தலைநகரத்திலிருந்து திரும்பும் வழியிலே நடுவில் உயிர் நீத்தார். இந்தச் சம்பவம் காளயுக்தி ஆண்டு நடந்ததாகக் குருபரம்பரைகள் கூறும்.

கூரத்தாழ்வானே கங்கை கொண்ட சோழ புரத்தின் நகர்ப்புறத்தே அரண்மனை வேலைக்காரி ஒருத்தியின் வீட்டிலே தன்னுடைய கண்ணின் புண் குணமாகும் வரையில் தங்கியிருந்து புண் நீங்கிக் குணம் ஏற்பட்டதும் ஸ்ரீரங்கத்தை அடைந்தார். இராமாநுஜர் அதற்கு முன்னதாக அந் நகரைத் துறந்து வெளியேறிவிட்டார். குருடரான கூரத்தாழ்வாருக்கு அங்கே தங்கியிருக்க இடம் கிடைக்கவில்லை. அதனால் மனம் கசந்த அவர் அவ்வூரை விட்டுக் கிளம்பித் திருமாலிருஞ்சோலையை அடைந்தார். அங்கே அவர் பதினொரு வருஷங்கள் தங்கியிருந்தாராம். ஹொய்சள நாட்டினின்றும் இராமாநுஜர் திரும்பி வந்த பிறகு, பழையபடியே இருவரும் ஒன்றாகக் கூடினாராம்.

பெரியநம்பி திருநாடு சென்ற காளயுக்தி வருஷத்தைக் கி. பி. 1078-79-க்குச் சரியாக வந்த ஆண்டாகவே கொள்வர்.

அது முதற் குலோத்துங்க சோழன் ஆட்சிக் காலமாகும். அவர் சோழர் தலைநகரான கங்கை கொண்ட சோழபுரத் துக்கு வந்த சிறிது காலத்துக்குள்ளாகவே இறந்துபட்டாராதலின், இராமாநுஜரைச் சோழமன்னன் நிர்ப்பந்தப்படுத்தியதும், அதற்குப் பணியவிரும்பாமல் சோழ நாட்டைத் துறந்து இராமாநுஜர் ஹொய்சள தேசத்தை அடைந்ததும் அந்த வருஷமே நடைபெற்றிருத்தல் வேண்டும் எனவும் கொள்வர்.

இராமாநுஜர் ஹொய்சள நாட்டிலே பன்னிரண்டு ஆண்டுகள் தங்கியிருந்தாராம். அதன் பிறகு அவரைத் துன்புறுத்திய சோழ மன்னன் (அதாவது முதற் குலோத்துங்கன்) இறந்துவிட்டான் என்ற செய்திகேட்டு அவர் திரும்பவும் ஸ்ரீரங்கத்தை வந்தடைந்தாராம். அதற்குப் பிறகே அவர்தம் சிஷ்யரான கூரத்தாழ்வானேடு சேர்ந்தது. அவர் ஹொய்சள தேசத்தில் இருந்த நாளில் அந்நாட்டு ஜைன மன்னனான பிட்டிகதேவனை வைஷ்ணவ மதத்துக்கு மாற்றித் 'தப்த முத்திரை' தரிக்கச் செய்து அவனுக்கு விஷ்ணுவர்த்தனன் என்ற பெயரையும் அளித்தாராம்.

குருபரம்பரை விவரப்படி பிட்டிகதேவன் முதலில் ஜைன மதத்தைப் பின்பற்றுபவனாக இருந்தான் என்றும் அவன் வைஷ்ணவ மதத்தையடைந்த பிறகு விஷ்ணுவர்த்தனன் என்ற பெயரைத் தரித்தான் என்றும் தெரியவருகிறது. ஆனால் சாசனங்களிலே அவனுடைய ஆட்சிக் காலத்தின் ஆரம்பத்திலிருந்தே, ஆட்சிக்காலம் முழுவதும் அவன் விஷ்ணுவர்த்தனன் என்று குறிக்கப் பெற்றிருப்பதைக் காணலாம். அன்றி, பிட்டி அல்லது பிட்டிகன் என்பதும் விஷ்ணு என்பதன் வேறு வடிவமே; பிராகிருதத்தின் வழியாக வந்ததாகும்.

இராமாநுஜர் தம்மைத் துன்புறுத்திய சோழ மன்னன் (அதாவது முதற் குலோத்துங்கன்) இறந்துபோன செய்தியைக் கேட்டபிறகே ஹொய்சள நாட்டிலிருந்து சோழதேசம் வந்தடைந்தார் என்பதானால் அவர் ஹொய்சள நாட்டில் தங்கியிருந்த காலம் பன்னிரண்டு ஆண்டுகளுக்கு மேலாக வரும். அம்மன்னன் கி. பி. 1170 ஆண்டு சிங்காதனம் ஏறி ஐம்பது ஆண்டுகள் அரசுபுரிந்திருக்கிறான். அதனால் அவன் இறந்து

போனது கி.பி. 1120-ஆண்டாகும். கி.பி. 1078-9-ஆம் ஆண்டுக்குச் சரியான காலயுக்தியில் இராமாநுஜர் சோழ தேசத்தை விட்டுப் புறப்பட்டுப் போய், கி. பி. 1120-ஆம் ஆண்டுக்குப் பிறகு அவர் திரும்பி வந்தார் என்பாராயின், அவர் வெளி தேசத்திலே தங்கிய காலம் நாற்பது ஆண்டுகளுக்கு மேலாகும். ஆயினும் குருபரம்பரைகளோ அந்தக் காலம் பன்னிரண்டு ஆண்டுகளே என்று கூறுகின்றன.

இராமாநுஜருடைய வாழ்க்கை வரலாற்றைக் கூறுவதாகப் பிள்ளை லோகஞ்சீயர் என்பார் இராமாநுஜார்ய தீவ்ய சரிதம் என்று தமிழிலே ஒரு நூல் எழுதியிருக்கிறார். அதிலே அவர் பழையநூல் ஏதோ ஒன்றிலிருந்து சில பாடல்களை மேற்கோளாக எடுத்து ஆண்டிருக்கிறார். அந்தப் பாடல்கள் எந்த நூலிலிருந்து எடுக்கப்பெற்றவை என்பதோ அந்த நூலை இயற்றியவர் யார் என்பதோ தெரியவில்லை. எனினும் அவை பழமை வாய்ந்தவை என்பது நிச்சயம்.

இராமாநுஜர் வேதாந்த சூத்திரங்கள் எனப்பெறும் பிரம்ம சூத்திரத்துக்குத் தாம் இயற்றிய ஸ்ரீ பாஷ்யத்தை எழுதப் பல தடவைகள் ஆரம்பித்திருக்கிறார். ஒவ்வொரு சமயமும் அது முற்றும் பூர்த்தியாகாமல் ஏதோ இடைபூறுகளால் நின்றுவிட்டது. சோழ நாட்டைத் துறந்து அவர் ஹொய்சள தேசம் போன சமயம் அது மூன்றில் இரண்டு கூறே முடிந்திருந்தது ; ஒரு கூறு பாக்கியிருந்தது. அந்த மூன்றில் ஒரு பகுதியை அவர் திரும்பவும் சோழ நாட்டை அடைந்து தம் சிஷ்யர் கூரத்தாழ்வானோடு கூடி அரங்கமாநகரில் வசிக்கத் துவங்கிய பின்னரே எழுதி முடித்தாராம். இவ்விதம் அவர் ஸ்ரீ பாஷ்யத்தை எழுதி முடித்தது சகாப்தம் 1077, அதாவது கி. பி. 1155-56-ஆம் ஆண்டாகும் என்று இராமாநுஜார்ய தீவ்ய சரிதையில் மேற்கோளாக எடுத்துக் காட்டப்பெற்ற செய்யுள் ஒன்று தெரிவிக்கிறது.

இன்ன வாறு திருப்பதிகள்  
எங்கும் வாழ்வித் தெதிராஜன்  
தன்ன தாக்கித் தரிசனமும்  
தரணி யெங்கும் விளங்குவித்து

முன்னம் உரைத்த பாடியத்தின்  
முற்ற மூன்றத் தொருகூறு  
தன்னைச் சென்றூண் டாயிரத்தாங்  
கேழுபத் தேழில் சாத்தினுன்.

(பக்கம்—243.)

குரு பரம்பரைகளில் காணும் சம்பிரதாயக் கணக்குப்படி அவர் சகாப்தம் 1059, அதாவது கி.பி. 1137-38-ஆம் ஆண்டில் பரமபதம் அடைந்தார். அப்படியானால் அவர் ஸ்ரீபாஷ்யத்தை எழுதிப் பூர்த்தி செய்தது அதற்கு முந்திய நிகழ்ச்சியாக இருத்தல் வேண்டும். ஆகவே அந்த ஆண்டு சகாப்தம் 1047 அதாவது கி.பி. 1125-26-ஆம் வருஷமாக இருத்தல் வேண்டும் என்று நிச்சயித்து, பாடலில் கண்ட சகாப்தத்தை முப்பது வருஷம் குறைத்துக் கணக்கிட்டார் ஸ்ரீ ராயர்.

எனினும் ஒரு விஷயத்தை நாம் முக்கியமாகக் கருதவேண்டும். இவ்வாசாரியப் பெருமானுடைய வாழ்க்கை வரலாற்றைத் தெரிவிக்கும் நூல்களிலே இம் மேற்கோள் செய்யுள்களில் காணும் சகாப்த வருஷமே காலமுறைப்படி மிகவும் பழமையான நூலைச் சேர்ந்ததாகும்; அன்றி, இவர் வாழ்க்கையின் இரு வேறு சம்பவங்களை எடுத்துக்கூறும் இடங்களில் அந்நூலிலே மேற்கோள் காட்டப்பெற்ற இரு வேறு செய்யுட்களில் குறிக்கப்பெறும் காலத்தை ஒத்ததாகவும் உள்ளது.

இராமானுஜர் ஹொய்சள தேசத்திலிருந்து ஸ்ரீரங்கம் திரும்பிய வரலாறு வேறு ஒரு பாடலில் காணப்படுகிறது.

ஆய்ந்த சகாப்த மாயிரத்தைம்  
பத்தொன்பதினீங்கி நின்றும்  
போந்து பதினே ராண்டிங்ஙன்  
புகழ்தான் வளர்ந்த பெரும்பூதூர்  
வேந்தன் எண்ணி லாஅன்ப  
ருடனும் அரங்க நகர்எய்திப்  
பாந்த ள்ணை(யில்) துயில்பரமன்  
பாதம் பணிந்தங் குறைந்திடுநாள்.

(பக்கம்—227.)

சகாப்தம் 1059-ஆம் ஆண்டில் ஸ்ரீரங்கத்தை விட்டுக் கிளம் பிய அவர் பதினேர் ஆண்டுகள் வெளி நாட்டிலே இருந்து விட்டுத் திரும்பவும் அரங்கப் பெருங்கரை அடைந்தார் என்று கூறுகிறது அந்தச் செய்யுள். அவர் ஹொய்சள தேசத்திலே தங்கியிருந்த காலம் பன்னிரண்டு ஆண்டுகள் என்று சம்பிரதாய நூல்கள் கூறுகின்றன. ஆனால் இந்தச் செய்யுளிலே அது பதினேராண்டுக் காலமே என்று தெளிவாகக் காணப் படுகிறது. இரண்டும் சரியானதாகத்தான் இருத்தல் வேண் டும். ஏதாவது ஒன்றைத் தவறெனத் தள்ள வேண்டியதில்லை. அவர் ஹொய்சள நாட்டிலே சென்றிருந்த இடத்தில் தங்கியது பதினேராண்டுகள் எனவும், மற்றும் ஓர் ஆண்டு ஸ்ரீரங்கத் திலிருந்து அவ்விடம் சென்றதிலும் மறுபடியும் திரும்பிவந்த திலும் செலவழிந்த காலமாகவும் இருக்கலாம்.

இவ்விதமே இருத்தல் வேண்டும் என்பது அதே நூலில் மேற்கோளாக எடுத்தாளப்பட்ட மற்றொரு செய்யுளிலிருந்து விளங்குகின்றது.

அன்றங் கிருந்த வருள்கூரத்  
தாழ்வா னரங்க நகரடைய  
அன்றெதி ராச னடியார்  
தம்மை வாசல் விடாதிருப்பச்  
சென்று திருமா லிருஞ்சோலைச்  
செல்வர் தம்மைத் தோத்திரம்செய்து  
ஒன்றி யழகர் தம்பதியில்  
பதினே ராண்டு றைந்ததற்பின்.

(பக்கம்—229.)

கங்கை கொண்ட சோழபுரத்திலிருந்து திரும்பிய கூரத்தாழ் வானுக்கு அங்கே புகவிடம் கிடைக்காததால் அவர் திரு மாலிருஞ்சோலையை அடைந்து அவ்விடத்திலே அழகரைப் பணிந்துகொண்டு பதினேராண்டுகள் வசித்தார் என்றும் அதற்குப் பிறகே தம் ஆசிரியரான இராமாநுஜரைச் சேர்ந் தார் என்றும் இந்தப் பாடல் கூறுகிறது. அவரும் தம் கண்ணை இழந்த பிறகு அந்தப் புண் ஆறுவதற்காகத் தலை நகரிலேயே நகர்ப் புறத்தில் அரண்மனைப் பணிப்பெண்



ஒருத்தியின் வீட்டில் சிறிது காலம் தங்கியிருந்தார். அதற்குப் பிறகே அவர் ஸ்ரீரங்கத்தை நோக்கிக் கிளம்பினார். இதனால் அவர் கங்கைகொண்ட சோழபுரத்தில் தம் கண்ணை இழந்த பின் திருமாலிருஞ்சோலையை அடைந்ததற்கு ஒரு வருஷ காலம் பிடித்திருக்கலாம் என்று கொள்வதில் தவறு இல்லை.

மேலே நாம் எடுத்துக்காட்டியுள்ள செய்யுளின்படி, இராமாதுஜர் சோழ நாட்டைவிட்டு மைசூர்ப் பகுதிக்குக் கிளம்பியது சகாப்தம் 1059 அதாவது கி.பி. 1137-38-ஆம் ஆண்டாகும். அவ்விதமாயின், பெரியநம்பி தம் கண்ணைப் பறிகொடுத்து அந்தக் கொடுமை தாங்கமாட்டாமல் உயிர் துறந்ததாகக் குறிக்கப்பெறும் காளயுக்தி ஆண்டு சகாப்தம் 1060 அல்லது கி.பி. 1139-39 ஆண்டுக்குச் சரியான காளயுக்தியே ஆகும். கண்ணைப் பிடுங்கிய உடனே பெரியநம்பி இறந்துபட்டார் என்று குறிக்கப் பெறவில்லை; சிறிது காலம் உயிர் தாங்கித் தலைநகரிலிருந்து ஊர் திரும்பும் வழியிலே ஓர் இடத்தில் உயிர் துறந்தார் என்று கூறப்படுகிறது. அன்றி, பெரியநம்பியும் கூரத்தாழ்வானும் இராஜ மனுஷ்யர்களுடன் ஸ்ரீரங்கத்தைவிட்டுக் கிளம்பிய வுடனே இராமாதுஜரும் அந்நகரத்தைத் துறந்து மைசூருக்குக் கிளம்பிவிட்டார். தலைநகருக்குக் கிளம்பிய பெரியநம்பியும் கூரத்தாழ்வானும் அதை அடைந்து, இராஜமனுஷ்யர்களுடன் விவாதத்தில் ஈடுபட்டுப் பார்வை இழந்ததற்குச் சிறிது காலமாவது பிடித்திருக்கும். ஆகவே இராமாதுஜர் சோழநாட்டை விட்டுப் புறப்பட்டது சகாப்தம் 1059-இன் கடைசியிலும், பெரியநம்பிகள் இறந்தது அடுத்த சகாப்தம் 1060-இன் ஆரம்பத்திலும் நடைபெற்றிருத்தல் சாத்தியமே. அவ்விதமாயின் இந்தச் சம்பவங்கள் கி.பி. 1138-ஆம் ஆண்டில் நிகழ்த்திருத்தல் வேண்டும்.

பன்னிரண்டு ஆண்டுகள் கழித்து ஹொய்சள தேசத் திலிருந்து இராமாதுஜர் சோழ நாடு திரும்பியது, தம்மைத் துன்புறுத்திய சோழ மன்னன் இறந்துவிட்டான் என்ற செய்தியைக் கேட்ட பின்னரே ஆகும் என்பர். அவ்விதமாயின், அவர் சோழ நாடு திரும்பியதாகக் கொள்ளக்கூடிய கி.பி. 1150-ஆம் ஆண்டுக்கு அணித்தாகவே அவரைத் துன்புறுத்திய சோழ மன்னன் இறந்துபோயிருத்தல் வேண்டும்.

அந்நாளிலே சோழ சிங்காதனத்தில் அமர்ந்திருந்தவன் இரண்டாம் குலோத்துங்கன் ஆவான். அவன் கி. பி. 1133-ஆம் ஆண்டில் மே மாதத்துக்கும் ஜூலை மாதத்துக்கும் இடைப்பட்ட காலத்தில் முடிசூட்டப் பெற்றான் என்று கணக்கிடப்பட்டுள்ளது. (எபி. இந்திகா, பத்தாம் வால்பூம், 135 பக்கம்; பதினேராம் வால்பூம், 287 பக்கம்). அவன் பதினாறு வருஷங்களுக்கு மேல் அரசு செலுத்தியிருக்கிறான்: தெலுங்கு தேசத்திலே கிடைக்கும் அவனுடைய சாசனங்களிலே ஆட்சி ஆண்டோடு சகாப்தமும் சேர்ந்துக் காணப்படுகிறது. அதைக் கொண்டு கவனிக்கும்போது அவனுடைய ஆட்சியின் பதினாறாம் ஆண்டு சகாப்தம் 1070-71 ஆகும் (தே. இ. சாசனங்கள், நான்காம் வால்பூம், 1044 நெ.; ஆறாம் வால்பூம், 134 நெ.). அவனுடைய ஆட்சியின் பதினேழாம் (1908-ஆண்டு 6 நெ. சாசனம்.) ஆண்டுக்கு மேற்பட்ட ஆண்டைக் கொண்ட சாசனம் இதுவரையில் கிடைக்கவில்லை. ஆகவே அவனது ஆட்சி கி. பி. 1150-ஆம் ஆண்டிலே முடிவடைந்திருத்தல் வேண்டும் என்று கொள்ளலாம்.

இரண்டாம் குலோத்துங்கன் சிவபெருமானிடத்திலே அதீதமான பக்தி கொண்டவன் என்பதையும் நாம் அறிவோம். அவன் தில்லையில் நடம்புரியும் எம்பெருமான் கோயிலை விஸ்தாரமாக்கினான். அதற்கு இடையூறுக இருந்த கோவிந்தராஜப் பெருமானாகிய விஷ்ணுவின் விக்கிரகத்தைப் பெயர்த்து எடுத்து 'அவருடைய வாசஸ்தலமான கடலுக்கே' அனுப்பிவைத்தானாம். இதை அவனுடைய ஆசிரியரும் ஆஸ்தானக் கவிஞருமான ஒட்டக்கூத்தர்,

“தில்லைத் திருமன்றின் முன்னிற் சிறுதெய்வத்  
தொல்லைக் குறும்பு தொலைத் தெடுத்து” —  
(கண்ணி-39)

என்று குலோத்துங்கசோழன் உலாவிலும்

“பொன்னிற் குயிற்றிப் புறம்பிற் குறும்பறுத்து  
முன்னர்க் கடலகழின் முழுகுவித்த—சென்னி”  
(கண்ணி-33)

என்று இராஜராஜசோழன் உலாவிலும்

“முன்றிற் கிடந்த கருங்கடல் போய்

முன்னைக் கடல்புகப் பின்னைத் தில்லை

முன்றிற் கிடங்கண்ட கொண்டன் மைந்தன்

மரகத மேருவை வாழ்த்தினவே.”

(தாழிசை 777)

என்று தக்கயாகப்பரணியிலும் தெளிவாக எடுத்துரைத்திருக்கிறார். தக்கயாகப்பரணியின் உரையாசிரியரும் இந்நிகழ்ச்சியைக் குலோத்துங்கன் புரிந்ததென்றே விளக்கமாகக் கூறுகிறார். அன்றி, இம்மன்னனுடைய ஆட்சியின் பதினான்காம் ஆண்டு கொண்டதாகத் தஞ்சாவூர் ஜில்லா ஆடுதுறைப் பிலிருந்து கிடைக்கும் கல்வெட்டு ஒன்றிலும் இந்தச் சம்பவம் குறிக்கப்பட்டிருக்கிறது. (1907-ஆம் வருஷத்தின் 363 நெ. சாசனம். இந்த விவரத்தைப் புகழ்ந்து உரைத்துக்கொண்டே இந்தக் கல்வெட்டு ஆரம்பமாவதாகத் தோற்றுகிறது. ஆயினும் அந்தப் பகுதி சிதிலமாக உள்ளது. அந்தக் கல்வெட்டின் மற்றப்பகுதி நல்ல நிலைமையில் இருப்பதைக் கவனிக்கும் போது இந்தப் பகுதி வேண்டுமென்றே சிதைக்கப் பெற்றிருத்தல் வேண்டும் என்று எண்ணத் தோன்றுகிறது.) இவ்விதம் சாசன வழக்கு, இலக்கிய வழக்கு ஆகிய இரண்டும் ஒருங்கே இதன் புகழை இரண்டாம் குலோத்துங்கனுக்கு ஏற்றிக்கூறுவது தெளிவாகும்.

[இவற்றைக் கவனிக்கும்போது இரண்டாம் குலோத்துங்க சோழன் தில்லையில் நடராஜப்பெருமான் ஆலயத்தை விஸ்தரித்து, திருப்பணி செய்த விவரத்தை எடுத்துக்கூறும் புலவர், ‘அவனுடைய முன்னோர்களிலே ஒருவன் செய்த செயலை அம்மன்னனுக்கு ஏற்றிக் கூறுகிறார்’ என்று கொள்ளமுடியாதென்பது தெளிவாக விளங்கும். இன்னும், அந்தக் கவிஞர் பெருமான் விக்கிரமசோழன், இரண்டாம் குலோத்துங்கன், இரண்டாம் இராஜராஜன் ஆகிய மூவருடைய அவைக்களத்தையும் அலங்கரித்தவர் என்பதையும், அம் மூவர் பேரிலும் தனித்தனியே உலாப் பிரபந்தம் பாடியுள்ளார் என்பதையும் நாம் அறிவோம். அவற்றுள் அவர் இந்தச் செயலை மற்றவர்களுக்கு ஏற்றிக் கூறாமல் இரண்டாம் குலோத்துங்கன் புகழாகவே உரைக்கிறார் என்பதையும் நாம் கருத்தில் கொள்ள வேண்டும்.]

இவ்விதம் கோவிந்தராஜப் பெருமாள் விக்ரகத்தைப் பிடுங்கிக் கடலில் எறிந்த சோழமன்னன் குலோத்துங்கனே யாவன் என்பதை வைஷ்ணவ சம்பிரதாய நூல்களும் தெரிவிக்கின்றன. இராமாநுஜராய தீவ்ய சரிதையில் இதுபற்றிக் குறைப் பாடல் ஒன்று மேற்கோள் கொடுக்கப்பட்டுள்ளது.

“ அம்பொற் குடைச் சகனயிரத்  
தோன்பதாம் வருஷத்துத் தென்பால்  
சென்னி குலோத்துங்கன் சித்திரகூடச்  
செங்கண்மால் தன்னை அலையெறி நாள்தான் ”

(பக்கம்-226)

இதிலே அம்மன்னன் சென்னி குலோத்துங்கன் என்று தெளிவாக உள்ளது. [இந்தப் பாடலின்படி கோவிந்தராஜரைக் கடலில் எறிந்த ஆண்டு சகாப்தம் 1009 ஆகும். அப்படியானால் அது கி.பி. 1087-8-ஆம் ஆண்டில் முதற் குலோத்துங்க சோழன் ஆட்சியின் முற்பகுதியில் நிகழ்ந்திருத்தல் வேண்டும். ஆனால், இந்தச் சம்பவம் இரண்டாம் குலோத்துங்கன் ஆட்சிக் காலத்தே நிகழ்ந்த தென்பதை நாம் மேலே கண்டோம். ஆகவே இந்தப் பாடலில் உள்ள ஆண்டு இரண்டாம் குலோத்துங்கன் சிங்காதனம் ஏறிய சகாப்தம் 1055-க்கும், இந்தச் சம்பவம் குறிக்கப்பட்டிருக்கும் அவனுடைய ஆடுதுறைக் கல் வெட்டின் ஆண்டான அவனது ஆட்சியின் பதினான்காம் வருஷத்துக்குச் சரியான சகாப்தம் 1038-க்கும் இடைப்பட்டதாக இருத்தல் வேண்டும். அது 1059-ஆம் ஆண்டேபோலும். அவ்விடம் மேற்கோள் கொடுக்கப்பட்டிருக்கும் பாடல் குறையாக உள்ளது. அதன் முழு உருவம் கிடைக்கவில்லை. அது கிடைக்குமானால் ஆண்டு என்னவென்பதை நிச்சயமாகக் கூற முடியும்.] இவற்றைக் கவனிக்கும்போது இராமாநுஜர் காலத்தில் ஆண்ட சோழமன்னன், வைஷ்ணவ மதத்துக்கு விரோதமாக இருந்தான் என்பதை எடுத்துக்காட்டக் குருபரம்பரை நூல்கள் கூறும் இரண்டு சம்பவங்களுள் ஒன்று இரண்டாம் குலோத்துங்கன் காலத்தில் நிகழ்ந்ததென்பது நன்கு விளங்கும். [இன்னும், குலோத்துங்கன் என்ற பெயரைப் பிற்காலத்துக் குருபரம்பரை நூல்கள் சோழர்களுடைய பொதுப் பெயராகக் கொண்டுள்ளன என்று கூறுவதும் ஏற்கக் கூடியதல்ல வென்பது தெளிவாகும்].

இதே சம்பவம்பற்றிக் குருபரம்பரை நூல்கள் கூறும் மற்றொரு நிகழ்ச்சியும் இதே முடிவை உறுதிப் படுத்துகிறது. சிதம்பரத்திலே கோவிந்தராஜப் பெருமான் கோயில் அழிக் கப் பெற்றபின், வைஷ்ணவ அடியார்கள் சிலர் அவருடைய விக் கிரகத்தை மீட்டுத் திருப்பதி எடுத்துச் சென்று அங்கே தங்கள் வீட்டில் வைத்துப் பாதுகாத்து வந்தார்களாம். இதைக் கேள்வியுற்ற இராமாநுஜர் ஒதுங்கவும் கூரையில்லாமல் திண் டாடும் எம்பெருமானுக்குத் திருப்பதியிலே ஒரு கோயில் கிர்மாணித்து அதிலே அவரைப் பிரதிஷ்டைசெய்து வைத் தாராம். இந்தக் கைங்கரியத்தில் அவரால் வைஷ்ணவ மதத்துக்கு மாறிய கட்டிடதேவ யாதவராயன் என்னும் வேந் தன் ஒருவன் அவருக்குப் பெரிதும் உதவியாக நின்றானும்.

திருப்பதியிலே இராமாநுஜர் தம் காரியத்தைச் செய்து முடிக்க உதவிய கட்டிடதேவன் என்பான் அந்நாளிலே திருப்பதி, காளஹஸ்தி ஆகிய இடங்கள் கொண்ட பகுதியை ஆண்டுவந்த யாதவராயர் என்னும் குறுநிலமன்னர் வம்சத்தைச் சேர்ந்த வன். இரண்டாம் குலோத்துங்கனுடைய ஆட்சியின் ஆறாம் ஆண்டு கொண்டதாகக் காளஹஸ்தியிலிருந்து கிடைக்கும் சாசனம் ஒன்றில் கட்டிடதேவனுன் குலோத்துங்க யாதவராயன் என்பான் பிராமணர்கள், தபஸ்விகள், மற்றும் இதரர் ஆகி யோருக்குக் கோயிலிலே உணவு அளிப்பதற்காக வீரமங்கலம் என்னும் கிராமத்தைத் தானம் அளித்த செய்தி காணப்படு கிறது. (1922-ஆம் ஆண்டின் 83-வெ. சாசனம்). இராமாநுஜர் திருப்பதியிலே கோயில் எழுப்ப உதவி புரிந்த கட்டிடதேவ யாதவராயன் இவனே போலும்.

இவ்வாசாரியர் வைஷ்ணவ மதத்தை நிலை நிறுத்திப் பரப்புவதற்காகச் செய்த கைங்கரியங்களுள் இதையே கடைசி யானதாகச் சம்பிரதாய நூல்கள் கூறுகின்றன. அதற்குள் ளாகவே அவர் மிகவும் முதுமைப் பருவம் அடைந்து விட்டார். இந்தச் சம்பவம் இரண்டாம் குலோத்துங்க சோழன் இறந்த பிறகு, இராமாநுஜர் மைசூர் நாட்டிலிருந்து சோழநாடு திரும் பிய பின் நிகழ்ந்ததாகவே இருத்தல் வேண்டும்.

வைஷ்ணவ மதத்தைப் பின்பற்றுபவர்கள் அனைவரும் சிவனே பரதேய்வம் என்று தெரிவிக்கும் ஒலையில் கையெழுத் திடவேண்டும் என்று சோழமன்னன் நிர்ப்பந்தித்தான் என்று

வ்வண்ணவ குருபரம்பரைகள் கூறும் இந்த வரலாறு வேறு எந்த இடத்திலும் சொல்லப்பெறவில்லை. அதனால் இந்தச் சம்பவமே உண்மையாக நடந்ததுதானா அல்லது மதவிஷயமாக அதிதமான வைராக்கியம் கொண்ட சிலருடைய கற்பனையாக இருக்குமா என்று சந்தேகிக்கவும் இடம் ஏற்பட்டுவிடுகிறது. எனினும், சேக்கிழார் எழுதிய திருத்தோண்டர் புராணம் என்னும் பெரியபுராணத்திலே காணும் ஒரு செய்யுள் இந்தச் சம்பவத்தைப் பிரதிபலிப்பதாக உள்ளது. அந்தப்புராணத்தில் வரும் திருஞானசம்பந்த சுவாமிகள் புராணத்தில் வருகிறது அந்தச் செய்யுள். மதுரையிலே பாண்டிய மன்னன் முன்னிலையில் திருஞானசம்பந்தருக்கும் சமணர்களுக்கும் நடந்த மூன்றாவது பரீட்சையிலும் சம்பந்தப் பெருமான் வெற்றிகொண்ட வரலாற்றைக் கூறும் இடத்தில் ஆசிரியர் சேக்கிழார் பின்வருமாறு கூறுகிறார்.

‘எம்பிரான் சிவனே எல்லாப்  
பொருளும்’என் நெழுதும் ஏட்டில்  
தம்பிரான் அருளால் வேந்தன்  
தன்னுமுன் ஓங்கப் பாட  
அம்புய மலரான் மார்பன்  
அனபாயன் என்னுஞ் சீர்த்திச்  
செம்பியன் செங்கோல் என்னத்  
தென்னன் கூன் நியிர்ந்த தன்றே.’

(செய்யுள்-847)

அந்த வரலாறு பின் வருமாறு: சம்பந்தர் பெருமானும் சமணர்களும் தங்கள் தங்கள் சமய உண்மைகளை ஒலையில் எழுதி அந்த ஒலைகளை வைகையில் இடவேண்டும். எந்த ஒலை வெள்ளத்தோடு அடித்துக்கொண்டு போகப் பெருமல் வெள்ளத்தை எதிர்த்து முன்னேறிச் செல்கிறதோ அந்த ஒலை கூறும் சமயமே உண்மையானது என்றும் அந்த ஒலையை எழுதியவர்களை வாதத்தில் வெற்றி கொண்டவர்கள் என்றும் தீர்மானிக்கப்படும். இவ்விதம் செய்த முடிவை ஏற்றுச் சம்பந்தர் பெருமான் வாழ்க அந்தணர் என்று தொடங்கும் பதிகத்தை எழுதி அந்த ஒலையை ஆற்றில் இட்டார். சமணர்கள் அத்தி நாத்தி (அஸ்தி நாஸ்தி: உண்டு இல்லை) என்று தங்கள் சமய உண்மையை எழுதிய ஏட்டை அதேபோல வைகை ஆற்றில்

இட்டார்கள். சம்பந்தர் இட்ட ஏடு வெள்ளத்தோடு செல்லாமல் வெள்ளத்தை எதிர்த்து முன்னேறிச் சென்றது. சமணர்களுடைய ஏடோ வெள்ளத்தோடு போய்விட்டதாம். இவ்விதம் நடந்த விவாதப் பேட்டியிலே சம்பந்தர் வெற்றிகொண்டாராம்.

இதைக் கூறுமிடத்தில் தான் வருகிறது இந்தச் செய்யுள். 'எம்பிரான் சிவனே எல்லாப்போருளும் என்று எழுதும் ஏட்டில் சம்பந்தர் பெருமான் வேந்தன் ஓங்க வேண்டும் என்று பாடிய தால், பாண்டிய மன்னனுடைய கூன் நிமிர்ந்து சோழ மன்னனுடைய செங்கோல் போல நேராக ஆயிற்று' என்று உரைக்கிறார் ஆசிரியர் சேக்கிழார். பெரிய புராணத்திலே இந்தச் செய்யுளுக்கு முன்னுள்ள பாடல்களிலே சம்பந்தர் தம் பதிகத்திலே எந்த எந்த விஷயங்களைக் குறித்துப் பாடியிருக்கிறார் என்பது தெளிவாகக் கூறப்பட்டுள்ளது. வேந்தனும் ஓங்குக என்று அவர் பாடியிருக்கிறார். இது பதிகத்தின் முதற் பாட்டிலேயே காணப்படுகிறது. ஆயினும் 'எம்பிரான் சிவனே எல்லாப் பொருளும்' என்பது அந்தப் பதிகத்தில் எந்த இடத்திலும் காணப் பெறவில்லை. பதிகத்தில் காணப் பெறாத ஒரு தொடரை—சைவ சமயத்தின் உள்ளுறை உண்மையைத் தெளிவாக எடுத்துக் கூறும் அந்தத் தொடரை—சேக்கிழார் தம் புராணத்தில் உபயோகித்திருப்பது கவனிக்கத்தக்கது.

பெரிய புராணத்தின் பாயிரத்திலே,

‘மேய விவ்வுரை கொண்டு விரும்புமாஞ்  
சேய வன்றிருப் பேரம்பலஞ் செய்ய  
தூய பொன்னணி சோழனீ டுழிபா  
ராய சீரந பாய நரசவை’

(பாயிரம்-8)

என்று காணப்படுவதிலிருந்து அது பேரம்பலத்துக்குப் பொன்வேய்ந்த சோழ மன்னன் அநபாயன் நாளையிலே இயற்றப் பெற்ற தென்பது தெளிவாகும். அதன் ஆசிரியர் சேக்கிழாருடைய வரலாற்றை எழுதிய உமாபதி சிவாசாரியார்,

நாடெங்குஞ் சோழன்முனந் தெரிந்தே யேற்று  
நற்குடிநாற் பத்தெண் ணயிரத்து வந்த  
கூடல்கிழான் புரிசைகிழான் குலவுசீர் வெண்  
குளப்பாக்கி ழான்வரிசைக் குளத்து ழான்முன்

தேடுபுக ழாரிவ்ருஞ் சிறந்து வாழச்  
சேக்கிழார் குடியிலிந்தத் தேச முய்யப்  
பாடல்புரி யருண்மொழித்தே வரும்பி னந்தம்  
பாலறு வாயரும்வந் துதித்து வாழ்ந்தார்

(சேக்கிழார் நாயனார் புராணம், செய்யுள்-12)

அத்தகைய புகழ்வேளாண் மரபிற் சேக்கி  
ழார் குடியில் வந்தவருண் மொழித்தே வார்க்குத்  
தத்துபரி வளவனுந்தன் செங்கோ லோச்சுந்  
தலைமையளித் தவர்தமக்குத் தனது பேரும்  
உத்தமச்சோ முப்பல்ல வன்று னென்று  
முயர்பட்டங் கொடுத்திடவாங் கவர்நீர் நாட்டு  
நித்தனுறை திருநாகே சுரத் திலன்பு  
நிலைதலினுன் மறவாத நிலைமை மிக்கார்

(ஷே செய்யுள்-18)

என்று கூறிச்செல்கிறார். இதிலிருந்து பெரிய புராண ஆசிரியர்  
குன்றத்தூரில் சேக்கிழார் மரபில் பிறந்தவர் என்பதும், அருண்  
மொழித்தேவர் என்ற பெயரைப் பெற்றவர் என்பதும், பாலறு  
வாயர் என்னும் தம்பியை உடையவர் என்பதும், உத்தம  
சோழப் பல்லவன் என்ற பட்டத்தோடு சோழ மன்னனுக்கு  
மந்திரியாக விளங்கியவர் என்பதும் தெரியவரும். இரண்டாம்  
குலோத்துங்கனுடைய ஆட்சியின் இரண்டாம் ஆண்டு கொண்ட  
தாகத் தஞ்சாவூர் ஜில்லா கோட்டுரிலிருந்து கிடைக்கும் கல்  
வெட்டு ஒன்று குன்றத்தூர் சேக்கிழார் பாலறுவாயன் களப்  
பாளராயன் என்பான் ஒருவன் விளக்கெரிக்கப் பொன்  
கொடுத்த செய்தியைத் தெரிவிக்கிறது. (1912-ஆம் ஆண்டின்  
445 நெ. சாசனம்). பெரிய புராண ஆசிரியரின் தம்பியே  
போலும் இவ் வதிகாரி.

இவற்றால் பெரிய புராணம் இயற்றிய சேக்கிழார் இரண்  
டாம் குலோத்துங்க சோழன் ஆட்சியில் அரசாங்கத்தே உயர்  
பதவி வகித்தார் என்பது தெளிவாகும். சைவ சமயத்துக்காக  
மன்னன் புரிந்த திருப்பணிகள் எல்லாவற்றையும் அவர் அறிந்  
திருப்பார். இந்நிலையை அறிந்து கவனித்துப் பார்த்தால் அவர்  
தம் புராணத்திலே இந்தப் பகுதியை எழுதும்போது சோழ  
மன்னன் 'சிவன் அன்றி வேறு பொருள் இல்லை' (சிவாத்



பரதரம் நாஸ்தி) என்று பிறமதத்தினர் அனைவரும்—முக்கிய மாக வைஷ்ணவ மதத்தைப் பின்பற்றுகிறவர்கள்—ஒலையில் எழுதிக் கையெழுத்திட வேண்டும் என்று வற்புறுத்திப் பெற்று வந்ததை மனத்தில் கொண்டிருக்க வேண்டும். இல்லாவிட்டால் சம்பந்தர் பதிகத்தில் காணாத இவ்வாக்கியத்தைப் புராணத்தே இந்தச் சந்தர்ப்பத்தில் உபயோகித்ததற்குப் பிரமேயமே இல்லை என்னலாம்.

இராமாநுஜருடைய வாழ்க்கையின் கடைசி நாட்கள் அதிகமான தொந்தரவுகள் ஏதும் இல்லாமல் அமைதியாகக் கழிந்தன வென்று தெரிகிறது. அந்நாளில் அரசு புரிந்த சோழ மன்னன் அவரை ஆதரித்து வந்தான் என்றும் வைஷ்ணவ சம்பிரதாய நூல்கள் கூறுகின்றன. அவரும் முதுமை அடைந்து விட்டதால் தமக்குப் பிறகு தாம் மேற் கொண்ட சமயத் திருப்பணியை நடத்திச் செல்லக் கூடத்தாழ் வான் குமாரராகிய பரர்சர பட்டரை ஆசாரியராக நியமனம் செய்தார். பின்பழகிய பெருமாள் ஜீயர் இயற்றியதும் ஆரூர்ப் படி என்று பிரசித்தமாக வழங்கப் பெறுவதுமான குருபரம் பரையிலிருந்து பட்டருடைய நாளில் சோழ சிங்காதனத்தில் அமர்ந்திருந்தவன் திரிபுவனவீரதேவராயன் என்ற பெயர் கொண்டவன் என்று தெரிகிறது. திரிபுவனவீரன் என்பது மூன்றாம் குலோத்துங்கனுடைய விருதுகளுள் ஒன்றாகும். அவனுடைய சாசனங்கள் பல அந்தப் பெயரையே குறிக்கின்றன. அவன் கி.பி. 1178-ஆம் ஆண்டு முதல் கி.பி. 1217-ஆம் ஆண்டு வரையில் நாற்பது வருஷங்கள் அரசு செலுத்தியிருக்கிறான்.

பட்டர் அதிகநாள் உயிரோடு இருக்கவில்லை யென்றும் சீக்கிரமாகவே திருநாடு அலங்கரிக்கச் சென்று விட்டார் என்றும் ஸ்ரீவைஷ்ணவர்கள் சொல்வர். இதை யொட்டியே அவர் தம்முடைய இருபத்தெட்டாம் வயதில் இறந்தார் என்று அண்ணா அப்பங்கார் தம்முடைய பழநடை விளக்கத்திலே கூறியிருக்கிறார். (கோபிராத ராயர் நூலில் 40-ஆம் பக்கம் பார்க்க). இருபத்தெட்டு என்பதை அவருடைய வயசாகக் கொள்ளாமல் ஆசாரிய பதவி வகித்த வருஷமாகக் கொள்வர் சிலர். எவ்வித மாயினும், இதைக் கொண்டு பட்டர் இராமாநுஜருக்குப் பிறகு நீண்ட காலம் ஆசாரியராக விளங்காமல் சீக்கிரமாகவே இறந்துவிட்டார் என்று கொள்ளலாம்.

பட்டருக்குப் பின் நஞ்சியர் வந்தார். அவருக்குப் பிறகு நம்பூர் வரதராஜர் பட்டத்துக்கு வந்தார். அவர் நம்பிள்ளை எனப்படுவார்; பின்னால் லோகாசாரியர் என்றும் வழங்கப் பெற்றவர். சகாப்தம் 1175, அதாவது கி.பி. 1253-ஆம் ஆண்டு ஜடாவர்மன் சுந்தரபாண்டியன் ஸ்ரீரங்கம் கோயில் கர்ப்ப கிருகத்துக்குப் பொன் வேய்ந்த நாளில் நம்பிள்ளை ஜீவிய தசையில் இருந்தார் என்று கோயிலோழுது தெரிவிக்கிறது. இவற்றைக் கவனித்தால் இராமாநுஜர் இரண்டாம் குலோத்துங்கன் காலத்தில் இருந்திருக்கவேண்டும் என்பது தெரிய வரும்.

சற்றேறக்குறைய இதே காலமுறையைத்தான் டாக்டர் எஸ். கிருஷ்ணஸ்வாமி ஐயங்காரும் ஏற்றிருக்கிறார். சிதம்பரம் கோவிந்தராஜப் பெருமானைப் பிடுங்கிக் கடலில் எறிந்த சோழ மன்னன் இரண்டாம் குலோத்துங்கனே யாவன் என்று அவர் கொண்டிருக்கிறார். அன்றி, இராமாநுஜருடைய கால வரையறையைப்பற்றி அவர் பின்வருமாறு எழுதுகிறார்: “கி. பி. 1119-ஆம் ஆண்டில் அவர் (அதாவது இராமாநுஜர்) நூற்றிரண்டு வயதானவராகில், அதற்கப்பால் அவர் பதினெட்டு ஆண்டுகள் உயிர்வாழ்ந்திருத்தல் வேண்டும். ஆகவே அவர் கி. பி. 1139-ஆம் ஆண்டுக் கணித்தாகக் காலஞ்சென்றிருக்கவேண்டும். ஆயினும் இரண்டாம் குலோத்துங்க சோழன் சிங்காதனம் ஏறிய காலம் நமக்கு நிச்சயமாகத் தெரியும். அதைக்கொண்டு பார்த்தால் இராமாநுஜர் கி. பி. 1139-ஆம் ஆண்டுக்கு அணித்தாகக் காலம் சென்றார் எனக் கொள்வது பொருந்தாது; அதற்குப் பிறகே நிகழ்ந்திருத்தல் வேண்டும். ஆயினும் நாம் ஏற்கெனவே குறிப்பிட்டுள்ளபடி இவ்வாசாரியருடைய வாழ்க்கைச் சம்பவங்கள் பதினைந்து பதினாறு வருஷங்கள் முன்னதாகக் கணக்கிடப்பட்டுள்ளனவென்று எடுத்துக்கொள்வோமான்ால், அவர் பரகதி அடைந்த ஆண்டு கி.பி. 1155-ஆம் வருஷமாகவே ஆகும். இதுவே சரியான காலமாக இருத்தல் கூடும்.” (திருப்பதி வரலாறு, முதல் பாகம், 287-பக்கம்).

இந் நிலையிலே மற்றொரு விஷயத்தையும் நாம் கவனிக்க வேண்டும். இவ் விஷயத்தைப்பற்றி இதுகாறும் ஆராய்ந்த ஆசிரியர்கள் எல்லோரும் திவ்யசூரி சரிதம், யதிராஜ வைபவம்

ஆகிய இரண்டுமே இராமாநுஜருடைய வாழ்க்கை வரலாற்றைத் தெரிவிக்கும் நூல்களுள் மிகவும் பழமையானவை என்று எடுத்துக்கொண்டிருக்கிறார்கள். அவற்றுள்ளும் திவ்ய சூரி சரிதம் என்பது இராமாநுஜர் உயிருடன் இருந்த காலத்திலேயே எழுதப்பட்டதென்றும் முடிவு செய்திருக்கிறார்கள். ஆயினும் சமீப காலத்திய ஆராய்ச்சிகளிலிருந்து அவை பிற்பட்டவை என்றே கொள்ளவேண்டியிருக்கிறது. (திவ்விய சூரி சரிதத்தின் காலத்தைப்பற்றி ஜர்னல் ஆப் இந்தியன் ஹிஸ்டரி, பதின்மூன்றாம் வால்யூம், இரண்டாம் பாகம் பார்க்க. மற்றதைப்பற்றி இந்தியன் ஆண்டிதவரி, நாற்பதாம் வால்யூம், 152-ஆம் பக்கம் பார்க்க.)

இதுகாறும் நாம் கூறியவற்றிலிருந்து இராமாநுஜருடைய வாழ்க்கை வரலாறு பற்றிக் கிடைக்கும் ஆதாரங்களுள் இராமாநுஜர் திவ்ய சரிதையில் மேற்கோளாகக் காட்டப்பெற்ற தமிழ்ச் செய்யுள்களே மிகவும் பழமையானவை என்பதும், அவருடைய வாழ்க்கைச் சம்பவங்களைச் சரியான ஆண்டுக் கணக்கோடு எடுத்துக் கூறுபவை வென்பதும், அவருடைய வாழ்க்கைச் சம்பவங்களில் முக்கியமானவை சில நிகழ்ந்த ஆண்டுகள் பின்வருமாறு அமையும் என்பதும் தெளிவாகும்.

(1) இராமாநுஜர் காலத்திலே ஆட்சி புரிந்து வைஷ்ணவர்களுக்கு விரோதமான மதத் துவேஷத்தால் அவர்களைத் துன்புறுத்திய சோழ மன்னன் இரண்டாம் குலோத்துங்கன் ஆவான்.

(2) சோழ நாட்டைத் துறந்து இராமாநுஜர் ஹொய்சன் தேசம் சென்றது கி. பி. 1138-ஆம் ஆண்டு ஆகும்.

(3) பன்னிரண்டு வருஷங்கள் கழித்து, தம்மைத் துன்புறுத்திய சோழ மன்னன் இறந்துவிட்டான் என்று கேட்ட பிறகு அவர் சோழ நாடு திரும்பியது கி. பி. 1150-ஆம் ஆண்டு ஆகும்.

(4) மைசூரிலிருந்து திரும்பிய பின் அவர் ஸ்ரீபாஷ்யத்தைப் பூர்த்தி செய்தது ககாப்தம் 1077, அதாவது கி. பி. 1155-56-ஆம் ஆண்டு ஆகும்.

## பிற குறிப்பு:

I. திரிபுரி நகரத்தைத் தலைநகராகக்கொண்டு ஆண்டுவந்த சேதி மன்ன னான காங்கேயன் என்பான் கி. பி. 1041-ஆம் ஆண்டு பிரயாகையில் தன்னு டைய தேவிமார் நூறுபேருடன் முக்தி பெற்றான் என்று கூறப்படுகிறது. அவன் அங்கே புண்ணிய தீர்த்தத்தில் மூழ்கி உயிர் துறந்திருத்தல் வேண்டும் என்பதையும், அவ்விதம் அவன் செய்ததற்குப் பரமார வேந்தனான போஜ ராஜனும் சோழமன்னனும் சேர்ந்து அவனைத் தாக்கிப் பெருவெற்றி கொண்டதே காரணமாக இருத்தல் வேண்டும் என்பதையும் நாம் மேலே ௪௮, ௪௮-ஆம் பக்கங்களில் குறிப்பிட்டிருக்கிறோம். திருநெல்வேலி ஜில்லா அம்பாசமுத்திரம் தாலுகாவில் உள்ள திருவாலீச்வரத்திலிருந்து கிடைக்கும் ஒரு கல்வெட்டு (1905-ஆம் ஆண்டு 120-௧௨. சாசனம்) இதனை வலியுறுத்து கிறது. மூன்றுகை மஹாசேனை என்னும் போர்ப்படையின் வரலாற்றைத் தெரிவிக்கும் அந்தக் கல்வெட்டிலே அந்தப் படையினர் காங்கேயனைக் கொன்ற னர் என்று புகழப்படுகிறார்கள். “அந்த மஹா சேனையார் விஷ்ணுவையும், சிவபெருமானையும் சதா வழிபட்டு வருகிறவர்கள் என்றும், கன்னரனைத் தோற்கடித்து அவனைத் துரத்திச் சென்றவர்கள் என்றும், காங்கேயனைக் கொன்றவர்கள் என்றும், கல்மடத்தைக் கைப்பற்றிக் கடற்கரையில் உள்ள விழிஞத்தை அழித்தவர்கள் என்றும், கடல் கடந்து சென்று மறுகரையில் உள்ள மாதோட்டத்தைத் தரைமட்டமாக்கினவர்கள் என்றும், மலைநாடு கைக்கொண்டவர்கள் என்றும், சாலைக் கலமறுத்தவர்கள் என்றும், வல்லானை (சாளுக்கியனை) விரட்டி வனவாசியைக் கைப்பற்றியவர்கள் என்றும், இந்த அரிய செயல்களுக்காகக் காளஹஸ்தியில் உள்ள தமிழ்க் கவிஞர்களால் புகழ்மாலை சூடப் பெற்றவர்கள் என்றும் அந்தக் கல்வெட்டுக் கூறுகிறது.” (க. அ. நீலகண்ட சாஸ்திரிகள் எழுதிய சோழர் சரித்திரம், இரண்டாம் பாகம், 226-ஆம் பக்கம்). அந்தச் சாசனத்தின் காலம் குறிக்கப் பெறவில்லை. எனினும் அது முதலாம் இராஜேந்திர சோழனுடைய மக்களின் ஆட்சிக் காலத்தைச் சார்ந்தது என்று நிச்சயமாகக் கூறலாம். இதிலிருந்து சோழர் கள் வடக்கே போர் நடத்திச் சேதி மன்னனான காங்கேயனை வெற்றி கொண்டு அவனை உயிர் துறக்கச் செய்தார்கள் என்பது உறுதியாகிறது.

II. இடங்கை வகுப்பாரைப்பற்றிக் கல்வெட்டுக்களிலே நீண்டகாலமாகக் குறிக்கப்பட்டிருப்பினும் அவர்கள் போர்ப் படையோடு தொடர்பு கொண்ட தாகத் தெரிவிக்கும் கல்வெட்டு ஒன்றும் இதுவரையில் கிடைக்கவில்லையென்று மேலே ௬௫-ஆம் பக்கத்தில் குறிப்பிட்டிருந்தோம். எனினும் சித்தூர் ஜில்லா வில் வேலஞ்சேரியிலிருந்து கிடைத்துள்ள ஒரு கல்வெட்டு (1942-43-ஆம் ஆண்டு 115-௧௨.) இடங்கை மகாசேனையைக் குறிப்பிடுகிறது. அவ்வூரி லிருந்தும் அதன் படாக்கைகளிலிருந்தும் வகுலாகும் இடங்கை வரியை வேளிறஞ்சேரியில் உள்ள தக்ஷிணமூர்த்தி, அழகியபெருமாள் ஆலயங்களின் ஜீர்ணோத்தாரணத்துக்குச் செலவிடுவதாக இடங்கை மகா சேனையார் முடிவு செய்ததை எடுத்துக்கூறுகிறது அந்தக் கல்வெட்டு.

## தமிழ்நாட்டுச் சாசனங்கள்

### 1. சாசனங்கள்

நம் நாடு மிகப் பழங்காலத்திலிருந்தே புண்ணியபூமி கர்மபூமி என்று குறிக்கப்பட்டுவருகிறது. உலகத்தில் உள்ள மற்ற எல்லா வகுப்பாரையும்விட நம் மக்கள் மதவுணர்ச்சியால் மிகவும் கட்டுப்பட்டவர்கள் என்பதை யாவரும் அறிவர். அதனால் இத்தகைய மதப்பற்று உள்ள நாட்டில் கோயில்கள் அதிகமாகக் காணப்படுவது அதிசயமன்று. அதிலும் வடநாட்டைக் காட்டிலும் தென் இந்தியாவில் கோயில்கள் அதிகம். வட இந்தியாவில் கோயில்கள் கட்டாமல் இல்லை. முன்காலத்தில் அங்கே பல கோயில்கள் இருந்தனவென்று தெரிகிறது. ஆயினும் பிற்காலத்தில் பிற நாட்டவர்களும், பிற மதத்தினரும் நம் நாட்டின் மீது அடிக்கடி படையெடுத்து வந்து அக் கோயில்களை அழித்துவிட்டனர். தென்னாட்டுக்கு அந்த விதமான தூதிரிஷ்டம் நேரிடாமையால் இங்கே கட்டிய கோயில்கள் தப்பிப் பிழைத்தன.

‘கோயில் இல்லா ஊரில் குடியிருக்க வேண்டாம்’ என்று ஒரு முதுமொழி உண்டு. தமிழ் நாட்டிலே உள்ள ஒவ்வொரு கிராமத்திலும் குறைந்தபட்சம் ஒரு கோயிலாவது பார்க்கலாம். ஒரு விஷ்ணு ஆலயமோ, ஒரு சிவன் கோயிலோ, ஒன்றும் இல்லாவிட்டால் ஒரு பிள்ளையார் கோயிலோ பிடாரி கோயிலோ ஏதாவது ஒன்று இருக்கும். ‘கோயில்கள் நிறைந்த பிரதேசம்’ என்று தென்னாட்டைக் கூறுவது மிகவும் பொருத்தமாகும்.

தமிழ் நாட்டில் உள்ள பெரிய கோயில்களில் பல பண்டைக் காலத்தே நம் நாட்டை ஆண்டுவந்த மன்னர்கள் கட்டியவையாகும். அவர்கள் அந்தக் கோயில்களுக்கும், கற்றறிந்த பண்டிதர்களுக்கும் பல தானங்களைச் செய்திருக்கிறார்கள். அவ்விதம் கொடுத்த தானத்தைப் பெற்றவர்கள் அவற்றை நீண்டகாலம் அனுபவிக்கவும் தங்களுக்குப் பின்னாலவரும் அரசர்கள் அந்தத் தானங்களைத் தவிர்க்காமல் இருக்கவும், அந்த அரசர்கள் அவற்றைப் பிரபலமான இடங்களில் கல்விலை பொறித்து வைத்துச் சென்றார்கள்.

நம் நாட்டில் உள்ள விஷ்ணு ஆலயங்களும், சிவன் கோயில்களும் பெரும்பாலும் கருங்கற்களால் கட்டப்பட்டுள்ளன. அவ்விதமான கோயில்களின் சுவர்களில் நான்கு புறங்களிலும் அந்தக் காலத்து எழுத்துகளில் ஏதோ பொறிக்கப்பட்டிருப்பதை நாம் காண்கிறோம். அவற்றில் பெரும்பாலானவை அந்த அரசர்கள் வழங்கிய தானங்களைத் தெரிவிப்பனவேயாகும். அவை பொதுவாகச் சாசனம் என்ற பெயரால் குறிக்கப்படும்.

ஆனால் முன்னாளிலே கோயில்கள் பெரும்பாலும் செங்கல்லும் சுண்ணாம்பும் கொண்டே கட்டப்பட்டு வந்தன. அதனால் அந்தச் சாசனங்களை அந்நாளிலே தனிக் கருங்கற்களில் பொறித்து அந்தக் கற்களைக் கோயிற் சுவர்களில் பதித்தோ பிராகாரங்களில் நட்போ வைத்து வந்தார்கள். பின்னால் அக்கோயிற்களைக் கற்றளிகளாக மாற்றியபோது அந்தச் சாசனங்களைக் கோயிற் சுவர்களில் பொறித்துவைத்தார்கள். பழைய கோயிலைப் புதுப்பிக்கும்போதும் அதன் சுவரில் காணப்படும் சாசனங்களுக்குப் படி எடுத்து வைத்திருந்து பின்னால் ஜீர்னோத்தாரண வேலை முடிந்ததும் அவற்றைப் பழையபடியே சுவரில் பொறித்து விடுவார்கள்.

இத்தகைய சாஸனங்கள் கோயில் சுவர்களில் மட்டுமன்றித் தூண்களிலும், விக்கிரங்களின்மீதும், அவற்றின் பீடங்களிலும், ஊர்ப்புறத்தே நிறுவப்பட்ட விஜயஸ்தம்பங்களிலும், மற்றும் ஒங்கியுயர்ந்த பாறைகளிலும் பொறிக்கப்பட்டிருப்பதைக் காண்கிறோம். கருங்கல்லில் வெட்டப்பட்டுள்ள சாசனங்கள் கல்வெட்டு, சிலாசாசனம், சிலாலேகை, கல்லெழுத்து, சாசனம் என்பன போன்ற பலபெயர்களாலும் குறிக்கப்பட்டுள்ளன. சில சமயங்களில் பிரசஸ்தி என்றும் குறிக்கப் பெறும்.

கல்லில் பொறிக்கப்பட்டவற்றுள் தானம் அளித்த செய்தியைத் தெரிவிக்காமல் வழிபாட்டு முறையிலே உள்ளனவும் உண்டு. பெரும்பாலும் அவை புண்ணியஸ்தலங்கள் போன்ற இடங்களுக்குத் தாங்கள் வந்ததன் அறிகுறியாகவும் வழிபாடாகவும் யாத்திரிகர்கள் தங்கள் பெயரை வெட்டிச் சென்றதாகவே இருக்கும்; மற்றும் சில சமயங்களில் சிறு பலகைகளாகவும் உருவங்களாகவும் இருத்தல் உண்டு. விக்கிரகங்கள் சிற்பங்கள் ஆகியவற்றின் விளக்கமான கல்வெட்டுக்களும் காணப்படுகின்றன.

சாசனங்கள் பாறைகளில் வெட்டப்பட்டது போலவே செப்பேடுகளிலும் பொறிக்கப்பட்டுள்ளன. அவை சில பழைய குடும்பத்தாரிடமிருந்தும் பூமிக்குள்ளிருந்தும் கட்டிடங்களின் அஸ்திவாரங்களிலிருந்தும் கிடைக்கின்றன. அவை தாம்ரசாசனம், தாம்ரப்பட்டயம் செப்புப்பட்டயம், செப்பேடு என்ற பெயர்களாலும் அடைமொழி ஏதும் இல்லாமல் வெறுமே பட்டயம் என்றும் குறிக்கப்படுகின்றன.

சாசனம் பெரியதாக இருந்து ஒன்றுக்கு மேற்பட்ட தகடுகளை உடையதாக இருந்தால், அவற்றுள் துளையிட்டு ஒரு வளையத்தால் கோத்து அவற்றைப் பிணைத்திருப்பார்கள். அந்த வளையத்தின் இரு முனைகளையும் சேர்க்கும்படித் தாள் அரகாங்க முத்திரையும் இருக்கும். அந்த முத்திரையில் தானத்தை வழங்கிய அரசன் பெயருடன், அவன்

விருது, கொடி முதலிய வெற்றிச்சின்னங்களும் காணப்படும். செம்பைத் தவிர, தங்கம், வெள்ளி, பித்தளை, ஈயம் முதலிய உலோகங்களால் ஆன தகடுகளிலும் சாசனங்கள் எழுதப்பட்டிருக்கின்றன. அவ்வாறே, கருங்கற்கள் மட்டுமன்றி மண் பாண்டம், செங்கல், சுட்டமண், பளிங்குக்கல் முதலிய பொருள்களின் மீதும் சாசனங்கள் பொறிக்கப் பட்டுள்ளன.

பழைய காலத்தனவாகக் கிடைக்கும் தங்கம், வெள்ளி, செம்பு ஆகிய உலோகங்களில் செய்யப்பட்ட நாணயங்களிலும் எழுத்துக்கள் காணப்படுகின்றன. அவை அந்த நாணயங்களை அடித்து வழங்கிய அரசன் போன்றோர் பெயரைத் தெரிவிக்கின்றன. அவை ஒரு தனிவகை; நாணயவியல் என்பதில் அடங்கும். அந்த எழுத்துகளைச் சாசனம் என்று நாம் குறிப்பிடுவதில்லை; அவை சாசனங்களும் ஆகா. ஆகவே அவை இவ்வாறாய்ச்சியில் சேரவில்லை.

சாசனம் என்னும் வடமொழிச் சொல்லுக்கு உத்தரவு, கட்டளை என்று பொருள். இப்போது கல்லிலும், செம்பிலும் பொறிக்கப் பட்டுக் காணப்படும் சாசனங்களுள் பெரும்பாலானவை பண்டைக் காலத்திலே நம் நாட்டை ஆண்ட மன்னர்கள் கோயில்களுக்கும், வித்வான்களுக்கும் அளித்த தானங்களைப் பற்றிய உத்தரவுகளே ஆகும். முதலில் அரசன் உத்தரவையே குறித்துவந்த 'சாசனம்' என்னும் சொல் நாளடைவில் தானம் பெற்றவர்கள் நிலத்தை அனுபவிப்பதற்கு ஆதாரமாகக் கொண்ட பத்திரங்களைக் குறித்துக் கடைசியாக இப் பொழுது பொதுவாகக் கிரயபத்திரத்தையே குறிக்கிறது.

பழைய சாசனங்கள் அநேகமாக உளிகொண்டு செதுக்கியே வெட்டப்பட்டிருக்கும். மையினால் எழுதப்பட்டனவும் சில உண்டு.

நமக்குக் கிடைக்கும் சாசனங்கள் எல்லாம் முற்காலத்து அரசர்கள் வழங்கிய தானங்களை மட்டுமே தெரிவிப்பன அல்ல. அரசர்களைப் போலவே அரசாங்க உத்தியோகஸ்தர்களும் மற்றும் பலரும் வழங்கிய தானங்களையும், உள்நாட்டு மக்கள் ஒருவர்க்கொருவர் செய்துகொண்ட பரிவர்த்தனைகளையும் அவற்றுள் சில அறிவிக்கின்றன. தானங்களை அன்றி, மக்களின் நன்மையைக் கருதிக் குளம் வெட்டியது போன்ற செய்திகளைத் தெரிவிக்கும் சாசனங்கள் உண்டு.

இவ்விதமாகப் புண்ணியத்தை எதிர்பார்த்துச் செய்தவற்றோடு உண்மைச் சரித்திர நிகழ்ச்சிகளும், சரித்திர சம்பந்தமே இல்லாத இலக்கியப் பகுதிகளும் கல்லிலும் செம்பிலும் பொறிக்கப்பட்டுக் காணப்படுகின்றன.

தானம் வழங்கப்பட்டதை அறிவிக்கும் சாசனங்கள் பெரும்பாலும் ஹிந்து தர்மசாஸ்திரங்களிலும், தான காண்டத்திலும் கொடுத்துள்ள விதிகளைப் பின்பற்றியே எழுதப்பட்டுள்ளன. எனினும் கல்வில வெட்டப்பட்டுள்ளவற்றுக்கும் செம்பில் பொறிக்கப்பட்டுள்ளவற்றுக்கும் மிகுந்த வேறுபாடுகள் உண்டு.

கல்வில உள்ள சாசனங்கள் பொதுவாக அந்த அந்த நாட்டு மொழியிலேயே எழுதப்பட்டிருக்கும். தமிழ் நாட்டுச் சாசனங்களில் பெரும்பாலானவை தமிழ் மொழியில் உள்ளன. அதுவும் வசன நடையில் இருக்கும். சிற்சில சமயங்களில் அவை வடமொழியில் இருப்பதும் உண்டு. தானம் அளித்தவர்கள் பிறநாட்டவர்களாக இருக்கும் போது ஏதோ சில சமயங்களில் அச் சாசனங்கள் அவர்களுடைய நாட்டு மொழியிலே காணப்படுவதும் உண்டு. செப்பேடுகளோ வடமொழிச் சுலோகங்கள் நிரம்பியவை. பல சமயங்களில் வடமொழிப் பகுதியுடன் தமிழ்ப் பகுதியும் காணப்படும்.

கல்வெட்டுக்கள் மங்கலச் சொல்லுடன் ஆரம்பித்து, அந் நாளில் ஆட்சிபுரிந்த மன்னனது புகழைத் தெரிவிக்கும் மெய்க்கீர்த்தியைக்கூறி அந்த அரசனுடைய ஆட்சியின் இன்ன ஆண்டில் இன்னாருக்கு இன்னது அளிக்கப் பட்டது என்பதைச் சொல்லி அவ்விதம் செய்வதற்குப் பொறுப்பு வாய்ந்தவர்களின் கையெழுத்துக்களோடு ரகசியையும் கொண்டு முடியும்.

செப்பேடுகளிலோ முதலில் மங்கல வாசகமும், வாழ்த்துச் செய்யுளும் காணப்படும். பிறகு தானம் வழங்கிய அரசனுடைய பூர்வோத்தாங்களும் அவன் முன்னோர்களுடைய பிரதாபங்களும் விரிவாகக் கூறப்பட்டிருக்கும். அப்பால் ஒருவனுடைய விண்ணப்பத்தின் மீது மற்றோர் அதிகாரியை ஆணத்தியாகக் கொண்டு அரசன் வழங்கிய தானமும் அதன் பரிகாரங்களும் விவரிக்கப்பட்டிருக்கும். தானம் பெறுபவர்களுடைய விவரங்களும் கொடுக்கப்பட்டிருக்கும். கடைசியில் அதிகாரிகள் கையெழுத்தும் அந்தத் தானத்தைக் காப்பவர்கள் அடையும் புண்ணியமும், தவிர்ப்பவர்கள் அடையும் பாபமும் காணப்படும். பல சமயங்களில் தான வாசகத்தை எழுதியவர் பெயரும், செப்பேட்டில் வெட்டிய சிற்பியின் பெயரும் கூடச் சேர்க்கப்பட்டிருப்பது உண்டு. சில சமயங்களில் அரசனுடைய கையெழுத்தும் காணப்படும்.

பழைய காலத்துச் சாசனங்களுக்கும், சமீபகாலத்தில் எழுதப்பட்டவற்றுக்கும் வேறுபாடுகள் உண்டு. பழமை வாய்ந்த சாசனங்கள் சுருக்கமாக இருக்கும். நாளாக ஆக அவற்றை எழுதுவதில் சம்பிரதாயங்கள் ஏற்பட்டு அவை நீண்டுவிட்டன. இவ்வாறே சாசனங்களின் அமைப்பும் வாசகமும் பிரதேசத்துக்கேற்றபடி, மாறுபடும்.



கல்லிலும் செம்பிலும் உள்ள சாசனங்கள் எவ்விதம் ஏற்பட்டன வென்பதை அறிந்தால் அவற்றுள் காணப்படும் வேறுபாடுகள் விளங்கும்.

பண்டைக்காலத்து அரசர்கள் கிரஹணம் முதலிய புண்ணிய காலங்களிலோ, தாங்கள் பிறந்த நக்சத்திரத்தையுடைய தினங்களிலோ, வேறு விசேஷ சந்தர்ப்பங்களிலோ தானம் செய்வது வழக்கம். யாகங்களைக் காட்டிலும் தானங்களே சிறந்தவை என்றும் புண்ணியம் பயப்பவை என்றும் தர்ம சாஸ்திரங்களின் தான காண்டங்கள் கூறுவதைப் பின்பற்றியே அவர்கள் நடந்துவந்ததாகத் தெரிகிறது. அவற்றிலே விவரிக்கப்பட்டுள்ள துலாபாரம், ஹிரண்ய கர்ப்பம் முதலியவைகளையும் அவர்கள் செய்து புகழ்பெற்ற செய்திகள் கல்வெட்டுக்களில் அங்கங்கே குறிக்கப்பட்டுள்ளன.

எனினும், தானகாண்ட விதிகளின்படி யல்லாமல் முன்னாலில் அரசர்கள் அளித்த தான தர்மங்களைப்பற்றித் தெரிவிக்கும் தமிழ்ச் சாசனங்கள் ஏராளமாக உள்ளன. தானம் கொடுப்பதை அங்கீகரித்து உத்தரவு அளித்த காலங்களில் அரசன் அந்தப்புரத்தில் இருந்ததாகவோ இசையைக்கேட்டிருந்ததாகவோ வேறு ஏதோ ஒருகாரியம் செய்து கொண்டிருந்ததாகவோ காணப்படுவதால், அரசாங்க உத்தியோகஸ்தர்கள் அரசனிடத்தில் சமயம் பார்த்து விண்ணப்பம் செய்து அவனிடமிருந்து வாய்மொழியாக உத்தரவைப் பெறுவதே வழக்கம் என்று தெரிகிறது. பட்டத்தாள் மங்கலம் எனப்படும் கொற்றங்குடிச் செப்பேடுகளில், “கோவிசய நந்திவிசுரமபருமருக்கு யாண்டு அறுபத் தொன்றாவது மங்கல நாடாள்வான் விண்ணப்பத்தால் ஆலப்பாக்க விசைய நல்லாமுன் ஆணத்தியாக”த் தானம் கொடுக்கப்பட்ட செய்தி காணப்படுவதினின்று இது நன்கு விளங்கும்.

அரசனது வாய்மொழி உத்தரவைக் கேட்டிருந்த ‘கேள்வி’ அல்லது ‘திருமுநம்’ என்னும் அதிகாரி அதனை எழுதி அரசாங்கத்தில் அதற்கு உரிய இலாகாவுக்கு அனுப்புவான். தானம் பெற்றவர்க்கு அதனை வரவு வைத்து அரசாங்கத்தின் பல கணக்குகளிலும் அந்த உத்தரவு பதிவு செய்யப்பட்டு ஸ்தல அதிகாரிகளுக்கு ஓலை அனுப்பப்பெறும். அதற்குப் பிறகுதான் நிலத்தைப் பெற்றவர்க்குப் பல அதிகாரிகள் கையெழுத்திட்டபத்திரம் அளிக்கப்படுகிறது. அக்காலத்தில் இவ்வித உத்தரவுகள் ஓலையிலேயே கொடுக்கப்பட்டிருந்தன. அந்தத் தானங்கள் சூரிய சந்திரர்கள் உள்ளவரை நிலத்திருக்கவும், எல்லோருக்கும் தெரியும் படியாகவும் முக்கியமான இடத்தில் கல்லில் எழுதப்படும். நிலத்தைப் பெற்றவர்களுக்கு வேண்டிய உரிமைப் பத்திரங்களாக அவற்றை

றைச் செம்பிலும் வெட்டிக்கொடுக்க நேரிடும். இதனால்தான் சில சமயங்களில் செப்பேடு, 'திரிபலீ தாம்ர சாசனம்' (செப்புப்பட்டய மான மூன்றாம் பிரதி) என்று வழங்கப்படுகிறதேபோலும்.

சாசனங்களே நிலத்தைப் பெற்றிருந்தவர்களுடைய உரிமைப் பத்திரங்களாக விளங்கினவாதலின் அவ்வித உரிமை இல்லாதவர்கள் தங்கள் கைப்பற்றை நிலைநிறுத்தவேண்டிப் போலிச் சாசனங்களைச் சிருஷ்டிக்கவும் கூடும். அப்படிப்பட்ட சாசனங்களும் சில காணப்படுகின்றன. ஆதலின் கிடைக்கும் எல்லாச் சாசனங்களையும் உண்மையெனக் கொள்ள முடியாது. அவற்றை நன்றாகக் கவனித்தால் போலிகள் எளிதில் விளங்கிவிடும். கல்லில் எழுதப்பட்டவற்றுள் போலிச் சாசனங்கள் பெரும்பாலும் இரா. போலிச் சாசனங்களும் சரித்திர ஆராய்ச்சிக்கு உபயோகம் உள்ளனவே.

இவ்விதம் நமக்குக் கிடைக்கும் சாசனங்கள் நம் நாட்டுப் பழைய சரித்திரத்தைத் தெரிவிப்பதற்காக ஏற்பட்டனவல்ல என்பது தெளிவாகும். ஆயினும் பழைய வரலாற்றை ஆராய்ந்து எழுதுவதற்கு அவையே முக்கிய ஆதாரங்களாக உள்ளன.

தான சாசனங்களிலே அந்த அந்தச் சாசனம் அளிக்கப்பட்ட காலம் குறிப்பிடப்படுகிறது. பொதுவாக அவை அந்நாளில் அரசு செலுத்திய மன்னனுடைய ஆட்சிக் காலத்தையும் சில சமயங்களில் சகாப்தம், கொல்லம் ஆண்டு போன்ற வருஷங்களையும் தெரிவிக்கும். ஓரொரு சாசனத்தில் ஆண்டுடன் மாதம், தேதி, திகி, கிழமை, நட்சத்திரம், கிரகணம் போன்ற பஞ்சாங்கக் குறிப்புகளும் காணப்படும். இவற்றைக்கொண்டு தானம் அளிக்கப்பட்ட நாளை நிச்சயமாகக் கணித்து அறியமுடியும். இவ்விதம் அரசர்களுடைய ஆட்சிக்காலம் நமக்கு நிர்ணயமாகத் தெரியவருகிறது. இன்னும், சாசனங்களில் காணப்படும் மெய்க்கீர்த்தி அல்லது பிரசஸ்தியிலிருந்து அரசனுடைய வெற்றிகளும் புகழும் நன்கு விளங்கும். அன்றி ஓர் அரசனுடைய சாசனங்கள் கிடைக்கும் இடங்களைக் கொண்டு அவனுடைய ஆட்சி எவ்வளவு தூரம் பரவியிருந்ததென்பதையும் நாம் அறியலாம்.

இவற்றைத் தவிர, சாசனங்களின் அமைப்பையும் வாசகத்தையும் கொண்டு வேறு எத்தனையோ விஷயங்களை நிர்ணயிக்கலாம். அந்நாளின் ஆட்சிமுறை, அதை நடத்திய அரசாங்க அதிகாரிகளின் வரம்பு, சமூக அமைப்பு, நாடு இருந்த நிலை, நாகரிகம், மக்கள் நடத்திய வாழ்க்கை, வாணிகம் முதலிய எல்லாத்துறைகளிலும் நம் நாட்டின் பழைய வரலாற்றை நாம் அறியலாம். இன்னும், இச் சாசனங்கள் அந்த அந்த நாட்டு மொழிகளில், பெரும்பாலும் உரைநடையிலும்

சில சமயங்களில் செய்யுளாகவும் அமைந்திருப்பதைக் கவனித்து அந் நாளில் மொழி, இலக்கியம், இலக்கணம் ஆகியவற்றின் நிலையையும் நாம் காணலாம்.

சாசனங்களை அவை கிடைக்கும் பிரதேசத்தைக் கொண்டோ, அவற்றுள் காணப்படும் அரசர்கள் அல்லது வம்சங்களைக் கொண்டோ, அவை பொறிக்கப்பட்ட நூற்றாண்டுகளைக் கொண்டோ பல பகுதிகளாகப் பிரித்துத் தொகுத்து வைத்துக்கொண்டு ஆராயவேண்டும். அப்போதுதான் அந்த ஆராய்ச்சியின் பயனாக உண்மைச் செய்திகள் பல வற்றை அறியமுடியும். ஒவ்வொன்றையும் தனித்தனியாக எடுத்துக் கொண்டு ஆராய்ந்தால் அது அதிகமாகப் பயன்படமாட்டாது.

இதற்குச் சாசனங்களின் மூலபாடங்கள் அத்தியாவசியம். சென்ற முக்கால் நூற்றாண்டாக அரசாங்கத்தார் தமிழ் ஜில்லாக்களில் இருந்து மட்டுமே இருபதினாயிரத்துக்கு மேற்பட்ட கல்வெட்டுக்களைப் பிரதி செய்திருக்கிறார்கள். ஆனால் வெளியிடப்பட்டவைகளோ நாலாயிரத்துக்குமேல் இருக்காது. 1904-ஆம் ஆண்டிலிருந்து பிரதி செய்யப்பட்ட சாசனங்களின் பெரும்பகுதி இன்னும் வெளியிடப்பெறாமல் உள்ளன. அவை விரைவில் வெளியிடப்பட்டால்தான் சாசன ஆராய்ச்சியைத் திறம்பட நடத்தமுடியும்.

## 2. பழைய சரித்திர நூல்கள்

நம் நாட்டுப் பழைய சரித்திரத்தை அறிவதற்கு நாம் சாசனங்களுையே முக்கிய ஆதாரங்களாகக் கொண்டுள்ளோம். எந்த எந்தக் காலங்களில் நாட்டின் எந்த எந்தப் பாகங்களில் யார் யார் அரசு செலுத்திவந்தார்கள், எவ்வெப்பொழுது எந்த எந்த அரசாங்கங்கள் நாட்டின் எந்த எந்தப் பகுதியைக் கைக்கொண்டன, நாட்டை ஆண்டவந்த அரசர்களில் யாருக்குப்பின் யார் அரசாங்கத்தை ஏற்று நடத்திவந்தார்கள், அவர்களில் ஒருவருக்கு ஒருவர் பெற்றிருந்த முறை என்ன, ஒவ்வொருவரும் எத்தனை வருஷகாலம் அரசாண்டனர் என்பன போன்றவற்றை ஆராய்வதற்குத்தான் நாம் சாசனங்களை இப்பொழுது உபயோகிக்கின்றோம்.

ஆனால் இச்செய்திகளை அறிவதற்குச் சாசனங்கள் மட்டுமே ஆதாரங்களாக நிற்கவில்லை. கர்ண பரம்பரைச் செய்திகள், இலக்கியம், பழைய நானயங்கள், சிற்பம், சித்திரம், வெளிநாட்டார் எழுதிவைத்துச் சென்ற குறிப்புக்கள் என்பனபோன்ற வேறு பலவகை ஆதாரங்களும் உள. ஆயினும் அவற்றுல் நாம் அறிந்துகொள்வனவற்றை ஒருவிதமாக முறைப்படுத்தி முடிவுகட்டி நிச்சயம் செய்துகொள்வதற்குச் சாசனங்களே தக்க கருவியாக இருக்கின்றன.

நம் முன்னோர்களுக்குச் சரித்திர உணர்ச்சி கிடையாது என்ற பழிச்சொல் ஒன்று உண்டு. அது சமீபகாலத்தில் ஏற்பட்டதன்று. கி. பி. பதினொராம் நூற்றாண்டில் இந் நாட்டிற்கு அல்பேரூரீ என்னும் அராபிய யாத்திரிகர் ஒருவர் வந்திருந்தார். அவர் ‘‘ ஹிந்துக்கள் சரித்திர முறையைப்பற்றிக் கொஞ்சமும் கவனிப்பதில்லை. அவர்கள் தங்களுடைய அரசர்களைப்பற்றி வான்முறையாகச் சொல்லமாட்டார்கள். நெருக்கியடித்துக் கேட்டால் இன்னது செய்வது என்னும் வகை யறியாமல், கதைகட்ட ஆரம்பித்து விடுவார்கள் ’’ என்று கூறியிருக்கிறார். இது அவருடைய அனுபவம் போலும்.

இதுகாறும் நம் நாட்டுச் சரித்திரத்தை ஆராய்ந்த ஆசிரியர்களில், வெளிநாட்டவர் நம் தேசத்தவர் என்ற வேற்றுமையில்லாமல், பலரும் அக்கொள்கையை உடம்பாடாகக் கொண்டிருக்கிறார்கள். ‘இதையே தான் நாம் இன்றைக்கும் காண்கிறோம்’ என்பது அன்றார் கூற்று.

நாம் இப்பொழுது விரும்பும் முறையில் நாட்டுச் சரித்திரத்தை நம் முன்னோர்கள் எழுதிவைத்துச் செல்லவில்லை என்பது உண்மை தான். ஆனால் அவர்களுக்குச் சரித்திர உணர்ச்சி இல்லையென்றாவது, சரித்திரங்களை எழுதிவைக்கவே இல்லை யென்றாவது கூறமுடியாது. நாம் இக்காலத்தில் கொண்டிருக்கும் மனப்பான்மைக்கும் நம் முன்னோர்கள் பெற்றிருந்ததற்கும் மிகுந்த வேறுபாடுகள் உண்டு. அவர்கள் தங்கள் மனத்திற்கு இசைந்தவாறு சரித்திரத்தை எழுதிவைத்தே சென்றிருக்கிறார்கள்.

மக்களுடைய விருப்பங்களும், உள்ளக் கிளர்ச்சிகளும் நாகரிகம் முன்னேற்றம் அடையுந்தோறும் நாளுக்கு நாள் மாறி வருகின்றன. அன்றி, அவை தேசந்தோறும் வேறுபடுகின்றன. இன்றைக்கு முறையாக இருப்பது நாளைக்குத் தவறாக மாறுகின்றது. அவ்வாறே இன்றைக்குத் தவறாக உள்ளது நாளைக்கு முறையானதாகக் கருதப்படுகின்றது.

பண்டைய மக்கள் சரித்திரத்தையும் கால முறையையும் நாம் இப்பொழுது கருதுவதைப் போன்று மதிப்பிடவில்லை. அவர்களுக்குத் தெய்வபக்தியும் காவியாசனியுமே முக்கியமானவைகளாகத்தோன்றின. இந்தக் கருத்தைக் கொண்டே அவர்கள் காவிய நாடகங்களையும் புராணங்களையும் அதிகமாக எழுதிவைத்துச் சென்றனர் போலும். அவைதாம் பொதுமக்களுக்கு மிகவும் உபயோகப்படக் கூடியவை; அவர்கள் மனத்தை நல்வழியில் திருப்பக்கூடியவை. அந்த முறையில் அல்லாமல் நம் முன்னோர்கள் வேறு துறைகளில் சரித்திர நூல்களை ஜனசமூகத்திற்கு அத்தியாவசியமானவைகளாகக் கருதவில்லை.

எனிலும், அவர்கள் சரித்திரங்களை எழுதாமல் விட்டுவிடவில்லை. பழைய புராணங்களில் நம் நாட்டுச் சரித்திரப் பகுதிகள் காணப்படுகின்றன. சிருஷ்டி காலத்திலிருந்து பூ மண்டலத்தின் வரலாற்றை எடுத்துரைப்பனவே புராணங்கள். இப்போது நமக்குக் கிடைக்கும் அவற்றின் பாடங்கள் மூல உருவங்கள் அல்ல; பல இடைச் செருகல்களும் திருத்தங்களும் கொண்டவை. நம் நாட்டைப் பழைய காலத்தில் ஆண்டவர்களாக அதிலே கூறப் பெறும் ராஜ வமிசங்களையும் அரசர்களையும் அவர்களுடைய ஆட்சியின் வரலாற்றையும் நாம் சரித்திர உண்மைகளாகக் கொள்ளாமல் வெறும் கட்டுக் கதைகளென்று கூறி ஒதுக்கிவிடுகிறோம்.

இன்னும், அந்தப் புராணங்களில் விவரிக்கப்பெற்றுள்ள அரசர்கள், பெரியோர் ஆகியவர்களுடைய காலத்திற்குப் பிறகு நாடு எவ்விதம் இருக்கும் என்று கூறுவதுபோலப் பாதகண்டத்தின் சரித்திரம் கூறப்பட்டுள்ளது. பவிஷ்யத், அதாவது வருங்காலத்தை அறிவிப்பதாக அமைந்திருக்கும் அந்தப் பாகம், அநேகமாக எல்லாப் புராணங்களிலும் ஒரேவிதமாகக் காணப்படுகின்றது. அவற்றுள் தோன்றும் வித்தியாசங்களும் பாடபேதங்களால் ஏற்பட்டனவேயன்றி வேறல்ல. பார்ஜிதர் என்னும் ஆசிரியர் அவற்றைத் தொகுத்து ஒப்பிட்டு, சரியான பாடம் என்று தீர்மானித்ததைக் 'கலியுக ராஜவமிசங்கள் பற்றிய புராண பாடம்' என்ற பெயரில் வெளியிட்டுள்ளார்.

அந்தப் பாகத்தில் கி. மு. நான்காம் நூற்றாண்டின் மத்தியிலிருந்து கி. பி. நான்காம் நூற்றாண்டு வரையில் சுமார் ஐந்தாறு நூற்றாண்டுகளின் சரித்திரம் உள்ளது. அதிலே மௌரியர், சுங்கர், கணவர், ஆந்திரர் அல்லது ஆந்திரபிருத்தியர்கள் எனப்படும் சாதவாகனர்கள் ஆகியோர்களுடைய வமிசாவளிகளும் அந்த அரசர்களுடைய ஆட்சி விவரங்களும் காணப்படுகின்றன. ஆனால் அது பாதகண்டம் முழுமைக்கும் இல்லை; மகத தேசத்திற்கும் அதைச் சுற்றியுள்ள நாடுகளுக்கும் இல்லை. இந்தியாவின் எல்லைப்புறங்களிலும் தக்ஷிணத்திலும் ஆண்ட அரச வமிசங்களைப்பற்றிய செய்திகள் காணப்படவில்லை. புராண ஆசிரியர்கள் தாங்கள் வாழ்ந்துவந்த நாட்டை மத்தியாகக் கொண்ட பாகத்தை மட்டுமே முக்கியமாகக் கருதினார்கள் போலும். அன்றி, அந்நாளிலே மகதத்தை ஆண்டு வந்தவர்களே இந்நாட்டின் பேரரசர்கள் என்றும் மற்ற மன்னர்கள் யாவரும் அவர்களுக்குக் கீழ்ப்பட்டவர்கள் என்றும் ஓர் எண்ணம் நிலவி வந்திருக்கிறது.

புராணங்களின் பவிஷ்யத் பாகத்தில் காணப்படும் அரசர்களுடைய வமிசம், அவர்களுடைய ஆட்சிக்காலம் முதலியன சரித்திர ஆராய்ச்சி

யால் கண்ட முடிவுகளையே தழுவிருக்கின்றன. பல சமயங்களில் புராணங்களில் காணப்படும் செய்திகளைக் கொண்டே சரித்திர முடிவுகளை நாம் வரையறுக்கவேண்டி யிருக்கிறது.

ஆனால் அவ்விடத்தில் கூறப்பட்டவற்றுள் முக்கியமான ஒரு மாறுதலை நாம் செய்து கொள்ளவேண்டும். நாட்டின் பல பாகங்களிலும் சமகாலத்தில் ஆண்ட அரசு பரம்பரைகளைப் புராணங்கள் அந்த அந்த வமிசங்கள் ஆதிக்கியம் பெற்ற வரிசையில் குறிப்பிட்டு அவற்றின் வமிசாவளியை ஆதிமுதல் முடிவு வரையில் அந்த இடத்தில் கொடுத்திருக்கின்றன. உதாரணமாகப் பின்வருவதைக் காட்டலாம்: கி. மு. இரண்டாம் நூற்றாண்டின் ஆரம்பத்தில் அரசு நிறுவிய சுங்க வமிசத்தவர்கள் மகதநாட்டை நூற்றுப்பன்னிரண்டு வருஷங்கள் ஆண்டுவந்தனர். அவர்களுக்குப் பிறகு நாற்பத்தைந்து ஆண்டுகள் கண்வ வமிசத்து மன்னர்களும் ஆண்டு வந்தார்கள். அக்காலங்களில் தக்ஷிணத்தின் வடகோடியில் மத்திய இந்தியாவை ஒட்டிய பாகத்தில் ஆந்திரர்கள் என்றும் ஆந்திரபிருத்தியர்கள் என்றும் வழங்கப்பெறும் சாதவாகனர்கள் அரசு செலுத்தினர். சாதவாகன வேந்தன் ஒருவன் கண்வ வமிசத்துக் கடைசி அரசனைக் கி. பி. 27-ஆம் ஆண்டளவில் கொன்று மகதநாட்டையும் கைக்கொண்டான். கண்வ வமிசம் வீழ்ச்சியடைந்ததும் சாதவாகனர்கள் ஆதிக்கியம் பெற்றனர். ஆகையால் புராணங்களில் சாதவாகனர்கள் கண்வ வமிசத்திற்குப் பிறகு வைத்துக் கூறப்பட்டுள்ளனர். அவ்விதம் கூறும்போது அந்த வமிசத்தின் முதல் அரசனிலிருந்து ஆரம்பிக்கின்றனர். இவ்விதமான திருத்தம் ஒன்றை மட்டில் செய்துகொண்டால் புராணங்களில் உள்ள சரித்திரப் பகுதி நம்பக் கூடாதது என்று கருத இடமில்லாமற் போய்விடும்.

இதேபோல், சுமார் கி. மு. 700 முதல் கி. பி. 770 வரையில் ஆயிரத்தைந்தாறு ஆண்டுகளுக்கு இந்நாட்டின் சரித்திரம் 'மஞ்சு ஸ்ரீ மூலகல்பம்' என்னும் புத்தமத நூலில் காணப்படுகிறது. ஸம்ஸ்கிருதத்தில் எழுதப்பெற்ற அந்நூலுக்குத் திபேத்திய பாஷையில் ஒரு மொழிபெயர்ப்பும் உள்ளது. அவ்விரண்டையும் ஒப்பிட்டுப் பார்த்துச் சரியான மூல பாடத்தை நிர்ணயித்து ஆராய்ச்சிக் குறிப்புகளுடன் காலஞ்சென்ற காசிப் பிரசாத ஜயஸ்வால் என்பார் 'இந்தியப் பேரரசின் வாலாறு' (ஆன் இம்பீரியல் ஹிஸ்டரி ஆப் இந்தியா) என்ற பெயரில் வெளியிட்டிருக்கிறார்.

கல்ஹணர் எழுதிய 'ராஜதரங்கினி' மற்றொரு சரித்திர நூலாகும். அது காசுமீர தேசத்தின் சரித்திரத்தைக் கூறுவதாகும். அந்த நூல் கி. பி. புன்னிரண்டாம் நூற்றாண்டின் மத்தியில் (1148-9-ஆம் ஆண்டு)

எழுதப்பட்டது. அவர் அந்தாலை எழுதுவதற்கு முன்னர் அந் நாட்டுச் சரித்திரத்தைக் கூறும் தூல்கள் சில இருந்தன. கேஷமேந்திரர் எழுதிய நிருபாவலி, ஹேலாராஜர் பன்னீராயிரம் செய்யுட்களில் எழுதிய பார்த்திவாவலி, நீலமுனி எழுதிய நீலமத புராணம் என்பன அவற்றுள் முக்கியமானவை. அன்றி, ஸுவ்ருதர், பத்மமிஹிரர் என்போர் எழுதிய தூல்களும் இருந்தன.

கல்ஹணர் பழைய தூல்களில் காணப்படும் குறைகளை நீக்கி உண்மைச் சரித்திரத்தை எழுதுவதாகக் கூறுகிறார். அரசாங்கத்தில் உயர்ந்த பதவியைப் பெற்றிருந்த ஒருவருடைய குமாரராகிய கல்ஹணருக்கு அதற்கு வேண்டிய சௌகரியங்கள் பல இருந்தன. அவர் தம் முடைய தூலைத் தமக்கு முன்னர் எழுதப்பட்டுள்ள பதினொரு ராஜகதைகளையும் நீலமத புராணத்தையுமே ஆதாரங்களாகக் கொண்டு எழுதியிருக்கிறார்; பண்டை மன்னர் அளித்த சாசனங்கள் பலவற்றையும், முதிர்ந்தோர் வாய்மொழிகளையும், சுவடிகளையும் ஆராய்ந்து எழுதியதாக அவரே கூறியுள்ளார். எனினும் ராஜதரங்கினியில் சில குறைகள் இல்லாமல் இல்லை. அது கி. மு. 2448-ஆம் ஆண்டிலிருந்து சரித்திரத்தைக் கூறிவருகின்றது. ஆயினும் அவ்வளவு பழைய காலத்ததாகக் கூறப்படும் சரித்திரம் நம்பத்தகுந்ததல்ல. ஆசிரியரின் காலத்திற்குச் சுமார் நூலாந்து நூற்றாண்டுகளுக்கு முற்பட்ட காலத்தில் ஆண்டவர் களாகத் தெரியும் மன்னர்களுடைய ஆட்சிக்காலங்களை நாம் அப்படியே ஏற்றுக்கொள்ள முடியாது.

தமிழ் நாட்டிலும் அத்தகைய சரித்திரங்கள் உள்ளன. சென்ற நூற்றாண்டின் துவக்கத்தில் கர்னல் மக்கென்ஸி என்பவர் நம் நாட்டுச் சரித்திரத்தை ஆராய்ந்து எழுதவேண்டும் என்னும் நோக்கத்துடன் அதற்குத் தேவையான ஆதாரங்களைத் தேடிச் சேகரித்தார். அதற்காக அவர் பல உதவியாளர்களை நியமித்து அவர்களை நாட்டின் பல பாகங் களுக்கும் அனுப்பிவைத்தார். அவர்கள் அங்கங்கே உள்ள வயது சென்ற வர்களிடமும் முக்கியஸ்தர்களிடமும் கிடைத்த பழைய தூல்களையும் செய்திகளையும் பெற்று வந்தார்கள்.

அவ்விதம் கிடைத்தவற்றை அப்படியே தொகுத்துப் பிரதி செய்து வைத்துள்ளார்கள். அந்தத் தொகுதிகளுள் கர்ணபரம்பரைச் செய்திகள், நாட்டுச் சரித்திரங்கள், மகாத்மியங்கள், ஸ்தலபுராணங்கள், சிற்றூர் வரலாறுகள், கோயிற் சுவர்களினின்றும் பெயர்த்தெழுதிய கல் லெட்டுகள், செப்பேட்டுப் பிரதிகள், சில்லறைப் பிரபந்தங்கள், நாட்டுப் பாடல்கள் ஆகியவை நிறைந்து இருக்கின்றன.

மக்கென்ஸி அவற்றைத் சேகரித்தாரே ஒழிய அவற்றை உபயோகிக்கவில்லை. அந்த தூல்கள் இன்னும் நன்கு முறையாக ஆராயப்படவில்லை. சென்ற நூற்றாண்டின் மத்தியில் டெயிலர், வில்ஸன் என்னும் ஆசிரியர் இருவர் அவற்றைத் தனித் தனியாக ஆராய்ந்து தொகுத்து அட்டவணைகள் வெளியிட்டிருக்கிறார்கள். டெயிலர் என்பவர் அவற்றுள் சிலவற்றைச் சுருக்கமாக ஆங்கிலத்தில் மொழிபெயர்த்து 'ஓரியண்டல் ஹிஸ்டாரிகல் மானுஸ்கிருப்ட்ஸ்' என்ற பெயரில் 1835-ஆம் ஆண்டு வெளியிட்டார்.

அந்தத் தொகை தூல்களை ஆராய்ந்த ஆசிரியர்களிற் பலர் அவற்றைப் புராணக் கதைகளென்றும், சரித்திர ஆதாரங்களாகக் கொள்ளத் தகுதிவாய்ந்தனவல்ல வென்றும் ஒதுக்கிவிட்டனர். கால்டுவெல் போன்ற ஆசிரியரும் அவற்றைக் 'கர்ணபரம்பரைச் செய்திகளைவிட மிகவும் மட்டம்' என்றும், 'கட்டுக்கதை நிலையைக் காட்டிலும் அதிக ஆதாரமனவை யல்ல' என்றும் கூறுகிறார். (திருநெல்வேலி வரலாறு, பக்கம் 55.) ஆனால் அது நடந்தது வெகு காலத்திற்கு முன்பு. அக்காலத்தில் நம் நாட்டுப் பூர்விக சரித்திரத்தைப்பற்றிய ஆராய்ச்சி ஆரம்பப் பருவத்திலே இருந்தது; முன்னேற்றம் அடையவில்லை. அதை நடத்தி வந்த ஆராய்ச்சியாளர்களுக்கும் நம் நாட்டுக் கலைச் செல்வம், மனப் பான்மை ஆகியவைகளின் அடிப்படைத் தத்துவம் தெரியாது. மேலை நாடுகளில் உள்ள சரித்திர தூல்களுடன் இவற்றை ஒப்பிட்டே அந்த விதமான முடிவுக்கு வந்தனர்.

அதுமிகவும் தவறு. மக்கென்ஸி தொகையில் கிடைக்கும் 'கர்நாடக தேச ராஜாக்கள் சரிஸ்தார சரித்திரம்', 'கொங்குதேச ராஜாக்கள்', 'மதுரைத்தல வரலாறு', 'தஞ்சாவூரி ஆந்தர ராஜுல சரித்திரமு' (தெலுங்கு) என்பனபோன்ற தூல்களை நாம் அங்ஙனம் கூறமுடியாது. கி. பி. பதினைந்து, பதினாறு, பதினேழாம் நூற்றாண்டுகளின் தமிழ் நாட்டுச் சரித்திரத்தை எழுதுவதற்கு அந்தவகை தூல்களை முக்கிய ஆதாரங்களாக உள்ளன. நாட்டின் பல பாகங்களையும் ஆண்டுவந்த சிற்றரசர்கள் ஆகியோர்களுடைய சரித்திரங்களுக்கு அவற்றைத் தவிர வேறுவகை ஆதாரங்கள் கிடையா. சமீப காலத்தில் எழுதப்பட்ட அந்த நூற்றாண்டுச் சரித்திரங்கள் பலவற்றுக்கும் அவை நன்கு பயன்பட்டிருக்கின்றன.

'மதுரை நாயக்க மன்னர்களின் சரித்திர'த்தை எழுதிய பேராசிரியர் ஆர். சத்தியநாத ஐயர், "இத்தகைய தூல்களை நடுநிலைமையோடு ஒப்பிட்டு ஆராய்ந்து கண்ட முடிவே இந்தச் சரித்திரம் எழுதுவதற்கு



முக்கியமான ஆதாரமாக அமைந்துள்ளது” (பக்கம் 33) என்று குறிப்பிட்டிருக்கிறார். சோழ மன்னர்கள் வரலாற்றை விரிவாக ஆராய்ந்து எழுதிய பேராசிரியர் க. அ. நீலகண்ட சாஸ்திரிகள் ஓர் இடத்தில், “சோழர் சரித்திரத்தின் ஆரம்பகாலத்தைப் பற்றிக் ‘கொங்கு தேச ராஜாக்கள்’ என்னும் நூலில் காணப்படும் சில விஷயங்கள் சிலா சாசனங்களால் பெரிதும் வலியுறுத்தப்பட்டுள்ளன” என்று கூறிவிட்டு, “இந்த வரலாறுகள் எவ்விதம் எழுதப்பெற்றன வென்பதைப் பற்றிய விவரம் நமக்கு இப்போது அதிகமாகத் தெரியவில்லை. அவற்றை நல்ல முறையில் கவனமாக ஆராயவேண்டுவது அவசியம்” என்றும் தெரிவித்திருக்கிறார். (க. அ. நீலகண்ட சாஸ்திரிகள், ஹெச் எஸ். ராமண்ண ஆகிய இருவரும் எழுதிய ‘இந்திய வரலாறு பற்றிய சரித்திர ஆராய்ச்சி முறை’ பக்கம் 46). சமகாலத்தில் ஆண்டுவந்த அரச பரம்பரைகளை அவை ஆதிக்கம்பெற்ற முறையிலே வைத்து, அந்த அந்த வமிசத்துச் சரித்திரத்தையும் ஆதிமுதல் தெரிவிப்பதாகப் புராணங்களில் காணப்படுகிற குறை ‘கொங்குதேச ராஜாக்களிலும்’ ஓர் அளவு தென்படுகிறது. அதுவும் மிகப் பழங்காலத்துக்குத்தான். இது ஒன்றைத் தவிர மற்ற விஷயங்களில் இது முற்றிலும் நம்பத் தகுந்தது. இந்த ஒலைச் சுவடி நிலயத்திலேயே ‘கொங்கண தேச ராஜா வ்ருத்தார்தமு’ என்னும் தெலுங்கு நூல் ஒன்றும் உள்ளது. அது இந்நூலில் தெலுங்கு வடிவமேயாகும் என்பர்.

இந்தச் சுவடி நிலயத்திலேயே ‘கங்க வம்சாறு சரித்திரம்’ என்னும் வடமொழிக் காவியம் ஒன்று இருக்கிறது. ஒரிஸ்ஸா தேசத்தை ஆண்டு வந்த கீழைக் கங்க வமிசத்து மன்னர்களின் வரலாற்றைக் கூறும் அந் நூல் ராஜகுருவாக இருந்த வாஸுதேவ ரத ஸோமயாஜி என்பவரால் இயற்றப்பெற்றது. முதல் பத்துப் பரிச்சேதங்கள் உள்ளன. அது கி. பி. பதினான்காம் நூற்றாண்டில் இயற்றப்பெற்றதெனத் தெரிகிறது. அதன் ஆசிரியர் ராஜகுருவாக அரச குடும்பத்தாருடன் நெருங்கிய தொடர்பும் அரசாங்கப் பதவியும் பெற்றிருந்தமையால் அரச வமிசத் தாரின் வரலாறுபற்றிய ஆதாரமான செய்திகளை அவர் பெறுவதற்கு நல்ல வசதியும் வாய்ப்பும் இருந்திருக்கவேண்டும். எனினும் அந்நூல் சரித்திரமாக இல்லாது இலக்கியச்சுவை பெற்ற காவியமாகக் காணப்படுகிறது. (1919-20 ஆண்டு முதல் 1921-22 ஆண்டு வரை உள்ள மூவருட்க் கேட்லாக்கு, ஆர் நெ. 3033 கொண்ட சுவடி.)

தவிர, பாரதீகம் முதலிய மொழிகளிலும் சாதத்நாமா, துஸ்கத்-இ-வாலாஜாஹீ என வாலாஜா நவாபுகளின் சரித்திரங்களைக் கூறும் நூல்களைப்போல அநேகம் இருக்கின்றன.

ராஜதாங்கிணி உட்பட இவ்வகை நூல்கள் எல்லாவற்றிலும் நாம் முன்னமே கூறியுள்ளபடி நடை அழகும் கற்பனைகளும் கலந்து காவிய வாசனை வீசுவது கவனிக்கத்தக்கது.

இவ்விதம் நாட்டை ஆண்டுவந்த அரசு பரம்பரையினரின் சரித் திரத்தைக் கூறும் நூல்களைப் போலவே தனிப்பட்ட அரசர்களின் வாழ்க்கையைத் தெரிவிக்கும் நூல்களும் உள. அவற்றுள் பாண கவி எழுதிய ஹர்ஷ சரித்திரம், பில்ஹணர் எழுதிய 'விக்ரமாங்க தேவ சரித்திரம்' ஆகிய இரண்டையும் முக்கியமானவைகளாகக் கொள்ள லாம்.

ஹர்ஷ சரித்திரம் கி. பி. ஏழாம் நூற்றாண்டின் முற்பகுதியில் (கி. பி. 606 முதல் 648 வரையில்) வடக்கே கன்னேசி எனவும் கன்ன குச்சி எனவும் குறிக்கப்பெறும் கன்யாகுபஜ நாட்டை ஆண்டு வந்த ஹர்ஷவர்த்தனன் என்பவனுடைய சரித்திரத்தைக் கூறுவது. பில்ஹணர் எழுதியதோ கி. பி. பதினேராம் நூற்றாண்டின் பிற்பகுதியில் (கி. பி. 1075 முதல் 1126 வரையில்) கல்யாணியினின்றும் அரசு செலுத்திய ஆறாம் விக்கிரமாதித்தன் என்னும் மேலைச் சாளுக்கிய அரசு னுடைய சரித்திரத்தைத் தெரிவிப்பதாகும். இவ்விரு நூல்களின் ஆசிரியர் களும் முறையே அவ்வரசர்களின் ஆஸ்தானத்திலே வித்துவான்களாக விளங்கியவர்கள்.

இவ்வகை நூல்களுள் மேலே கூறிய இரண்டுமே பிரபலமாக வழங்குபவை. அவற்றுள் காணப்படும் இலக்கியச் சுவையே அதற்குக் காரணமாகும்; அவை சரித்திர நூல்கள் என்பதற்காக அல்ல.

அவற்றைப் போல வேறு பல நூல்களும் உள்ளன. தஞ்சாவூர்ச் சீமையைக் கி. பி. பதினாறு, பதினேழாம் நூற்றாண்டுகளில் ஆண்டுவந்த நாயக்க மன்னர்களில் ரகுநாத நாயக்கருடைய ஜீவிய சரித்திரத்தைப் பற்றிப் புகழ்பெற்ற மந்திரியான கோவிந்ததீக்ஷிதர் குமாரர் யஜ்ஞநாராயண தீக்ஷிதர் எழுதிய 'ஸாஹித்ய ரத்நாகரம்,' அம்மன்னன் தேவிகளுள் ஒருத்தியான ராமபத்ரம்மா எழுதிய ரகுநாதாப்யுதயம் என்னும் வட மொழி நூல்களும், ரகுநாத நாயக்கர் புத்திரர் விஜயராகவ நாயக்கர் ரகுநாதாப்யுதயம் என்ற பெயரிலேயே தெலுங்கில் எழுதிய யக்ஷகானம் எனப்பெறும் நாடகவகை நூல், ரகுநாதநாயகாப்யுதயம் என்னும் தெலுங்கு மொழிக் காவியம் போன்றவைகளும் உள்ளன.

இவற்றைப் போலவே விஜயநகர சாம்ராஜ்யத்தை ஆண்டுவந்த மன்னர்களான சாளுவ நரசிம்ஹன் மீது டிண்டிம கவி எழுதிய 'சாளு வாப்யுதயம்,' அச்சுத தேவராயர் மீது இயற்றிய 'அச்சுதராயாப்யுதயம்'

ஆகிய சரித்திரங்களும் கிடைத்துள்ளன. இன்னும் குமார தூர்ஜடி என் பார் கிருஷ்ணதேவராயர்மீது தெலுங்கில் இயற்றிய கிருஷ்ணராய விஜயம் என்னும் காவியமும் இருக்கிறது.

இவ்வகை நூல்கள் யாவும் இலக்கியச்சுவை மிகுந்தே காணப்படு கின்றன. இவற்றை அம் மன்னர்களுடைய ஜீவியத் தத்துவத்தைக் கூறும் வாழ்க்கைச்சித்திரங்களாகவே நாம் கொள்ளவேண்டும். நாம் இப் பொழுது விரும்பும் முறையில் உள்ள சரித்திர நூல்களாகக் கொள்ள முடியாது. உதாரணமாக, பில்ஹணர் தம்முடைய விக்ரமமாங்க தேவ சரித்திரத்தில் விக்ரமமாதித்தன் பிறந்த செய்தியைக் கூறுமிடத்தே அவன்பிறந்தவுடன், “தேவர்கள் ஆர்த்தனர். துந்துபி முழங்கிற்று, பூமாரி பொழிந்தது” என்று சம்பிரதாயமான முறையில் எழுதியிருக்கிறாரே ஒழியப் பிறந்த வருஷம், மாதம், தேதி முதலிய விவரங்களைக் கூற வில்லை.

இம்மாதிரியே பாணகவியும் தம் பாட்டுடைத் தலைவனான ஹர்ஷ வர்த்தனன் “ஜைஷ்ட மாசத்துக் கிருஷ்ணபக்ஷத் துவாதசிதினம் சந்தி ரன் கார்த்திகை நட்சத்திரத்தில் நிற்கையில், சந்தியா காலம் தாண்டி முன்னிரவு ஆரம்பிக்கும் சமயம் பிறந்தான்” என்று கூறுகிறாரே யன்றி, அது எந்த வருஷம் நிகழ்ந்தது என்பதைத் தெரிவிக்கவில்லை.

“இவ்விரு ஆசிரியர்களில் யாரும் தாங்கள் வாழ்ந்த காலத்தையோ நூல் எழுதிய காலத்தையோ குறிப்பிடவில்லை. ஆகவே ஹர்ஷவர்த்த னனைப்பற்றியோ விக்ரமமாதித்தனைப் பற்றியோ சரித்திர பூர்வமான வேறு ஆதாரங்களிலிருந்து நமக்குத் தெரியாமல் இருந்திருக்குமாயின் அந்தக் கவிஞர்கள், அவர்களுடைய பாட்டுடைத்தலைவர்கள் ஆகியோரு டைய காலம் நமக்குத் தெரியாமலே போயிருக்கும்” என்று பிரபல ஆசிரியர் ஒருவர் இந்த நூல்களின் சரித்திர மதிப்பைப்பற்றிக் கூறும் போது எழுதிச் செல்கிறார்.

இந்தக் குறை இலக்கியங்களில் மட்டுமல்லாமல் சாசனங்களிலும் காணப்படுகின்றன. பல்லவர்களில் சிம்ஹவிஷ்ணுவின் காலத்திற்கு முற் பட்டவர்கள் அளித்தனவாகவுள்ள செப்பேடுகள் ஏராளமாகக் கிடைத் திருக்கின்றன. அவற்றில் தானம் வழங்கிய மன்னனுடைய முன்னோர் மூன்று தலைமுறைக்குப் பெயர் குறிக்கப்பட்டிருக்கிறார்கள். எனினும் அவை சாசனம் வழங்கப்பட்ட காலங்களை நிர்ணயிக்கக் கூடியனவாக இல்லை. பல சமயங்களில் அரசனுடைய ஆட்சியின் ஆண்டே கொடுக்கப் பட்டிருக்கும். சிலசமயங்களில் அதுவும் இராது. அன்றி, அவர்களில் புனர் ஒரேமாதிரியான பெயரைத் தாங்கியிருப்பர். ஆகவே சாசன

எழுத்துக்களின் வரி வடிவத்தைக்கொண்டே அந்தச் சாசனங்களின் காலத்தை நிர்ணயித்து அம்மன்னர்களுடைய வமிசாவளியை நிச்சயிக்க வேண்டியிருக்கிறது.

ஹர்ஷசரித்திரம் போன்ற நூல்கள் தமிழிலும் முன்னாளிலே இயற்றப்பட்டிருந்தனவாகத் தெரிகிறது. அவை இப்போது கிடைக்க வில்லை. எனினும் அவைகளைப்பற்றி நாம் கல்வெட்டுகளிலிருந்து அறி கிறோம். தஞ்சாவூர் ஜில்லா திருப்பூந்துருத்தியில் உள்ள முதலாம் இரா ஜேந்திர சோழனுடைய காலத்தைச் சேர்ந்ததான குறைச்சாசனம் ஒன்று (1931-ஆம் ஆண்டின் 120-ஆம் நெ. கல்வெட்டு), 'ஸ்ரீராஜராஜ விஜயம்' என்னும் நூலை வாசிப்பதற்காக நிவந்தம் அளிக்கப்பெற்ற செய்தியைக் கூறுகிறது. இரண்டாம் இராஜேந்திரசோழன் காலத்த தாகத் தஞ்சாவூர் பெரியகோவிலிலிருந்து கிடைக்கும் மற்றொரு சாச னம் (நெ. இ. சாசனங்கள், இரண்டாம் வால்பூம், நெ. 67) அக்கோயி லிலே வைகாசிப் பெருவிழாவில் ராஜராஜேச்வர நாடகத்தை ஆடிக் காட்டுவதற்கான நிவந்தம் அளிக்கப்பட்டிருந்ததைத் தெரிவிக்கிறது. இந்நூற்கள் எந்த மொழியில் எழுதப்பட்டிருந்தன என்ற விவரம் தெரியவில்லை; பெரும்பாலும் தமிழில் எழுதியவைகளாகவே இருத் தல் வேண்டும். தஞ்சைப் பெரியகோயிலில் எழுந்தருளியிருக்கும் எம் பெருமான் பெயரே ராஜராஜேச்வரர் என்பது. ஆகவே, அக்கோயில் நிர்மாணிக்கப்பெற்ற சம்பவத்தையே நாடக உருவில் எடுத்துக்காட்டுவ தாக அந்த நாடகத்தைச் சொல்லலாம். மற்றது அம்மன்னன் வாழ்க் கைச் சம்பவங்களை எடுத்துக்கூறும் காவியமாக இருந்தல் வேண்டும். எவ்விதமாயினும் இரண்டிலும் முதலாம் இராஜராஜ சோழனுடைய வாழ்க்கைச் சம்பவங்களுள் முக்கியமானவை சில விவரிக்கப்பட்டிருத் தல் இயல்பே.

இதேபோல் முதற் குலோத்துங்கசோழ மன்னன்மீது 'குலோத் துங்க சோழசரிதை' என்ற நூல் ஒன்று இயற்றப்பட்டிருந்ததென்பது புதுச்சேரிக்குப் பக்கத்தில் உள்ள திரிபுவனி என்னுமிடத்திலிருந்து கிடைக்கும் ஒரு கல்வெட்டி (1919-ஆம் ஆண்டின் 198-நெ.) விருந்து தெரிகிறது. மானகுலாசனிச்சேரியைச் சேர்ந்த திருநாராயண பட்டர் என்னும் கவிமுதாசன்திரன் அதை இயற்றினார். அந்நூலைப் படிக்கக் கேட்டு அரங்கேற்றி ஆசிரியருக்கு ஏற்ற சம்மானம் செய்ய வேண்டு மென்று அரசன் அளித்த திருமுகத்தின்படி அவ்வூர்ச் சபையார் நூலைப் படிக்கக்கேட்டு அதன் ஆசிரியருக்கு நிலம் அளித்திருக்கிறார்கள்.

திருவாரூர்க் கோயிலில் ஒரு சமயம் தேவரடியார் ஒருத்தியின் நடனத்தைப் பார்த்திருந்த சோழமன்னன் ஒருவன் சிற்றாசனான

வீரசோழ அணுக்கன் என்பானைப் புகழ்ந்து 'வீரணுக்க விஜயம்' என்ற பெயரில் ஒரு தூல் எழுதிய பூங்கோயில் நம்பி என்பாருக்கு இறையிலி யாக நிலம் வழங்கிய செய்தியைத் தெரிவிக்கும் சாசனம் ஒன்றும் (1904-ஆண்டின் 548-நெ.) கிடைத்திருக்கிறது.

இத்தகைய தூல்கள் இப்போது கிடைக்காமல் மறைந்து போனது நம் நாட்டுச் சரித்திர ஆராய்ச்சிக்குப் பெரு நஷ்டமேயாகும்.

இம்மாதிரியே சேஷத்திரங்கள், பெரிய கோயில்கள் ஆகியவற்றின் வரலாற்றைக்கூறும் தூல்கள் உள்ளன. மதுரையில் கோயில்கொண்டு எழுந்தருளியிருக்கும் மீனாட்சிசுந்தரேசர் ஆலயம் அந்நகரம் ஆகிய வற்றின் வரலாற்றை உரைக்கும் மதுரைத்தல வரலாறு என்பதைப்பற்றி முன்னரே நாம் குறிப்பிட்டுள்ளோம். அது வரலாற்றை ஆகி காலத்தி லிருந்து கூறுவதாக இல்லை. சமீபகாலத்திய சரித்திரம் முற்றிலும் நம்பத் தகுந்ததாக உள்ளது.

கோயிலொழுது என்பதும் இதே போன்றதுதான். கோயில் என்று ஸ்ரீவைஷ்ணவர்கள் பக்தியோடு குறிக்கும் திருவரங்கப் பெரு நகர்க் கோயில் வரலாற்றையும் அதற்குப் பலர் செய்த சேவையையும் விரிவாக எடுத்துக் கூறுகிறது அந்தூல். அதிலே காணப்படும் செய்திக ளில் பல சாசனங்களால் உறுதிப்படுகின்றன. பூரி சேஷத்திரத்தில் உள்ள ஜகந்நாதர் ஆலயத்துக்கு இதேபோல் 'மாதலாபாஞ்சி' என்ற தூல் ஒன்று உண்டு. திருப்பதி என்னும் வடவேங்கடத்துக் கோயில் பற்றிய 'திருமலை ஒழுது' உள்ளது. காளஹஸ்திக் கோயிலைப் பற்றிய தூல் ஒன்றும் இம்மாதிரியே உண்டாம்.

### 3. சரித்திர ஆதாரங்களும் சாசனங்களும்

நம் நாட்டு மன்னர்கள் பெற்ற வெற்றிகளைப் புகழ்ந்து கூறுமுகத் தால் அவர்களுடைய போர்க்களங்களைப் பாடும் பிரபந்த வகைகள் தமிழிலே காணப்படுகின்றன. சேர வேந்தனான கணேக்கால் இரும் பொறையைச் சோழமன்னன் செங்கணன் கழுமலத்தில் முறியடித்து வெற்றி கொண்ட போர்க்களத்தைப் புகழ்ந்து பொய்கையார் பாடிய 'களவழி நாற்பது' என்பதே இந்தவகையில் இப்போது கிடைப்பவற் றுள் மிகவும் பழமையானது. முதற் குலோத்துங்க சோழன் கலிங்கப் போரிலே கொண்ட வெற்றியைப் புகழ்ந்து கவிச் சக்கரவர்த்தி சயங் கொண்டார் பாடிய 'கலிங்கத்துப் பாணி' மிகவும் பிரசித்தமானது. அவ் வேந்தன் மகனான விக்கிரம சோழன் கலிங்கத்திலே போர் நடத்தி வெற்றி கொண்டதை அவன் அவைக்களப் புலவான ஒட்டக்

கூத்தரும் கவிங்கத்துப் பாணி எனப் பாணி ஒன்று பாடிப் புகழ்ந்திருக்கிறாம். அதை அவரே தம்முடைய இதர நூல்களில் குறித்திருக்கிறார். ஆனால் அது கிடைக்கவில்லை. இவை யாவும் சரித்திர நிகழ்ச்சியான அரசன் வெற்றியை விவரித்துக் கூறுகின்றனவே ஆயினும் பெரிதும் சம்பிரதாயத்தை ஒட்டியே கவிஞர்களது கற்பனைத் திறம் விளங்க இலக்கியச் சுவை மிகுந்து உள்ளனவே.

பதினான்காம் நூற்றாண்டின் மத்தியில் தமிழ்நாட்டிலே ஆதிக்கியம் பெற்று அரசு புரிந்துவந்த முஸ்லிம்களிடமிருந்து நாட்டை மீட்பதற்காக விஜயநகர அரசினங்குமான குமார கம்பணன் படைநடத்தி வந்து போரிட்டு வெற்றிகொண்டதை விவரித்து அவன் தேவிகளுள் ஒருத்தியான கங்காதேவி என்பவள் 'மதுராவிஜயம்' என்ற பெயரில் வடமொழிக் காவியம் ஒன்று இயற்றியிருக்கிறார். தமிழ்நாட்டிலே அந்நாளில் முஸ்லிம் ஆட்சி நிறுவியதைப்பற்றித் தெரிவிக்கும் முஸ்லிம் சரித்திரங்களில் காணும் தவறுகளைத் திருத்தி உண்மையை உணரவதற்கு இந்நூல் பெரிதும் உதவுவதாகும்.

இவற்றைத் தவிர, நம் நாட்டு மன்னர்களைப் பாட்டுடைத் தலைவர்களாகக் கொண்டு அவர்களுடைய கீர்த்திகளைக் கூறும் வேறு பல சில்லறைப் பிரபந்தங்களும் உள. விக்கிரம சோழன், இரண்டாம் குலோத்துங்கன், இரண்டாம் இராஜராஜன் ஆகிய மூவரில் ஒவ்வொருவர் மீதும் தனித்தனியாகக் கவிச்சக்கரவர்த்தி ஒட்டக்கூத்தர் பாடிய மூன்று உலாக்களைக் கொண்ட மூவருலா, மூன்றாம் குலோத்துங்கனுடைய தம்பியான சங்கரசோழனைப் புகழ்ந்து ஒரு கவிஞர் பாடிய சங்கரசோழனுலா ஆகியவை உலாப் பிரபந்தங்களிலே முக்கியமானவை.

கோவை என்னும் வகையிலே மிகவும் பழமையானது இறையனார் அகப்பொருளுரைக்கு உதாரணச் செய்யுட்களாக அமைந்த 'பாண்டிக் கோவை'யாகும். குலோத்துங்க சோழன்மீது பாடப் பெற்ற குலோத்துங்கன் கோவையும் கிடைத்துள்ளது. அதன் ஆசிரியர் பெயர் தெரியவில்லை. பாட்டுடைத் தலைவனையும் மூன்றாம் குலோத்துங்கனாகவே கொள்வர். பொட்டைத் தஞ்சை என்றும் குறிக்கப்படும் பாண்டி நாட்டுத் தஞ்சாக்கூரிலிருந்து அரசு புரிந்த வாணர் குலச் சிற்றரசன்மீது பொய்யாமொழிப் புலவர் இயற்றிய 'தஞ்சை வாணன் கோவை'யும் இவ்வகையைச் சேர்ந்ததே. நம்பி அகப்பொருளுக்கு உதாரணச் செய்யுட்களாக அமைந்தது இக் கோவை.

இரண்டாம் குலோத்துங்க சோழனுக்கு அவைக்களப் புலவராக மட்டுமல்லாமல் அவனுடைய இளமைப் பருவத்தில் ஆசிரியராகவும்

இருந்த ஒட்டக்கூத்தர் அம்மன்னன்மீது ‘குலோத்துங்கன் பிள்ளைத் தமிழ்’ என்ற பிரபந்தம் ஒன்றும் பாடியிருக்கிறார்.

கலம்பக வகையிலே பிரசித்தமானது ‘நந்திக் கலம்பகம்’ ஆகும். தெள்ளாற்றுப் போரிலே வெற்றிகொண்ட பல்லவ மன்னன் நந்திவர்மன் மீது பாடப்பெற்ற அந்தூல் அதன் இலக்கியச் சுவைக்காகப் பலரும் விரும்பிப் படிப்பது; மன்னன்மீது பொறுமை கொண்ட அவன் தம்பி ஒருவன் அரம் வைத்துப் பாடியது என்பர். ‘நந்தி கலம்பகத் தூல் மாண்ட கதை நாடறியும்’ என்று சோமேசர் முதுமொழி வெண்பா கூறுவதிலிருந்து இது விளங்கும்.

இத்தகைய தூல்களிலும் சரித்திர முக்கியத்வம் பெற்ற பல விஷயங்கள் சம்பிரதாயமான முறையிலேயே குறிக்கப்பட்டுள்ளன. குலோத்துங்கன் அவதாரத்தைக் கூறும்பொழுது சயங்கொண்டார் கவிங்கத்துப் பாணியில்,

“வந்தருளி யவதாரஞ் செய்தலுமே  
மண்ணுலகு மறைக ணாங்கும்  
அந்தரீங் கினவென்ன வந்தாதுந்  
துபிமுழங்கி யதிர்ந்த வாங்கே”

என்று புகழ்ந்து கூறுகிறார். அதே போல வீரராஜேந்திரன் இறந்த பின்னர் குலோத்துங்கன் சோழநாடு போந்து பட்டமேற்கும் காலத்தில் நாடு இருந்த நிலையை,

“மறையவர் வேள்வி குன்றி மனுநெறி யனைத்து மாறித்  
துறைகளோ ராறு மாறிச் சுருதியு முழக்க மோய்ந்தே”

என்று வருணிக்கிறார். இவை யாவும் பழைய முறையைப் பின்பற்றி இலக்கியச் சுவை தோன்ற மொழிந்தனவே யன்றிச் சரித்திர நிகழ்ச்சிகளாக கருதவேண்டுமெனல்.

அன்றி, சரித்திர நிகழ்ச்சிகள் குறிக்கப்பட்டிருக்கும் இடங்களிலும் அவற்றின் விவரங்கள் காணப்படவில்லை. நந்திக் கலம்பகத்தில் தெள்ளாற்றெறிந்த நந்திவர்மன் “படையாறுசாயப்பழையாறுவென்றான்” என்று பொதுவாகக் கூறப்பட்டிருக்கிறது. ஆனால் பழையாற்றுச் சண்டைக்குக் காரணம் என்ன, அவ்விடத்தில் அவன் யாரை வெற்றி கொண்டான் முதலிய விவரங்கள் காணப்படவில்லை.

எனினும், பல சமயங்களில் சாசனங்களில் காணும் விஷயங்களை விளக்குவனவாக அமைந்துள்ள இவ்வகை தூல்கள் சரித்திர ஆராய்ச்சிக்கு மிகவும் உபயோகமாக இருக்கின்றன. இவற்றில் உள்ள சரித்திரச் செய்திகள் மிகவும் முக்கியமானவை. ஆயினும் இவற்றை நாம் ஜாக்கிரதை யாகவே உபயோகிக்க வேண்டும்.

பாணி, உலா முதலிய நூல்களில் 'திருமுடியடைவு' என்று வழங்கப்பெறும் இராசபாரம்பரியப் புகுதி காணப்படுகிறது. அதனுள்,

“மண்கண்ட பொன்னிக் கரைகட்ட வாராதாம்  
கண்கொண்ட சென்னி கரிகாலன்”

(குலோ. உலா.)

என்பது போன்று பாட்டுடைத் தலைவனுடைய முன்னோர் கொண்ட வெற்றிகள் விரிவாகக் கூறப்பட்டுள்ளன.

ஆயினும் பல இடங்களில் அவர்களுடைய பெயர்களை வெளிப் படையாகக் கூறாமல் அவர்களுடைய சிறப்பை மட்டும் எடுத்துக் காட்டிச் செல்வர் நூலாசிரியர்.

“தண்டினா”

கங்கா நதியும் கடாரமும் கைக்கொண்டு

சிங்கா தனத்திருந்த செம்பியனும்”

என்று விக்ஃம சோழனுலாவில் முதலாம் இராஜேந்திர சோழன் புகழப்பட்டிருக்கிறான். கங்கையும் 'கடாரமும் கொண்ட அவன்' 'கங்கைக் கொண்ட சோழன்' எனவும், 'கடாரம் கொண்டான்' எனவும் சிறப்புப் பெயர்களைப் பெற்றிருந்த செய்தியை நாம் சாசனங்களின் மூலம் அறிவோமாதலால், இவ்விடத்தில் குறிக்கப்பட்டவன் அவனே என நாம் நிச்சயிக்கமுடியும். இராசபாரம்பரியம் வரு முறையிலும், அந்த இடத்தில் அது வேறு யாரையும் குறிக்கமுடியாது.

மற்றும் ஒருவகை இலக்கியம் உண்டு. ஜனரஞ்சகமான சந்தங்களில் அம்மாளை சிந்து போன்று எழுதப்பட்டனவற்றை இதுகாறும் யாரும் உன்னிப்பாக ஆராயவில்லை. எளிய நடையில் மக்களிடையே வாய்மொழியாகப் பரவுவதற்கு ஏற்ப அமைந்துள்ள இவ்வகை இலக்கியத்தில் இராமப்பையன் அம்மாளை, தேசிங்குராஜன் கதை, கான் சாயபு சண்டை, சிவகங்கைச் சரித்திர அம்மாளை, பாஞ்சாலங்குறிச்சி சிந்து முதலியவற்றைக் கூறலாம். இந்த ஒலைச்சுவடி நிலயத்திலேயே மக்கென்வியின் தொகுப்பில் தேசிங்குராஜனைப்பற்றிய பாடல் ஒன்று இருக்கிறது. இப்போது வழக்கில் உள்ளதனின்றும் வேறான அது பெரும்பாலும் சரித்திர நிகழ்ச்சியை ஒட்டியுள்ளது.

இவ்விதம் பலவகையாக உள்ள சில்லறைப் பிரபந்த இலக்கியங்கள் படிக்க அழகாகவும் பல விஷயங்களைத் தெரிவிப்பனவாகவும் இருக்கும் எனினும் அவற்றுள் பெரும்பாலானவை சரித்திர ஆராய்ச்சியிலே காலவரையறைக்கு உபயோகப்படா. அது ஒன்றைத் தவிர அவை வேறு துறைகளில் மிகுதியும் பயன்படக் கூடியவை.



காவியமோ, பிரபந்தமோ, ஸ்தலபுராணமோ, மாகாத்மியமோ எதுவாயினும் பொதுவாக எல்லா தூல்களிலும் உள்ள சிறப்புப் பாயிரப்பகுதி மிகவும் முக்கியமானது. அதனுள் அந் தூலை இயற்றிய ஆசிரியர் பெயர், அவர் அதனை இயற்றிய காலம், அக்காலத்திலிருந்து அவரை உபசரித்த வள்ளலைப்பற்றிய விவரங்கள் ஆகியவை காணப்படும். எனினும் அவ்விடம் காணப்படுபவை பெரும்பாலும் தூலாசிரியர்களின் பெருமையை எடுத்துக்காட்டும் நோக்கத்துடனேயே எழுதப் பெற்றிருக்கும். அவர்களை ஆதரித்த புரவலர்களைப்பற்றிய புகழ்ச்சியும் இதே காரணத்துக்காக அமைந்ததே என்னலாம்.

‘லோக விபாகம்’ என்னும் ஜைனமதக் கிரந்தம் ஒன்று உண்டு. அது மோக்ஷபாகம் உள்ளிட்டுப் பதினொரு பிரகாணங்களைக் கொண்டது. அது வர்த்தமானரால் ஸுதர்மாவுக்கும் மறவர்களுக்கும் உபதேசிக்கப்பட்டது என்பர். குருசிஷ்ய முறையாக வழிவழி வந்து வெகு காலத்திற்குப் பிறகு ரிஷி வலிம்ஹ ஸுமி என்பவர் அதனை வட மொழியில் எழுதினார். (மைசூர் ஆர்க்கி. அறிக்கை, 1917) இப் பொழுது கிடைக்கும் அந்த தூலின் ஏட்டுப் பிரதிகள் எல்லாவற்றிலும் அது பாணராஷ்டிரத்தில் உள்ள பாடலிகை என்னும் கிராமத்தில் குறிப்பிட்ட கிருஹநிலைகளைக்கொண்ட ஒரு நாளில் ஸர்வநந்தி என்பவரால் பெயர்த்தெழுதப்பட்டது என்று குறிக்கப்பட்டிருக்கிறது. அன்றி, காஞ்சிபுரத்தினின்றும் அரசு செலுத்திவந்த பல்லவ அரசன் வலிம்ஹ வர்மன் ஆட்சியின் இருபத்திரண்டாம் ஆண்டுக்குச் சமமான 380-ஆம் வருஷத்தில் அது பூர்த்தியாயிற்று என்றும் ஒரு சுலோகம் தெரிவிக்கின்றது. பாடலிகை என்பது பாடலிபுரம் என்று வழங்கப் பெறும் திருப்பாதிரிப் புலியூரேயாகும். அங்கே சமணப்பள்ளி இருந்துவந்தது என்பது பெரியபுராணத்தினின்றும் தெரிகிறது. தூலைப் பெயர்த்தெழுதிய நாளில் இருந்தனவாக ஸர்வநந்தி கொடுத்திருக்கும் கிருஹ நிலைகளைக் கொண்டு ஜோதிஷரீதியாகக் கணித்தால் அது ஒத்திருப்பதைக் காணலாம். இதனால் வலிம்ஹவர்மன் என்னும் பல்லவ அரசன் ஒருவன் சக 359 (கி. பி. 437) -ஆம் ஆண்டில் காஞ்சிபுரத்தைத் தலைநகராகக் கொண்டு அரசு செலுத்த ஆரம்பித்தான் என்பதும், அவன் ஆட்சியின் இருபத்திரண்டாம் ஆண்டில், (கி. பி. 459) திருப்பாதிரிப்புலியூரிலிருந்த ஸர்வநந்தி என்பவர் ‘லோகவிபாகம்’ என்னும் ஜைனமதக் கிரந்தத்தைப் பெயர்த்தெழுதினார் என்பதும் ஏற்படும். அக்காலத்தில் வலிம்ஹவர்மன் என்னும் பல்லவ அரசன் அரசு செலுத்தி வந்தான் என்பதைப் பெனு கொண்டைச் செப்பேடுகள் உறுதிப்படுத்துகின்றன.

சோமதேவ ஸுமி என்னும் ஜைன ஆசிரியர் தம்முடைய வடமொழி தூலான ‘யசஸ்திகை சம்பு’வைச் சகாப்தம் 881-க்கு மேல் செல்லா

நின்ற சைத்ர மாதம் (கி. பி. 959-ஆம் ஆண்டு) எழுதி முடித்தார். அப்போது கிருஷ்ணராஜன்கீழ்ச் சிற்றரசனாக அரிகேசரியினுடைய மூத்த குமாரன் ஆட்சி புரிந்து வந்தான் என்றும், கிருஷ்ணராஜன் பாண்டிய சிங்கள சேர மன்னர்களை வெற்றி கொண்டு மேல்பாடியிலிருந்து அரசு செலுத்திவந்தான் என்றும் அவர் நூலிலே கூறியிருக்கிறார். இவற்றைத் தவிர, அவர் தம்மை ஆதரித்த குறுநில மன்னன் எந்தப் பிரதேசத்தை ஆண்டுவந்தான் என்றோ அவன் எந்த வமிசத்தைச் சேர்ந்தவன் என்றோ கூறவில்லை. எனினும், கி. பி. 959-ஆம் ஆண்டு மார்ச்சு மாதம் ஒன்பதாம் தேதி கொண்டதாகக் கிடைத்துள்ள ராஷ்டிரகூட வேந்தனான மூன்றாம் கிருஷ்ணனுடைய கர்ஹாட்செப்பேடுகளிலிருந்து அவன் அப்போது தென்னாட்டின்மீது வெற்றிகொண்டு சித்தூர் ஜில்லாவில் உள்ள மேல்பாடி என்னும் இடத்தில் தங்கியிருந்தான் என்றும், அவன் புரிந்த கிக்குவிஜயத்தில் 'சோழர்களை முறியடித்துச் சிங்களம் உள்படப் பல நாட்டு மன்னர்களிடமிருந்தும் திறைபெற்றான்' என்றும் தெரியவருகிறது. இவற்றிலிருந்து சோமதேவ ஸூரியை ஆதரித்த அரிகேசரியின் மகன் ராஷ்டிரகூட வேந்தனான மூன்றாம் கிருஷ்ணன் கீழ்ச் சிற்றரசனாக இருந்தவன் என்பது தெரியவரும். கன்னட மொழி யிலே விக்கிரமாஜயா விஜயம் என்ற மறு பெயருடன் பம்ப கவி எழுதிய பாரதத்திலிருந்து இந்த அரிகேசரியைப் பற்றி மேலும் விவரங்கள் கிடைக்கின்றன. கி. பி. 941-42-ஆம் ஆண்டில் எழுதப்பெற்ற பாரதத்தில் அம்மன்னனுடைய புகழும் அவன் முன்னேரில் எழுதலைமுறை வந்தவர் விவரங்களும் சரித்திரக் குறிப்புகளும் காணப்படுகின்றன. சாளுக்கியர்களில் லேமூலவாடக்கிளையின் சரித்திரத்தை எழுதுவதற்குச் சாசனங்களோடு இவைகளே முக்கிய ஆதாரங்களாக உள்ளன.

இதேபோன்றதுதான் கி. பி. பதின்மூன்றாம் நூற்றாண்டின் மத்தியில் ஹேமாத்ரி என்பார் எழுதிய விரதகண்டத்தின் பாயிரப்பகுதியும். தேவகிரி யாதவ மன்னர்களான மகாதேவன், அவன் மகன் இராமசந்திரன் ஆகியோர்களின் ஆட்சியிலே ஸ்ரீகாண்திபர், அதாவது ஒலை எழுதும் துறையின் தலைவரான ஒலைநாயகம் போன்ற பதவியை வகித்து வந்த அவர் தம்மை ஆதரித்த அரசு பரம்பரையின் வரலாற்றைப் புராணகாலத்திலிருந்து அந் நாள் வரையில் அந்தப் பாயிரத்திலே கொடுத்திருக்கிறார். அவர் வகித்திருந்த பதவியின் காரணமாக அரசு பரம்பரையின் உண்மை வரலாற்றை நன்கு அறிந்து கொள்வதற்கான வசதியும் வாய்ப்பும் அவருக்குக் கிட்டியிருத்தல் வேண்டும். அவற்றை கொண்டு அவர் கொடுத்த வரலாற்றை நாம் உண்மையாகவே கருதலாம். எனினும் பல சமயங்களில் அவர் ஓர் அரசனுக்கும் அவனுக்குப் பின்

பட்டத்துக்கு வந்தவனுக்கும் உள்ள உறவு முறையைத் தெளிவாக எடுத்துக் கூறாமல் விட்டுவிடுகிறார். தந்தைக்குப் பின் மகன் என்ற முறையிலேயே முன்னோர் அரசுபாரம் ஏற்று வந்திருத்தலால் நாம் அம்முறையிலேயே கொள்ளவேண்டும் போலும்.

இவற்றைப் போலவே நூலாசிரியர்களும் தங்களைப் பற்றிய செய்திகள் சிலவற்றைக் கூறிச் செல்வர். வடமொழி நூல்கள் சிலவற்றுள் ஆசிரியருடைய பரம்பரைச் செய்திகளும் காணப்படுகின்றன. அவர்களுடைய தந்தை, பாட்டன் ஆகியோருடைய விருத்தாந்தங்களும், அவர்கள் யார் யாரிடம் படித்து வந்தார்கள் என்பதும் கூறப்பட்டுள்ளன. தமிழ் நூல்களில் அத்தகைய செய்திகள் அதிகம் காணப்படவில்லை.

உதாரணமாக, நதிண்டலா கோபமந்திரி என்பவர் தாம் எழுதிய 'கிருஷ்ணர்ஜுந ஸம்வாதம்' என்னும் நூலில் தம்முடைய முன்னோர்களைப் பற்றியும், தமக்கு மாமனும், அப்பாஜி என்று சரித்திர பிரசித்தி பெற்றவருமான (கிருஷ்ணதேவராயருடைய மந்திரி) சாளுவ திம்மாஜியைப்பற்றியும் விவரமாகக் கூறியுள்ளார்.

'அவந்தி சுந்தரிகதை' என்ற பெயரில் மகாகவி தண்டி வடமொழியிலே இயற்றிய காவியத்தின் முன்னுரையில் தாம் மகாகவி பாரவியின் தோழனான தாமோதரன் என்பாருடைய கொட்பெயரன் என்று கூறிக் கொள்ளுகிறார். இன்னும் அதிலிருந்து பாரவி என்பார் சாளுக்கிய வேந்தனான விஷ்ணு வர்த்தனன், மேலைக் கங்க அரசனான துர்வீரீதன், பல்லவ மன்னனான வலிம்ஹவிஷ்ணு ஆகிய மூவருடைய சபைக்கும் விஜயம் செய்திருக்கிறார் என்பது தெரிகிறது. ஆகவே இந்த மூன்று மன்னர்களும் சமகாலத்தவர்கள் என்பது எளிதில் விளங்கும்.

நூல்களுள் காணப்படும் சிறு செய்திகளும், குறிப்புகள் சிலவும் சரித்திர ஆராய்ச்சிக்குப் பெரிதும் உபயோகமாகவுள்ளன. மண்டல புருடர் எழுதியுள்ள சூடாமணி நிகண்டில் அதன் ஆசிரியர்,

“கெடிமன்னர் வணங்குந் தாளான் கிருட்டின ராயன் கைபோற் கொடைமட மென்ப தம்ம வரையாது கொடுத்த லாமே”

என்று கிருட்டினராயன் என்னும் அரசனுடைய கொடைத்திறனைப் புகழ்ந்து கூறுகிறார். அங்கே குறிக்கப்பட்டவர் கி. பி. பதினாறாம் நூற்றாண்டின் தொடக்கத்தில் விஜயநகர ஸாம்ராஜ்யத்தை ஆண்டுவந்த கிருஷ்ணதேவராயரேயாவார். ஆதலின் இந் நூலினுடைய ஆசிரியரும் அக்காலத்தில் வாழ்ந்தவர் என்று கொள்ளலாம்.

இவ்விதம் சரித்திர நூல்களாக உள்ளவற்றைத் தவிர, பிற நூல்களிலும் அவை எழுதப்பட்ட காலங்களில் ஆண்ட அரசர்களைப்பற்றி மட்டுமேயன்றி அம் மன்னர்களுடைய முன்னோர்களைப் பற்றிய விவரங்களும் காணப்படுவது எங்ஙனம்? அவையாவும் உண்மையாக இருக்க முடியுமா? அவர்கள் அந்த விவரங்களையும் மன்னர்களின் வமிசாவளியையும் எவ்விதம் அறிந்தனர்? இத்தகைய கேள்விகள் உண்டாவது இயற்கையே.

நம் நாட்டவர்களுக்கு வமிசங்களின் கிளைகளைப் பற்றிய விவரங்கள் நன்றாகத் தெரிந்திருப்பது மிகவும் சாதாரண விஷயம். இன்றைக்கும் பல குடும்பங்களில் ஏழு தலைமுறைகளுக்கு மேற்பட்ட வமிசாவளிகள் இருப்பதை நாம் காணலாம். ஒரே குடும்பம் பலவாறாகப் பிரிந்து போய்விடலும் சபாசப காரியங்களுக்கு அந்தக் குடும்பத்தைச் சேர்ந்தவர்கள் ஒன்றுசேர வேண்டியதைக் கருதியே அங்ஙனம் வைக்கப்பட்டிருக்கிறது போலும். அன்றி, அவை லௌகிகமாகவும் மானியம் போன்ற சொத்துக்களின் உரிமை, அந்தர வாரிசு பாத்தியதை முதலியவற்றை நிலை நிறுத்தவும் உபயோகப்படக் கூடியன.

நம் நாட்டில் உள்ள முக்கியமான மடம் ஒவ்வொன்றிலும் அது ஏற்பட்ட நாள்முதல் அதிலே குருசிஷ்ய பாம்பரையாகப் பதவி ஏற்று அருளாட்சி நடத்திவந்த தலைவர்களின் வரன்முறையைத் தெரிவிக்கும் பட்டாவளி இருந்துவருகிறது. கிறிஸ்து பிறப்பதற்கு ஐந்தாறு ஆண்டுகளுக்கு முற்பட்ட காலத்திலிருந்தே தொடங்கி ஜைனமதத்தின் கடைசித் தீர்த்தங்கரரான மகாவீரர் முதல் வரிசையாக வரும் ஜைன மடப் பட்டாவளிகள் சிலவற்றை ஆராய்ச்சியாளர்கள் ஆராய்ந்திருக்கிறார்கள் (இந்தியன் ஆண்டிகுவரி, 20, 21-ஆம் தொகுதிகள்). திருவள்ளூர் வீரராகவப்பெருமாள் கோயிலுக்குச் சகாப்தம் 1552, அதாவது கி. பி. 1680-ஆம் ஆண்டில், வீரராகவ சடகோப ஜீயர் என்பார் பொன் அளித்த செய்தியைத் தெரிவிக்கும் கல்வெட்டு ஒன்றை அந்தக்கோயிலிலிருந்து மக்கென்லியின் உதவியாளர்கள் பிரதி செய்திருக்கிறார்கள். (இந்தத் தொகுப்பின் 1107 நெ. சாசனம்). அந்தக் கோயில் அஹோ பலமடத்தின் நிர்வாகத்தில் உள்ளது. அந்த மடத்தின் பதின்மூன்றாம் பட்டம் வகித்த வீரராகவ சடகோப ஜீயர் கி. பி. 1630-முதல் 1675-வரையில் இருந்தார் என்று கூறப்படுகிறது. இதிலிருந்து அந்தக் கோயிலுக்குப் பொன் அளித்த ஜீயர் அந்த மடத்தைச் சேர்ந்தவரே என்பது தெளிவாகும்; அன்றி மடத்து வமிசாவளியின் நம்பிக்கைத் தன்மையும் விளங்கும்.

விஜயநகர மன்னனான வீர நரசிம்மன் சகாப்தம் 1429-க்குச் சரியான கி.பி. 1506-ஆம் ஆண்டில் சதாசிவ சரஸ்வதியின் சிஷ்யரான மகாதேவ சரஸ்வதி என்பாருக்குக் குடியாந்தண்டலம் என்னும் கிராமத்தை அளித்ததெய்தியைத் தெரிவிக்கும் செப்பேட்டுச் சாசனம் ஒன்று (எபி. இந்திகா, 14-வால்யும்) காஞ்சி காமகோடி மடத்தில் இருக்கிறது. அந்த மடத்துப் பீடத்தில் அமர்ந்திருந்த சங்கராசாரியர்களின் வரலாற்றைக் கூறும் 'குருராஜாத்நமாலிகா' என்னும் நூலிலிருந்து மகாதேவசரஸ்வதியைப் பற்றிய விவரம் தெரியவருகிறது. சாசனத்தில் கூறியுள்ளபடியே அவர் சதாசிவ சரஸ்வதியின் சிஷ்யராவர். அன்றி, அவருக்குச் சந்திரசூட சரஸ்வதி என்பவர் சிஷ்யராக இருந்தார் என்பதையும் தெரிவிக்கிறது அந்த நூல். சகாப்தம் 1444, அதாவது கி. பி. 1521-ல் சந்திரசூடருக்குக் கிருஷ்ணராயபுரம் கிராமத்தைக் கிருஷ்ணதேவராயர் தானம் செய்ததைத் தெரிவிக்கும் செப்பேட்டுச் சாசனம் உள்ளது. (ஷ) இவருக்குச் சந்திரசேகர சரஸ்வதி என்ற பெயரும் இருந்ததாகத் தெரிகிறது. கிருஷ்ணதேவராயர் ஆட்சியில் சகாப்தம் 1436, அதாவது கி. பி. 1514-ல், காஞ்சிபுரத்துக்குப் பக்கத்தில் உள்ள அம்பி என்னும் ஊர்க்கோயிலுக்கு அரசன் அளித்த நிவந்தத்தைத் தெரிவிக்கும் இந்தச் சந்திரசேகர சரஸ்வதியின் சாசனம் ஒன்றும் அந்தக் கோயிலிலே கிடைத்திருக்கிறது. கிருஷ்ணதேவராயரே சகாப்தம் 1450, அதாவது 1527-ஆம் ஆண்டில் உதயம்பாக்கம் கிராமத்தைச் சந்திரசேகர சரஸ்வதியின் சிஷ்யரான சதாசிவ சரஸ்வதிக்கு அளித்த செய்தியைத் தெரிவிக்கிறது (ஷ பதின்மூன்றாம் வால்யும்). குருபரம்பரைகளிலே சந்திரசூடர் என்பார் நேபாள மன்னனால் கௌரவிக்கப்பெற்ற செய்தி காணப்படுகிறது. நேபாள நாட்டு வரலாற்றிலிருந்தும் சோமசேகரானந்தர் என்னும் பெரியார் ஒருவர் கி.பி. 1503-ஆம் ஆண்டில் அந்நாட்டுக்கு விஜயம் செய்தார் என்பது தெரியவருகிறது. சந்திரசூடர், சந்திரசேகரர், சோமசேகரர் ஆகியவை ஒரே பொருளைக் கொடுக்கும் பெயர்கள். ஆகவே நேபாள சரித்திரத்தில் காணும் சோமசேகரானந்தர் என்பார் சந்திரசேகர சரஸ்வதியேயாவர் என்று கொள்வதில் தவறு ஒன்றும் இல்லை. இவற்றால் அவர் நேபாளம் போய்வந்த செய்தி உறுதியாவதுடன் வமிசாவளியின் மெய்ம்மைப்பாடும் விளங்கும்.

நேபாள நாட்டில் கலியுகம் பிறந்த நாள் முதல் ஆண்டுவந்த அரசர்களையும் அவர்களுடைய ஆட்சிக் காலங்களையும் தெரிவிப்பதாக உள்ள வமிசாவளியும் கிடைத்திருக்கிறது. (இ. ஆ., 13-வால்யும், பக்கம் 114). காலமுறையிலே அதில் பல தவறுகள் காணப்படுகின்றன வென்பது உண்மைதான். சமகாலத்தில் ஆதிக்கியம் வகித்த வமிசபுரம்

பணர்களை ஒன்றன்பின் ஒன்றாக வைத்துக் கூறும் தவறு அதிலும் உள்ளது. எனினும் அதுகூட ஆராய்ச்சிக்குப் பெரிதும் உபயோகமாக உள்ளது. பலசமயங்களில் அதில் காணும் சரித்திர நிகழ்ச்சிகள் கல் வெட்டுக்களால் உறுதியாகியுள்ளன. உதாரணமாக, அதிலே அந்நாட்டை ஆண்ட சூரிய வமிசத்தாருள் 18-ஆம் மன்னனான விருஷதேவனுக்கும் 23-ஆம் அரசனான வசந்த தேவனுக்கும் இடையில் ஆண்டவர்களாகக் காணும் ஆறு அரசர்களின் பெயர்கள் கல்வெட்டுக்களால் உறுதியாவதுடன் அவர்கள் அதே வரிசையில் ஆண்டதாகவும் தெரிய வருகிறது.

அவ்விதமே முற்காலத்தில் ஒவ்வொரு ராஜகரத்திலும் ராஜாவளிகள், அதாவது ராஜ்யபாரம்வற்ற அரசர்களின் வரன்முறை இருந்திருத்தல் வேண்டும். இது தமிழ் நாட்டுச் சாசனங்களினின்றும் நமக்கு நன்கு விளங்கவில்லையாயினும், பக்கத்திலே தெலுங்கு கர்நாடக தேசங்களில் ஆண்ட அரசர்களுடைய சாசனங்களால் தெரியவருகின்றது.

உதாரணமாக, வேங்கி நாட்டை ஆண்டுவந்த கீழைச் சாளுக்கிய வமிசத்துச் சாசனங்களில், கி.பி. பதினொராம் நூற்றாண்டில் பொறிக்கப்பட்ட செப்பேடுகளிலும், கி. பி. ஏழாம் நூற்றாண்டின் முற்பகுதியில் வாதாபி (மேலை)ச் சாளுக்கிய வேந்தன் இரண்டாம் புலிகேசியின் தம்பியான குப்த விஷ்ணுவர்த்தனால் அந்த வமிசம் நிறுவப்பெற்றகாலத்திலிருந்து சாசனகாலம் வரையில் ஆண்ட அரசர்களின் பெயர்கள், அவர்கள் அரசசெலுத்திய கால அளவு முதலியனவூரிசையாகக்கொடுக்கப்பட்டுள்ளன. ஏழாம் நூற்றாண்டுக்கும்பதினொராம் நூற்றாண்டுக்கும் இடைப்பட்ட காலத்துச் சாசனங்களை ஒன்று சேர்த்துக் கவனித்தாலும், அந்த விவரங்கள் ஒரே விதமாக உள்ளதை அறியலாம். ஒரு சாசனத்தில் உள்ளது போலவே மற்றொரு சாசனத்திலும் இருக்கும். அவற்றுள் ஒன்றிரண்டு இடங்களில் பேதங்கள் இருக்கின்றன. நேர் முறையில் இல்லாமல் பலாத்காரமாக நாட்டைக் கைப்பற்றிய இளைய பரம்பரையைச் சார்ந்தவர் முதலியோரை மூத்த பரம்பரையைச் சேர்ந்தவர்கள் கூறாமல் விலக்கியிருப்பது போன்ற வேறுபாடுகளே அவை. கலிங்க தேசத்தை அரசுபுரிந்த கீழைக் கங்க வமிசத்து அரசர்கள் அளித்தனவாகக் கிடைக்கும் சாசனங்களிலும் இதேபோல அந்த வமிசத்தின் ஆரம்பத்திலிருந்து நாட்டை ஆண்டுவந்த மன்னர்களின் பெயரும் அவர்களுடைய ஆட்சிக்காலமும் முறையாகக் கொடுக்கப்பட்டிருப்பதைக் காணலாம். ராஜகரத்திலே அத்தகைய ராஜாவளிகளை வைத்திருந்தாலே இவ்விதம் கொடுப்பது சாத்தியமாகும்.

காஞ்சீபுரத்துப் பல்லவமன்னர்கள் காலத்திலும் இத்தகைய தஸ்தாவேஜுகள் இருந்திருக்கவேண்டும். கி. பி. எட்டாம் நூற்றாண்டின் முற்பகுதியில் இரண்டாம் பரமேஸ்வரவர்மன் இறந்துபோன பிறகு சிங்காதனம் ஏறுவதற்கு உரியவர் 'உபயகுல பரிசுத்தராக' யாரும் இல்லாமை யால், மந்திரிகளும் மற்றப் பிரமுகர்களும் ஒன்று சேர்ந்து இளைய பரம்பரையைச் சேர்ந்த ஹிரண்யவர்மன் மகனான நந்திவர்மன் பல்லவ மல்லனைத் தேர்த்தெடுத்தார்கள் என்று காஞ்சீபுரம் வைகுண்டப்பெருமான் கோயிலில் உள்ள சாசனம் (தெ. இ. சாசனங்கள், வால்பூம் 4, சாசனம் 147 நெ.) தெரிவிக்கிறது. பல்லவமல்லனுடைய கசாக்குடிச் செப்பேடுகளிலிருந்து அவனுடைய வமிசாவளியும் நமக்குத் தெரிகிறது. ஏழுதலைமுறைகளுக்கு முன்னதாக மூத்தகிளையில் அரசுபுரிந்த ஸிம்ஹவிஷ்ணு மகாராஜாவின் தம்பியான புத்தவர்மனுடைய பெயரனுக்குப் பெயரனே ஹிரண்யவர்மனாவன் (ஹி. இரண்டாம் வால்பூம்). இந்த விவரங்கள் அத்தகைய தஸ்தாவேஜுகளிலிருந்தே கிடைக்க முடியும்.

மேலைச் சாளுக்கியர்கள் வாதாபியைத் தலைநகராகக் கொண்டு ஆறாம் நூற்றாண்டின் மத்தியிலிருந்து எட்டாம் நூற்றாண்டின் மத்தி வரையில் சுமார் இருதாறுவருஷகாலம் ஆண்டுவந்தனர். அவர்களுக்குப் பிறகு ராஷ்டிரகூடர்கள் அந்த நாட்டைக் கைக்கொண்டு இரண்டு நூற்றாண்டுகளுக்கு மேல் அரசு செலுத்தினர். அப்பால் சாளுக்கிய பரம்பரையினர் மறுபடியும் தலையெடுத்துத் தங்கள் முன்னோர்கள் இழந்த நாட்டைக் கைப்பற்றிக் கல்யாணபுரம் என்னும் நகரினின்றும் ஆண்டு வந்தனர். அவர்கள் பதினொராம் நூற்றாண்டின் முற்பகுதியில் கொடுத்த சாசனம் ஒன்றில் வாதாபிச் சாளுக்கியர்களுடைய பரம்பரையும் வீரப்பிரதாபங்களும் விரிவாக எழுதப்பட்டிருக்கின்றன. அந்த அரசை மறுபடியும் பழைய நிலைக்குக் கொண்டந்த இரண்டாம் தைலபனுடைய பெயரான ஐந்தாம் விக்கிரமாதித்தியன் கி. பி. 1009-ஆம் ஆண்டில் அளித்த கவுட்டேம் செப்பேடுகளில் (இ. ஆ., வால்பூம். 16) வாதாபிச் சாளுக்கியர்களில் கடைசியாக அரசுபுரிந்த மன்ன னிடமிருந்து தங்களுடைய வமிசாவளியையும் தொடர்ச்சியாகக்கொடுத்திருக்கக் காணலாம். வாதாபிச் சாளுக்கியர்களிலும் நேர்முறையில் வராத மங்கலேசன் ஆட்சியைக் குறிப்பிட்டு, அவன் அரசுக்கு உரியவனும் தன் தமையன் மகனுமான இரண்டாம் புலிகேசியின் பிரதிநிதியாகவே ராஜ்யபாரம் தாங்கினான் என்றும், புலிகேசிக்கு உரிய வயது வந்ததும் தரும்பபடி அரசை அவனிடம் ஒப்படைத்துவிட்டான் என்றும் கூறுகிறது அந்தச் சாசனம். மங்கலேசன் அரசுக்கு முறைப்படி உரிய

புலிகேசியை ஒதுக்கித் தன் மகனையே இளவரசனாக்கிய செய்தியை அது கூறாமல் மெழுகிவிடுகிறது.

சிற்றரசர் பதவி வகித்துவந்த வமிசங்களைச் சேர்ந்த சிலர் தங்களுக்குப் பேரரசர்களாக விளங்கியவர்களுடைய பரம்பரையைப் பற்றிய விவரங்களைக்கூட இதேபோல் எழுதிவைத்திருந்தனர் என்றும் தெரிகிறது. தென் கொங்கணத்தை ஆண்டுவந்த சிலாஹார வமிசத்து அரசர்களுடைய சாசனங்களிலிருந்து இது விளங்குகிறது. கல்யாணபுரத்தினின்றும் அரசு செலுத்திய மேலைச் சாளுக்கிய அரசனான சத்தியாசிரயன் ஆட்சியில் கி. பி. 1008-ஆம் ஆண்டில் சிலாஹார வமிசத்து ரட்டராஜன் வழங்கிய காரோபாட்டன் செப்பேடுகளில் ராஷ்டிரகூடமன்னர்களின் ஆட்சிக்காலத்தே சிலாஹாவமிசம் முன்னணிக்கு வந்ததையொட்டிப் பேரரசர்களில் ராஷ்டிரகூட ஆட்சியை நிறுவின தந்தி தூர்க்கன் முதல் அவ்வமிசத்துக் கடைசி வேந்தனான இரண்டாம் கர்க்கராஜன் வரையில் அவர்கள் வமிசாவளி கொடுக்கப்பட்டிருப்பதோடு அவர்களுக்குப் பின்னால் ராஜ்யபாரம் தாங்கிய சாளுக்கியர்களின் விபரமும் காணப்படுகிறது. (எபி. இந்திகா, மூன்றாம் வால்பூம்.)

இவற்றை நோக்குங்கால், அக் காலங்களிலே அரசாங்கங்களில் ராஜகரத்து விஷயங்களைத் தெரிவிக்கும் சுவடிகளைத் தனியாகவே வைத்துப் பாதுகாத்து வந்தனர் என்று எண்ணவேண்டி இருக்கிறது. அந்த அந்த வம்சங்கள் நாட்டில் ஆதிக்கியத்தை இழந்துவிட்டாலும் அவ்வம்சத்தினர் அத்தகைய சுவடிகளைப் பாதுகாத்திருந்தல் வேண்டும்.

‘பவர்சுவடி’ என்று பெயர் பெற்றுள்ள கணித நூல் ஒன்று சுமார் கி. பி. ஐந்தாம் நூற்றாண்டில் எழுதப்பட்டதாயினும் நல்ல நிலைமையில் நமக்குக் கிடைத்திருக்கின்றது. அது காசுமீரத்துக்கு வடக்கே காஷ்கரியா என்னும் பிரதேசத்தில் ஒரு கட்டடத்தின் அஸ்திவாரத்தினின்றும் எடுக்கப்பட்டது; பூர்ஜ பத்திரத்தில் எழுதப்பட்டுள்ளது. இதனால் நன்றாய்ப் பாதுகாக்கப்பட்ட ராஜகரத்துச் சுவடிகளை ஐந்தாறு நூற்றாண்டுக் காலம் சிதிலமாகாமல் பாதுகாக்க முடியும் என்று நிச்சயமாகக் கொள்ளலாம்.

முன்னாளிலே ஒவ்வோர் அரசாங்கத்திலும் தினசரிக் குறிப்பு ஒன்று எழுதப்பட்டு வந்தது என்று தெரிகிறது. பேரரசாயினும் சரி, சிற்றரசாயினும் சரி, நாள்தோறும் நடந்த முக்கியமான சம்பவங்கள் அதிலே எழுதப்பட்டிருக்கும். பல சமயங்களில் அத்தகைய குறிப்புகளை எழுதுவதற்கெனத் தனி அதிகாரிகளும் இருந்தனர்



எனத் தெரிகிறது. அவை கிரந்தவாரி எனக் குறிக்கப்பெறும். சென்ற நூற்றாண்டின் ஆரம்பத்தில் கர்னல் மக்கென்வியின் உதவியாளர்கள் இத்தகைய கிரந்தவாரிகள் சிலவற்றைச் சேகரித்திருக்கிறார்கள். ஆனால் அவை எல்லாம் சமீபகாலத்தைச் சார்ந்தனவே. மராத்தியர் ஆட்சிக் காலத்து நாட்குறிப்புகள் (ரோஜ்நிசீ), மொகலாயர் காலத்துக் குறிப் புகள் முதலியனவும் கிடைத்துள்ளன. ஆனால் அவற்றுக்கு முற்பட்ட காலத்தைச் சேர்ந்தனவாக நம் நாட்டு ஹிந்து மன்னர்கள் ஆட்சியிலே எழுதப்பட்டவை இதுகாறும் கிடைக்கவில்லை.

பிற்காலத்தில் பேஷ்வாக்கள் முதலியோர் வைத்திருந்த கணக்கு களைப் பார்த்து, பழைய காலத்திலும் அவ்விதமே இருக்குமோ என்று ஒருவாறு எண்ணலாம். பேஷ்வாக் குறிப்புகளில் ஒவ்வொரு நாள் சம்பவங்களும் தொடர்ச்சியாக, இலாக்காவாரியாகப் பிரிக்காமல், எழுதப் பட்டுள்ளன.

இத்தகைய வரலாறுகளை அவர்கள் அவ்வப்பொழுது எழுதிச் சேர்த்துக்கொண்டே போயிருத்தல் வேண்டும். சோழ பாண்டிய மன் னர்களின் சாசனங்களைக் கவனித்தால் இது நன்கு விளங்கும். அவற் றுள் காணப்படும் மெய்க்கீர்த்தி அந்த அந்த அரசாங்கது ஆட்சியின் ஆண்டை ஒட்டியே வளர்ந்து வருவது தெரியும். ஓர் அரசனுடைய இரண்டாம் ஆண்டுச் சாசனத்தில் உள்ள மெய்க்கீர்த்தியை விட அவ னுடைய மூன்றாம் ஆண்டுச் சாசனத்தில் உள்ளது நீளமாகவும் அதிக மான செய்திகளைத் தெரிவிப்பதாகவும் காணப்படும். ராஜாங்க வித்து வான்கள் மன்னர்களுடைய புகழ்களை அவ்வப்பொழுது நிகழுந்தோறும் பாடிச் சேர்த்துக்கொண்டே வந்திருக்கிறார்கள். இவ்விதம் வளர்ந்து வரும் மெய்க்கீர்த்தியில் பழைய பாகங்களை மாற்றாமல் மேலே சேர்த் துக்கொண்டு போவது குறிப்பிடத்தக்கது.

கிறிஸ்து பிறப்பதற்கு முன்பு கலிங்க தேசத்து அரசனாக விளங் கிய காரவேலனது ஹாதிகும்பாச் சாசனத்தையும் இத்தகைய மெய்க் கீர்த்திபோலவே கொள்ளவேண்டும். பிறந்தது முதல் அவன் ஆட் சியின் பதின்மூன்றாம் வருஷம் வரையில் அவன் வாழ்க்கையை வருணி கிறது அச் சாசனம். மன்னன் தன் வாழ்நாளின் முதல் பதினைந்து வருஷங்களை விளையாட்டுக்களிலும், பிறகு ஒன்பது வருஷங்களை யுவரா ஜனாகவும் கழித்து இருபத்துநான்காம் ஆண்டின் முடிவில் முடிசூட்டப் பெற்றான் என்பதைக் கூறி அப்பால் அவன் ஆட்சியில் ஒவ்வோர் ஆண்டிலும் நடந்த நிகழ்ச்சிகளை முறையாக விவரித்துச் செல்கின்றது அது. ஹர்ஷ சரித்திரம்போல இதுவும் ராஜ கவியால் எழுதப்பட்டது

போலும். எக்காரணத்தினாலோ அது அரசன் ஆட்சியின் பதின்மூன்றாம் ஆண்டுடன் நின்றுவிட்டது. (எபி. இந்திகா, இருபதாம் வால்யூம்).

ஆனால் புதிய அரசன் ஒருவன் பட்டமேற்றவுடன் அவனுக்காகப் புதிய மெய்க்கீர்த்தி ஒன்றைச் சிருஷ்டிக்கும் வழக்கத்துக்கு மாறாக வாதாபிச் சாளுக்கியர்கள் தங்கள் பிரசஸ்தியில் முன்னோர்களைப்பற்றிய பகுதியை அப்படியே வைத்துக் கொண்டு மேலே எழுதிச் சேர்த்துக் கொண்டே போயிருக்கிறார்கள்.

இவ்விதம் ராஜகரத்து வரலாறுகளை எழுதியவர்கள் சுவடிகளையும் ஆதாரங்களாகக் கொண்டனர்போலும். இப்பொழுது உள்ளது போலவே முற்காலத்திலும் அரசாங்கத்தில் தஸ்தாவேஜுகளைப் பாதுகாத்து வந்திருத்தல் வேண்டும்.

சோழ பாண்டிய சாசனங்களிலிருந்து அந்நாளிலே இராஜ்ய நிர்வாகம் எவ்வாறு நடந்து வந்ததென்பதை நாம் ஓர் அளவு தெளிவாக அறியலாம். முற்காலத்தில் அரசாங்கம் இப்பொழுது உள்ளது போலவே பல இலாக்காக்களாகப் பிரிக்கப்பட்டிருந்தது. எனினும், அவற்றுள் ஒன்றுக்கொன்று நெருங்கிய சம்பந்தம் பெற்றிருந்தது. ஒவ்வோர் இலாக்காவிலும் உயர்தர அதிகாரிகள் பலர் இருந்திருக்கின்றனர். அத்தகையோரின் பதவிப் பெயர்களை நாம் கல்வெட்டுக்களிலே காணலாம். பெருந்தரத்து அதிகாரிகளுக்கேற்பச் சிறுதரத்து உத்தியோகஸ்தர்களும் இருந்திருப்பார். அக்காலத்திலே அரசாங்கக் கணக்குகளை எவ்விதம் வைத்திருந்தார்கள் என்பது நமக்குத் தெரியாது. எனினும் அவை இருந்துவந்தன என்பது மட்டில் நிச்சயம். நாடு முழுவதும் பயிரிடும் நிலங்களை மிகவும் நுணுக்கமாக அளவிட்டுத் தரம் பிரித்து வகைசெய்து கணக்கு வைத்திருந்தனர் என்றும் கல்வெட்டுக்களிலிருந்து தெரியவருகிறது.

நாடு, ஊர் போன்ற சபைகளுக்குத் திருமந்திரவோலை அனுப்பும் உத்தரவுகள் சரிவர நிறைவேற்றப்பட்டனவா என்பதைக் கவனித்து அறிய மூலப் பிரதிகளை அரசாங்கத்தில் வைத்திருத்தல் வேண்டும். அதேபோலச் சபையாரும் தாங்கள் நிறைவேற்றும் காரியங்களுக்கு ஆதாரங்களாகப் பின்னால் தணிக்கை செய்பவர்களுக்குக் காண்பிப்பதற்கு அந்த உத்தரவுகளைக் காப்பாற்றி வைக்கவேண்டும்.

ஓர் அரசாங்கம் மற்றொன்றுடன் செய்துகொள்ளும் உடன்படிக்கை முதலியன சரிவர நடைபெறுகின்றனவா என்பதைக் கவனிக்க இரு தரத்தாரிடமும் அவற்றின் பிரதிகள் இருத்தல் வேண்டும். அதே

போலச் சிற்றரசர்கள் செலுத்தும் கப்பம், நாட்டில் வருலாகும் வரிப் பணம் முதலியவற்றுக்கும் சம்பந்தப்பட்டவர்களிடம் கணக்குகள் இருக்கவேண்டும். இவற்றுள் பல நிரந்தரமாகப் பாதுகாக்கப்பட வேண்டியவை. ஆயினும் இவை ஒன்றும் இப்பொழுது கிடைக்கவில்லை.

முதலாம் இராஜேந்திரன் அளித்த திருவேலங்காட்டுச் செப்பேடுகளில் அம்மன்னன் வாய்மொழியாகத் தன்னுடைய ஆட்சியின் ஆறாம் ஆண்டு எண்பத்தெட்டாவது நாள் அளித்த உத்தரவு முப்பத்திரண்டு நாள் கழித்து, அதாவது அதே ஆண்டு தூற்றிருபதாம் நாள் கணக்கில் எழுதப்பட்டது என்று கூறப்பட்டுள்ளது. (தெ. இ. சாசனங்கள், இரண்டாம் வால்யூம்). தென் ஆர்க்காடு ஜில்லா எண்ணுயிரம் என்னும் இடத்திலிருந்து கிடைக்கும் முதலாம் இராஜாதிராஜனுடைய காலத்துச் சாசனம் (1917-ஆண்டு 330-நெ.) ஒன்றில் அவன் ஆட்சியின் இருபத்தேழாம் ஆண்டு தூற்று முப்பத்தேழாம் நாள் அளிக்கப்பெற்ற உத்தரவு மூன்று வருஷம் தூற்று மூன்று நாள் கழித்து, அதாவது முப்பதாம் ஆண்டு இருதூற்று நார்பதாம் நாள் அந்த ஊர்ச் சபைக்கு வந்து சேர்ந்ததாகக் குறிக்கப்பட்டிருக்கிறது. அதேபோலத் திருப்புவனம் செப்பேடுகளில் ஸ்ரீ கோச்சடையவன்மரான 'திரிபுவன சக்கர வர்த்திகள் ஸ்ரீ குலசேகராதேவர்க்கு யாண்டு 13-ஆவது நாள் நாலாயிரத்து முந்தூற்று அறுபது' என்று காணப்படுகிறது. (எபி. இந்திகா, இருபத்தைந்தாம் வால்யூம்). இவற்றைக் கவனித்தால் ராஜகர்த்துக் கணக்குகளிலும் குறிப்புகளிலும் நாட்களையும் கணக்கிட்டு எழுதிவந்தனர் என்பது விளங்கும்.

அவர்கள் அவ்விதம் எழுதிச் சென்ற கணக்குகளும், குறிப்புகளும் கிடைத்துவிட்டால் போதும். நம் நாட்டின் சரித்திரம் முழுவதையும் பல துறைகளிலும் விரிவாக எழுதிவிடலாம். அது சலபமான காரியமாக இருக்காதுதான். கட்டுக் கட்டாகக் கிடைக்கக் கூடிய அவற்றுள் புகுந்து ஆராய்ந்து தேடவேண்டும். எப்படியிருந்தால் வன்ன? அவை இப்பொழுது கிடைக்கவில்லை. அதனாலே யன்றோ நாம் வேறு பலவகை ஆதாரங்களைத் தேடி அலேகிறோம்?

இத்தகைய குறிப்புகளுக்குப் பதிலாக நமக்குக் கிடைக்கும் சாசனங்களையே கொள்ளவேண்டும். நாட்டுச் சரித்திரத்திற்குப் பலவகை ஆதாரங்கள் இருந்தாலும், அவற்றால் அறியப்படும் உண்மைகளை நிர்ணயம் செய்து நிச்சயமாக்கச் சாசனங்களே பெரிதும் உதவுகின்றன. சாசனங்கள் இல்லாவிடின் நம் நாட்டுச் சரித்திரத்துள் பெரும் பகுதி இருள் சூழ்ந்து விளங்காமல் போயிருக்கும். சாசனங்கள் சரித்திரத்தின் பல துறைகளுக்கும் உபயோகப்படக் கூடியனவாம்.

#### 4. இலக்கிய சாசனங்களும் சரித்திரக் கல்வெட்டுகளும்

நம் நாட்டில் கிடைக்கும் சாசனங்களை இராஜகரத்துச் சாசனங்கள், மக்களைப்பற்றியவை என இருவகையாகப்பிரிக்கலாம். அதே போலத் தான சாசனங்கள், தான சாசனங்கள் அல்லாதவை எனவும் இரு பெரும் பிரிவுகளாகப் பிரிக்கலாம்.

இகலோகத்தில் புகழும், பரலோகத்தில் புண்ணியமும் கிடைக்க வேண்டி அளிக்கப்பட்ட தானங்கள் நம் நாட்டுக் கோயில்களுக்கும் தர்ம ஸ்தாபனங்களுக்கும் மற்றையோருக்கும் கொடுக்கப்பட்டனவாகும். இதனால் தான சாசனங்களையும் மதம் சம்பந்தமாகக் கொடுத்த தானங்கள், இதர தானங்கள் என இருவகைகளாகப் பிரிக்கலாம்.

தானங்கள் அல்லாத பிற செய்திகளைத் தெரிவிக்கும் சாசனங்களையும் சமூக வாழ்க்கையைப் பற்றியவை, தனிப்பட்டவர்களைக் குறித்தவை என இரண்டாக வகுக்கலாம். குளம் தொட்டது, பள்ளிக் கூடம் ஆதலு சாலை முதலியன நிறுவியது ஆகியவற்றைத் தெரிவிப்பவை; நாட்டின் மக்கள் தங்களுக்குள் செய்துகொண்ட உடன்படிக்கைகள் முதலியவை முதல் வகுப்பைச் சார்ந்தவை. வீரக்கல் போன்று இறந்தவர்களுக்கு எழுப்பும் ஞாபகச் சின்னங்கள், மக்கள் தங்களுக்குள் செய்துகொண்ட நிலப் பரிவர்த்தனைகள், அடிமைச் சீட்டுகள் முதலியன இரண்டாம் பிரிவைச் சாரும்.

இனி இந்த இரண்டு பெரும் பிரிவுகளையும் சேராமல் தனித்து நிற்கும் சாசனங்கள் சில உண்டு. அவை இலக்கிய சாசனங்களும், சரித்திர நிகழ்ச்சியைத் தெரிவிக்கும் சாசனங்களும் ஆகும்.

#### இலக்கிய சாசனங்கள்

பண்டைக் காலத்தில் நூல்களைப் பனையேடுகளில் எழுதுவதைப் போலவே செப்பேடுகளிலும் எழுதிவந்தார்கள். இறையனார் அகப் பொருளுரையின் முன்னுரையினின்றும் இது நமக்குத் தெரிகிறது. 'பாண்டி நாடு பன்னீராண்டு பஞ்சத்தால் வாடியது. அதனால் புலவர்கள் பிறநாடுகளை அடைந்தனர். பஞ்சம் தீர்ந்தபிறகு, அவர்களில் பலர் பாண்டிய நாட்டுக்குத் திரும்பினர். எனினும், அவர்களுள் பொருள் நூல் வல்லார் இல்லை. அதனை அறிந்த மன்னன் மனம் தளர்ந்து இக்குறையை ஆலவாய் அவிர்ச்சடைக் கடவுளிடம் முறையிட்டான். இறையனாரும் களவியல் என்னும் நூலை இயற்றிச் செப்பேடுகளில் எழுதி இரவில் தம் பீடத்தின் கீழ் இட்டனர்.' இச் செய்தியைத் தெரிவிக்கின்றது அந்த நூலின் உடாப்பாயிரம்.

இலக்கியங்களையும் அழிந்துபோகாமல் காக்க முன்னாளிலே அவற்றைச் செப்பேடுகளில் பொறித்து வந்தார்கள் என்பது இவ்வுரையால் தெரிகிறது. இதேபோன்ற விஷயங்களைத் தெரிவிக்கும் கர்ணபரம்பரைச் செய்திகள் நாட்டின் வேறு பகுதிகளிலும் காணப்படுகின்றன. குஷான வமிச அரசனான கனிஷ்கன் புத்தமதப் பெரியார்களின் பேரவை ஒன்றுகூட்டி அவர்களைக் கொண்டு (புத்தமதத்தின் மூலக் கிரந்தமான்) திரிபிடகத்துக்கு வியாக்கியானம் எழுதச் செய்து அதைச் செப்பேடுகளிலே பொறித்து அவற்றைக் கட்டடத்திலேவைத்து மேலே ஸ்தூபம் ஒன்றை எழுப்பிப் பாதுகாத்தான் என்று கி. பி. ஏழாம் நூற்றாண்டின் மத்தியில் நம் நாட்டுக்கு வந்திருந்த சீன யாத்திரிகர் யுவான் சுவாங் தம்முடைய குறிப்புகளில் எழுதியிருக்கிறார். பிற்காலத்தில் சாயணர் என்பவர் வேதங்களுக்கு எழுதிய பாஷியத்தையும் அதேபோலச் செப்பேடுகளில் பொறித்து வைத்தார் என்ற கர்ணபரம்பரைச் செய்தி இருப்பதை மாக்ஸ்-முல்லர் என்னும் ஐரோப்பிய ஆராய்ச்சியாளர் தம்முடைய ரிக்வேதப் பதிப்பில் (முதல் வால்யூம், முன்னுரை, 17-ஆம் பக்கம்) குறிப்பிட்டிருக்கிறார்.

சென்ற நூற்றாண்டின் முற்பகுதியில் காம்பெல் என்னும் ஆசிரியர் தம்முடைய 'தெலுங்கு வியாகரணம்' என்னும் ஆங்கில நூலில் பின் வருமாறு எழுதியுள்ளார். "திருப்பதி மலைக் கோயிலில் ஒரு பிராமண வமிசத்தாருடைய பாதுகாப்பில் ஆயிரம் செப்பேடுகளுக்குமேல் உள வென்றும், அவற்றில் பலநூல்கள் எழுதப்பட்டுள்ளனவென்றும் கேள்விப்பட்டேன். அதன்மீது இந்தியர் ஒருவரை அனுப்பி அவற்றைப் பார்வையிடச் செய்தேன். ஆனால் அவற்றுள் வியாகரண நூல் ஒன்றைத் தவிர, மற்றவை அம்மலையில் கோயில் கொண்டு எழுந்தருளியுள்ள பெருமானைப் புகழ்ந்து பாடிய பாசாங்களாகவே காணப்பட்டன. அவ் விலக்கண நூல் மட்டும் பிரதி செய்யப்பட்டது." (1820-ஆம் வருஷம் வெளியான இரண்டாம் பதிப்பு, 13-பக்கம்: டாக்டர் பர்னெல் எழுதிய தென்னிந்தியப் பிராசினலிபி என்னும் ஆங்கில நூலின் 86, 87-ஆம் பக்கங்களில் மேற்கோளாகக் காட்டியுள்ளது.) இங்கே குறிக்கப்பட்டவர்கள் தள்ளப்பாக்கம் குடும்பத்தைச் சேர்ந்தவர்கள் ஆவார். அவை இப்போதும் திருப்பதி தேவஸ்தானத்தில் சங்கீர்த்தன பண்டாரத்தில் பாதுகாக்கப்பட்டு வருகின்றன. கி. பி. பதினைந்து, பதினாறாம் நூற்றாண்டுகளில் விஜயநகர மன்னர்களின் ஆதரவில் வாழ்ந்த மூன்று கவிஞர்கள் இயற்றியவை. சுமார் மூவாயிரம் செப்பேடுகள் உள்ளன. (ஒரு சமயம் 'வண்டிக்கணக்காக உள்ளன' என்றும் வருணிக்கப்பட்டுள்ளது.) வேங்கடத்தில் எழுந்தருளியுள்ள எம்பெருமான் மீது சங்கீர்த்தனம் என்னும் பாணியில் இயற்றிய பாடல்களும் வேறு புல

இவ்விதம் சரித்திர நூல்களாக உள்ளவற்றைத் தவிர, பிற நூல்  
களிலும் அவை எழுதப்பட்ட காலங்களில் ஆண்ட அரசாங்கப்பற்றி  
மட்டுமேயன்றி அம் மன்னர்களுடைய முன்னோக்கிப் பற்றிய விவரங்  
களும் காணப்படுவது எவ்வளவு? அவையாவும் உண்மையாக இருக்க  
முடியுமா? அவர்கள் அந்த விவரங்களையும் மன்னர்களின் வமிசாவளி  
யையும் எவ்விதம் அறிந்தனர்? இந்தகைய கேள்விகள் உண்டாவது  
இயற்கையே.

எம் நாட்டவர்களுக்கு வமிசங்களின் மீள்களைப் பற்றிய விவரங்  
கள் கன்றாகத் தெரிந்திருப்பது மிகவும் சாதாரண விஷயம். இன்றைக்  
கும் பல குடும்பங்களில் ஏழு தலைமுறைகளுக்கு மேற்பட்ட வமிசா  
வளிகள் இருப்பதை எம் காணலாம். ஒரே குடும்பம் பலவாறுகப்  
பிரிந்து போய்விடும் சபாசப காரியங்களுக்கு அந்தக் குடும்பத்தைச்  
சேர்ந்தவர்கள் ஒன்றிரே வேண்டியதைக் கருதியே அங்ஙனம்  
வைக்கப்பட்டிருக்கிறது போலும். அன்றி, அவை லெனகெமராவும்  
மானியம் போன்ற சொத்துக்களின் உரிமை, அந்தர வாரிசு பாத்தி  
யதை முதலியவற்றை நிறு நிறுத்தவும் உபயோகப்படக் கூடியன.

எம் நாட்டில் உள்ள முக்கியமான மடம் ஒவ்வொன்றிலும் அது  
ஏற்பட்ட நான்முதல் அதிலே குருகிப்ப பாம்பகாபாகப் பதவி ஏற்று  
அருளாட்சி நடத்திவந்த தலைவர்களின் வான்முறைகைத் தெரிவித்  
கும் பட்டாவளி இருந்தவருமே. இதில்து பிறப்பதற்கு ஐந்தாறு  
ஆண்டுகளுக்கு முற்பட்ட காலத்திலிருந்தே தொடங்கி கஜனமதத்தின்  
கடைசித் தீர்த்தம்சாரான மகாவீர முதல் வரிசையாக வரும் கஜன  
மடப் பட்டாவளிகள் சிலவற்றை ஆராய்ச்சியாளர்கள் ஆராய்ந்திருக்  
கிறார்கள் (இந்தியன் ஆண்டிகுவரி, 20, 21-ஆம் தொகுதிகள்). திருவன்  
ளர் விராகவப்பெருமான் கோயிலுக்குச் சகாப்தம் 1552, அதாவது  
கி. பி. 1680-ஆம் ஆண்டில், விராகவ சடகோப ஜீவர் என்பார் பொன்  
அணித்த செப்தியைத் தெரிவிக்கும் கல்வெட்டு ஒன்றை அந்தக்கோயிலி  
லிருந்து மக்கெல்லியின் உதவியாளர்கள் பிரதி செய்திருக்கிறார்கள்.  
(இந்தத் தொகுப்பின் 1107 கெ. சாசனம்). அந்தக் கோயில் அந்நா  
பலமடத்தின் நிர்வாகத்தில் உள்ளது. அந்த மடத்தின் பதின்மூன்  
றும் பட்டம் வசித்த விராகவ சடகோப ஜீவர் கி. பி. 1630-முதல்  
1675-வரையில் இருந்தார் என்று கூறப்படுகிறது. இதிலிருந்து அந்  
தக் கோயிலுக்குப் பொன் அணித்த ஜீவர் அந்த மடத்தைச் சேர்ந்த  
வரே என்பது தெளிவாகும்; அன்றி மடத்து வமிசாவளியின் கம்பித்  
தைத் தன்மையும் விளங்கும்.

குடியியான்மிகக்குப் பக்கத்திலே உள்ள திருமெய்யத்திலும் குடைவரைக் கோயிலுக்கு வலதுபுறத்தின் மிகச்சரியில் மற்கொரு சந்தைக் கல்வெட்டு காணப்படுகின்றது. அது குடியியான்மிகக் கல்வெட்டில் காணப்படும் வர்ணத்தினின்றும் வேறுபட்டது. எனினும் பிற்காலத்தில் மாறவர்மன் சுந்தரபாண்டியன் என்பான் 'பாண்டிய புரிபாத கல்வெட்டு' என்று அதை அழித்தாவிட்டு அந்த இடத்தில் சிலன் கோயிலுக்கும் கிஷ்டு கோயிலுக்கும் ஏற்பட்ட ஓர் உடன்படிக்கையை வெட்டுவித்தான் (புதுக்கோட்டைச் சாசனங்கள், 840, 841).

\* எனினும் பழைய கல்வெட்டின் பகுதிகள் சிற்சில அங்கங்கே தென்படுகின்றன. அவற்றுள் ஷட்ஜ, காந்தார, தைவத முதலிய சொற்கள் காணப்படுகின்றன. இவ்வெழுத்துக்களும் குடியியான்மிகக் கல்வெட்டு எழுத்துக்களைப்போ ஒத்திருக்கின்றன.

தஞ்சை ஜில்லா என்னிலம் தாலுகாவில் கொடபச்சேரி என்னும் ரயில்வே ஸ்டேஷனுக்கு இரண்டுகைமல் தெற்கேயுள்ள திருவிடைவாரியில் என்னும் ஊரில் இருக்கும் புண்ணியசாதேசுவர் கோயிலில் அங்கே எழுந்தருளியிருக்கும் பெருமானைப்பற்றித் திருஞானசம்பந்தர் பாடிய நாகக் கூறப்படும் பதினொரு பாடல்களை உடைய பதிகம் ஒன்று பொறிக்கப்பட்டுள்ளது. (1918-ஆம் ஆண்டு 8 செ. கல்வெட்டு).

உமாபதி சிவாசாரியார்,

“பண்புற்ற திருஞான சம்பந்தர் பதிகமூன்றாற்று  
எண்பத்த நான்கிலு லிலக்குதிரு முறைமுன்று”

(திருமுறைகண்ட புராணம், 25)

என்று கூறுகிறார். அதனால், தேவாரத்துள் சம்பந்தருடைய பதிகங்கள் மூன்றாற்று எண்பத்த நான்கு அடங்கியிருந்தன வென்பது பெறப்படும். ஆயினும், இக் கல்வெட்டுக் கிடைப்பதற்கு முன்னர் அச்சிட்ட பதிப்புணில் சம்பந்தர் வர்க்காக மூன்றாற்று எண்பத்த முன்று பதிகங்களே இருந்தன. அவற்றுள் இக்கல்வெட்டில் கண்ட பதிகம் சோகிலில்லை.

இதைப்போன்ற பதிகக் கல்வெட்டு வேறு எந்த இடத்திலும் கிடைக்கவில்லை. இதனால் வேறு விதமாகவும் ஊகிக்கலாம். சம்பந்தர் பதிகங்களில் ஒன்று குறைவாக இருப்பது, இந்தக் கல்வெட்டு பொறிக்கப்பட்டதற்கு முன்னதாகவே காணப்பட்டிருத்தல்வேண்டும் என்றும், அவ்விதம் காணாமற் போனது இதுதானா என்பதில் அபிப்பிராய பேதம் இருக்கிருந்தல்கூடும் என்றும் சொன்னலாம்.

சாசனத்தில் கண்ட பதிகத்தில் சம்பந்தருடைய மற்றப் பதிகங் களைப் போலவே ஒவ்வொரு பாட்டிலும் ஒரு பாதியில் அந்த ஊரைப் பற்றிய வர்ணனையும், மற்றப் பாதியில் சிவபெருமானைப் பற்றிய புகழும் பாடப்பட்டுள்ளன. அன்றி, சம்பந்தருடைய வழக்கமான கடை காப் பும் இந்தப் பதிகத்திலே இருக்கிறது. ஆதலால் ஏடுகளில் கிடைக்காம லிருந்த பதிகமே கல்வெட்டு மூலமாக நமக்குக் கிடைத்துள்ளது என்று துணியலாம். (மிதிக் சொஸைட்டி ஜர்னல், இருபத்து நான்காம் வால் யும், பக்கம் 160.)

திருச்சிராப்பள்ளியில் மலைமேலுள்ள குடைவரைக் கோயிலின் பின் சுவரில் ஒரு கல்வெட்டு உள்ளது. அது சுமார் கி. பி. 1100-ஆம் ஆண்டுக்கு அணித்தான காலத்தைச் சார்ந்த தமிழ் எழுத்துக்களால் பொறிக்கப்பட்டுள்ளது என்பர். சிவபெருமான்மீது பாடிய கவித்துறை யந்தாதி ஒன்றைக் கொண்டுள்ளது, அச் சாசனம். (தெ. இ. சாசனங் கள், நான்காம் வால்யூம், 167 நெ. சாசனம்). அந்த அந்தாதியின் ஆசிரிய னான நாராயணன் என்னும் கவியைப் பற்றிய வரலாற்றை அக் கல் வெட்டின் கடைசியிலுள்ள பின்வரும் பாடல்கள் தெரிவிக்கின்றன.

“மற்பந்த மார்பன் மணியன் மகன்மதில் வேம்பையர்கோன்  
நற்பந்த மார்தமிழ் நாரா யணனஞ் சிராமலைமேற்  
கற்பந்த னீழலில் வைத்த கவித்துறை னூறுங்கற்பர்  
பொற்பந்த நீழ லான்றிருப் பாதம் பொருந்துவரே”

“மாட மதுரை மணலூர் மதில்வேம்பை  
கோடமர் சேய்ஞலூர் குண்டேரிந்—நீடிய  
நற்பதிக்கோ னாரா யணனஞ் சிராமலைமேற்  
கற்பதித்தான் சொன்ன கவி.”

இவ்வந்தாதி சொல் நயம், பொருள் நயம் கொண்டு மிக்க அழகாகப் பாடப்பட்டுள்ளது. சமீபத்திலே பண்டித மு. இராகவையங்கார் அவர் களால் இது தருமபுர ஆதினத்தின் வெளியீடாகப் பதிப்பிக்கப்பெற் றுள்ளது.

விஜயநகர வேந்தனான முதலாம் வேங்கடபதிதேவ மகாராயருக்கு ஆசாரியராக விளங்கிய கோடிகன்யாதானம் லக்ஷ்மீகுமாரதாதாசாரியார் ஐயங்கார்குளத்தில் தாதசமுத்திரம் என்ற பெயரில் ஒரு குளம் தோண்டி அதன் கரையில் அனுமாருக்கு ஒரு கோயிலும் எடுப்பித்தார். அங்கே பிரதிஷ்டித்த அனுமாரைப் புகழ்ந்து இருபது சுலோகங்கள் கொண்டதாக ஹனுமத்விம்சதி என்ற ஸம்ஸ்கிருத ஸ்தோத்திரம் ஒன்



றையும் அவர் இயற்றினார். அது அந்தக் கோயிலிலே கல்வெட்டாகப் பொறிக்கப்பட்டுள்ளது. (1923-ஆம் வருஷத்து 92 நெ. கல்வெட்டு). அது இன்னும் காஞ்சிபுரம் வரதராஜர் கோயிலிலே கர்ப்பகிருகமான அஸ்திகிரியின் கிழக்கு வடக்குச் சுவர்களிலும், தாயார் ஆலயத்துச் சுவர்களிலும் (1919-ஆம் ஆண்டு, 651 நெ. கல்வெட்டு), வெளிக் கோபுரத்திலும் பொறிக்கப்பட்டிருப்பதைக் காணலாம். மக்கென்வரியின் உதவியாளர்களும் இதைப் பிரதி செய்திருக்கிறார்கள். இது ஜர்னல் ஆப் ஒரியண்டல் ரிஸர்ச் பத்திரிகை, பதினெட்டாம் வால்யூமில் பதிப்பிக்கப் பெற்றுள்ளது.

சிதம்பரம் ஸ்ரீநடராஜர் கோயிலின் கிழக்கு மேற்குக் கோபுரங்களில் அழகான சிற்பங்கள் செதுக்கப்பட்டுள்ளன. அவற்றுள் பல நடன உருவங்கள் : நாட்டிய சாஸ்திரத்தில் காணும் நிலைகளை எடுத்துக் காட்டுவனவாக உள்ளன. பரதநாட்டிய சாஸ்திரத்தில் கூறப்பட்டிருக்கும் தூற்றெட்டு வகைகளையும் விளக்கிக்காட்டும் அந்தச் சிற்பத்தில் ஒவ்வொரு மாடத்தின் மீதும் அந்தவகையைத் தெரிவிக்கும் சுலோகம் கிரந்த எழுத்தில் பொறிக்கப்பட்டிருக்கிறது. இந்தக் கோபுரங்களும் அவற்றில் காணும் சிற்பங்களும் கி. பி. பதின்மூன்றாம் நூற்றாண்டின் மத்தியில் கோப் பெருஞ்சிங்கன் காலத்தில் ஏற்பட்டவை. (சிலாசாசன அறிக்கை, 1914-ஆம் ஆண்டு). அந்தச் சுலோகங்களுக்கும் அச்சிட்ட பரத நாட்டிய சாஸ்திரச் சுலோகங்களுக்கும் பாடபேதங்கள் காணப்படுகின்றன. அருமை வாய்ந்த இச் சுலோகங்கள் விளக்கப் படங்களுடன் டாக்டர் பி. வி. நாராயணசாமிநாயுடு அவர்களால் வேறு இருவருடைய கூட்டுறவோடு தாண்டவலக்ஷணம் என்ற பெயரில் தனி வெளியீடாகப் பிரசுரிக்கப்பட்டுள்ளது.

காஞ்சிபுரத்திலே கச்சப்பேசுவார் கோயிலில் தூர்க்கை சந்நிதியில் உள்ள மண்டபத்தின் தூணில் சூர்ய சதகம் என்னும் வடமொழி தூலின் முதல் ஆறு சுலோகங்கள் பொறிக்கப்பட்டுள்ளன. மயூர கவியால் எழுதப்பெற்ற அந் தூலின் முதல் ஆறு சுலோகங்கள் மந்திரசக்தி வாய்ந்தவை என்ற ஓர் எண்ணம் நிலவிவருகிறது. பதினொராம் நூற்றாண்டு எழுத்துக்களில் உள்ள அச்சாசனம் யாரோ ஒரு பத்தனால் உண்டாக்கப்பட்டதுபோலும் (1921-ஆம் ஆண்டு 81 நெ. கல்வெட்டு).

இவ்விதமான இலக்கிய சாசனங்கள் தமிழ்நாட்டில் மட்டுமின்றி இந்தியாவின் பிறபாகங்களிலும் கிடைக்கின்றன. மத்திய இந்தியாவிலே தாரா நகரத்தில் (Dhar) பாரிஜாத மஞ்சரி அல்லது விஜயஸ்ரீ என்னும் நாடிகை அதாவது நான்கு அங்கங்களைக் கொண்ட நாடகவகையின்

முதல் இரண்டு அங்கங்களைக் கொண்ட கல்வெட்டு ஒன்று இருக்கின்றது. பரமார வமிசத்து அரசனான அர்ச்சனவர்மனைக் கதாநாயகனாகக் கொண்டு ராஜகுருவான மதனன் என்னும் கவியால் அது கி. பி. 1200-ஆம் ஆண்டுக்கு அணித்தாக இயற்றப்பெற்றது. (எபி. இந்திகா, எட்டாம் வால்யூம்.)

சாஹமான வமிசத்து அரசனான விக்ரஹராஜனைக் குறித்து ஸோமதேவர் என்பவர் 'லலித விக்ரஹராஜ நாடகம்' என்று ஒரு நாடகம் எழுதியிருக்கிறார். அந்த விக்ரஹராஜனை 'ஹரகேளிராடகம்' என்பதை இயற்றி யிருக்கிறான். இவ்விரண்டும் கி. பி. 12-ஆம் நூற்றாண்டின் மத்தியில் எழுதப்பட்டவை; சரித்திர சம்பந்தமான நாடகங்கள் என்றும் கூறப்படுகின்றன. இந்த இரண்டு நாடகங்களின் பாகங்கள் ஆஜ்மீரில் உள்ள கற்களில் பொறிக்கப்பட்டுள்ளன. (இ. ஆ., இருபதாம் வால்யூம்.)

தாரா நகரத்திலேயே மகாவிஷ்ணுவின் கூர்மாவதாரத்தைத் துதித்து 'அவனி கூர்ம சதகம்' என்று எழுதிய பிராகிருத நூல்கள் இரண்டு பொறிக்கப்பட்ட வேறு கல்வெட்டுகளும் காணப்படுகின்றன. அவை போஜராஜனைப் பாராட்டி இயற்றப்பட்டவை. (ஹி.) அவ்விரு நூல்களில் ஒவ்வொன்றும் நூற்றொன்பது சுலோகங்கள் கொண்டது. பூமியின் பராரத்தைக் கூர்மம் (ஆமை) போல் வேறு யாரும் தாங்கியதில்லை என்றும் அந்த ஆமையைப் பெற்ற தாயைப்போன்ற பாக்கியசாலியான தாய் வேறுயாரும் இல்லையென்றும் முதல் சதகம் தெரிவிக்கிறது. போஜராசன் தன் எதிரிகளை வென்று பூபாரம் தாங்குவதால் அந்தக் கூர்மத்துக்கும் ஒவ்வொன்றொன்றாக இரண்டாம் சதகம் தெரிவிக்கிறது. போஜராஜனை அந்த இரண்டு சதகங்களையும் இயற்றினான் என்று அவற்றின் இறுதிச் செய்யுள்கள் தெரிவிக்கின்றன.

இந்த நூல்கள் யாவும் கல்வெட்டுக்கள் மூலமாகவே நமக்குக் கிடைத்துள்ளன. இக் கல்வெட்டுக்கள் கிடைத்திராவிட்டால், இந்த நூல்களைப்பற்றி நாம் அறிவதற்கு மார்க்கமே இல்லை.

தாரா நகரத்திலேயே போஜராஜன் கலைமகளுக்கு ஓர் ஆலயம் அமைத்திருந்தான். அக்கோயில் முக மண்டபத்தில் இருந்த இரு நூண்களில் நூணுக்கு ஒன்றாக இரண்டு நாகபந்தங்கள் வெட்டப்பட்டுள்ளன. ஒன்றில் வடமொழியின் உயிரொழுத்துக்களும் மெய்யொழுத்துக்களும் அமைக்கப்பட்டுள்ளன. மற்றொன்றில் வடமொழியிலக்கணத்தில் கூறப்படும் தாதுக்கள் என்னும் வினை முடிபுகள் அமைக்கப்

பட்டிருக்கின்றன. இவை வடமொழியின் காதந்திரிய விபாகணத் தின்படி அமைந்துள்ளன என ஆராய்ச்சியாளர் கூறுவர்.

வங்காளத்தில் சந்தால் பர்காணு என்னும் பகுதியில் உள்ள தேவ் கர் (தேவகிரி) வைத்தியநாத சுவாமி கோயிலிலிருந்து கிடைத்துள்ள தும் கி. பி. ஏழாம் நூற்றாண்டு எழுத்துக்களில் பொறிக்கப்பட்டதுமான ஒரு சாசனம் இதி மந்தரகிரி ப்ரகரணம் என்று முடிக்கிறது. ஆகவே அது ஸ்தலபுராணம் போன்ற ஏதோ ஒரு பெரிய நூலின் பாகமாக இருத்தல் வேண்டும் என்பது தெளிவாகும். (குப்த சாசனங்கள், 213 பக்கம்).

பல சருக்கங்களுடைய ஜைன ஸ்தல புராணம் ஒன்று ராஜபுத னத்தில் பிஜோல்லி என்னும் இடத்தில் கல்வில் பொறிக்கப்பட்டிருப்ப தாகக் கூறுவர். (இ. ஆ. முப்பத்து மூன்றாம் வால்பூம், அனுபந்தம், பக்கம், 97).

இன்னும் உலோகத் தகடுகளில் பொறிக்கப்பட்டிருக்கும் நூல்கள் இன்றைக்கும் கிடைக்கின்றன. வெள்ளியேட்டில் சமீப காலத்தில் எழுதிய பாலிபாஷை நூல் ஒன்று லண்டன் நகரத்தில் உள்ள பிரிட்டிஷ் கண்காட்சி சாலையில் இருக்கிறது. அதே கண்காட்சி சாலையில் ஈயத் தகட்டில் எழுதப்பட்டுள்ள பெளத்தமத நூல் ஒன்றும் உள்ளது.

உத்தரப் பிரதேசத்திலே குசினகரத்தில் மஹாநிர்வாண ஸ்தூபத் திலிருந்து கிடைத்த ஒரு செப்பேட்டில் புத்தபகவானுடைய உதான ஸுத்தம் என்னும் உபதேசம் பதின்மூன்று வரிகளில் பொறிக்கப் பட்டிருக்கிறது. (இந்தியப் புதை பொருள் இலாக்காவின் ஆண்டு அறிக்கை, 1907-ஆம் ஆண்டு, 46-ம் பக்கம்).

இனி, இவ்விதம் முழு நூல்களாகவோ அவற்றின் பகுதிகளா கவோ இல்லாமல் சில்லறைப் பாட்டுக்களைத் தெரிவிக்கும் சாசனங் களும் பல உள. குடுமியான்மலையில் உள்ள ஒரு கல்வெட்டு (1930-ஆம் ஆண்டு 361 நெ. சாசனம்) பின்வரும் பாடலைக் கொண்டுள்ளது.

“எங்கள் நலக் குன்றரைப்பார்த்து ஏழுஉலகும் ஈன்றஉமை  
நங்கைபல காலும் நகைசெயுமே — கங்கைஉறை  
கொங்கை கமழ்சடிலம் போய்க்குடுமி ஆய்விட்டது  
எங்கே மறைப்பார் என்று.”

அங்கே எழுந்தருளியிருக்கும் சிவபெருமான் பெயர் குடுமித்தேவர் என் பதைக் கொண்டு எழுந்த கவியின் கற்பனை இது. சிவனுடைய சடா மகுடம் போய்க் குடுமி ஏற்பட்டுவிட்டது. அதுகாறும் சடையில் மறைத்திருந்த கங்கையை அவர் இனிஎங்கே மறைப்பார் என்று தேவி அவரைப் பார்த்துக் கேலி செய்கிறாளாம்.

## சரித்திரக் கல்வெட்டுக்கள்

தானம் செய்யப்பட்ட செய்தியைப் பற்றிய குறிப்பு ஒன்றும் இல்லாமல் சரித்திர நிகழ்ச்சிகளைமட்டுமே தெரிவிக்கும் சாசனங்களும் சில உண்டு. இலக்கிய சாசனங்களைப் போலவே இவ் வகையைச் சேர்ந்தனவும் மிகக் குறைவே.

சரித்திர சாசனங்களுள் முக்கியமானதாகத் தென்னார்க்காடு ஜில்லாவிலே திருவகீர்த்திரபுரத்தில் கிடைக்கும் கல்வெட்டைக் கூறலாம். அது சோழமன்னனான மூன்றாம் இராஜராஜனுடைய ஆட்சியின் பதினேந்தாம் ஆண்டுக்கு எதிராம் ஆண்டில், அதாவது பதினாறாம் ஆண்டில், (கி. பி. 1231) பொறிக்கப்பட்டதாகும் (எபி. இ., ஏழாம் வால்யூம்). 'சோழ சக்கரவர்த்தியைக் கோப் பெருஞ்சிங்கன் சிறைப்பிடித்துச் சேந்தமங்கலத்திலே வைத்துக்கொண்டு தன் படையை விட்டு இராஜயத்தை அழித்துத் தேவாலயங்களையும், விஷ்ணு ஸ்தலங்களையும் கெடுத்துவந்தான். அதனைக் கேட்ட ஹொய்சள மன்னனான வீர நரசிம்ஹன் கோபம் கொண்டு 'சோழ மண்டலப் பிரதிஷ்டாசாரியன்' என்னும் கீர்த்தியை நிலைநிறுத்தினால் அல்லது காளம் ஊதுவதில்லை என்று உறுதிக்கொண்டு தன் தலைநகரான தோரசமுத்திரத்திலிருந்து புறப்பட்டான். படையைச் செலுத்திச்சென்று கோப் பெருஞ்சிங்கனை வெற்றிகொண்டு இராஜராஜனை மீண்டும் சிங்காதனத்தில் அமர்த்த வேண்டும் என்று அவன் ஆணையிட்டதால் அவனுடைய தண்டநாயகர்களான அப்பண்ணன், சமுத்திர கோப்பையன் ஆகிய இருவரும் பல ஊர்களை அழித்து, வேந்தன் முகலிகள் ஈழத்துராஜா பராக்கிரம பாகு உள்ளிட்ட நால்வரைக் கொன்று மக்களுக்குப் பயத்தை விளைவித்தனர். சேந்தமங்கலத்தைத் தாக்கப்போகிற அளவிலே கோப் பெருஞ்சிங்கன் குலைந்த சோழ சக்கரவர்த்தியை எழுந்தருளிவிப்பதாக ஹொய்சள வேந்தனுக்குச் செய்தி அனுப்பினான். அரசன் அதைத் தன் தண்டநாயகர்களுக்கு அறிவிக்க அவர்களும் சோழ சக்கரவர்த்தியை எழுந்தருளுவித்து இராஜயத்தே புகவிட்டனர்." இச் செய்தியைத் தெரிவிக்கும் இந்தக் கல்வெட்டு, தமிழ் நாட்டுச் சரித்திரத்திற்கு மிகவும் முக்கியமானது.

இவ்வாறே தஞ்சைப் பெரியகோயிலில் மராத்தியபாஷையில் பொறிக் கப்பட்ட நாகரி எழுத்துக் கல்வெட்டு ஒன்று இருக்கிறது. (1924-ஆம் ஆண்டு 424 நெ.). அது சகாப்தம் 1725 (கி.பி. 1803-4) ஆம் ஆண்டில் தஞ்சை மன்னனான சரபோஜியால் வெட்டுவிக்கப்பட்டது. தஞ்சையில் அரசசெலுத்திய போசள வமிசத்து மகாராஷ்டிர மன்னர்களுடைய

வமிசாவளியை இருபது தலைமுறைக்கு மேலாகக் கொடுக்கிறது. மகாராஷ்டிரப் பேரரசை நிறுவிய சிவாஜி, அவன் தந்தை ஷாஜி ஆகியோரைப் பற்றிய விவரங்களையும், அவர்களுக்கும் தஞ்சை மன்னர்களுக்கும் உள்ள உறவு முறையையும் தெளிவாகக் கூறுகிறது. அந்த வமிசத்து மன்னர்களின் ஆட்சிக் காலத்தில் நடந்த முக்கியமான செய்திகளையும் கொண்டு அவர்களுடைய வரலாற்றை எடுத்துக் கூறும் நூல்போல அமைந்துள்ளது அச் சாசனம். அதை வெட்டுவித்த சரபோஜி மன்னர் தாம் அந்தக் கோயிலுக்கு அளித்த மானியம் போன்றவற்றைத் தெரிவிக்கும் வேறு சில கல்வெட்டுகளையும் மராத்திய பாஷையில் அங்கே பொறித்திருக்கிறார். அவை எல்லாவற்றையும் ஸ்ரீ சாம்ப மூர்த்தி ராவ் என்பார் தனியாக வெளியிட்டிருக்கிறார். அதிலே இந்தச் சரித்திரக் கல்வெட்டுமட்டுமே சுமார் நூற்றிருபது பக்கங்கள் கொண்டிருக்கிறது.

காஞ்சீபுரம் கைலாசநாதர் கோவிலில் வேறு வேறு பாகங்களில் வைத்துக் கட்டப்பட்ட நான்கு தனிக் கற்களில் பொறிக்கப்பட்ட சாசனம் ஒன்று இருக்கிறது. அக் கற்களை ஒன்று சேர்த்துப் பார்த்தால் அது ஒரே சாசனம் என்பது விளங்கும். தமிழ், தெலுங்கு, சமஸ்கிருதம் ஆகிய மூன்று பாஷைகளும் கலந்து எழுதப்பட்டுள்ள அந்தக் கல்வெட்டு, சக 923 (கி. பி. 1001-2) ஆம் ஆண்டில் ஜடாசோட பீமன் என்னும் தெலுங்குச் சோழ அரசனைத் தஞ்சைச் சோழ சக்காவர்த்தியான முதலாம் இராஜராஜன் போரில் வென்று சிறைப் பிடித்த செய்தியைக் கூறுகின்றது. (எபி. இந்திகா, இருபத்தொன்றாம் வால்யூம்). முதலாம் இராஜேந்திர சோழனுடைய திருவேலங்காட்டுச் செப்பேடுகளிலே அவன் தந்தையான முதலாம் இராஜராஜனைப் பற்றிப் பின்வரும் சுலோகம் காணப்படுகிறது: “என் பெயர் கொண்ட இராஜராஜனைப் போரில் சமர்த்தனான பீமன் கதாயுதத்தால் கொன்றதால் பீமன் என்னும் இந்த ஆந்திர வேந்தனை நான் சென்று தாக்குவேன்— இவ்விதம் சொல்லி இராஜராஜன் அவனைத் தாக்கினான்.” (தெ. இ. சாசனங்கள், மூன்றாம்வால்யூம்). சாசனத்தை எழுதிய கவிஞர் அரசன் பெயர்களைக் கொண்டு சமத்கரமான கற்பனையைச் செய்திருக்கிறார். மகாபாரதக் கதையிலே துர்யோதனனைப் பீமன் கதாயுதத்தால் கொன்றான். துர்யோதனனுக்கு இராஜராஜன் என்ற பெயர் உண்டு. இதை ஞாபகத்தில் கொண்டால் கவியின் கற்பனை எளிதில் விளங்கும். இராஜராஜனும் பீமனும் ஒரே வமிசத்தில் பிறந்தவர்கள்; ஆனாலும் ஜன்ம விரோதிகள். ஆந்திர அரசனான ஜடாசோட பீமன் என்பான் சோழர்களின் தெலுங்கு நாட்டுக் கீளையைச் சேர்ந்தவன்.

நாட்டின் பல பகுதிகளிலே அரசு செலுத்திய குறுநில மன்னர்கள் பலர் தங்களுக்குள்ளே 'நிலைமைத்தீட்டு' என்று குறிக்கப்பெறும் உடன் படிக்கை செய்துகொண்டு அவற்றைக் கல்லிலே பொறித்தும் வைத்திருக்கிறார்கள். பேராசர்களாகவிளங்கியவர்களின் ஆதிக்கியம் குறைந்து, சிற்றாசர்கள் தலைதூக்கிப் பெயரளவுக்குமட்டும் பேராசர்களின் ஆதிக்கியத்தை ஏற்றுக்கொண்டு மற்றப்படி சுயேச்சையாகக் காரியங்களை நடத்தி வந்த காலங்களிலேதான் இத்தகைய சாசனங்கள் காணப்படும்.

மூன்றாம் குலோத்துங்க சோழனுடைய ஆட்சியின் பதின்மூன்றாம் ஆண்டு கொண்டதாகச் சேலம் ஜில்லா ஆற்காடுர் என்னுமிடத்திலிருந்து ஒரு கல்வெட்டு (1913-ஆம் ஆண்டு 440 நெ) கிடைத்திருக்கிறது. ராஜராஜதேவன் பொன்பரப்பினான குலோத்துங்கசோழவாணகோவரையனுக்கும் திருக்கோவலூர் கிளியூர் மலையமானுக்கும் இடையில் ஏற்பட்ட உடன்படிக்கையில் அழிவினையாற்றுக்குத் தென்புறம் உள்ள பகுதியை வாணகோவரையனும், அதற்கு வடக்கே உள்ள பகுதியை மலையமானும் அனுபவிக்கவேண்டும் என்று ஏற்றுக்கொள்ளப்பட்டது. அன்றி, அவர்களுள் ஒருவரை வேறு யாராவது தாக்கில் மற்றவர் உதவவேண்டுமென்றும், இருவரும் பேராசனுக்கு அடங்கியவர்களாக நடக்கவேண்டுமென்றும் ஒப்பந்தம் செய்துகொண்டனாம். அதே இடத்திலிருந்து அதே மன்னனுடைய ஆட்சியின் முப்பத்தைந்தாம் ஆண்டு கொண்டதாகக் கிடைக்கும் மற்றொரு கல்வெட்டு (1913-ஆம் ஆண்டு 435 நெ.) செங்கேணி அம்மையப்பன் அழகிய சோழனான எதிரிவிசோழச் சம்புவராயன் என்பான் பொன்பரப்பின் வாணகோவரையனான குலோத்துங்கசோழ வாணகோவரையன், அவன் மைத்துனன் காடவராயர் ஆகியோர்களுடன் இதேபோலச் செய்துகொண்ட மற்றோர் உடன்படிக்கையைத் தெரிவிக்கிறது. சில சமயங்களில் இத்தகைய சாசனங்களின் முடிவில் ஒப்பந்தத்தை மீறி நடப்பவர்கள் எந்த எந்தப் பாவத்துக்கோ பழிக்கோ ஆளானவர் ஆவர் என்று குறிக்கப்பட்டிருப்பது கவனிக்கத்தக்கது.

இன்னும் குறிப்பிட்ட சில அரசர்களுக்கோ அரசபரம்பரைக்கோ விசுவாசம் தெரிவித்து அதிகாரிகள் சிலர் பிரமாணம் எடுத்துக்கொண்டதைத் தெரிவிக்கும் சாசனங்களும் இந்த வகையைச் சார்ந்தனவே. கோதாவரி ஜில்லா திராக்ஷாராமத்திலிருந்து சோழவேந்தனான மூன்றாம் பராந்தகதேவனுக்கு விசுவாசம் தெரிவிக்கும் அதிகாரிகள் சிலருடைய பிரமாண சாசனங்கள் ஐந்தாறு கிடைத்துள்ளன. (தெ. இ. சாசனங்கள், நான்காம் வால்யூம், 1270-1274, 1275-A.) அந்நாளில் உள் நாட்டுக் கலகம் ஏதோ நிகழ்ந்திருந்தல் வேண்டும் என்பதை இக்கல்வெட்டுக்கள் குறிப்பிடுகின்றன.

இவ்விதம் சரித்திர நிகழ்ச்சிகளைக் கூறும் சாசனங்கள் வட நாட்டிலும் பல உள.

கிறிஸ்து பிறப்பதற்கு முன்னரே கலிங்க நாட்டை ஆண்டு வந்த காரவேல மன்னனது ஹாதிகும்பாச் சாசனத்தை முக்கியமானதாகக் கூறலாம். அதில் காரவேலன் பிறந்ததிலிருந்து அவன் பட்டம் கட்டப் பெற்றபின் பதின்மூன்று வருஷ காலம் அரசாண்டது வரையில் உள்ள அவனுடைய சரித்திரம் கூறப்பட்டிருக்கிறது. அவன் தன்னுடைய இளமையை, அதாவது அவன் வாழ்நாளில் முதல் பதினைந்து வருஷங்களைப் படிப்பிலும், அப்பால் ஒன்பது ஆண்டுகளை யுவராஜனாகவும் கழித்தான். இருபத்து நான்காவது வயது முடிந்தபிறகு அவனுக்கு ராஜ்யாபிஷேகம் நடைபெற்றது. சாசனம் இவற்றைக் கூறிய பிறகு வருஷவாரியாக அவனுடைய ஆட்சியில் நடந்த விசேஷச்செய்திகளையும் பொதுஜன நன்மைக்காக அவன் செலவு செய்த பெருந் தொகைகளையும் எடுத்துக்கூறிச் செல்கிறது. அது திடீரென்று பதின்மூன்றாம் ஆண்டுடன் நின்றுவிடுகிறது. மேலே அவன் எவ்வளவுகாலம் ஆண்டுவந்தான் என்பது போன்ற விவரங்கள் குறிக்கப்படவில்லை. (எபி. இந்திகா, இருபதாம் வால்பூம்).

அலஹாபாத்திலுள்ள சமுத்திராகுப்தனது பிரசஸ்தியும் இப்பிரிவையே சேர்ந்ததே. (குப்த சாசனங்கள், முதற்பக்கம்). அதில் அவ்வரசனுடைய வமிசாவளியும் அவன் செய்த திக்கு விஜயங்களும் விவரமாகக் கொடுக்கப்பட்டுள்ளன. அவன் எந்த எந்த நாடுகளை ஜயிக்க முயன்றான் என்பதும் அக்காலத்தில் பிற நாடுகள் எவ்வித நிலையில் இருந்தன என்பதும் அந்தச் சாசனத்தினின்றும் நன்றாக விளங்குகின்றன.

அதேபோல மந்தஸோர் என்னுமிடத்தில் உள்ளதும், யசோதர்மனுடைய புகழைக் கூறுவதுமான சாசனமும் இந்த வகுப்பைச் சேர்ந்தது. சிவபெருமானுக்கு அன்றிப் பிறருக்கு எப்போதும் தலைவணங்கியறியாத மஹிரகுலன் என்னும் ஹூணர் தலைவனை அவன் தோல்வியுறச் செய்த செய்தி இதனால் வெளியாகிறது. (ஷெ. 142, 149 பக்கங்கள்).

புமராஸ்தம்ப சாசனம் (குப்த சாசனங்கள், பக்கம் 110) என்பது மகாராஜா ஹஸ்தி, மஹாராஜர் சர்வநாதன் ஆகிய இரண்டு வேந்தர்களும் ஆண்டுவந்த நாடுகளுக்குப் பொதுவாக அமைந்த எல்லையைக் குறிப்பதற்காக நடப்பட்ட தூண் என்பதைத் தெரிவிக்கிறது. இதுவிலிருந்து அந்த வமிச அரசர்களையும் அவர்களுடைய கால வரையறையையும் நாம் அறியமுடிகிறது.

கி. மு. மூன்றாம் நூற்றாண்டைச் சார்ந்தனவாகக் கூறக்கூடிய பிராமி எழுத்துக்களால் பொறிக்கப்பட்ட செப்பேடு ஒன்று உத்தரப் பிரதேசத்தில் ஸோகௌரா என்னுமிடத்திலிருந்து கிடைத்துள்ளது. (எபி. இந்திகா, இருபத்திரண்டாம் வால்பூம்). நான்கே வரிகளைக் கொண்டதாகப் பிராகிருத மொழியில் உள்ள அந்தச் சாசனம் பஞ்சகாலம் போன்ற சமயங்களில் அவசர உபயோகத்துக்காக, உணவுத் தானியம், மிருகங்களின் தீவனமான வைக்கோல் ஆகியவற்றைச் சேகரித்து வைப்பதற்கென இரண்டு கொட்டாரங்கள் நிறுவப்பெற்ற செய்தியைத் தெரிவிக்கிறது.

பண்டை மன்னர்கள் தாங்கள் கொண்ட வெற்றிக்கு அறிகுறியாக ஜயஸ்தம்பங்கள் எழுப்பியதைத் தெரிவிக்கும் சாசனங்களையும் இந்த வகையிலே சேர்க்கவேண்டும்.

ஏழாம் நூற்றாண்டின் மத்தியில் காஞ்சிபுரத்திலிருந்து ஆண்டுவந்த 'வாதாபி கொண்ட நாசிம்ஹ வர்மன்' என்னும் பல்லவ அரசன் சாளுக்கிய மன்னர்களைப் போரில் வென்று அவர்கள் தலைகரான வாதாபியிலே ஜயதம்பம் ஒன்றையும் கொண்டான் என்று வேலூர்ப் பாளையம் செப்பேடுகள் கூறுகின்றன. (தெ. இ. சாசனங்கள், இரண்டாம் வால்பூம்). அந்த வாதாபியிலேயே மல்லிகார்ஜுனர் ஆலயத்துக்குப் பின்புறம் பாறையில் அழகான பல்லவ கிரந்த எழுத்தில் பொறிக்கப்பெற்றுச் சிதிலமாகக் கிடைக்கும் பல்லவ நாசிம்மனுடைய பதிமூன்றாம் ஆண்டுக் கல்வெட்டு இதனை வலியுறுத்துகிறது. (ஸெபதினோராம் வால்பூம்).

அதேபோல, சென்ற நூற்றாண்டின்தொடக்கத்தில் நெப்போலியன் மீது ஆங்கிலேயர்கள் கொண்ட வெற்றிக்குச் சின்னமாகத் தஞ்சை மன்னர் சரபோஜி கி. பி. 1814-ஆம் ஆண்டில் ஒரு ஞாபகச் சின்னம் நிறுவினர். 'மனோரா' எனப்படும் அந்தக் கட்டிடம் தஞ்சை ஜில்லா பட்டுக்கோட்டைத் தாலுக்காவில் சாளுவநாயக்கன்பட்டினத்தில் எழுப்பப்பட்டுள்ளது. அந்தச் செய்தியைத் தெரிவிக்கும் சாசனம் ஆங்கிலம், தமிழ், தெலுங்கு, மராட்டி, பாரசீகம் ஆகிய ஐந்து பாஷைகளிலும் அதிலே பொறிக்கப்பட்டுள்ளது. (1925-ஆம் ஆண்டு 343, 344 எண் கொண்ட சாசனங்கள்).

இவ்விதம் நமக்குக் கிடைக்கும் இலக்கிய சாசனங்கள், சரித்திர சாசனங்கள் ஆகியவற்றின் எண்ணிக்கை மிகவும் குறைவு என்று ஒரு காலத்தில் கருதப்பட்டு வந்தது. ஆனால் அப்படியல்ல. அதிகமாகக்



கிடைக்கும் தான சாசனங்களாடு ஒப்பிட்டுப் பார்த்தால் அவை குறைவுதான். எனினும் அதிகமாகவே கிடைத்துள்ளன.

சுமார் கி.பி. 700-ஆம் ஆண்டுக்கு அணித்தாக ஆட்சிபுரிந்த இராஜ வலிம்ஹன் காலம் வரையில் பல்லவ மன்னர்களின் வமிச பரம்பரையைக் கொடுக்கும் வாயலூர்ச் சாசனம் (எபி. இந்திகா, பதினெட்டாம் வால்பூம்), பரமார மன்னனான போஜ தேவனுடைய பிரசஸ்தியைக் கொடுக்கும் குவாலியர்ச் சாசனம் (ஹெடி), மாளவ நாட்டுப் பரமார மன்னர்களின் புகழை எடுத்துரைக்கும் நாகபுரிச் சாசனம் (ஹெடி முதல் வால்பூம்), காலசூரிகளின் புகழைக் கூறும் காவியாச் சாசனம் (ஹெடி பதினெட்டாம் வால்பூம்) என்பன போன்றவைகளையும் சரித்திரக் கல் வெட்டுகளின் எடுத்துக்காட்டாகக் கொள்ளலாம்.

## 5. சாசன வகைகள்

தர்ம சாஸ்திரங்களிலே விசுதங்கள் (1) இராஜகீயம் அதாவது அரசன் அல்லது அரசாங்கம் பற்றியவை (2) ஜானபதம் அல்லது மக்களைப்பற்றியவை என இரு பிரிவுகளாகப் பகுத்துக் கூறப்பட்டுள்ளன. ஜானபதம் என்பது சில சமயங்களில் லௌகிகம் எனவும் பெறும். இராஜகீயம் என்பவை அரசனோ, அவனுடைய மந்திரிகளோ, அதிகாரிகளோ அளிக்கும் உத்தரவுகள் ஆகும். ஜானபதம் என்பவை பொது மக்கள் தங்களுக்கிடையில் அவர் அவர் செய்துகொள்ளும் உடன் படிக்கை, கிரய பத்திரம் முதலியவை ஆகும்.

இராஜகீயம் வகையைச் சாசனம், ஜயபத்திரம், ஆஜ்ஞாபத்திரம், பிரஜ்ஞாபனம் என மேலும் நான்கு பிரிவுகளாகப் பகுப்பர்.

(1) சாசனம் என்னும் வடமொழிச் சொல் உத்தரவு, கட்டளை என்ற பொருள்படும் என்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். பொதுவாக அது கோயில்களுக்கும் வித்துவான்களுக்கும் அரசன் பூமிதானம் அளித்ததை அறிவிக்கும் உத்தரவுகளையே குறிப்பிட்டுவந்தது. இடைக் காலத்திலே இச் சொல் பூமிதானத்தையே குறித்து வந்தது.

சாசனம் என்னும் வகையை யாஜ்ஞவல்கிய ஸ்மிருதி பின்வருமாறு விவரிக்கிறது : “ நிலத்தையோ நிவந்தத்தையோ அளித்த அரசன் பின்னால் வரும் மன்னர்களும் அறிந்து கொள்வதற்காக அதை எழுத்து மூலம் நிலைநிறுத்தவேண்டும். துணியிலோ, செப்பேட்டிலோ

அதை எழுதச் செய்து தன் (கையெழுத்து) அடையாளத்துடனும் முத்திரையுடனும் அளிக்கவேண்டும். அரசன் வமிசாவளி, அவனுடைய புகழ், தானம் பெறுவோன் பெயர், தானம் அளிக்கப்பெறும் நிலத்தின் அளவு, நான்கெல்லை, தானம் செய்யப்பெற்ற காலம், கையெழுத்திட்ட காலம் ஆகியவற்றையும் தெரிவிக்கவேண்டும்.”

ஆகவே முன்னாளில் அரசர்கள் நிலதானம் செய்ததைத் தெரிவிப்பனவாக உள்ள செப்பேடுகள், கல்வெட்டுக்கள் ஆகியவை எல்லாம் இந்த வகையைச் சேர்ந்தனவாகும். நிலதானத்தைத் தெரிவிப்பனவற்றுள் முன்னாளில் எழுதப்பட்டவற்றுக்கும் பிற்காலத்தனவற்றுக்கும் முக்கியமான வித்தியாசம் ஒன்று உண்டு. பிற்காலத்தை, முக்கியமாக விஜயநகர சாம்ராஜ்ய காலத்தைச் சார்ந்தவை, குறிப்பிட்ட தானங்களை நேரிடையாகவே தெரிவிக்கின்றன. தற்காலத்தில் எழுதப்பெறும் தான பத்திரங்களைப்போலவே அதன் வாசகம் அமைந்திருக்கக் காணலாம். இவ்விதம் தானம் பெறுவோர் அதை அனுபவிப்பதற்கான ஆதார பத்திரம் போலவே அது இருக்கிறது. ஆனால் முற்காலத்தை அப்படி அல்ல. உதாரணமாகப் பல்லவ அரசர்கள் அளித்தனவாகக் காணப்படும் பழைய தானங்களைக் கொள்ளலாம். அவையாலும் தானம் அளித்த செய்தியைத் தானம் வழங்கப்பெற்ற கிராமத்தின் பிரதேச அதிகாரிக்கோ, அவ்வூரின் சபைக்கோ தெரிவிக்கும் உத்தரவுகளாகவே அமைந்துள்ளன. பிற்காலத்திய பல்லவ மன்னர்கள், சோழ வேந்தர்கள் ஆகியோர் வழங்கிய சாசனங்களில் இதே செய்தியை அறிவிக்கும் தமிழ்ப் பகுதியும் சேர்க்கப்பட்டிருக்கும். அதிலே அரசன் உத்தரவைப் பெற்ற சபையார் அதன்மீது எடுத்துக்கொண்ட நடவடிக்கைகளும் கொடுக்கப்பட்டிருக்கும். அரசன் உத்தரவைப் பெற்ற சபையார் அதைத் தலையால் தாங்கி, தானம் வழங்கப்பெற்ற நிலப்பகுதியின் எல்லையை வலஞ்செய்து நிர்ணயித்துக் கல்லும் கள்ளியும் நாட்டி, தானம் பெற்றவர் அனுபோகத்துக்கு விட்ட செய்தியும் காணப்படும். ஆகவே அதற்குப் பிறகே செப்பேட்டில் கண்ட சாசனம் தயாரிக்கப்பெற்று உரிய அதிகாரிகளின் கையெழுத்தோடு ஏட்டில் பொறிக்கப்பெற்று அரசாங்க முத்திரையோடு வழங்கப்பட்டிருத்தல்வேண்டும் என்பது தெளிவாகும். அவற்றை நோக்கும்போது அந்நாளிலே தானம் செய்யப்பட்ட நிலத்துக்கு ஆதாரமாகச் செப்பேட்டிலே சாசனம் எழுதி வழங்குவதற்கு மிகவும் துணுக்கமான நடைமுறையும் சம்பிரதாயங்களும் இருந்து வந்தன வென்பது விளங்கும்.

(2) ஜயபத்திரம் என்பது பின்வருமாறு விவரிக்கப்பட்டுள்ளது :  
“விவரத்துக்கு வந்த விஷயத்தை அரசனே நேரில் கேட்டு ஆராய்ந்து,

நியாயம் வல்லோர் அபிப்பிராயத்தையும் அறிந்து, முடிவு செய்து அந்த முடிவைப் பொதுமக்களுக்கு ஜயபத்திரம் மூலமாக அறிவித்தல் வேண்டும்.”

இவ்விதம் மக்களில் ஒருவர்க்கொருவர் வழக்குப் புரிந்து அதை அரசனுடைய தீர்ப்புக்கு விட்டு அரசனே அவனுடைய அதிகாரிகளோ செய்த தீர்ப்புகளைத் தெரிவிப்பனவாகப் பல சாசனங்கள் கிடைத்துள்ளன. அத்தகைய விவாதங்களும் சாதாரணமான சொத்துரிமை முதல் சமூகத்தின் நிலையையே பாதிக்கும் வாழ்க்கை உரிமை வரையில் பலதரப்பட்டவை.

தஞ்சாவூர் ஜில்லா பட்டிச்சரத்திலிருந்து கிடைக்கும் கல்வெட்டு ஒன்று (1927-ஆம் ஆண்டு 257 நெ.) அவ்வூரில் வாழும் பட்டுதாற்காரர்களுக்கும் (சேணியர்) செட்டிகளுக்கும் கல்யாண கர்லங்களில் தாம்பூலம் வழங்கும் முறையைப் பற்றிய விவாதம் எற்பட்டு அந்த ‘வழக்குமுறி’ கி. பி. 1634-ஆம் ஆண்டில் மந்திரி கோவிந்த தீக்ஷிதர் முன்னிலையில் முடிவுசெய்யப்பட்ட விவாதத்தை அறிவிக்கிறது. இவ்விதம் வரும் வழக்குகள் சிற்சில சமயங்களில் சுலபமாகத் தீர்க்க முடியாதபடி சிக்கலாக அமைந்து நெடுநாள் இழுத்துக்கொண்டே போவதும் உண்டு. ஸ்ரீகண்ட சதுர்வேதிமங்கலத்துச் சபையாருக்கும் திருவெறும்பியூர்ச் சபையான ஊருக்கும் எல்லைத் தகராறு ஒன்று இருந்தது. அது ஒரு விதமாகவும் முடிவாகாமல் நீண்ட காலம் இழுத்துவந்தது. முடிவில் இருவருக்கும் திருப்தியான விலையைக் கொடுத்து அந்த நிலத்தை ஒரு வன் கிரயம் பெற்று அதை அவ்வூர்க் கோயிலுக்குத் தானமாக அளித்து விவாதத்துக்கு முடிவுகண்டான் என்ற செய்தியைத் தெரிவிக்கிறது ஒரு சாசனம். (கி. பி. 1914-ஆம் ஆண்டு 129 நெ.)

ஒரு வழக்கை அரசாங்கத்தின் தீர்ப்புக்கு விடுவது சம்பந்தமாக வழக்குத் தொடுப்பதிலிருந்து தீர்ப்பு அளிக்கப்பெறும் வரையில் உண்டாகும் அதன் நடைமுறையைப்பற்றிய விவரங்களைத் தெளிவாகச் சாசனங்கள் எடுத்துக் கூறவில்லை. ஆயினும் இங்கொன்றும் அங்கொன்றாக அவற்றில் காணப்படும் செய்திகளைக் கொண்டு குறையைப் பூர்த்தி செய்து ஒரு வழியாக நாம் அறிந்துகொள்ள முடியும். வழக்கை விசாரித்துத் தீர்ப்புக் கூறுவதற்காக அரசாங்கத்துக்கு உண்டாகும் செலவை வழக்கின் இரு தரத்தாரும் முன்னதாகவே அரசாங்கத்துக்குச் செலுத்திவிடவேண்டும் என்றும் தெரிகிறது. இலக்கியங்களிலிருந்து அறியப்படும் இச் செய்தி செங்கற்பட்டு ஜில்லா குன்றத்

துரிலிருந்து கிடைத்த ஒரு செப்பேட்டுச் சாசனத்தாலும் உறுதி யாகிறது. கலியப்தம் 4468, பராபவ வருஷம் விஜயநகர வேந்தன் சதாசிவதேவ மகாராயர் ஆட்சிக் காலத்தில் அவ்வூர்க்கோயில் பண்டா ரத்தாருக்கும் ஊராருக்கும் முதன்மையாரோடு விவாதம் உண்டாகி யது. அதன்மீது அவர்கள் வழக்கை அரசன் சமூகம் கொண்டுபோய்த் தீர்ப்பளிக்க வேண்டினார்கள். அதைத் தெரிவிக்குமிடத்தில் 'சமஸ்தா னம் கஜானா(வு)க்கு கப்பம் கட்டி ஜபாபஜயம் பண்ணி வாரா நிற்கிற காலத்தில்' என்று சாசனம் கூறுகிறது. இதிலிருந்து அவர்கள் செல வுத்தொகையை அரசாங்கத்துக்கு முன்னதாகவே செலுத்திவிடவேண் டும் என்பது தெளிவாகும்.

தஞ்சாவூர் ஜில்லா கீழையூரிலிருந்து கிடைக்கும் மூன்றாம் குலோத்துங்க சோழனுடைய ஆட்சிக் காலத்துக் கல்வெட்டு ஒன்று (1925-ஆம் ஆண்டு 80 நெ.) வேறு ஒரு வகையான வழக்கைப்பற்றித் தெரிவிக்கிறது. அந்த ஊரிலே வாழ்ந்த இருவர் கிராமத் துரோகி களாகவும் சமூக வாழ்க்கைக்கே பெரிய விரோதிகளாகவும் இருந்தனர். ஊரிலே தீ வைத்துக் கலகம் விளைவித்தனர் என்று குற்றம் சாட்டி அவர்களை விசாரித்து ஆயிரம் காச அபராதம் விதிக்கப்பட்டது. இதே போலக் கலகம் செய்து தீ வைத்த குற்றங்கள் நடந்தால் இருபதினா யிரம் காச வரையில் அபராதம் விதிக்கலாம் என்று அரசன் உத்தரவு அளித்திருந்தான். அவ்விருவருக்கும் விதிக்கப்பெற்ற ஆயிரம் காசை அபராதம் செலுத்த அவர்களுக்கு வழியில்லை. ஊரில் யாரும் அவர் களுக்கு உதவ முன்வரவில்லை. ஆகவே அவர்களுடைய நிலங்களைப் பறிமுதல் செய்து கோயிலுக்கு ஆயிரத்து அறுபது காசுக்கு விற்க வேண்டி வந்தது. நில விலையில் அதிகப்படியாகக் கிடைத்த அறுபது காசும் அபராதம் செலுத்தாதற்கான தண்டமாகக் கொள்ளப்பட்டது.

இவைகளைக் கவனிக்கும்போது முன்னாளிலே வழக்குகளை விசாரித்து நியாயம் வழங்கப்பட்ட முறையை ஓர் அளவு அறியலாம். ஆயினும், அந்நாளிலே அளிக்கப்பட்ட ஜயபத்திரங்களின் பிரதிகள் நமக்குக் கிடைக்கவில்லை.

கர்நாடக தேசத்துக் கிட்டிரில் ஒரு நிலத்தைத் தங்கள் தங்கள் கோயிலுக்கே உரியது என்று இரண்டு சைவாசாரியார்கள் கூறி வாதம் செய்ததைத் தெரிவிக்கும் கல்வெட்டு ஒன்று கிடைத்திருக்கிறது (ராயல் ஏஷ்டியாடிக் ஸொஸைட்டி, பம்பாய்க் கிளை, பத்திரிகை, ஒன்பதாம் வால்யூம்). அதிலிருந்து அந்நாளிலே ஒருவன் பழுக்கக் காய்ச்சிய மழுவைக் கையிலேந்தித் தன் கட்சியை நிரூபிக்கும் பழுக்கம் இருந்தது தெரிகிறது.

விஜயநகர வேந்தனான புக்கராயர் காலத்தில் சிவவணபெள்ள கொளத்தில் ஜைனர்களுக்கும் வைஷ்ணவர்களுக்கும் ஏற்பட்ட உரிமை வழக்கு ஒன்றைப்பற்றி அவ்வூரில் கிடைத்துள்ள சாசனம் ஒன்று தெரிவிக்கிறது. (எபி. கர்நாடிகா, இரண்டாம் வால்யூம், 344 நெ. சாசனம்). அவ்விரு சமூகத்தினரையும் மன்னன் சமரசம்செய்துவைத்து வைஷ்ணவர்களைப்போலவே ஜைனர்களும் மதானுஷ்டான உரிமையை யும் உற்சவம் முதலியவை நடத்தும் சுதந்தரத்தையும் அனுபவிக்க வேண்டும் என்று செய்த முடிவை அது எடுத்துரைக்கிறது.

(3) ஆஜ்ஞாபத்திரம்: 'சாமந்தர், உயர்தர அரசாங்க அதிகாரிகள், ராஜப்பிரதிநிதிகள் ஆகியோருக்கு அரசன் அனுப்பும் உத்தரவுகொண்ட ஒலை ஆஜ்ஞாபத்திரம் எனப்படும்.'

முன்னாளிலே பூதானம் செய்யப்பட்டதைத் தெரிவிப்பனவாக வடநாட்டிலும் சரி, தென்னாட்டிலும் சரி, கிடைக்கும் செப்பேடுகள் உண்மையில் அரசன் அச்செய்தியை அறிவித்துத் தன் அதிகாரிகளுக்கு அனுப்பும் உத்தரவுகளாகவே அமைந்துள்ளன வென்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம்.

காஞ்சிபுரத்துப் பல்லவமன்னனான சிவஸ்கந்தர்வமனுடைய ஹீர ஹடகள்ளிச் செப்பேடுகள் (எபி. இந்திகா, முதல்வால்யூம்) பிராமணர்கள் சிலருக்கு நிலதானம் செய்யப்பெற்ற விவரத்தை அறிவித்து, "நம் மாகாணத் தலைவர்கள், வத்தர்கள், அரசகுமாரர்கள், சேனாபதிகள், கோட்ட நிர்வாகிகள், சுங்க அதிகாரிகள், நாட்டு நிர்வாகிகளும் மற்றோர்களும், இன்னும், பலகிராமங்களை மானியமாக அனுபவிப்பர், கால்நடை மந்தைவைத்திருப்போர், கோபாலர், மந்திரிகள், வனத்து அதிகாரிகள், குமிகர், தூதிகள், நெயிகர், இன்னும் நம்மிடம் சேவைசெய்யும் எல்லோரும், இன்னும் சாரணர், படைவீரர் ஆகிய பலருக்கும்" அனுப்பிய ஆணையாக அமைந்துள்ளன.

அதேபோலத்தான் ஸ்ரீ ஹர்ஷன் என்பானது பன்ஸ்கேரா சாசனம் (ஷெ. ஆறாம் வால்யூம்) "ஹர்ஷன்...மஹா சாமந்தர், போலீஸ் அதிகாரிகள், நிலஅளவு அதிகாரிகள், ராஜப்பிரதிநிதி, குமாரஅமாத்தியர், கண்காணிப்போர், விஷயபதி, நிலைப்படையினர், கூலிப்படையினர், இன்னும் இதர ஊழியர்கள், இன்னும் அஹிச்சத்திர மாகாணத்தில் அங்கதிய விஷயத்தில் மேல்படாகையில் உள்ள மர்க்கடசாகரத்தில் கூடியுள்ள மஹாஜனங்கள் ஆகியோருக்கு" ஆணையிடுவதாகக் கூறுகிறது.

உண்மையில் அரசன் தானம் அளித்த செய்தியைத் தெரிவிப்பனவாகத் தமிழ்நாட்டில் கிடைக்கும் சாசனங்கள் எல்லாம் அந்த அந்த ஊர்ச்சபையாருக்கோ நாட்டாருக்கோ அரசன்விடுத்த திருமுகமாகவே உள்ளன. அந்தத் திருமுகங்களைப் பெற்ற பின்னரே சபையார் தான பூமியின் எல்லையை நிர்ணயித்துத் தானம் பெற்றவருக்கு நிலத்தை ஒப்புவித்துச் சாசனம் வழங்கியிருக்கிறார்கள். தமிழ்ச் சாசனங்கள் பலவற்றின் ஆரம்பத்தில் அரசனுடைய திருமுகத்தை அதை எழுதிய அதிகாரிகளின் கையெழுத்தோடு முழுதும் கொடுத்திருப்பதுடன், சபையார் அதையொட்டி மேலே எடுத்துக்கொண்ட நடவடிக்கைகளும் விவரிக்கப்பட்டிருக்கக் காணலாம். இவ்விதம் செய்வதால் தான வாசகமும் அதன் பரிகாரங்களும் சாசனத்திலே இரண்டு மூன்று இடங்களில் கொடுக்கப்பட்டிருக்கும். ஆகவே சாசனம் சிதிலமாகப் போய் ஏதாவது ஒர் இடத்தில் குறை இருந்தாலும் அதைப் பூர்த்தி செய்துவிட இயலும்.

சில சமயங்களில் அரசனுடைய திருமுகம் தனியாகவும் அதன்மீது சபையார் பணித்த உத்தரவு தனியாகவும் இருவேறு சாசனங்களாகக் கல்லில் வெட்டப்பட்டிருப்பதும் உண்டு.

(4) பிரஜ்ஞாபனம்: ‘ரித்விச், புரோஹிதர், ஆசாரியர், மான்யர் (கௌரவிக்கத்தக்கோர்), அப்யர்ஹிதர்(உரிமையுள்ளவர்) ஆகியோருக்கு ஒரு விஷயத்தைத் தெரிவிக்கும் ஒலை பிரஜ்ஞாபனம் எனப்பெறும்.’

இத்தகைய சாசனங்கள் மிகவும் குறைவு. இவை பொதுமக்களுக்கு அறிவிப்பனவாக ஏற்பட்டனவல்ல. குறிப்பிட்ட சிலருக்கு அவர்களுடைய வித்தையைக் கருதியோ அவர்களுடைய பதவி காரணமாகவோ முக்கியமான விஷயங்களை எடுத்து உரைப்பதற்காக அரசன் எழுதும் ஒலையே ஆகும்.

இராஜகீயம் என்னும் அரசாங்க வகையிலேயே ‘பிரசாதலேக்யம்’ என்று ஒரு வகையும் காணப்படுகிறது. “ஒருவனுடைய சேவையையோ வீரத்தையோ மெச்சி நிறைந்த மனத்துடன் அரசன் அவனுக்கு நிலமாகவோ வேறு விதமாகவோ பரிசு வழங்குவதை எழுத்து மூலமாக அறிவிப்பது பிரசாதலேக்யம் எனப்படும்.”

கி.பி. 949-50-ஆம் ஆண்டு கொண்டதாகக் காணப்படும் ஆதிகூர்க் கல்லில் உள்ள சாசனத்தை இதற்குச் சிறந்த உதாரணமாகக் கூறலாம். தக்கோலத்தில் நடந்த போரில் சோழ அரசிளங்குமானான இராஜாதித்தியன் ஏறியிருந்த யானையின்மீது அம்பாரியையே பேரர்க்களமாகக்

கொண்டு சண்டையிட்டுச் சோழ அரசன் இராஜாதித்தியனைக் கொன்று வெற்றியை அளித்ததற்காக மேலைக்கங்க அரசன் இரண்டாம் பூது கனுக்கு அவன் பேரரசனும் மைத்துனனுமான இராஷ்டிரகூடவேந்தன் மூன்றாம் கிருஷ்ணன் வனவாசி பன்னீராயிரம் பகுதியையும், பெள்ள குளம் முன்னூறு, புரிகேதே முன்னூறு, கிசுகாடு எழுபது, பாகேநாடு எழுபது ஆகிய பிரதேசங்களையும் அளித்தான் என்பதைத் தெரிவிக்கிறது அக் கல்வெட்டு. (எபி. இந்திகா, ஆறாம் வால்பூம்).

அதே கல்வெட்டில் உள்ள மற்றொரு சாசனத்திலிருந்து அந்தப் போரிலே ஈடுபட்டு உயிர் துறக்காமல் பிழைத்த வீரன் ஒருவனுடைய சாகசத்தை மெச்சி அவனுக்குச் சில கிராமங்கள் அளிக்கப்பெற்ற செய்தியும் தெரியவருகிறது. இந்தச் சாசனத்திலிருந்து மற்றொரு விஷயமும் நமக்குப் புலனாகிறது. மதாசாரியர் முதலிய பெரியோருக்குத் தானம் வழங்கப்பெறும் காலங்களில் அவர்களுடைய பாதங்களைக் கழுவி வழிபட்டுத் தானம் செய்வதுபோலப் போர்வீரர்களுக்குப் பரிசு அளிக் கும் சமயங்களில் அவர்களுடைய வாளைக்கழுவிக்கொளவிப்பார்களாம்.

கதம்பகுல வேந்தனான காகுஸ்தவர்மன் யுவராஜனாக இருந்த காலத்தில் போர்க்களத்திலே அவனுடைய உயிரைக்காதத் சேனாபதி சுருதகீர்த்தி என்பானுக்குக் கேட்டகிராமம் என்பதில் சில பூமிகளை அவன் பரிசாக அளித்த செய்தியைத் தெரிவிக்கின்றன ஹால்லிச் செப்பேடுகள் (இ. ஆ. ஆறாம் வால்பூம்). அந்தச் சாசனம் என்பதாவது விஜய ராஜப் ஸம்வதஸரத்தில் கொடுக்கப்பட்டிருப்பதாகக் காண்பதால், அப்போது கதம்ப ராஜபம் நிறுவப்பெற்று என்பது ஆண்டுகள் ஆயினவென்பதும் விளங்கும்.

ஜானபதம் எனப்பெறும் பொதுமக்கள் தனிப்பட்டவர் ஆகியோரின் பத்திரங்களை வியாசருடைய 'ஸ்மிருதி சந்திரிகை' பின்வருமாறு விவரிக்கிறது : “அது பிரசித்தமான ஊரைச் சேர்ந்த லேகக (எழுதுவோ)னால் எழுதப்பெறுதல் வேண்டும். அரசனுடைய வமிச பரம் பரை, ஆண்டு, மாதம், பக்ஷம், கிழமை ஆகியவைகளையும் அதிலே குறித்தல் வேண்டும்.” இத்தகைய பத்திரங்கள் பற்பல விதமான விஷயங்களைப்பற்றியனவாக இருக்கும். பணவிஷயமான அல்லது ஒப்பந்தம் பற்றிய பத்திரங்கள் குறிப்பிட்ட முறையிலே எழுதப்படவேண்டும் என்று ஸ்மிருதி தாலாசாரியர்கள் கூறுகிறார்கள். “பரஸ்பரம் சம்மதித்து முடிவு செய்யப்பெறும் விஷயங்கள் சாட்சிகளுடைய பெயர்களை யும், தனிகனுடைய பெயரையும் கொண்டு எழுத்து மூலமாக உறுதிப்

பெறுதல் வேண்டும்” என்று யாஜ்ஞவல்கியர் என்னும் ஸ்மிருதி ஆசிரியர் எழுதியிருக்கிறார்.

இவ்விதம் வகுக்கப்பட்டிருப்பதாலேயே பொதுமக்களுடைய விவகாரங்களைத் தெரிவிக்கும் சாசனங்களும் சரித்திர முக்கியத்துவம் வாய்ந்தனவாக ஆகின்றன. அவற்றிலே அந்நாளில் அரசு சேலுத்திய அரசனைப் பற்றிய விவகாரங்கள் காணப்படுகின்றனவன்றோ ?

கௌடில்யருடைய அர்த்த சாஸ்திரத்திலே சாசனங்கள் ஏழு வகையாகப் பகுக்கப்பட்டிருக்கின்றன. அவை: (1) பிரஜ்ஞாபனலேகை (2) ஆஜ்ஞா லேகை (3) பரிதான லேகை (4) நிச்ருஷ்டிலேகை (5) ப்ராவிருத்திகா லேகை (6) ப்ரதிலேகை (7) ஸர்வதரக லேகை எனப்பெறும்.

பிரஜ்ஞாபனம் என்னும் முதல்வகை அரசனுடைய ஆணையை அவன் அறிவித்தபடியே கொஞ்சமும் பிசகாமல் உரியவர்களுக்கு ‘இவ் விதம் அரசர் தெரிவிக்கிறார்’ என்று அறிவிக்கும் ஓலையாகும்.

ஆஜ்ஞாலேகை என்பது அரசன் தன்னிடம் சேவகம் புரியும் அதிகாரிகளுக்கும் ஊழியர்களுக்கும் அவர்களுடைய சேவையை மெச்சிப் பரிசு அளித்தோ குறையை எடுத்துக்காட்டிக் கண்டித்தோ விடுக்கும் ஓலை என்பர்.

மூன்றாவதான பரிதானலேகை என்பது தகுதி வாய்ந்தவர்களைக் கௌரவிப்பதற்காக அவர்களைப் புகழ்ந்து அவர்களுக்குச் சில நிவந்தங்களுையோ பரிசுகளையோ வழங்கி விடுக்கும் ஓலையாகும்.

நான்காவதான நிச்ருஷ்டிலேகை என்பது குறிப்பிட்ட சில சமூகத்தாருக்கோ அல்லது ஏதாவது ஒரு பகுதியில் வசிப்போர் அனைவருக்குமோ வரிவஜா போன்ற அதுக்கிரஹங்களைச்செய்து அரசன் அளிக்கும் ஓலையைக் குறிப்பதாகும். இது அரசன் வாய்மொழியாகவோ வேறு நடவடிக்கைகள் மூலமோ அளிக்கும் சலுகைகளைக் குறிப்பதாகக் கொண்டு ‘வாசிகலேகை’ எனப்பெறுவதாகும் என்பர்.

ஐந்தாவது ப்ராவருத்திகாலேகை என்பது நாட்டிலே துரிதங்கள், விபத்துக்கள் முதலியன ஏற்படக்கூடிய காவங்களில் எந்த எந்த விதமாக நடந்து அவற்றைத் தடுத்தும் அவற்றின் கொடுமையைக் குறைத்தும் நன்மை புரியவேண்டும் என்ற விவரங்களை எடுத்துக் கூறும் ஓலை என்பர்.



ஆறாவதான பிரதிலேகை என்பது அரசாங்கத்துக்கு வரும் கடிதங்களுக்கு அரசன் உத்தரவைப் பெற்று எழுதும் பதில் அல்லது மறுமொழி வாசகம் ஆகும்.

கடைசியான ஸர்வதரகலேகை என்பது நாட்டின் நலத்தையும் பொதுமக்களின் கேஷமத்தையும் குறித்து, பலதரப்பட்ட அதிகாரிகள் உள்பட அனைவருக்கும் அரசன் விடுக்கும் உத்தரவுகளைத் தெரிவிக்கும் ஓலையை எழுதுவதற்கான வாசகம் என்பதாகும்.

இவ்விதம் கௌடில்யர் வகுத்த பிரிவுகளுக்கும் தர்ம சாஸ்திரங்களில் காண்பனவாக மேலே நாம் எடுத்துக் காட்டிய பிரிவுகளுக்கும் வேறுபாடு இருப்பதைக் காணலாம். ப்ராஜ்ஞாபனம் எனப்படும் வகைக்கு இருவர் கூறும் விவரங்களும் வெவ்வேறாக உள்ளன. எனினும் இவற்றை ஒப்பு நோக்கும்போது கௌடில்யர் கூறிய பிரிவுகள் அந்நாளிலே அரசாங்கங்களின் நடைமுறையில் இருந்தன என்று கொள்ளலாம்.

தமிழ்நாட்டிலே கிடைக்கும் சாசனங்களையும் கௌடில்யர் கூறியுள்ள பல பிரிவுகளிலும் அடங்குவனவாக வகுத்துக் காட்டலாம். 'வாசிகலேகை' என்பதனோடு சோழ மன்னர்களின் ஆட்சிக் காலத்திலே அரசன் வாய்மொழியாக இடம் உத்தரவைத் திருவாய்க் கேள்வி என்னும் அதிகாரி கேட்டு எழுந்து மூலம் அனுப்பும் ஓலையை ஒப்பிட்டுக் கூறலாம்.

## 6. மத சம்பந்தமான சாசனங்கள்

நமக்குக் கிடைக்கும் சாசனங்களுள் பெரும் பகுதி நம் நாட்டுச் சரித்திரத்தை எழுதவேண்டும் என்னும் நோக்கத்துடன் ஏற்பட்டவையல்லவென்பதையும், நம் முன்னோர்களுடைய பக்தியும் மதப்பற்றுமே அவற்றுக்கு முக்கிய காரணங்கள் என்பதையும் நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். இந்தக் கலியுகத்திலே யாகங்களைக் காட்டிலும் தானங்களை யே புரியவேண்டும் என்றும், அவைகளே புண்ணியம் பயக்கும் என்றும் தர்ம சாஸ்திரங்கள் தெரிவிக்கின்றன. நம் முன்னோர் சந்தர்ப்பம் நேரிட்ட காலங்களிலெல்லாம் தானங்களையும் தருமங்களையும் செய்து வந்ததற்கு இதுவே காரணம் என்னலாம். அதனாலேதான் அத்தகைய தான தருமங்களைத் தெரிவிக்கும் சாசனங்கள் மிகுந்த அளவில் கிடைக்கின்றன.

இவை தவிர, தான தருமங்களைப்பற்றித் தெரிவிக்காமல் மத சம்பந்தமான நோக்கத்துடனே எழுந்த சாசனங்கள் சிலவும் உண்டு,

பொதுவாக இவ் வகுப்பைச் சேர்ந்த சாசனங்கள் மதத்தைப் பரவச் செய்யும் நோக்கத்துடனேயோ, அல்லது மதாசாரியர்களின் ஞாபகார்த்தமாகவோ ஏற்பட்டவையாகும். மதத்தைப் பரவச்செய்யும் நோக்கத்துடன் ஏற்பட்டவற்றிற்கு அசோக மன்னனுடைய சாசனங்களை நாம் உதாரணமாகக் கூறலாம்.

அசோக மன்னனுடைய கல்வெட்டுக்கள் வடக்கே இப்போது பாகிஸ்தானில் சேர்ந்திருக்கும் பெஷாவர் ஜில்லாவில் உள்ள ஷாபாஜ் கரீ என்னுமிடத்திலிருந்து தெற்கே மைசூரில் உள்ள சித்தபுரம், ஆந்திரப் பிரதேசத்தில் எற்றகுடி, கர்நாடகம் உள்ள ராஜஸூலமண்டிகிரி ஆகியவை வரையிலும்; கிழக்கே ஓரிஸாவில் கட்டாக்குக்குப் பக்கத்தில் உள்ள தெளஸி, கஞ்சம் ஜில்லாவில் உள்ள ஜெனாகட ஆகிய இடங்களிலிருந்து மேற்கே கத்தியவார் பிரதேசத்தில் உள்ள கிர்நார் (ஜுநாகத்) வரையில் உள்ள பிரதேசத்தில் பலவிடங்களில் காணப்படுகின்றன. தர்மத்திற்கு விரோதமாக இல்லாமலும் நீதிக்கு ஒத்தாப்போலும் நாட்டைப் பரிபாலனம் செய்ய அசோக மன்னன் கொண்டிருந்த உத்தேசத்தையும் மன்னன் அனுஷ்டித்து வந்த மதத்தைத் தவிரப் பிற மதங்களுக்கும் அவற்றிற்குரிய சுயேச்சையை அவன் அளித்திருந்ததையும் அச் சாசனங்கள் தெரிவிக்கின்றன.

அவனுடைய சாசனங்கள் கிடைக்கும் இடங்கள் எல்லாம் அவனுடைய ஆட்சியில் அடங்கியனவாக இருத்தல்வேண்டும் என்றும், தூரப்பிரதேசங்களில் கிடைப்பவை அவனுடைய நாட்டின் எல்லைப்புறங்களைக் குறிப்பனவென்றும் கருதப்பட்டு வருகிறது. தென்னாட்டில் சேர, சோழ, பாண்டியர்கள் தனியரசர்களாக இருந்ததும் சிரியா, எகிப்து, மசிடோனியா முதலிய பிற நாட்டு மன்னர்களுடன் அசோகன் சிறேக பாவத்துடன் இருந்ததும் அக் கல்வெட்டுகளால் நன்கு வெளியாகின்றன. அன்றி, அக்காலத்தில் மௌரிய சாம்ராஜ்யத்தின் தலைநகர் பாடலிபுரத்தில் இருந்ததென்பதையும், உஜ்ஜயினி, தக்ஷசீலம் முதலிய நகரங்களில் ராஜப் பிரதிநிதிகள் இருந்தனர் என்பதையும் அவை தெரிவிக்கின்றன; அம் மன்னன் கலிங்க நாட்டின்மீது படையெடுத்துச் சென்றதையும், அதன் பயனாக மன்னனுக்கு மதப் பற்று ஏற்பட்டதையும் அறிவிக்கின்றன.

அசோக மன்னனுடைய சாசனங்களில் பல வகைகள் இருக்கின்றன. மைசூர் சமஸ்தானத்தில் பிரம்மகிரி, சித்தபுரம், முதலிய இடங்களிலும் வட இந்தியாவில் ஸஹஸ்ராம், ரூப்நாத் முதலிய இடங்களிலும் உள்ள கல்வெட்டுகள் அசோகன் துறவியான பிறகு பொறிக்கப்

பட்டனவாகவும் சொண்ணகிரி (சுவர்ணகிரி) என்னுமிடத்தில் அசோகன் துறவியாக வசித்துவந்த காலத்தில் செய்த தர்மோபதேசத்தைத் தெரிவிப்பனவாகவும் உள்ளன. இவ்விடம் குறிக்கப்பட்ட சுவர்ணகிரி என்பது மாஸ்கிக்குத் தெற்கேயும் விஜயநகர-ஹம்பிக்கு வடக்கேயும் உள்ள கனககிரி என்னும் ஊராகவோ கர்தூல் ஜில்லாவில் உள்ள ஜோன்னகிரி என்னும் ஊராகவோ இருத்தல் வேண்டும் என்று ஆராய்ச்சியாளர் கருதுவர். எவ்விதமாயினும், அசோகன் துறவு பூண்டநாளில் தென்னாட்டில் வசித்து வந்தான் என்பது விளங்கும்.

பழைய காலத்து மன்னர்கள் யாகங்களைச் செய்து அந்தச் செய்தியைப் பொறித்துவைத்துள்ள கல்வெட்டுகளைக் கொண்டனவாகக் கிடைக்கும் யூப ஸ்தம்பங்களும் இந்த வகையைச் சேர்ந்தனவே. அத்தகைய சாசனங்கள் தமிழ் நாட்டிலே இதுகாறும் கிடைக்கவில்லை. எனினும், அணிமையிலே ஆந்திரப் பிரதேசத்திலும் வடக்கேயுள்ள மற்றப் பகுதிகளிலும் கிடைக்கின்றன.

இத்தகைய யூபஸ்தம்பச் சாசனங்கள் கடல் கடந்த பிரதேசங்களான தென் கிழக்கு ஆசியத் தீவுகளிலும் கிடைத்துள்ளன. அவற்றுள் போர்னியோவிலிருந்து கிடைத்த மூலவர்மனுடைய யூபஸ்தம்ப சாசனங்கள் பிரசித்தமானவை. கி. பி. நான்காம் நூற்றாண்டின் முடிவு அல்லது ஐந்தாம் நூற்றாண்டின் ஆரம்ப காலத்தைச்சார்ந்தனவென்று கொள்ளக்கூடிய பல்லவர்காலத்துக் கிரந்த எழுத்துக்களில் பொறிக்கப்பட்டுள்ள அவை, மூலவர்மன் என்னும் அந் நாட்டு அரசன் வைதிக மார்க்கத்தைச் சார்ந்த யாகங்களை நடத்தினான் என்றும் பிராமணர்களுக்கு ஏராளமான தகவிலையும் கோதானங்களும் வழங்கினான் என்றும் தெரிவிக்கின்றன. இவற்றால் தமிழ்நாட்டு நாகரிகமும் கலாசாரமும் அந்நாளில் எவ்வளவு தூரம் கிழக்கே கடல் கடந்து வெளிநாடுகளில் பரவியிருந்தனவென்பது நன்கு தெளிவாகும். (வங்காளத்து ராயல் ஏஷ்யாடிக் ஸொஸைட்டி பத்திரிகை, இலக்கியப் பிரிவு, முதல் வால்யூம்).

யமுனைப் பள்ளத்தாக்கில் அந்நதியின் உற்பத்தி ஸ்தானத்துக்கு அருகே ஜகத்கிராமம்என்னும் இடத்தில் நடந்த புதைபொருள் ஆராய்ச்சியில் ஏராளமான செங்கற்கள் கிடைத்துள்ளன. அவற்றில் ஒவ்வொன்றின் மீதும் ஒரே சமஸ்கிருத சுலோகம் கி. பி. மூன்றாம் நூற்றாண்டைச் சேர்ந்த எழுத்துக்களால் பொறிக்கப்பட்டிருக்கிறது. சீலவர்மன் என்னும் அரசன் நான்காவது தடவையாக அசுவமேத யாகம் செய்த விபரத்தைத் தெரிவிக்கிறது அது. சீலவர்மன் என்பான் இது

வரையில் வேறு ஆதாரங்களிலிருந்து தெரியவராத யௌதேய வமிசத் தைச் சேர்ந்த அரசனாக இருத்தல் வேண்டும் என்று ஆராய்ச்சியாளர் சொல்வர். (ஜர்னல் ஆப் ஒரியண்டல் ரிஸர்ச், இருபத்தோராம் வால்யூம்.)

சாதவாகன வமிசத்தைச் சேர்ந்த சாதகர்ணி என்னும் அரசன் இரண்டு அசுவமேதங்கள் உள்ளிட்டுப் பல பெரிய யாகங்களைச் செய்ததையும், அவன் தேவி நாகனிகை என்பவள் யாகப்பிராமணர்களுக்கு விலையுயர்ந்த தக்ஷிணைகளைக் கொடுத்ததையும் நாகாகாட் சாசனங்கள் கூறுகின்றன. சாதகர்ணி இறந்த பிறகு அந்த நாகனிகை என்பாள் இளவரசர்களான தன் பிள்ளைகளின் சார்பாக ராஜ்யபாரம் ஏற்றதும் அவற்றால் வெளியாகிறது.

அசோக மன்னனுடைய ரும்மிந்தேயி ஸ்தம்ப சாசனம் மதர்சாரி யரைப் பெருமைப்படுத்தும் நோக்கத்துடன் வெட்டுவிக்கப்பட்டதாகும். அக் கல்வெட்டால் புத்த பகவான் பிறந்தவிடமாகியதும் நேபாளத்தில் உள்ளதுமான லும்பினீவனம் என்னும் இடம் எது என்பதை நாம் நிச்சயமாகக் கூறமுடிகிறது. அசோகன் முடி சூட்டப்பெற்று இருபது வருஷங்கள் சென்ற பிறகு ஒரு சமயம் தனது நாட்டின் வடகிழக் குப் பாகத்தில் உள்ள அந்த இடத்தை நேரில் தரிசித்ததாகவும், அது சாக்கிய முனிவரின் பிறந்த இடமாதலால் அதைச் சுற்றிலும் சுவர் எழுப்பி அவ்விடத்தில் ஒரு ஸ்தம்பத்தை எழுப்பியதாகவும், லும் மினிகாம (லும்பினீகிராம)த்தார்கள் செலுத்தவேண்டிய சில வரி களுக்கு விலக்குகள் செய்து கொடுத்ததாகவும் அது தெரிவிக்கின்றது.

இவ்விதமாக, புத்தபகவானுடைய ஞாபகச் சின்னங்களைப் பத்திரப் படுத்திவைப்பதான எண்ணத்தால் ஏற்பட்ட சாசனங்களும் பல சரித் திர உண்மைகளைத் தெரிவிக்கின்றன. வட மதுரையில் உள்ள பெயர் பெற்ற சிங்கத்தூணில் உள்ள கல்வெட்டு ராஜூலன், சோடாஸன் முத லிய கூத்தரபர்களையும் தக்ஷசீலத்துச் சாசனம் பதிகன் என்னும் கூத்தரப னையும் பற்றிய விவரங்களைத் தெரிவிக்கின்றன. புத்தபகவானுடைய ஞாபகச் சின்னங்களைச் சேமித்து வைப்பதற்காகப் பேழைகளை உதவி யதைத் தெரிவிக்கும் பட்டிப்பேரோலுச் சாசனங்கள் அசோக மன்னன் காலத்தில் வழங்கிவந்த பிராமி எழுத்துகளினின்றும் வேறுபட்ட தென்தேசத்து எழுத்துக்களின் ஒரு வகையைக் காட்டுகின்றன.

ஆசாரியர்கள் முனிவர்கள் முதலிய பெரியோர்களின் சின்னங் களைக் கொண்டு அவற்றின் பேரில் ஸ்தூபங்கள் எழுப்பப்பட்டதைத் தெரிவிக்கும் கல்வெட்டுகளும் இவ் வகுப்பைச் சேர்ந்தனவேயாகும்.

ஸாஞ்சியிலும் ஸோநாரியிலும் கொதீபுத்த கஸ்ஸப கொத்தன், கொடினீபுத்த மஜ்ஜிமன், கொதீபுத்த துந்துபிஸ்ஸன் முதலியோர்களுடைய சின்னங்கள் பத்திரப்படுத்தப்பட்டுள்ளன வென்று அச்சின்னங்களை யுடைய சிமிழ்களின் பேரில் காணப்படும் சாசனங்கள் கூறுகின்றன. இச் சாசனங்களால் அசோகன் காலத்தில் எல்லைப்புற நாடுகளில் தர்மத்தைப் பரவச் செய்வதற்காக மொக்கலிபுத்த திஸ்ஸன் என்பவன் பிரசாகர்களை அனுப்பியதாகத் தீபவம்சம் என்னும் இலங்கைச் சரித்திர நூல் கூறுவது ஊர்ஜிதம் ஆகிறது.

கி. பி. பன்னிரண்டாம் நூற்றாண்டின் ஆரம்பத்தில் இலங்கையிலே விஜயபாஹு மன்னனுடைய ஆட்சி முடியப்போகும் தறுவாயில் பொலந்றுவையிலே அவ் வேந்தன் 'தலதாயப் பெரும்பள்ளி' என்னும் பெரிய ஆலயம் ஒன்றை எழுப்பினான். புத்த பகவானுடைய புனிதச் சின்னமான அவருடைய (பல்) தந்தத்தின் மீது எழுப்பப் பெற்றதே அவ்வாலயம். இடைக்காலத்திலே, அந்தப் புனிதமான சின்னத்தை அடைந்திருப்பதே அந்நாட்டு அரசுக்குரிய சின்னங்களுள் ஒன்றாக மதிக்கப்பட்டு வந்தது. இவ்விதம் அமைக்கப்பட்ட அந்த ஆலயத்துக்கு மூன்று கைத் திருவேளைக்காரர் தலதாயப் பெரும்பள்ளி என்று பெயரிட்டு அதன் பாதுகாப்பைத் தமிழ் நாட்டு வேளைக்காரப் படைவசம் ஒப்புவித்ததைத் தெரிவிக்கும் தமிழ்ச் சாசனம் ஒன்று அங்கே கிடைக்கிறது. (எபி. இந்திகா, பதினெட்டாம் வால்யூம்).

தெய்வ பக்தி மிகுந்தவர்கள் வழிபடுவதற்காக அங்கங்கே புகிய கோயில்களை நிர்மாணம் செய்த விவரத்தைத் தெரிவிப்பனவாகக் கிடைக்கும் பல்லவ சோழ மன்னர்களுடைய கல்வெட்டுக்களில் பல் இவ்விதம் மதப்பற்றினால் உண்டாகியவைகளே. இவ்வகையுள் கிடைப்பவற்றிலே மிகவும் பழமையானது மண்டகப்பட்டுக் குடைவரைக் கோயிலில் கிடைக்கும் பல்லவ அரசனான மகேந்திரவர்மனுடைய கல்வெட்டாகும். (ஐ. பதினேழாம் வால்யூம்). நான்கு வரிகளில் எழுதப்பெற்ற ஒரே சம்ஸ்கிருத சுலோகத்தால் ஆன அக் கல்வெட்டு, கல்லில்லாமலும், மரம் இல்லாமலும், உலோகம் இல்லாமலும், சுண்ணாம்பு இல்லாமலும், பிரம்மா, ஈசுவரன், விஷ்ணு ஆகிய மூவருக்கும் இருப்பிடமாக அக்கோயில் சமைக்கப்பட்டதைத் தெரிவிக்கிறது. தமிழ் நாட்டில் நிர்மாணிக்கப்பெற்ற முதல் குடைவரைக் கோயில் பூர்த்தியானதைக் கண்டு அம் மன்னன் அடைந்த களிப்பும், பெருமிதமும் அச்சிறு சாசனத்தில் நன்றாக ஒலிக்கின்றன. அதிலிருந்து அதற்கு முன்னர், கோயில்கள் செங்கல், சுண்ணாம்பு, மரம், உலோகம் ஆகியவற்றால் நிர்மாணிக்கப்பெற்று வந்தன என்ற செய்தியும் நமக்குத் தெரியு

வருகிறது. இவை காலக்கிரமத்தில் அழிந்துவிடக்கூடிய பொருள் களாகையால் கோயில்கள் அழியாமல் இருப்பதற்காகப் பிற்காலத்தில் கற்களால் எழுப்பப்பெற்று வந்தன.

இவ்விதம் செங்கல்லால் அமைந்திருந்த கோயில்கள் கற்றளி களாக நிர்மாணிக்கப்பெற்ற செய்தியைத் தெரிவிக்கும் பல சாசனங்கள் நமக்குக் கிடைக்கின்றன. தஞ்சாவூர் ஜில்லா திருக்கோடிக் காவிலிருந்து மதுராரந்தக உத்தம சோழனுடைய ஆட்சியின் பதினே ராம் ஆண்டு கொண்டதாகக் கிடைக்கும் சாசனம் ஒன்று (1931-ஆம் ஆண்டு 36 செ.) அம் மன்னனைத் திருவயிறு வாய்த்த பிராட்டியா ரான செம்பியன் மாதேவியார் அவ்வூரில் இருந்த கோயிலைக் கற்றளி யாக எடுப்பித்து, தனிக் கற்களில் பொறித்துக் கிடந்த கல்வெட்டுக்களை கோயில் ஸ்ரீவிமானத்தில் பொறித்துவைத்தாள் என்ற செய்தியைத் தெரிவிக்கிறது. அவள் அவ்விதம் செய்ததால் அவள் காலத்துக்கு முற்பட்டனவாக இருபத்தாறு சாசனங்களின் பிரதிகள் நமக்கு இப் போது கிடைத்துள்ளன. அன்றி அந்தச் சாசனத்திலிருந்து நமக்கு மற்றொரு விபரமும் தெரியவருகிறது. செங்கல் முதலியவற்றால் கோயில்கள் எழுப்பப்பெற்று வந்த அந் நாளிலே சாசனங்களைக் கருங் கற்களில் பொறித்து அந்தக் கற்களைக் கோயிலில் நிறுவியோ நட்டு வைத்தோ இருந்தார்கள் என்பதையும் அறிகிறோம்.

நமக்குக் கிடைக்கும் கல்வெட்டுக்களில் பெரும் பகுதி தான தரு மங்களைப் பற்றியனவே என்பதை நாம் முன்னரே குறிப்பிட்டிருக் கிறோம். அத்தகைய தானங்கள் நாட்டை ஆண்ட அரசர்களாலோ அவர்களுடைய அதிகாரிகளாலோ அல்லது நாட்டு மக்களில் தரும சிந்தை வாய்ந்த சிலராலோ அளிக்கப்பட்டவை. அவை பெரும்பா லும் கடவுள் வழிபாட்டிற்காகக் கோயில்களுக்கும், கோயில்களின் சார்பாகத் தேவகன்மிகளுக்கும், வேறு தர்ம ஸ்தாபனங்களுக்கும், மத போதகர்களுக்கும், மடங்களுக்கும் இன்னும் இவைபோன்ற இதர ஸ்தாபனங்களுக்கும் கொடுக்கப்பட்ட தானங்களைக் குறிக்கும்.

கோயிலுக்கு அளிக்கப்பெற்றவை பெரும்பாலும் நிலங்களாகவோ பொன்னாகவோ, இல்லாவிட்டால் ஆடு மாடு போன்ற கால்நடைகளா கவோ இருக்கும். அவ்விதம் அளிக்கப்பட்டவை கோயிலில் விளக்கு எரிப்பது, நித்த நைமித்திக பூஜை நடத்துவது, குறிப்பிட்ட காலங் களில் கட்டளைகளைச் செய்வது, விசேஷ உற்சவங்கள், தபஸ்விகளுக் கும் பக்தர்களுக்கும் உணவளிப்பது, இன்னும் பல பூசை திருப்பணி முதலியவைகளைச் செஷ்வுஷே நடத்துவதற்காகவே ஆகும்.

கோயிலுக்கு அளிக்கப்பெற்ற கால்நடைகளில் ஆடு, மாடு ஆகிய இருவகையும் அடங்கியிருந்தன. இரவும் பகலும் ஒரு நுந்தாவினுக்கு எரிப்பதற்குத் தேவையான நெய் அட்டுவதற்குத் தொண்ணூற்றாறு ஆடுகள் கொண்ட ஒரு மந்தை அளிக்கப்பட்டு வந்தது. அதையே பசுவாகக் கணக்கிடும்போது மூன்று ஆடுகளுக்கு ஒரு பசு வீதம் கொண்டு முப்பத்திரண்டு பசு கொண்ட மந்தையாகக் கணக்கிட்டனர். இந்த விதம் அளிக்கப்பெறும் ஆடு 'சாவா மூவாப் பேராடு' என்று வழங்கப்பெறும். முதுமையாலோ, சாவினாலோ மந்தைக்கு ஏற்படும் குறைவைக் குட்டிகளைக் கொண்டு பூர்த்தி செய்து குறிப்பிட்ட தொகை ஆடுகள் எப்போதும் கோயிலார்க்கு உபயோகமாகும் என்பதையே இத்தொடர் குறிப்பதாகும்.

அரசர்கள் தங்களுடைய பிறந்த நாளிலும் தங்கள் தேவிகளுடைய பிறந்த நாளிலும் கோயில்களிலே விசேஷ பூஜை நடத்துவதற்கு ஏற்பாடு செய்துவந்தார்கள். அதற்காகப் பொன்னோ, நிலமோ கோயிலுக்கு அளித்து வந்தனர். பல சமயங்களில் அரசன் பெயரால் இந்த நிவந்தங்களைச் சிற்றரசர்கள் அதிகாரிகள் முதலியோர் ஏற்படுத்துவதும் உண்டு.

சோழர் பேரரசன் இராஜராஜனுடைய தஞ்சைப் பெரிய கோயில் சாசனங்கள், பல்லவ அரசனான பாமேஸ்வர வர்மனுடைய கூரம் செப்பேடுகள் முதலியன கோயில்களுக்குக் கொடுக்கப்பட்ட கிராமங்களையும் தானங்களையும் பற்றித் தெரிவிக்கின்றன. .

வானவாசியிலிருந்து அரசாண்ட கதம்ப குல அரசர்களின் பழைய சாசனங்களிற் பல ஜினேந்திரருக்கும் அவரைப் பூஜை செய்வதற்காக ஜன முனிவர் பலருக்கும் தானமாகக் கொடுக்கப்பட்ட கிராமங்களையும் நிலங்களையும் பற்றித் தெரிவிக்கின்றன. அதேபோல, கி. பி. 466-ம் வருஷத்தில் ஸ்கந்த குப்தன் காலத்தில் கொடுக்கப்பட்ட இந்தோர்ச் சாசனம் சூரியபகவானுடைய கோயிலில் நிசதம் ஒரு விளக்கு எரிப்பதற்கு வேண்டிய நெய் கொடுத்து வருவதற்காகச் செய்யப்பட்ட தர்மத்தைத் தெரிவிக்கிறது.

சிவன் கோயில்களிலும் விஷ்ணு ஆலயங்களிலும் பூஜாகாலங்களில் மத்தளம் கொட்டுவதுபோன்ற இசைக்கருவிகளின் ஒலியோடு திருப்பதியம் பாடுவதும் பூஜை முறையின் ஓர் அம்சமாக விளங்கி வந்திருக்கிறது. இதை நடத்துவதற்கான நிவந்தங்களும் ஏற்பட்டிருந்தன. இச்செய்தியைத் தெரிவிக்கும் சாசனங்கள் முதற்பார்ந்தக

சோழன் காலத்திலிருந்தே தொடர்ச்சியாகக் கிடைக்கின்றன. (1914-ஆம் ஆண்டு 129 ரெ; 1915-ஆம் ஆண்டு 199 ரெ; 1918-ஆம் ஆண்டு 349-ரெ; 1933-ஆம் ஆண்டு 176-ரெ. முதலிய சாசனங்கள்.) இதே போலக் கோயில்களிலே பூஜைவேளையில் வேதம் ஒதுவதற்கும் வேறு ஸ்தோத்திரங்களைப்பாடுவதற்கும் நிவந்தங்கள் ஏற்படுத்தப்பெற்றதைத் தெரிவிக்கும் சாசனங்களும் உள்ளன. (1926-ஆம் ஆண்டு 123-ரெ.)

அந்நாளிலே திவ்வியதேச யாத்திரை செல்லும் பெரியோர்களுக்கும் தபஸ்விகளுக்கும் உணவு அளிப்பதும் கோயில் நிர்வாகத்தார் ஏற்றுவந்த பொறுப்புக்களுள் ஒன்றாக விளங்கியது. ஆகவே இதற்கு ஆகும் செலவுக்கு ஈடுகட்டக்கூடிய வருமானத்தைக் கொடுக்கும் நலத்தையோ, பொன்னை மீயா கோயில்களுக்குக் குறிப்பிட்டு அளித்த செய்தியைத் தெரிவிக்கும் சாசனங்களும் உள்ளன.

கோயம்புத்தூர் ஜில்லா கடத்தூரிலிருந்து கிடைக்கும் கொங்கு நாட்டு மன்னன் விக்கிரமசோழதேவனுடைய ஆட்சியின் இருபத்தோராம் ஆண்டு கொண்ட கல்வெட்டு ஒன்று (மக்கென்ஸி தொகுதியின் 286-ரெ.) அவ்வரசன் அதிகாரிகளுள் ஒருவனுை விக்கிரமசோழ திரிபுவனசிங்கதேவன் என்பான் தன்னுடைய மேகநோயைத் தீர்த்தருளியதற்காக அவ்வூர்ச் சிவபெருமானுக்கு நிலம் அளித்த செய்தியைத் தெரிவிக்கிறது.

இத்தகைய தருமங்கள் கோயில் தானத்தாரிடம் ஒப்படைக்கப்பட்டிருக்கும். சிற்சில சமயங்களில் கோயில் நிர்வாக உரிமையைப் பரம்பரையாகப் பெற்றிருப்பவரிடமோ நிர்வாகத்துடன் நெருங்கிய தொடர்புகொண்ட தனிமனிதரிடமோ ஒப்படைக்கப்படுவதும் உண்டு. மற்றும் சில சமயங்களில் கோயிலைச் சார்ந்த மடங்களின் பொறுப்பில் விடப்பெறுவதையும் காண்கிறோம். வட ஆர்க்காடு ஜில்லா காவேரிப் பாக்கத்திலிருந்து கிடைக்கும் பல்லவ அரசன் நிருபதுங்கவர்மனுடைய ஆட்சியின் இருபத்தைந்தாம் ஆண்டு கொண்ட சாசனம் ஒன்று (தெ.இ. சாசனங்கள், பன்னிரண்டாம் வால்பூம், 79-ரெ.) அவ்வூர்க் கோயிலில் விளக்கு எரிக்க அளிக்கப்பெற்ற பொன் 'மடத்து சட்டப் பெருமக்கள்' வசம் ஒப்புவிக்கப்பெற்ற தென்பதை அறிவிக்கிறது.

மடங்களுக்கும் வேறு தர்மஸ்தாபனங்களுக்கும் நிவந்தங்கள் அளித்த விவரத்தை அறிவிக்கும் சாசனங்கள் உள்ளன.

தமிழ்நாட்டில் கிடைக்கும் சாசனங்களுள் மிகப் பழமையானவை மூன்றாம் குன்றுகளில் உள்ள குகைகளில் கிடைப்பனவும் பிராமி



எழுத்துக்களில் பொறிக்கப்பட்டிருப்பவையுமான சாசனங்கள் புத்த மதத்தையோ சமணமதத்தையோ சார்ந்த துறவிகளுக்கு அந்தக் குகைகளைக் குடைவித்து அளித்த செய்தியைத் தெரிவிப்பனவென்றாகருதப்பட்டு வருகிறது.

பீஹார் ராஜ்யத்தில் பராபர், நாகார்ஜுனி மலைகளில் உள்ள குகைகளில் கிடைக்கும் அசோகன் காலத்தனவும் அவன் பெயரன் தசரதன் காலத்தனவுமான சாசனங்கள் அந்தக் குகைகள் ஆஜிவகதர்சனத்தைச் சார்ந்த துறவிகளின் உபயோகத்துக்காக வழங்கப்பெற்ற செய்தியைக் கூறுகின்றன. (இ. ஆ., இருபதாம் வால்யூம்).

காஞ்சிபுரம் காமகோடி பீடத்தில் அமர்ந்துள்ள சங்கராசாரியருக்கு விஜயநகர வேந்தர்கள் நிலம் அளித்த செய்தியைத் தெரிவிக்கும் செப்பேட்டுச் சாசனங்களைப் பற்றி முன்னரே (உசுள பக்கத்தில்) கூறியிருக்கிறோம். இன்னும் கோளகி மடத்து லக்ஷாத்தியாய சந்தானத்தைச் சார்ந்த சைவ ஆசாரியர்களுக்கு அளித்த தருமங்களைத் தெரிவிக்கும் சாசனங்கள் ஏராளமாகக் கிடைக்கின்றன. அன்றி, காசி, காஷ்மீரம் முதலிய இடங்களைத் தலைமையாகக் கொண்டு தமிழ் நாட்டில் இப்பங்கிவந்த வேறு பல மடங்களுக்கும் இத்தகைய தருமங்கள் அளிக்கப்பெற்றுள்ளன.

கூதராத்திர அரசனை நாகபானனுடைய மாப்பிள்ளையான உஷ்வதாதன் என்பவனுடைய சாசனம் ஒன்று நாகிக் என்னுமிடத்தில் இருக்கிறது. பௌத்த பிக்ஷுக்கள் சிலர் வசிப்பதற்காக ஒரு குகையைக் கொடுத்துதவியதுடன் பொருளையும், தென்னந்தோப்பையும் அவர்களுக்குத் தானம் செய்ததாக அது தெரிவிக்கிறது.

கன்னட தேசத்தில் இப்பொழுது அதிகமாக அனுஷ்டிக்கப்பட்டு வரும் வீர சைவமதம் எப்படி ஏற்பட்டது என்பதைத் தார்வார் ஜில்லாவில் அப்லூர் என்னுமிடத்தில் ஸோமநாதர் கோவில் கட்டப்பட்டதைத் தெரிவிக்கும் ஒரு சாஸனத்தால் நாம் அறிய வருகிறோம். அது ஹங்கலைச் சேர்ந்த கதம்பகுலத்து மஹாமண்டலேச்வரன் காம தேவனுடைய (சுமார் கி.பி. 1181-1203) காலத்தைச் சார்ந்தது. ஸோமநாதர் கோயிலைப் பற்றியும் அதைக் கட்டிய ஏகாந்த ராமய்யாவீர சைவமதத்துக்குச் செய்துள்ள பெருந்தொண்டுகள்பற்றியும் அது கூறுகிறது. அம்மதமானது பஸவர் சன்னபஸவர் என்று கூறப்படுகிற மாமன் மருமகன் ஆகிய இருவர்களால் ஏற்படுத்தப்பட்டது என்று பொதுவாக இப்பொழுது கூறப்பட்டு வருகிறது. லிங்காயதர்கள் என்று பொதுவாகக் கூறப்படுகிற வீர சைவர்களும் சற்றேறக் குறைய அதே

கொள்கையைப் பின்பற்றும் ஆராத்நியர்கள் என்று வழங்கப்பெறும் பிராம்மணர்களும் முக்கியமான காரியங்களைச் செய்யப்புகுமுன் நான்கு ஆராத்நியர்களுக்காக நான்கு பாத்திரங்களில் நீரை வைத்து அவர்களை வழிபாடு செய்கிறார்கள். ஆராத்நியர்கள் என்றால் ஆராதிக்கப்பட வேண்டியவர்கள், முனிவர்கள் என்று பொருள்படும். அந்த நான்கு பேர்களும் ரேவணர், மருலர், ஏகோராமர், பண்டித ஆராத்நியர் எனப் படுபவர்கள் ஆவர். வீர சைவ மதத்தை ஸ்தாபித்த பஸவர் காலத்தில், பிஜ்ஜலன் என்பவன் மேலைச்சாளுக்கிய நாட்டை அக்கிரமமாகக் கைப்பற்றி அரசனாக ஆண்டு வந்திருக்கிறான். ஆனால் அந்தப் பிஜ்ஜலன் இச்சாஸனத்தில் மஹாமண்டலேச்வரன் என்று ஓர் அதிகாரி (கவர்னர்)யாகவே குறிக்கப்பட்டிருக்கிறான். வீர சைவர்கள் இந்நான்கு ஆராத்நியர்களும் பஸவர் காலத்திற்கு முன்பு வாழ்ந்தவர்கள் என்று கூறுவதால், மேலை மூன்றாவதாகக் குறிக்கப்பட்ட ஏகோராமர் எனப் படுவர் அப்லூர் சாசனத்தில் குறிக்கப்பட்ட ஏகாந்த ராமய்யாவாகவே இருக்கவேண்டும் என்பது நன்கு பெறப்படுகிறது.

மதப்பற்றுக்கொண்டு அளித்தனவாக நம் நாட்டில் கிடைக்கும் சாசனங்களைக் கவனித்துப் பார்த்தால் ஒரு விஷயம் தெரியவரும். ஒரு குறிப்பிட்ட மதம் மட்டுமேயல்லாமல் எல்லாமதங்களுக்கும் அவை வழங்கப்பட்டுள்ளன. அதனால் பல மதங்களும் நம் நாட்டிலே தாராளமாகப் பரவிப் பெருகியிருந்த செய்தி தெரியவரும்.

நமக்குக் கிடைக்கும் சாசனங்களில் பெரும்பாலானவை சிவன் கோவில் விஷ்ணு ஆலயம் ஆகிய இரண்டுக்குமே அளித்த தருமங்களுையே தெரிவிப்பனவாகும். எனினும், வேறு மதங்களைப்பற்றிய சாசனங்களும் இல்லாமல் இல்லை. ஜாவா நாட்டு ஸ்ரீவிஜய ராஜ்யத்து அரசன் தமிழ்நாட்டு நாகபட்டினத்தில் புத்த பகவானுக்குச் சூடாமணி வர்ம் விகாரம் என்ற பெயரில் ஆலயம் எடுத்த செய்தியையும் அந்த மன்னர்களின் வேண்டுகோளுக் கிணங்கிச் சோழ வேந்தர்கள் அக் கோயிலுக்குப் பல கிராமங்களை அளித்த செய்தியையும் தெரிவிக்கின்றன லீடன் பட்டயங்கள். (எபி. இந்திகா, இருபத்திரண்டாம் வாழ்வும்). அந்நாளிலே தமிழ்நாட்டுக்கும் இந்தோனேசியத் தீவுகளுக்கும் இருந்து வந்த உறவு இந்தச் சாசனங்களால் நன்கு விளங்குகின்றது.

அதேபோல ஜைனப் பள்ளிகளுக்கும் கிராமங்கள் அளிக்கப் பெற்றிருந்தன. சித்தாமூர், திருப்பருத்திக்குன்றம், விஜயமங்கலம் முதலிய இடங்களிலிருந்து கிடைத்தனவாகக் கர்னல் மக்டென்ஸியின்

உதவியாளர்கள் சேகரித்து இந்தத் தொகுதியில் வெளியிடப்பட்ட சாசனங்களை அதற்கு ஆதாரங்களாகக் காட்டலாம்.

சமீபத்தில் காஞ்சிபுரம் காமாட்சி அம்மன் கோயிலிலிருந்து கிடைத்ததும் எட்டாம் நூற்றாண்டு எழுத்துக்களில் பொறிக்கப்பெற்றதும் பல்லவ அரசனான நாலிம்ஹபோத்தரையனுடைய ஆட்சியின் பதினெட்டாம் ஆண்டு கொண்டதுமான தமிழ்ச் சாசனம் ஒன்று ஆஜீவக தர்சனத்தையும் அறிவர் கோயிலையும் குறிப்பிடுகின்றது. (இந்தியன் ஆர்க்கியாலஜி, அறிக்கைச் சுருக்கம், 1954-55)

இவற்றைத் தவிர, புண்ணியஸ்தலங்களுக்குச் செல்லும் யாத்திரிகர்கள் தங்கள் பெயர்களை அவ்விடங்களிற் பொறித்துவைத்து வரும் பழக்கத்தால் உண்டான சாசனங்களிற் பல ஸாஞ்சி, பார்ஹுத் முதலிய இடங்களிற் கிடைக்கின்றன. எந்த எந்தத் தேசங்களிலிருந்து அவ்விதம் யாத்திரிகர்கள் வந்துபோனார்கள் என்பதை அறிய உதவுகின்றன அந்தச் சாசனங்கள். இப் பழக்கத்தை இப்பொழுதும் திருப்பதி போன்ற புண்ணியஸ்தலங்களுக்குச் செல்லும் யாத்திரிகர்கள் அனுஷ்டித்து வருகிறார்கள். செங்கற்பட்டு ஜில்லாவில் உள்ள திருக்கழுக்குன்றத்திலிருந்து கிடைத்துள்ள சாசனங்களிலிருந்து கி.பி.பதினேழாம் நூற்றாண்டில் அந்தக் கோத்திரத்துக்கு விஜயம்செய்ததச்ச (உலாந்தாக்கும்பெனி) அதிகாரிகளின் பெயர்களும் அவர்கள் வந்துபோன தேதிகளும் கிடைக்கின்றன. (சாசன இலாகா அறிக்கை, 1908-ஆம் ஆண்டு, 79 - பாரா.)

இறந்த பெரியோர்களின் ஞாபகார்த்தமாக அவர்களுடைய வழிவந்தவர்களாலோ சிஷ்யர்களாலோ எழுப்பப்பெற்ற சின்னங்களும் இந்த வகையைச் சார்ந்தனவே.

சமண மதத்தைச் சார்ந்த சந்திரநந்தி என்னும் ஆசாரியர் ஐம்பத் தேழுநாள் உண்ணாவிரத நோன்பு இருந்து உயிர் துறந்ததையும் அவருக்கு அங்கே ஒரு நிசீதிகை எழுப்பியதையும் தெரிவிக்கும் திருநாதர் குன்றிலிருந்து பழந்தமிழ் எழுத்தில் உள்ளதாகக் கிடைக்கும் சாசனம் (1904-ஆம் ஆண்டு 239 நெ.) இந்த வகைக்குச் சிறந்த உதாரணமாகக் கொள்ளலாம். இவ்விதம் சமணமுனிவர்கள் சல்லேகனை நோற்று உயிர் துறந்ததையும் அதற்காக அவர்களுடைய சிஷ்யர்கள் நிசீதிகை எழுப்பியதையும் தெரிவிக்கும் சாசனங்கள் ஏராளமாகக் கன்னட தேசத்தில் கிடைக்கின்றன.

இறந்துபட்ட வீரர்களுக்கு எழுப்பப்பெற்ற நடுகல்களும் இவ்வகையே. பகைவருக்கு அஞ்சாமல் ஆற்றலோடு போர்புரிந்து இறந்துபட்ட வீரர்களுக்கு அவர்கள் இறந்துபட்ட இடங்களிலோ வேறிடங்களிலோ நடுகல் அமைத்து முன்னோர் விழா நடத்திப் பாராட்டி வந்த செய்தி பழைய தமிழ் இலக்கியங்களில் காணப்படுகின்றன. அந்நடுகல்லில் இறந்த வீரர்களின் பெயரும் பெருமையும் சில சமயங்களில் உருவமும் பொறிக்கப்பட்டிருக்கும்.

“ நல்லமர்க் கடந்த நாணுடை மறவர்  
பெயரும் பீடும் எழுதி அதர்தொறும்  
பீலி சூட்டிய பிறங்குநிலை நடுகல் ”

(அகநானூறு-67)

என்று சங்க நூல்களில் காணும் பழக்கத்தை யொட்டி எழுந்த நடுகற்கள் அங்கங்கே இன்றைக்கும் கிடைக்கின்றன.

லால்சூழிக்குப் பக்கத்தில் உள்ள சென்னிவாய்க்கால் என்னுமிடத் திவிருந்து கிடைக்கும் நடுகல் ஒன்றில் பிராமணன் ஒருவனுடைய கழுத்துக்குப் பக்கத்தில் அம்பு துளைத்து அவன் உயிர் துறக்கும் காட்சியில் உருவம் செதுக்கப்பட்டுள்ளது. ‘தெள்ளாற்றெறிந்து ராஜ்யமும் கொண்ட’ நந்திவர்மனுடைய ஆட்சியின் இருபத்தோராம் ஆண்டில் சேவணர் குதிரைகளுடன் மாவலி வாணராயன் படையெடுத்து வந்து தாக்கி மடமும் சுட்டு, குரவரையும் எரித்த நாளில் ஒரு சிஷ்யன் காக்கப்போய் உயிர் துறந்த செய்தியைத் தெரிவிக்கிறது. அதிலே சோழமன்னர்களான முதல் பராந்தகன், அவன் மகன் அரிஞ்சயன் ஆகியோருடைய பெயர்கள் காணப்படுவதால் கி. பி. பத்தாம் நூற்றாண்டின் தமிழ்நாட்டுச் சரித்திரத்துக்கு அக் கல்வெட்டு மிகவும் முக்கியமானது.

இதேபோல, சதிகளாக உடன்கட்டை ஏறி உயிர்துறந்த பெண் மணிகளைப்பற்றித் தெரிவிக்கும் சாசனங்களும் இவ்வகையைச் சார்ந்தனவே. கி. பி. 1057-ஆம் ஆண்டில் ஒருவன் மல்யுத்தப் போட்டியில் அரசன் உறவினன் ஒருவனைக் கொன்றுவிட்டான். அந்தக் குற்றத்துக்காக அவனுக்கு மாணதண்டனை விதிக்கப்பெற்றது. அவன் மனைவியும் துங்கநாட்டுச் சிற்றரசன் மகளுமான தேகப்பே என்பாள் பெற்றோர்கள் எவ்வளவோ தடுத்தும் கேளாமல் தன் புருஷனுடன் உடன் கூட்டி ஏறத் தீர்மானித்தாள். இச் செய்தியைத் தெரிவிக்கும் சாசனம்

கன்னடமொழியிலே உருக்கமாகக் காவியம்போல் அமைந்திருக்கிறது. (எபி. இந்திகா, ஆறாம் வால்பூம், 213-19 பக்கம்; எபி. கர்நாடிகா, நான் காம் வால்பூம், எச். ஜி. 18.)

தென் ஆர்க்காடு ஜில்லாவில் எலவானூர் என்னுமிடத்திலிருந்து சோழ மன்னனான வீரராஜேந்திரன் ஆட்சிக்காலத்துச் சாசனம் ஒன்று (1906-ஆம் ஆண்டு 156 நெ.) கிடைத்துள்ளது. அதிலே உடன் கட்டையேறிய ஒருத்தி, புருஷன் இறந்த பிறகு தான் உயிருடன் இருந்தால் தன்னுடைய சக்களத்தியருக்கு அடிமையாக உழைக்க நேரிடும் எனக்கூறி, தன்னை உடன் கட்டை ஏறாமல் தடுப்பவர்கள்மீது சொல்லொணப் பழிபாவங்களைச் சுமத்திச் சபிக்கிறாள். அதுமட்டுமல்ல; தன்னைக் கட்டி நெருப்பிலே போட முன்வராதவர்கள் மீதும் அவ்விதம் பழி சுமத்துகிறாள் அவள்.

இவ்விதம் உடன்கட்டை ஏறியவர்கள் செயற்கரிய காரியங்களைச் செய்து புண்ணியம் பெற்றவர்கள் என்பது நம்முன்னோர் கருத்து. ஆகவே இவ்விதம் உயிர்த்துறந்தவளை அவளுடைய வழி வந்தோர்கள் தெய்வப் பிறவியாகக் கருதி வழிபட்டு வந்தனர். மாசதிக்கல்கள் என்னும் இக்கல்கள் நிறுவப்பெற்றதற்கு இதுவே காரணம்.

புரீரங்கத்திலிருந்து கிடைக்கும் சாசனம் ஒன்று (இத்தொகுதியில் 783 நெ.) பிராமணன் ஒருவன் கோயிலின் கோபுரத்திலிருந்து கீழே விழுந்து பிராணத்தியாகம் செய்துகொண்டதைத் தெரிவிக்கிறது. கோயிலில் பூஜை சரிவர நடக்காததைக் கண்டு மனம் வருந்தி அதை ஒழுங்குபடுத்துவதற்காகவே அவன் தன்னைப் பலியிட்டுக்கொண்டான். உடனே அதற்கு உரிய பலன் கிட்டியது. பூஜைகள் செவ்வனே நடைபெற ஆரம்பித்தன. அவனுக்கும் பிரம்மமேத சம்ஸ்காரத்தால் அந்திமக் கிரியைகளை நடத்திக் கோயிலார் அவனைப் பெருமைப்படுத்தினர்.

## 7. உலக வாழ்க்கைபற்றிய சாசனங்கள்

மக்களின் சமூக வாழ்க்கையைப்பற்றியும் அதிலே அவர்கள் அனுபவித்துவந்த உரிமைகள் பற்றியும் இன்னும் அவர்களுடைய சொத்து சுதந்தரங்கள் பற்றியும் தெரிவிக்கும் சாசனங்களும் வேண்டிய அளவு கிடைக்கின்றன.

செங்கற்பட்டு ஜில்லா உத்தரமேரூரிலிருந்து முதற் பராந்தக சோழனுடைய ஆட்சிக் காலத்தனவாக இரண்டு தமிழ்ச் சாசனங்கள் கிடைத்துள்ளன. (இந்தியப் புதை பொருள் இலாகாவின் ஆண்டு

அறிக்கை, 1905). அவற்றுள் அவ்வூர்ச் சபைக்கும் அதன் வாரியங்கள் களுக்கும் உறுப்பினர்கள் குடவோலை மூலம் தேர்ந்தெடுக்கப்படுவதற்கான விதிகளும், அவ்விதம் தேர்ந்தெடுக்கப்படுவோர் பெற்றிருக்க வேண்டிய யோக்கியதாம்சங்களும் விரிவாகக் கொடுக்கப்பட்டுள்ளன. இதேபோன்ற சாசனங்கள் தமிழ்நாட்டின் வேறு பகுதிகளிலிருந்தும் கிடைக்கின்றன. அவற்றிலிருந்து அந்நாளிலே அத்தகைய சபைகளும் அவைபோன்ற இதர ஸ்தாபனங்களும் எவ்விதம் நிறுவப்பட்டுச் செயலாற்றி வந்தன வென்பது தெளிவாக விளங்கும். தஞ்சாவூர் ஜில்லாவில் முத்துப்பேட்டைக்குப் பக்கத்தில் உள்ள சித்தமல்லியிலிருந்து இத்தகைய சாசனம் ஒன்று கிடைத்துள்ளது. சோழ வேந்தனான அதிராஜேந்திரனுடைய ஆட்சியில் சுத்தமல்லிச் சதுர்வேதி மங்கலத்துச் சபையார் செய்த விவஸ்தையைக் கூறும் அந்தச் சாசனம் (1946-ஆம் ஆண்டு, 5 நெ.) அந்நாளின் பஞ்சாங்கக் குறிப்புகளைக் கொண்டுள்ளது. ஆகவே அது அதிராஜேந்திரனுடைய ஆட்சிக் காலத்தை நிர்ணயிக்கப் பெரிதும் உதவுகிறது. (1944-ல் நான் கண்டுபிடித்த இச்சாசனம் எபி. இந்திகாவில் விரைவில் வெளியாகும்.)

இதேபோல் உழுதுண்டு வாழும் வெள்ளான்மக்கள் நிரம்பிய கிராமத்துக்கு ஊர் என்னும் சபையும், வணிகர் நிறைந்த இடத்துக்கு நகரம் என்னும் சபையும் இருந்த செய்தியும் சாசனங்கள் வாயிலாகத் தெரியவருகின்றன. சிற்சில சமயங்களில் ஒரே இடத்தில் ஒன்றுக்கு மேற்பட்ட சபைகளும் இருந்து அதன் அதன் காரியத்தைக் கவனித்து வந்ததையும் காண்கிறோம்.

இன்னும், பெரும்பாலும் உழவோர்கள் நிறைந்த 'சித்திரமேழிப் பெரியநாட்டவர்', பல தேசத்து வியாபாரிகள் அமைத்துக்கொண்ட 'நானாதேசி' எனப்பெறும் 'திசை ஆயிரத்து ஐந்துாற்றுவார்', தச்சர், கம்மாளர் போன்றோருடைய 'ரதகாரர்' ஆகிய ஸ்தாபனங்கள் பல தேசங்களுக்கும் பொதுவாகப் பெரிய அளவில் செயலாற்றி வந்த விவரத்தையும் அறிகிறோம்.

இதுகாறும் கிடைத்துள்ள சாசனங்களைக் கவனித்தால் ஒரு விஷயம் தெரியவரும். நம்முடைய வாழ்க்கையில், சமூக வாழ்க்கையிலும் சரி, தனி மனிதர் வாழ்க்கையிலும் சரி, மதம் வெகுவாக ஊடுருவி இரண்டறக் கலந்து நிற்கிறது. மக்களின் சமூக வாழ்க்கை பற்றியவை என்று நாம் இப்போது கருதும் பல காரியங்கள் அந்நாளிலே புண்ணியம் பயப்பவை என்ற எண்ணத்தால் மத அடிப்படையில் முக்கியத்துவம் பெற்றிருந்தன. உண்மையில் நம் வாழ்க்கை முறையிலிருந்து மதத்தைத் தனியாகப் பிரித்துவிடுவது முடியாத ஒன்றாகும்.

பொதுமக்களின் நல்வாழ்க்கைக்கு உபயோகப்படுவனவாகக் குளம் தொடுவது போன்ற நற்பணி செய்த விவரங்களை அறிவிக்கும் சாசனங்கள் கிடைக்கின்றன. வனவாசியிலிருந்து அரசாண்ட கதம்ப வமிசம் எப்படி நிறுவப்பெற்றது என்பதைக் கூறி அதன் பிழைய வரலாற்றைக் காவிய நடையில் எடுத்துக் கூறும் கதம்ப காகுஸ்தவர்மன் காலத்துத் தாளகுண்டா ஸ்தம்ப சாசனம் முக்கியமாக அவ்விடம் ஒரு பெரிய குளம் அமைக்கப்பட்ட விவரத்தை அறிவிப்பதாகவே உள்ளது. (எபி. இந்திகா, எட்டாம் வால்யூம்). கத்தியவார்ப்பிரதேசத்தில் ஜுநா கத்திலிருந்து கிடைக்கும் ஸுத்திரப் அரசன் ருத்திரதாமன் காலத்துச் சாசனமும் (௯௮) இதேபோன்றதுதான்; சுதர்சனம் என்னும் பெரிய ஏரியின் கரையைச் செப்பனிட்ட செய்தியை அறிவிக்கிறது. அதிலிருந்து அந்த ஏரி மௌரிய அரசனான சந்திரகுப்தன் காலத்தில் அவனுடைய பிரதிரிதி ஒருவனால் நிர்மாணிக்கப்பட்டதென்பதும், அசோகனுடைய பிரதிரிதி ஒருவன் அதைச் செப்பனிட்டான் என்பதும் தெரியவருகின்றன. அவ்விடத்திலே கிடைக்கும் மற்றொரு சாசனத் தால் பிற்காலத்தில் ஸ்கந்தகுப்தன் என்னும் குப்த மன்னன் காலத்திலே அந்த ஏரிக்கு மறுமுறையும் ஒரு தடவை மராமத்து வேலை நடந்த விவரம் தெரிகிறது. (குப்த சாசனங்கள், 56 பக்கம்).

இராமநாதபுரம் ஜில்லா எருக்கங்குடியிலிருந்து கிடைக்கும் ஒரு தமிழ்ச் சாசனம் (1930-ஆம் ஆண்டு, 334 நெ.) நெடுமாரன் ஸ்ரீவல்லபன் என்னும் பாண்டிய அரசன் காலத்தில் எட்டி சாத்தன் என்பான் பாண்டி நாட்டு மக்களுக்குச் செய்த அரும்பெரும் சேவைகளை எடுத்து உரைக்கிறது. தூர்ந்து கிடந்த பல குளங்களையும் ஏரிகளையும் செப்பனிட்டதுடன் அவன் புதிதாகவும் பல குளங்களைத் தோண்டினானாம். அவன் சேவையை மெச்சி அரசன் அவனுக்கு 'இருப்பைக்குடிக்கிழான்' என்னும் விருதை அளித்தானாம். இதே போன்ற சாசனங்கள் நாடு முழுவதும் அங்கங்கே கிடைக்கின்றன.

கடுங்கோடையில் வழிநடை செல்வோர்க்கும் தாகத்தால் தவிப்போர்க்கும் குளிர்த நீர் வழங்கி அவர்கள் விடாயைத் தணிப்பதற்காகத் தண்ணீர்ப்பந்தல்கள் அங்கங்கே நிறுவும் பழக்கம் அந்நாளிலும் காணப்படுகிறது. அவ்விதம் பந்தல் அமைத்து, நீர் வார்ப்பவன் சம்பளம் உள்ளிட்டு ஆகும் செலவுக்குத் தேவையான வருமானத்தை அளிக்கும் நிலத்தையோ பொன்னையோ வழங்கிய செய்தியைத் தெரிவிக்கும் சாசனங்கள் கிடைத்துள்ளன.

இத்தகைய சம்பவங்களை நாம் இப்போது சமூக வாழ்க்கையின் அமைப்புக்கு அவசியமான செயல்கள் என்றே கொள்வோம். ஆயினும்

நம் முன்னோர் இச் செயல்களைப் புண்ணியம் பெறவேண்டுமென்று கருதியே நடத்தினர் எனக் கொள்ளலாம்.

தென்னார்க்காடு ஜில்லாவில் உள்ள எண்ணூர்பிரம் என்னும் ஊரி லிருந்து சோழ சக்கரவர்த்தியான இராஜேந்திரன் காலத்திய சாசனம் ஒன்றினால் அவ்வூர்ப் பெருமாள் கோயிலில் சில கட்டளைகளை நடத்து வதற்காகவும்; வேதம், வேதாந்தம், தர்க்கம், வியாகரணம் முதலிய வற்றைக் கற்பிப்பதற்காகப் பதினான்கு ஆசிரியர்களையும் முந்நூற்று நார்பது மாணவர்களையும் கொண்ட ஒரு பாடசாலையை ஏற்படுத்தி ஆசிரியர்களுக்கும் மாணவர்களுக்கும் சாப்பாட்டிற்கு வேண்டிய ஏற்பாடு களையும் செய்து அவை நன்கு நடைபெறுவதற்கு வேண்டிய செலவு களுக்காகவும் இரண்டு கிராமங்கள் இனாமாக அளிக்கப்பட்டதை நாம் அறிகிறோம். (1917-ம் ஆண்டு நெ. 333 சாசனம். அம்மாணவர் களில் எழுபது பேர் நன்கு கற்ற சாத்திரர்கள்; பாக்கி இருநூற்று எழுபது பேரும் பூர்வாங்கப்பயிற்சி அடைந்தவர்கள். இராஜராஜ சதூர் வேதி மங்கலம் என்னும் அவ்வூர்ச்சபையார் இந்த ஏற்பாடுகளை அரசன் திட்டம் வகுத்து அளித்த ஓர் உத்தரவுப்படியே அரசனுடைய அதிகாரி களுள் ஒருவன் முன்னிலையில் செய்தனராம். அதே தென்னார்க்காடு ஜில்லாவில் இப்பொழுது திருபுவனி என்று வழங்கப்படும் திருபுவன மஹாதேவி சதூர்வேதி மங்கலம் என்னும் ஊரிலும் இதேபோலச் சில தானங்களைச் செய்து வேறு ஒரு பாடசாலையும், அதைச் சேர்ந்த ஓர் அறச்சாலையும் (ஹாஸ்டல்) இராஜாதிராஜன் காலத்தில் ஏற்படுத்தப் பட்ட செய்தி தெரிய வருகிறது. (1919 ஆண்டு, 176 நெ. சாசனம்).

செங்கற்பட்டு ஜில்லாவில் காஞ்சீபுரத்துக்குப் பக்கத்தில் உள்ள திருமுக்குடல் என்னும் இடத்திலிருந்து வீர ராஜேந்திரன் காலத்துச் சாசனம் ஒன்று கிடைக்கிறது. கி.பி. 1067-ஆம் கொண்ட அக்கல் வெட்டு அவ்வூரில் எழுந்தருளியிருக்கும் மஹாவிஷ்ணுவின் ஆலயத் துக்கு வருஷந்தோறும் ஆகும் செலவுகளையும் அவற்றை நடத்துவதற் காகக் கிடைக்கும் வருமானங்களையும் விவரித்துக் கூறுகிறது. வீர சோழன் என்ற பெயரால் ஆதுலசால் (வைத்தியசாலை)யும் மருத்துவம் கற்பிக்கும் கலாசாலையும் கோயிலால் நிர்வகிக்கப் பெற்றுவந்த செய்தி அதிலிருந்து தெரிகிறது. (எபி. இந்திகா, இருபத்தோராம் வால்பூம்).

நக்கூர் நற்பார்ப்பார் போன்ற தனி மனிதர்களுக்கு அளிக்கப் பெற்ற தானங்களும் தானம் செய்தவர்கள் தங்களுக்குப் புண்ணியம் கிட்டவேண்டுமென்று கருதிச் செய்தனவே ஆகும்.



மைசூர் சமஸ்தானத்தில் உள்ள மாவட்டம் என்னும் ஊரில் ஒரு ஸ்தம்பத்தில் பொறிக்கப்பட்டுள்ள பிராகிருத சாசனம் (எபி. கர் நாடிகா, ஏழாம் வால்பூம், ஷிகர்பூர் 263) வைஜயந்திரருந்து அரசு செலுத்திய ஹாரிதிபுத்ர விஷ்ணுகட சூடுகுலானந்த சாதகர்ணி என்பவன் ஒரு பிராமணனுக்குச் சில கிராமங்களை அளித்த செய்தியைத் தெரிவிக்கிறது. அதே ஸ்தம்பத்தில் அந்தச் சாசனத்தின் கீழே உள்ள மற்றொரு பிராகிருதக் கல்வெட்டு வைஜயந்தியைத் தலைநகராகக் கொண்டு ஆண்ட கதம்பமன்னன் சிவ(ஸ்கந்த) வர்மன் என்பான் அதே கிராமங்களை வேறு சிலவற்றோடு முன்னால் பெற்றிருந்தோர்களின் வழியினருகே திரும்பவும் அளித்த செய்தியைக் கூறுகிறது. (ஹி. 264 நெ.) இந்தச் சாசனம் கதம்ப வமிசத்து மன்னர்களின் ஆட்சிக்காலம் எப்போது நிறுவப்பெற்றதென்பதை நிர்ணயிப்பதற்கு ஒருவகையில் உதவுவதாக இருக்கிறது.

இது போலவே சங்க காலத்தில் இருந்ததாகக் கூறப்படும் பாண்டியன் பல்யாகசாலை முதலுருமிப் பெருவழுதி என்பான் அளித்த ஒரு கிராமத்தை நடுவில் பாண்டிய நாட்டைப் பிடித்து ஆண்டு வந்த களப் பிரர்கள் கைப்பற்றிக் கொண்டு விட்டானாம்; பின்னால் மதுரையிலே பாண்டிய அரசு திரும்பவும் நிலைபெற்றபிறகு, தானம்பெற்ற வமிசத்தில் வந்த ஒருவனுக்கு ஜடிலவர்மன் பரார்தகன் என்னும் பாண்டிய மன்னன் இந்தக் கிராமத்தைத் திரும்பவும் அளித்தான் என்ற செய்தியைத் தெரிவிக்கின்றன வேள்விக்குடிச் செப்பேடுகள். (எபி. இந்திகா, பதினேழாம் வால்பூம்.)

மேலைக் கடற்கரையோரத்தில் முற்காலத்தில் யூத வகுப்பினர் குடியேறி இருந்தனர் என்பதையும், அவர்களுக்குச் சில உரிமைகளையும், கிராமங்களையும் பாஸ்கர ரவி வர்மன் என்னும் அரசன் அளித்ததையும் கொச்சிச் செப்பேடுகளால் நாம் அறிகிறோம். (ஹி. மூன்றாம் வால்பூம்) அதேபோல அந் நாட்டிலேயே கிறிஸ்துவர்கள் குடியேறியதையும் அவர்களுக்குக் கொடுக்கப்பட்ட உரிமைகளையும் ஸ்தானு ரவி, வீரராகவச் சக்கரவர்த்தி ஆகிய மலைநாட்டு அரசர்களுடைய கோட்டயம், திருவள்ளாச் செப்பேடுகள் தெரிவிக்கின்றன. (திருவா. ஆர்க்கி. வரீஸ், இரண்டாம் வால்பூம்).

நாட்டு மக்களில் பொதுவாக அடங்கியிருந்த பல வகைப் பிரிவினரும் இனத்தவரும் தர்ம சாஸ்திரங்களில் கண்டுள்ளபடியே அவர் அவர் தர்மத்தைப் பின்பற்றித் தொழிலையும் நடத்தி வந்தனர். இதை வலியுறுத்தித் தெரிவிக்கும் சாசனங்களும் அங்கங்கே கிடைக்கின்றன. திருச்சிராப்பள்ளி ஜில்லா உய்யக்கொண்டான் திருமலையில் கிடைக்கும்

சோழர் காலத்துச் சாசனம் ஒன்று (1908-ஆம் ஆண்டு 479 நெ.) இரதகாரர் வகுப்பைச் சேர்ந்த அனுலோமஜாதியினர் தங்கள் தொழில் களைச் சாஸ்திரங்களில் கண்டுள்ளபடியே எவ்விதம் நடத்தவேண்டுமென்பதை இராஜாசரய சதுர்வேதி மங்கலத்துப் பட்டர்கள் கூடி விவஸ்தை செய்த விவரத்தை எடுத்துக் கூறுகிறது.

அதேபோல, படைவீட்டுப் பிராமணர்கள் தங்கள் பெண்களைக் கன்னியாதானம் செய்து கொடுக்கவேண்டுமேயன்றிப் பெண்களுக்காகப் பணம் பெறக்கூடாது என்றும், அப்படிப் பணம் கொடுக்கும் மாப்பிள்ளைகளும் பணத்தைப் பெறும் பெண்களின் தகப்பன்மார்களும் ஜாதிப் பிரஷ்டம் செய்யப்படுவதுடன் அரசரால் தண்டிக்கவும் படுவார்கள் என்றும் தங்களுக்குள்ளே முடிவு செய்து தீர்மானித்துக் கொண்டதை விரிஞ்சிபுரத்துச் சாசனம் ஒன்று கூறுகிறது. (தெ. இ. சாசனங்கள், முதல் வால்யும், பக்கம் 82).

சமூக வாழ்க்கையிலே நாட்டு மக்களின் ஒவ்வொரு பிரிவைச் சேர்ந்தவர்களும் எந்த நிலைமையில் இருந்தனர், அவர்களுக்கு ஏற்பட்ட உரிமைகள் என்ன, என்பன போன்ற விஷயங்களும் சில சாசனங்களில் விவரிக்கப் பட்டிருப்பதைக் காணலாம். பெரும்பாலும் எல்லாப் பிரிவினருமே தாங்கள் அப்போது வகித்துவந்த நிலைமையைக் காட்டிலும் உயர்ந்தவர்கள், ஆகவே அந்த உயர்நிலைக்கான ஏற்றங்களை அனுபவிக்கும் உரிமை பெற்றவர் என்று கூறிவந்தனர். அதற்காக அவர்கள் பல சமயங்களில் தங்கள் பூர்வோத்தரத்தைப்பற்றிக் கட்டுக் கதைகள் புனையவும் செய்தனர். திருச்சிராப்பள்ளி ஜில்லா ஊற்றத்தூரில் மூன்றாம் குலோத்துங்க சோழனுடைய ஆட்சியின் நாற்பதாம் ஆண்டு கொண்டதாகக் கிடைக்கும் சாசனம் (1912-ம் ஆண்டு 409 நெ.) இடங்கை வகுப்பார் தங்களைப்பற்றி அந்நாளில் என்ன வரலாற்றை உரைத்து வந்தனர் என்பதைக் கூறுகிறது. அவர்கள் கச்யப முனிவரின் யாகத்தை ஸம்ரக்ஷிப்பதற்காக அக்ரிகுண்டத்திலிருந்து தோன்றியவர்களாம், அவர்கள் அரிந்தம சக்கரவர்த்தியின் நாளில் சோழ நாட்டுக்கு வந்து தங்கினார்களாம். அந்தச் சக்கரவர்த்தி அந்தர்வேதி (கங்கை-யமுனைப் பிரதேசம்) பூமியிலிருந்து அழைத்து வந்த பிராமணர்களோடு அவர்களுடைய பணியாளர்களாக வந்து சேர்ந்தவர்களாம், இடங்கைச் சாதியினர். (இப்போது திருச்சிராப்பள்ளி ஜில்லாவில் உள்ள) ஐந்து கிராமங்களில் அவர்களுக்கு நிலம் அளிக்கப்பட்டதாம். தங்கள் பூர்வோத்தரத்தைப்பற்றிய விவரங்கள் அவர்களுக்கு நீண்ட காலம் தெரியாமல் மறந்துபோய் இருந்ததாம். அப்பால் சுருதிமான்களுடைய உதவியால் அவர்கள் அதை மறுபடியும் அறிந்தனாம்.

கொங்கு நாட்டுச் சோழன் ஒருவன் வெங்கால நாடு, தென் கொங்கு ஆகிய பிரதேசங்களில் வாழும் கண்மாளர்களுக்கு வழங்கிய உரிமையைத் தெரிவிக்கும் சாசனங்கள் திருச்சிராப்பள்ளி ஜில்லா கருவூரிலிருந்தும் கோயம்புத்தூர் ஜில்லா பேரூரிலிருந்தும் கிடைத்துள்ளன. அவர்களுடைய குடும்பங்களில் நடக்கும் நன்மைதின்மைகளுக்கு இரட்டைச் சங்கு ஊதுவது, மேளம் கொட்டுவது, வெளியில் செல்லும்போது காலில் செருப்பு அணிந்துகொள்வது, வீட்டுச் சுவர்களுக்குச் சுண்ணாம்புச் சாந்து பூசுவது, இன்னும் வீட்டு வாசல்களில் தோரணம் அமைப்பது போன்ற உரிமைகள் அவை. இவற்றால் அந் நாளில் அவர்கள் நடத்திவந்த வாழ்க்கைமுறை ஓர் அளவு தெரியவரும்.

கம்மாள் (விசுவகர்ம்) வகுப்பைச் சேர்ந்த ஜந்து பிரிவினர்களுக்குள்ளும் 'உடன் கூட்டம் வேண்டாம்' என்று தெரிவிப்பனவாகத் திருநெல்வேலி ஜில்லா பிரம்மதேசம், அம்பாசமுத்திரம் முதலிய இடங்களிலிருந்து கிடைத்த மதுரைநாயக்க வமிசத்து அரசன் முதலாம் முத்து வீரப்பநாயக்கருடைய சாசனங்களும் இந்த வகையைச் சேர்ந்தனவே. (1936-ஆம் ஆண்டு 309, 378 நெ.)

பிராமணர்களைப் போலவே பட்டு நூற்காரர்களும் (ஸௌராஷ்டிரர்கள்) (வருஷந்தோறும் பூணூல் போட்டுக்கொள்ளும் ஆவணி அவிட்டம் என்னும்) உபாகர்மத்தைச் செய்துகொள்ளலாம் என்று புகழ் பெற்ற மதுரை ராணி மங்கம்மாள் கி. பி. 1705-ல் உத்தரவிட்டதாகக் கூறும் ஒலைச் சாசனமும், கலியாண காலங்களில் சேணியர்கள் யார் யாருக்கு முதலில் வெற்றிலைபாக்குக் கொடுக்கவேண்டும் என்பதை நிச்சயம் செய்து தெரிவிக்கும் பட்டிச்சரத்துச் சாசனமும் இப் பிரிவைச் சேர்ந்தவைகளேயாகும்.

கோயிலில் சந்தி விளக்கோ, நுந்தா விளக்கோ எரிப்பதற்காக நிவந்தம் ஏற்படுத்தியதைத் தெரிவிப்பனவாகக் காணும் சாசனங்கள் சிலவற்றுள் அத்தகைய நிவந்தங்களை அவர்கள் தாங்கள் செய்த பாபத்துக்குக் கழுவாயாக ஏற்படுத்தியதாகக் காணப்பெறுகிறது. அவ்விதம் அவர்கள் செய்தது சிலசமயங்களில் தங்கள் மனச்சாட்சியின் பயனாகவும் வேறு சில சமயங்களில் நியாயத்தார் வழங்கிய தீர்ப்பையொட்டியும் ஆகும்.

வடஆர்க்காடு ஜில்லா சீயமங்கலத்திலிருந்து கிடைக்கும் சாசனம் ஒன்று (தெ. இ. சாசனங்கள், ஏழாம் வால்யூம், 68 நெ.) பின் வருவதைத் தெரிவிக்கிறது: ஒருவன் அம்பெய்து தவறுதலாகத் தன் ஊரைச் சேர்ந்த வேறு ஒருவனைக் கொன்றுவிட்டான், அதன்மீது நாட்டவரும்

சம்பவராயரும் கூடி ஆலோசித்து, தற்செயலான தவறுதலால் நேர்ந்த விபத்துக்காக அவன் உயிரை வாங்கவேண்டியதில்லை யென்றும் துணுண்டார் கோயிலிலே அவன் ஒரு விளக்கு எரித்துத் தன் பாவத் தைக் கழுவிக்கொள்ளலாம் என்றும் முடிவு கூறினர். அவனும் அதன் படியே துணுண்டார் கோயிலில் விளக்கு எரிப்பதற்காகப் பதிலுறு பசுக்களை அளித்தானாம்.

அதே ஜில்லா திருவோத்தூரிலிருந்து கிடைக்கும் மற்றொரு கல் வெட்டு (பெடி. 85 நெ) ஒருவன் வேட்டைக்குப் போன இடத்தில் எய்த அம்பு குறிதவறி வேறொருவனை அடித்துவிட்டதாகவும் அதன் மீது பன்னாட்டார் திரண்டு கோயிலில் விளக்கு எரிக்க அவன் பதி னுறு பசுக்களை அளிக்கவேண்டும் என முடிவு செய்தனர் என்பதையும் கூறுகிறது.

மானிடர்களை அடிமைகளாக விற்ற செய்தியைத் தெரிவிக்கும் சாசனங்களும் கிடைக்கின்றன. பெரும்பாலும் அத்தகைய விற்பனை கள் கோயில்களுக்கோ மடங்களுக்கோ செய்யப்பட்டனவாக இருக் கும். தனிமனிதர்களுக்கு இவ்விதம் விற்பனை செய்யப்பட்டவர் களைப்பற்றிய சாதனங்கள் கல்லில் பொறிக்கப்பட்டிருக்காவே. தஞ்சா வூர் ஜில்லாவிலிருந்து கிடைத்த சாசனம் ஒன்றிலிருந்து (1925-ஆம் ஆண்டு 218 நெ.) சோழர்களுடைய ஆட்சிக்காலத்தில் இரண்டு பெண் கள் தங்களை யண்டியவர்களையும் உறவினர்களையும் சேர்த்து கொண்டு தங்களை ஒரு கோயிலுக்கு விற்றுக்கொண்ட செய்தி தெரியவருகிறது. முதற்குலோத்துங்க சோழனுடைய காலத்தில், கி.பி. 1088-ல், பொறிக் கப்பட்ட சாசனம் ஒன்று (1921-ஆம் ஆண்டு 230 நெ.) பின் வருவ தைக் கூறுகிறது: காளஹஸ்தி கோயிலுக்குச் சொந்தமான தேவாடி யார் சிலர் தவறுதலாக அரண்மனை ஊழியத்தில் சேர்க்கப்பட்டு விட்ட னாராம். அதையறிந்த மன்னன் அவர்களைத் திரும்பவும் கோயிலுக்கே அனுப்பிவிட்டான். அப்போது அரண்மனை ஊழியர்கள் என்பதற்காக அவர்களுக்கு இட்டிருந்த அரசாங்க முத்திரையை நீக்கிக் கோயில் தேவாடியார் என்பதற்காகச் சூல முத்திரை இடப்பெற்றதாம். கொடிய பஞ்சம் நேர்ந்த காலங்களில் வாழ வழி இல்லாதவர்கள் தங்கள் உயி ரையும் தங்கள் சந்ததியாரையும் காப்பாற்றிக்கொள்ள அடிமைகளாக விற்றுக்கொண்டு உயிர்தப்பிய விவாங்களும் சாசனங்களிலிருந்து தெரியவருகின்றன.

தனிப்பட்ட மக்களின் சொத்துரிமையைப் பற்றிய சாசனங்களும் கிடைத்துள்ளன.

தஞ்சாவூர் ஜில்லா உடையாளூரிலிருந்து கிடைத்த சாசனம் ஒன்று (1927-ஆம் ஆண்டு 309 நெ.) மூன்றாம் இராஜ ராஜ சோழனுடைய ஆட்சியின் ஐந்தாம் ஆண்டில் நிலவிய சேஷாபத்திலே ஊரில் உள்ளோருடைய நிலங்களின் மூலபத்திரங்கள் அழிந்துபோயினமையால் நான்காம் ஆண்டளவில் உள்ள அனுபோக முறைப்படி நிர்ணயித்துப் புதிய பத்திரங்கள் வழங்க வேண்டி வந்ததென்று கூறுகிறது. அதே ஜில்லா தலைச்சங்காட்டிலிருந்து மூன்றாம் இராஜராஜனுடைய ஆட்சியின் பத்தொன்பதாம் ஆண்டு கொண்டதாகக் கிடைக்கும் மற்றொரு கல்வெட்டிலே, (1925-ஆம் ஆண்டு, 213 நெ. சாசனம்), அம்மன்னனுடைய ஆட்சியின் ஐந்தாம் ஆண்டிலே நாட்டில் நடந்த துரிதங்களால் பழைய கணக்குகள் அழிந்துபோயினமையால், அனுபோகப் பற்றொழுகையொட்டி ஆதாரச் சீட்டுகளைப் புதுப்பிக்க வேண்டியிருந்தது என்னும் செய்தி காணப்படுகிறது. இவற்றால் மூன்றாம் இராஜ ராஜ சோழனுடைய ஆட்சியின் ஐந்தாம் ஆண்டில் (கி. பி. 1220-21) நாட்டிலே மக்களின் உயிருக்கும் பொருளுக்கும் பெருத்த சேதத்தை விளைவித்த கலகம் நடந்த செய்தி தெளிவாகும்.

தென்னாக்காடு ஜில்லா கீழூர் வீரட்டானேசுவரர் கோயிலிலிருந்து கிடைக்கும் கல்வெட்டு ஒன்றிலிருந்து (இந்தத் தொகுதியில் 42 நெ.) மூன்றாம் குலோத்துங்க சோழனுடைய ஆட்சியின் இருபத்து நான்காம் ஆண்டில் திருக்கோவலூரில் உள்ள சிவன் கோயிலுக்கும் விஷ்ணு ஆலயத்துக்கும் நிலப்பரிவர்த்தனை நடந்த விவரம் தெரியவருகிறது. இந்தப் பரிவர்த்தனையைச் சிவன் கோயிலுக்காகச் சண்டேசுவரப் பெருமான் பெயராலும், விஷ்ணு ஆலயத்துக்காகச் சேனாபதி ஆழ்வார் பெயராலும் செய்து கொண்டார்கள். அந்நாளிலே சிவன் கோயில் நிர்வாகம் சண்டேசுவரர் பெயராலும், அதேபோல விஷ்ணு ஆலயத்தின் நிர்வாகம் சேனாபதியாழ்வார் என்னும் விஷ்வக்சேனர் பெயராலும் நடந்து வந்தன வென்ற விவரம் அகிலிருந்து வெளியாகிறது.

வட ஆர்க்காடு ஜில்லா திருமால்புரம் என்னும் ஊரில் மதுராந்தக உத்தம சோழனுடைய ஆட்சியின் பதினான்காம் ஆண்டு கொண்ட சாசனம் ஒன்று கிடைக்கிறது. (தெ. இ. சாசனங்கள், மூன்றாம் வால்யூம், 142 நெ.) அது ஒரு விஷயத்தைப்பற்றிய ஒரு தாற்றாண்டுக் கால விவரத்தைக் கூறுகிறது. சிற்றியாற்றூர் என்னும் கிராமம் தொண்டைமாறாற்றூர்த் துஞ்சின (முதலாம் ஆதித்திய) உடையாருடைய ஆட்சியின் இருபத்தோராம் ஆண்டில் புதுப்பாக்கத்துச் சபையாருக்குத் தேவதானப் பிரமதேயமாக அளிக்கப்பட்டது, அடுத்த

ஆண்டிலேயே அதற்கான சாசனம் எழுதப்பட்டிருந்தும், உடனே கிராமத்தைத் தேவதானப் பிரமதேயமாகக் கணக்கில் எழுதவில்லை. இந்தக்குறை மதுரையும் ஈழமுங்கொண்ட பரகேசரிவர்ம (முதற் பார்த்தக)னுடைய ஆட்சியின் நாலாம் ஆண்டில் நிவர்த்திக்கப் பெற்று வியிலிடப் பெற்றது. அதுமுதல் புதுப்பாக்கத்துச் சபையார் தாங்கள் செலுத்த வேண்டிய பொருளைத் திருமால்பேற்று மகாதேவர் கோயிலுக்குக் கிராமமாக அளித்து வந்தனர். முதற் பார்த்தகனுடைய முப்பத்தாரும் ஆண்டில் புதிதாக அளித்த சிலவற்றைக் கொண்டு புதுப்பாக்கம் சபையார் செலுத்தவேண்டிய பொன் அதிகமாக்கப்பட்டது. அதிகமாகச் செலுத்தவேண்டியதைச் சபையார் சரியாகச் செலுத்தவில்லை. அதன் பிறகு கோயில் அதிகாரிகள் மதுரார்தக உத்தம சோழனிடம் முறையிட்டுக் கொண்டார்கள். அரசனும் காஞ்சிபுரத்தில் தங்கியிருந்த நாளில் விசாரணை செய்து சபையாருக்குத் தண்டம் விதித்து, அவர்கள் முறைப்படி செலுத்தவேண்டுமென்று உத்தரவிட்டான்.

ஸ்ரீரங்கத்திலிருந்த முதற் குலோத்துங்க சோழனுடைய ஆட்சியின் பதினேராம் ஆண்டு கொண்டதாக ஒரு சாசனம் (1937-ஆம் ஆண்டு 31 நெ.) கிடைத்துள்ளது. இராஜ மஹேந்திர சதுர்வேதி மங்கலத்துச் சபையார் அவ்வூர் மும்முடிசோழ விண்ணகர் ஆழ்வார் கோயிலுக்குச் சொந்தமான நிலங்களை எழுபது கழஞ்சு பொன் கொண்டு இறையிலி ஆக்கிய செய்தியைக் கூறும் அக்கல்வெட்டு ரசமான விஷயங்கள் சிலவற்றையும் தெரிவிக்கிறது. “மன்னனுடைய ஆட்சியின் இரண்டாம் ஆண்டில் வலங்கை இடங்கைச் சமூகத்தார் களுக்குள் ஒரு பெருங்கலகம் நடந்தது. அதிலே கிராமம் சுட்டு எரிக் கப் பட்டது; கோயில்கள், புண்ணிய ஸ்தலங்கள் பாழாயின; கோயில் விக்கிரகங்களும் கோயில் பண்டாரமும் கள்வர்களால் சூரையாடப் பட்டன. அவர்களுடைய கொள்ளைக்குத் தப்பிய பொருள்களையும் கோயிலிலே பாதுகாக்க முடியவில்லை. கிராமத்தைப் புனர் நிர்மாணம் செய்து குடியேற்றிக் கோயில்களை ஜீர்னோத்தாரணம் செய்து, பிராகாரங்களுக்குப் புதிய மதில்களை எழுப்பி விக்கிரகங்களைப் புதிதாய்ப் பிரதிஷ்டை செய்யவேண்டினேர்ந்தது. அதற்காகச் சபையினர் கோயில் பண்டாரத்திலிருந்து இராஜேந்திர சோழன் மாடைக்கு அரைமாற்றுக் குறைவாக உள்ள ஐம்பது கழஞ்சு பொன்னைக் கடனாகப் பெற்றனர். அதன் வட்டி இருபத்தைந்து கழஞ்சு ஆகியது. மொத்தம் கூடுதலான பொன் எழுபத்தைந்து கழஞ்சில் மூன்றாம் ஆண்டில் கோயில் ஜீர்னோத்தாரணத்துக்கும் புதிய பிரதிஷ்டைக்குமாக ஐந்து கழஞ்சு செலவாகியது. மீதமுள்ள எழுபது கழஞ்சு பொன்னைக்கொண்டு

கோயிலின் நித்த நிவந்தங்களுக்காகச் சில நிலங்களை வாங்கி இறையிலி யாக்கிவிடச் சபையார் முன் வந்தார்கள்.” இதிலிருந்து நாட்டின் அமைதியான வாழ்க்கைக்குப் பங்கம் நேரிட்ட காலங்களில் கோயில் பண்டாரத்தார் பணத்தை நற்காரியங்களுக்காகக் கடன் கொடுத்து உதவிவந்தார்கள் என்பதும் தெரியவருகிறது.

கல்லிலே இந்தக் கல்வெட்டின் பக்கத்தில், “ இந்தக் கல்வெட்டு இராஜமஹேந்திர சதுர்வேதி மங்கலத்துக்கு உரியது ” என்றும் குறிக்கப்பட்டுள்ளது. அவ்வூர் சுமார் நார்பது மைல்களுக்கு அப்பால் உள்ள ஒரு கிராமம் ஆகும். இதைக் கவனித்தால் சில குறிப்பிட்ட சந்தர்ப்பங்களில் ஓர் ஊருக்கு உரிய சாசனம் வேறு ஓர் ஊரில் பொறிக்கப்பட்டுக் காணும் பழக்கமும் இருந்ததென்பது தெரியவரும்.

## 8. போலிச் சாசனங்கள்

சாசனங்களெல்லாம் சரித்திர ஆராய்ச்சிக்கு உபயோகப்பட வேண்டும் என்னும் நோக்கத்துடன் எழுதப்பட்டன அல்லவென்பதையும் அநேகமாக அவை நிலங்கள் முதலியவற்றின் உரிமைச் சீட்டுக்கள் ஆகும் என்பதையும் நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். அவ்வூரி மைகளை அனுபவிப்பதற்கு ஆதாரங்களான அச் சீட்டுக்கள் எவ்வளவு அவசியமென்பதைச் சொல்லவேண்டியதில்லை. இவ்வாறு அவை பெரி தும் உபயோகமாயிருந்ததே ஓர் அபாயத்திற்கும் காரணமாகிவிட்டது. தங்களுக்கு உரிமையில்லாத அனுபாகங்களின் பாத்தியதையை நிலை நிறுத்திக் கொள்ளவும், உண்மையாகவே உரிமையுள்ளவற்றின் ஆதாரச் சீட்டுகள் கைசார்ந்துபோன விடத்தில் அவற்றிற்குப் பதிலாகவும் புதிய சீட்டுக்கள் சிருஷ்டிக்கப்பட்டு வந்தன. அதனால் கல்லிலும் செம் பிலும் பொறிக்கப்பட்டு அழிவில்லாமலிருப்பதனாலேயே சாசனங்கள் யாவும் நம்பிக்கைக்கு உரிய ஆதாரங்களெனக் கொள்வது அபாயம். இலக்கியங்களிற் புகுந்து உண்மையோல் நிலவிவரும் இடைச் செருகு களைப்போல, சாசனங்களிலும் போலிகள் உண்டு. போலிச் சாசனங்கள் வழக்கிற்கு வந்ததற்கு இதுவே முக்கிய காரணமாகும்.

எவ்வளவுக்கெவ்வளவு ஒரு நாடு பல்வேறு காலங்களில், பல்வேறு வமிசங்களின் ஆளுகையின்கீழ் வந்து அதன் பயனாக இராஜ்ய, சமூக நிலைமையில் வேறுபாடுகளைப் பெறுகிறதோ, அவ்வளவுக் கவ்வளவு அந்த நாட்டில் போலிச் சாசனங்கள் அதிகமாக ஏற்பட இடமுண்டா கிறது. ஒரு நாட்டை வேற்றரசன் பிடித்துக்கொண்டால், அச்சமயத் தில் அந்த நாட்டிலிருந்த இறையிலி யாவற்றையும் தவிர்த்துவிடுவான் ;

மறுபடியும் தானே கொடுப்பதுபோலச் சிலவற்றைக் கொடுப்பான். அக் காலத்தில் தானத்தை மறுபடியும் பெற விரும்புவோர் தங்களுக்கு உள்ள பழைய உரிமைகளை ஆதாரங்கள் மூலம் நிலைநிறுத்தவேண்டும். புதிய அரசன் ஒவ்வொன்றையும் கவனித்து, தான் இஷ்டப்பட்டதை மட்டும் புதுப்பித்துக் கொடுப்பான்.

இவ்விதம் பண்டைய தானங்கள் நடுவிலே வேற்றரசர்கள் நாட்டைப் பிடித்துக்கொண்ட காலத்தில் நிறுத்தப்பட்டதையும், பிற்காலத்திற் பழைய பரம்பரையினர் மீண்டும் அரசைப்பெற்ற சமயம் புதுப்பிக்கப்பட்டதையும் பற்றிய குறிப்புகள் நம் நாட்டுச் சரித்திரத்தில் மிகுதியாக உள்ளன.

உதாரணமாக, வேள்விக்குடிச் செப்பேடுகளைக் கூறலாம். பாண்டியன் பல்யாகசாலை முதுகுடுமிப் பெருவழுதி என்பவன் வேள்விக்குடி என்னும் கிராமத்தைக் கேள்வி அந்தணுளர்க்குத் தானம் செய்திருந்தான். பாண்டிய நாட்டைக் களப்பிரர்கள் கைக்கொண்ட காலத்தில், அவர்கள் அந்தத் தானத்தைத் தவிர்த்துக் கட்டிக்கொண்டுவிட்டார்கள். பின்னர், பாண்டியர்கள் கிளம்பி நாட்டைக் கைக்கொண்டு வெகுகாலம் சென்ற பிறகு, முதலில் தானம் பெற்றவர்களுடைய சந்ததியார், பரந்தகன் நெடுஞ்சடையன் என்னும் அரசனிடம் தங்கள் குறையை முறையிட்டுத் தங்களுக்குள்ள பழைய உரிமைகளை ஆதாரங்களுடன் நிலைநிறுத்தினர். அரசன் அதன்பேரில் வேள்விக்குடி என்னும் பழம்பதியை மீண்டும் அவர்களுக்கு வழங்கினான் என்பதை அச் சாசனம் கூறுகின்றது. இவ்விதம் அந்தச் சாசனம் அந்தக் கிராமத்தின் வரலாற்றை ஐந்தாறு நூற்றாண்டுகளுக்குக் கூறுகிறது.

ராஷ்டிரகூட மன்னனான மூன்றாம் இந்திரன், தான் பட்டத்திற்கு வந்ததும், துலாபாரம் செய்ததுதவிரப் பண்டைய அரசர்கள் அபகரித்துக்கொண்ட நானூறு கிராமங்களை மறுபடியும் தானம் வழங்கினான் என்பதை அவனுடைய கி. பி. 915-ஆம் வருஷத்திய நவசாரிகைச் செப்பேடுகள் தெரிவிக்கின்றன. (ராயல் ஏஷ்யாடிக் ஸொஸைட்டி பம்பாய்க் கிளை பத்திரிகை, பதினெட்டாம் வால்யூம்). அதேபோலச் சாளுக்கிய அரசனான முதலாம் விக்கிரமாதித்தன், தன் தந்தையான இரண்டாம் புஷிகேசியை வென்று நாட்டைக் கைக்கொண்ட காலத்து, முடியுடைவேந்தர் மூவர் நிறுத்திய தானங்களைத் தெய்வங்களுக்கும் பிராமணர்களுக்கும் தான் புதுப்பித்ததாகக் கூறிக்கொள்ளுகிறான்.

பண்டைக்காலத்து அரசர்கள் தாங்கள் கொடுத்த தானம் ஆசந் திரார்க்கம் அனுப்பிக்கப்படவேண்டும் என்பதையே விரும்பினார்கள் ;



ஆகவே தங்களுக்குப் பின் வருபவர்கள் அந் தானங்களை மதித்து அவற்றின் உரிமைகளை அளிக்க வேண்டுமென அவர்களைக் கேட்டுக் கொண்டனர். இவ்விதமான வேண்டுகோள் பொதுவாக எல்லாச் சாசனங்களிலும் காணப்படும். அச் சாசனங்கள் எக்காரணத்தாலோ அழிந்துவிடின், அவ்வுரிமையாளர்கள் போலியாக அவ்வுரிமைகளை எழுதிவைத்துக்கொள்ளுகிறார்கள்.

இவ்விதம் போலிச்சாசனங்களை உற்பத்தி செய்யும் வழக்கம் தொன்றுதொட்டதாகும். கன்னேசியை ஆண்ட ஹர்ஷவர்த்தனன் காலத்தைச் சார்ந்த (கி. பி. 631-2) மதுவனச் செப்பேடுகளால் சோமகுண்டிகை என்னும் கிராமத்தைக் கூட்சாஸனத்தின் ஆதரவால் ஒரு பிராமணன் அனுபவித்து வந்த செய்தியும், மன்னன் அதை நிவர்த்தித்து அந்தக் கிராமத்தை வேறு சிலருக்குத் தானம் கொடுத்த செய்தியும் தெரியவருகின்றன. அதேபோலத் தாராசண்டி என்னும் இடத்திலுள்ள கல்வெட்டு ஒன்றால், கன்னேசி அரசனான விஜயசந்திரனின் வேலைக்காரர்களுள் ஒருவனிடமிருந்து சில பிராமணர்கள் கூடாம் பரத்தைப் பெற்று, அதைக் கொண்டு சில கிராமங்களை அனுபவித்து வந்தார்கள் என்பதும், அப்போலிச் சாசனத்தை ஏற்றுக் கொள்ளாது அக்கிராமங்களினின்றும் கடமைகளைப் பெறலாம் என்று மகாநாயகன் பிரதாபன் என்பவன் தனக்குப் பின் வருபவர்களுக்கு அறிவித்தான் என்பதும் தெரிய வருகின்றன.

தரும சாஸ்திரங்களிலே இவ் விஷயத்தைப்பற்றிய குறிப்புகள் காணப்படுவது இவ்வழக்கம் இருந்துவந்ததை வற்புறுத்துகிறது. போலிச் சாசனங்களை உற்பத்தி செய்பவர்களுக்குச் சாஸ்திரங்களில் விதிக்கப்பட்டிருக்கும் தண்டனை சிரச்சேதமேயாகும். அந்தாற்களில் சாசனங்களை ஆராய்வதற்கு லேக்ய பரீக்ஷை எனப்படும் விரிவான விதிகள் கூறப்பட்டுள்ளன. அவ்விதிகளின்படி நோக்கினால், இப் பொழுது கிடைத்திருக்கும் சாசனங்களுட் பெரும்பாலான அவற்றிற்கு விரோதமாகவே காணப்படும். சாசனங்களை எழுதுவதற்குக் கடைப் பிடித்த சம்பிரதாயங்கள் நாட்டுக்கு நாடு, காலத்துக்குக் காலம் வேறு பட்டமையே இதற்குக் காரணம் ஆகும்.

இங்ஙனம் போலியாகவுள்ள சாசனங்களைத் தயார்செய்பவர்கள், மூல சாசனத்தில் கண்டிருந்த செய்திகளை அரைகுறையாக அறிந்தோ, முழுமையும் அறியாமலோ, தங்கள் மனம் போல் எழுதிவிடுகிறார்கள். இதனால் இவ்வுண்மையை அறியாத சரித்திர ஆராய்ச்சியாளர்கள் சிலர் அவற்றின் கண்ட வமிசாவளி முதலியவற்றின் மாறுபாடுகளை உணர இயலாது மிழைபடக் கூற ஏதுவாகிறது.

இவ்விதம் கிடைக்கும் போலிச் சாசனங்கள் மிகவும் குறைவானவே ; ஆயினும் அவை யாவும் செம்பிலேயே உள்ளன. கல்வெட்டுக்களில் கிடையா. ஏனெனில், செப்பேடுகளில் பொறிப்பதை இரகசியமாக முடித்துவிடலாம். கல்வெட்டுக்களோ கோயில் முதலிய பொது இடங்களில் பொறிக்கப்படவேண்டும். அன்றி, அவற்றைப் பொறிப்பதற்குக் கிராமஉத்தியோகஸ்தர்கள் முதலிய பலரது அனுமதியைப் பெறவேண்டியதால் பகிரங்கமாகப் போய்விடும். இதனாலேதான் போலிச் சாசனங்கள் கற்களில் காணப்படவில்லை.

இராமநாதபுரம் ஜில்லா திருப்புத்தூர்ச் சிவன் கோயில் சுவரில் பொறிக்கப்பட்டுள்ள சாசனம் ஒன்று (1908-ஆம் ஆண்டு 127 நெ.) போலிச்சாசனம் பற்றிய சில விவரங்களைக் கூறுகிறது. சகாப்தம் 1309, அதாவது கி.பி. 1387-ஆம் ஆண்டில், அவ்வூர் மூலபரிஷத் மஹா சபையார் ஊரின் கணக்குக் காணியை விற்றுக்கொடுத்த செய்தியைத் தெரிவிக்கும் அக்கல்வெட்டு அவ்விதம் விற்கவேண்டிய சந்தர்ப்பம் எப்படி நேர்ந்தது என்பதைப் பின்வருமாறு கூறுகிறது. அவ்வூரில் அதற்கு முன் இருந்த கணக்கன் அந்த ஊரில் தனக்கு இல்லாத சில உரிமைகளைக் கொண்டாட விரும்பி, ஒரு தட்டானுடன் சதியாலோசனை செய்து சபையார் தனக்கு அவற்றை அளித்ததாகக் கல்தச்சன் ஒரு வனைக் கொண்டு கோயில் சுவரில் இரகசியமாகக் கல் வெட்டச் செய்தான். செய்தி வெளியாகிவிட்டது. கணக்கன் ஊரை விட்டு ஓடி விட்டான். தட்டானும் கல் தச்சனும் 'கண்மாளர்' வசம் ஒப்புவிக்கப்பட்டனர். கண்மாளர்கள் குற்றவாளிகளை 'அழியச்செய்து' சபையாருக்குப் பொருந்திய பரிஹாரங்களைச் செய்தனர். அவ்விதம் ஓடிப் போன கணக்கனுடைய காணிதான் சபையாரால் (பறிமுதல் செய்யப் பெற்று) விற்கப் பட்டதாம்.

சாசனங்களை நாம் கூர்ந்து கவனித்தால் அவை போலியா, உண்மையா என்பதைச் சுலபமாகத் தெரிந்துகொள்ளலாம். போலிச் சாசனங்களை அறிந்துகொள்வதற்கு அடியிற் கண்டவை முக்கியமான பரீகைகளாகும்.

பண்டைய சாசனங்களைப் பொறித்த வினையாளர்கள் அவற்றை அழகாகவும், எழுத்துக்களை நன்கு விளங்கும்வண்ணமும் பொறித்துள்ளார்கள். மேலும், எடுகளில் எழுதப்பட்ட சாசனங்கள் அவ்வக் காலத்திற் கேற்றவாறு உருவ வேறுபாடுகளை உடைத்தாயிருந்தன. தென்னாட்டிற் காணப்படும் பழைய காலத்துச் செப்பேடுகள் சுவடி

போன்ற நீண்ட வடிவத்தையும், விஜயநகர அரசர் காலத்துச் செப்பேடுகள் புத்தக வடிவையும் உடையன.

பண்டைக்காலத்து வழக்கிலிருந்த எழுத்துக்கள் நாளடைவில் வளர்ச்சியடைந்து இப்பொழுதுள்ள நிலையை அடைந்திருக்கின்றன. இவ்வெழுத்துக்களும் ஒவ்வொரு தேசத்திலும் வெவ்வேறு விதமான வளர்ச்சியைப் பெற்றுள்ளன. ஆதலின், ஒரு சாசனம் எந்த நாட்டில், எந்தக் காலத்தில் ஏற்பட்டதோ, அக்காலத்தில், அந்நாட்டில் வழங்கி வந்த எழுத்துக்களாற் பொறிக்கப்பட்டிருத்தல்வேண்டும். அவ்வாறன்றி மிகவும் பிற்பட்டகாலத்து எழுத்துக்களையோ வழக்கொழிந்தஎழுத்துக்களையோ கொண்டு எழுதப்பட்டிருக்குமானால், அது போலிச் சாசனம் என்று நாம் நிச்சயமாகக் கூறலாம்.

சாசனங்கள் பொதுவாகத் தானங்களையே குறிப்பனவாகும். தான சாசனங்களில் எந்தெந்த விஷயங்கள் கூறப்படவேண்டும் என்பதைத் தாம் சாஸ்திரங்கள் விரிவாகக் கூறுகின்றன. அவை, தானங் கொடுத்தோன், அவனது வமிசாவளி, தானம் பெற்றவர், கொடுக்கப்பட்ட தான விபரம், காலம், தானத்திற்குரிய பாதுகாப்புகள், சாட்சி முதலிவாகும்.

தான பத்திரங்களை எழுதுவதில் ஒவ்வொருகாலத்தில் ஒவ்வொரு விதமான உரைநடை வழங்கி வந்திருக்கிறது. தானம்பெற்றோர்கள் அனுபவிக்க வேண்டிய உரிமைகளும் வெவ்வேறு காலங்களில் வெவ்வேறு விதமாகக் கூறப்பட்டுள்ளன. உதாரணமாக, உடும்போடி ஆமை தவழ்தவெல்லாம், சாவாமுவாப் பேராடு, கற்றா, முற்றாட்டு என்பன போன்ற சொற்கள் ஓரோர் காலங்களில் வழங்கிவந்து, பின்பு வழக்கொழிந்தன. சாசனங்களின் உரைநடை சரியானபடி இல்லாவிட்டால், அவற்றைப் போலியென நாம் நிச்சயமாகக் கூறலாம்.

சாசனங்களிற் குறிக்கப்படும் காலம், தேசந்தோறும் மாறுபட்டிருக்கும். சகம், கலி, கொல்லம், புதுவைப்பு, விக்கிரம ஆண்டுகள் போலப் பல அப்தங்கள் வழக்கில் இருந்துள்ளன. பாண்டிய சாசனங்களில் 'இரண்டாம் ஆண்டைக் கெதிர் பதினாலாமாண்டு' என்பதுபோலப் பொதுவாக ஈராண்டுகள் குறிக்கப்பட்டுள்ளன. இதைப்போலவே, மாதம், தேதி, நாள், நகஷத்திரம் முதலியவற்றைக் குறிப்பதிலும் மாறுபாடுகள் உள. இவையாவும் சரியான முறையில் உபயோகப்படுத்தப்பட்டிருத்தல் வேண்டும். தானங்கள் பொதுவாகக் கிரஹணம் முதலிய புண்ணியகாலங்களிலேதான் கொடுக்கப்படுவது மரபு. இதை அனுசரித்துப் போலிச் சாசனங்களைச் சிருஷ்டிப்பவர்களும், அந்தத் தானங்

கள் ஏதாவது ரூர் சந்திர கிரஹணங்களை முன்னிட்டுக் கொடுக்கப் பட்டன எனக் கூறுவதுண்டு. கணிதமுறைப்படி அவற்றை ஆராய்ந்தால் சில சமயங்களில் அவ்விதமான கிரஹணங்களே ஏற்பட்டிருக்க முடியா வென்பது புலப்படும்!

போலிச் சாசனங்களை எழுதுபவர்கள் பொதுவாகப் பிரசித்தி பெற்ற ஓர் அரசன் கொடுத்தனவாகக் கூறக்கூடிய தானங்களையே சிருஷ்டிப்பார்கள். அங்ஙனம் அவர்கள் எழுதும்பொழுது அந்த அரசனுடைய சாசனங்களுள் ஏதோ ஒன்றைப் பின்பற்றியே தயாரிப்பார்கள். ஆகவே அந்த அரசனுடைய பிரசஸ்தியைப் பழைய சாசனத்தில் கண்டபடியே வைத்துக் கொண்டு மேலே தாங்கள் விரும்பிய உரிமை தானம்வழங்கப் பெற்றதாக எழுதிக்கொள்வார்கள். ஆகவே இத்தகைய சாசனங்களில் தானப் பகுதியையே நாம் முக்கியமாகப் பிற்காலத்திய சிருஷ்டி. என்று தள்ளி விடவேண்டும். அரசனுடைய பிரசஸ்திப் பகுதியோர் போலிச்சாசனத்தைச் சேர்ந்ததெயாபினும் பெரும்பாலும் பழைய சாசனம் ஒன்றன் பிரதியாகவே இருக்குமாதலால் அவ்விதம் விலக்கப் படவேண்டியதல்ல.

வாதாபிச் சாளுக்கியர்கள் அளித்தனவாகக் கூறப்படும் சாசனங்களில் சில போலிச் சாசனங்களும் கிடைத்துள்ளன, அவை செப்பேடுகளில் அறுநூறு ஆண்டுகளுக்குப் பின்னால் வழங்கிய எழுத்துக்களால் பொறிக்கப்பட்டுள்ளன. அவை போலிச்சாசனங்களே ஆயினும் சிற்சில அம்சங்களில் சரித்திர ஆராய்ச்சிக்கு உபயோகமானவை என்றே ஆசிரியர்கள் கருதுகிறார்கள்.

சிற்சில சமயங்களில் கிடைக்கும் சாசனங்களில் அவை மூல சாசனங்கள் அல்லவென்றும், அவற்றின் பிரதிகள் எனவும் கூறப் பட்டிருப்பதுண்டு. ஆயினும் மூலம் நமக்குக் கிடைப்பதில்லை. இப்படிப்பட்ட சாசனங்களையும், முக்கியமாகச் செம்பில் உள்ளவற்றை, நாம் நம்பமுடியாது. இம்மாதிரியான ஒரு பிரதியை நாம் ஆராயுங்கால், எழுத்துக்களின் வரிவடிவங்களைத் தவிர மற்றைய பரிகைகளின் முடிவாகச் சாசனம் எந்தக் காலத்தைச் சார்ந்ததாகக் கூறப்படுகின்றதோ அந்தக் காலத்திற்கு ஏற்றபடி இருக்கிறதா என்பதைக் கவனித்தல் வேண்டும். தமிழ்நாட்டிற் கிடைக்கும் கல்வெட்டுக்களில் இம்மாதிரியான பிரதி சாசனங்கள் பல உள. பொதுவாக, அப்படிப்பட்டவை பழையகோயில்களைப் பிரித்துக்கட்டுவதற்கு முன்பு அவற்றின் சுவர்களில் காணப்பட்ட கல்வெட்டுகளைப் பெயர்த்தெழுதி வைத்துக்கொண்டு புதிய கட்டிடம்முடிந்த பிறகு பொறிக்கப்பட்டனவாகும்.

எழுதுவோரின் பிழையால், மூலத்திற்கும் பிரதிக்கும் வேறுபாடுகள் ஏற்படுவது இயல்பு. ஆராய்ச்சியாளர்கள் அவற்றைச் சுலபமாகக் கண்டு கொள்ளுதல் கூடும்.

இராஷ்டிரகூட அரசனான முதலாம் அமோகவர்ஷன் காலத்தில் கி. பி. 860-ஆம் ஆண்டில் கொடுக்கப்பட்ட ஒரு செப்பேட்டுச் சாசனத்தை ஆதாரமாகக் கொண்டு கல்லில் வெட்டப்பெற்றதாகக் குறிக்கப்படும் கல்வெட்டு ஒன்று தார்வார் ஜில்லா கொன்னூர் என்னுமிடத்திலிருந்து கிடைக்கிறது. (எபி. இந்திகா, ஆறாம் வால்யூம்). கி. பி. பன்னிரண்டாம் நூற்றாண்டில் இருந்தவராகக் காணும் மேகசந்திரரின் குமாரரான வீரநந்தி என்னும் ஜைன ஆசாரியர் செப்பேட்டிலிருந்து வாசித்துச் சொல்லியபடி கல்வெட்டு தயாரிக்கப்பட்டதாம். ஆயினும் அதிலே காணும் சில தவறுகளைக் கொண்டு அவரால் சரியாக வாசித்துச் சொல்லமுடியாததாலோ வேண்டுமென்றே திருத்திக் கூறியதாலோ தான் அந்தத் தவறுகள் ஏற்பட்டிருத்தல் வேண்டும் என்பதை நாம் நிச்சயமாகக் கூறலாம்.

சேக்கிழார் பிறந்த ஊரான குன்றத்தூரிலிருந்து செப்பேட்டுச் சாசனம் ஒன்று கிடைத்துள்ளது. செப்பேடு விஜயநகர ஆட்சிக் காலத்தில் வழக்கிலிருந்த உருவம் கொண்டது. எனினும் 'கச்சியுந் தஞ்சையும் கொண்ட கன்னர தேவ'னுடைய ஆட்சிக் காலத்தனவாக மூன்று கல்வெட்டுக்களையும் சோழ மெய்க்கீர்த்திப் பகுதிகளின் சில வரிகளையும் கொண்டிருந்திறது. கல்லில் காணும் உருவத்திலேயே பெயர்த்தெழுதியதாகக் காண்பதால் சரியாகவும் வாசிக்கமுடியாது. இவ்வளவு இருந்தும் அதை ஒரு போலிச் சாசனம் எனவே கொள்ள வேண்டும்.

இவ்விதம் போலிச் சாசனங்களை உண்டாக்குவது சமீப காலத்திலும் நடந்துள்ளது; இப்பொழுதும் நடந்து வருகின்றது. மேலைக் கங்க அரசனான இரண்டாம் சிவமரான் என்பவனால் கி. பி. 807-ஆம் வருஷத்தில் கொடுக்கப்பட்ட தானத்தைத் தெரிவிப்பதாக எழுதப்பட்டுள்ள சுரதேனுபுரச் செப்பேடுகள், சென்ற நூற்றாண்டிலேதான் மைசூர் ஸம்ஸ்தானத்தின் இனாம் கமிஷனர் முன்பாகத் தாக்கல் செய்வதற்காகத் தயார் செய்யப்பட்டனவாகும் என்னும் செய்தியை மைசூர் சாசன இலாகா அதிகாரியாயிருந்த ரைஸ் குறித்துள்ளார்.

அதேபோல, வங்காள ஏஷ்யாடிக் ஸொஸைட்டியின் புத்தகசாலையில் ஒரு செப்பேடு உள்ளது; அது தானபத்திரம் அல்ல. கி. பி. 1347-இல் வடஇந்தியாவில் முஸ்லிம் அரசர்களுடன் நடந்த ஒரு சண்டை

யைப் பற்றிக் கூறுகின்றது. கி. மு. முன்றும் தாற்றாண்டில் ஆண்ட அசோக மன்னனின் கல்வெட்டுக்களிற் காணப்படும் எழுத்துக்களைக் கொண்டு இவ்வேடு பொறிக்கப்பட்டுள்ளது. இச்சாசனத்துள் அந்த எழுத்து 'பாலி' என்னும் பெயரால் குறிக்கப்பட்டிருக்கிறது. பாலி என்பது ஒரு மொழியே அன்றி, எழுத்தின் வகை அல்ல என்பதை நாம் அறிவோம். சாசனம் ஸம்ஸ்கிருதத்தில் எழுதப்பட்டுள்ளது. அசோக மன்னன் காலத்தைச் சார்ந்த ஸம்ஸ்கிருத சாசனம் ஒன்றும் இது வரையில் கிடைத்ததில்லை. இச்சாசனத்தில் காணப்படும் எண்கள் தற்கால வழக்கில் உள்ளவைகளேயாகும். பெயர்களோ, ஆங்கில நாகரிகம் நம் நாட்டில் புகுந்த பிறகு அவை திரிபுபெற்று அடைந்த உருவில் எழுதப்பட்டுள்ளன!

### 9. சாசனங்களைப் பொறித்திருக்கும் பொருள்கள்

நாம் இதுகாறும் சாசனங்கள் தெரிவிக்கும் விஷயங்களைக்கொண்டு அவற்றைப் பலவகைகளாகப் பிரித்து ஆராய்ந்தோம். அவை சுட்ட மண் முதல் தங்கம் வரையில் உள்ள பலவகைச் சாமான்கள் மீதும் பொறிக்கப்பட்டுக் காணப்படுகின்றன வென்பதை நாம் முன்னமேயே கூறியிருக்கிறோம். அதனால் அவை எவ்வெவற்றின்பேரில் பொறிக்கப் பட்டுள்ளன வென்பதை ஆராய்ந்தாலும் அவற்றைப் பல வகைகளாகப் பிரிக்கலாம். ஆயினும் அப்பிரிவுகள் யாவும், உலோகங்கள், உலோக மல்லாதவை என்னும் இரு பெரும் பிரிவுகளுள் அடங்கிவிடும்.

#### உலோகங்கள்

உலோகங்களிலே செம்புதான் அதிகமாக உபயோகிக்கப் பெற்ற தாயினும், தங்கம், வெள்ளி, பித்தளை, வெண்கலம், இரும்பு ஆகிய வேறு பலவும் உபயோகப்பட்டுள்ளன.

1. தங்கம்: ருருஜாதகம், குருதம்மஜாதகம் போன்ற புத்த ஜாதகக்கதைகளிலிருந்து முன்னாளிலே செல்வச்சீமான்களான வணிகர்களுடைய குடும்பப்பத்திரங்கள், ராஜசாசனங்கள், தர்மோபதேச வாக்கியங்கள், அழகிய கவிதைகள் ஆகியவை பொன்னிலே பொறிக்கப் பட்டு வந்தனவென்று தெரிய வருகிறது. ஒருகால் ஜாதகக் கதைகள் விவரிக்கும் வாழ்க்கை லக்ஷியவாழ்க்கையின் வருணனையாக இருக்கலாம். தங்கம் விலையுயர்ந்த பொருள்; எளிதில் யாவருக்கும் கிட்டியிராது. பெரும்பாலும் சம்பிரதாயமான காரியங்களிலும் ஆடம்பரவிஷயங்களிலுமே பொன்னை உபயோகித்திருப்பார்கள். இன்றைக்கும் ராசக்ஷயாக அணியப் பொன்தகட்டிலே யந்திரங்களை எழுதிவருகிறார்கள்.

இதுகாறும் நமக்குப் பொன்னில் எழுதியனவாகக் கிடைத்த சாசனங்கள் மிகச் சொற்பமே. பஞ்சாபில் விர்ஸுக்கிற்கு அருகில் கங்கு என்னுமிடத்தில் உள்ள பெளத்த ஸ்தூபத்தில் காணிக்கை செலுத்திய செய்தியைத் தெரிவிக்கும் சாசனம் ஒன்று தங்கத் தகட்டில் கரோஷ்டி எழுத்தில் பொறிக்கப்பட்டுக் காணப்படுகிறது. (கன்னிங்ஹாம் எழுதிய புதை பொருள் ஆராய்ச்சி அறிக்கை, இரண்டாம் வால்யூம், 130 பக்கம்).

கி.பி. நான்கு அல்லது ஐந்தாம் நூற்றாண்டு எழுத்துக்களிலே புத்தமத சூத்திரங்களையும் பாவி மொழிச் சுலோகம் ஒன்றையும் கொண்ட இரண்டு தங்கத் தகடுகள் பர்மாவிலிருந்து கிடைத்துள்ளன. (எபி. இந்திகா, ஐந்தாம் வால்யூம்). இன்னும் பர்மா தேசத்து ஆவா நாட்டு அரசனுக்கும் போர்ச்சுகீசியருக்கும் ஏற்பட்ட உடன்படிக்கை ஒன்றைத் தங்கத்தகட்டில் எழுதித் தந்தப் பேழையில் வைத்து அளித்ததாகப் பர்ணல் குறித்திருக்கிறார். (தென்னிந்தியப் பிராசீனலிபி, பக்கம் 93). அதேபோல, கோபகா பட்டினத்திலிருந்த போர்ச்சுகீசியத் தலைவனுக்குக் கி.பி. 1514-ஆம் ஆண்டில் விஜயநகர மன்னர் (கிருஷ்ணதேவ ராயர்) அனுப்பிய கடிதத்தைத் தங்கத்தகட்டில் பொறித்து அனுப்பினாராம். (ஓடி பக்கம் 90).

2. வெள்ளி: இது தங்கத்தைப்போல் அவ்வளவு அதிக விலை பெற்றதல்ல; ஆதலின் வெள்ளியில் பொறிக்கப்பட்ட சாசனங்கள் தங்கத்தைக் காட்டிலும் கொஞ்சம் அதிகம் என்னலாம்.

கிருஷ்ண நதி தீரத்தில் உள்ள பட்டிப்ரோலு ஸ்தூபத்திலும், (தென்னிந்தியப் புதை பொருள் ஆராய்ச்சி, ஆறாவது வால்யூம்), வட நாட்டில் தக்ஷிண ஸ்தூபத்திலும் (ராயல் ஏஷ்யாடிக் ஸொஸைட்டி பத்திரிகை, 1914, 1915-ஆண்டுகள்), இன்னும் ராவல்பிண்டி ஜில்லாவில் மாணிக்கியாலா என்னுமிடத்தில் உள்ள ஸ்தூபத்திலும் (கன்னிங்ஹாம் எழுதிய புதை பொருள் ஆராய்ச்சி அறிக்கை, இரண்டாம் வால்யூம், பக்கம் 160) கிடைத்த சிறு சாசனங்கள் வெள்ளியிலே பொறிக்கப்பட்டு இருக்கின்றன.

தஞ்சை நாயக்க வம்சத்துக் கடைசி மன்னனான விஜயராகவ நாயக்கர் நாகபட்டினத்தை டச்சுக்காரர்களுக்குக் கொடுத்ததைத் தெரிவிக்கும் சாசனம் தெலுங்கிலே வெள்ளியேட்டிலே பொறிக்கப்பட்டுள்ளது. தஞ்சை மராத்திய மன்னர்களில் முதல் அரசனான எக்கோஜி கி. பி. 1676-ல் அதை ஊர்ஜிதம் செய்து எழுதிய தமிழ்ச் சாசனமும் வெள்ளியேட்டிலே எழுதப்பட்டுள்ளது. இவ்விரு ஏடுகளும் பட்டேவியா பொருட் காட்சி சாலையில் வைக்கப் பட்டிருக்கின்றனவாம். விஜயநகரத்துக் கடைசி

மன்னனான மூன்றாம் ஸ்ரீரங்கனுடைய தேவிக்கும் குமாரர்களுக்கும் அழிந்துபோன விஜயநகர சாம்ராஜ்யத்தின் ஸ்தானத்தில் மஹாராஷ்டிர ராஜ்யத்தை ஏற்படுத்திப் பெரும் புகழ் பெற்ற சிவாஜி மன்னன் கொடுத்த உரிமைகளும் தானங்களும் வெள்ளியேடுகளில் பொறித்து அளிக்கப்பட்டனவாம்.

சமீப காலத்திலே வெள்ளி யேட்டிலே எழுதப் பெற்ற பாவி பாஷை நூல் ஒன்று இலங்கையிலிருந்து கிடைத்ததாக டாக்டர் பர்ணல் கூறியிருக்கிறார். தங்கமுலாம் வெள்ளி முலாம் பூசிய ஏடுகளில் எழுதப் பட்ட நூல்கள் லண்டன் பிரிட்டிஷ் மியூசியத்தில் உள்ளனவாம்.

3. பித்தளை: தங்கம், வெள்ளி இவற்றைக் காட்டிலும் பித்தளையில் பொறிக்கப்பட்டுள்ள சாசனங்கள் சற்று அதிகமாகவே காணப்படுகின்றன. எனினும், சாசனங்களை எழுதிய தனி ஏடுகள் கிடைக்கவில்லை. அவை பெரும்பாலும் விக்கிரகம் முதலியவற்றின்மீதே காணப்படும்.

அப்கானிஸ்தானத்தைச் சேர்ந்த வர்தக் என்னுமிடத்தில் ஞாபகச் சின்னங்களைத் தாங்கி நிற்கும் பித்தளைப் பாத்திரம் ஒன்று கிடைத்துள்ளது. 'அதில் குஷான மன்னனான ஹுவிஷ்கனுடைய சாசனம் ஒன்று பொறிக்கப்பட்டுள்ளது. (கரோஷ்டி சாசனங்கள்).

அலகாபாத்திற்குச் சமீபத்தில் உள்ள கோசம் என்னுமிடத்திலிருந்து குப்தர்கள் ஆண்டுவந்த காலத்திய சாசனம் பொறிக்கப்பட்டுள்ள ஏடுகளைச் சேர்த்துக் கோத்திருந்த வளையம் ஒன்று முத்திரையுடைய பித்தளையில் கிடைத்திருக்கிறது. (கன்னிங்ஹாம் எழுதிய புதை பொருள் ஆராய்ச்சி அறிக்கை, பத்தாம் வால்யூம், படம் 2).

கையக்குப் பக்கத்திலிருந்து புத்த பகவானுடைய பித்தளை விக்கிரகம் ஒன்று கிடைத்திருக்கிறது. அதன் பீடத்தில் அதை அர்ப்பணம் செய்ததைத் தெரிவிக்கும் சாசனம் ஒன்று காணப்படுகிறது. அச்சாசனத்திலிருந்து "ஆணி எழுத்துக்கள்" என்று சரித்திர ஆசிரியர்களால் வழங்கப்படும் ஒருவகை எழுத்துக்கள் வெளியாகின்றன. (இ.ஆ., பத்தொன்பதாம் வால்யூம், 99 பக்கம்.) சம்பா ஸம்ஸ்தானத்திலிருந்து பித்தளைப் படிமங்கள் சில கிடைக்கப்பெற்றுள்ளன. அவற்றில் அப் படிமங்களைச் செதுக்கிய சிற்பிகளின் பெயர்களும் அவற்றைச் செய்வித்த அரசர்களின் பெயர்களும் காணப்படுகின்றன. (இந்தியப் புதை பொருள் இலாகா ஆண்டு அறிக்கை, 1903). ஆபு மலைகளில்



உள்ள ஜைனக்கோயில்களில் அவர்களுடைய மதத்தின் கிரந்தங்கள் பொறித்த பித்தளை ஏடுகள் இன்றைக்கும் உள்ளன என்று மஹாமஹோபாத்யாய பண்டித ஓஜா கூறுகிறார்.

4. வெண்கலம்: இவ்வகைக் கலவையினால் செய்யப்பட்ட விக் கிரகங்கள் சில ஓரோரிடங்களில் காணப்படுகின்றன. உதாரணமாகப் பிஷாவரிவிருந்து வெண்கலத்தால் செய்யப்பட்ட ஒரு விக் கிரகத்தின் தலைமட்டும் கிடைத்திருக்கிறது. அதை அளித்த விவரத்தைத் தெரிவித்து அதன் அடியைச் சுற்றிலும் ஒரு சாசனம் பொறிக்கப்பட்டுள்ளது. (வங்காளத்து ஏஷ்யாடிக் ஸொஸைட்டி பத்திரிகை, 1836, பக்கம் 482). நாகபட்டினத்திலிருந்த கிடைத்த புத்த பகவானுடைய விக் கிரகங்கள் நம் நாட்டில் உள்ள பொருட்காட்சி சாலைகள் பலவற்றிலும் இப்போது காணக் கிடைக்கின்றன. அவற்றின் பீடத்தில் தமிழிலே பொறிக்கப் பட்ட சாசனங்கள் உள்ளன. (நாகபட்டினப் படிமங்கள் என்ற பெயரில் சென்னை மியூசியம் வெளியீடு).

அரசு முத்திரைகளைச் செய்வதற்கு வேண்டிய படிமங்கள் பல வெண்கலத்தால் செய்யப்பட்டுக் காணப்படுகின்றன. அவற்றுள் ஒன்றில் பிராமி, கரோஷ்டி, கிரேக்கம் ஆகிய மூன்று வகை லிபிகளிலும் எழுத்துக்கள் காணப்படுகின்றன. (ராயல் ஏஷ்யாடிக் ஸொஸைட்டி பத்திரிகை, 1901, 1905-ஆண்டுகள்).

செம்புப் பட்டயங்களைக் கொத்திருக்கும் வளையங்களில் காணப்படும் முத்திரைகளை நாம் செம்பு என்று மதித்து வருகிறோம். ஆனால் செம்பில் உருவங்களை அவ்வளவு அழகாகவும் தெளிவாகவும் வார்க்க முடியாது என்றும் ஆழ்ந்து நோக்கினால் அவற்றுள் பெரும்பாலானவை வெண்கலம் என்றே ஏற்படும் என்றும் ஆராய்ச்சியாளர் கொள்வர்.

5. செம்பு: உலோகங்களில் காணப்படும் சாசனங்கள் பெரும்பாலும் செம்பிலேதான் உள்ளன. செம்பிலே நமக்கு அதிகமாகக் கிடைப்பவை பட்டயங்களே ஆகும். செம்புப் பட்டயங்கள் மிகச் சிறிய அளவிலிருந்து மிகப் பெரிய அளவுவரை பலவித உருவங்களில் காணப்படுகின்றன. உத்தரப் பிரதேசத்தில் கோரக்பூர் ஜில்லாவில் ஸோ கௌரா என்னுமிடத்திலிருந்து கிடைத்த பட்டயமே இதுவரையில் நமக்குக் கிடைத்தவற்றுள் மிகச் சிறிய அளவில் உள்ளதாகும். அது இரண்டரை அங்குலம் நீளமும், ஒன்றேழுக்காலே அரைக்கால் அங்குல அகலமுமுள்ள செப்பேட்டில் எழுதப்பட்டதாகும். (ஐ. 1907). ஸுயே விஹாரத்திலிருந்து கிடைத்த கனிஷ்க மன்னன் காலத்துச் செப்பேடே மிகப் பெரியதாகும். அது இரண்டரையடிச் சதுரமாக இருக்கிறது. (கரோஷ்டி சாசனங்கள்).

செம்பில் உள்ள சாசனங்களிலே சிலவற்றுள் அவை பட்டிகா (பட்டயம்) அல்லது தாம்பரப்பட்டிகா (தாம்பரப் பட்டயம்) என்று குறிக்கப்பட்டுள்ளன. மற்றும் சில சாசனம் அல்லது தாம்பரசாசனம் என்றும் கூறப்பட்டுள்ளன. இரண்டு இடங்களில் அவை பிரசஸ்தி என்றும் தெரிவிக்கப்பட்டுள்ளன. கல்விலே வெட்டுவிக்கப்பட்ட சாசனங்கள் தாம் அதிகமாகப் பிரசஸ்தி என்று வழங்கப்படுகின்றன. செம்பில் உள்ளவற்றுள் இப்பெயரையுடையவை இவற்றைத் தவிர வேறு காணப்படவில்லை. ஒரிடத்திலே செப்பேடு திரிபலீ தாம்ரா சாசனம் (அதாவது செம்பில் செய்யப்பட்ட உத்தரவின் மூன்றாம் ப்ரதி) என்றும் குறிக்கப்பட்டுள்ளது. (எபி. இந்திகா, மூன்றாம் வால்யூம், பக்கம் 345).

அரசன் கொடுத்த தானத்தைத் தெரிவிக்கும் உத்தரவு முதலிலேயே செம்பில் எழுதப்படமாட்டாது. அது முதலில் ஒலையிலே எழுதப்பட்டு மற்றைய உத்தரவுகளைப் போலவே பல அதிகாரிகள் பார்த்துக் கையெழுத்திட்டப் பிறகே தானம் பெற்றவருக்கு வந்து சேருகிறது. அதே சமயத்தில் அச் செய்தி நாட்டாருக்கும் அறிவிக்கப்படுகிறது. இந்தத் தானம் நீடுழிகாலம் அனுபவிக்கப்படுவதற்காக அது கோயில் சுவரில் அல்லது வேறு பொதுஸ்தலத்தில் வெட்டப்படுகிறது. இன்னும் ஒலையானது சீக்கிரம் அழிந்துவிடக்கூடிய பொருளாதலின் தானம்பெற்றவர்களுக்கு வெகுகாலம் உபயோகப்படுவதற்காகச் செம்பிலும் வெட்டிக்கொடுக்கப்படுகிறது. பல சாசனங்களில் 'கல்விலும் செம்பிலும் வெட்டிக்கொள்ளக் கடவதாகவும்' என்று உத்தரவிடப்பட்டதாகக் காணப்படுவது நாம் மேலே கூறியதை உறுதியாக்குகின்றது. இவ்விதமாக இவ்வுத்தரவு முதலில் ஒலையிலும், பின்னால் கல்விலும், அதற்கப்பால் செம்பிலும் எழுதப்படுவதால் செப்பேடு மூன்றாவது பிரதி ஆகிறதுபோலும்.

பொதுவாகச் செப்புப் பட்டயங்கள் தானம் செய்யப்பட்ட நிலங்களின் மீது தானம் பெற்றவர்களுக்கு உள்ள உரிமையைத் தெரிவிக்கும் பத்திரங்களேயாகும். சிற்சில ஞாபகார்த்தமாக ஏற்பட்டவைகளாகவும் உள்ளன. அவ்விதமானவை ஸ்தூபங்கள், கட்டிடங்கள் முதலியவற்றுள் வைத்துப் பத்திரப்படுத்தி வைக்கப்பட்டுள்ளன. சில சமயங்களில் தானம் கொடுக்கப்பட்ட நிலங்களுக்குள்ளேயே இப்பட்டயங்கள் புதைக்கப்பட்டிருந்தும் கிடைத்துள்ளன. வேறு சில கட்டிடங்களின் அஸ்திவாரங்களிலும், சுவர்களிலும் இரகசியமாக வைக்கப்பட்டு அவற்றின்மேல் கட்டிடங்கள் எழுப்பப்பட்டுள்ளன. இவ்விதம் அந்தரவாரம் என்னுமிடத்தில் சாசனங்களோடு பூமியிலே புதைக்கப்பெற்ற

நிருந்த மண்பாணியின் புகைப்படங்கள் (என்ஷியண்ட் இந்தியா) 'புராதன இந்தியா' ஒன்பதாம் இதழில் வெளியிடப்பட்டுள்ளன.

தாம்பர சாசனங்களை வைத்திருப்பவர்கள் அவற்றை வெளியில் காண்பிப்பதற்கு மிகவும் கஷ்டப்படுகிறார்கள். அவற்றுள் எழுதப் பட்டிருப்பதை என்னவென்று அறியாமல் ஏதோ புதையல் இருக்கு மிடத்தையோ அல்லது வேறு அதிர்ஷ்டத்தைப் பற்றியோ மந்தி ரங்கள் எழுதப்பட்டிருப்பதாகவும், பிறருக்குக் காண்பித்தால் அதன் பலனைத் தாங்கள் அனுபவிக்க இயலாது போய்விடும் என்றும் எண்ணம் கொண்டு அவர்கள் சாசனங்களை இரகசியமாகப் பாது காத்து வருகிறார்கள். மற்றும் சிலர் ஆதிகாலத்தில் தங்கள் குடும் பத்திற்கு கொடுக்கப்பட்டதாகக் கூறப்படும் சொத்தைத் திரும்ப அடைவதற்காக அவற்றை அதிகாரிகளிடம் கொண்டுவந்து கொடுக் கிறார்கள். ஆனால் தானம் பெற்ற சந்ததிகள் நசித்துப்போதல், ராஜ்ய மாறுதல்கள், அரசாங்க சுதந்தரம், இவை யாவற்றுக்கும் மேலாகக் காலாவதி (அனுபோகப் பாத்தியதை) முதலியவற்றால் தங்களுடைய உரிமையை ஸ்தாபிக்க முடியாது என்பதை அவர்கள் அறிந்து கொண்டார்கள் இல்லை. இவ்விதமாகச் செப்புப் பட்டயங்கள் தனிப் பட்டவர்களிடமே அதிகமாக இருக்கின்றன வென்றும், இதுகாறும் வெளியானவற்றைவிட இன்னும் வெளிப்படவேண்டியவையே அதிக மாக இருக்கும் என்றும் நாம் எண்ணுவதற்கு இடமிருக்கிறது.

ஓர் இடத்தில் யாராவது அரசனுடைய கல்வெட்டு ஒன்று கிடைக்கு மானால் அந்த அரசனுடைய ஆட்சி அந்த ஊர்வரை பரவியிருந்தது என்கிறோம். அதேபோல் ஓர் ஊரில் ஓர் அரசனுடைய தாம்பர சாசனம் ஒன்று கிடைக்குமானால் அந்த அரசனுடைய ஆட்சி அந்த ஊர்வரையில் பரவியிருந்தது என்று நாம் நிச்சயமாகக் கூறமுடி யாது. தானம் கொடுக்கப்பட்ட நிலங்களின் பேரில் தானம் பெற்றவர் களுக்கு உள்ள உரிமைகளை ஸ்தாபிக்கும் பத்திரங்களாக அவைஉபயோ கப்பட்டன வாதலின், அப்பட்டயங்கள் பல கைகள் மாறித் தானம் கொடுக்கப்பட்ட இடத்திற்கு வெகுதூரத்தில் உள்ள வேறோர் ஊரில் கிடைக்கக் கூடும். ஆதனால் அந்தப் பட்டயத்தில் கூறப்பட்டுள்ள ஒவ் வோர் ஊரையும் நாம் நிச்சயித்தால் அல்லாது அந்தத் தானத்தைக் கொடுத்த அரசனது ஆட்சி எவ்வளவு தூரம் பரவியிருந்தது என்பதைக் கூறமுடியாது. மேலைச் சாளுக்கிய மன்னனான இரண்டாம் கீர்த்தி வர்மன் கி. பி. 757-ம் வருஷத்தில் கொடுத்த தானத்தைத் தெரிவிக்கும் வக்கலேரிச் செப்பேடுகளை நாம் இதற்கு உதாரணமாகக் கூறலாம். அவற்றுள் குறிக்கப்பட்ட தானத்தைக் கொடுக்கையில் அரசன் பீடி

நதியின் வடக்கரையில் பண்டாரக விட்டகை என்று கூறப்படும் இடத்தில் பாடி இறங்கியிருந்ததாகத் தெரிவிக்கப்பட்டுள்ளது. அது ஷோலாப்பூருக்குத் தென்மேற்கே இருபது மைல் தூரத்தில், பீமநதியின் வடக்கரையில் உள்ள பண்டார் கௌடேம் என்னும் இடமாகுமென ஆசிரியர்கள் கொள்வர். தானம் கொடுக்கப்பட்டதாகக் கூறப்படுவதோ இப்பொழுது தார்வார் என்று வழங்கப்படும் ஜில்லாவில் ஹாங்கல் என்னுமிடத்திற்குச் சமீபத்தில் உள்ள சுள்ளியூர் என்னும் கிராமம் ஆகும். தானம் பெற்றவர் அவ்வூரிலேயோ அல்லது அதற்குச் சமீபத்திலேயோ வசித்து வந்திருக்கவேண்டும். அவர் அந்த ஊரை அனுபவிப்பதற்கான உரிமைக்கு ஆதாரமாக அரசன் கொடுத்த தானப் பட்டயத்தை அவர் வைத்திருக்கவேண்டும். அதனால் சாதாரணமாகப் பார்க்கும்பொழுது அச்செப்பேடுகள் அந்த ஊர்ப்பக்கத்தில், அதாவது தார்வார் ஜில்லாவில், கிடைத்திருக்கவேண்டும். ஆனால் அவை மைசூர் சம்ஸ்தானத்தில் கோலார் ஜில்லாவில் உள்ள வக்கலேரி என்னுமிடத்தில் கிடைத்தன.

செப்பேடுகள் ஏட்டுச் சுவடிகளைப்போல அமைக்கப்பட்டிருக்கும். அவற்றை ஒழுங்காக அடுக்கி வைத்தால் சுவடியையே ஒத்திருக்கும். ஆயினும் ஒரு பட்டயத்தின் ஏடுகள் மற்றொரு பட்டயத்தின் ஏடுகளை ஒத்திரா. அந்தந்தச் சாசனங்களின் வாசகத்திற்குத் தகுந்தாற்போலவும் வழக்கத்தை யொத்தும், அவ்வேடுகளின் நீளமும், அகலமும் காணப்படும். ஒன்றிற்கு மேற்பட்ட ஏடுகளையுடையவற்றின் முதற்பக்கமும், கடைசிப் பக்கமும் எழுதப்படாமல் காணப்படும். ஏதாவது ஒரு சாசனம் கடைசிப் பக்கத்தில் முடிவதாக இருந்தால் அதற்குப் பிறகு வெற்று ஏடு ஒன்று சேர்க்கப்படுவதும் உண்டு. இதனால் எழுதப்பட்ட ஏடுகளின் பக்கங்கள் பழுதாகாமலும் சேதமுறாமலும் பாதுகாக்க இயலும். இன்னும் இதே நோக்கத்துடன் ஏடுகளின் ஓரங்களிலும் சற்றே கனமான விளிம்பும் காணப்படும்.

செப்பேட்டுச் சாசனம் ஒரே ஏடு கொண்டதாக இருக்குமானால் ஒரு பக்கத்தில் மட்டுமே எழுதப்பட்டிருக்கும். சிற்சில சுமயங்களில் இரு புறங்களிலும் எழுதப்பட்டிருப்பது உண்டு. ஆயினும் பெரும்பாலான செப்பேட்டுச் சாசனங்கள் ஒன்றுக்கு மேற்பட்ட ஏடுகள் கொண்டனவாகவே இருக்கும். அவ்விதம் அதிகமான ஏடுகள் கொண்டவை தமிழ் நாட்டிலிருந்துதான் கிடைக்கின்றன.

இதிகாரம் கிடைத்துள்ள செப்பேட்டுச் சாசனங்களிலே மிகவும் பருமனும் கனமும் கொண்டவை தஞ்சைச் சோழமன்னர்கள் அளித்தனவே ஆகும். முதலாம் இராஜராஜசோழன் அளித்த பெரிய லீடன்

பட்டயம் இருபத்தொரு செப்பேடுகள் கொண்டது. அந்தச் சாசனம் நானூற்று நார்பத்து மூன்று வரிகளில் எழுதப்பட்டது. (எ.பி. இந்திகா, இருபத்திரண்டாம் வால்யூம்). முதலாம் இராஜேந்திர சோழன் வழங்கிய திருவேலங்காட்டுச் செப்பேடுகளில் மொத்தம் முப்பத்தோர் ஏடுகள் உள்ளன. கனமான வளையத்தோடு அவை ஏழாயிரத்துத் தொள்ளாயிரத்து என்பது தோலா எடை கொண்டனவாகும். அந்தச் சாசனம் எண்ணூற்றுப் பதினாறு வரியில் எழுதப்பட்டிருக்கிறது. (தெ. இ. சாசனங்கள், மூன்றாம் வால்யூம்). இவையாவற்றிலும் மிகப்பெரியது சமீபத்திலேகிடைத்த முதலாம் இராஜேந்திர சோழனுடைய கரந்தைத் தமிழ்ச் சங்கத்துச் செப்பேட்டுச் சாசனம். இரண்டாயிரத்து ஐந்து வரிகளுக்கு மேலாகச் செல்லும் அது ஐம்பத்தைந்து ஏடுகளில் எழுதப்பட்டிருக்கிறது. ஒவ்வோர் ஏடும் பதினாறரை அங்குல நீளமும் ஒன்பதரை அங்குல அகலமும் கொண்டது. அந்த ஏடுகளைக் கோக்கும் வளையம் இல்லாமல் ஏடுகள் மட்டுமே எண்ணியிரத்து அறுதூற்று நார்பத்தைந்து தோலா (அதாவது ஒன்பது மணங்குக்குமேல்) எடை உள்ளன. (புராதன இந்தியா, ஒன்பதாம் இதழ், 219-ஆம் பக்கம்).

ஒவ்வோர் ஏட்டிலும் எண் இடப்பட்டிருக்கும். ஆனால், சில கல்வெட்டுகளில் காணப்படுவதைப்போல் ஏட்டிலுள்ள வரிகள் எண் இடப்பட்டிருக்கமாட்டா. தற்காலத்தில் புத்தகங்களில் காணப்படுவதுபோல் பக்கங்களும் எண்ணிடப்பட்டிருக்கமாட்டா. ஏடுகளே கணக்கிடப்பட்டிருக்கும். அந்த எண் ஏட்டில் உள்ள துவாரத்தின்பக்கத்தில் இருக்கும். தென்னாட்டுச் சாசனங்கள் பொதுவாக ஏட்டின் முன்பக்கமே எண்ணிடப் பட்டிருக்கும். வடநாட்டுச் சாசனங்கள் சிலவற்றில் பின் புறம் இடப்பட்டுக் காணப்படுவதும் உண்டு.

அவ்வேடுகள் நீண்டனவாக இருந்தால் இடதுபுறத்திலும், சதுரமாக இருந்தால் தலைப்புறத்திலும், சுவடிகளைப்போலத் துளை இடப்பட்டு ஒரு வளையத்தில் ஒன்றாகக் கோக்கப்பட்டிருக்கும். அவ் வளையத்தில் அரசனுடைய முத்திரையை உடைய ஒரு முகப்பும் காணப்படும். மிகவும் அதிகமான ஏடுகளைக் கொண்ட சாசனங்களுக்கு இரண்டு வளையம் காணப்படுவதும் உண்டு. சில சமயங்களில் அரசனுடைய முத்திரை தனியாக ஒரு வளையத்தில் ஏடுகளோடு சேர்க்கப்பட்டிருப்பதும் உண்டு.

சாசனங்களிலே எழுத்துக்கள் பொதுவாக நீளவாக்கில் வரி வரியாகக் காணப்படும், உதாரணமாக ஒலைச்சுவடி உருவத்தில் உள்ள ஏடு

களில் எட்டின் அகலத்துக்குத்தக்கபடி ஏழெட்டுவரிகளே காணப்படும். பூர்ஜ பத்திரத்தை மாதிரியாகக் கொண்டு இப்போது காணும் புத்தகம் போன்ற வடிவில் உள்ள சாசனங்களின் ஏடுகளோ அச்சப் புத்தகத்தில் காண்பதுபோல நிறைய வரிகள் கொண்டு அமைந்திருக்கும்.

ஏடுகளை முதலில்காய்ச்சி வேண்டிய உருவத்தில் அடித்து வைத்துக் கொண்டு பிறகே அதன் மீது சாசனங்களைப் பொறிப்பார்கள் முதலில் பளிச்சென்று தெரியும் ஏதாவது ஒரு பொருளால் எட்டிலே எழுதுவார்கள். இதைப் பெரும்பாலும் நன்றாகப் படித்தவனே செய்வான். அப்பால் உளிபோன்ற கூரிய ஆயுதத்தால் அந்த எழுத்துக்களை எட்டில் செதுக்கி அமைப்பார்கள். தவறுகள் நேர்ந்து விட்டால், ஏதோ சில எழுத்துக்களையே சேர்க்கவேண்டுமானால் நடுவில் இடைச் செருகலாகச் சேர்ப்பார்கள். அதிகமாக இருந்தாலோ எழுதிய எழுத்துக்களை நீக்க வேண்டியிருந்தாலோ எட்டின் அந்தப் பகுதியை மறுபடியும் காய்ச்சி அடித்துப் பழைய எழுத்தை அழித்து விட்டுப் புதிதாக எழுதுவார்கள். அவ்விதம் காய்ச்சி அடிக்கும்போது பல சமயங்களில் பழைய எழுத்துக்கள் முற்றிலும் மறைந்து விடுவதில்லை. அம்மாதிரி ஒரு தரம் எழுதிய பிறகு மேலே திரும்பவும் புதிதாக எழுதிய சாசனங்கள் அவ்வப்போது கிடைக்கின்றன.

சில சாசனங்களில் எழுத்துக்களைக் கோடாக எழுதாமல் சிறு சிறு புள்ளிகளாக அமைத்து எழுதுவதும் உண்டு. பெரும்பாலும் அத்தகைய புள்ளிகள் முதலில் கீறிய கோட்டின் மீதே இடப்பட்டிருக்கும். (எபி. இந்திகா. நான்காம் வால்யூம், 56 பக்கம்).

இவ்விதம் எழுதாமல் வார்ப்பாகச் செய்யப்பட்ட சாசனம் ஒன்றும் கிடைத்துள்ளது. லோகௌராச் செப்பேடு அவ்விதம் அமைந்தது. எழுதவேண்டிய சாசனத்தை முதலில் மண்ணிலே சமம் செய்த தளத்தில் கூரிய எழுத்தாணியால் எழுதிப் பிறகு செம்பை உருக்கி அதன் மீது ஊற்றி அந்தச் சாசனத்தைத் தயாரித்திருக்கிறார்கள். அதனால் அந்தச் சாசனத்தில் எழுத்துக்கள் பள்ளமாக இல்லாமல் எடுப்பாக உள்ளன.

கவிஞன் ஒருவன் தன்னை ஆதரித்த வேந்தனைப் புகழும்போது அவனுடைய நாட்டிலே செம்புக்குப் பஞ்சம் ஏற்பட்டுவிட்டதென்று வருணிக்கிறான்; அரசன் ஏராளமாக அளித்த பூதானங்களைச் செம்பேட்டில் எழுதி வழங்குவதிலேயே செம்பு முழுவதும் செலவாகி விட்டதென்றும், மேலும் அவன் வழங்குவதை எழுதுவதற்குச் செப்

பேடுகள் இல்லையென்றும் கூறுகிறான். (வல்லாளனுடைய போஜப் பிரபந்தம்). அதை முற்றிலும் கற்பனை என்று சொல்லிவிடுவதற்கில்லை. சோழமன்னர்கள் அளித்த தானங்களைத் தெரிவிக்கும் செப்பேடுகளைக் கவனித்தால் கவியின் கூற்று ஓர் அளவு உண்மையே என்று கொள்ளலாம். இதை வலியுறுத்துவதேபோல, பழைய காலத்தில் சாசனங்கள் பொறித்திருந்த செப்பேடுகளைத் திரும்பவும் காய்ச்சி அடித்துப் புதிய சாசனங்களை எழுதுவதற்கு உபயோகித்த பல ஏடுகள் கிடைத்துள்ளன. அவ்விதம் காய்ச்சி அடித்த காலங்களில் அந்த ஏடுகளின் பழைய எழுத்துக்கள் முற்றிலும் மறைந்து விடாமல் சிற்சில சமயங்களில் நன்றாகத் தெரிகின்றன. நூதிமடுகு என்னுமிடத்திலிருந்து கிடைத்த விஜயநகர வேந்தனான இரண்டாம் தேவராயனுடைய செப்பேட்டுச் சாசனத்தில் ஓர் ஏட்டிலே வேங்கிச் சாளுக்கியர்களுடைய பிரசஸ்தி பத்தாம் நூற்றாண்டுத் தெலுங்கு எழுத்திலே பொறிக்கப்பட்டிருப்பதைக் காணலாம். (எபி. இந்திகா, இருபத்தைந்தாம் வால்யூம்).

செம்பிலே எழுதப்பட்டிருக்கும் சாசனங்கள் பெரும்பாலும் ஏட்டு உருவத்திலேதான் கிடைக்கின்றன. எனினும், கலப்பை, கோடரி என்பன போன்ற வேறு உருவங்களிலும் அவ்வப்போது நமக்குக் கிட்டியுள்ளன. கி. பி. பதின்மூன்று அல்லது பதினான்காம் நூற்றாண்டில் வழங்கிய தமிழ் எழுத்துக்களில் சித்திரமேழிப் பெரிய நாட்டவர் என்னும் ஸ்தாபனத்தாரின் சாசனம் ஒன்று செம்பிலே செய்யப்பட அவர்களுடைய சின்னமான கலப்பை உருவத்தின்மீது பொறிக்கப்பட்டிருக்கிறது.

பிஷாவருக்குப் பக்கத்தில் உள்ள குர்ரம் என்னும் இடத்திலிருந்து ஹர்மிகை குடை முதலியவை யாவற்றையும் உடைய ஸ்தூபத்தின் சிறு உருவத்தில் அமைந்த பேழை ஒன்று செம்பிலே கிடைத்துள்ளது. அதன் அடியில் உள்ள சதுரமான பீடத்தின் நான்கு புறங்களிலும் புள்ளி புள்ளியாகத் துவாரம் செய்யப்பட்ட கரோஷ்டி எழுத்துக்களால் ஆன சாசனம் ஒன்று இருக்கிறது. சாக்கிய முனிவருடைய புனித உடலின் சின்னங்கள் அதிலே சேமிக்கப்பட்டிருந்த செய்தியைத் தெரிவிக்கிறது அந்தச் சாசனம். (எபி. இந்திகா, பதினெட்டாம் வால்யூம்).

6. இரும்பு: நீண்ட காலமாகவே மக்கள் இரும்பைப் போர்க்கருவிகள், உழவுக்கு வேண்டிய உபகரணங்கள், மற்றும் வாழ்க்கைக்கு அத்தியாவசியமாக வேண்டிய சாமான்கள் ஆகியவற்றைச் செய்வதற்கு உபயோகித்து வந்திருக்கிறார்கள். எனினும், சாசனம் எழுதுவதற்கு

அந்த உலோகத்தைப் பெரும்பாலும் உபயோகித்ததில்லை. இருந்தாலும் ஒன்றிரண்டு கிடைக்கின்றன. சந்திரன் என்னும் அரசன் ஒருவனைப் பற்றிய சாசனம் பொறிக்கப்பட்ட இரும்புத் தூண் ஒன்று (தில்லில் குதுப்மினார் சமீபம் உள்ள) மேஹருளியில் கிடைக்கிறது. (குப்த சாசனங்கள், 139 பக்கம்). இருபத்துமூன்று அடி எட்டு அங்குலம் உள்ள அந்தத் தூண் ஆறு டன் கனம் உள்ளதென மதிப்பிடுவர். அதைப் போல் இருமடங்கு உயரம் உள்ள மற்றொரு தூண் உடைந்து துண்டுகளாகச் சிதைந்து தாரா நகரத்தில் கிடைக்கிறது. அதிலே மொகலாய மன்னனை அக்பருடைய பாரசீக மொழிச் சாசனம் ஒன்று காணப்படுகிறது. இன்னும் நாகரி எழுத்திலும் பாரசீக எழுத்திலும் சில பெயர்கள் பொறிக்கப்பட்டுள்ளன. இவை தவிர, இரும்பால் செய்யப்பட்ட சிவபெருமான் ஆபுதமான திரிகுலம், போரில் உபயோகிப்பதற்காகச் செய்த பிரங்கிக்குண்டுகள் ஆகியவற்றின்மீதும் சாசனங்கள் பொறிக்கப்பட்டுள்ளன. ஆனால் அவை யாவும் பதினேந்தாம் நூற்றாண்டையும் அதற்குப் பிற்பட்ட காலத்தையும் சார்ந்தவை.

### உலோகமல்லாதவை

சாசனங்களை எழுதுவதற்கு உலோகங்களிலே செம்புதான் அதிகமாக உபயோகப்படுவதுபோல, உலோகமல்லாதவற்றிலே கருங்கல் தான் முக்கியமானது. எனினும், பளிங்கு, மரத்தூண், பலகைகள், மண்பாண்டம், சுட்டமண், செங்கல், சங்கு, ஆமையோடு, தந்தப்பலகை முதலிய பலவற்றிலும் சாசனங்கள் பொறித்திருக்கக் காண்கிறோம்.

1. பளிங்கு: பளிங்கிலே எழுதியுள்ளதாகக் கிடைக்கும் சாசனம் மிகவும் அரிது. அவ்வகைக் கல் எளிதில் கிட்டக்கூடிய பொருள் அல்ல. அன்றி அது உறுதியும் செறிவும் கொண்டிருப்பதால் சுலபமாக அதிலே சாசனங்களைப் பொறிக்க முடியாது. உண்மையில் இப்போது நமக்குக் கிடைத்திருக்கும் பளிங்குச் சாசனமும் அதிலே வெட்டப்பெறாமல் கீறப்பெற்றிருப்பதையே காண்கிறோம். கிருஷ்ண ஜில்லா பட்டிப் ரோலுவிருந்த பெளத்த ஸ்தூபத்தினின்றும் கிடைத்த பொருள் களுள் சுமார் இரண்டேகால் அங்குலம் உள்ள ஆறுபட்டை ஸ்படிகக் கல்லும் ஒன்று. காலேயரைக்கால் அங்குல அகலம் உள்ள அதன் ஆறுபட்டைகளில் ஒவ்வொன்றிலும் எழுத்துக்கள் கீறப்பட்டுள்ளன. (எபி. இந்திகா, இரண்டாம் வால்யூம்). அந்தக் கல்லின் மத்தியிலே நீளவாக்கில் ஒரு சிறு துவாரம் காணப்படுவதால் அதை ஒரு கயிற்றிலே கோத்துத் தாயத்துப்போல அணிந்துகொள்ள உபயோகித்து வந்ததாகக் கொள்ளலாம். நந்தபுரத்தைச் சேர்ந்த மங்கையொருத்தி



தான் நோய் நீங்கிப் பிழைத்தெழுந்ததற்காகப் பிரார்த்தனை செலுத்து வதற்காக அளித்ததாகும் என்று அதை ஆராய்ச்சியாளர் கூறுவர்.

இன்னும் பளிங்கிலேயே செய்த பேழைகள், சம்புடங்கள் போன்ற வேறு உருவங்களும் பட்டிப்போலு, ஸோநாரி, கோல்ஹாப் பூர் முதலிய இடங்களிலிருந்து கிடைத்துள்ளன. அவற்றிலே சாசனம் ஏதும் காணப்படவில்லை. எனினும், அந்தப்பொருள்கள் எதற்காக அளிக்கப்பெற்றன வென்பதைத் தெரிவிக்க வேறு வழிகள் கையாளப் பட்டுவந்தன. சோநாரியிலிருந்து கிடைத்த பேழைக்குள் முக்கால் அங்குல நீளமும் அரை அங்குல அகலமும் உள்ள ஒருகல்துண்டில் இரு புறங்களிலும் எழுதிவைத்திருந்தனர். (ராயல் ஏஷ்யாடிக் ஸோஸைட்டி ஜர்னல், 1905). கோல்ஹாப்பூரிலோ அந்தப் பேழை ஒரு சிறு கருங் கம்பெட்டியில் வைத்துப் பாதுகாக்கப்பட்டிருந்தது. அந்தப் பெட்டி யின் மூடியில் சாசனம் காணப்படுகிறது. (மேலை இந்தியப் புதை பொருள் ஆராய்ச்சி, பத்தாம் வால்யூம், படம் 1).

2. செங்கல் : புண்ணிய சுலோகங்கள் எழுதிய கற்கள் அவ்வப் போது நம் நாட்டின் பல பாகங்களிலும் கிடைக்கின்றன. எனினும் அவை தென்னாட்டில் கிடைக்கவில்லை. மெசோபடோமியா முதலிய மேற்கு ஆசிய நாடுகளிலே செங்கல்லில் சாதாரணமாக எழுதும் பழக் கம் முன்னாளில் இருந்துவந்திருக்கிறது. ஆயினும் அவ்விதம் நம் நாட்டில் இருந்ததில்லை. ஒன்றிரண்டு எழுத்துக்களைக் கொண்ட செங்கற்கள் கோயில் சுவர்களிலும் மாடங்களிலும் வைத்துக் கட்டப் பட்டிருந்ததை நாம் காணலாம். உத்தரப் பிரதேசத்தில் கோரக்பூர் ஜில்லா பிதாரி என்னும் இடத்தில் ஸ்ரீகுமாரகுப்தன் என்ற பெயர் பொறித்த செங்கல்கள் கண்டெடுக்கப்பட்டுள்ளன. (கன்னிங்ஹாம் பிளாட் புதைபொருள் ஆராய்ச்சி அறிக்கை, முதல் வால்யூம், 94 பக்கம்). அதே ஜில்லாவில் கோபால்பூர் என்னுமிடத்தில் புத்தமதக் கிரந்தங் களான சூத்திரங்கள் சிலவற்றைப் பொறித்துள்ள செங்கல்கள் கிடைத் துள்ளன. அவற்றுள் ஒன்று சிராவஸ்தியில் புத்தபகவான் செய்த உபதேசத்தைக் கொண்ட சூத்திரத்தின் ஸம்ஸ்கிருத வடிவம் ஆகும். (வங்காளத்து ஏஷ்யாடிக் ஸோஸைட்டி ஜர்னல், 1896, நடவடிக்கை கள் பகுதி, பக்கம் 99).

அந்த உத்தரப் பிரதேசத்திலேயே ஜான்பூர் ஜில்லாவிலிருந்து கிடைத்த செங்கற்பலகை ஒன்றில் வாங்கிய கடனுக்கு ஈடுகாட்டிக் கி.பி. 1217-ஆம் ஆண்டில் எழுதிக்கொடுத்த நில அடைமானப் பத்திரம் பொறிக்கப்பட்டிருக்கிறது. (மேடி 1850-ஆண்டு, பக்கம் 454).

யமுனை நதி உற்பத்தி ஸ்தானத்தையொட்டிய குறுகிய பள்ளத் தாக்கில் உள்ள ஜகத்கிராமம் என்னுமிடத்தில் நடந்த புதை பொருள் ஆராய்ச்சியிலே சாசனங்களைக்கொண்ட செங்கற்கள் அதிகமாகக் கண்டெடுக்கப்பட்டன. சுமார் கி.பி. மூன்றாம் நூற்றாண்டு எழுத்துக்களில் பொறிக்கப்பட்ட அந்தச் செங்கற்களில் ஒரு வடமொழிச் சுலோகமே திரும்பத் திரும்பக் காணப்படுகிறது. அதிலிருந்து சீலவர்மன் என்பான் நான்காவது தடவையாக அசுவமேத யாகம் செய்த இடம் அது என்று தெரியவருகிறது. சீலவர்மன் என்பான் அந்நாளிலே ஆண்ட யௌதேயவமிசத்து ராஜகுமாரர்களுள் ஒருவரை இருத்தல்வேண்டும் என்று ஆசிரியர்கள் கருதுவர். (ஜர்னல் ஆப் ஒரியண்டல் ரிஸர்ச், இரு பத்தோராம் வால்யூம்).

3. களிமண்ணும், சுட்டமண்ணும்:—செங்கல்லைப் போலவே சாசனம் எழுதிய களிமண் பலகைகளும் அதிகமாகக்கிடைத்துள்ளன. அவை சில சமயங்களில் இயற்கையாகவே வெய்யிலில் காய்ந்து கெட்டி யாகவிடப்பட்டிருக்கும். மற்றும் சில சமயங்களில் சுடப்பட்டும் காணப் படும். பெரும்பாலும் அவை புத்தமதத்தார் காணிக்கை செலுத்தியன வாக இருக்கும். அதனால் அவற்றில் அந்த மதத்தின் மூலாதாரமான புண்ணிய சுலோகங்கள் பொறிக்கப்பட்டிருக்கும். சில சமயங்களிலே அதனோடு ஸ்தூப உருவங்களையும் காணலாம். ஒரொரு சந்தர்ப்பத்தில் புத்தபகவானுடைய உருவமும் சேர்க்கப்பட்டிருக்கும்.

புத்தமதம் அல்லாத வேறு மதத்தினரும் இவ்விதம் காணிக்கை யாகச் செலுத்திய களிமண் பலகைகளும் கிடைத்துள்ளன. பஞ்சாபில் லாதியானாவுக்குப் பக்கத்தில் உள்ள ஸுநேத் என்னுமிடத்தில் 'சங்கா நாராயணர்'களுக்குக் காணிக்கை செலுத்திய விவரம் பொறிக்கப்பட்ட களிமண் பலகைகள் கிடைத்துள்ளன. (ராயல் ஏஷ்யாடிக்கெஸொஸைட்டி, ஜர்னல், 1901). சிலவற்றிலே ஒரு பக்கத்தில் 'ஸ்ரீ விஷ்ணுதாஸஸ்ய' என்பது போலக் காணிக்கை செலுத்தியவன் பெயரும் பொறிக்கப்பட்டிருக்கும்.

கண்மண்ணால் செய்யப்பட்டுக் கிடைத்தவற்றுள் முக்கியமானவை எழுத்துக்கள் பொறிக்கப்பெற்ற களிமண் முத்திரைகள். வங்காளத்து முஜபர்பூர் ஜில்லாவில் உள்ள பஸார் என்னுமிடத்தில் தோண்டிய போது இத்தகைய களிமண் முத்திரைகள் ஆயிரத்து ஒரு நூற்றுக்கு மேல் கிடைத்தன. அவற்றை ஆராய்ந்தபோது நூற்றிருபதுக்கு மேற்பட்ட வகைகளும் எழுதுவதற்கும் மேற்பட்ட மாதிரிகளும் அதிலே

இருந்த விவரம் தெரியவந்தது. அவை பலவகைப்பட்ட மனிதர்கள், அதிகாரிகள், சபையினர் ஆகியோருடைய அதிகார முத்திரைகளாகும். ஒன்றிலே 'ஸ்ரீ க்டோத்கச குப்தஸ்ப' என்று காணப்படுகிறது. குப்த அரசனான க்டோத்கசகுப்தனே அவன். இன்னும் மூன்றிலே துருவ சுவாமிநி என்பவன் பெயர் காணப்படுகிறது. துருவதேவி என்று சாசனங்களிலே குறிக்கப்பட்டிருக்கும் இரண்டாம் சந்திரகுப்தன் மனைவியே அவன். (இந்தியப் புதை பொருள் இலாகா ஆண்டு அறிக்கை, 1904).

பீஹாரில் பாட்னா ஜில்லாவில் நாலந்தா என்னுமிடத்திலிருந்து புதகுப்தனுடைய களிமண் முத்திரை ஒன்று சிதிலமாகக் கிடைத்துள்ளது. அதிலே அவனுடைய வமிசாவளி நான்கு தலைமுறைகளுக்குக் கொடுக்கப்பட்டுள்ளது. (இந்தியன் ஹிஸ்டாரிகல் குவார்ட்டர்லி, பத்தொன்பதாம் வால்யூம்). அதனால் குப்த வமிசத்திலே அவனுடைய நிலை நமக்கு நன்கு விளங்குகிறது. மத்திய பாரதத்தில் உள்ள சாகர் ஜில்லா ஏரண் என்னுமிடத்திலிருந்து 1838-ஆம் ஆண்டில் புதகுப்தனுடைய சிற்றரசனான ஸூர்யசந்திரன் என்பான் சாசனம் ஒன்று கிடைத்தது. (குப்த சாசனங்கள், 88-பக்கம்) அதிலிருந்து ஒரு நூற்றாண்டுக்காலம் வரையில் நிச்சயமாகத் தெரியாதிருந்த புதகுப்தனுடைய ஸ்தானம் இந்த நாலந்தா முத்திரையினால் நிர்ணயமாகிறது.

சுட்டமண்ணிலே செய்த முத்திரைகளும் கிடைத்துள்ளன. அவ்விதம் கிடைத்தவற்றுள் உத்தரப்பிரதேசத்துப் புலந்தஷர் என்னுமிடத்திலிருந்து கிடைத்ததை முக்கியமானதாகக் கூறலாம். (இ. ஆ., பதினெட்டாம் வால்யூம்). கோரக்பூர் ஜில்லா காசியா என்னுமிடத்திலிருந்து கி.பி. ஐந்தாம் நூற்றாண்டு எழுத்துக்களால் பொறிக்கப்பட்ட சாசனத்தையுடைய புத்தபகவானுடைய சுட்டமண் விக்கிரகம் ஒன்றும் கிடைத்திருக்கிறது. (பஞ்சாப், ஐக்கிய மாகாண வட்டத்தின் புதை பொருள் ஆராய்ச்சி இலாகா ஆண்டு அறிக்கை, 1904-5).

நாலந்தாவிலிருந்து கிடைத்த மௌகரி மன்னன் சர்வவர்மனுடைய சுட்டமண்முத்திரையும் (எபி. இந்திகா, இருபத்துநான்காம் வால்யூம்) கோரக்பூர் ஜில்லா ஸோநாக் என்னும் இடத்திலிருந்து கிடைத்த அவனுடைய மகன் அவந்திவர்மனுடைய சுட்டமண் முத்திரையும் (ஹி. இருபத்தேழாம் வால்யூம்) அவ்வமிசத்து அரசர்களின் சரித்திர ஆராய்ச்சிக்கு மிகவும் முக்கியமானவை.

4. மண் பாண்டம்:—பாளை, சாடி போன்ற வடிவங்கள் உள்ள பழையகாலத்து மண்பாண்டங்கள் எழுத்துக்கள் பொறிக்கப்பட்டு அவ்

வப்போது கண்டெடுக்கப்படுகின்றன. ஆந்திரப்பிரதேசத்தில் உள்ள நந்தாரு என்னுமிடத்திலிருந்து கிடைத்ததைச் சிறந்த எடுத்துக் காட்டாகக் கொள்ளலாம். சாலிஹுண்டத்துப் பெளத்த ஸ்தூபத்திலிருந்தும் இத்தகைய பாளை ஒன்று கிடைத்துள்ளது. (ஷெ. இருபுத் தெட்டாம் வால்யூம்; இந்தியப் புதை பொருள் இலாகா ஆண்டறிக்கை, 1920).

புதுச்சேரிக்குப் பக்கத்தில் உள்ள அரிக்கமேட்டிலிருந்து எழுத்துக்கள் பொறித்த மண்பாண்டச் சில்லுகள் தோண்டி எடுக்கப்பட்டுள்ளன. அந்தச் சில்லுகளில் காணும் எழுத்துக்கள் கி. பி. முதல் அல்லது இரண்டாம் நூற்றாண்டில் வழங்கிவந்த பிராமி எழுத்துக்களாகும். அந்நாளில் அவ்விடம் முக்கியமான ஒரு வியாபார ஸ்தலமாக விளங்கியது என்பதையும் ரோம ராஜ்யத்தோடு நெருங்கிய தொடர்பு பெற்றிருந்த தென்பதையும் அவ்விடம் நடந்த ஆராய்ச்சியிலிருந்து அறிகிறோம். (புராதன இந்தியா, இரண்டாம் இதழ்.)

ஸாஞ்சீக்குப் பக்கத்தில் உள்ள போஜ்பூரில் கிடைத்த புராதனப் பொருள்களுள் ஒரு மண்பாண்டப் பேழை சரித்திர முக்கியத்துவம் வாய்ந்தது. அதன் மூடியில் சுண்ணாம்பு பூசி அதன்மீது மசியினால் எழுதப்பெற்றிருக்கிறது. இப்போது அந்த எழுத்துக்களின் மங்கிய ரேகைகளே தெரிகின்றன வாதவின் என்ன எழுதப்பட்டிருக்கிறதென்பதைப் படிக்க முடியவில்லை. (கன்னிங்ஹாம் எழுதிய 'பிஸா தோப்புகள்', பக்கம் 331). அம்மாதிரி மசியினால் எழுதப்பெற்ற கரோஷ்டி சாசனங்களைக் கொண்ட மூன்று மண்பாண்டச் சாடிகள் (இப்போது பா கி ஸ் த ர னி ல் வடமேற்கு மாகாணப் பகுதியில் சேர்ந்துள்ள) சார்ஸதாவுக்குப் பக்கத்தில் பாலாட்டு - டேரி குன்றிலிருந்து கிடைத்துள்ளன. அவ்விடத்திலிருந்த புத்த பிக்ஷுக்களின் சங்கத்துக்கு அந்தச் சாடிகள் காணிக்கை செலுத்தப் பெற்ற விவரத்தைக் கூறுகின்றன அந்தச் சாசனங்கள். (இந்தியப் புதை பொருள் இலாகா ஆண்டு அறிக்கை, 1903.)

கத்தியவார்ப் பிரதேசத்திலிருந்து அங்கே ஆண்ட வல்லப - மைத்திரக ராஜ குமாரர்களில் ஒருவனான குஹசேனன் என்பான் பெயரையும், கி. பி. 566-7-ஆம் ஆண்டுக்குச் சமமான காலத்தையும் குறிக்கும் சாசனம் ஒன்று பொறிக்கப்பட்ட மண் பாளையின் உடைந்த பகுதி கிடைத்துள்ளது. (இ. ஆ., பதினான்காம் வால்யூம்).

5. மரம் :-மரத்தைச் சாசனம் பொறிப்பதற்கு ஏற்ப நீண்டகாலம் அழியாமல் இருக்கக்கூடிய பொருளாகக் கருதுவதில்லை. எனினும்

அவ்விதம் மரத்திலே பொறிக்கப்பெற்ற சாசனங்கள் சில கிடைத்துள்ளன. சட்டல்கர் பகுதியில் கிராரீ என்னுமிடத்திலிருந்து கி.பி. இரண்டாம் நூற்றாண்டுப் பிராமி எழுத்துக்களில் வெட்டப்பட்ட சாசனத்தையுடைய மரத்தாண் ஒன்று பழைய குளத்தின் அடியிலிருந்து தோண்டி எடுக்கப்பட்டது. (எபி. இந்திகா, பதினெட்டாம் வால்யூம்). தூதிர்ப்புடவசமாக அது காய ஆரம்பித்ததும் அதிலே வெடிப்புக்கண்டு சாசனத்தின் பெரும்பகுதியோடு அதன் மேற்புறணி பெயர்ந்துபோய் விட்டது. இப்போதுள்ள நிலையிலே அந்தத் தூணில் வெட்டப்பட்டுள்ள சாசனம் எதைக் குறிக்கிறதென்று நிச்சயமாகக் கூறமுடியாது. எனினும் கிடைத்திருக்கும் பகுதியிலே முன்னுளில் வழக்கிலிருந்த அரசாங்க உயர் பதவிகள் சிலவற்றின் பெயர்களும் அவற்றை வகித்து வந்தவர்கள் பெயர்களும் காணப்படுவதாகக் கொள்ளலாம்.

இதேபோல மரத்திலே பொறிக்கப்பட்ட மற்றொரு சாசனம் சமீபத்திலே கிடைத்துள்ளது. பூனாவுக்குச் சமீபமாகப் பாஜம் என்னுமிடத்தில் புத்தவிஹாரம் ஒன்று உள்ளது. அந்தச் சைத்தியத்தின் (மேற்கூரை) விதானத்தில் அமைத்திருக்கும் மாப்பாவுச் சட்டம் ஒன்றில் கி.மு. இரண்டாம் நூற்றாண்டைச் சேர்ந்த பிராமி எழுத்துக்களில் ஒரு சாசனம் வெட்டப்பட்டிருக்கிறது. (இந்தியன் ஆர்க்கியாலஜி, அறிக்கைச் சுருக்கம், 1955-56, பக்கம் 29, படம் 44). அதிலிருந்து அந்தச் சைத்தியம் எப்போது ஏற்பட்டதென்பது நன்கு விளங்கும்.

மரத்தாலான பொருள்கள்மீது எழுதும் பழக்கத்தைப் பற்றிய பழமையான குறிப்புகள் புத்தமத நூல்களிலே காணப்படுகின்றன. இறந்தபின் சுவர்க்கத்தை யடையலாம் என்ற நோக்கத்துடனோ, மறுபிறப்பில் பொருளும் புகழும் அடைய வேண்டும் என்ற நோக்கத்துடனோ பிராணத்தியர்க்கம் செய்ய விரும்புகிறவர்களுக்கு அந்த முறைகளைப் பற்றி எதையும் எழுதிக்கொடுக்கக் கூடாது என்று புத்த பிக்ஷுக்களுக்குத் தடைவிதித்துக் கூறுமிடத்தில் பிக்ஷுக்கள் அவ்விதம் பலகைகளில் எழுதக்கொடுக்கக்கூடாது என்று விரயபிடகத்தில் குறிக்கப் பட்டுள்ளது. புத்தஜாதகக் கதைகளிலும் அந்நாளிலே எழுத்து அறியப்புகும் சிறுவர்கள் எழுதுவதற்கு மரப் பலகைகளை உபயோகித்து வந்த செய்தி காணப்படுகிறது. இன்னும் அந்நாளிலே, மூங்கில் துண்டுகளைப் புத்தபிக்ஷுக்கள் தங்கள் அடையாளச் சீட்டுக்களாகக் கொண்டிருந்தனர் என்றும் தெரியவருகிறது. அந்தத் துண்டுகளில் அந்தப் பிக்ஷுக்களின் பெயரோ அல்லது ஏதோ சில அடையாள எழுத்துக்களோ பொறிக்கப்பட்டிருக்குமாம்.

கூத்தரப அரசனான நாஹபாணன் காலத்துச் சாசனம் ஒன்றில் கடன்கள் பற்றிய ஒப்பந்தங்களை நகரத்தார் மன்றத்திலே பலகையில் எழுதி வெளியிட்டுவந்த செய்தி குறிக்கப்பட்டுள்ளது. (மேலை இந்தியப் புதைபொருள் ஆராய்ச்சி, நான்காம் வால்யூம், நாசிக் கல்வெட்டுக்கள், நெ. 7). சட்டசம்பந்தமான விவரங்களை உரைக்கும் நூலான காத்யாயன ஸ்மிருதியில் நியாய மன்றத்திலே வழக்குகளைப் பற்றிப் பலகைகளில் (பாண்டுரேகை) சுண்ணாம்புக்கட்டியால் எழுதவேண்டும் என்று கூறப்பட்டிருக்கிறது.

பர்மாவிலே மரப் பலகைகளுக்குப் பொன் அல்லது வெள்ளி நிறம் கொண்ட எண்ணெய்க்கலவைபூசி அதன்மீது கறுப்பு எழுத்துக்களால் அவர்களுடைய மத சம்பந்தமான நூல்களை எழுதி வந்தார்கள். அவ்விதம் எழுதிய பலகைகள் சில லண்டன் நகரத்துப் பிரிட்டிஷ் மியூஸியத்தில் உள்ளன. எனினும் இத்தகைய பலகைகள் நம் நாட்டில் கிடைக்கவில்லை. அஸ்ஸாம் பகுதியிலிருந்து மரப்பலகையில் எழுதப்பெற்ற நூல் ஒன்று இங்கிலாந்தில் போட்லீன் லைப்ரரியில் இருப்பதாக விண்டர்ரிட்ஸ் என்னும் ஜர்மன் ஆசிரியர் கூறினார் என்று டாக்டர் பீலர் எழுதியிருக்கிறார்.

மூங்கிலில் எழுதும் பழக்கமும் உண்டு. இவ்விதம் எழுதப் பெற்ற மூங்கில் குழாய் ஒன்றை நான் பார்த்திருக்கிறேன். அது கேரள நாட்டுப் பழைய கொச்சி சம்ஸ்தானப் பகுதியிலிருந்து கிடைத்தது. இரண்டு கணுக்களுக்கும் இடைப்பட்ட பாகத்தில் மூங்கிலின் மேல் புறணியில் எழுத்தாணி போன்ற கூரிய ஆபுதத்தால் கீறி எழுதப்பட்டிருந்தது. ஒரு பக்கத்தில் உள்ள கணுவை எடுத்துவிட்டு, நடுவில் உள்ள குழாயில் நொச்சியிலே, வேப்பந்தழை போன்றவற்றைச் செருகி அது பூச்சியடிக்காமல் பாதுகாக்கப்பெறுவது வழக்கமாம். முக்கியமாக நீண்டகாலம் காக்கவேண்டியவற்றை இவ்விதம் மூங்கில்மீது எழுதும் பழக்கம் சமீபகாலம்வரையில் மலையாள தேசத்தில் இருந்துவந்ததாம். இத்தகைய மூங்கில்கள் இன்றைக்கும் கிடைக்குமாம்.

6. கருங்கல் பாறை: நமக்குக் கிடைக்கும் சாசனங்களில் பெரும் பகுதி கல்லில் பொறிக்கப்பட்டிருப்பனவே. தென் இந்தியாவிலே அவை பெரும்பாலும் கோயில் சுவர்களிலே வெட்டப்பட்டிருக்கும். அந்தச் சாசனங்களில் காணப்பெறும் விஷயங்கள் அநேகமாக அந்த அந்தக் கோயில்களுக்குச் சம்பந்தம் கொண்டிருந்தமையாலே போலும் அவை அங்ஙனம் கோயில் சுவர்களில் பொறிக்கப்பட்டுவந்தன என்று கொள்ளலாம். எனினும் பழைய சாசனங்கள், முக்கியமாகக் குடை

வரைக் கோயில்களில் உள்ளவை, சுவர்களில் பொறிக்கப்பட்டிருக் காமல் தூண்களிலோ உத்தரங்களிலோ பொறிக்கப்பட்டிருக்கின்றன. பல்லவமன்னனான மஹேந்திரவர்மன் பாறைகளில் குடைவித்து நிர் மாணித்த கோயிலில் காணும் கல்வெட்டுக்களை இதற்கு எடுத்துக்காட் டாகக் கொள்ளலாம். முன்னாளிலே செங்கல் முதலிய அழியக்கூடிய பொருள்களால் எழுப்பப் பெற்ற கோயில்களின் சாசனங்களைத் தனிக் கற்களில் பொறித்து அங்கே போட்டு வந்தனர் என்பதை முன்னரே (மேலே ௩௩-ஆம் பக்கம்) நாம் குறிப்பிட்டிருக்கிறோம். அத்தகைய கற்கள் இப்போதும் கோயிலிலோ அதற்குப் பக்கத்திலோ அல்லது சிற்சில சமயங்களில் அந்த ஊர்களிலே நட்டிருப்பதைக் காணலாம்.

சில சமயங்களில் கோயில் கட்டிடங்களிலும் பிராகாரங்களிலும் கல்வெட்டுப் பொறிக்கப்பட்ட கற்களைப் பாவித் தளம் அமைத்திருப் பதைக் காணலாம். பிற்காலத்தில் கோயிலை ஜீர்ணோத்தாரணம் செய்து பிரித்துக்கட்டியபோது கல்வெட்டுக்களைக் கவனியாமல் கற்களை அங்ஙனம் அமைத்ததாலேயே நாம் அவ்விதம் காணநேரிடுகிறது. எனினும் சில இடங்களில் கல்வெட்டுக்களை அவ்விதம் தளத்திலேயே பொறித்திருந்திருக்கிறார்கள். இராமநாதபுரம் ஜில்லா குன்றக்குடியில் உள்ள குடைவரைக் கோயில் ஒன்றன் முன்புறம் உள்ள தாழ்வாரத் திலே இத்தகைய கல்வெட்டு பொறிக்கப்பட்டிருப்பதைக் காண லாம். பாறையிலேயே அமைக்கப்பட்ட அந்தத் தாழ்வாரத்தின் நடுவில் ஆரம்பித்து அதன் கீழே செங்குத்தாக உள்ள படங்கிலும் அதைத் தொடர்ந்து எழுதியிருக்கிறார்கள். கோயிலுக்கு வரும் சேவார்த்திகள் நடந்து நடந்து எழுத்துக்கள் தேய்ந்துபோய் இப்போது அந்தச் சாசனம் படிக்கமுடியாத நிலையில் இருக்கிறது.

கோயில் சுவர்களைப் போலவே ஊர்ப்புறங்களில் உள்ள பாறை களிலும் சாசனங்களைப் பொறித்து வந்திருக்கிறார்கள். ஊருக்குப் பக்கத்தில் இருப்பது, யாவரும் எளிதில் காணும் விதமாகப் பிரதான மான இடத்தில் அமைந்திருப்பது, என்பனபோன்ற காரணங்களாலே போலும் அவ்விதம் கல்வெட்டுக்களைப் பொறிக்கப் பாறைகளைத் தேர்ந் தெடுத்தனர் என்னலாம். நம் நாட்டின் பல பாகங்களிலும் உள்ள அசோக மன்னன் சாசனங்களை இந்தவகைக்குச் சிறந்த உதாரணமாகக் கொள்ளலாம். குடும்பான்மலையில் உள்ள சங்கீதக் கல்வெட்டும் (மேலே ௨௩௬-ஆம் பக்கம்) இந்த வகையைச் சேர்ந்ததுதான்.

இவ்விதம் பாறைகளில் கிடைக்கும் சாசனங்கள் சில சமயங்களில் ஒற்றையாக இருக்காது. பின்னால் வந்த தலைமுறையினரும் முதலில் பொறித்த சாசனத்துக்குப் பக்கத்திலும் அதைத் தொடர்ந்தும் தங்

கள் கல்வெட்டுக்களைப் பொறித்து வந்திருக்கிறார்கள். னௌராஷ்டிரப் பிரதேசத்தில் உள்ள கிர்நார் மலையில் கிடைக்கும் சாசனங்களை உதாரணமாகக் காட்டலாம். அதிலே அசோகமன்னன் கல்வெட்டுக்கள் காணப்படுகின்றன. அவற்றைத் தொடர்ந்து கி. பி. 150-ஆம் ஆண்டு கொண்ட மஹாசூத்ரப அரசன் ருத்திரதாமனுடைய கல்வெட்டு ஒன்றும் அங்கு இருக்கிறது. இன்னும் ஐந்தாம் நூற்றாண்டின் மத்திய காலத்தைச் சார்ந்த குப்த மன்னன் ஸ்கந்த குப்தனுடைய சாசனமும் காணப்படுகிறது.

மைசூரில் சிரவண பெள்ளகொளத்தில் உள்ள சந்திரகிரி மலையில் ஏராளமான சாசனங்கள் உள்ளன. சமணர்களிலே திகம்பரப்பிரிவினர் மிகப் பழங்காலத்திலே தென்னாடு போந்து சிரவண பெள்ளகொளத்தில் தங்கிய செய்தியைத் தெரிவிப்பதாக உள்ள ஜைன ஆசிரியர் பிரபா சந்திரருடைய நிசீதிகை உள்படப் பல சாசனங்கள் கிடைக்கின்றன.

திருநெல்வேலி ஜில்லாவில் கழுகுமலையில் பாரையிலே வரிசை வரிசையாக நூற்றுக்கு மேற்பட்ட உருவங்கள் செதுக்கப்பட்டுள்ளன. அவற்றிலே ஒவ்வொன்றின் கீழேயும் கி. பி. எட்டாம் நூற்றாண்டில் வழங்கிவந்த வட்டெழுத்துக்களில் பொறிக்கப்பட்ட சாசனங்கள் வெட்டப்பட்டுள்ளன. அந்த உருவங்கள் யாரைக் குறிக்கின்றன வென்பதையும் அவற்றை யார் யார் செய்துவைத்தார்கள் என்பதையும் அக்கல்வெட்டுக்கள் (தெ. இ. சாசனங்கள், ஐந்தாம் வால்யூம்) கூறுகின்றன.

தஞ்சாவூர் ஜில்லா தராசரம் ஐராவதேச்வரர் கோயில் பிராகாரச் சுவர்களில் உள்ள மாடங்களில் சிவனடியார் பலருடைய வாழ்க்கைச் சம்பவங்களையும் உருவங்களையும் விவரிக்கும் சிற்பங்கள் நிறைய அமைக்கப்பட்டுள்ளன. அவை ஒவ்வொன்றின் கீழும் அந்தச் சிற்பம் எதை எடுத்துக் காட்டுகிறது என்பதைத் தெரிவிக்கும் சாசனம் பொறிக்கப்பட்டிருக்கிறது.

சில விக்கிரகங்களின் பீடங்களிலும், தோள் முதுகு போன்ற இதர இடங்களிலும் சாசனங்கள் பொறிக்கப்பட்டுக் காண்கின்றன. கி. பி. 977-ஆம் ஆண்டுக்கும் 984-ஆம் ஆண்டுக்கும் இடைப்பட்ட காலத்தில் மைசூர் சிரவண பெள்ளகொளத்தில் வானளாவ நிற்கும் பாஹுபலி என்றும் கும்மடர் என்றும் குறிக்கப்பெறும் ஜைநமுனி வர் கொம்மடேசுவரருடைய திருமேனியின் சாசனம் இவ்வகையைச் சார்ந்தது (எபி. இந்திகா, ஏழாம்வால்யூம்). இதேபோன்ற திருவுருவங்



கள் இவ்வளவு பெரியவாக இல்லாவிட்டாலும், தென்கன்னட ஜில்லாவில் கர்க்கால், வேணூர் என்ற இடங்களில் முறையே கி. பி. 1432-ஆம் ஆண்டிலும் 1604-ஆம் ஆண்டிலும் நிறுவப்பட்டுள்ளன.

உத்தரப் பிரதேசத்துக் கோரக்பூர் ஜில்லாவில் உள்ள காஸியாவில் படுத்த கோலத்தில் நிர்வாணம் அடையும் நிலையில் உள்ள பகவான் புத்தருடைய பிரம்மாண்டமான சிலை ஒன்று கிடைத்துள்ளது. (கன்னிஹரம் எழுதிய புதைபொருள் ஆராய்ச்சி அறிக்கை, பதினெட்டாம் வால்யூம்). அதன் பீடத்தின் ஒரு பகுதியிலே கி. பி. ஐந்தாம் நூற்றாண்டு எழுத்துக்களில் பொறிக்கப்பட்ட சாசனம் காணப்படுகிறது. (குப்த சாசனங்கள், பக்கம் 272).

தில்லிக்குப் பக்கத்தில் உள்ள வடமதுரையிலிருந்து குஷான மன்னனான ஹுவிஷ்கன் ஆட்சிக் காலத்தைச் சேர்ந்த போதிஸத்வருடைய திருவுருவம் ஒன்று கிட்டியுள்ளது. அமர்ந்த கோலத்தில் அமைந்துள்ள அதன் பீடத்தில் அந்த விக்கிரகத்தைப் புத்த பிக்ஷுணிகள் இருவர் அளித்த செய்தியைத் தெரிவிக்கும் சாசனம் காணப்படுகிறது. அவ்விடத்திலேயே குஷான மன்னனான கனிஷ்கனுடைய உருவம் ஒன்றும் சிதைந்த நிலையில் கிடைத்திருக்கிறது. அது யாருடைய உருவம் என்பதை முழங்காலுக்குக் கீழே உள்ள ஆடைப் பகுதியில் காணும் சாசனம் தெரிவிக்கிறது. (இந்தியப் புதைபொருள் இலாகா ஆண்டு அறிக்கை, 1912).

தூண்களில் பொறிக்கப்பட்ட சாசனங்களிலே பிரசித்தமானது அலஹாபாத் ஸ்தம்ப சாசனம் ஆகும். அதிலே அசோகனுடைய ஸ்தம்ப சாசனங்களுள் முதல் ஆறுடன் தேவியின் சாசனம், கோசாம்பி சாசனம் என்று குறிக்கப்பெறும் அசோக சாசனங்கள் இரண்டும் உள்ளன. இவை தவிர, கி.பி. 375-ஆம் ஆண்டுக்கு அணித்த தாகப் பொறிக்கப்பட்ட குப்த மன்னனான சமுத்திர குப்தனுடைய பிரசஸ்தியும் காணப்படுகிறது. (குப்த சாசனங்கள், முதல் பக்கம்).

மைசூர் ராஜ்யத்தில் கதம்ப வமிசத்து ஆதிவரலாற்றைக் கூறும் தாளகுண்டை ஸ்தம்ப சாசனம் (எபி. இந்திகா, ஏழாம்வால்யூம்), கதம்ப ராஜ்யம் எப்போது நிறுவப்பட்டிருக்கலாம் என்பதை நிர்ணயிக்க உதவும் மாளவல்லி ஸ்தம்ப சாசனம் (எபி. கர்நாடிகா, ஏழாம்வால்யூம்), கி.பி. 602-ஆம் ஆண்டு கொண்டதாகக்கணிக்கப்பட்டுப் பிஜாப்பூர்ஜில்லாமஹாகூடத்தில் கிடைக்கும் மேலைச் சாளுக்கிய அரசனான மங்கலேசனுடைய ஸ்தம்ப சாசனம் (இ. ஆ., பத்தொன்பதாம் வால்யூம்) ஆகிய வற்றையும் உதாரணங்களாகக் கொள்ளலாம்.

பாட்டு ஜில்லாவில் கைல்வன் என்னுமிடத்தில் வயலிலிருந்து கிடைத்த கருங்கல் பாண்டம் ஒன்றன் விளிம்பைச் சுற்றிலும் கி. பி. இரண்டாம் நூற்றாண்டைச் சார்ந்த பிராமி எழுத்துக்களால் ஆன சாசனம் ஒன்று பொறிக்கப்பட்டிருக்கிறது. (இந்தியன் ஆர்க்கியாலஜி, அறிக்கைச் சுருக்கம், 1955-56). அதிலே இன்னது என்று குறிக்கப் பெறாத ஏதோ ஓர் அப்தத்தின் நூற்றெட்டாம் ஆண்டும், மகதநாட்டு மைத்ரகராஜ வமிசத்தவர்களுள் இதுவரையில் அறியாத ஓர் அரசன் பெயரும் காணப்படுகின்றனவாம்.

கல்லில் காணும் சாசனங்கள் கருங்கல்லில் உள்ள பலவகைகளிலும் காணப்படுகின்றன. அவ்வித நிலைமை ஏற்பட்டதற்கு எந்த எந்தப் பிரதேசத்தில் எந்த எந்த வகைக் கற்கள் சுலபமாகக் கிடைத்து வந்தன வென்பதே காரணமாக இருக்கலாம்.

முத்திரைகளுக்கான படிமங்களில் முக்கியமானவை சில மாக்கல்லில் தயாரிக்கப்பட்டுள்ளன. உத்தரப்பிரதேசம் பருக்காபாத் ஜில்லாவில் ஸங்கீஸா அல்லது ஸங்கீஸா வஸந்த்பூர் என்னுமிடத்திலிருந்து உதராசேனன் என்பவன் பெயர்கொண்ட ஒருவனுடைய முத்திரையின் படிமம் கிடைத்துள்ளது. மேலே ஏதோ வொரு சின்னமும் கீழே ஸ்வஸ்திகை உருவமும் கொண்டு அதில் எழுத்துக்கள் கண்ணாடியில் காண்பதுபோல் திருப்பி எழுதப்பட்டுள்ளன. (கன்னிங்ஹாம் எழுதிய புதை பொருள் ஆராய்ச்சி அறிக்கை, பன்னிரண்டாம் வால்யூம்). அவ்விடத்திலிருந்து கரோஷ்டி எழுத்துக்களில் தயாரிக்கப்பெற்ற பொற்கொல்லனுடைய முத்திரைப் படிமம் ஒன்றும் கிடைத்திருக்கிறது. அதிலே எழுத்துக்கள் பிரதிபிம்பம் போலத் திரும்பி இருக்கவில்லை. அன்றி, எழுத்துக்கள் பள்ளமாகவும் இல்லை; எடுப்பாக உள்ளன. இவை மாக்கல்லால் ஆனவை.

வங்காளத்து ஷாஹாபாத் ஜில்லாவில் உள்ள ரோதாஸ்கர் என்னும் இடத்தில் கி. பி. ஏழாம் நூற்றாண்டின் முற்பகுதியைச் சார்ந்த முத்திரைப்படிமம் ஒன்று பாறையில் செதுக்கப்பட்டிருக்கிறது. சுமார் நாலரை அங்குலம் குறுக்களவு கொண்ட ஒரு வட்டத்துக்குள் அடங்கிய அதிலே படுத்திருக்கும் ரிஷிபம் ஒன்றும் அதன்கீழ் 'ஸ்ரீ மஹாஸாமந்த சசாங்க தேவஸ்ய' என்ற எழுத்துக்கள் பிரதிபிம்பம்போல் தலைகீழாகவும் உள்ளன. இவ்வளவும் எடுப்பாக இல்லாமல், பாறையில் பள்ளமாகச் செதுக்கப்பட்டிருக்கின்றன. ஆகவே அந்தப் படிமத்தைக் கொண்டு முத்திரை தயாரிப்பதற்காகவே அதை வெட்டி வைத்திருப்பதாக ஆராய்ச்சியாளர் கருதுவர். (குப்த சாசனங்கள், 283 பக்கம்).

எனினும் முத்திரைசெய்வதற்காகச் செம்பு வெண்கலம் போன்ற உலோகத்தை உருக்கி ஊற்றினால் அதை அந்தப் பாறை தாங்குமா வென்பது சந்தேகம்; தாங்காது என்றே கருதுவர். ஆகவே அந்த முத்திரை உலோகத்தால் செய்யப்படுவதாக இராது என்றும் களிமண், மெழுகு அல்லது அரக்கு போன்ற ஏதோ ஒன்றால் செய்யப்படுவதாக இருக்க வேண்டும் என்றும் கொள்வர்.

முஸ்லீம் அரசர்களுடைய சாசனங்கள், அவற்றுள்ளும் முக்கியமாக வடநாட்டில் உள்ளவைகளும் அரபு பாரசீக மொழிகளில் உள்ளனவும், வெட்டப்பட்டிருக்கமாட்டா. எழுத்து உருவங்களை எடுப்பாக விட்டுப் பக்கத்தில் உள்ள இடைவெளியைச் செதுக்கி எடுத்து விடுவது வழக்கம். மத்திய காலத்தில் வடநாட்டிலே வேறுசில சாசனங்களிலும் இந்த முறை கையாளப் பட்டிருப்பதைக் காணலாம்.

7. சங்கு, தந்தம் முதலியன: வெண்சங்கு, தந்தம் முதலியவற்றில் காணும் சாசனங்கள் அதிகம் இல்லை. ஒன்றிரண்டே உள்ளன. சாவிஹுண்டத்தில் பிராமி எழுத்தில் உள்ள சாசனத்தோடு வெண்சங்கு ஒன்று கிடைத்துள்ளது. (எபி. இந்திகா, இருபத்தெட்டாம் வால்யூம்) ஸட்லஜ் நதிக்கரையில் அம்பாலாவுக்கு அறுபது மைல் தூரத்தில் உள்ள ரூபார் என்னுமிடத்தில் நடந்த புதை பொருள் ஆராய்ச்சியில் மௌரியர் ஆட்சிக் காலத்துப் பிராமி எழுத்துக்கள் கொண்டு தந்தத்தால் ஆன முத்திரை ஒன்று சமீபத்திலே தோண்டி எடுக்கப்பட்டுள்ளது. (புராதன இந்தியா, ஒன்பதாம் இதழ், படம் 48-வ்).

### எழுதுவதற்கு உபயோகிக்கும் வேறு பொருள்களைப் பற்றிய குறிப்பு

எவ்வளவு பழமை வாய்ந்தனவாயினும் பனைஓலை, பூர்ஜ பத்திரம் முதலியவற்றில் காணும் எழுத்துக்களைச் சாசனமெனக் கொள்வதில்லை. எனினும் அத்தகைய எழுத்துக்களை, முக்கியமாகப் பழைய காலத்தனவாக உள்ளவற்றை, சாசனங்களிலும் எழுத்துக்களின் வரிவடிவ வளர்ச்சியிலும் பயிற்சி பெற்றவர்களை நன்கு வாசிக்கமுடியும். தவிர, அத்தகைய பொருள்களைப்பற்றிய விவரங்கள் இல்லாமல் எழுதுகருவிகளைப்பற்றிய எந்த ஆராய்ச்சியும் பூர்த்தியாகாது.

1. பனை ஓலை:—முன்னாளிலே எழுதுவதற்கு உபயோகமாக விளங்கிய பொருள்களுள் பனையோலையே முக்கியமானது. தாலபத்திரம், தாடபத்திரம் என்பனபோன்ற பெயர்களால் அது குறிக்கப்பட்டு வந்தது. சமீபகாலம் வரையில் அது வழக்கில் இருந்திருக்கிறது.

பணியிலே இருவகை உண்டு. சாதாரணமாக நம் நாட்டில் காணும் பண ஒன்று. அகலமான ஓலைகளையுடைய தாளிப் பண மற்றொன்று. இவ்விருவகையும் தென்னாட்டுக்கே உரியவை என்பர். எனினும்வடக்கே புஞ்சாபில், கூடப் பணையைக் காணலாம். முன்னாளில் காச்மீரத்திலும் இன்னும் நம் நாட்டின் வடமேற்குப் பகுதிகளிலும் பூர்ஜபத்திரமே பெருவழக்கில் இருந்தது. எனினும், அந்தப் பகுதியிலும் பழங் காலத்திலே பணையோலையே எழுதுவதற்கு உபயோகப்பட்டு வந்தது என்பதை நாம் நிச்சயமாகக் கூறலாம். அந்நாளிலே பூர்ஜபத்திரத் தையும் பணையோலையைப் போன்ற அளவிலேதான் கத்தரித்து எழுதி வந்ததிலிருந்து இது தெளிவாகும். கி. பி. முதலாம் நூற்றாண்டு எழுத்துக்களைக் கொண்டதாகத் தக்ஷசீலத்திலிருந்து கிடைத்த செப் பேடும் பணையோலை உருவத்திலேதான் அமைந்திருக்கிறது. (எபி. இந்திகா, இருபத்தோராம் வால்யூம்). புத்த ஜாதகக் கதைகளில் பண்ண (அதாவது பர்ணம் அல்லது இலை) என்பது எழுது கருவிகளுள் ஒன்றாகக் குறிக்கப்பட்டுள்ளது. அது பணையோலையே போலும். புத்த ப்கவான் நிர்வாணம் ஆனபிறகு கூடிய முதல் புத்தமதச் சபையில் அவர்களுடைய மதத்தின் மூலக் கிரந்தமான திரிபிடகம் தொகுக்கப் பெற்றுப் பணையோலையில் எழுதப்பெற்றனவென்னும் கர்ணபரம்பரைச் செய்தியைச் சீன யாத்திரிகரான யுவான் சுவாங் குறித்திருக்கிறார்.

தென்னாட்டில் கிடைக்கும் பணையோலைச் சுவடிகள் பெரும்பாலும் கி. பி. பதினேந்தாம் நூற்றாண்டுக்கோ அதற்குப் பிற்பட்ட காலத் துக்கோ சேர்ந்தவையாக இருக்கும். அதற்கு முற்பட்ட காலத்தைச் சார்ந்தவை கிடைக்கவில்லை. இவ்விடம் உள்ள சீதோஷ்ண நிலையே இதற்குப் பெரிதும் காரணமாகும். குளிர்ச்சியும் வறட்சியும் கொண்ட வடஇந்தியப் பகுதிகள் சிலவற்றிலும் அதற்கு அப்பால் உள்ள பிரதே சங்களிலும் பழையகாலத்துச் சுவடிகள் கிடைக்கின்றன. இதுவரையில் நமக்குக் கிடைத்துள்ள பணையோலைச் சுவடிகளுள் மிகவும் பழமை யானது கி. பி. இரண்டாம் நூற்றாண்டுக்கு உரியது என்னலாம். அது மத்திய ஆசியாவிலிருந்து கிடைத்தது. ஸம்ஸ்கிருத நாடகம் ஒன்றன் பகுதிகள் சிலவற்றைக் கொண்டது. காஷ்கர் பிரதேசத்தில் மக்கார்டன் என்பவர் கண்டெடுத்த சுவடிகள் நான்காம் நூற்றாண்டைச் சார்ந்தன. இப்போது ஜப்பானில் புத்தமடம் ஒன்றில் பாதுகாக்கப்பட்டுவரும் பிரஜ்ஞாபாரமித ஹ்ருதயஸூத்ரம், உஷ்ரீச விஜயதாரினி ஆகிய புத்த மதக் கிரந்தங்களைக் கொண்ட சுவடிகள் மத்திய இந்தியாவில் கி. பி. ஆறாம் நூற்றாண்டில் எழுதப்பட்டவை. நேபாளத்தில் காட்மாண்டு தர்பார் சுவடி நிலையத்தில் உள்ள ஸ்கந்த புராணச் சுவடி ஏழாம் நூற் றாண்டில் எழுதப்பட்டது. கேம்பிரிட்ஜில் உள்ள புரமேஸ்வர தந்திரம்

என்னும் நூல் எழுதப்பட்ட சுவடி ஹர்ஷ அப்தம் 252-ல் (அதாவது கி. பி. 858-ல்) தயாரிக்கப்பட்டது. அதேபோலப் புத்த மத நூலான லங்காவதாரம் என்பதன் பிரதி ஒன்று நேவார் அப்தம் 28-ல் (அதாவது கி. பி. 906-7-ல்) எழுதப்பட்டது. இன்னும் தென்னிந்தியாவிலிருந்து சென்ற ஒலைச் சுவடிகள் சில திபேத்திலும் இருக்கின்றன. கி. பி. பதினேராம் நூற்றாண்டுக் கிரந்த எழுத்துக்களில் காணும் வடமொழிச் சுவடிகளும் பதின்மூன்றாம் நூற்றாண்டுத் தமிழ் எழுத்துக்களில் உள்ள தமிழ்ச் சுவடிகளும் திபேத் நாட்டுப் புத்த மடம் ஒன்றில் காணப்பட்டனவாம். அவற்றின் புகைப்படப் பிரதிகள் பாட்டு நகரத்துக் காசிப்பிரசாத் ஜயஸ்வால் ஆராய்ச்சிக் கழகத்தில் உள்ளன.

நீண்டகாலம் பாதுகாக்கவேண்டிய பத்திரங்களையும் நூல்களையும் எழுதுவதற்குப் பனையோலைகளைப் பாடம் செய்தே எழுதுவார்கள். அப்போதுதான் ஒலையிலே ஒரு துவள்வு இருக்கும்; எழுதுவதற்கும் சுலபமாக இருக்கும். அதற்கு முதலிலே ஒலையை நன்றாகக் காய வைப்பார்கள். பிறகு தண்ணீரில் ஊறவைத்தோ கொதிக்கவைத்தோ துவளச்செய்து மறுபடியும் காயவைப்பார்கள். சில சமயங்களில் பனிப் பாடம் செய்வதும் உண்டு. கடைசியிலே அதைச் சோழியாலோ கூழாங்கல்லாலோ தேய்த்து மெருகு ஏற்றுவார்கள். பிறகு அதை வேண்டிய அளவுக்குக் கத்தரித்து வைத்துக்கொள்வார்கள். பழைய சுவடிகளை ஊன்றிக் கவனித்தால் இங்ஙனம் பாடம் செய்யப்பட்டிருப்பது தெரியும். தாளிப் பனையோடுகள் ஒன்று முதல் மூன்று அடி நீளம் வரையில் காணப்படுகின்றன. அகலத்திலும் ஒன்றுமுதல் நான்கு அங்குலம் வரையில் உள்ளன. வட இந்தியாவிலே ஒலைகளில் மசிகொண்டே எழுதி வந்தனர். ஆனால் தென்னாட்டில் எழுத்தாணிகொண்டு எழுதுவதே வழக்கம். அவ்விதம் எழுதிய பிறகு எழுத்துக்கள் பளிச்சென்று தெரிவதற்காகக் கரியையும் மஞ்சளையும் கலந்து தடவுவார்கள். (படிக்கும் போது சில சமயங்களில் பச்சிலையைக் கசக்கித் தடவுவதும் உண்டு.) இவ்விதம் எழுதிய பிறகு எட்டின் மத்தியில், பெரும்பாலும் இடது பக்கம், துவாரம் இட்டு அதிலே கயிற்றைக் கோத்து ஏடுகள் கலையாமல் கட்டுவர். ஏடுகள் மிகவும் நீளமாக இருந்தால் இடதுபுறம் வலதுபுறம் ஆகிய இரண்டிலும் துவாரங்கள் இட்டுக் கயிறு சேர்ப்பார்கள்.

சாதாரணக் கடிதங்களுக்கும் தினசரி உபயோகத்துக்கும் இவ்விதம் ஏடுகளைப் பாடம் செய்யமாட்டார்கள். சிற்சில சமயங்களில் நன்கு வாரி நரம்பை எடுக்காமலேகூட உபயோகப்படுத்துவதும் உண்டு.

விலைமலிவான காகிதம் பழக்கத்துக்குவந்த பிறகு கூடப் பணியோலைகளிலே எழுதுவது தொடர்ந்து இருந்துவந்திருக்கிறது. சென்ற இருபத்தைந்து ஆண்டுகளில்தான் அதன் உபயோகம் மறைந்தது என்னலாம். எனினும், குழந்தையை வாசிக்கவைத்தல் முதலிய சுபச் சடங்குகளுக்கும் ரகசியப்போன்றவற்றுக்கும் இன்னும் பணியோலையையே புனிதமாகக் கருதி உபயோகித்து வருகிறார்கள்.

2. பூர்ஜபத்திரம்: முன்னாலே எழுதுவதற்கு முக்கியமாக இருந்தவற்றுள் பூர்ஜபத்திரம் மற்றொன்று. அது பூர்ஜம் என்னும் மரத்தின் உள் பட்டையைக் கொண்டு தயாரிக்கப்பெறுவது. அந்த மரம் இமயமலைக் காடுகளில் ஏராளமாக வளர்கின்றது. அதனால் பூர்ஜபத்திரத்தின் உபயோகம் வட இந்தியாவிலேதான் அதிகமாக இருந்துவந்தது. அப்பால் அதன் உபயோகம் இந்தியாவின் மற்றப் பாகங்களுக்கும் மத்திய ஆசியாவுக்கும் பரவியது.

அலெக்ஸாந்தர் இந்தியாவின்மீது படையெடுத்து வந்தபோது அவனுடன் கூட வந்திருந்த கிரேக்க ஆசிரியரான குர்ட்டிஸ் என்பார் இந்தியர்கள் அந்நாளிலே மரப்பட்டையில் எழுதி வந்தததாகக் கூறியிருக்கிறார். புத்தமதக் கிரந்தங்களில் வடகலையைச் சேர்ந்தவற்றுள் பூர்ஜபத்திரத்தைப்பற்றிய குறிப்புகள் அதிகமாகக் காணப்படுகின்றன. இந்தப் பட்டையைப்பற்றி அல்பெரூசி என்னும் அராபியாத்திரிகர் விவரமாகத் தெரிவித்திருக்கிறார்: மத்திய இந்தியாவிலும் வட இந்தியாவிலும் மக்கள் தூஜ் என்னும் வகையைச் சேர்ந்த ஒரு மரத்தின் பட்டையை எழுதுவதற்கு உபயோகிக்கிறார்கள். அந்த மர வகையின் பட்டையை வில்லுக்கு உறையாகவும் உபயோகப்படுத்துவது உண்டு. எழுதுவதற்காக அவர்கள் இரண்டு முழ நீளமும் ஒரு சாண் அகலமும் உள்ள பட்டையாகத் தேர்ந்தெடுப்பார்கள். அதன்மீது எண்ணெய் தடவிப் பாடப்படுத்தித் தேய்த்து வழுவுழுப்பாக்குவர். அதன்மீதுதான் எழுதுவார்கள். அதற்கெனத் தயாரித்த தனிவகை மசியால் கொறுக்கைத்தட்டை எழுதுகோலால் எழுதுவார்கள். பிறகு ஏட்டின் நடுவிலே துளையிட்டு அதன் வழியாகக் கயிறு செலுத்தி அந்த ஏடுகளைக் கோப்பார்கள். கடைசியாக மேலும் கீழும் அதே அளவு கொண்ட மரப் பலகைகளை வைத்து எல்லாவற்றையும் சேர்த்துத் துணிபால் கட்டிப் பத்திரப்படுத்துவார்கள். தினசரி உபயோகத்துக்குப் பட்டையை இவ்வளவு விரிவாகப் பாடம் செய்யமாட்டார்கள். தூஜ் மரத்தின் பட்டைகளையும் உபயோகிப்பார்கள்.

மொகலாயர் காலத்தில் காகிதம் அதிகமான பழக்கத்துக்கு வந்த பிறகு, பணியோலையைப் போலவே பூர்ஜபத்திரத்தின் உபயோகமும்

அரிதாகிவிட்டது. இன்றைக்கும் அது புனிதத் தன்மை வாய்ந்ததாகக் கருதப்பட்டுச் சில சடங்குகளில் உபயோகிக்கப்பட்டு வருகிறது. இந்தப் பத்திரத்தின் உபயோகம் தமிழ்நாட்டில் காணப்படவில்லை.

பூர்ஜ பத்திரத்தில் எழுதியதாகக் கிடைத்துள்ள நூல்களுள் மிகவும் பழமையானது கி. பி. இரண்டு அல்லது மூன்றாம் நூற்றாண்டைச் சார்ந்த கரோஷ்டி எழுத்துக்களில் எழுதப்பட்டு மத்திய ஆசியாவில் கோட்டான் பிரதேசத்திலிருந்து கிடைத்த தம்மபதம் என்னும் புத்தமத நூலாகும். ஸம்யுக்தாகமம் என்னும் நூலின் சுவடி நான்காம் நூற்றாண்டைச் சார்ந்தது. அடுத்தபடியாக உள்ளவை அப்கானிஸ்தானத்து ஸ்தூபங்களிலிருந்து கிடைத்த 'முடிப்புகள்'. பவர், காட்ப்ரே ஆகியோர் சேகரித்த சுவடிகள் ஆறாம் நூற்றாண்டைச் சார்ந்தவை. பக்ஷாஸி கணக்குச்சுவடி எட்டாம் நூற்றாண்டில் எழுதப்பட்டதென்பர். இன்னும் காஷ்மீரம் முதலிய பகுதிகளிலிருந்து பதினைந்தாம் நூற்றாண்டையும் அதற்குப் பிற்பட்ட காலத்தையும் சார்ந்த சுவடிகள் கிடைத்துள்ளன.

3. காகிதம் :—முதன் முதலில் கி. பி. 105-ஆம் ஆண்டில் சீன தேசத்தில்தான் காகிதம் செய்யப்பட்டதென்றும் அதற்குப் பிறகு முஸ்லீம்களால் அது இந்த நாட்டுக்குக் கொண்டுவரப்பட்டதென்றும் ஆராய்ச்சியாளர்கள் பொதுவாகக் கருதுவர். (பார்னட் எழுதிய இந்தியப் புராதனப் பொருள்கள் - ஆண்டிகுடெஸ் ஆப் இந்தியா, பக்கம் 229). எனினும் அலெக்ஜாந்தரோடு இந்தியாவுக்கு வந்திருந்த நீர்ச்சர்ஸ் என்பவர் அந்நாளிலே இந்தியமக்கள் பருத்தி (நூலால் ஆன துணி)யை அடித்து எழுதும் காகிதம் தயாரித்து வந்ததாகக் குறித்திருக்கிறார். (ஸ்டிராபோ, 717). காகிதத்தில் எழுதிய சுவடிகளிலே இதுகாறும் நமக்கு கிடைத்தவற்றுள் மிகவும் பழமையானது மத்திய ஆசியப் பகுதியில் காஷ்கரிலிருந்து கி.பி. ஐந்தாம் நூற்றாண்டில் வழங்கிய குப்த எழுத்துக்களில் எழுதப்பட்டுக் கிடைத்ததாகும். (வங்காள ஏஷ்யாடிக் ஸொஸைட்டி ஜர்னல், அறுபத்தாராம் வால்யூம்). எனினும் நம் நாட்டில் கிடைக்கும் காகிதப் பிரதிகள் கி. பி. பதினான்காம் நூற்றாண்டுக்கு முற்பட்ட காலத்தைச் சேர்ந்தனவாக இல்லை.

முன்னாளிலே காகிதத்திலே எழுதுவதையும் பனையேடுகளிலோ பூர்ஜ பத்திரத்திலோ மசியினால் எழுதுவதைப் போலவே செய்து வந்தார்கள். இதற்காகக் காகிதத்தின்மீது அரிசிக் கஞ்சியையோ கோதுமைக் கஞ்சியையோ நீர்க்கத் தயாரித்துப் பூசி அது காய்ந்ததும் கூழாங்கல்லையோ சோழியையோ கொண்டு தேய்த்து வழுவழுப்பாக்கு

வார்கள். அப்போதுதான் காகிதத்தில் எழுதும்போது மசி ஊறும் இருக்கும். இவ்விதம் தயாரித்த காகிதத்தை வேண்டிய அளவுக்குக் கத் தரித்து வைத்துக்கொள்வார்கள். காகிதத்தில் எழுதிய புத்தகத்தைப் பனை எடுகளைப் போலவே மேலும் கீழும் மரப் பலகைகளை வைத்துக் கட்டியிருப்பார்கள். சில சமயங்களில் பனையோலைச் சுவடிகளைப்போல் காகிதங்களிலும் நடுவில் துளையிட்டு நூலைக் கோத்துக் கட்டியிருப் பார்கள்.

4. பருத்திநூல்துணி: முன்னாளிலே நம் நாட்டில் பருத்தி நூலால் நெப்த துணிகளையும் எழுதுவதற்கு உபயோகித்து வந்தார்கள். அது படம், படிதா, கார்பாசிகபடம் என்பனபோன்ற பெயர்களால் குறிக் கப்பட்டு வந்தது. தர்ம சாஸ்திரங்களிலே துணியில் எழுதுவது குறிக் கப்பட்டிருக்கிறதென்பதை நாம் முன்னரே (மேலே ௨௮௮-ஆம் பக்கம்) தெரிவித்திருக்கிறோம். சாசனங்களில் படம் அல்லது துணியிலே எழுது வதைப்பற்றிக் கூறுவனவற்றுள் மிகவும் பழமையானவை சாதவாகன அரசர்கள் காலத்து நாசிக் கல்வெட்டுக்கள் ஆகும். (மேலே இந்தியப் புதைப்பொருள் ஆராய்ச்சி அறிக்கை, நான்காம் வால்யூம், 11 - எ. பி. சாசனங்கள்). காகிதத்தைப்போலவே துணியும் நீண்டகாலம் நிற் காது. சீதோஷண ஸ்திதியால் மக்கிப்போய், பூச்சியரித்துச் சீக்கிரமே வீணாகிவிடும்.

ஸ்ரீபிரபாகுரி என்னும் ஜைன ஆசிரியர் இயற்றிய 'தர்மவிதி' என்னும் நூலுக்கு விக்கிரம சம்வதஸரம் 1418-ல் (அதாவது கி. பி. 1361-2-ல்) காகிதத்தில் எழுதிய பிரதி ஒன்று கர்ஜரத்து அணவரில் வாட் பட்டணத்தில் கிடைத்தது என்று பீடர்ஸன் என்னும் ஆசிரியர் கூறுகிறார். ஜஸல்மீர் நகரத்தில் பிரஹஜ்ஞானகோசம் என்னும் புத்த சாலையில் ஜைனசூத்திரங்களின் பட்டியல் ஒன்று பட்டுத் துணியில் மசி யினால் எழுதப்பட்டிருந்ததைத் தாம் பார்த்திருப்பதாக டாக்டர் பீலர் கூறுகிறார். இரண்டு மூன்று நூற்றாண்டுகளுக்கு முற்பட்ட காலத்துக் கணக்குகளை எழுதிய துணிக்கணக்குப் புத்தகங்கள் சிருங்கேரிமடத்தில் இப்போதும் பாதுகாக்கப்பட்டு வருகின்றன வென்பர். இராஜபுதனத் திலே ஒரு வகுப்பினர் நீளமான துணியிலே வருஷவருஷம் பஞ்சாங் கங்களைத் தயாரித்து எழுதிவருகிறார்கள் என்று மகாமகோபாத்தியாய பண்டித ஓஜா தம் நூலில் கூறுகிறார். (பாரதிய ப்ராசீன விபிமாலா, பக்கம் 146). கர்காடக தேசத்து வணிகர்கள் கடதம் என்று வழங்கப் படும் ஒருவகைத் துணியைத் தங்களுடைய கணக்குகளை எழுத உப யோகித்து வந்தனர் என்று பர்ணல், ரைஸ் போன்ற ஆசிரியர்கள் கூறு கிறார்கள். அந்தத் துணியின்மீது புளியங்கொட்டையிலிருந்து தயா



ரித்த பசையைப் பூசியிருப்பார்களாம். தமிழ் நாட்டிலும் சமீபகாலம் வரையில் மார்வாடி வியாபாரிகளில் சிலர் இத்தகைய கணக்குப் புத்தகங்களை வைத்திருந்தனர்.

காகிதத்தைப்போலவே துணியிலும் கஞ்சிபோன்ற பசையை நீர்க்கக் கரைத்துப் பூசுவார்கள். அப்போதுதான் துணியில் இழையோடியுள்ள துவாரங்கள் தெரியாமல் அடைபடும். நன்றாகக் காய்ந்த பிறகு அதைக் கூழாங்கல்லாலோ, சோழியினாலோ இழைத்து வழு வழுப்பாக்குவர். அப்பால் அதற்கெனத் தயாரித்த ஒருவகைக் கறுப்பு மசியினால் அதன்மீது எழுதுவர். சில சமயங்களில் துணிகளுக்கே கரியைத் தடவித் கறுப்பாக்கிவிடுவார்கள். அப்போது அதன்மீது மாக்கல், சுண்ணாம்புக்கட்டி முதலியவைபோன்ற வெண்மையான பொருள்களால் எழுதுவர்.

5. தோல்: ஆசியாவின் மேற்குப்பகுதி, எகிப்து, ஐரோப்பா ஆகிய பிரதேசங்களில் முன்னாலிலே தோலிலும் எழுதி வந்திருக்கிறார்கள். ஆனால் அது நம் நாட்டிலே பழக்கத்தில் இருந்ததாகத் தெரியவில்லை. புத்தமதக் கிரந்தங்கள் சிலவற்றிலே தோலும் எழுதுகருவிகளுள் ஒன்றாகக் குறிக்கப்பட்டிருக்கிறது. ஸுபந்து என்பவர் எழுதிய வாசவதத்தை என்னும் வடமொழி நூலும் ஏறக்குறைய இதேபோன்ற கருத்தை ஓரிடத்தில் தெரிவிக்கிறதென்பர். எனினும், நம்மக்கள் தோலை அசுத்தப் பொருளாகவே மதித்து வந்திருக்கிறார்கள். மத விஷயங்களில் புனிதம் வாய்ந்த பொருள்களாக உபயோகிக்கும் புவித்தோல், மான்தோல் ஆகிய இரண்டையும் தவிர மற்றவைகளைக் கையால் தொடக்கூடமாட்டார்கள். அன்றி, தோலில் எழுதப்பெற்றது ஏதும் இதுவரையில் நம் நாட்டில் கிடைக்கவில்லை. எனினும் இந்திய எழுத்துக்கள் பொறிக்கப்பெற்றுக் காஷ்கர்பகுதியி லிருந்து கிடைத்த தோல் துண்டுகள் பீட்டர்ஸ்பர்க்கில் இருக்கின்றனவாம்.

6. மசி: இந்திய மக்கள் பூர்ஜபத்திரம், காகிதம், பருத்தி தூல் துணி ஆகியவற்றில் எழுதிவந்தார்கள் என்று கிரேக்க ஆசிரியர்கள் கூறுவதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். அதைக் கவனித்தால் அவற்றின்மீது எழுதுவதற்கு ஏதோ ஒரு வகையான சாயத்தை உபயோகித்திருக்கவேண்டும் என்பது விளங்கும். கிறிஸ்து அப்தத்துக்கு முற்பட்டகாலத்தில் எழுதப்பட்டனவாகக் காணும் கிருஹ்ய ஸூத்திரங்களில் மஷி, மஷி, மசி என்பனபோன்ற உருவங்களில் இந்தச் சொல் காணப்படுகிறது. மசிகொண்டு எழுதியதாக நமக்குக் கிடைப்பவற்றுள் மிகவும் பழமையானது கி. மு. இரண்டு அல்லது மூன்றாம்

நூற்றாண்டு எழுத்துக்களால் அந்தோர் என்னும் இடத்தில் மூன்றாம் எண் கொண்ட ஸ்தூபத்தினின்றும் கிடைத்த பாத்திரப்பேழையே யாகும். அதன் மூடியில் இந்தச் சாசனம் காணப்படுகிறது. (கன்னிங் ஹாம் எழுதிய 'பிஸ்சாத்தோப்புகள்', 349 பக்கம்). இன்னும் அசோக சாசனங்களில் சில இடங்களில் புள்ளிகளுக்குப் பதிலாகச் சுழிகள் காண்பதைக்கொண்டு அந்நாளிலே மசியினால் எழுதும் பழக்கம் இருந்திருக்க வேண்டும் என்று ஆராய்ச்சியாளர் சிலர் கொள்வர். கோட்டானி லிருந்து கிடைத்த கரோஷ்டி எழுத்தில் உள்ள தம்மபதம் என்னும் நூல், அப்கானிஸ்தானத்து ஸ்தூபங்களிலிருந்து கிடைத்த கருங்கல் பாத்திரங்கள், 'முடிப்புகள்' ஆகியவை மசியினால் எழுதப்பட்டனவே. அஜந்தாவிலும் மசியினால் எழுதிய சாசனங்கள் சில கிடைத்துள்ளன.

மசியிலும் பல வர்ணங்களை உபயோகித்திருக்கிறார்கள். எனினும் கறுப்பு மசியே பெருவழக்கு. கறுப்பு மசியிலும் இரண்டு வகைகள் உண்டு. தினசரி உபயோகத்துக்கும் சாதாரணமான விஷயங்களை எழுதுவதற்கும் உபயோகமாகும் மசி ஒரு வகை. ஏதோ ஒரு வகையான கரித் தூளோடு கோந்து, வெல்லம் போன்ற பசைப்பொருளைக் கலந்து தண்ணீர் விட்டுக் குழைத்து எழுதுவார்கள். அந்த மசி நிலைத்து நிற்காது; சீக்கிரத்தில் கலைந்துவிடும். மற்றொரு வகை முக்கியமான பத்திரங்களுக்கும் நீண்டகாலம் காக்க வேண்டியவற்றையும் எழுதுவதற்கு உபயோகமாகவது. இதை அரக்கு, வெங்காரம், லோத்ரா, எண்ணெய் விளக்கு எரித்த புகைக்கரி ஆகியவற்றைத் தண்ணீரில் குழைத்து வேறு பசையுடன் சேர்த்து நன்றாகக் கொதிக்கவைத்துத் தயாரிப்பார்களாம். இவ்விதம் தயாரித்த மசியினால் எழுதியது தண்ணீரிலும் கலையாதாம். காஷ்மீரத்திலே பூர்ஜ பத்திரத்தின்மீது எழுதுவதற்கு வாதாம் கொட்டை ஓட்டைச் சுட்ட கரியை உபயோகித்துப் பசுமாட்டின் சிறு நீரில் கொதிக்கவைத்து மசி தயாரிப்பார்களாம். அவ்விதம் தயாரித்த மசியினால் எழுதிய மரப்பட்டையை அவ்வப்போது தண்ணீரில் போட்டுக் கழுவினாலும் எழுத்துக்கள் கலையாவாம்.

மசிகளைப் பலவேறு வர்ணங்களிலும் தயாரித்து வந்திருக்கிறார்கள். சிவப்பு மசி சாதாரணமானது. சுவடிகளை எழுதுவதற்குச் சில சமயங்களில் மஞ்சள் வர்ண மசியையும் உபயோகித்திருக்கிறார்கள். பலவித வர்ணங்களில் எழுதிய சுவடிகளைத் தானம் செய்வதைப்பற்றி ஹேமாத்ரி தம்முடைய 'தானகாண்ட்'த்தில் கூறியிருக்கிறார். சிவப்பு மசியை அலக்தகம் அல்லது ஹிங்குளத்தைத் தண்ணீரில் கரைத்துப் பசை சேர்த்துத் தயாரித்துவந்திருக்கிறார்கள். பெரும்பாலும் ஏடுகளில் வலத்திலும், இடத்திலும் கோடு இழுக்கவும், இடையிலே சில குறிகளை இடு

வதற்குமே அதை உபயோகித்திருக்கிறார்கள். சில சமயங்களில் அத்தியாயமுடிவுகளையும் சிலைக முடிவுகளையும் இதனால் குறித்திருக்கிறார்கள். ஜைன ஆசிரியர்கள் சிலர் அத்தியாய முடிவைக் காட்டப் பச்சை அல்லது மஞ்சள் வர்ண மசியைக் கையாண்டிருக்கிறார்கள்.

சித்திரங்களின் நடுவே எழுதுவதற்கும், அரசர்கள், தனிகர்கள் போன்றோர் உபயோகத்திற்கான நூல்களை எழுதுவதற்கும், புனிதமான சிறு நூல்களை எழுதுவதற்கும் தங்கத்தாலும், வெள்ளியாலும் ஆன மசிகளை உபயோகித்தார்கள். அத்தகைய மசியைப்பற்றிய குறிப்புக்கள் பழங்காலத்திலிருந்தே இலக்கியங்களிலும் கிடைக்கின்றன. ஆயினும் இப்போது நமக்குக் கிடைக்கும் இத்தகைய எழுத்துக்கள் சமீப காலத்தைச் சார்ந்தனவே.

## 10. சாசன அமைப்பு

சாசனங்களை எவ்விதம் அமைத்து எழுதவேண்டும் என்பதைப் பற்றிய விதிகள் தர்ம சாஸ்திரங்களிலே காணப்படுகின்றன வென்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். பொதுவாகச் சாசனங்கள் ஐந்து பிரிவுகளாக அமையும். மங்கல வாசகம், தானம் கொடுப்பவன், தானம் பெறுபவன், தான விவரம், முடிவு ஆகியவை அவ்வவந்து பகுதிகள். பழைய சாசனங்கள் எளிய நடையில் சுருக்கமாகக் காணப்படும். காலம் செல்லச் செல்ல வாசகத்திலும் முறையிலும் சம்பிரதாயங்கள் ஏற்பட்டன. அவை இடத்துக்கு இடம், காலத்துக்குக் காலம் வேறுபட்டன. எனினும் மேலே காட்டிய ஐந்து முக்கியமான அம்சங்களை விட்டுவிடவில்லை; முறையாகக் கடைப்பிடிக்கப்பட்டு வந்தன.

**மங்கல வாசகம் :** இலக்கியமோ தத்துவமோ அல்லது வேறு எந்தத் துறையிலும் சரி, ஒரு நூலை மங்கல வாசகத்துடன் ஆரம்பிப்பதே நம் மரபு. நூல் அல்லாமல் வேறு எதை எழுதினாலும்கூட அதை நாம் பின்பற்றுகிறோம். சாதாரணக் கடிதம் எழுதும்போது கூடப் பிள்ளையார் சுழி போட்டே ஆரம்பிக்கிறோம். அந்த மங்கல வாசகம், வாழ்த்து, வணக்கம் மங்கலச் சொல் என மூன்று வகைப்படும். கடவுள் வாழ்த்து ஏதும் இல்லாமல் எடுத்த எடுப்பிலே நூலைத் துவக்குமிடத்திலும் மங்கலச் சொல்லையாவது முதலில் கொடுத்தே எழுதுவது வழக்கம்.

பழைய சாசனங்கள் பலவற்றில் ஆரம்பத்திலே கடவுள் வணக்கத் தோடு மங்கலத்தைக் கொடுப்பனவாகக் கருதும் குறிகள் சிலவும் காணப்

படுகின்றன. பெரும்பாலும் இந்தக் குறிகளை முதலில் கொடுத்தே பிறகு கடவுள் வணக்கத்தைக் கூறுவார்கள். பிற்காலத்திய தமிழ்ச் சாசனங்கள் பலவற்றின் ஆரம்பத்திலே பிள்ளையார் சுழியும் காணப் படுகிறது. அது பல வேறு உருவங்களில் எழுதப்பட்டு வந்திருக்கிறது. (இதை விவரமாகக் கலைகளில் வெளிபான கட்டுரை ஒன்றில் ஆராய்ந்திருக்கிறேன்). கர்நாடக தேசத்துச் சாசனங்களிலும் இது காணப்படுகிறது. அவ்விடத்திலே இது ஒன்றுக்குள் ஒன்றாகத் தொடர்ந்து வரும் ஒரு சுழி உருவத்தில் உள்ளது. அதை ஸித்தம் என்றே வாசிப்பர்; சில இடங்களில் ஒங்காரமான பிரணவமாகவும் கொள்வர். சில சமயங்களில் முதலில் இந்தப் பிள்ளையார் சுழியை எழுதி அதைத் தொடர்ந்து ஸித்தம் அல்லது ஓம் என்பதை எழுத்தாலும் எழுதியிருப்பர்.

கலிங்கநாட்டு மன்னனான காரவேலனுடைய ஹாதிகும்பாச் சாசனத்தின் ஆரம்பத்திலே ஒரு கிரீடமும், ஒரு ஸ்வஸ்திகையும் ஒன்றன் கீழ் ஒன்றாகப் பொறிக்கப்பட்டுள்ளன. அவற்றை ஸ்வஸ்திகை, ஸ்ரீவத்ஸம் ஆகிய இரண்டையும் குறிப்பனவாகக் கொள்வர். பழைய சாசனங்களில் சில 'ஸ்வஸ்தி ஸ்ரீமதாம்' என்றே ஆரம்பிக்கின்றன. அதனால் இவ்வுருவங்கள் 'ஸ்வஸ்தி ஸ்ரீ' என்று சாசனங்களின் ஆரம்பத்தில் காணும் மங்கலச் சொல்லைக் குறிப்பனவாக இருக்கலாம் என்று ஆசிரியர்கள் சிலர் கருதுவர். அந்தச் சாசனத்திலே இவ்வுருவங்கள் மட்டுமல்லாமல் ஜின்பகவானுக்கு வணக்கமும் ஆரம்பத்தில் கூறப்பட்டுள்ளது.

சில சாசனங்களில் 'உடுக்கையும் போதி மரமும்' என்று ஆராய்ச் சியாளர் கூறும் குறியும் காணப்படுவது உண்டு. அவற்றுள் முதலாவதைப் பிரணவம் அல்லது பகவான் என்றும் பிந்தியதை நாராயணன் என்றும் கொள்வர். 'திரிகுலத்தின்மீது உள்ள சக்கரம்' எனப்படும் குறியீடும் சில இடங்களில் எழுதியிருப்பர். 'நமோ' என்ற சொல்லே இவ்விதம் குறியீடாக அமைந்தது என்று ஆசிரியர்கள் கூறுவர்.

பெரும்பாலான சாசனங்கள் இத்தகைய குறிகளைக் கொண்டு நின்றாலும் இல்லாவிட்டாலும், 'ஸ்வஸ்தி' என்ற சொல்லுடனே தான் ஆரம்பமாகும். சிலவற்றுள் 'ஸித்தம்' என்பது காணப்படும். பழைய சாசனங்களிலே இது முதல்வரியின் ஆரம்பத்தில் எழுதப்பட்டிருக்காது. இடதுபுறமாக ஏட்டின் நடுவில் நடு வரியை உள்ளே தள்ளி ஆரம்பிக்கச் செய்யும் வகையில் எழுதப்பட்டிருக்கும். இது தவிர, தானம் கொடுத்தோன் வழிபடும் கடவுளையோ, தானம் வழங்கப்

பட்டாரின் மத்தத்துக்குரிய கடவுளையோ வணங்கும் வாசகமும் ஆரம்பத்தில் காணப்பெறும். பல்லவர், மேலைக் கங்கர் ஆகியோருடைய பழைய சாசனங்கள் ஜீதம் பகவதா என்று கூறி ஆரம்பிக்கும். இதேபோல வேறு சாசனங்களில் நமச்சிவாய (எபி. இந்திகா, இரண்டாம் வால்பூம், 10,410-பக்கங்கள்), நமோ புத்தாய (ஹெ. ஆரூம் வால்பூம், 287-பக்கம்), நமோ பகவதே வாஸுதேவாய (ஹெ. இரண்டாம் வால்பூம், 350-பக்கம்), நமோ அர்ஹதோ வர்த்தமானஸ்ய (ஹெ.), நமோ ஸுரஸ்வத்யை அல்லது பாரத்யை (ஹெ. பக்கங்கள் 182, 333) என்றும் காணப்படும். விஜயநகர ஸாம்ராஜ்ய மன்னர்கள் வழங்கிய சாசனங்கள் கணுதிபத்யே நம: என்று ஆரம்பிக்கும்.

பல சாசனங்களின் ஆரம்பத்திலே தானம் வழங்குவோரின் இஷ்ட தெய்வத்துக்கு வணக்கம் கூறுவதாக அழகான சுலோகங்கள் காணப்படுகின்றன. அந்தச் சுலோகங்கள் சிவன், விஷ்ணு, தேவி, கார்த்திகேயன், பிரம்மா, ஸுரஸ்வதி ஆகிய பலரைப் பற்றியும் வணக்கம் கூறுவனவாக இருக்கும். விஷ்ணுவைப் பற்றியவை அவருடைய அவதாரங்களில் பலவற்றின் பெயரிலும் காணப்படும். கர்நாடக தேசத்திலே ஜைனர்களுடைய சாசனங்கள் அதிகமாகக் கிடைக்கின்றன. அவை ஜின பகவானுக்கு வணக்கம் செலுத்துவதாகவோ ஜினசாசனத்தைப் புகழ்வதாகவோ உள்ள சுலோகத்துடன் ஆரம்பமாகும். புத்தமத சம்பந்தமான சாசனங்களிலே புத்த பகவான் வணக்கம் கூறப்பட்டிருக்கும். சில சமயங்களில் மஞ்சுகோஷர், மஞ்சுபுத்ரி போன்ற வேறு புத்தமதத் தெய்வங்களின் வணக்கமும் காணப்படும். அந்த அந்தத் தெய்வங்களின் விக்கிரக லக்ஷணத்தை அறிவதற்கு உதவும் வகையில் இந்தச் சுலோகங்கள் விவரங்களைக் கொடுத்திருக்கும்.

தானம் வழங்கியவர் : சாசனங்களிலே மங்கல வாசகத்துக்கு அடுத்தபடியாகத் தானம் வழங்கியவர் பெயர் காணப்படும். தானம் வழங்குவோருடைய பரம்பரையை மூன்று தலைமுறைக்குக் கொடுக்க வேண்டுமென்று தர்ம சாஸ்திரங்கள் விதிக்கின்றன. இதனால் அவனுடைய தந்தை, பாட்டன், முப்பாட்டன் ஆகியோர்களுடைய பெயர்கள் காணப்படும். தானம் கொடுப்போர் பெயரையும் சேர்த்தால் நான்கு தலைமுறைகளுக்கு ஆகும். பழைய சாசனங்கள் இந்த விதியை அப்படியே பின்பற்றியிருக்கக் காணலாம். பல்லவ மன்னர்களுடைய பழைய ஸம்ஸ்கிருதச் சாசனங்கள் இதற்குச் சிறந்த எடுத்துக்காட்டுகளாகும். சிலசமயங்களில் அந்த அரசர்களுடைய பெயர்களோடு அவர்களுடைய வெற்றிகளும் வேறு புகழ்ச்செய்திகளும் கூறப்பட்டிருக்கும். மற்றுள் சில சாசனங்களில் இவ்விதம் தானம் வழங்கிய அரசன் பரம்பரையைப்

பற்றிக் கூறுமிடத்தில் மூன்று தலைமுறைகளோடு நிறுத்திவிடமாட்டார்கள்; அந்த வமிசம் நிறுவப்பட்ட காலத்திலிருந்து ஆண்ட அரசர்கள் எல்லோரையும் குறிப்பிட்டிருப்பார்கள். மேலேச் சாளுக்கியர், சீழைச் சாளுக்கியர் ஆகியோருடைய செப்பேட்டுச் சாசனங்களில் இந்த முறை பின்பற்றப்பட்டிருப்பதைக் காணலாம். அவற்றுள் காணப்படும் பிரசஸ்தி ஒரே விதமாக இருக்கும். புது அரசர்கள் பட்டமேற்கும்போது பழைய பிரசஸ்தியின் சுலோகங்களை அப்படியே வைத்துக்கொண்டு புது அரசர்களுக்கான புதுச் சுலோகங்களைச் சேர்ப்பர்.

ஆனால் தமிழ்ச் சாசனங்களிலே இந்த முறை பின்பற்றப்படவில்லை. தானம் வழங்கியவர்களுடைய வமிச பரம்பரை பெரும்பாலும் காணப்படாது. பிரசஸ்தியும் அந்த அரசனைப் பற்றியதாகவே இருக்கும். தஞ்சையிலிருந்து ஆண்ட சோழ மன்னர்கள், அவர்களுக்குப் பின்னால் ஆதிக்கியம் பெற்ற பாண்டிய மன்னர்கள் ஆகியோருடைய சாசனங்களில் இதைக் காணலாம். இந்தப் பிரசஸ்தியைத் தமிழில் மெய்க்கீர்த்தி என்பர். செய்யுள் உருவில் அமைந்த இம் மெய்க்கீர்த்தி ஒவ்வோர் அரசனுக்கும் தனித்தனியாக அமைந்திருக்கும். சிலசமயங்களில் ஓர் அரசனுக்கே ஒன்றுக்கு மேற்பட்ட மெய்க்கீர்த்திகளும் காணப்படும். அவை ஆட்சியின் ஆண்டு ஏற ஏற உருவத்திலும் பெருகிக் கொண்டே வரும். அவ்வப்போது நிகழும் புதுப் புது வெற்றிகள் அம் மெய்க்கீர்த்தியில் சேர்க்கப்படும். வடமொழிப் பிரசஸ்தியில் சிலசமயங்களில் காணும் கவியின் கற்பனைகள் இந்த மெய்க்கீர்த்தியில் இடம் பெறா. இவை தெளிவாகவும் சுருக்கமாகவும் சரித்திர நிகழ்ச்சிகளை அப்படியே எடுத்துக் கூறுகின்றன. தானம் வழங்கிய அரசனுடைய பெயர் மெய்க்கீர்த்தியின் முடிவிலே கொடுக்கப்பட்டிருக்கும். அரசனுடைய ஆட்சியின் ஆண்டும் அதைத் தொடர்ந்து காணப்படும்.

தமிழ் இலக்கண நூல்களிலே பாட்டியல் வகையில் மெய்க்கீர்த்தியின் இலக்கணமும் கொடுக்கப்பட்டிருக்கக் காணலாம்.

சில சாசனங்களிலே மெய்க்கீர்த்தி கொடுக்கப்பட்டிருக்காது. இன்னும் சிலவற்றுள் 'புயல் வாய்த்து' என்பது போல மெய்க்கீர்த்தியின் ஆரம்பத்தை மட்டும் கொடுத்து அதை முழுதும் எழுதாமல் விட்டு விடுவார்கள். வேறு சிலவற்றிலே மெய்க்கீர்த்தியையே கொடுக்காமல், 'ஸ்ரீ மெய்க்கீர்த்திக்குமேல்' என்று ஆரம்பித்து விடுவர். அத்தகைய கல்வெட்டுக்களிலும் அரசன் பெயரை ஒட்டி அவன் ஆட்சியின் ஆண்டு காணப்படும்.

வேறு சிலவற்றுள் மெய்க்கீர்த்தி இல்லாததோடு மட்டுமல்லாமல் அரசனுடைய பெயரும் தெளிவாகக் காணப்படாது. திரிபுவனசக்கரவர்த்திகள் என்றோ கோனேரின்மை கொண்டான் என்றோ அரசன் பொதுவில் குறிக்கப் பட்டிருப்பான். அவை பெரும்பாலும் அரசாங்கத்தாரிடமிருந்து கிராமசபை, நாட்டார் போன்ற ஸ்தாபனங்களுக்கு வந்த நிர்வாக உத்தரவுகள் அடங்கிய ஒலைகளாகும். அவைகளையும் சபையார் கல்லில் பொறித்திருப்பதே அவை கிடைப்பதற்குக் காரணம். அவற்றில் அரசனுடைய ஆண்டு பெரும்பாலும் கடைசியிலே கொடுக்கப் பட்டிருக்கும்.

தானம் பெற்றவர் : சாசனங்களிலே யாருக்குத் தானம் வழங்கப் பெற்ற தென்பது தெளிவாகக் கூறப்பட்டிருக்கும். தானம் பிராமணர்களுக்கு அளிக்கப் பெற்றதாயின் அவர்களுடைய வேதசாகை, சூத்திரம், கோத்திரம் போன்றவற்றுடன் அவர்கள் எந்த ஊரில் வசித்து வந்தனர் என்ற விவரமும், சிற்சில சமயங்களில் அவர்களுடைய தந்தையின் பெயரும் கொடுக்கப் பட்டிருக்கும். கோயில் மடங்கள் போன்ற ஸ்தாபனங்களுக்கு அளித்தனவாயின் அந்த ஸ்தாபனங்களின் சார்பாக யார் அந்தத் தானங்களைப் பெற்றுக் கொண்டார்கள் என்பதும் விவரிக்கப் பட்டிருக்கும்.

தான விவரம் : இந்தப் பகுதிதான் சாசனத்திலே முக்கியமானது. தான விவரமும் அதன் பரிகாரங்களும் அதை அனுபவிக்கும் முறையும் இந்தப் பகுதியிலே விரிவாகவும் தெளிவாகவும் கூறப்பட்டிருக்கும். அன்றி, பூமி தானமாக இருக்குமானால் அந்தப் பூமியின் நான்கெல்லையும், அந்த நிலத்துக்கான வரி விவரங்களும், அந்த வரிகளுள் விலக்கப் பட்டனவும் கொடுக்கப்பட்டிருக்கும். தான சாசனம் அல்லாது வேறு வகையாயின் அதன் விவரம் தெளிவாக இந்தப் பகுதியில் தான்காணப் பெறும். ஆகவே இந்தப் பகுதியின் வாசகம் சாசனத்தின் உள்ளுரையை ஒட்டிச் சாசனத்துக்குச் சாசனம் வேறுபடும்.

முடிவு : இந்தப் பகுதியும் ஒவ்வொரு சாசனத்திலும் வெவ்வேறு விதமாக இருக்கும். இருந்தாலும், ஒம்படைக் கிளவி என்னும் இந்தப் பகுதி இல்லாத சாசனமே இல்லை என்னலாம். பழைய தமிழ்ச் சாசனங்களின் முடிவில் 'இது பன்மாகேச்வர ரகைத்', 'இவ்வறம் காத் தார் ஸ்ரீபாதம் என் தலை மேலன்' 'அறம் மறவற்க, அறமல்லது துணையிலலை' என்பன போன்ற வாசகங்கள் காணப்படும். இன்னும் பலவற்றின் முடிவில் சில குறிப்பிட்ட ஸம்ஸ்கிருத சுலோகங்கள் காணப்படுவதும் உண்டு. இந்தச் சுலோகங்களில் பல உள்ளன. சில சமயங்களில்

அவற்றுள் ஒரு சுலோகம் மட்டுமே எழுதப்பட்டிருக்கும். மற்றஞ் சில வற்றில் அதிகப்படியான சுலோகங்களும் காணப்படும். தமிழில் உள்ள சாசனங்கள் சிலவற்றின் முடிவிலும் இந்த ஸம்ஸ்கிருத சுலோகங்கள் கொடுக்கப்பட்டிருப்பதைக் காணலாம். (பெரும்பாலும் வழக்கில் உள்ள இத்தகைய சுலோகங்கள் இந்தத் தொகுப்பின் இரண்டாம் பாகத்தில் ஒரு பிற்சேர்க்கையாகக் கொடுக்கப் பட்டுள்ளன.)

இன்னும் சாசனங்களில் காணும் தர்மங்களைக் காப்பவர்கள் அடையும் புண்ணியமும் அவற்றுக்குக் கெடுதல் செய்பவர்கள் அடையும் பாபமும் விவரிக்கப்பட்டிருக்கும். தர்மத்தைக் காத்தவர்கள் அசுவமேதயாகம் செய்த பலனை அடைவார்களாம். சில சமயங்களில் ஆயிரம் யாகங்கள் என்றும் கூறப்பட்டிருக்கும். அன்றி, சிவலிங்கப் பிரதிஷ்டையினால் உண்டாகும் புண்ணிபத்தையும் பெறுவார்களாம். அதே போலக் கெடுதல் செய்தவர்கள் பஞ்ச மகாபாதகங்களைச் செய்த பாவத்தை அடைவார்களாம். 'இது இறக்குவான் கங்கையிடை குமரியிடை ஏழு தூற்றுக்காதமும் செய்தார் செய்த பாவமும் எய்துவான்', 'இதற்கு அஹிதம் செய்தவன் ஏழு பிறப்பும் வழியெச்சம் அறுவான்', 'இது விலக்குவான் கங்கையிடை குமரியிடை குரால் பசு கொன்றான் செய்த பாபம் கொள்வான்' என்பன போல் பலவிதமான பாபங்களும் தர்மத்தை விலக்குவார்மீது ஏற்றிக் கூறப்பட்டிருக்கும்.

பல்லவ அரசனான சிவஸ்கந்தவர்மன் தான் அளித்த நில தானத்தைப் பெற்றவர் அதை அனுபவிக்கமுடியாதபடி பீடையோ வாதையோ விளைவித்துத் தடை செய்பவர்களுக்குச் சரீர தண்டனை விதிக்கப்பெறும் என்று தன்னுடைய மயிதீவோலுச் செப்பேட்டுச் சாசனத்திலே கூறியிருக்கிறான். (எபி. இந்திகா, ஆறாம் வால்யூம்). அவ்விதம் அவன் உயிருடன் அரசுபுரியும் வரையில் தான் ரக்ஷிக்கமுடியும். என்றைக்கும் அவன் உடன் இருந்து பாதுகாப்பு அளிக்கமுடியாது. அதனாலேதான் அத்தகைய தர்மங்களுக்கு அஹிதம் செய்பவர்களைத் தெய்வமே தண்டிக்கும் என்று தெரிவித்துப் பழிபாவங்களை ஏற்றிக் கூறுவது சாசனங்களிலே வழக்கமாகிவிட்டது. அன்றி, ஒவ்வொரு அரசனும் தனக்கு முன்னால் ஆண்ட மன்னர்கள் அளித்த தானங்களை நல்ல முறையில் பரிபாலனம் செய்யவேண்டுமென்று கூறித் தானம் அளித்தவன் தனக்குப் பின்னால் வரப்போகும் அரசர்களைப் பிரார்த்தித்துக் கொள்வதாகவும் காணப்படும். அவ்விதம் அவர்கள் ஊழிக்காலம் வரையில் தானத்தைப் பரிபாலனம் செய்யவேண்டுமென்று கை கூப்பிப் பிரார்த்திக்கும்போது, செல்வ நிலையாமையையும் புகழ் நீர்க்குமிழி போன்ற தென்பதையும் தெரிவித்திருப்பார்கள். 'அதனோடு, பின்னால்



வரும் அரசர்கள் தங்களுக்கு முன்னால் இருந்தவர்கள் அளித்த தர்மங்களைப் பாதுகாக்கவேண்டுமென்று, அயோத்தி மன்னனான ராம பத்திரன் (அதாவது ராமபிரான்) வேண்டிக் கொண்டதாக உள்ள சுலோகத்தையும் கொடுத்திருப்பதைக் காணலாம். புதிதாகத் தானம் வழங்குவதைக் காட்டிலும் பழைய தர்மங்களைப் பரிபாலனம் செய்வதே சிறந்தது என்று வியாசர் இயற்றியதாகக் காணப்படும் ஒன்றிரண்டு சுலோகங்களும் எழுதப்பெற்றிருக்கும்.

இந்தப் பகுதி நாளாக ஆக விரிந்துகொண்டே வந்தது. தமிழ்ச் சாசனங்களிலும் இதே முறை கையாளப்பட்டு வந்திருக்கிறது.

சில சாசனங்களின் கடைசியில், முக்கியமாகச் செப்பேடுகளில், அவற்றை எழுதியவர் பெயர்களும் காணப்படும். நந்திவர்மன் பல்லவ மல்லனுடைய பட்டத்தாள் மங்கலச் செப்பேடுகளில் முடிவில் 'இவ் வெழுத்து வெட்டினேன் கச்சிப்பேட் டைம்பணச்சேரி விடேல் விடுகு பல்லவப் பெருந்தச்சன் மகன் ஸ்ரீ ஐணி(தண்டி)யேன்' என்று காணப்படுகிறது. (எபி. இந்திகா, பதினெட்டாம் வால்யூம்). சில சமயங்களில் பிரசஸ்தியை இயற்றிய கவிஞன் பெயர், அதைச் செதுக்குவதற்காகச் செப்பேட்டில் எழுதியவன் பெயர் ஆகியனவும் கூடக் கொடுக்கப்பட்டிருக்கும். ஒரு சாசனத்திலே (ஐ. முதல் வால்யூம், பக்கம் 49) பிரசஸ்தியை இயற்றிய கவியின் பெயர் தேவகணன் என்றும், அதைச் செப்பேட்டில் எழுதியவன் பெயர் கூத்திரியன் குமாரபாலன் என்றும், எழுத்து வெட்டியவன் பெயர் சம்புலன் என்றும் காணப்படுகிறது. மற்றொரு சாசனத்திலே (ஐ. பக்கம் 45) கவிஞன் பெயர் ரத்ன ஸிம்ஹன் என்றும், ஏட்டில் எழுதியவர், எழுத்து வெட்டியவர் ஆகிய இருவர்களும் மேலே காட்டிய சாசனத்தில் குறிக்கப்பட்டவர்களே என்றும் கூறப்பட்டுள்ளது.

எழுதுவோர் :-முன்னாளிலே சமூக வாழ்க்கையில் எழுதுவோர்கள் ஒரு முக்கியமான ஸ்தானத்தை வகித்து வந்தார்கள். அந்நாளில் இருந்த வாழ்க்கை நிலை, எழுதுகருவிகள், எழுதும் முறை, வாசிப்பதற்கு ஏற்றவகையில் தெளிவாக எழுதவேண்டிய அவசியம் ஆகியவையே எழுதுவோர்களுக்கு அத்தகைய ஸ்திதியை அளித்தனவென்னலாம். முத்ராராகுஸம் என்னும் வடமொழி நாடகத்தின் நாடக பாத்திரங்களுள் ஒருவரான சாணக்கியன், 'எவ்வளவு சிரத்தையோடு எழுதினாலும் என்னைப்போன்ற சுரோத்திரியர்களின் எழுத்து தெளிவாகவோ சுலபத்தில் புரியக்கூடியதாகவோ இரா' என்றும், 'ஆகவே எழுதுவோன் ஒருவனைக் கொண்டே என்னுடைய லிசிதங்களை எழுதிக் கொள்வது' என்றும் கூறுவதாக அதன் ஆசிரியரான குத்ரகர் எழுதி

யிருக்கிறார். நாட்டுமக்களில் நன்றாகப் படித்தவர்களும் தாங்களே அதிகமாக எழுதாமல் கையெழுத்து அழகாக உள்ளவர்களைக் கொண்டே தங்களுக்கு வேண்டியவற்றை எழுதிக்கொண்டனர். சமீபகாலம் வரையில் கூட, சர்க்கார் கச்சேரி ஒவ்வொன்றிலும் வெளியே அனுப்பவேண்டிய கடிதங்களையும் இதர தஸ்தாவேஜுகளையும் பிரதி செய்வதற்காகக் கையெழுத்து அழகாகவும் தெளிவாகவும் உள்ளவர்களை நியமித்து வந்தனர். டைப் அடிப்பது பழக்கத்துக்கு வந்தபிறகே இந்த முறை மாறலாயிற்று.

முன்னாளிலே பனையோலை, பூர்ஜபத்திரம், துணி முதலியவற்றில் எழுதுவதற்கு, அவற்றிலுள்ளும் முக்கியமாக அரசாங்கத் தஸ்தாவேஜுகளை எழுதுவதற்குப் பயிற்சிபெற்ற எழுத்தாளர்கள் இருந்தனர். எனினும், அவற்றைக் கல்விலும் செம்பிலும் கைதேர்ந்த வினைஞர்களே வெட்டிவந்தனர். இன்னும் அந்த எழுத்துக்களைச் சித்திரித்து எழுதுவதானால் அது நல்ல கைலாகவமும் கலையுணர்ச்சியும் உள்ளவர்களாலே தான் முடியும்.

எழுதுவோர்கள் அந்நாளிலே லேககர் என்று குறிக்கப்பட்டவந்தனர். சில சமயங்களில் லிபிகாரர் எனவும் பெறுவர். கிருஷ்ண ஜில்லா அமராவதியிலிருந்து கிடைத்த சாசனம் ஒன்றிலே ராஜ லேககன் ஒருவன் தானம் வழங்கிய செய்தி காணப்படுகிறது. அதிலிருந்து எழுதுவோர்களிலே கைத்திறமையும் சாமர்த்தியமும் வாய்ந்த சிலர் அரண்மனையிலும் அரசாங்கத்திலும் சேவகம் புரிந்துவந்தனர் என்பது தெளிவாகும். அசோகனுடைய பிரம்மகிரி, சித்தபுரச் சாசனங்களைப் பொறித்தவன் சபதன் எனப்பெறும் லிபிகாரன் என்று அந்தச் சாசனங்களில் காணப்படுகிறது. அரசனுடைய ஊழியத்தில் இருந்த எழுதுவோர்களைப் பற்றிக் கிடைக்கும் சாசனங்களில் இவையே மிகவும் பழமையானவை. ஸாஞ்சியிலிருந்து கிடைத்த சாசனத்திலே (எபி. இந்திகா, இரண்டாம் வால்யூம்) ஸுபாஹித கோதிபுதன் என்னும் ராஜலிபிகாரன் பெயர் காணப்படுகிறது.

தமிழ்நாட்டில் கிடைக்கும் கல்வெட்டுக்களிலே அதைக் கல்லில் பொறித்தவர்களுடைய பெயர் குறிக்கப்படுவதில்லை. செப்பேடுகளிலும் ஏதோ சிலவற்றிலே அவர்களுடைய பெயர் கொடுக்கப்பட்டிருக்கும். எனினும் தெலுங்கு நாட்டிலே கல்வெட்டுக்களிலும் பல சமயங்களில் அவற்றைப் பொறித்தவர்கள் யார் என்பது குறிப்பிடப்பெற்றிருக்கும். மேற்கு கோதாவரி ஜில்லா திராகூடாராமத்திலிருந்து கிடைக்கும் முதற் குலோத்துங்க சோழனுடைய தமிழ்ச் சாசனங்கள் இரண்டின்

முடிவிலும் அவற்றைக் கல்லிலே பொறித்தவன் 'டாக்ரேமி சுராசாரி ஆன விராஜேந்திர சோட ஆசாரி' என்பான் ஆவன் என்று தெலுங்கிலே வெட்டப்பட்டிருக்கிறது. (தெ. இ. சாசனங்கள், நான்காம் வால்யூம், 1246, 1227 எண்கள்). அவன் பெயரிலிருந்தே அவன் கல்வெட்டுகளைப் பொறிக்கும் பொறுப்பு ஏற்றிருந்த அரசாங்க அதிகாரியான கல்தச்சன் என்பது விளங்கும். இவ்விதம் அரசாங்க அதிகாரம் பெற்ற கல்தச்சர்கள் தமிழ்நாட்டிலும் இருந்திருக்கிறார்கள். இது சாசனங்களிலிருந்து நன்றாகத் தெரிகிறது. தஞ்சாவூர் ஜில்லாவிலே திருவையாற்றிலிருந்து கிடைக்கும் முதலாம் இராஜேந்திர சோழன் காலத்துச் சாசனம் ஒன்று, முதலாம் இராஜராஜ சோழனுடைய தேவியான உலோகமகாதேவி அவ்விடம் எழுப்பிய தக்ஷிண கைலாசம் என்னும் ஆலயத்தின் சுவர்களிலே கல்வெட்டுக்களைப் பொறிக்கும் உரிமையைக் காணியுடைய கல்தச்சனே அனுபவிக்கவேண்டும் என்று அவள் உத்தரவிட்ட செய்தியைத் தெரிவிக்கிறது. (இந்தத் தொகுப்பின் 610 நெ.) இதேபோல் கல்வெட்டும் காணியுடைய கல்தச்சர்கள் வேறு பல கோயில்களிலும் இருந்த விவரம் சாசன வாயிலாகத் தெரிய வருகிறது.

பிரசஸ்தி புனைந்தவர்—பல சாசனங்கள் உயர்ந்த காவிய நடையில் சொல் நயமும் பொருள் நயமும் கொண்டு சிறந்த கற்பனைகளுடன் அமைந்திருக்கின்றன. இதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். உண்மையில் சில சாசனங்கள் சிறந்த காவியங்களோடு சமமாக வைத்து எண்ணத்தக்கவை. எனினும் அத்தகைய பிரசஸ்தியைப் புனைந்த கவிஞர்களின் பெயர் பெரும்பாலும் பிறருக்குத் தெரியாமலே மறைந்து போயின. ஆனாலும் இங்கு ஒன்றும் அங்கொன்றுமாகச் சில பெயர்கள் தெரிகின்றன. கதம்ப வமிசத்து ஆதிகால வரலாற்றைக் கூறுவதாகத் தாளகொண்டை ஸ்தம்பத்தில் காணும் காவிய சாசனம் குப்ஜன் என்னும் புலவனால் புனையப் பெற்று அவனாலேயே கல்லிலும் எழுதப்பட்டதாம். இது 'குப்ஜஃ ஸ்வகாவியம் இதம் அஸ்மதலே விலேக' என்று அந்த கல்வெட்டிலேயே கூறப்பட்டிருக்கிறது. (எபி. இத்திகா, எட்டாம் வால்யூம்).

இவ்விதம் சாசனங்களுக்காகப் பிரசஸ்தி இயற்றும் கவிஞர்களும் அவற்றைச் செப்பேட்டில் பொறிப்பவர்களும் சில சமயங்களில் தங்கள் பதவிகளைப் பரம்பரை வழியிலே வகித்து வந்திருக்கிறார்கள் என்று தெரிகிறது. நந்திவர்மன் பல்லவமல்லனுடைய உதயேந்திரம் செப்பேட்டுச் சாசனத்தின் பிரசஸ்தியை எழுதிய கவிஞனை பரமேசுவரன் தன்னை ஸ்ரீசந்திரன் மகனென்றும் மேதாவியின் குலத்தில் உதித்தவன் (மேதாவி குலோத்பவன்) என்றும் கூறிக்கொள்ளுகிறான். (தெ. இ.

சாசனங்கள், இரண்டாம் வால்பூம்). பல்லவமல்லனுக்கு முன் ஆண்ட பல்லவ அரசர்களுள் ஒருவனான வலிம்ஹவர்மனுடைய செப்பேட்டுச் சாசனம் ஒன்று சமீபத்திலே கிடைத்துள்ளது. அதில் காணும் பிரசஸ்தியை மேதாவி என்னும் கவி இயற்றினான் என்று அந்தச் சாசனம் கூறுகிறது. உதயேந்திர சாசனத்தின் பிரசஸ்தி கர்த்தாவான பரமேச்வரன் குலத்தையே இவனும் சேர்ந்தவன் போலும்.

பூதானம் வழங்கிய சாசனத்தின் பிரசஸ்தியை இயற்றிய கவிஞர், அந்தச் சாசனத்தைச் செம்பில் பொறித்தவர் ஆகியோர்களும் சிற்சில சமயங்களில் தானம் வழங்கிய பூமியில் பங்கு பெற்றவர்களாக இருக்கக் காண்கிறோம். உதயேந்திரம் சாசனத்தை எழுதிய கவிக்கு அந்தக் கிராமத்தில் ஒரு பங்கு அளிக்கப்பட்டதாக அதே சாசனம் கூறுகிறது. இதேபோல் பாண்டிய மன்னனான பரார்தகன் நெடுஞ்சடையனுடைய வேள்விக்குடிச் செப்பேடுகளை எழுதிய யுத்தகேசரி பெரும்பனைக் காரன் அந்தக் கிராமத்திலே ஒரு மனையும், இரண்டு மா நன்செய் நிலமும் ஒரு புன்செய் பூமியும் பெற்றான் என்று காணப்படுகிறது. (எபி. இந்திகா, பதினேழாம் வால்பூம்).

கையெழுத்து:—எந்தப் பத்திரத்துக்கும் கடைசியில் கையெழுத்திட்டு முத்திரையையும் இட்டால்தான் அது பூர்த்தியாகும். சாசனங்களிலே அரசன் கையெழுத்து இடப்பட்டுக் காண்பதற்குப் பழமையான உதாரணம் கன்னேசியில் ஆண்ட வர்த்தன வமிசத்து அரசன் ஸ்ரீ ஹர்ஷனுடையதாகும். அது 'ஸ்வஹஸ்தோ மம மஹாராஜாதிராஜ ஸ்ரீ ஹர்ஷ தேவஸ்ய' என்று மிகவும் சித்திரித்த வகையில் எழுதப்பட்டிருக்கும். (எபி. இந்திகா, நான்காம் வால்பூம், பக்கம் 288). தாராநகரத்துப் பரமார வேந்தன் போஜதேவனுடைய சாசனங்களிலும் 'ஸ்வஹஸ்தோ மம ஸ்ரீபோஜதேவஸ்ய' என்று எழுதப்பட்டிருக்கும். (ஹெ. பதினேழாம் வால்பூம், 192-ஆம் பக்கம்). சில சமயங்களில் 'ஸ்வஹஸ்த' என்பது சேர்க்கப் பெறாமல் 'ஸ்ரீமூலராஜஸ்ய' என்பதுபோல அரசன் பெயர் மட்டுமே காணப்படும். (ஹெ. பத்தாம் வால்பூம்). வேறு சில சாசனங்களில் அரசன் பெயர் இல்லாமல் 'ஸ்வஹஸ்தோ மம' என்றே 'என்னுடைய கையெழுத்து இது' என்பது மட்டுமே காணப்படும். (ஹெ. முதல் வால்பூம், பக்கம் 88). சாசனத்தோடு சேர்ந்திருக்கும் முத்திரையில் அரசன் பெயர் காணப்படுமாதலால் இவ்விடத்தில் கொடுக்காமல் போனாலும் தவறு இல்லையென்றே கொண்டனர் போலும்.

தென்னாட்டிலே அரசனுடைய கையெழுத்து தெலுங்கு தேசத்தில் அரசு செலுத்திய சிற்றரசர்களுடைய சாசனங்களிலும் விஜயநகர வேந்தர்களுடைய சாசனங்களிலுமே காணப்படுகின்றன. விஜயநகர

ஸாம்ராஜ்யத்தின் ஆரம்பகாலத்துச் சாசனங்களின் முடிவில் 'ஸ்ரீ ஹரி ஹர' என்பதுபோல அரசன் பெயர் எழுதப்பட்டிருக்கும். தெலுங்கு தேசத்துச் சிற்றரசர்கள் சாசனங்களிலே 'சிங்கநாயனிவ்ராலு' என்பது போல வ்ராலு (கையெழுத்து) என்பது சேர்த்துக் காணப்படும். ஆனால் விஜயநகர சாசனங்களில் இந்தச் சொல் சேர்க்கப்பட்டிருக்காது. ஆரம்ப காலத்தில் அரசர்கள் பெயரையே எழுதிவந்தார்கள். எனினும் சிறிது காலத்திலே அந்த முறையை மாற்றித் தங்கள் தலைநகரில் கோயில் கொண்டு எழுந்தருளியிருக்கும் எம்பெருமான்பெயரையே தங்கள் இலச் சிணையாகக் கொண்டு 'ஸ்ரீ விருபாக்ஷ' என்று எழுதிவந்தார்கள். அம் மன்னர்கள் வைஷ்ணவ மதத்தைத் தழுவி விஷ்ணு பக்தர்களாக மாறிய பிறகு அதை மறுபடியும் மாற்றி 'ஸ்ரீ வேங்கடேச' என்று எழுதி வந்தார்கள்.

ஆனால் தமிழ்நாட்டிலே இம்முறை கையாளப்படவில்லை. பல்லவர், சோழர், பாண்டியர் போன்ற அரசர்களுடைய சாசனங்களிலும் அவர்களுக்கு அடங்கியவர்களாக அரசு செலுத்திய சிற்றரசர்களுடைய கல் வெட்டுக்களிலும் அவர்களுடைய கையெழுத்து காணப்படவில்லை. எனினும், அந்தச் சாசனங்களிலே கையெழுத்தே இல்லாமலும் இல்லை. சோழ சாசனங்கள் பலவற்றிலே புரவுவரி திணைக்களநாயகம், முக வெட்டி, திருவாய்க்கேள்வி என்பனபோன்ற உயர்தர அரசாங்கத்து அதிகாரிகள் பலருடைய கையெழுத்துக்கள் இடப்பட்டிருக்கின்றன. சில சாசனங்களில் இத்தகைய அதிகாரிகள் பலருடைய கையெழுத்துக்கள் ஒன்றன்பின் ஒன்றாக இடப்பெற்றுக் காணப்படுவதும் உண்டு. அந்தச் சாசனத்தில் காணும் அரசனுடைய உத்தரவு அரசாங்கத்திலே எந்த எந்தத் துறைகளில் எந்த எந்த அதிகாரிகளால் பரிசீலிக்கப்பட்டு அந்த அந்தத் துறை வரிப் புத்தகங்களில் வரியிலிடப்பெற்றது என்ற விவரத்தை அவை எடுத்துக் காட்டுகின்றன.

தமிழ்ச் சாசனங்கள் பலவற்றிலே இத்தகைய கையெழுத்துக்களே முடிவுப்பகுதியாக இராது. அரசன் அளித்த உத்தரவு அந்த அந்த ஊர்ச் சபையார்களுக்கே யாகும். அதன்மீது சபையார் எடுத்துக் கொண்ட நடவடிக்கையும் சாசனங்களில் கூறப்பட்டிருக்கும். பூமி தானங்களைத் தெரிவிக்கும் சாசனங்களிலே "நாட்டார் திருமுகம் கண்டு தொழுது தலைக்கு வைத்துப் படாகை நடந்து கல்லுங் கள்ளியும் நாட்டி"னர் என்பதுபோலச் சபையார் எடுத்துக்கொண்ட நடவடிக்கைகளும் விவரிக்கப்பட்டுள்ளன. (பாகூர்ச் செப்பேடுகள், எபி. இந்திகா, பதினெட்டாம் வால்பூம்). அரசன் ஓலைகளிலே 'கல்விலும் செம்பிலும் வெட்டிக்கொள்வாராக' என்று காணப்படுவதினின்றும் அந்த ஓலைகளைப்

பெற்ற சபையார் எடுக்கவேண்டிய நடவடிக்கை விவரமும் தெரியவரும். சபையாரே அந்த உத்தரவுகளைக் கல்லில் பொறித்துவந்தனர். அதனால் பல சமயங்களில் கல்லில் பொறித்த சபை அதிகாரியின் பெயரும் சாசனங்களின் முடிவில் காணப்பெறும்.

**முத்திரை :—** ஒரு பத்திரத்தின் மெய்ம்மையை நிரூபிக்கக் கையெழுத்துக்கு அடுத்தபடியாக அரசனுடைய முத்திரை முக்கியமானது. தர்மசாஸ்திர விதிகளின்படி பத்திரங்களுக்கு அரசாங்க முத்திரை இடவேண்டுமென்பது அவசியம் இல்லை யென்றும், ஆகவே அதைப் பழையகாலத்தில் முக்கியமானதாகக் கருதவில்லை யென்றும் சில ஆசிரியர்கள் சொல்வர். கி. பி. முதல் அல்லது இரண்டாம் நூற்றாண்டில் எழுதப்பெற்றதாகக் கருதப்படும் யாஜ்ஞவல்கிய ஸ்மிருதியிலே அரசன் அளிக்கும் பூதான பத்திரங்களில் அவன் முத்திரையும் இடப்படவேண்டும் என்று விதிக்கப்பட்டிருக்கிறது. எனினும் அரசனுடைய முத்திரை செப்பேட்டுச் சாசனங்களிலே தான் காணப்படுகிறது. கல்வெட்டுக்களிலே அதை இட முடியாதே.

உண்மையை நிரூபிக்க அரசன் முத்திரையோ முத்திரை பதித்த மோதிரத்தையோ உபயோகிக்கும் வழக்கம் மிகப் பழங்காலத்திலிருந்தே காணப்படுகிறது. இலங்கையில் இராவணனால் சிறை வைக்கப்பட்டிருந்த சீதையைப் பார்த்தபோது ஹனுமான் தான் கூறுவது முற்றிலும் உண்மை யென்பதை இராமனுடைய கணையாழியைக் காட்டி நிரூபித்தான் என்று இராமாயணம் கூறுகிறது. காளிதாசன் எழுதிய நாடகங்களுள் சிறந்த சாகுந்தலமும் துஷ்யந்த மன்னனுடைய முத்திரை மோதிரத்தை ஆதாரமாகக் கொண்டு எழுந்ததாகும். முத்திரா ராக்ஷஸம் என்னும் நாடகத்திலும் மந்திரியின் முத்திரை மோதிரமே பிரதானமாக விளங்குகின்றது. நாடகத்தின் பெயரே அதைக் குறிக்கிறது.

இன்னும் பாணகவி எழுதிய ஹர்ஷ சரித்திரத்திலும் அரசனுடைய முத்திரையைப் பற்றிய ஒரு சம்பவம் கூறப்பட்டிருக்கிறது. கௌட தேசத்தின் மீது படையெடுத்துச் செல்வதற்காகக் கிளம்பிய மன்னன் ஹர்ஷவர்த்தனன் சாஸ்வதி நதிக்கரையில் பாடி இறங்கியிருந்தான். அப்போது அந்த ஊர் அதிகாரி அரசன் முன்னிலையில் வந்து அன்றைத்தினம் செய்யவேண்டிய காரியங்களுக்கு ஆணையிட வேண்டி, அந்த உத்தரவை முத்திரையிட்டு அளிக்கப் புதிதாகச் செய்த பொன் முத்திரை ஒன்றையும் கொடுத்து, அதைப் பொறிப்பதற்காகக் களிமண்ணையும் நீட்டினானும், அரசன் கையில் வாங்கிய முத்திரை தவறிக் கீழே

கறுப்பு ஈரமண்ணில் விழுந்து உருண்டு ஓடியது. தலைகீழாக விழுந்த அது கீழே மண்ணில் தோய்ந்து பக்கத்துப் பூமியில் பதிந்தபோது அரசன் முத்திரை அந்த நிலத்திலே விழுந்தது. இதைக் கண்ட பரிஜனங்கள் இது தூர்நிமித்தமோ என்று எண்ணி மனங்கலங்கினர். ஆனால் அரசனே அதை ஒரு சுப ருசுகமாகவே கொண்டான். பூவுலகம் முழுதும் அவனுடைய ஒரே ஆணைக்கு அடங்கியதாக ஆகும் என்பதையே அது அறிவிப்பதாகக் கருதினனும். அவ்விடம் கூறியுள்ள படியே களிமண்ணைக் கையில் ஏந்தியே அதன்மீது முத்திரையைப் பதிப்பர் என்பதும் இப்போது கிடைக்கும் களிமண் முத்திரைப் படிமங்களால் உறுதியாகின்றது. அந்தப் படிமங்களின் பின்புறம் உள்ளங்கை ரேகைகள் பதிந்திருப்பதைக் இப்போதும் காணலாம். (ராயல் ஏஷ்யாடிக் ஸொஸைட்டி பத்திரிகை, 1901).

நம் நாட்டுக்கு வந்திருந்த சீன யாத்திரிகரான யுவான் சுவாங் கடைசியாக ஹர்ஷ மன்னனிடம் விடைபெற்றபோது அரசன் மெல்லிய பருத்தி நூல் துணியில் எழுதிச் செவ்வாக்கு முத்திரையிட்டலிகிதங்களை வழங்கினனும். அந்த யாத்திரிகரும் அவரோடு உடன் செல்வோர்களும் தாங்கள் பிரயாணம் செய்யும் நாடுகளிலே அரசன் அளித்த உத்தரவைக் காண்பித்தால் அந்நாட்டவர் அவர்களுக்கு வேண்டிய வசதிகளையும் வாகனங்களையும் அளித்து உதவுவார்களாம். இந்தச் செய்தி யுவான் சுவாங் வரலாற்றிலே விவரிக்கப்பட்டிருக்கிறது.

அவ்விதம் முன்னாளில் வழங்கி வந்த முத்திரை மோதிரம் ஒன்றும் இப்போது கிடைத்துள்ளது. அது செம்பினாலோ வெண்கலத்தாலோ செய்யப் பெற்றது. விரலில் கோத்துக் கொள்ளும் அதன் பாகம் ஒன்றேகால் அங்குலம் குறுக்களவு கொண்டது. முகப்பு ஒன்றே முக்காலே அரைக்கால் அங்குல நீளமும் ஒன்றையே அரைக்கால் அங்குல அகலமும் கொண்டு முட்டை வடிவமாக அமைந்துள்ளது. அதிலே நாகபட்டன் குமாரனான மஹாராஜா மஹேச்வரநாகன் என்பான் பெயர் காணப்படுகிறது. (குப்த சாசனங்கள், ப. 282) எழுத்துக்கு மேலே ஒரு கோடுஇட்டு அதற்கு மேலே படுத்திருக்கும் நிஷபத்தின் உருவம் ஒன்றும் பிறைச் சந்திரனும் காணப்படுகின்றன. எழுத்துக்குக் கீழே நாகத்தின் உருவம் காணப்படுகிறது.

செப்பேடுகளிலே காணப்படும் முத்திரைகளைப் பற்றி நாம் மேலே குறிப்பிட்டிருக்கிறோம். ஒற்றை யேட்டுச் சாசனமானால் முத்திரை அந்த ஏட்டிலேயே சேர்க்கப்பட்டிருக்கும். தேவபாலனுடைய மூங்கிர் சாசன ஏட்டை இதற்கு உதாரணமாகக் காட்டலாம். (எபி. இந்திகா,

பதினெட்டாம் வாலயும்). ஒன்றுக்கு மேற்பட்ட ஏடுகளையுடையதாயின் அந்த ஏட்டுத் துளைவழியாகக் கோத்திருக்கும் வளையத்திலே முத்திரை பொறிக்கப்பட்டிருக்கும். இவ்விதம் செய்வதால் சாசனத்திலே பிற்காலத்தில் புதிய ஏட்டைச் சேர்க்கவோ ஏற்கெனவே உள்ள ஏட்டை எடுக்கவோ முடியாமல் தடுப்பதற்கு வேண்டிய பாதுகாப்பாகவும் அது அமையும். ஒற்றை ஏட்டிலே பொருத்தப்பட்டிருக்கும் முத்திரை சில சமயங்களில் பெயர்ந்து தனியாக வந்துவிடுவதும் உண்டு. குமார குப்தனுடைய பிதாரி முத்திரை (வங்காளத்தா ஏஷ்யாடிக் ஸொஸைட்டி ஜர்னல், 1889), சர்வவர்மனுடைய அவரீகர் முத்திரை ஆகியவை இதற்கு உதாரணங்கள் ஆகும். (குப்த சாசனங்கள், பக்கம் 230).

முத்திரையிலே சாசனம் வழங்கிய அரசனுடைய பரம்பரையின் இலச்சினை முக்கியமாகப் பொறிக்கப்பட்டிருக்கும். பல்லவ முத்திரைகளில் படுத்திாக்கும் ரிஷபம், சாளுக்கிய, விஜய நகர மன்னர்களில் முத்திரைகளில் வராஹ (பன்றி) உருவம் ஆகியவைகளைக் காணலாம்.

சில சமயங்களில் முத்திரைகளில் ஒன்றுக்கு மேற்பட்ட உருவங்களும் காணப்படும். எனினும் அவற்றுள் அந்த அரசனுடைய வமிசத்து இலச்சினையே பிரதானமானதாக இருக்கும். மற்ற உருவங்கள் சிறிய அளவில் காணப்படும். அவற்றுக்கு உரிய அரசர்கள் அந்தச் சாசனம் வழங்கிய பேராசனுக்கு அடங்கிய சிற்றரசர்களாவர் என்பதையே அந்த உருவங்கள் குறிக்கின்றன. உதாரணமாக, சோழ மன்னர்களுடைய சாசனங்களில் காணும் முத்திரையிலே அவர்களுடைய இலச்சினையான புலியின் உருவத்தோடு பாண்டியர்களுக்கு உரிய மீனும் சேரர்களுக்கு உரிய வில்லும் இதே போல இன்னும் சில உருவங்களும் காணப்படும். மீன், வில் முதலியவை அந்நாளிலே பாண்டியச் சோழர் போன்றோர் சோழர்களுக்கு அடங்கியவர்கள் என்பதையே குறிக்கும். எனினும் சோழ வேந்தன் பேராசன் என்பதை எடுத்துக்காட்ட அவன் இலச்சினையான புலியின் உருவம் பிரதானமானதாக அமைந்திருக்கும்.

சாசனத்தை அளித்த அரசன் பெயரும் முத்திரையிலே காணப்படும் பழைய சாசனங்களில் அரசன் பெயர் மட்டுமே இருக்கும். எனினும் தமிழ் நாட்டுச் சாசனங்களின் முத்திரையிலே அதற்கு உரிய அரசனைப் புகழ்ந்து கூறும் பிரசஸ்தி போன்ற ஸம்ஸ்கிருத சுலோகம் ஒன்று சாசனத்தின் வட்டமான விளிம்பை யொட்டி எழுதப்பட்டிருக்கும். ஓரோரு சமயங்களில் அவ்வரசனுடைய கல்வெட்டுக்களிலும் அந்தச் சுலோகம் முதலில் கொடுக்கப்பட்டிருக்கும். வடநாட்டுச் சாசன முதல்



திரைகள் சிலவற்றில் அரசன் பெயர் மட்டுமேயல்லாமல் அந்த வம்சத்தை நிறுவிய முதல் அரசன் முதல் தொடர்ச்சியாக அவனுடைய வம்சாவளியும் கொடுக்கப்பட்டிருக்கும். குமார குப்தனுடைய பிதாரி முத்திரை, நாலந்தாவிலிருந்து சிதிலமாகக் கிடைத்த புதகுப்தனுடைய முத்திரை (மேலே ௩௬௭-ஆம் பக்கம்) ஆகியவை இதற்கு எடுத்துக் காட்டுகளாகும்.

சில சாசனங்களிலே மற்றொரு வகையான அரசாங்க அங்கீகாரமும் காணப்படுகிறது. அவற்றின் ஆரம்பத்திலே 'திருஷ்டம்' அதாவது 'பார்வையிடப்பட்டது' என்று பொறிக்கப்பட்டிருக்கும். பல்லவ அரசனான சிவஸ்கந்தவர்மனுடைய மயிதேவாலு (எபி. இந்திகா, ஆறாம் வால்யூம்), ஹீரஹடகல்விச் செப்பேடுகளில் (௧௭௫ முதல் வால்யூம்), இது திட்டம் என்ற பிராகிருதவடிவில் எழுதாமல் விடப்பட்ட முதல் ஏட்டின் முதற் பக்கத்திலே இடதுபுறத்தில் காணப்படுகிறது. வாகாடக அரசனான இரண்டாம் விந்தியசக்தியின் பாஸிம் செப்பேடுகளில் திருஷ்டம் என்ற ஸம்ஸ்கிருத வடிவில் அது கொடுக்கப்பட்டுள்ளது. (இந்திய சரித்திர காங்கிரஸ் நடவடிக்கைகள், கல்கத்தா, 1939) சாசனத்தை அரசனோ அரசாங்க அதிகாரிகளோ பார்வையிட்டு ஒப்புக் கொண்டனர் என்பதையே இந்தச் சொல் குறிப்பதாகும்.

இதேபோலத் தமிழ்ச் சாசனங்கள் சிலவற்றில், முக்கியமாகப் பாண்டிய அரசர்கள் வழங்கியவற்றில், துல்யம் என்ற சொல் ஆரம்பத்திலோ முடிவிலோ காணப்படுகிறது. இந்தச் சொல் 'சமம்' என்பதைக் குறிக்கும். தற்கால வழக்கில் உள்ளபடி இது 'சரியான பிரதி' என்பதற்கு ஒப்பாகும். கல்லில் பொறிக்கப்பட்ட சாசன வாசகத்தை மூலத்தோடு ஒப்புநோக்கிய பின் அது சரியான பிரதி என்று அதிகாரிகள் ஏற்றுக்கொண்டதையே துல்யம் என்னும் சொல் குறிக்கிறது. பாண்டியர்களின் ஆட்சியிலே இவ்விதம் கல்வெட்டுக்கள் பொறிப்பதை அரசாங்கமே நேரிடையாகக் கண்காணித்து வந்ததுபோலும்.

சில சமயங்களில் ஆரம்பத்தில் காண்பதுபோலவே சாசனங்களின் முடிவிலும் மங்கலச் சொற்களும் குறிகளும் காணப்படுகின்றன.

## 11. கல்வெட்டுக்களில் காலம் குறிக்கும் முறை.

ஒவ்வொரு பத்திரத்திலும் அது எழுதப்பெற்ற காலத்தைத் தெளிவாகக் கொடுக்கவேண்டுமென்று தர்மசாஸ்திரங்கள் விதிக்கின்றனவென்பதை நாம் முன்னரே எடுத்துக்காட்டியிருக்கிறோம். பெரும்பாலான சாசனங்களில் இந்த முறை முழுமையும் பின்பற்றியிருக்கக் காண

லாம். இவ்விதம் காலம் குறிக்கப்படுவதால்தான் தனி மனிதர்களுடைய விவகாரங்களை விவரிக்கும் சாசனங்களும் சரித்திர முக்கியத்துவம் வாய்ந்து ஆராய்ச்சிக்குப் பெரிதும் உபயோகப்படுகின்றன.

ஆனால் இவ்விதம் காலத்தைக் குறிப்பிடுவதிலே எல்லாச் சாசனங்களும் ஒரே முறையைப் பின்பற்றவில்லை. காலத்தைப் பலவகைகளில் கொடுத்திருக்கின்றன. சில சாசனங்கள் அந்தக் காலத்தில் அரசு புரிந்த மன்னனுடைய ஆட்சி ஆண்டையே குறிக்கின்றன. மற்றுஞ் சில குறிப்பிட்ட அப்தங்களின் ஆண்டுகளைக் கொடுக்கின்றன. வேறு சிலவற்றில் இரண்டும் சேர்ந்து காணப்படுகின்றன. இன்னும் சிலவற்றிலே வருஷம் தவிர, மாதம், பக்ஷம், திதி, கிழமை, நக்ஷத்திரம், தேதி போன்ற விவரங்களும் உள்ளன. அன்றி, சங்கராந்தி, கிரகணம் போன்ற புண்ணிய காலங்களையும் குறிப்பிட்டிருக்கக் காணலாம். இந்தப் பஞ்சாங்க விவரங்களைக் கொண்டு தானம் வழங்கப்பெற்ற நாளை நாம் நிச்சயமாகக் கணித்துவிடலாம். பிராகிருத சாசனங்களிலும் ஸம்ஸ்கிருத சாசனங்களில் பழமையானவைகளிலும் நாள் விவரம் வேறுவிதமாகக் காணப்படும். வருஷத்தை வருஷகாலம் (மழைக்காலம்), கிரீஷ்ம காலம் (கோடை), ஹேமந்தகாலம் (பனிக் காலம்) என்று குறிப்பிட்டு மூன்றாகப் பிரித்து ஒவ்வொரு காலத்தின் பக்ஷங்களையும் கொடுத்திருக்கக் காணலாம்.

தமிழிலே கிடைக்கும் சாசனங்களில் அரசனுடைய ஆட்சியின் ஆண்டே பெரும்பாலும் குறிக்கப்பட்டிருக்கும். பழையகாலத்துச் சாசனங்களில் ‘கோ விசைய நந்திவிக்கிரம பருமற்கு யாண்டு அறுபத்தொன்றாவது’ (எ.பி. இந்திகா, பதினெட்டாம் வால்யூம், பட்டத்தாள் மங்கலம் செப்பேடுகள்) என்பதுபோல ஆண்டு எழுத்தால் எழுதப்பட்டிருக்கும். அதேநாளில் வேங்கியிலும் இதர இடங்களிலும் கிடைக்கும் சாசனங்களில் இந்த ஆண்டு இலக்கத்தால் எழுதப்பட்டிருக்கும். கி. பி. ஒன்பது, பத்தாம் நூற்றாண்டுகளில் பொறிக்கப்பட்ட தமிழ்ச் சாசனங்களில், ‘கோ ராஜகேசரி பற்ம் [ர்] க்கு யாண்டு அ-எட்டாவது’ (தெ.இ. சாசனங்கள், பதினமூன்றாம் வால்யூம், 187-௧௭.) என்பது போல அரசனுடைய ஆட்சி ஆண்டு இலக்கத்திலும் எழுத்திலும் கொடுக்கப்பட்டிருக்கும். பிற்காலத்திலேதான் அந்த ஆண்டு இலக்கத்தாலேயே எழுதப்பட்டு வந்தது.

பாண்டிய சாசனங்கள் பலவற்றிலே, “யாண்டு இரண்டாவதின் எதிர் நாற்பத்திரண்டு” (செந்தமிழ், நான்காம் தொகுதி, பக்கம் 114), அல்லது ‘பதினமூன்றாவதின் எதிர் பன்னிரண்டாவது’ (இ. ஆ.,

இருபதாம் வால்யூம், பக்கம் 288) என்பவைபோல இரட்டை ஆண்டுகள் காணப்படுகின்றன. இவ்விதம் இரண்டு ஆண்டுகள் காணப்படுவதில் எது சாசனகாலம் என்பதை நிர்ணயிக்க முடியாமல் நீண்ட காலம் அதுபெரும்புதிராகவே இருந்தது. பாண்டிய மன்னனான இராஜசிம்மனுடைய சின்னமனுர்ச் செப்பேடுகளில் பெரிய சாசனத்திலே தான் இதற்கு விளக்கம் கிடைத்தது. அந்தச் சாசனத்தின் காலம் தமிழ்ப்பகுதியிலே 'இரண்டாவதின் எதிர் பதினான்காவது' என்றும் ஸம்ஸ்கிருதப் பகுதியில் 'ஷோடசே ராஜ்ய வர்ஷே' என்றும் காணப்படுகிறது. ஆகவே இரட்டை ஆண்டுகள் குறிக்கப்பெறும் இடங்களில் அந்த இரண்டு ஆண்டுகளையும் கூட்டிவந்த மொத்தத்தொகையே சாசனத்தின் காலத்தைக் குறிப்பதாகும் எனக்கொள்ளவேண்டுவது தெளிவாகும்.

ஆனால் ஏன் இந்தமுறை, முக்கியமாகப் பாண்டிய சாசனங்களில் மட்டும் காணப்படும் முறை, கையாளப்பட்டு வந்தது என்பது விளங்கவில்லை. இதை விளக்குவதற்கு ஆராய்ச்சியாளர்கள் பலவிதமான சமாதானங்களைக் கூறியிருக்கின்றனர். ஆயினும் எந்தக் கொள்கையும் ஏற்றுக்கொள்ளக் கூடியதாக இல்லை. ஒவ்வொன்றுக்கும் ஒவ்வொரு விதமான ஆகேஷ்பனை கிளம்புகிறது. எந்தக் கொள்கையும் எல்லா ஆகேஷங்களுக்கும் சமாதானம் கூறுவதாக இல்லை. திருப்பதி தேவஸ்தானத்தில் சாசனபரிசோதகராக இருந்த பண்டித சுப்பிரமணிய சாஸ்திரிகள் இதைப்பற்றி விரிவாகத் திருப்பதி ஸ்ரீ வேங்கடேசுவரர் கீழ்த்திசைக் கலை ஆராய்ச்சி நிலையத்துப் பத்திரிகையில் (ஜர்னல் ஆப் ஸ்ரீ வேங்கடேசுவர ஓரியண்டல் ரிஸர்ச் இன்ஸ்டிடியூட், ஆறு ஏழாம் தொகுதிகள்) ஆராய்ந்திருக்கிறார்.

தென் ஆர்க்காடு ஜில்லா எண்ணூயிரம் என்னும் கிராமத்திலிருந்து கிடைத்த முதலாம் இராஜாதிராஜ சோழன் ஆட்சி காலத்துச் சாசனம் ஒன்றிலிருந்து அரசன் உத்தரவு ஒன்று அவ்வூர்ச் சபையாரிடம் வந்து சேர்வதற்கு மூன்று வருஷமும் தூற்றுமூன்று நாட்களும் பிடித்தன வென்பதை நாம் முன்னரே (மேலே ௨௭௩ பக்கம்) குறிப்பிட்டிருக்கிறோம். முதலாம் இராஜேந்திர சோழனுடைய திருவேலங்காட்டுச் செப்பேடுகளிலிருந்து (தெ. இ. சாசனங்கள், மூன்றாம் வால்யூம்) அரசனுடைய ஆட்சியின் ஆறாம் ஆண்டு அளிக்கப் பெற்ற அந்தத் தானம் அவனுடைய ஆட்சியின் பன்னிரண்டாம் ஆண்டுக்குப் பிறகே செப்பேட்டில் பொறிக்கப்பட்டது என்பது தெரியவருகிறது. அவனுடைய ஆட்சியின் பன்னிரண்டாம் ஆண்டில் நிகழ்ந்த கங்காவிஜயம் அந்தச் சாசனத்தின் வடமொழிப் பிரசஸ்தியில் வருணிக்கப் பட்டிருப்பதி

வீருந்து இது விளங்கும். இவ்விதம் அரசன் உத்தரவு அளித்ததற்கும் அதை நிறைவேற்றி முடிப்பதற்கும் நடுவே இடைவெளி ஏற்படுவதைக் கவனிக்கும்போது, பாண்டிய சாசனங்களில் காணும் இரண்டு ஆண்டுகளுள் முதலில் கொடுக்கப்படுவதே சாசனத்துக்கான உத்தரவு வழங்கப்பட்ட வருஷம் என்றும், இரண்டாவதாகக் கொடுக்கப்படுவது அவ்விதம் உத்தரவு அளிக்கப்பட்டது முதல் சாசனம் பொறிக்கப்பட்ட நாள்வரையில் சென்ற இடைவெளிக்காலம் என்றும் கொள்ளலாம்.

இந்த ஆண்டுகள் சில சாசனங்களில் இரண்டுடன் நின்றுவிடாமல் ஐந்துவரையில் செல்வதையும் காணலாம். உதாரணமாக, ஒரு சாசனத்தில் (1907 ஆண்டு 358 ரெ.) 'நான்காம் ஆண்டுக்கு எதிராம் ஆண்டுக்கு எதிராம் ஆண்டுக்கு எதிராம் ஆண்டுக்கு எதிராம் ஆண்டுக்கு எதிராம் ஆண்டு' (4+1+1+1+1) குறிக்கப்பட்டிருக்கிறது. இவ்விதம் பின்னால் வரும் பல எதிராம் ஆண்டுகளையும் முதலில் அளிக்கப் பெற்ற உத்தரவை நிறைவேற்றுவதில் அந்த அந்த நிர்வாகக் கட்டடங்களில் செல்லும் காலத்தைக் குறிப்பனவாகக் கொள்ளலாம். (இதற்குத் தற்கால நடைமுறையில் ஓர் உதாரணமும் காட்டலாம். சர்க்கார் உத்தரவுகள் சிலவற்றிலே 15/19 என்பது போலத் தேதி குறிக்கப்பட்டிருக்கும். அதிலிருந்து 15௨ யன்றே உத்தரவு அளிக்கப்பட்டதென்றும் அதற்குப் பிரதி எடுத்து அதில் அதிகாரிகள் கையெழுத்திடுவதற்குச் சிலகாலம் பிடித்தது என்றும் 19௨ அது கையெழுத்தாயிற்று என்றும் கொள்கிறோம்).

அப்தங்கள் :—தென்னிந்தியச் சாசனங்களிலே, அவற்றுள்ளும் முக்கியமாகத் தமிழ்நாட்டிலே கிடைக்கும் சாசனங்களில், கி.பி. 78-ஆம் ஆண்டிலிருந்து கணக்கிடப்படும் சகாப்தமே பெருவழங்கில் காணப்படுவது ஆகும். முதன் முதலாக அந்த அப்தத்தில் வழங்கிய சாசனம் சகாப்தம் 465 கொண்டதாக வாதாபியிலே ஒரு பாறையில் பொறிக்கப்பட்டுள்ள முதலாம் புலிகேசி எனப்படும் சாளுக்கிய வல்லபேசுவா னுடையதாகும். (எபி. இந்திகா, இருபத்தேழாம் வால்யூம்). அடுத்த படியாக உள்ளது சகாப்தம் 500 கொண்டு அதே ஊரில் விஷ்ணுவின் குடைவரைக் கோயிலில் காணும் முதலாம் கீர்த்திவர்மனுடைய சாசனமாகும். (இ. ஆ., பத்தாம் வால்யூம்). எனினும் இலக்கிய வழக்கிலே இந்த அப்தம் இன்னும் முன்னதாகவே காணப்படுகிறது. தமிழ்நாட்டுத் திருப்பாதிரிப்புலியூரிலே திகம்பர ஜைனமுனிவரான ஸிம்ஹஸூரியின் தூலான லோக விபாகம் என்பது சகாப்தம் 380-ல் பிரதி செய்யப் பெற்றதாகக் காணப்படுகிறது. (மைசூர் புதை பொருள் இலாகா அறிக்கை, 1922).

தமிழ்நாட்டுச் சாசனங்களிலே சகாப்தத்தை இரண்டு வகையில் குறிப்பிடுவர். 'சகாப்தம் 1665-ன்மேல் செல்லாநின்ற' (இந்தத் தொகுப்பின் 947-ஆம் எண் கொண்ட சாசனம்) என்பதுபோல முடிந்து போன ஆண்டைக்கொண்டு குறிப்பிடுவது ஒரு முறை. அதன்படி அந்தச் சாசனம் பொறிக்கப்பட்ட காலத்தில் சகாப்தத்தின் 1665-ஆம் ஆண்டு முடிந்து 1666-ஆம் ஆண்டு நடந்துகொண்டிருந்ததென்று ஆகும். மற்றொரு முறையில் முடிந்துபோன ஆண்டைக் குறிப்பிடாமல் நடப்பு வருஷத்தைக் குறிப்பதாகும். இவ்விதம் நடப்பு வருஷமே குறிக்கப் பட்டுள்ளதென்பதை எடுத்த எடுப்பிலே தெரிந்துகொள்ள முடியாது. அறுபது வருஷக் கணக்கில் வரும் அந்த ஆண்டின் பெயரையும் இதர விவரங்களையும் கொண்டு கணித்துப் பார்த்தே நிர்ணயிக்க முடியும். இந்த முறைகளுக்குப் பின் வருவதை உதாரணமாகக் காட்டலாம். இப்போது அரசாங்கத்தார் நடைமுறையில் கொண்டிருந்த இந்திய தேசியப் பஞ்சாங்கத்தின்படி ஹேவிளம்பி வருஷத்துக்குச் சகாப்தம் 1879-ஆம் ஆண்டு ஆகும். இது முடிந்துபோன ஆண்டைக் கொண்டு கணக்கிடப்பட்டது. ஆயினும் தமிழ்நாட்டுப் பஞ்சாங்கங்களில் அது 1880-ஆம் ஆண்டு என்றே காணப்படும். அது நடப்பு வருஷக் கணக்கில் இடப்பட்டதாகும்.

தென் பாண்டிநாட்டிலும் மேலைக் கடற்கரை யோரமாகவுள்ள கேரளநாட்டிலும் பெருவழக்காக உபயோகப்படும் அப்தம் கி. பி. 824-ஆம் வருஷத்திலிருந்து தொடங்கும் கொல்லம் ஆண்டு ஆகும். பழைய சாசனங்களிலே இது 'கொல்லம் தோன்றி' எத்தனை ஆண்டுகள் சென்றனவென்றே குறிக்கப்படும். கொல்லம் எனப்படும் நகரம் நிர்மாணிக்கப் பெற்ற வருஷத்திலிருந்து இந்த ஆண்டு கணக்கிடப் படுவதாகக் கருதுவர்.

மற்றொரு வகையான கொல்லம் ஆண்டு, அதாவது கி.பி. 1096-ஆம் வருஷம் கொல்லம் அழிக்கப்பட்டதை யொட்டி எழுந்த 'கொல்லம் அழிந்த ஆண்டு' ஒன்றும் ஓரிடத்தில் குறிக்கப்பட்டதை நாம் இதே நூலில் மற்றோர் இடத்தில் (சரித்திரக்குறிப்பு, ராகு-நாக-ஆம் பக்கங்கள்) பிரஸ்தாபித்திருக்கிறோம்.

கி. மு. 3101-ஆம் ஆண்டு விஷுவினிலிருந்து ஆரம்பம் ஆவதாகக் கணக்கிடப்படும் கலியுக வருஷத்திலும் சில சாசனங்களில் காலம் குறிக்கப்பட்டிருக்கும். மதுரை ஜில்லா ஆணைமலைக் குடைவரைக் கோயிலில் கிடைத்த இரண்டு சாசனங்களில் ஒன்று (எபி. இந்திகா, ஏழாம் வால்யூம்) கி. பி. 770-ஆம் ஆண்டுக்குச் சமமான கலியுக வருஷம்

3871-ல் பொறிக்கப்பட்டதாகும். பிற்காலத்துச் சாசனங்கள் சிலவற்றில் கலியுக வருஷம் சகாப்தத்துடன் சேர்த்தே கொடுக்கப்பட்டிருக்கும்.

கோள தேசத்தில் கிடைக்கும் சில சாசனங்கள் வியாழவட்டம் எனப்பெறும் பார்ஹஸ்பத்ய வருஷத்தில் கணக்கிடப்பட்டிருக்கும். பிரஹஸ்பதி என்றும் குரு என்றும் குறிக்கப்படும் வியாழன் ஒவ்வோர் இராசியிலும் சுமார் ஒரு வருஷம் தங்குகிறார் என்று வானநூல் வல்லோர் கூறுவர். அவர் தங்குகிற இராசியைக் கொண்டு மேஷ வியாழன், விருச்சிக வியாழன் என்பனபோல் ஆண்டைக் கணக்கிட்டு கூறுவர். பாஸ்கர ரவிவர்மனுடைய தமிழ்ச் சாசனங்களின் ஆண்டு (திருவாங்கூர் ஆர்க்கியலாஜிகல் ஸீரிஸ், இரண்டாம் வால்யூம்) இந்த முறையிலே குறிக்கப்பட்டுள்ளது.

முஸ்லிம்கள் உபயோகிக்கும் ஹிஜ்ரி வருஷத்தில் கணக்கிட்ட மூன்று தமிழ்ச் சாசனங்கள் கிடைத்துள்ளன. ஒன்று தேவகோட்டையிலும் மற்றொன்று திருப்புத்தூரிலும் கிடைத்துள்ளன. இராமநாத புரம் ஜில்லாவில் கிடைத்த இவ்விரண்டையும், டாக்டர் கிருஷ்ணசாமி ஐயங்கார் அவர்கள் தம்முடைய 'தென்னிந்தியாவும் அதன்மீது படை எடுத்துவந்த முகம்மதியர்களும்' என்னும் நூலில் அனுபந்தமாகக் கொடுத்திருக்கிறார். மூன்றாவது சாசனம் கோயம்புத்தூர் ஜில்லா அலங்கியத்தில் கிடைத்தது. (1920-ஆம் ஆண்டின் 160-நெ). இம் மூன்றும் கி.பி. பதினான்காம் நூற்றாண்டில் அந்தப் பகுதிகளை மதுரை சுல்தான்கள் ஆண்டுவந்த நாளில் பொறிக்கப்பட்டவை.

மேலைச் சாளுக்கிய வேந்தனான ஆரூர் விக்கிரமாதியன் கி. பி. 1075-76-ஆம் ஆண்டு முதல் தன்னுடைய பெயரால் சாளுக்கிய விக்ரம் அப்தம் என ஒன்றைப் புதிதாக ஆரம்பித்தான். அவனுக்குப் பிறகு சாளுக்கிய சிங்காசனம் ஏறிய அவன் மகன் காலத்திலும் அந்த அப்தம் வழக்கில் இருந்தது. எனினும் நாளடைவில் வழக்கொழிந்து மறைந்து விட்டது. அதேபோல அவனுக்குப் பின்னால் வந்த அரசர்களில் வேறு ஒருவனும் தன் பெயரால் ஒரு புதிய அப்தத்தை ஆரம்பித்தான். அதுவும் நீடிக்கவில்லை. சிக்கிரமாகவே மறைந்துவிட்டது. அன்றி அந்த அப்தங்களில் காலம் குறிக்கப்படும் சாசனங்கள் தெலுங்கு கர்நாடகப் பிரதேசங்களிலேதான் காணப்படுகின்றன.

கோள தேசத்திலிருந்து கிடைக்கும் சாசனங்களில் வேறுபலவகையான அப்தங்கள் காணப்படுகின்றன.

“திருக்கண்டியூர் மகாதேவர்க்கு ஸர்வாதித்யம் செய்தருளிச் செல்லாநின்ற யாண்டு முந்நூற்றுத் தொண்ணூற்று நாலாம் ஆண்டை மேட வியாழத்தில்” (திருவாங்கூர் ஆர்க்கியலாஜிகல் வலீரிஸ், முதல் வால்யூம், 290-பக்கம்).

“திருக் குலசேகரபுரத்துத் தளிக்குச் செல்லாநின்ற யாண்டு நூற்றுத் தொண்ணூத்தஞ்சு; இவ்வாண்டு மகர நாயற்று” (ஷே, ஆறாம் வால்யூம், 193-பக்கம்).

கி. பி. 1663-ஆம் ஆண்டில் கொச்சி மன்னருக்கும் ‘லேந்தா கும் மஞ்ஜி’ (உலாந்தாக் கும்பினி) எனப்பெற்ற டச்சு கிழக்கு இந்தியக் கம்பெனியாருக்கும் இடையில் ஏற்பட்ட ஒப்பந்தம் புதுவைப்பு ஆண்டு 322-ல் செய்யப்பெற்றதாகப் பாலியம் செப்பேடுகள் கூறுகின்றன. (ஷே முதல் வால்யூம்.) வைப்பு என்னும் தீவு புதிதாகக் கடலில் தோன்றிய காலத்திலிருந்து கணக்கிடப்படுவதே இந்த அப்தம் என்று கூறுவர்.

இதேபோல, அந்த அந்த ஊர்களில் முக்கியத்துவம் பெற்ற ஏதோ சில சம்பவங்களைக் கொண்டு கணக்கிடப்பெற்ற சாசனங்களும் மலைநாட்டில் கிடைத்துள்ளன. (தேசிக விநாயகம் பிள்ளை எழுதிய ‘காந்தளூர்ச் சாலை’, பக்கங்கள் 18-20 பார்க்க).

சகாப்தத்துக்கு நூற்று முப்பத்தைந்து ஆண்டுகளுக்கு முன்னால், அதாவது கி. மு. 57-ஆம் ஆண்டு, ஆரம்பிப்பதாகக் கணக்கிடப்படும் விக்கிரம அப்தமும் சாசனங்களிலே பெரிதும் வழங்கப்பெறும் அப்தங்களுள் முக்கியமானதாகும். எனினும், அது வட இந்தியாவிலேதான் அதிகமாக வழங்கிவந்திருக்கிறது. தென்னாட்டிலே அதன் உபயோகம் மிகவும் குறைவு. பழைய சாசனங்களிலே இது கிருத வருஷம், மாலவ அப்தம் என்பன போன்ற பெயர்களாலும் எந்த அடைமொழியும் இல்லாமல் ஸம்வத் அல்லது ஸம்வத்ஸரம் என்றும் காணப்படும். பிற்காலச் சாசனங்களில் அவ்வாண்டு விக்கிரம ஸம்வஸ்தரம் என்றும் குறிக்கப் பட்டிருக்கும்.

வட இந்தியச் சாசனங்களில் இன்னும் பல வேறு அப்தங்களும் உபயோகிக்கப்பட்டு வந்துள்ளன. கி. பி. 319-ஆம் ஆண்டில் ஆரம்பமாகும் குப்த ஸம்வத்ஸரம், அதே ஆண்டில் ஆரம்பமாகும் வல்லபி ஸம்வத்ஸரம் (இவ்விருண்டும் ஒரே அப்தமாகும் எனவும் கொள்வர்), கி. பி. 248-ஆம் ஆண்டு ஆரம்பமாவதாகக் கணக்கிடப்படும் சேதி அப்தம் அல்லது கலசூரி அப்தம், அதே காலத்தில் ஆரம்பிக்கும் திரைகூட-

ஆபிர ஸம்வத்ஸரம் (குப்த-வல்லபி ஸம்வத்ஸரத்தைப் போலவே இவ் விரண்டும் ஒரே அப்தத்தைக் குறிக்கும் என்று கூறுவர் ஆராய்ச்சி யாளர்), கி. பி. 606-7-ஆம் ஆண்டு ஆரம்பமாகும் ஹர்ஷவர்ஷம், கி. பி. 879-ஆம் ஆண்டை முதல் வருஷமாகக் கொண்டுள்ள நேவார் அப்தம், கி. பி. 1179-ஆம் வருஷம் ஆரம்பமாகி வங்காளத்தில் பெரு வழக்கில் காணும் லக்ஷ்மண ஸேன அப்தம், கி. பி. 496-ஆம் ஆண்டு துவங்கும் கலிங்கநாட்டுக் கங்க மன்னர்கள் அனுஷ்டித்த கங்க அப்தம் ஆகியவை முக்கியமானவை.

இன்னும் இதேபோல எத்தனையே அப்தங்கள் உள்ளன. ஜைன தீர்த்தங்கரரான மஹாவீரர் நிர்வாணம் ஆன நாளிலிருந்து கணக்கிடப் பட்ட மஹாவீர அப்தம் அல்லது வீர நிர்வாண அப்தம் ஒன்று வழங் குகிறது. இது பெரும்பாலும் ஜைனர்களால் சுவடிகளிலே காலம் குறிப் பிடுவதற்குத் தான் உபயோகிக்கப்பட்டு வந்தது. அம்மாதிரியே புத்த பகவான் நிர்வாணம் ஆன நாளிலிருந்து கணக்கிடப்படும் அப்தமும் உண்டு. அது அந்த மதத்தினரால் பெரிதும் கையாளப்பட்டு வந்தது. இன்றைக்கும் இலங்கை, பர்மா போன்ற நாடுகளில் இந்த ஆண்டுக் கணக்கு வழக்கில் உள்ளது.

இந்த அப்தங்கள் பலவற்றின் ஆரம்பகாலம் சந்தேகத்துக்கு இட மின்றித் தீர்மானிக்கப்பட்டு விட்டதென்று சொல்லமுடியாது. சில வற்றின் ஆரம்ப காலத்தைப்பற்றி ஆசிரியர்களுக்குள்ளே அபிப்பிராய பேதம் இருந்து வருகிறது. வேறு சில அப்தங்கள் எவ்விதம் யாரால் தோற்றுவிக்கப்பட்டன வென்பதைப் பற்றியும் ஆசிரியர்கள் மாறு பட்ட கருத்தைக் கொள்வர். உதாரணமாகப் பெருவழக்கில் உள்ள சகாப்தத்தை யார் நிறுவினர் என்பது இன்னும் உறுதியாகவில்லை. பலர் பலவிதமாகக் கூறுவர். இந்த அப்தங்களைப் பற்றிய ஆராய்ச்சியே தனி ஞாலாக விரியும்.

### எழுத்துக்களுக்கு எண் ரதீப்பீடும் முறை

சாசனங்களிலே சில சமயங்களில் ஆண்டை எண்ணுகக் கொடுக்கா மலும் எழுத்தால் எழுதாமலும் சில குறிப்பிட்ட எழுத்துக்களைக் கொண்டோ சொற்களைக் கொண்டோ தெரிவிக்கும் பழக்கமும் காணப்படுகிறது.

எழுத்துக்களுக்கு எண்மதிப்பிட்டுக், குறிப்பதில் கட்பயாதி, ஸித்தமாத்திரிகை என்று இரண்டு முறைகள் உண்டு. இவ்விரண்டு



வகைகளும் தென்னிந்தியாவுக்கே உரியன என்று கூறுவர் டாக்டர் பர்ணல். (தென்னிந்தியப் பிராசினலிபி, பக்கம் 79).

கடபயாதி முறையில் ஸம்ஸ்கிருத நெடுங்கணக்கில் உள்ள மெய்யெழுத்து ஒவ்வொன்றுக்கும் பின்வருமாறு எண் மதிப்பிட்டு உபயோகிப்பர்.

1	2	3	4	5	6	7	8	9	0
க	வ	ம	வ	ஐ	அ	அ	ஜ	ஸ	ரூ
ட	௦	௩	௩	ண	த	ய	டி	ய	ந
வ	ம	வ	ஹ	உ	....	...	....	...	....
ய	ர	ரு	வ	ய	ஷ	ஸ	ஹ	௭	....

இந்த முறையில் காலத்தைக் குறிப்பிடுவதற்கு வேண்டிய எழுத்துக்களைக் கொண்டு ஏற்ற சொல்லை அமைத்து அந்தச் சொல் மூலமாகக் காலத்தைத் தெரிவிப்பர். பெரும்பாலும் அது சுலோக வடிவிலே தான் இருக்கும். அவ்விதம் செய்யும்போது எண் மதிப்பு வாய்ந்த மெய்யெழுத்துக்களை மட்டும் கொண்டு அந்தச் சொல்லை அமைக்க முடியாது. மொழி வழக்கையொட்டி அதிகப்படியான எழுத்துக்களை உபயோகிக்கவேண்டும். அதனால் அவ்விதம் அமைந்த சொல்லில் வரும் உயிர் எழுத்துக்களுக்கும் கூட்டெழுத்துக்களில் முன்னால் உள்ளவற்றுக்கும் மதிப்பு இல்லை. மெய்யெழுத்துக்களுக்கு மட்டுமே, அதுவும் கூட்டெழுத்துக்களாயின், பின்னால் வருவனவற்றுக்கு மட்டுமே எண்மதிப்பு உண்டு. பல சமயங்களில் அவ்விதம் அமைக்கப்படும் சொல்லுக்கும் காலத்தைத் தெரிவிக்கவேண்டிய விஷயத்துக்கும் பொருள் தொடர்பும் இருக்கக் காணலாம்.

காஞ்சிபுரம் வரதராஜர் கோயிலில் உள்ள சாசனம் ஒன்று (இந்தத் தொகுப்பில் 1290 நெ.) சகாப்தம் 1536-ஆம் ஆண்டில் லக்ஷ்மீகுமார தாதாசாரியார் அந்தக் கோயிலில் கல்யாணகோடி விமானத்தைக் கட்டி முடித்தார் என்பதைத் தெரிவிக்கிறது. சுலோக ரூபமாக அமைந்திருக்கு அது சகாப்தத்தைத் தெரிவிக்கும்போது,

தல்லக்ஷ்மீயே சகாப்தே

6 3 5 1

என்று கூறுகிறது. கடபயாதி முறையில் கணக்கிடும்போது அந்த வருஷம் 1536 ஆகும்.

இந்தமுறையிலும், இதேபோன்ற மற்றொன்றான பூதசங்கியை என் பதிலும், கொடுக்கப்படும் எண்களில் ஒன்றாவது ஸ்தானம் முதலிலும் பத்தாவது ஸ்தானம் அதற்கு அடுத்தபடியாகவும் நூறாவது ஸ்தானம் அதை அடுத்து மூன்றாவதாகவும், மற்ற ஸ்தானங்களும் இவ்விதமே தொடர்ச்சியாகவும் கொடுக்கப்பட்டிருக்கும். அதனால் அந்த எண்களை இப்போது உள்ள முறையில் கணிக்க வலத்திலிருந்து இடமாகக் கொள்ளவேண்டும்.

ஸித்தமாத்திரிகை என்னும் மற்றொருமுறை பாராக்கடி என்றும், துவாத்தாஃஃரீ என்றும் கூடக் குறிக்கப்பெறும். அதிலே வடமொழி உயிர் எழுத்துக்களில் ஃ, ஃ3, ள, ள3 ஆகிய நான்கையும் நீக்கி மற்றப் பன்னிரண்டுக்கும் பின்வருமாறு ஒன்று முதல் பன்னிரண்டு வரையில் எண் மதிப்பிட்டு வழங்குவர்.

சு	சூ	உ	஁	உ	ஊ	வ	வெ	ஐ	ஐ	ஃ	ஃ
1	2	3	4	5	6	7	8	9	10	11	12

சுவடிகளின் ஏடுகளை எண்ணிடுவதற்கே இம்முறை உபயோகிக்கப் பட்டுவந்தது. இன்றைக்கும் இலங்கை, பர்மா, தாய்லந்து போன்ற நாடு களில் வழக்கில் உள்ளது. இம்முறையில் எண்களைக் குறிக்கும்போது உயிர் எழுத்துக்கள் முடிந்தவுடன் உயிர் ஏறிய மெய்யெழுத்துக்களை உபயோகிப்பார். ஆகவே ௯ முதல் ௧௧ வரையில் உள்ள பன்னிரண்டு எழுத்துக்களுக்கும் 13 முதல் 24 வரையில் மதிப்பு; ௨5 முதல் ௩6 வரையில் உள்ளவை 25 முதல் 36 வரையில் மதிப்பு அடையும். இவ் விதமே மற்ற எழுத்துக்களுக்கும் ஆகும்.

பர்மாவிலிருந்து கிடைத்துள்ள ஒரு சுவடியில் ஏடுகளுக்கு இடப் பட்டிருக்கும் எண் உயிர் எழுத்துக்களைக் கொண்டு ஆரம்பிக்காமல், மெய்யெழுத்துக்களைக் கொண்டே ஆரம்பிக்கப்பட்டுள்ளது. அதிலே ஃ, ஃ3, ள, ள3 ஆகிய நான்கையும் விலக்காமல் சேர்த்துக்கொண்டு பதினாறு எழுத்துக்களாகக் கணக்கிடப்பட்டிருக்கிறது. ஆகவே ௯ முதல் ௧௧ வரையில் உள்ள எழுத்துக்களுக்கு 1 முதல் 16 வரையிலும் மதிப்பு ஆகும். அதற்கு அடுத்த எழுத்தான ௨ அப்பால் உப யோகிக்கப்படும். இவ்விதம் எல்லா எழுத்துக்களும் ஒரு முறை உப யோகித்த பிறகும் வேண்டியிருந்தால் ௨ ௯, ௨ ௧௦ என்ற வரிசையில் ஆரம்பிக்கப்படும்.

தாய்லந்தில் கிடைக்கும் சுவடிகளில் ஏடுகளை எண்ணிடப் பர்மா வில் காணும் முறையே கையாளப்பட்டிருக்கிறதாம்.

## பூதசங்கியை

எண்ணைச் சில குறிப்பிட்ட சொற்களால் உணர்த்தும் முறை மற்றொன்று. உலகம் மூன்று என்பதையும் வேதம் நான்கு என்பதையும் யாவரும் அறிவர். அதனால் மூன்று, நான்கு என்னும் எண்களை முறையே லோகம், வேதம் என்ற சொற்களால் குறிப்பிடுவது இம் முறை. இவைபோல மற்ற எண்களுக்கும் உண்டு. இது பூதசங்கியை எனப் பெறும்.

இவ்விதம் எண்களைச் சொற்களால் உணர்த்தும் பழக்கம் பழைய நூல்களிலும் காணப்படுகிறது. காத்யாயனர், லாத்யாயனர் போன்றார் எழுதிய சிரௌத ஸூத்திரங்களில் இம்முறை குறிக்கப்பட்டுள்ளது. பூதசங்கியையால் எண்ணை உணர்த்துவனவாகக் காண்பதிலே சிரௌத சூத்திரங்களே மிகவும் பழமையானவை என்பர். இன்னும் இம்முறை வேதாங்கஜோதிஷத்திலும் உபயோகிக்கப்பட்டுள்ளது. வராஹமிஹிரர் எழுதிய 'பஞ்சசித்தாந்திகை', பக்ஷாலி கணிதச்சுவடி ஆகியவற்றிலும் காணப்படுகிறது. அரபு யாத்திரிகரான அப்பெரூரீ இம்முறையில் பூஜ்யம் முதல் நாற்பத்தொன்பது வரையில் உள்ள எண்களை எந்த எந்தச் சொற்களைக் கொண்டு குறிப்பர் என்பதை விவரமாகக் குறித்திருக்கிறார்.

சாசனங்களிலும் காலம் குறிப்பிடுவதற்கு இந்த முறை பயிலப்பட்டு வந்திருக்கிறது. ஸ்ரீரங்கத்திலே சகாப்தம் 1461-ஆம் ஆண்டு கொண்டதாக விஜயநகரவேந்தன் அச்சுததேவராயனுடைய சாசனம் ஒன்று கிடைத்துள்ளது. அரசன், ஹம்பியிலே போலும், நடத்திய துலாபாரத்தைப் பற்றிக் கூறும் அந்தச் சாசனத்திலே அவன் தேவியான திருமலாம்பா இயற்றிய இரண்டு ஸம்ஸ்கிருத சுலோகங்களும் உள்ளன. (எபி. இந்திகா, இருபத்துநான்காம் வால்யூம், 270 பக்கம்). அதிலே ஒரு சுலோகத்தில் அவள் சகாப்தம் 1461 என்பதைச் 'சாகே சந்த்ர ரஸா மரேந்திர கணிதே' என்று குறிக்கிறாள். சந்திரன் என்பது ஒன்று ஆகும். ரஸம் ஆறு. அமரேந்திரர், அதாவது இந்திரர், பதினான்கு. இவ்விதம் குறித்த எண்ணை வலமிருந்து இடமாக வாசித்தால் 1461 ஆகும்.

கடபயாதியைப் போலவே இம்முறையிலும் ஒன்றும் ஸ்தானத்தை முதலிலும், பத்தாம் ஸ்தானத்தை அடுத்தபடியாகவும், இவ்விதமே மற்ற ஸ்தானங்களையும் பின்னால் சேர்த்துக் கொடுப்பர். அதனால் இலக்கத்தின் மதிப்பை அறிய வலத்திலிருந்து இடமாக வாசிக்க வேண்டும்,

இம்முறையில் ஒன்று முதல் பன்னிரண்டு வரையில் உள்ள எண்களுக்கு உபயோகிக்கும் சொற்களில் முக்கியமானவை பின்வருமாறு. பலசமயங்களில் இவற்றின் பொருளைக் கொடுக்கும் வேறு சொற்களும் காணப்படுவது உண்டு.

0(பூஜ்யம்). சூன்யம்; அம்பரம், ஆகாசம்; அனந்தம் (முடிவு இல்லாதது).

1. இந்து, சசி (சந்திரன்); பூ, மஹி; ஆதி; பிதாமகன் (பிரம்மா); ரூபம், தனு (தேகம்); நாயகன் (தலைவன்).

2. நயனம் (கண்கள்); கர்ணம்(காதுகள்); பாஹு; கரம்; பக்ஷம்; யமம், யமளம் (இரட்டை); அச்வின், தஸ்ரர் (அசுவினி தேவர்கள்); ரவி சந்த்ரோள (சூரிய சந்திரர்); குடும்பம்.

3. அக்ரி, ஹோத்ரு (மூன்று வேள்வித் தீ); ராமா: (மூன்று ராமர்கள்); குணம், திரிகுணம்; லோகம், திரிஜகத் (சுவர்க்கம், பூமி, பாதாளம்); காலம், திரிகாலம் (இறந்த காலம், நிகழ்காலம், எதிர் காலம்); சகோதரன்.

4. வேதம், சுருதி; திசை; வர்ணம்; அப்தி, ஜலதி (சமுத்திரம்); அயம், கிருதம் (பகடைக்காய்); பந்து, கோஷ்டம்.

5. பாண்டவர், இந்திரியம் (மெய், வாய், கண், மூக்கு, செவி); அர்த்தம், விஷயம்; பூதம் (நிலம், நீர், நெருப்பு, காற்று, வெளி); இஷு, பாணம் (காமன் கணைகள்); பிராணன்; ரத்தினம்; சுதன், புத்திரன்

6. ரஸம் (அறுசுவை); ருது; அங்கம் (வேதாங்கம்); தர்சனம் (அறுசமயம்) காயம்; ராகம் (இசைப் பண்கள்); அரி, சத்தரு.

7. ரிஷி (சில சமயங்களில் ஏழு முனிவர்களில் முதல்வரான அத்திரி என்றே குறிக்கப் பெறுவதும் உண்டு); அசுவம் (சூரியனுடைய ஏழு குதிரைகள்); அகம் (மலைகள்); தாது; சந்தஸ்; களத்திரம்.

8. வசு (அஷ்ட வசுக்கள்); அஹி (எட்டுவகைப் பாம்புகள்); கஜம் (அஷ்ட திக்குக் கஜங்கள்); ஸித்தி (அஷ்டமாசித்தி); மங்களம்.

9. அங்கம் (தசாம்ச கணிதம்); நந்தர் (நவநந்தர்கள்); கோ, கிரகம் (நக்கிரகங்கள்); சித்ரம், துவாரம் (உடலின் நவத்துவாரங்கள்); நிதி (குபேரனுடைய நவநிதி); பவனம்; பாக்கியம்,

10. அவதாரம் (விஷ்ணுவின் பத்து அவதாரங்கள்); ராவண சிரசு; கர்மா; கேந்து (க் + இந்து, அதாவது ஆகாசமும் (0) சந்திரனும் (1) அல்லது (10).

11. ருத்திரர் (சில சமயங்களில் ஏகாதச ருத்திரர்களில் முதல்வரான ஈசன் அல்லது சிவன் என்றே குறிப்பர்); அக்ஷேஷ்விணி; (போர்ப்படை); இலாபம் (வரவு).

12. ஆதித்தியர், அர்க்கர் (பன்னிரண்டு சூரியர்கள்); வியயம் (செலவு).

ஜோதிஷத்தில், ஜாதகத்தைக் கொண்டு பலன்காணும் பிரிவிலே, பன்னிரண்டு இராசிகளில் முதல் வீட்டைத் தேகம் என்றும், இரண்டாவதைக் குடும்பம் என்றும், மூன்றாவதைச் சகோதரர் என்றும், நான்காவதைப் பந்து என்றும், ஐந்தைப் புத்திரஸ்தானம் என்றும், ஆறாவதைச் சத்துரு வீடு என்றும், ஏழாவதைக் களத்திரஸ்தானம் என்றும், எட்டாவது மங்கலியஸ்தானம் என்றும், ஒன்பதாவது பாக்கியஸ்தானம் என்றும், பத்தாவது கர்மஸ்தானம் என்றும், பதினென்றை லாபம் எனவும், பன்னிரண்டை வியயஸ்தானம் என்றும் குறிப்பிடுவார்கள்.

சாசனங்களிலே காலத்தைக் குறிப்பிடும்போது சில சமயங்களில் ஒன்றுக்கு மேற்பட்ட முறைகளைக் கலந்துவிடுவார்கள். உதாரணமாக ஒரு சாசனத்தில் மூவாயிரத்து எண்ணூறு என்னும் எண் 'ஸஹஸ்ர த்ரதய வஸு சதை' என்று கொடுக்கப்பட்டுள்ளது.

## 12. சில சாசன வழக்காறுகள்

இதுகாறும் கல்விலும் செம்பிலும் கிடைத்துள்ள சாசனங்களில் பழமையானவை எளியனவாகவும் சுருக்கமாகவும் எழுதப்பட்டுள்ளன. வாசக அமைப்பிலோ நடையிலோ சம்பிரதாயங்கள் அப்போது ஏதும் ஏற்பட்டு விடவில்லை. அந்தச் சம்பிரதாயங்கள் காலக்கிரமத்திலே உண்டாயின. குறிப்பிட்ட சொற்றொடர்கள் சிருஷ்டிக்கப்பட்டு வந்தன. இவை யெல்லாம் நாட்டுக்கு நாடு, காலத்துக்குக் காலம் வேறுபட்டுக் காண்கின்றன. உதாரணமாக, மேடு பள்ளம் எல்லாவற்றையும் அவற்றின் பலன் உள்பட அனுபவிப்பதைக் குறிக்கப் பல்லவ சாசனங்களில் 'உடும்போடி ஆமை தவழ்த வெல்லாம்' என்று குறிப்பிட்டனர். அதையே பிற்காலத்தில் 'மேல்நோக்கிய மரமும் கீழ்நோக்கிய கிணறும்' என்று குறித்து வந்தார்கள். பிறிதொருகாலத்தில் 'புற்றும் தெற்றி

யும்' என்றனர். இதேபோல் கொங்கு நாட்டுச் சாசனங்களில் அரசனுடைய ஆட்சி ஆண்டைக் குறிப்பிடும்போது, 'திருவெழுத்திட்டுச் செல்லா நின்ற திருநல்லியாண்டு' என்று எழுதப்பட்டுள்ளது. பிற்காலத்துச் சாசனங்களில் 'ஸர்வமானியம்' என்று வருவதைப் பழைய தமிழ்ச் சாசனங்களில் முற்றாட்டு என்று குறிப்பிடுவார்கள். இவ்விதம் சாசன வழக்கில் காணும் சொற்களையும் சொற்றொடர்களையும் ஆராய்ந்தால் ரசமான பல புதிய விஷயங்கள் தெரியவரும்.

மத்திய காலத்தில் சில கோயில்களிலே ஒரு சம்பிரதாயம் வழக்கில் இருந்தது. கோயில்களுக்கு அளிக்கப்பெறும் தானங்கள் போன்றவற்றுக்கு அரசன் பெயரிலோ அந்தத் தானங்களை அளித்தவர்களின் பெயரிலோ சாசனங்கள் எழுதப்படமாட்டா. அந்தக் கோயிலில் எழுந்தருளியிருக்கும் எம்பெருமான் அளித்தனவாக அவர் பெயராலேயே சாசனங்கள் காணப்படும். 'நான்', 'எனது' என்ற எண்ணத்தையும் ஆசையையும் ஒழிக்கவேண்டும் என்று வேதாந்த நூல்கள் கூறுகின்றன. அதைக்கொண்டே இந்தச் சம்பிரதாயம் ஏற்பட்டிருக்கலாம்.

இராமநாதபுரம் ஜில்லா ஸ்ரீவில்லிபுத்தூரிலிருந்து (கி. பி. 1454) சகாப்தம் 1375 கொண்டதாகக் கிடைக்கும் பாணர் தலைவன் உறங்காவில்லிதாசனான மகாபலி வாணதிராயன் காலத்துச் சாசனம் இந்த வழக்காறுக்குச் சிறந்த உதாரணமாகும். (மடைப்பள்ளிச் செலவுக்காக) அடுக்களைப்புறமாகத் திடயனான திருவரங்க நல்லூரை அளித்த செய்தியைத் தெரிவிக்கும் அந்தச் சாசனம் (இந்தத் தொகுப்பில் 138, 139 எண்கள் கொண்டது) புதுவை விஷ்ணு சித்தர் மகளான கோதைக்கு (அதாவது ஸ்ரீவில்லிபுத்தூரில் பிறந்த வைஷ்ணவ ஆழ்வாரான பெரியாழ்வார் மகள் ஆண்டாளுக்கு) அரங்கநாதர் எழுதிய பிரணயபத்திரிகை உருவில் அமைந்திருக்கிறது. சூடிக்கொடுத்த நாச்சியார் எம்பெருமான் மீது கொண்டிருந்த ஆறுக்காதலை எடுத்துக் கூறுவதாக ஆரம்பிக்கும் அந்தச் சாசனம் நாலாயிர திவ்யப்பிரபந்தத்தில் சேர்ந்துள்ள திருப்பாவை, நாச்சியார் திருமொழி ஆகியவற்றில் காணும் அவள் வாக்காகவே உள்ள செய்யுட்களைக் கொண்டு புனையப்பட்டிருக்கிறது. முழுப் பாடல்களும் அரைப் பாடல்களும் இன்னும் அழகிய தொடர்களும் அங்கங்கே விரவிக் காணப்படுகின்றன. இவ்விதம் அவள் கொண்ட காதலால் அகமகிழ்ந்த எம்பெருமான் அரங்கநாதர் தமக்கு நடக்கும் உபசாரங்கள் அனைத்தும் அவளுக்கும் நடைபெறவேண்டுமென்று உத்தரவிட்டு அதற்காக உறங்காவில்லிதாசன் சீமையில் உள்ள திடயன் என்னும் கிராமத்தை அடுக்களைப்புறமாகக் குறிப்பிட்ட அந்த நாளிலே அருளிச் செய்தாராம். இவ்விதம் சாசனம் கூறுகிறது.

இதுபோல, கோயிலில் எழுந்தருளியிருக்கும் எம்பெருமானே அருளிச் செய்தனவாகக் காணும் சாசனங்கள் வேறு பலவும் கிடைத்துள்ளன. இந்தப் பழக்கம் இதற்கும் முன்னதாகவே இருந்துவந்ததென்று தெரிகிறது. தஞ்சாவூர் ஜில்லா திருவாரூர்க் கோயிலில் கிடைக்கும் விக்கிரம சோழனுடைய ஐந்தாம் ஆண்டுச் சாசனம் ஒன்றும் இதே மாதிரி காணப்படுகிறது. பாழையூர் உடையான் சந்திரசேகரன் ஆதிவிடங்களை குலோத்துங்கச்சோழ மஹாபலி வாணதராயனுக்கு ஒரு மாளிகை வழங்கப்பட்ட செய்தியைக் குறிக்கும் அந்தச் சாசனத்திலே அவ்வூரிலிருந்து அரசாண்ட சோழமன்னன் மதுரீதிச் சோழனுடைய வரலாறு கூறப்பட்டிருக்கிறது. (வாணதராயன் குலமுன்னோன) பாழையூர் உடையான் உபயகுலாமலன் என்பான் மதுரீதிச் சோழனுக்கு மந்திரியாக இருந்தானாம். தன் கன்றின் மீது அரசகுமாரன் தேரைச் செலுத்தி அதைக் கொன்றதால் மனம் உடைந்து முறையிட்ட பசவுக்கு நீதிவழங்க மன்னன் தன் மகன்மீதே தேரைச் செலுத்துமாறு மந்திரியான உபயகுலாமலனுக்கு உத்தரவிட்டான். அரசன் ஆணையை நிறைவேற்ற மனமில்லாமலும் அதைப்புறக்கணிக்க முடியாமலும் தவித்த மந்திரி அந்த உத்தரவைக்கேட்ட தன் காதையே குடைந்துகொண்டு இறந்தான். அதனை அறிந்த மன்னன் தானே அதை நிறைவேற்றப் புகுந்தான். அதனால் மகிழ்ந்த எம்பெருமான் அரசகுமானோடு மந்திரி உபயகுலாமலனையும் உயிர்ப்பித்தாராம். அப்போது மன்னன் மந்திரிக்குவழங்கிய மாளிகை வழக்கொழிந்து கிலமாகி வேறு கைக்கு மாறிவிட்டது. அதன்மீது இப்போது அந்த உபயகுலாமலன் வமிசத்திலவந்த பாழையூர் உடையான் வாணதராயனுக்கு அந்த மாளிகையைத் திரும்பவும் அளித்த செய்தியைத் தெரிவிப்பதே அந்தச் சாசனம். (தெ. இ. சாசனங்கள், ஐந்தாம் வால்யூம், 456 நெ.)

சித்திரித்த எழுத்து: சாசனங்கள் எளிதில் படிக்கக்கூடியனவாகவும் பார்வைக்கு அழகாகவும் இருப்பதற்காக அவற்றை வெட்டுவதற்குத் திறமைவாய்ந்த கல்தச்சர்கள் இருந்தார்கள் என்பதை முன்னரே குறிப்பிட்டிருக்கிறோம். உண்மையில் சில சமயங்களிலே அவர்கள் மிகுந்த திறமைசாலிகளாக இருந்திருக்கிறார்கள். அதனால் அவர்கள் தங்கள் கைத்திறனிலே பெருமிதம் அடைந்ததையும் காணலாம். கிழைச் சாளுக்கிய மன்னனான நரேந்திர மிருகராஜனுடைய சாசனம் ஒன்றைப் பொறித்த ஸ்பிகாரன் அக்ஷர லலிதாசாரியன் (அழகிய எழுத்துக்களின் ஆசாரியன்) என்று புகழப்படுகிறான். (தெ. இ. சாசனங்கள், முதல் வால்யூம், பக்கம் 36). ஒரிஸ்ஸா ராஜ்யத்துப் புவனேசுவரத்திலிருந்து கிடைத்த ஒரு சாசனத்திலே அவ் வெழுத்துக்கள் பொன்னில் இழைத்த மணியும் முத்தும்போல் ஒளிர்கின்றன என்று கூறப்பட்டுள்

ளது. (எபி. இந்திகா, ஆறாம் வால்யூம், பக்கம் 202). மற்றொரு சாசனம் எழுத்துக்களை வானத்தில் காணும் தாரகைகளுக்கு ஒப்பிடுகிறது. (ஹெ இரண்டாம் வால்யூம், பக்கம் 13). ஒரு லேககன் தன்னைச் சித்திரகுப்தனோடு ஒப்பிட்டுக் கூறிக்கொள்கிறான். (ஹெ எட்டாம் வால்யூம், பக்கம் 153). மற்றொருவன் தன்னுடைய எழுத்துக்களைச் சரஸ்வதி தேவியாகவே காண்கிறான். (ஹெ ஒன்பதாம் வால்யூம், பக்கம் 254). இவற்றைக் கவனிக்கும்போது சிற்பிகள் தாங்கள் எழுதுவதை மிகுந்த சிரத்தையுடனும் கலையுணர்ச்சியுடனும் செய்து முடித்தனர் என்று கொள்ளலாம். ஒரு சிற்பி காதலியின் உருவத்தைப் பல வர்ணங்களால் தீட்டும் அழகிய ஓவியனுக்கு ஒப்பாகத் தன்னைக் கூறிக்கொள்கிறான். (ஹெ பதின்மூன்றாம் வால்யூம், பக்கம் 292). இவை வெறும் புகழ்ச்சியல்ல. இதை விளக்கிக்காட்டப் பல சாசனங்கள் அழகாக எழுதப் பட்டுக் காண்கின்றன. தங்கள் எழுத்துக்களுக்கு அழகு ஊட்டச் சிற்பிகள் பல சமயங்களில் அவற்றுக்குக் கொடி முதலிய வேலைப்பாடுகளையும் சேர்த்திருக்கிறார்கள். ஒரு கன்னட சாசனத்திலே அதன் சிற்பி பின்வருமாறு புகழப்படுகிறான் : “எழுத்துக்களின் நடுவே ஒளிரக்கூடிய விதம் யானை, சிங்கம், கிளி, இன்னும் எத்தனையோ உருவங்களையும் பிணைத்து எழுதக்கூடிய லேககன் ஸோவராசியுடன் யார்தான் பைத்தியக்காரத்தனமாகப் போட்டியிட முற்படுவர்?” (எபி. கர் நாடிகா, பதினேராம் வால்யூம், சிதல்தர்க்கம் 47).

இவ்விதம் சித்திரித்து அழகாகச் செய்யப்பட்ட சாசனங்கள் தமிழ் நாட்டிலும் கிடைத்துள்ளன. காஞ்சிபுரம் கைலாசநாதர் கோயிலை எழுப்பிய பல்லவ வேந்தனை இராஜவலிம்ஹன் அதன் அடிப்படையில் தன்னைப்புகழ்ந்து உரைக்கும் சாசனத்தை வெட்டியிருக்கிறான். அந்தச் சாசனம் நான்கு வகை எழுத்துக்களில் நான்கு தடவையாக வெட்டப்பட்டிருக்கிறது. ஒவ்வொருவகையும் ஒவ்வொருவிதம் அழகு பெற்றுக் காணப்படும்.

வடக்கே ராஜிம் என்னும் இடத்தில் உள்ள ராஜீவ லோசனர் ஆலயத்துத் தூண் ஒன்றிலே ‘ஸ்ரீ பூர்ணாதியன்’ பெயர் வெட்டப் பட்டிருக்கிறது. (கன்னிங்ஹாம் எழுதிய புதைபொருள் ஆராய்ச்சி அறிக்கை, பதினேழாம் வால்யூம், பட்டம் 10.) மேலும் கீழும் கொடி போன்ற கோடுகள் செல்ல எழுத்துக்களையே மறைக்கும் கொடிச் சித்திரம்போல அது காணப்படுகிறது. அதைச் சலபமாக வாசிக்க முடியாது. அந்தச் சித்திரத்தின் பக்கத்தில் அவன் பெயரை அந்நாளில் வழங்கிய சாதாரண எழுத்தில் பொறித்த உருவத்தையும் கன்னிங்ஹாம் கொடுத்திருப்பதைக் கொண்டே அதை வாசிக்க வேண்டும்,



மேலைச் சாளுக்கிய அரசனான நான்காம் ஸோமேசுவரனுடைய குறுகோட்டுச் சாசனத்தில் (இ. ஆ., பதினேந்தாம் வால்பூம், பக்கம் 364) வரும் அதுஸ்வாரங்கள் எழுத்துக்களின் மீது நகரத்திராங்கள் போல அமைக்கப்பட்டுள்ளன. அன்றி எழுத்துக்களும் மிருகங்கள் பகவிகளின் உருவங்களில் சித்திரிக்கப்பட்டுள்ளன. ஓர் எழுத்து அன்னப் பறவையின் உருவத்தில் அமைந்துள்ளது. மற்றொன்று மயில் போலக் காணப்படுகிறது.

மத்திய இந்தியச் சாசனங்கள் சிலவற்றில் காணும் 'சிப்பி எழுத்துக்கள்' சித்திர எழுத்துக்களிலே மற்றொருவகை. அவற்றைச் சுலபமாக வாசிக்க முடியாது. (பிகார் ஓரிஸ்ஸா ரிஸர்ச் ஸொஸைட்டி, பத்திரிகை, இருபதாம் வால்பூம், 10-12 பக்கங்கள்). இத்தகைய 'சிப்பி எழுத்துக்கள்' கடல்கடந்த பிரதேசமான ஜாவாவிலும் கிடைத்துள்ளன. (எபி. இந்திகா, இருபதாம் வால்பூம்).

மொழி:—நம் நாட்டிலே வழங்கும் பல மொழிகளிலும் அந்த அந்த மொழியின் வளர்ச்சியை நன்கு அறிவதற்கு இலக்கியங்களே யன்றி, அந்த மொழியில் உள்ள சாசனங்களும் முக்கியமானவை. உண்மையில் தமிழ் இலக்கண நூல்களில் காணும் விதிகள் சிலவற்றுக்கு இலக்கியங்களிலே உதாரணம் காட்டமுடியாது. ஆனால் சாசனங்களிலே அந்த வழக்குகளைக் காண்கிறோம்.

சாசனங்களில் காணும் பிரசஸ்திகளைப் புனைந்தவர்கள் பல சமயங்களில் சிறந்த கவிஞர்களாக இருந்திருக்கிறார்கள். இதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். மேலைச் சாளுக்கிய மன்னனான இரண்டாம் புலிகேசியின் ஐஹோரீள சாசனத்தை இயற்றிய கவியான ரவிகீர்த்தி, “தன்னுடைய கவிதாசக்தியால் காளிதாசன் பாரவி ஆகியோர்களுடைய புகழை எய்திவிட்டான்” என்று அந்தச் சாசனத்தில் புகழப்பட்டிருக்கிறான். (எபி. இந்திகா, ஆறாம் வால்பூம்). பல சமயங்களில் சாசனங்களிலே சிறந்த காவியங்களிலிருந்து சுலோகங்களை அப்படியே எடுத்தாண்டிருப்பதைக் காணலாம். மேலைச் சாளுக்கிய வேந்தனான ஆறாம் விக்கிரமாதித்தியனுடைய ஹுளிச் சாசனம் (எபி. இந்திகா, பதினெட்டாம் வால்பூம்) ஒன்றிலே காளிதாசன் எழுதிய ரகுவமிசத்தின் முதல் சுலோகம் கடவுள் வணக்கமாகக் கொடுக்கப்பட்டுள்ளது. அதே போல இராஜபுதனத்திலிருந்து கிடைக்கும் சாசனம் ஒன்றிலே காளிதாசனுடைய நாடகமான அபிஜ்ஞான சாகுந்தலத்தின் மங்கல சுலோகம் கடவுள் வணக்கமாகக் கொடுக்கப்பட்டிருக்கிறது. (மே. பதினேறாம் வால்பூம், 65-பக்கம்).

இராமநாதபுரம் ஜில்லா ஸ்ரீவில்லிபுத்தூரிலிருந்து கிடைக்கும் உறங்காவில்லிதாசன் மகாபலி வாணாதிராயன் அளித்த சாசனம் ஒன்றிலே நாலாயிர திவ்வியப் பிரபந்தத்திலிருந்து பாடல்கள் அப்படியே எடுத்தாளப்பட்டுள்ளன வென்பதை நாம் மேலே கண்டோம். திருச்சிராப்பள்ளி ஜில்லா திருமழுவாடியிலிருந்து கிடைத்த செப்பேடு ஒன்றிலே அதேபோலத் தேவாரத்திலிருந்து எடுத்தாளப்பட்டுள்ள பாடல்களைக் காணலாம். (இந்தத் தொகுப்பின் 693 நெ. சாசனம்),

சாசனங்கள் பொதுவாக அந்தப் பிரதேசத்தில் வழங்கிய மொழியிலோ ஸம்ஸ்கிருதத்திலோ அல்லது இரண்டு மொழியும் கலந்தோ எழுதப்பட்டிருக்கும் என்பதை நாம் முன்னரே குறிப்பிட்டிருக்கிறோம். எனினும் பிறமொழிகளில் வழங்கிய, சாசனங்களையும் காண்கிறோம். ஸ்ரீரங்கத்திலே முதற் குலோத்துங்கசோழனுடைய ஆட்சியின் இருபத் தொன்பதாம் ஆண்டு கொண்டதாகக் கன்னட சாசனம் ஒன்று கிடைத்திருக்கிறது. அந்தச் சாசனம் மேலேச் சாளுக்கிய அரசனான ஆறாம் விக்கிரமர்தித்தியனுடைய அதிகாரிகளுள் ஒருவனான கன்னட சந்திவிக் கிரகி தண்டநாயகன் அந்தக்கோயிலிலே இரண்டுவிளக்கு எரிக்கச் செய்த ஏற்பாட்டைத் தெரிவிக்கிறது. அவனே அந்தக்கோயிலில் விஷ்வக்ஸேநர் சந்திதியைச் செங்கல் சுண்ணாம்பு கொண்டு எழுப்பியவன் என்றும் தெரிகிறது. தமிழ் நாட்டில் சோழ அரசன் ஆட்சியில் அளிக்கப்பட்ட தாயினும் சாசனம் வழங்கியவன் கன்னடதேசத்து மந்திரியானபடியால் அவனுடைய மொழியான கன்னடத்திலே அவன் சாசனம் காணப்படுகிறது. (1942-ஆம் ஆண்டு 204 நெ.) தமிழ்நாட்டில் விஜயநகர ஸாம்ராஜ்யம் வேருன்றிய பிறகு இந்தப் பழக்கம் அதிகமாகிவிட்டது. அந்நாளில் வழங்கிய சில சாசனங்கள் தெலுங்கு கன்னடமொழிகளில் உள்ளன. தஞ்சாவூர் பிரகதீசுவரர் கோயிலிலே அவ்வூரைத் தலைநகராகக் கொண்டு அரசு செலுத்திய மராட்டிய மன்னன் சரபோஜியின் சாசனங்கள் மராட்டிய மொழியில் பொறிக்கப்பட்டிருப்பதையும் நாம் மேலே (௨௮௨-௩ பக்கங்கள்) கண்டோம். இவைகளைக் கவனித்தால் அத்தகைய சாசனங்களையோ சாசனங்களில் உள்ள தானங்களையோ வழங்கியவர்கள் எந்த நாட்டைச் சேர்ந்தவர்கள் என்பதும், அந்த நாட்டு அரசுமுறையிலே அவர்கள் பெற்றிருந்த உயர்ந்த பதவியும் தெளிவாக விளங்கும்.

சில சமயங்களில் ஒரு மொழியில் உள்ள சாசனம் மற்றொரு மொழியின் எழுத்துக்களிலே பொறிக்கப்பட்டிருப்பதையும் காணலாம். காஞ்சீபுரத்துக்குப் பக்கத்தில் உள்ள திருப்பருத்திக்குன்றத்திலிருந்து கிடைக்கும் விஜயநகர வேந்தனான கிருஷ்ணதேவராயனுடைய ஆட்சிக்

காலத்துச் சாசனம் ஒன்று (இந்தத் தொகுப்பிலே 458-௧௧, கொண்டது) கன்னடமொழியில் உள்ளது. எனினும் தமிழ் எழுத்துக்களிலே பொறிக்கப்பட்டிருக்கிறது. அந்தப்புரம் ஜில்லாவில் கொத்தசிவரத்திலிருந்து முதலாம் இராஜேந்திர சோழனுடைய ஆட்சிக் காலத்துச் சாசனம் ஒன்று அவனுடைய சேனாபதியான அரையன் இராஜராஜன விக்கிரம சோழச் சோழிய வரையன் அவ்வூரிலே கோயில் மண்டபம் எழுப்பியதைக் கூறுகிறது. (தெ. இ. சாசனங்கள், ஒன்பதாம் வால்யூம், 300 நெ.). ஆயினும் தமிழ் மொழியிலே உள்ள அந்தச் சாசனம் கன்னட எழுத்துக்களில் பொறிக்கப்பட்டுள்ளது. ஸ்ரீரங்கத்திலேயே தமிழ்மொழியில் உள்ள சாசனம் ஒன்று நாகரி எழுத்தில் பொறிக்கப்பட்டிருக்கிறது. ஆந்திரப் பிரதேசத்தில் உள்ள ஏலேச்வரத்தில் காகதீய மன்னனான கணபதி தேவனுடைய சாசனம் ஒன்று தெலுங்கு மொழியில் உள்ளது. எனினும் அது தெலுங்கு எழுத்தில் இல்லாமல் கிரந்த எழுத்தில் பொறிக்கப்பட்டிருக்கிறது. அதேபோல் மங்களுருக்குப் பக்கத்தில் உள்ள கதிரி என்னும் ஊரில் மஞ்சநாதர் கோயிலில் உள்ள லோகேச்வரனுடைய விக்கிரகத்தின் பீடத்தில் துளுநாட்டை ஆண்ட வந்த ஆரூப அரசன் குந்தவர்மனுடைய சாசனம் காணப்படுகிறது. (௧௨- ஏழாம் வால்யூம், 191 நெ.). கி. பி. 968-ஆம் ஆண்டு கொண்ட அந்தச் சாசனம் கிரந்த எழுத்தில் பொறிக்கப்பட்டுள்ளது. இதேபோல் நாட்டின் இதர பாகங்களிலும் வேறு சாசனங்கள் கிடைக்கின்றன.

தமிழ் மன்னர்கள் பேரரசர்களாக ஆதிக்கியம் செலுத்தி அரசாண்ட நாளில் தமிழ்நாட்டு எல்லையையும் தாண்டி வெகுதூரத்துக்கு அப்பாலும் தமிழ்ச் சாசனங்கள் கிடைக்கின்றன. அவற்றால் அந்நாளிலே தமிழ் மக்களின் செல்வாக்கு எவ்வளவு உந்தநிலையில் இருந்ததென்பது தெரியவரும். ஒரிஸ்ஸா ராஜ்யத்தில் புவனேச்வரத்திலே கலிங்க நாட்டுக் கஜபதி வேந்தனான (நான்காம்) நரவிம்ஹன் ஆட்சிக் காலத்தின் பன்னிரண்டாம் ஆண்டு கொண்ட தமிழ்ச் சாசனம் ஒன்று கிடைத்திருக்கிறது. (வங்காளத்து ஏஷ்யாடிக் ஸொஸைட்டி பத்திரிகை, 1924. இந்தச் சாசனம் ஒரியா மொழியிலும் அதே கல்லில் கொடுக்கப்பட்டுள்ளது. சாசனத்தின் பதிப்பு மிகவும் தவறாக உள்ளது. தமிழ்ப்பகுதி சரியாக வாசிக்கவும்பெறவில்லை; மொழி பெயர்ப்பும் சரியில்லை. அதன் திருத்தமான பாடத்தை நான்கு ஆண்டுகளுக்கு முன்பு அமுதசுரபி பத்திரிகையில் நான் வெளியிட்டிருக்கிறேன்).

கி. பி. பத்தாம் நூற்றாண்டு எழுத்துக்களில் பொறிக்கப்பட்ட தமிழ்ச் சாசனம் ஒன்று கடல்கடந்த பிரதேசமான சயாம் (தாய்லந்து) நாட்டிலும் கிடைத்துள்ளது. (ராயல் ஏஷ்யாடிக் ஸொஸைட்டி பத்திரிகை, 1913; எபி. இத்திகா, பதினெட்டாம் வால்யூம்).

முடிவுரை: இதுகாறும் கூறியவாற்றால், சாசனங்கள்,—அவை அரசாங்கத்தார் அளித்தனவாயினும் சரி, தனிமனிதர் விவகாரங்களை உணர்ப்பனவாயினும் சரி, இன்னும் அவை எந்த விஷயத்தைத் தெரிவிப்பனவாயினும் சரி—நம் நாட்டுச் சரித்திரத்தைப் பல துறைகளிலும் ஆராய்ந்து நிர்ணயிப்பதற்கு எவ்வளவு முக்கியமானவை என்பது தெரியவரும். எனினும் பல சாசனங்கள் சிதைந்தும் மறைந்தும் போயின. வேண்டுமென்றே அழிந்தவை பல. தெரிந்தும் தெரியாமலும் அழிந்தவை வேறு. நல்லெண்ணத்தால் மறைந்தனவும் உண்டு. ஐம்பது ஆண்டுகளுக்குமுன் தஞ்சாவூர் ஜில்லா திருவிடைமருதூரில் உள்ள மகாலிங்க சுவாமியின் கோயில் ஜீர்ணோத்தாரணம் செய்து புதுப்பிக்கப்பட்டது. அப்போது அதன் மதில்களிலும் மண்டபங்களிலும் தூண்களிலும் பொறிக்கப்பட்டிருந்த சாசனங்கள் எல்லாம் அழிந்து போய் விட்டன. கர்ப்பகிரகத்தின் சுவர்களில் பொறிக்கப்பட்டிருந்தவை மட்டும் பிரதிசெய்யப்பெற்றன. பின்னால் அந்தச்சாசனங்களும் அழிந்து போயின. இப்போது அந்தக் கோயிலில் பழையசாசனம் ஏதும் இல்லை. புண்ணியம் சம்பாதிக்கத் தரும் சிந்தனையுடன் செய்த திருப்பணிதான். எனினும் சாசனங்கள் அழிந்துவிட்டன. வடக்கே, சாசனம்பொறிக்கப்பட்ட ஸ்தம்பம் ஒன்றைத் தெய்வபக்தியுடைய பெரியார் ஒருவர் ஏரண் என்னும் இடத்தில் சிவலிங்கமாக மாற்றிவிட்டார். சாசனங்களின் அருமை தெரியாமல் அவற்றை அழித்து விடுவதற்கு இவை சிறந்த உதாரணங்களாகும் அன்றோ?

இன்னும் பண்டாரிபுரத்தில் 'சோராஸி சிலா' என்ற கல்லில் பொறிக்கப்பட்டிருந்த சாசனம் ஒன்று இப்போது தேய்ந்துபோய் உருத் தெரியாமல் ஆகிவிட்டது. அவ்விடம் செல்லும் யாத்திரிகர்களில் ஒவ்வொருவரும் அதிலே தங்கள் முதுகைத் தேய்த்துக்கொள்வதாலேயே அது அவ்விதம் ஆயிற்று. அவ்விதம் தேய்த்துக்கொள்வதால், எண்பத்து நான்கு லக்ஷம் மறுபிறப்பினின்றும் தாங்கள் விடுபடுவோம் என்ற நம்பிக்கையாலேயே அவர்கள் அவ்விதம் செய்து வருகிறார்கள். அதில் உள்ள சாசனத்தை அறிந்தோ, அதற்கு ஊறு விளைவிக்க வேண்டுமென்றோ அவர்கள் அவ்விதம் செய்யவில்லை. எனினும் அது பெருத்த நஷ்டத்தை உண்டாக்கிவிட்டது. இத்தகைய தவறுகள் மேலும் நேராமல் சாசனங்களைப் பாதுகாக்க வேண்டியது மிகவும் அவசியமானதாகும்.

## NOTE ON TRANSLITERATION, ETC.

The system of transliteration adopted by the Epigraphy Department has been followed in this publication. The Sanskrit vowel 'ṛi' is not distinguished. The Tamil consonant 'na' (ன) is distinguished very rarely, as the absence of it will not handicap a Tamil reader, while the use of it will be unintelligible to a non-Tamilian.

The number, like (No. 109 of 1904), at the beginning of the introduction to a record represents the number and year of the Epigraphical collection.

The equivalent of the dates of the inscriptions having astronomical details, in the Christian era have been calculated with the help of the *Indian Ephemeris* by L. D. Swamikannu Pillai.

The number, like D-3657, at the right-hand top of each record represents the accession number of the original in the Government Oriental Manuscripts Library, Madras, used for this edition.

---

## குறிப்பு

சாசனங்களின் பாடம் மூலப்பிரதிகளில் கண்டவாறே பின்கண்ட குறியீடுகளுடன் பதிப்பிக்கப் பெற்றுள்ளன.

( ) இவ்விரு குறிகளுக்குள் அகப்பட்ட எழுத்துக்கள் தவறாகவோ அதிகப்படியாகவோ காணப்பெறுகின்றன. அவற்றை நீக்கி விட்டு வாசிக்க வேண்டும்.

[ ] இவ்விதம் இருதலைப் பகரங்களுக்குள் காணும் எழுத்துக்கள் அவ்விடம் இருக்கவேண்டியவை. மூலத்தில் அவை சிதைந்தோ அல்லது சரியாக எழுதப்பெறாமலோ உள்ளன. ஒன்றுக்கு மேற்பட்ட பிரதிகள் உள்ள சாசனங்களில் மூலப்பிரதியில் சிதைந்துபோய் வேறு பிரதியில் காணப்பெறும் பகுதியையும் இது குறிக்கும்.

[ \* ] இவ்விதம் இருதலைப் பகரங்களுக்குள் உடுக்குறியிட்டுக் காட்டப்பெறும் எழுத்துக்கள் இவ்விடத்தில் இருக்கவேண்டியவை; ஆனால் மூலப்பிரதியில் காணவில்லை. சாசனங்களின் வாசகத்தைச் சரியாக உணர்ந்து கொள்வதற்காகப் பதிப்பாசிரியரால் சேர்க்கப்பட்டுள்ளன.

..... விடுபட்டுப்போன பகுதியைக் குறிப்பது. கல் சிதிலமாகி வாசிக்க முடியாமல் விடப்பட்ட பகுதியை மட்டுமல்லாமல் பிரதிசெய்யப்பெற்றும் ஏடு சிதைந்து போனதால் இப்போது பூர்த்தி செய்யமுடியாமல் உள்ள பகுதியையும் குறிக்கும். சாசனங்களைப் பதிப்பிக்கும் போது விடுபட்டுப்போன பகுதியில் ஓர் எழுத்துக்கு ஒரு புள்ளி என்று இடுவது சம்பிரதாயம். அதை இவ்விடம் அனுசரிக்கவில்லை. ஆகவே விடுபட்டுப்போனது ஓர் எழுத்தாகவும் இருக்கலாம்; பல வரிகளாகவும் இருக்கலாம்.

[.....] மூலத்திலே இடைவெளி எதுவும் இல்லாமல் தொடர்ச்சியாக எழுதப்பட்டிருப்பினும், அவ்விடத்திலே ஒரு பகுதி விடுபட்டுப் போயிருப்பதாகப் பதிப்பாசிரியர் கருதுவது இவ்விதம் குறிக்கப் பெற்றுள்ளது.

ஒவ்வொரு சாசனத்தின் தலைப்பிலும் வலது புறத்தில் D. 3657 என்பது போலக் கொடுக்கப்பட்டுள்ள எண், அந்தச் சாசனத்திற்கு மூலமாக ஒலைச்சுவடி நிலயத்திலே உள்ள பிரதியின் குறிப்பு எண் ஆகும்.

கீழ்க்குறிப்புகளில் சாசன இலாகாவின்ர் வேறு விதமாக வாசித்திருப்பதாகக் காட்டுவது அவர்களுடைய ஆண்டு அறிக்கையைக் கொண்டேயாகும்.

# கோயிற் சாசனங்கள்

(மூன்றாம் பாகம்—2-ம் பகுதி.)

—:—

கண்டியூர்

Kaṇḍiyūr

இவ்வூர் தஞ்சாவூர் ஜில்லாவில் தஞ்சாவூர்த் தாலுகாவில் உள்ளது. இவ் விடத்திலிருந்து கிடைத்த சாசனம் ஒன்று இரண்டாம் பாகத்தில் வெளியிடப் பட்டுள்ளது.

The village is in the Tañjāvūr taluk of the Tañjāvūr district and one inscription copied from this place has been published in Vol. II.

சாசனம் — 1265]

[D. 2744-சமஉ

பிரம்மசிரக் கண்டிச்வரர் என்னும் வீரட்டானேச்வரர் கோவிலின் கர்ப்ப கிருகத்தில் உள்ளது.

On the walls of the central shrine in the temple of Viraṭṭanēśvara, otherwise known as Brahmaśīraḥ-khaṇḍīśvara in the village. Record dated in the 10th year in the reign of the Chōḷa king Parakesarivarman (copied as Kō-Pa dēvar by mistake) registering the gift of ninety-six sheep by a resident of Pāmbuṇi-kūrṇam for burning a perpetual lamp in front of god Mahādēva.

This is one of the records in which portions have been copied in the same script as found on the stone instead of being transcribed.

ஷ்ஷி ஸ்ரீ [11\*] கோ ப தேவர்க்கு யாண்டு ம-ஆவது கருபதேத மஹாசெவ[ர்\*]க்கு அநுபூதிதவ.....நிசதி உழக்கு தெம லூல இரவும் பலு..... ம டாங்கலக்கு பாம்புணி கூற் றதெ பாம்பணி சவனப்பாடியாள திருவடி நாகா டு கு கக ஆடு தொண்டாபருனா ரு பம்மாஹெஸ்டி உ. உ

[இந்தச் சாசனத்தின் சில பகுதிகள் பெயர்த்து எழுதப்படாமல் கல்லில் கண்ட உருவத்திலேயே பிரதி செய்யப்பட்டுள்ளன. இதன் திருத்தமான பாடம் பின்வருமாறு இருத்தல் கூடும்.]

ஹீஷி ஸ்ரீ [11\*] கோப் பரகேசரி வர்மர்க்கு யாண்டு யி-ஆவது: திருக்கண்டியூர் மஹாசேவர்க்கு அந்ராஜித்தவல் நிசதி உழுக்கு நெய்யால் இரவும் பகலும் நொந்தா விளக்கு எரிக்கப் பாம்புணிக் கூற்றத்துப் பாம்புணி சங்கரப் பாடியான திருவடி..... வைத்த ஆடு தொண்ணூற்று. இது பன்மாஹேஸ்வர ரசெஷ [11\*]

சாசனம் — 1266]

[D. 2744-செரு

அதே இடத்தில் காண்பது.

At the same place. Record dated in the 11th year in the reign of the Chōla king Rajakesarivarman. Seems to be incomplete and mentions Ārkkadu-kūram, Brahmadēyam Tirukkaṇḍiyūr, Bālasiriyān Havyadēvan (?) and Nakkanpāḍi. Probably it registers the gift of a lamp.

ஹீஷி ஸ்ரீ [1\*] கொ ராஜ கேஸரி உகநதுக்கு<sup>1</sup> யாண்டு யிக-வது ஆர்[க்\*]காட்டுக்\*] கூட்டத்துக்கு<sup>2</sup> ஸ்ரீஷேய னிருக் கண்டியூர் பாலாசிரியன் ஹவ்ய (ஹவ்ய ?)சேவன் நக்கன்பாடி [பரேத புலிநகவுரவாயெ தெயாக்கதொர். உ]<sup>3</sup>

[சாசனம் பூர்த்தியாக இல்லை. தானப் பகுதி பிரதி செய்யப்பெற்றதாகக் காணவில்லை. சில எழுத்துக்கள் கல்லில் கண்ட வடிவத்திலே எழுதப் பெற்றுள்ளன.]

ஸ்ரீரங்கம்

Srīraṅgam

இது திருச்சிராப்பள்ளி ஜில்லாவில் உள்ள பிரபல வைஷ்ணவ ஸ்தலம். இவ்விடத்திலிருந்து கிடைத்த சாசனங்கள் இரண்டாம் பாகத்தில் வெளியாகியுள்ளன. பின் வருபவை மக்கென்வியின் சாசனப் பட்டியலில் காணப் பெறவில்லை. உத்தம நம்பி கூடஸ்தர்களுடைய வமிச பரம்பரையைத் தெரிவிக்கும் வரலாற்றில் காணப்படுவது.

1. கொ ராஜகேசரி வர்மர்க்கு என்று வாசிக்க.
2. 'ஆர்க்காட்டுக் கூற்றத்து' என வாசிக்க.
3. இந்தப் பகுதி விளங்கவில்லை.



The place, a great Vaishnavite centre, is in the Tiruchirappalli district and inscriptions copied from this place have been published in Vol. II. The following records are not found included in the *List of Inscriptions copied from the Southern Districts* prepared by the assistants of Col. Mackenzie, but are included in the manuscript giving the history of the family of Uttama-Nambi.

சாசனம்—1267]

[D. 3776-க

[ரங்கநாதர் கோயிலின் இரண்டாம் பிராகாரத்துத் தென்புற மதிலில் காணப்படுவது.]

[On the south wall of the second prakāra in the Raṅganātha temple.]

This record consists of two Sanskrit verses. The first of them, registered as No. 58 of 1939 in the Madras Epigraphical collection and dated in Śaka 1350 (given in chronogram), Kīlaka, ba. dvādaśi, Wednesday and Uttiram, corresponding to A.D. 1423, October 6, the month being Tula, registers the gift of a gold *kalaśa* to god Periya-perumāḷ, by the brother, whose name is not given, of Chakra-rāja, referred to also as Chakrarāya.

The donor is evidently Uttama-Nambi. The manuscript gives also the genealogy of the family of Chakrarāja, therein stated as a branch of the Uttama-Nambi family.

It is also stated therein that this family was descended from Periyāḷvār, the famous Vaishṇava saint and father of Āṇḍāl, otherwise known as S'ūḍikkoḍutta-Nāchchiyār.

சூகாநொகெ ஸகநரவதெ

ஹாயநெ கீரகொஜெ

கரஷெவகெஷ ஹரிஸுயலிநெ

பீதியுகொதரஸ்கெஷ |

பாஜாஸஹஷீர வெரிய வெருஜாஸ

ரஹினெஹெகசுஹஷ

ஹாதா யஸூ பூயிதயஸஸா

(ரஹ) [ஹ] து ஸ (கக) [க] ராஜ [ஃ] || 1

1. இதன் தமிழ் மொழிபெயர்ப்பு :

ஆத்மாலோகம் என்ற கணக்கையுடைய சகாப்தம் (அதாவது 1350) சிலை வருஷம், [துலா மாதம்\*] கிருஷ்ணபக்ஷத்துத் [துவாததி], புதன்கிழமை,

The next verse, though written in continuation of the above, seems to belong to the next record which is registered as No. 60 of 1939 by the Epigraphical Department. It registers the consecration of the Garuḍa image by Chakrarāja on Sunday, Rēvati in the month of Jyēṣṭha in the cyclic year Manmatha.

உவெல உதயவெஷ்ட ஜெஷ்டே

ரவிவார ரெவதி தாரெ ।

ஸ்ரீ உக்ரராஜ விஹநா ஸ்ரீஉ[ரஃ]ந

மரஃ: ஸ்ரீதிஷ்டொஹுதெதே । 1

ஸ்ரீ உதே நம்பி

சாசனம் — 1268]

[D.3776-உ

[சுவது தலைமுறையில் ராஜாவினால் கொடுக்கப்பெற்ற விருதுக்கு விவரம்; சிலாவிசுதம்.]

(No. 60 of 1939). At the same place. Record in Sanskrit verse stating that Uttama-Nambi was the recipient of several honours such as a pearl-umbrella, a big *kāhaḷa*, two lamps, a *bhadrāsana* and similar royal emblems from the Vijayanagara king Devaraya.

*Kāhaḷa* figures as one of the objects presented to temples in several inscriptions and a reference to the context shows that it should be a musical instrument. But what exactly it was is not clear. In the manuscript detailing the history of the family, the

உத்தர நகரத்திரம் கொண்ட நாளில் பெரிய பெருமானான ரங்கநாதருக்கு உத்தமனான சக்கர ராஜனுடைய சகோதரன் பக்தியுடன் ஒரு பொன் கலசத்தை அளித்தான்.

காணிக்கை அளித்தவன் உத்தம நம்பியே போலும். இந்தச் சாசனம் கொடுக்கப்பட்டுள்ள வரலாற்றின்படி சக்கரராஜர் என்பாரும் உத்தம நம்பி வமிசத்தின் ஒரு கிளையினர் ஆவர். அவர்கள் வைஷ்ணவ ஆழ்வாரான பெரியாழ்வார் வழி வந்தவர்களாம்.

1. இதன் தமிழ் மொழி பெயர்ப்பு:

மனமத வருஷம், ஜ்யேஷ்ட மாதம், ஞாயிற்றுக்கிழமை பெற்ற ரேவதி நான் சக்கரராஜர் என்பார் ஸ்ரீகருணைப் பிரதிஷ்டை செய்தார்.

contents of this record are given in Tamil making the donee as the fourth in descent in the line. Therein the name of the instrument is given as *karnā*, which we know from a reference to it in the *Rāmanāṭaka*, as a blowing instrument like the *kombu*.

ஓதூ(ஊ)[த]வசுவரயுகாஹஸதீவ யும  
 லஹாஸந ப்ரஹ வாதீ-வனாஹநாநி  
 ஸ்ரீ[ஹ]வராஜ தரவாஹவராடியாலீக  
 ஸ்ரீஹம-ஹாஸதீ வதிரா-தத ந-ஸிநாநா || 1 (சு)

ஹநதீஹ ஓதூதவசு ஸிஜயகரஹ  
 காஹஸதீ ஹவாஹநா  
 ஹவஹஹ ஹ ஹஹகரஹபகஸு  
 ஸஸய ஸுமாவதஹஸ  
 ஹநாநதீநதீநாநி ராஜாஹகாஹ ஹமயோ  
 ஹ-ஹவராஜயி ராஜாஹ  
 ஹநதீ[ஹ] ஸ்ரீஹம-ஹ ஹாஸதீ ப்ரஹநயிதவா  
 நுதீஹயிநாநா || 2 (உ)

# 1. இதன் மொழிபெயர்ப்பு :

‘ஸ்ரீமார்க்கதாஸ்யபதி எனப்பெறும் உத்தமநம்பி என்பார் அரசர்களில் சிறந்த ஸ்ரீதேவராஜனிடமிருந்து முத்துக்குடை, பெரிய காஹள வாத்தியம், இரு விளக்குகள் (தீவட்டிகள்?), பத்ராசனம் போன்ற ராஜ சின்னங்களைப் பெற்றார்.’

2. இந்தச் சுலோகமும் மேலே கண்ட விஷயத்தையே சற்று விரிவாகத் தெரிவிக்கிறது. உத்தம நம்பிக்கு அரசன் அளித்த காஹளம் என்பதன் பெயர் வேறு பல சாசனங்களிலும் காணப்பெறுகிறது. அது ஓர் இசைக் கருவி என்றே தெரிகிறது. இந்தப் பரம்பரை வரலாற்றைக் கூறும் தமிழ்ப் பகுதியிலே இவ் விஷயம் பின்வருமாறு கொடுக்கப்பட்டிருக்கிறது:

“சுவது அவர் குமாறர் திருமலனாத அய்யன் உத்தம நம்பி ஸ்ரீ ரெங்க ஸ்ரீகாரியங்களே நெறுவகிக்கையில் மகாருசவண தெவருச மகாருசவுனலெ முத்துகொடை கர்ணவாத்தியும் தங்க ஆசனம் யிதுகளே யெல்லாம் குடுத்தார்.”

இதிலிருந்து காஹளம் என்பதே கர்ணவாத்தியம் என்று பிற்காலத்தில் வழங்கப்பட்டதாகும் என்பது விளங்கும். ‘கர்ணவொடு சிறந்த கொம்புகள்... முழங்கிவர’ என்று வரும் இராம நாடகப் பகுதியிலிருந்து அது கொம்பு போன்ற ஓர் ஊதுகுழல் என்பதும் தெளிவாகும்.

அயி-ஆவது தலைமுறையில் பண்ணின கைங்கரியத்துக்கு விவரம்.

[Details of the benefactions made by the eightieth descendant in the line.]

It is not known where exactly this record is found engraved in the temple. It is made up of two Sanskrit verses. The first one registers that gold ornaments, utensils, several kinds of maṇḍapas buildings, gōpuras, large gardens, vehicles; endowments for special festivals and broad beautiful streets were furnished to god Raṅga-nātha out of devotion. The name of the donor is given only in the second verse which states that Uttama-Nambi, otherwise known as Krishṇarāya kavi, (the descendant of Uttama-Nambi) was protecting Raṅgarāja-nagarī, i.e., Srīraṅgam just like the city of Sakēta (Ayōdhya) was protected by the descendant of Raghu (i. e., Rama) and the city of Mathurā by the descendant of Yadu (i. e., Kṛishṇa).

ஹுஷாஃ காணநநிஜி-தாஃ வரிகராஃ

நாநாவியா ஜணவாஃ

பூரஸாஷா [சு\*]விமொபு-ராணி

உஹிதொஜிதாநாநி யாநாநி அ ।

பு-தஜெபூ தஸ (நி) வெஹொநி ஸுஹமாஃ

வீ[டு]யஜ(ன்)[ர] விஸாநூநரா

யெநாகாரிஷத பு(தி)[யி]தஜநஸா

ஸ்ரீராமிண[ஃ\*] ஸ்ரீதயெ ||

(க)

### 1. இதன் தமிழ் மொழிபெயர்ப்பு :

பொன்னால் ஆன ஆபரணங்கள், பாத்திரங்கள், பலவகையான மண்டபங்கள், மாளிகைகள், கோபுரங்கள், பெரிய நந்தவனங்கள், வாகனங்கள், புதிய உற்சவச் சிறப்புகள், அழகிய வீதிகள் ஆகியவற்றை ரங்கநாதரிடத்தில் பக்தி பூண்ட மனத்தினாலாகச் செய்தான்.

அவ்விதம் செய்தவன் யார் என்பது இதில் குறிக்கப்பெறவில்லை. எனினும் அடுத்த சுலோகத்திலிருந்து அவன் கிருஷ்ணராய கவி என்ற பெயர் பூண்ட உத்தமநம்பி யாவான் என்பது விளங்கும்.

விரகேத நாட நமரீவ ரவயுஅஹைந

சாநெஜாடியெந உயுரெவ யடிஅஹைந ।

ஸ்ரீ கஜநாய கவிநொதே நன்விநாஜா

ஸ்ரீராமராஜநமரீ வரிரசுத்தாவிசு ॥ 1 (உ)

சிதம்பரம்

Chidambaram

இது தென் ஆர்க்காடு ஜில்லாவில் உள்ளது; தாலுகாவின் தலைநகர். இவ் விடத்திலிருந்து பிரதி செய்யப்பட்ட கல்வெட்டுக்கள் முதல் பாகத்திலும், மூன்றாம் பாகத்தின் முதற் பகுதியிலும் வெளியாகியுள்ளன. இவ்விடம் கொடுக்கப்பட்டுள்ள சாசனங்கள் மக்கென்வியின் சாசனப் பட்டியலில் காணப்பெறுதவை.

This is a taluk head-quarter station in the South Arcot district. Inscriptions copied from this place have been published in Vol. I and in part I of Vol. III above. The inscriptions now given are not included in the *List of Inscriptions copied from the Southern Districts* prepared by the assistants of Col. Mackenzie.

சாசனம் — 1270]

[D. 3353-12

நடராஜர் கோவிலின் மூன்றாம் மதிலில் காண்பது.

On the third [prakāra] wall in the Natarāja temple. Two Sanskrit verses written in the Grantha script, eulogising the victories of the Chōḷa king Kulottunga I. The first verse says:

Having subdued the five Pāṇḍyas by an army which discharged numerous arrows, having burnt like straw the fort of Kōṭṭara, just as (Arjuna) the son of Pāṇḍu (had burnt) the Khāṇḍava (forest), (and) having crushed that extremely dense army of the Kēraḷas,— that glorious Kulōttunga Chōḷa who resembles a lion in majesty (and) Śakra (Indra) in valour, placed on the shore of the ocean a pillar (commemorative of his) conquest of the three worlds.

வசுதி ஸ்ரீ [!\*

வாணஜாதெனெநஜிதா ப்ரஹ்மராமரஹா

வன வனா [நந] ஸ்ரீ

1. 'வரிரசுத்தாவிசு' என்று வாசிக்க.

இதன் தமிழ் மொழிபெயர்ப்பு:

'அயோத்தியை ரகுவமிசத்தில் பிறந்த ராமனும், மதுரா நகரத்தை யது வமிசத்தில் பிறந்த கிருஷ்ணனும் பாதுகாத்ததுபோல ஸ்ரீரங்கராஜ நகரத்தை உத்தம நம்பி என்னும் பெயர் கொண்ட (வமிசத்தில் பிறந்த) கிருஷ்ணராய கவி பாதுகாத்து வருகிறான்,'

உ-ஹீவா கொ[ஹீ\*]டார உ-ஹீநாநு

(மரஉஃ) துணிலவ(ர)ல யயா

வாணவம் வாணு ஸூநு: |

விஹீவா தக் கொடாநாநம் ஸூநுதி

ஸ[ஹீ\*]ஹம்<sup>1</sup> ஸ்ரீ குஹோதூமமொஹம்

ஸகூ பூதாவ[ஃ\*] ச்ரீஹுவந விஜய

ஸஹம்ஹொயி [தீரெஹீ\*]:

(க)

The second verse says:

Having subdued the five Pāṇḍyas by masses of powerful armies that glorious Kulōttuṅga Chōḷa who has scattered (his) enemies (and) whose fame is spontaneously sung on the further shore of the ocean by the young women of the Persians (Pārsi), duly placed on the holy peak of the Sahyādri (mountain) a pillar (which commemorates his) conquest of the three worlds (and) before which the crowd of kings is trembling.

[வாணேஜ ஸஹீநாநு ஸூமெ ச்ரீஹுவந

விஜய ஸஹம்ஹொயி\*] வாரெ

ஸஹ[ஃ\*]ஹொ வாவநாநாநு

யாவதிவி ஹீ-யதெ<sup>3</sup> யஸூ கீதி-ஃ: |

[ஸ\*] ஸ்ரீநாநு சுஹ ஸஹ

புஸூஹம்<sup>4</sup> வஹ வாணநாநு விஜிதா<sup>5</sup>

1. 'ஸூநுதிஸஹம்' என்று வாசிக்க.

2. இதன் தமிழ் மொழி பெயர்ப்பு வருமாறு :

கம்பீரத்தில் சிங்கத்தையும், பராக்ரமத்தில் இந்திரனையும் நிகர்க்கும் ஸ்ரீகுலோத்துங்க சோழன் எண்ணற்ற அம்புகளை எய்யும் சேனையால் பாண்டியர் ஐவரை வென்றும், பாண்டவ புத்திரான அர்ச்சுனன் காண்டவ வனத்தை எரித்ததுபோலக் கோட்டாறுக்(கோட்டையைத்) துரும்பென எரித்தும், செறிந்த கேரளப் படையை நசுக்கியும், மூவுலகத்தையும் வென்றதற்கு அறிகுறியாகக் கடற்கரையில் ஜயஸ்தம்பம் நிறுவினான்.

3. 'ஸஹம்ஹொவாவநாநாநு'யாவதிவி-யதெ' என வாசிக்க.

4. 'சுஹஸூ புஸூஹம்<sup>4</sup> வஹ வாணநாநு விஜிதா' என்று வாசிக்க.

5. 'விஜிதா' என்று வாசிக்கவேண்டும்.

சுதூஹு<sup>1</sup>சுதூவாஹு அசூ<sup>2</sup>

[ஹ\*]னியிக(யி)[உ] கரொ

ஹீசூஹொதூஹ (ஹொ: ||) [ஹொஹ: ||]<sup>3</sup>

சாசனம் — 1271, 1272, 1273]<sup>4</sup>

[D. 3353-13, 17, 10

அதே இடத்தில் காண்பது.

மூலத்திலே இந்தச் சாசனம் மூன்று பகுதிகளாகப் பிரிக்கப்பெற்று மூன்றும் பின்னுமாகப் பிறழ்ந்து எழுதப்பட்டுள்ளது. நரலோகவீரன் என்னும் சோழ சேனாபதி செய்த திருப்பணியின் புகழை விதந்துகூறும் இச் சாசனம் மக்கென்வியின் உதவியாளர். தயாரித்த சாசனப் பட்டியலில் காணப் பெறவில்லை.

இந்தச் சாசனம் தேன்னிந்திய சாசனங்கள், நான்காம் வால்யூம், 225 நெ. ஆக வெளியிடப்பட்டுள்ளது. அது முப்பத்தொரு வடமொழிச் சுலோகங்களையும், வெண்பாவாக அமைந்த முப்பத்தாறு தமிழ்ச் செய்யுட்களையும் கொண்டு இரு பகுதிகளாக அமைந்துள்ளது. மக்கென்வியின் உதவியாளர் தமிழ்ப் பகுதியைப் பிரதி செய்யவில்லை. வடமொழிச் சுலோகத்தில் காணும் செய்தியையே தமிழ்ச் செய்யுள் எடுத்துரைப்பதாகக் காண்கிறது.

At the same place. This record is not found included in the *List of Inscriptions from the Southern Districts*. This has been copied as three fragments and registered as three different inscriptions. It details the various benefactions of the Chōla general Naralōkavīra.

This record which contains thirty-one verses in Sanskrit and thirty-six of Tamil in the *veṇṇbā* metre has been published as No.225 in the **South Indian Inscriptions**(Texts), Vol. IV. Col. Mackenzie's assistants have copied only the Sanskrit portion. The Tamil portion in

1. சுதூஹு<sup>1</sup> என வாசிக்க.

2. இதன் தமிழ் மொழி பெயர்ப்பு:

குலோத்துங்க சோழன் பலம் பொருந்திய தன் படைத்திரளால் பாண்டியர் ஐவரை அடிப்படுத்தி, எதிரிகளைச் சிதற அடித்தான். அவன் புகழ் கடலின் எதிர்க்கரையில் உள்ள பாரதீக நாட்டு யுவதிகளாலும் பாடப் பெறுகிறது. மூவலகையும் தான் கொண்ட வெற்றியின் சின்னமாக அவன் ஸஹயாத்ரி (மேற்குத் தொடர்ச்சி) மலையில் ஒரு ஜயஸ்தம்பம் நிறுவினான். அதன் முன்னர் அரசர் குழாம் நடுங்குகின்றது.

many places repeats and confirms the statements found in the Sanskrit portion.

[13]

The first verse forms a sort of an introduction. It states that to describe the benefactions of Mānavatāra, another name of Naralōka-vīra, to Sabhāpati performing the (cosmic) dance for the welfare of the three worlds and whose form occupies both the earth and heaven, even hundred faces would be insufficient and requests the reader to hear them leisurely. It is probably implied from this that one hundred verses have been composed. It is possible to read the word *vaktṛaiḥ* as *patṛaiḥ* and take it to mean that these verses were written on one hundred copper-plates.

ஸஷி ஸ்ரீ [||\*]

வகெடு தெந ஸஹாவதெஸீக்ரஹுவநகெஷராய நரதூம் வரம்  
கூவரோணஸூ தகெசுதாநஜநஸா ஜநாவதாரெண யக் |  
தததஸூரணு ஸாவயாநஜயுநா யகெஸூரகூவாதுஸூரெதெ:  
வகெடு தெ-ஹஹுதபூரணி ஸரஸம் ஐராவா வ்யயிவெஜா  
வ-யெயா: (க)

### 1. இதன் தமிழ் மொழிபெயர்ப்பு :

திரிபுவனங்களின் கேசுமத்துக்காக நடனம் புரிபவரும், ஆகாயம் பூமி ஆகிய இரண்டுக்கும் ஒன்றான தேகத்தை உடையவருமான சபாபதிக்கு மாநாவ தாரன் என்பான் ஏகாக்கிர சித்தத்துடன் செய்த (திருப்பணி)களை எடுத்துக் கூற நூறு முகங்கள் போதா. அவற்றைச் சாவதானமாக என்னிடம் கேள்.

மாநாவதாரன் என்பது நாலோக வீரனுடைய விருதுகளில் ஒன்றாகும். அவன் புகழைப் பிரபந்த வகையாகப் பாடுவதற்கு இச் செய்யுள் ஒரு முன்னுரையாக அமைந்ததுபோலும். நூறு செய்யுட்கள் இயற்றப்பெற்றன வாகக் கொள்ளலாம். 'வக்த்ரை' என்பதைப் 'பத்ரை' என்றும் வாசிக்க முடியும். அவன் புகழை நூறு செப்பேடுகளில் எழுதச் செய்தான் என்று கொள்ளவும் கூடும். தமிழ்ப் பகுதியிலே பின் வரும் பாடல் ஒன்றும் காணப் படுகிறது.

முத்திறத்தா ரீசன் முதற்றிறத்தைப் பாடியவாறு  
ஒத்தமைத்த செப்பேட்டி னுள்ளெழுதி—இத்தலத்தின்  
எல்லைக் கிரிவா யிசையெழுதி னுன்கூத்தன்  
தில்லைச்சிற் றம்பலத்தே சென்று.



The second verse states that he set up innumerable street-lights (*pathidipa*) to dispel the darkness and make the place in effulgent eternal sunshine.

நயித நிரலலாந ஜெஜாதிரெஜா வீயிழீவா -  
 நிஹ தஜலி விருவெத் தெரலாவெவ்யரஜஸூ |  
 தவநதுஹிநஹாஸொ ரத்ர பவ-சா 'அ-நா-சா  
 லிகரநிகரநாபேவ ஸாத-ஃ ப்ரகாஸஃ ||<sup>1</sup> (உ)

In this verse we are told that he made with his heart elated with bliss from the devotion, arrangements for watering the streets on the occasions of conducting festivals to Siva, the destroyer of Love, with water from the holy *tirthas*.

ஸ...நூணிர கூராத ருஸலீயிகாயா ஜெஷஜா -  
 லெகம் கத-ஃ உஜிதஹவநஷுக்  
 ஸவெஷுஸாராஸஃ |  
 வநதா ஸூதக்ஸஜயநிஹிதெஃ வ்ரரிதாஃ வுணஜிதாயெ-  
 ஸக்ஷிதாநடியதி ஹஜயெஸுநுஜதா  
 ஹக்ஷிபரெணை-ஃ ||<sup>1</sup> (ரு)

### 1. இதன் தமிழாக்கம்:

இருளைப்போக்குவதில் சூரியனுடைய காந்தியை ஒத்து, தினகர (சூரிய)னைப்போலப் பிரகாசம் பொருந்தி இடைவிடாமல் எரியும் எண்ணற்ற தெரு விளக்குகளை அவன் நிறுவினான்.

இந்தச் செய்தியைப் பின்வரும் தமிழ்ப் பாடலும் எடுத்துக் கூறுகிறது.

வீதிசூழ் நல்விளக்கும் வீற்றிருக்க மண்டபமும்  
 மாதுசூழ் பாக மகிழ்ந்தார்க்குப்—போதுசூழ்  
 தில்லைக்கே செய்தான் திசைக்களிறு போய்நிற்கும்  
 எல்லைக்கே செல்கலிங்க ரோறு.

### 2. இந்தச் சுலோகத்தைப் பின்வருமாறு தமிழில் கொள்ளலாம்.

பக்தியின் ஆனந்தத்தால் நிறைந்த மனத்தினனாக அவன், எல்லா உலகங் களும் சந்தோஷப்படும் சிவபெருமானுடைய உற்சவங்கள் நடக்கும் அந்த அந்தச் சமயங்களில் வீதிகளிலே புண்ணிய தீர்த்தங்களைத் தெளித்துவா ஏற் பாடு செய்தான்.

The fourth verse states that he, out of devotion, planted fifty thousand areca-palms (which grew) besprinkled with the Ganges water scattered by the matted hair on the head of Śiva during his dance.

In the Tamil portion it is said that he planted one hundred thousand areca-palms

ஸ்ரீவயஜநவ்ஹூதி ஸ்ரீதயே ஸ்ரீதஹக்ஷி:  
 சூலோகஹஸுஹஸ்ரீவாஅகண்சு அகெசு |  
 ஹரநடந விஸ்ரீண-ரே வீபமம்மாம்புரெக-  
 ப்ரஹ்மித உவ வகெசுய-சுபு வபுமாஸுருணி ||<sup>1</sup> (ச)

The next verse which is a continuation of the previous one states that he created a sacred garden (*nandavana*), extending upto the sea, with trees tall as if reaching the sky and pure fragrant flowers and which was filled with the bustle of the gods that came to witness the dance of Śiva.

ஸூஅிகுஸூஉஸூஉசூமுஸூஅிமேஜாஉஸீஉ  
 சூஉவநஉநூரூவஹ்சு வதூஹ்யத |<sup>2</sup>  
 விஷஉநயநநூஸூரூரூகநாயாமதாநாம்  
 விஸூயவரிஸூபாநாம் வஜாஹுதெவூரூபவாஸூ-சூ ||<sup>3</sup> (ரு)

### 1. இச் சுலோகம் தெரிவிப்பது :

நிறைந்த பக்தியால் சிவனுடைய பூஜைக்காக அவன் ஐம்பதினாயிரம் பாக்கு மரங்கள் அளித்தான். சிவ நடனத்தின்போது (ஆடும் சடையிலிருந்து) தெளிக்கும் கங்காஜலத்தால் பாக்கு மரங்களின் இலைகள் அசைகின்றன போலும்.

இந்தச் செய்தியைக் கூறும் தமிழ் பாடல்.

நூறு யிரங்கமுக மாங்கமைத்தான் னேன்சினத்தின்  
 மாருக வெல்களிற்று வாட்கூத்தன்—கூறாரும்  
 வல்லிச் சிறுகிடைக்கு வான்வளர மாடஞ்செய்  
 தில்லைச்சிற் றம்பலத்தே சென்று.

அவன் நட்பு பாக்கு மரங்கள் ஐம்பதினாயிரம் என்றே சுலோகம் கூறுகிறது. தமிழ்ச் செய்யுளோ நூறு ஆயிரம் என்று தெரிவிக்கிறது.

### 2. 'ஹசூதாவ்யத' என்று இருக்கலாம்.

3. இது முன் சுலோகத்தின் தொடர்ச்சியே ஆகும். எம்பெருமானுடைய நடனத்தைக் கண்டு களிக்கக் கூடியிருக்கும் தேவர்களுடைய ஆரவாரத்தால்

He erected a *maṇḍapa* near the sea which has long waves rolling as if inviting devotees with its hands, and opened a broad road to it for the *tīrthayātra* of the god. From the Tamil version it is seen that the *tīrthayātra* took place in the month of *Māṣi*.

[வலி](வி)ர அயலி வி ஸஹோஜிணவனீதுயா தா -

வலி அலி தலி தலி ஸஹோஜி வாரெலலி ஸஹோஜி ஸஹோஜி

ஸஹோஜி ஸஹோஜி ஸஹோஜி வாரெலலி ஸஹோஜி ஸஹோஜி

வணதிலி வ வியலெது வநதிலி வநதிலி வநதிலி (?) || 3

(சு)

The seventh verse says:

Near that *maṇḍapa*, he made a large tank of fresh water, sweet and sacred (capable of washing away the sins,) and appearing like the heart of the sea, with a large banyan tree which stood like a *maṇḍapa* spreading its branches on the bank to accommodate the visitors who flock there for the *tīrthayātra*.

கிரம்பியதும், கடல்வரையில் பரந்ததும், வானளாவ உயர்ந்து விளங்கும் மரங்  
களையுடையதும், தூய்மையான மலர்களை அளிப்பதுமான ஒரு நந்தவனத்தை  
அவன் நிருமாணித்தான் என்னும் செய்தியைத் தெரிவிக்கிறது.

தில்லை வளருந் தெளிதேன் ஒளிதழைப்ப

நல்லதிரு நந்தா வனஞ்சமைத்தான்—[வல்லத்திற்]

கோட்டங்கொள் வாழ்வேந்தர் கொற்றக் களியானை

ஈட்டங்கொள் காலிங்கர் ஏறு.

என்னும் தமிழ்ச் செய்யுளும் இதனையே உணர்த்துவதாகும்.

1. 'மூலித' என்று இருத்தல் வேண்டும் போலும்.

2. எம்பெருமான் தீர்த்தயாத்திரை செய்து கடலாடுவதற்காகப் (பக்தர்  
களை) வாவென்று கரங்களால் அழைப்பதுபோன்ற நீண்ட அலைகளையுடைய  
கடற்கரையில் ஒரு பெரிய மண்டபத்தையும் அதற்குப் போவதற்கு அகலமான  
ஒரு சாலையையும் அவன் அமைத்தான் என்று கூறுகிறது இந்தச் சுலோகம்.

இதே செய்தி பின்வரும் தமிழ்ப் பாடலில் காண்கிறது.

மாசிக் கடலாடி வீற்றிருக்க மண்டபமும்

பேசற் நவற்றைப் பெருவழியும் - ஈசற்குத்

தென்புலியூர்க் கேயமைத்தான் கூத்தன் திசையனைத்து

மன்புலியா ணைநடக்க வைத்து.

இந்தத் தீர்த்தயாத்திரை மாசி மாதத்தில் நடந்ததென்பது தமிழ்ப்  
பாடலிலிருந்து தெரிகிறது.

தலூரணிகெ உயுரவாவநஹூரிதொயம்

தொயாஸயம் ஹுஜயஃஸுநியெரிவெஷஃ |

கூதூர வடம் ஸுஜநஸாஜவி தீதீயாசூர

விஸூராயொமஜூ உகரொஜிஹ ஸஃவியாநஜூ ||<sup>1</sup> (௭)

This verse says that he constructed round the temple of lord Sabhāpati who took a *dikshā*, i. e, considered it as his duty and determined to burn the (three) cities of the *asuras*, a great wall called after his name *Naralōkavira*, with tall towers on which brilliant flags were flying. The poet imagines that the flag having reached the summit of the sky has become very hot by the heat of the sun and this is cooled down by its licking the waters of the cloud.

நாஜா தநூரொகவீர உகரொகி

ஸாஹுஜஹாஹம் வுஜெஹாஃ

த(ஸி)[ஸி]நீ[ஸி]வனஷ ஸஹாநடி வரவூர

வயுஃஸஜீகூதாமூரஃ |

யஜூம்மா மூநிஸகிகெதநவடாஃ

நெஜீயஸா ஹாஸூதா

தவூஷுக்ஷிதி வஹூஹி<sup>2</sup> ஸிபரி

வெஜூர வமாயாஃ வயஃ ||<sup>3</sup>

(௮)

1. அந்த மண்டபத்தின் பக்கத்திலே தீர்த்த யாத்திரைக்கு வருவோருடைய பாவங்களைக் கழுவக்கூடிய சுத்த ஜலம் நிறைந்ததாகவும், அவர்கள் தங்குதற்கான மண்டபம் போன்ற விசாலமான ஓர் ஆலமரத்தை அதன் கரையில் உடையதாகவும் கடலின் இதயம் போன்றதாகவும் உள்ள, பெரிய தடாகம் ஒன்றை அவன் நிர்மாணித்தான்.

2. 'விஹிணி' என்று வாசிக்க.

3. இதன் தமிழ் மொழிபெயர்ப்பு :

எதிரிகளின் அதாவது அசுரர்களுடைய திரிபுரங்களை எரிப்பதையே தீக்ஷயாகக்கொண்டு விளங்கும் சிவபெருமான் நடனம் புரியும் சபையைச் சுற்றிக் கோட்டைபோல் பெரிய சுவர் ஒன்றை எழுப்பி அதற்குத் தன் பெயரைக் கொண்டே) நரலோக வீரன் என்னும் பெயரையும் சூட்டினான். அந்த மதிலின் உச்சியில் விளங்கும் கொடி வானத்தை எட்டியதால் சூரியனுடைய உஷ்ணத்தைத் தாங்கமுடியாமல் மேகத்தில் உள்ள நீரைத் தன் நாவினால் நக்கி அந்த வெப்பத்தைக் குறைத்துக்கொள்ளுகிறது.

This verse refers to the same subject as the previous one. He also built two tall towers (*gōṭṭurayuga*) reaching ont to the sky from which flags flew majestically as if inviting people from different quarters to take shelter there from the scorching heat of the sun.

சுலோகம் ஸ அகார மொவாரயுமம்  
அரெவதா—

[17]

—ம ஸிரம்

வ காரஸி யடி கெதநவடா:

பெவ்வொஸிதா வாயுனி: |

ஹாநொ ஸாநுந வெவ்யுதெதடிதம்

ததூணு ஸங்கா க்ருபா-

பாமவெதி ஸிரம் உவெவ்விநயம்

ஸம் வததீயனீவ தெ ||

(சு)

The tenth verse says that whom the poets call Arulākara justified the name by constructing a hall with a hundred pillars where Paśupati, seeing that it was a place meet for his dance *dabhra-sabhā*, i.e., little-hall or *chirrambalam*, disported himself with his beloved.

ஸம்ஸூரிததிரம்ஸாகர: கவிஜநா

யஸூரஹாரஸூரங்கிதெள

ஸதூரகூரம் ஸதயாகரொஹதரிநா-

ஸம்ஸூரிநம் உணவடி |

1. இந்தச் சுலோகம் முன் சுலோகத்தின் தொடர்ச்சியேயாகும்.

அவன் அங்கே [அந்த மதிலில்] இரண்டு கோபுரங்களையும் எழுப்பினான். அவற்றின் சிகரத்தில் உள்ள கொடிகள் காற்றினால் அலைபுண்டு, சூரியனுடைய வெய்யிலால் களைப்புண்டவர்களுக்குப் புகலிடம் அளிப்பதாக நானா திசையிலும் உள்ளவர்களை அழைப்பதாகவே போலும் அசைந்து பறக்கின்றன.

நுதூஹ-ஃ ௨௨ கெவரு வஸுவதி:

உஹேதி உதூ ஸஹா

கெஸீநாஸிகயா ஸஃ விதநுதெ

ததூக்ஸவபுயஸீ ||<sup>1</sup>

(௨)

The next verse records that round the sacred tank in the temple he built a flight of stone steps which looked like the path by which his fame was to descend to the nether world.

சூநாமநொகம் வரிவாநிதாயா:

ததூதி ஸெநெஹ ஸ வுஷ்ஸினிநா:

அகார ஸா ததூஸஸொ மதஸூ

வாதாஸலீஉவரொஹஸூ ||<sup>2</sup>

(௩)

### 1. இந்தச் சுலோகம் தெரிவிப்பது :

அருளாகரன் என்று கவிஜனங்களால் புகழப்படும் அவன் அந்தப் பெயரை நிலை நிறுத்தவே போலும் நூற்றுக்கால் மண்டபம் ஒன்றை நிறுவினான். அதைக் கண்ட பசுபதியும் அதைத் தமக்காக அளிக்கப்பெற்ற சிற்சபை என்றே மதித்துத் தம் தேவியுடன் அவ்விடம் நடனம்புரிய ஆரம்பித்துவிட்டார்.

இதே செய்தியைக் கூறும் தமிழ்ப் பாடல் வருமாறு :

மல்லற் குலவரையால் நூற்றுக்கால் மண்டபத்தைத்  
தில்லைப் பிரானுக்குச் செய்தமைத்தான்—கொல்லம்  
அழிவுகண்டான் சேரன் அளப்பரிய வாற்றற்  
கிழிவுகண்டான் தொண்டையா ரோறு.

2. அபன் புஷ்கரிணிக்குக் கல்லால் படிகள் அமைத்துச் சீர் செய்ததை எடுத்துரைக்கிறது இந்தச் சுலோகம். குளத்தை ஆழமாக வெட்டி அவ்வளவு நூரத்துக்கும் அவன் படிகள் அமைத்திருந்தானாம். அதைப் பார்க்கும்போது அவன் புகழ் அந்தப் படிகளின் வழியாக இறங்கி நாகலோகமான பாதாளத்தையும் அடைவதற்காகவோ என்று எண்ணும்படி இருந்ததாம்.

இந்தச் செய்தி பின்வரும் வெண்பாவால் கூறப்பட்டுள்ளது.

புட்கரணி கல்சாத்து வித்தான்பொற் கோயிலின்வாய்  
விக்கரணம்(?) பார்ப்படத்தன் மேல்விதித்துத்—திக்களவு  
மாநடத்திக் கோனடத்தும் வாட்குத்தன் மண்ணிலறந்  
தானடத்தி நீடுவித்தான் தான்.

On either side of the golden gateway on the southern side [of the temple] he, Naraṭḥakavīra, set up *maṅgala dīpas* which dispelled from his subjects the darkness of earthly life,

உராவூத தருவடைமீயடி டுகழிணைவூத  
 வுண்வதுகேகாஹநலயீம் நராறொகவீரஃ |  
 தகுவாஹுபோநதியித டாமயிரிகௌ பூத்பெள  
 யௌ மூண்வது: பூவ வணையழபூதாநாழ்!¹(௮௨)

[10]

The priests responsible for worship of the god having the banner of bull, i.e., Śiva, [in the temple] were the recipients of rich endowments from him. Further, he erected a fine hall of gold for the constant recitation of *Kumāra-stōtra* which evidently refers to the *Tēvāram* of Jñānasambandha who is known as Āḷudaiya-pillaiyār.

From the Tamil verse it is learnt that he made tax-free the lands in the village of Tyāgavalli and others and constructed an *agrahāra* for the *brāhmanas* to live. Another verse states that he constructed a sluice to the big tank for irrigating the lands of the *brāhmanas* known as the Three-thousand of Tillai (*Tillai-mūvāyiravar*).

The twenty-fourth *ślōka* also refers to the grant to the temple of a village making it tax-free.

சுயபரிஹஸ்ய ஷ்டெக்தொ: வாலிகாநாம் விஜாநாம்  
 சுகுந மூலிதநாநாம் மூக்திஹெதாவி-ஃமூக்திழ் ।  
 ஐதரடிவி காலாரஹோத்வாராயணாய  
 க்ரிமூவநநாதஜெஹெ: கானநம் ஜைவண ||<sup>2</sup> (மௌ)

1. 'ஸன்துஸம்ப்ராநாடி' என்று இருக்கவேண்டும் போலும்.

கோயிலின் தென்புறத்தில் உள்ளதும் பொன்னால் ஆகியதுமான கோபுர வாயிலின் இரு புறங்களிலும் நரலோக வீரனாகிய அவன் குடிமக்களின் பிறவி யாகிய இருளைப் போக்கடிப்பதற்காகவே போலும் மங்கல தீபங்களை நிறுவி னான் என்பதைத் தெரிவிக்கிறது இந்தச் சுவோகம்.

2. இந்தச் சலோகம் தெரிவிப்பது: விருஷபக் கொடியோனாகிய பரம சிவனைப் பூசை செய்யும் அந்தணர்கள் தூய மனத்துடன் [பூசித்து] வாழ்க்கை

He covered the great Sabhā (*mahatīm sabhāṁ*, i.e., *Pērambalaṁ*) with copper. The latter half of the *śloka* is not clear.

ஸ த சூ லஹதீம் ஸஹாஸவி வியாய தாஜெ ஸுண தாம்  
ஐமஜீ-ஸிதஸாதிர: சிநு ஸஹாநஹொ யுஜி-ஸெ: |

நடத்த அவர்கள் உணவுக்கு வேண்டியவற்றைக் குறைவில்லாமல் அவன் அளித்தான். இன்னும், திருஞான சம்பந்தப் பெருமானுடைய தேவாரப் பதிகங்களைப் பாராயணம் செய்வதற்காகப் பொன்னால் ஆன மண்டபம் ஒன்றையும் அவன் நிறுவினான்.

திருப்பதியம் ஒதுவதற்கு இவன் மண்டபம் நிர்மாணித்த செய்தியைப் பின்வரும் தமிழ்ப் பாடல் கூறுகிறது.

நட்டப் பெருமானால் ஞானங் குழைந்தளித்த  
சிட்டப் பெருமான் திருப்பதியம்—மூட்டாமைக்  
கேட்போர்க்கு மண்டபத்தைச் செய்தான் தெவ் வேந்தர்கெட  
வாட்போர்க்குந் தொண்டையார் மன்.

‘குமாரஸ்தோத்ர பாராயணம்’ என்று சுலோகத்தில் காணப்படுகிறது. ஆளுடைய பிள்ளையார் என்று தமிழிலும் ‘திராவிட சிசு’ என்று வடமொழியிலும் குறிக்கப்பட்டுள்ள திருஞானசம்பந்தர் தேவாரப் பதிகங்களை ஒதுவதையே இது குறிக்கிறது போலும். பின்னால் 26-ஆம் சுலோகத்திலும் ஞான சம்பந்தப் பெருமான் ‘குமாரன்’ என்ற பெயரால் குறிக்கப்பட்டிருக்கிறார்.

‘தில்லை வாழ் அந்தணர்’ என்று சுந்தரமூர்த்திசுவாமிகள் போற்றியுள்ள பூஜகர்களுக்கு அவன் அளித்தவைகளைப் பின்வரும் பாடல்கள் எடுத்துக் கூறுகின்றன.

தில்லைத் தியாகவலி [விண்சிறி? பஞ்சவினி]  
எல்லை நிலங்கொண் டிறையிழிச்சித்—தில்லை  
மறைமுடிப்பார் வீதி மடஞ்சமைத்தான் மண்ணோர்  
குறைமுடிப்பான் தொண்டையர் கோ.

தில்லைமூ வாயிரவர் தங்கள் திருவளர  
எல்லையில்பே ரேரிக் கெழின்மதகு—கல்லினால்  
தானமைத்தான் தெவ்வேந்தர்க் கெல்லாஞ் தலந்தவிர  
வானமைத்தான் தொண்டையார் மன்.

24-ஆம் சுலோகத்தையும் பார்க்க,



ஸயங்கவஸிதாத் கூதலாமதாநிலஃ விஹாமநு

நிஜந்திநாய[ஸுஸா\*]ஸுநுநீயுஸாநீதிவஸாநுதாஸு ||<sup>1</sup>

(௧௪)

He constructed a golden vehicle with a bull mounted on it, and on this vehicle the god was taken in procession during the *bhikshā-tana-yātrā*.

ஸலாம-ஃ அரணதாரணயாநம்

ஸம்ஹாஸு காஹிநலகாரயதஹிதஸ்ரீ: |

விக்ஷாடநெஷு வுஷஹம் வுஷநாஜகெது-

யஜ்-ஃ துஸாஸுதக் ஸலயிரொஹதியுததெதக் ||<sup>2</sup>

(௧௫)

A bugle inlaid with gold intended to announce the arrival of Dēvadēva (god of gods) was presented by him to the temple. The verse states that on hearing the bugle-sound announcing the arrival, even the hands of Indra are automatically folded above his head touching his crown.

நத்யித கநக் கௌப்தம் காஹஸ்தத் யவ்ரிநு

ஐதி சுயதி நாதெநாமதொ ஷெவஷெவ: |

1. அவன் பேரம்பலத்துக்குச் செம்பு வேய்ந்த செய்தியைக் கூறுகிறது இந்தச் சலோகம். [எனினும் இது சரியாக விளங்க வில்லை.]

இதே செய்தியைக் கூறும் தமிழ்ப்பாடல் பின்வருமாறு:

தில்லைச் சிற்றம்பலத்தே பேரம் பலந்தன்னை

மல்லற் கடற்றூனை வாட்குத்தன்—வில்லவர்தம்

அம்புசேர் வெஞ்சிலையி னூற்றறனை மாற்றியகோன்

செம்புவேய் வித்தான் தெரிந்து.

2. எம் பெருமான் பிஷாடனமூர்த்தியின் கோலத்தில் விருஷபத்தின் மீது ஏறித் திருவுலாப் போவதற்காகப் பொன்னால் ஆன வாகனம் ஒன்றை அவன் செய்து சமர்ப்பித்த செய்தியைத் தெரிவிக்கிறது.

தமிழ்ப்பகுதியிலே இவ்விஷயத்தைத் தெரிவிப்பதாகப் பின்வரும் பாடலைக் கொள்ளலாம்.

ஆதிசெம்பொ னம்பலத்தி னம்மா நெழுந்தருளும்

வீதியுப்பொன் வேய்ந்தனனாய் மேல்விளக்குஞ்—[சோதித்

கொடியுடைத்தாய்ப் பொன்னாற் குறுகவலா னென்றும்]

படியமைத்தான் தொண்டையர்கோன் பார்த்து.

சூதலுக்ஊவித வாணி ஸ்ரீஸு-ஸு-ஊகி<sup>1</sup> கிரீடொ  
ஹவதிஸுரவதீநாஃ ஸுஹுரொஹதிஜநா ||<sup>2</sup>

(யசு)

This verse states that he made arrangements for the regular supply, as and whenever required for the worship of the Dancer in the Hall, of fresh flowers which give grace both to the humans and the celestials, and also gold vessels to keep food-offerings equal (in quality) to the nector.

‘வ்ருதிநவலிவ வுஷ்டம் ஹாரிதஸ்ரீஸுஹாயா:

ஹவதவதிஅராநா<sup>3</sup> ஸ்ரீஸுஅராநாஹவசூ<sup>4</sup> |

தஜிஜதஸியியொமஜ்<sup>5</sup> காஹநதூ<sup>6</sup> ருஹொ:

வரிகரஸகூதஸ்ரீஸு[சு\*]ஸுதயஸ்ரீ யசுஸுத ||<sup>4</sup>

(யௌ)

1. ‘வாணிஸுஸு-ஸு வு-ஊகி’ என்று இருத்தல் வேண்டும்.

2. இந்தச் சுலோகம், தேவதேவனுள் எம்பெருமான் [திருவுலாப்] புறப் பட்டு வந்து விட்டார் என்னும் செய்தியைத் தெரிவிப்பதேபோல் முழங்கு வதற்குப் பொன்னால் ஆன காஹ வாத்தியம் ஒன்றை அவன் அளித்ததைக் கூறுகிறது. அந்த வாத்தியத்தைக் கேட்டவுடன் இந்திரனுடைய கைகளும் தாமாகவே சிரமேல் கூப்பிக் கிரீடத்தைத் தொடுகின்றவாம்.

இதைத் தெரிவிக்கும் தமிழ்ப் பாடல் வருமாறு:

இட்டான் எழிற்றில்லை எம்மாற் கிசைவிளங்க

மட்டார் பொழின்மணவில் வாழ்குத்தன்-ஒட்டாரை

இன்பமற்ற தீத்தானம் ஏற்றினா ஸீண்டொளிகேர்

செம்பொற் றனிக்காளஞ் செய்து.

3. ‘ஹவதவதிஅராநாஃ’ என்று இருத்தல் வேண்டும் போலும்.

4. தேவர்களுக்கும் மானிடர்களுக்கும் ஒருங்கே அழகை அளிக்கும் புதுப் புது மலர்களை அவ்வப்பொழுது சபையில் நடம்புரியும் எம்பெருமான் பூசைக்கு அளிக்க ஏற்பாடுசெய்தான்; அன்றி, அமிருதத்துக்கு ஒப்பான நைவேத்தியம் பொருள்களை வைத்துக் கொள்வதற்குத் தங்கத்தாலான பரிகலங்களையும் செய்து அளித்தான்.

பின்வரும் தமிழ்ப்பாடல் பரிகலம் அளித்ததைக் கூறுகிறது:

ஏனை வடவந்தே ரிட்டிடைந்த செம்பொன்னால்

ஏன (?) லெனத்திலலை நாயகருக்—கானெய்

சொரிகலமா மாழயிலைத் தொண்டயர்கோன் கூத்தன்

பரிகலமாச் செய்தமைத்தான் பார்ந்து,

Naralokavira who knew the essence of Śiva's worship gave precious jewels which were pure and without any blemish, like the hearts of sages, to adorn the sacred body of the King of Dancers of the Hall.

சுயலகூரூத தவ்விந்நு தீராஜஸூய் மஹொ-  
ஸ்ரீவ யஜநரஸஹொ ளெள க்ரிகெஹ-உஷணாநி |  
வவூஷி வஸிமதாநா ஹ்வி-உயாநா வுராரொ:  
உநிஜநஹுடிபாநா யாநிஸாஜ்யம் வஹணி ||<sup>1</sup> (யஅ)

This verse states that he arranged for the offering of the nectar of milk with sugar-candy to the Lord of Gaurī, who was given [on a former occasion] poison to drink by the celestials. The poet wonders at the popular exclamation of the above and concludes that he be the celestial or the Dancer of the Hall, the divine grace is obtained easily where there is devotion.

கூரீரம் ஸவண லஜதா காரூதெ ஸ்ரீ தவ்விந்நு  
மௌஸீவதெஜி-உஷிஷெஷா விஷெஷ வாயா: |  
ஸ்ரூத ப்ரஜா: க்ரிகெஹஷு ஸஹாநதெ க்ரிகெ  
ஹ்விஷு க்ரிகெஹ (ஸ) மஹொ ஹவதி ப்ரஸாஜி: ||<sup>3</sup> (மக)

1. சிவபூசையின் ரசத்தை நன்கு அறிந்த நரலோகவீரன் மன்றினில் ஆடும் நடராஜப் பெருமானுடைய திருமேனியை அலங்கரிப்பதற்காக, முனி ஜனங்களின் இதயத்தைப்போல் கீர்மலமாகத் தோற்றமளிக்கும் ஆபரணங்களைச் செய்து அளித்தான் என்பதை எடுத்துக் கூறுகிறது இந்தச் சுலோகம்.

2. 'வ்ரவண' என்று வாசிக்க.

3. கௌரிபதியான சிவனுக்குத் தேவர்கள் [ஒருசமயம்] விஷத்தைப் பான்ம் செய்யக் கொடுத்தார்கள். அவனுக்கு இவன் கற்கண்டுடன் கூடிய பாலை அமிர்தம்போல் அளிக்க ஏற்பாடு செய்தான். இதைக் கண்டு மக்கள் வியந்து பேசுகின்றனர். தேவரானால் என்ன, மன்றிலாடும் பெருமானாயின் என்ன, பக்தி பூர்ணமாய் இருந்தால் பிரசாதம் சுலபத்தில் கிட்டுகிறது.

இச்செய்தியை தெரிவிக்கும் தமிழ்ப் பாடல்:

தொல்லை பதித்திலைக் கூத்தற்குத் தொண்டையர்கோன்  
எல்லைத் திசைக்கரிக ளெட்டளவுஞ்—செல்லப்போய்ச்  
சாலமுது பேய்தடிக்க [த்தார்ட்டிகத்?] தொண்டையர்கோன்  
பாடிமுது செய்வித்தான் பார்த்து

He endowed the temple of Dhūrjaṭi, i.e., Śiva, with ten (*nitya-dīpas*) perpetual lamps of fragrant camphor. The fragrance pervaded the whole earth and thus confirmed the maxim that 'the earth is of fragrance'.

கவ-ஃராவதி-ஃகருநாஸுரவிஹதிவாஃ<sup>1</sup>

நித்யநயத் நிகடு டுஸ யுஜ-ஃடுஹி: |

.... வ கருமயதபா யரிஃ

யடுவராஃ ஸுஹமதாதி ஸத்யதெதக் ||<sup>2</sup>

(உடு)

Naralōkavīra presented to god a brilliant golden water-pot (*kalāśa*) and other vessels made similarly of gold, the brilliance of which proclaimed [to the world] that unfailing service and devotion to the feet of Hara brought merit very easily.

ஜாஃஸுதடிஃ கருஸுத ஸியாய காஹஃ

உவாஹுஃஹெஹிஹிதாஹரொகவீர: |

ஃரஸுத ஹரஸுதவடியொஸு ஸுதநத்யுஹி

ஹிஹிஸுஹி ஸுஹுஹுதநயக் ஸுஸிஹி ||<sup>4</sup>

(உடுக)

1. 'ஸுரஸுதவாஹு' என்று இருத்தல் வேண்டும்.

2. கந்தமயமானது பூமி என்பதை விளக்கிக்காட்டுவதேபோல எங்கும் மணம் பரப்பும் கர்ப்பூர வர்த்திகளையுடைய பத்து நித்திய தீபங்களைத் தூர்ஜி எம்பெருமானுக்கு அவன் அளித்தான் என்பதைக் கூறுகிறது இந்தச் செய்யுள்.

இதன் தமிழ்ப்பாடல்:

ஆடுந் தனித்தேனுக் கம்பலத்தே கர்ப்பூரம்

நீடுந் திருவிளக்கு நீடமைத்தான்—கடார்

அடிக்க [த்திணை] நரியும் புள்ளுந் .....

தடிக்கப் பெருங்குத்தன் தான்.

3. 'சுவரஹு' என்று வாசிக்க.

4. நரலோகவீரன் ஹரனுக்குப் பிரகாசிக்கும் பொற்கலசம் ஒன்றையும் பொன்னாலான வேறு பாத்திரங்களையும் அளித்தான். எம்பெருமான் பாதங்களிலே இடையறாத பக்தியும் சேவையும் எளிதில் புண்ணியத்தை அளிக்கும் என்பதை எடுத்துக்காட்டுவனபோல அவற்றின் காந்தி ஒளிர்கிறது.

The next verse states that he presented one thousand milch-cows for conducting the *abhishēka* of milk resembling the nectar to the god in the temple.

தஞ்ராவிலெக லெநன வினொஹஹவ

. . . . . உபஸகிஜிராஉயெது: 1 |

வண்ணாநதீயஞ்ஞதயொ ஜமதீவகீதி-2-

நுமநுஹனிஹவநெ உநநவிஷஸா: ||2

(உருஉ)

This verse states that he set up an image of Nandi (the sacred-bull) who by his constant and uninterrupted devotion to god Śambhu (Śiva) had obtained His grace (*priti*), and whose permission for entrance to the sacred presence is sought by the lord of Vaikuṇṭha, i.e., Viṣṇu and the other gods coming there for worship every morning, as also an image of the goddess.

இதன் தமிழ்ப் பாடல் :

தெள்ளு புனல் தில்லைச் சிற்றம் பலத்தார்க்குத்  
தள்ளியெதி ரம்பலந்தா தன்பாதம்—புள்ளுண்ண  
நற்பயிக்கங் கண்ட நரலோக வீரன்செம்  
பொற்படிக்கங் கண்டான் புரிந்து.

சிற்றம் பலத்தானே யேற்றினார் தெவ்விடத்துக்  
கொற்றத்தால் வந்த கொழுநெதியாற்—பற்றார்  
தருக்கட்ட வஞ்சினவேற் றார்மணவிற் கூத்தன்  
திருக்கட்ட மஞ்சனமுஞ் செய்து (?)

1. 'காலயெநு:' என்று வாசிக்க.

2. எம்பெருமானுக்கு அமிர்தத்துக்கு ஒப்பான பால் அபிஷேகம் செய்வதற்காக அவன் ஆயிரம் பாற்பசுக்களை அளித்த செய்தியைத் தெரிவிக் கிறது இந்தச் சுலோகம்.

இதனையே கூறும் சாசனத் தமிழ்ப் பாடல் பின்வருமாறு :

ஒங்கியபொன் னம்பலத்தார்க் கோரா யிரஞ்சரவி  
ஆங்களித்தா னேற்றெதிர்ந்தா ராயிழையார்—தாங்கா  
தொருக்கியுட லாவி யுயிர்த்துநாட் போக்கி  
யிருக்கவென்ற தொண்டையா ரேறு

சூயாதா:1 பூதிவாஸரம் ஹரவடி  
 பூத: பூணாஜாதி-3நொ  
 வெகூண பூவாஸாரா சுவி வஹி-  
 விஷ்ணி யஸ்தாஜ்யா |  
 யஸிநு ப்ரேகிருவாஹிதா ஹமவத-  
 ஸ்ரஹாரதநஜாபுயா  
 நநீஸஸ்ய ஸ ததூஜி2 உதூநா-  
 நெவ்யாஸு தஸ்தாகரொகி || (உயந)

Naralōkavīra presented to the temple many beautiful jewels set with precious stones and also gave one village making it tax-free to meet the expenses of *archchana*.

Vide the Tamil verse given under *ślōka* 13 above where the gift of the village Tyagavalli as tax-free to the temple is referred to.

1. 'சூயாதா:' என்று இருத்தல் வேண்டும்.

2. 'உதி-3' என்று வாசிக்க.

3. அவன் தேவிக்கும் நந்தீசப் பெருமானுக்கும் திருவுருவங்கள் செய்து அமைத்த விவரத்தைக் கூறுகிறது இந்தச் சுலோகம். இடையறாமல் சம்புவை ஆசிரயித்திருப்பதால் அவருடைய பிரீதியைப் பெற்றிருப்பவன் என்றும் நான் தோறும் காலையில் ஹரனைச் சேவிக்கவரும் வைகுண்டப் பெருமானாகிய விஷ்ணு, தேவர் ஆகியோர்களும் சந்திதானத்துக்குள் செல்லுமுன் அவனுடைய அனுமதியைக் கோரிப் பெறுகிறார்கள் என்றும் நந்தீசனைப் புகழ்ந்து கூறுகிறது கவி.

அம்பிகைக்காகத் திருக்காமக்கோட்டம் நிறுவிய செய்தி குறிக்கப் பட்டிருக்கிறது இந்தச் சுலோகத்தில்.

பின்வரும் பாடலில் முதல் அடி சரியாக விளங்க வில்லை. எனினும் உமை, ரிடபம் என்னும் சொற்கள் காண்கின்றன. இந்தச் சுலோகத்தின் செய்தியைத் தெரிவிக்கும் தமிழ்ப் பாடல் இதுவே போலும்.

[பாருமைய மொடபச் செய்வீர் சிரியா]

திருவுருவ மானதிருக் கோலம்—பெருகொளியாற்  
 காட்டினான் தில்லைக்கே தாசினிவாய் வெங்கலியை  
 ஓட்டினான் தொண்டயர்கோ [னுற்று].

தகிலுஷ்ணாநி வஹுரத விவிசிரதாநி

கூதா டயாநியிரயம் நரஹாகவீரஃ ।

தஸ்யோதிநாவிபிஸிஹுதிகரம் கரண

முரஃ விஹீநககரொடிஸைநநகௌ ॥<sup>1</sup> (உயச)

This verse states that he made arrangements to perform *abhishēka* every year to the god enshrined in the *sanctum sanctorum* (*mūlasthāna*) with one thousand measures. From the Tamil verse it is learnt that the *abhishēka* was to be performed with one thousand *nāḍi* of ghee.

புதிவஸூஸஹஸௌண

உருஷாநநிவாஸிநாடி ।

சுதூஸிஷெகூம் புகஸ்ய-

ஃபம் பூதாஸு வராஃ ஸ்ரியடி ॥<sup>2</sup> (உயரு)

This verse states that he set up a golden image of *Kumāra*, i.e., Tiruñanasambandha who drank milk from the sacred breast of *Girija* i.e., *Pārvati* and obtained the grace of *Sarasvatī*, danced and sang the praise of *Śrīkaṇṭha*, i.e., *Śiva* and also made arrangements for the offering of *pūyasam* to the deity.

1. எம்பெருமானுக்கு அநேக ரத்தினங்கள் வைத்து இழைத்த ஆபரணங்கள் பலவற்றையும், அர்ச்சனை நடைபெறுவதற்காக இறைதவிர்த்து முற்றூட்டாக ஒரு கிராமத்தையும் நரலோக வீரன் அளித்த செய்தியைக் கூறுகிறது இந்தச் சுலோகம்.

தியாகவல்லி என்னும் கிராமத்தை அவன் அவ்வீதம் இறையிழித்து அளித்த செய்தியைக் கூறும் தமிழ்ப் பாடலுக்கு மேலே 13-ஆம் சுலோகத்தின் கீழ்க் குறிப்பைப் பார்க்க.

2. மூலஸ்தான எம்பெருமானுக்கு ஆண்டுதோறும் ஆயிரம் [நாழி நெய்] அபிஷேகம் செய்ய அவன் ஏற்பாடு செய்தான் என்பதைத் தெரிவிக்கிறது.

இதன் தமிழ்ப் பாடல் பின் வருமாறு :

ஆடுந் தெளிதேனை யாயிர நாழிநெய்யால்

ஆடும் படிசண்டா னன்றிரைக—ளோடும்

திறங்கண்ட தாளன் சினக்களிற்றான் ஞாலம்

அறங்கண்ட தொண்டையுர்கோ னுன்கு

யபாணீ மிரிஜா கூ அபு.மஸிதம்  
 வீஷா ப்ருதூதீவயொ  
 உயாஸூரூபிகாததொ விகயித-  
 ஸ்ரீகணகீதி-கூரா |  
 ஐ.தி-3ம் தவூதீ ஸுபாஸூதவகஸீம்  
 கானூதா கூபாஸூத தாம்  
 கூதூ யாம் அ ஸாதகூம்ஹவடிதம்  
 தவூதூபிஸகீ<sup>1</sup> வாயஸூ ||<sup>2</sup>

(உயக)

It is stated that he set up an image of Bhattachārya, who was the chief person of the *brāhmaṇa-kula* and who had on a former occasion defeated in debate the adherents of religions outside the Vedic lore and established the Śaiva religion on the earth. The word *bhattachārya* evidently means that he was a temple-priest and was popularly known by that name at that time. It is not known who is the person that is referred to here. Probably it refers to Sundramūrti-Nāyanar, one of the Śaivite trio and an *Ādi-Śaiva*, i.e., a temple-priest.

ஹதூபாஸூ உதி ஸூதாம் ஹஸிபிவா-  
 ஐ.தி-3ம் மூஹாயாம் வஹந்<sup>3</sup>  
 ஸ்வாபி-சிவ வெஷ்வாஹூஸூய-  
 ஸாதவூதீ அகூவூரா |

### 1. 'தவூதூபிஸகீ' என்று வாசிக்க.

2. மலைமகளின் ஸ்தனத்திலிருந்து பாலைப் பருகிக் கலைமகளின் அருளைப் பெற்று ஆனந்தக் கூத்தாடி ஸ்ரீகண்டன் புகழைப் பாடிய ஆளுடைய பிள்ளை யாரான திருஞான சம்பந்தப் பெருமானுடைய பொன் திருமேனியை நிறுவி அதற்குப் பாயஸம் நிவேதிக்க அவன் செய்த ஏற்பாட்டை எடுத்து உரைக் கிறது இந்தச் சுலோகம்.

மன்றுதிகழ் தில்லக்கே வாணிக் கரசகணந்  
 துன்றும் பொழின்மணவிற் ரெண்டைமான்—என்றும்  
 இருந்துண்ணக் கண்டா னிகல்வேந்த ராகம்  
 பருந்துண்ணக் கண்டான் பரிந்து.

### 3. 'ஸூதாம் யொவஹந்' என்று இருக்க வேண்டும் போலும்,



தாஸுதி-ஃ விநிவெடி றொகவரஃ.

நடிவடிஃ வாலநீ

ஸொயம் ஸுஹகூ றொஹொ விஹிதவாநு

தலிநு ஸதாஹுணீ ||<sup>1</sup>

(உயௌ)

He erected a *prākāra* and a *maṇḍapa* to the shrine of the goddess Pārvatī (*Tiru-k-kāmakkōṭṭam*) whose image was adorned from head to foot with fine jewels befitting the dancing-hall of her lord (*sva-pati naṇanasthāna-yōgyam*).

செவலா[ஹுஸலா\*]புரிவரிசுஹிதாஃ காலகொஹுஸிதாயாஃ

புராகாரஜாலவிடிபிதலெஸன் கௌபவாநுஹவஹ !

சிஹெஹதஸலாஃ ஸுவதிநடிநாஸுநாநபொமலபுகாரம்

ஸதாஹு ஹதூர ஸுகரஹகொரஃ ஹலஹுணீ ஹுவிவலஹு-||<sup>2</sup>

(உயஅ)

1. பிராம்மண குலத்தின் தலைசிறந்தவரும், முன்னொரு சமயம் வேதத்துக்குப் புறம்பமான சமயங்களைச் சேர்ந்தவர்களை வாதத்தில் வென்று இவ்வுலகில் சிவபெருமானுடைய பெருமையை நிலைநிறுத்தியவருமான பட்டாசாரியருடைய திருவுருவத்தை அவன் நிறுவினான் என்பதைத் தெரிவிக்கிறது இந்தச் சுலோகம். இந்தப் பட்டாசாரியர் யார் என்பது விளங்கவில்லை. எனினும் இந்தப் பெயரிலிருந்து அவர் சிவனைப் புகித்து வந்த ஆதிசைவராக இருத்தல் வேண்டுமெனக் கொள்ளலாம். ஒருகால் இது சுந்தர மூர்த்தி நாயனரைக் குறிப்பதாகக் கொள்ள வேண்டுமபோலும்.

2. திருக்காமக் கோட்டத்திலே எழுந்தருளியிருக்கும் தேவியான மலை மகளுடைய கோவிலுக்குப் பிராகாரத்தையும் ஒரு மண்டபத்தையும் எழுப்பினான்; அன்றி, அவளுடைய பதிபின் நடன அரங்குக்கு யோக்கியமாக அவள் திருமேனியைக் காலோடு தலை அழகிய ஆபரணங்களால் பூட்டிப் பொலிவுறச்செய்தான்.

இந்தச் சுலோகத்தின் தமிழ்ப் பாடல் :

நடங்கவின்கொ ளம்பலத்து நாயகச்செந் தேனின்

இடங்கவின்கொள் பச்சையிளந் தேனுக்—கடங்கார்

பருமா ளிகைமேற் பகடுதைத்த கூத்தன்

திருமா ளிகையமைத்தான் சென்று.

பின்வரும் பாடலும் இதனையே தெரிவிக்கிறது போலும்.

He presented to the goddess enshrined in the Kāmākōshṭha (*Tiruk-kāmakkoṭṭam*) of the temple, a *pīṭāmbara* (yellow-cloth) made of gold the brilliance of which pervaded everywhere like the smoke emanating from the forest-fire (immolating) the wives of the enemies conquered by him, Nalōkavira.

வீதாம்பரம் காணுந்நெய் செவ்வா-

வூசு காலகொடி ஸ்ரீதிராஸ்திராயா :

அகாரயவெளி விநாஸிநீநாம்

வநாபூபூதாம்பரதாம் கரொதி ||<sup>1</sup>

(உயக)

This verse states that Nalōkavira erected a high outer-wall of stone, the tower of which touched the clouds, to the shrine of the *dēvī* (i.e., *Tiruk-kāmakkoṭṭam*.)

சுனாயவெடுவ அகாரஸாராம்

வாஹ்யம் விநாஸிநீநாமொகவீர :

யபூமமெவ ஸ்ரீநிதிதஸ்ரீவாயா :

சூபாபூபூதா ர அயனி ஸ்ரீவாஸ்திராயா ||<sup>2</sup>

(நய)

தில்லைப் பெரிய திருச்சுற்று மாளிகையை

எல்லைக் குவவரைபோ லீண்டமைத்தான்—தொல்லைநீர்

மண்மகளைத் தங்கோன் மதிக்குடைக்கீழ் வீற்றிருத்தி

உண்மகிழந் தொண்டையர்கோ னுற்று.

1. திருக்காமக் கோட்டத்தில் எழுந்தருளியிருக்கும் தேவிக்கு அவன் பொன்னாலான பீதாம்பரம் ஒன்றை அளித்தான் என்று கூறுகிறது இந்தச் சுலோகம். அவன் வென்ற பகையரசர் மனைவிகள் [தீக்குளித்ததால் உண்டான] காட்டுத்தீயின் புகைபோல் அந்தப் பீதாம்பரத்தின் காந்தி எங்கும் பரவியிருந்த தாம்.

இதனைத் தெரிவிக்கும் தமிழ்ப் பாடல் :

சேதாம்பல் வாய்மயிற்குத் தில்லையந் தேவிக்குப்

பீதாம் பரஞ்சமைத்தான் பேரொலிநீர்—மோதா

அலைகின்ற வெல்லை அபயனுக்கே யாக

மலைகின்ற தொண்டையார் மன்.

2. 'ஸ்ரீவாஸ்திராயா' என்று வாசிக்க,

This last verse states that Naraḷōkavira gave a perpetual endowment for the daily supply of oil and milk for children to signify the universal motherhood of the goddess. The poet further adds that this item should receive the first preference of the person who intends to make charities.

தெருவொவியரவதி ஸுதாயாதி யாதும் சிஸுநா.

நெயுக்கு ரொஸு உயரக ரொடிஷ் நிதூம் விவதிதி !

ஸ்ரீராம ஸாஹிபுஜைவடிவீஸாநுகம்பாஸ்யாநாம்

பாம்பாம்பா வெளாக்கி தயவநீ ஞாஸ்திவிஹதெவ ||<sup>1</sup> (நயக)

The Tamil portion of the inscription gives some additional information about Naralōkavīra: (1) that he covered with gold several

திருக்காமக் கோட்டமான தேவியின் ஆலயத்துக்குக் கருங் கல்லால்  
மேகத்தைத் தொடும்படி உயர்ந்த மதில் சுவரை நாலோக வீரன் எழுப்  
பினான் என்று கூறுகிறது இந்தச் சுலோகம்.

இதைக் கூறும் சாசனப் பாடல் :

எவ்வுலகு மெவ்வுயிரு மீன்று மெழிவழியாச்

செவ்வியாள் கோயில் திருச்சுற்றைப்—பவ்வஞ்சுழி

எல்லாவட்டம் தன்கோற் கியலவிட்ட வாட்குத்தன்

தில்லைவட்டத் தேயமைத்தான் சென்று.

1. தேவி ஜகன்மாதா வெண்பதைக் காட்டுவதற்காகவே போலும் குழந்தைகளுக்கு நாஸ்தோறும் பாலும் எண்ணெயும் வழங்குவதற்கு அவன் செய்த ஏற்பாட்டை எடுத்துரைக்கின்றது இந்தக் கடைசிச் சுலோகம். மனிதர்கள் தானம் முதலிய புண்ணிய கருமங்களைச் செய்ய ஆரம்பிப்பதற்கு இதைக் காட்டிலும் சிலாக்கியமானது வேறு ஒன்றும் இல்லை என்கிறது.

இந்தச் செய்தியைத் தெரிவிக்கும் தமிழ்ப்பாடல் :

செல்வி [திருத்தறங்க டென்]னகரித் தில்லைக்கே

நல்லமகப் பாவெண்ணெய் நாடோறுஞ்—செல்லத்தான்

கண்டா னரும்பையர்கோன் கண்ணகனீர் ஞாலமெலாம்

கொண்டானந் தொண்டையார் கோ.

parts of the *sabha*, (2) that he presented an elephant to the temple and (3) that he built of stone the temple of Śuḍalai-y-amarndan (i.e., he who took his abode at the crematorium) at Tillai.<sup>1</sup>

1. வடமொழிப்பகுதியிலே காணப்படாத செய்திகள் சிலவற்றைத் தமிழ்ச்சாசனப் பாடல்கள் தெரிவிக்கின்றன. தில்லைச்சிற்பம்பலத்துக் கொடுங்கைக்குப் பொன் வேய்ந்தது, பொன்னின் திருவிளக்கால் திருச்சுற்று வந்தமைத்தது, யானையை அணித்தது, தில்லைச் சுடலையமர்ந்தான் கோயிலைக்கல்லால் எடுத்தது போன்ற செய்திகள் காணப்படுகின்றன. அந்தப் பாடல்களையும் கீழே கொடுத்துள்ளோம். இவை ஸ்ரீ மு. இராகவையங்கார் அவர்களால் பெருந்தோகையில் திருத்தப் பெற்ற செய்யுள் வடிவம்.

எல்லை கடலா விகல்வேந்த ரைக்கவந்த  
செல்வமெலாந் தில்லைச்சிற் றம்பலத்துத்—தொல்லைத்  
திருக்கொடுங்கை பொன்வேய்ந்தான் நிண்மைக் கலியின்  
தருக்கொடுங்க வெல்கூத்தன் தான்.

தில்லையிற்பொன் னம்பலத்தைச் செம்பொனூல் வேய்ந்துவா  
னெல்லையைப்பொன் னாக்கி னென்பரால்—ஒல்லை  
வடவேந்தர் செல்வமெலாம் வாங்கவேல் வாங்கும்  
குடைவேந்தன் தொண்டையார் கோ.

தென்வேந்தன் கூனியிர்த்த செந்தமிழர் தென்கோயில்  
பொன்வேய்ந்து திக்கைப் புகழ்வேய்ந்தான்—ஒன்றார்க்குக்  
குற்றம் பலகண்டோன் கோளிறழக்கும் வேற்கூத்தன்  
சிற்பம் பலத்திலே சென்று.

பொன்னம் பலக்கூத்த ராடம் பலமணவிற்  
பொன்னம் பலக்கூத்தர் பொன்வேய்ந்தார்—தென்னர்  
மலைமன்ன ரேனை வடமன்னர் மற்றக்  
குலமன்னர் செல்வமெலாம் கொண்டு.

பொன்னம் பலகுழப் பொன்னின் திருவிளக்கால்  
மன்னுந் திருச்சுற்று வந்தமைத்தான்—தென்னவர்தம்  
பூவேறு வாரகுழலா ரோடும் பொருப்பேற  
மாவேறு தொண்டையார் மன்.

வாளுடைய பொற்பொதுவின் [மன்ன னிடமாரும்]  
ஆளுடைய பாவைக் கபிடேகம்—வேளுடைய  
பொற்பினுன் பொன்னம் பலக்கூத்தன் பொங்குகட  
வெற்பினுன் சாத்தினுன் வேறு.

சேங்கற்பட்டு

Œengarpattu (Chingleput)

மக்கென்வியின் உதவியாளர்கள் தயாரித்துள்ள பிரதிகளிலே பின் வரும் ஆறு சாசனங்களும் ஒன்றன் பின் ஒன்றாகத் தொடர்ந்து காணப்படுகின்றன. எனினும், அவை எந்த இடத்திலிருந்து கிடைத்த சாசனங்களின் பிரதிகள் என்பது குறிக்கப்பெறவில்லை. ஒவ்வொன்றின் தலைப்பிலும் வலது மூலையில் 'தாம்ர சாசனப் பிரதி' என்று தெலுங்கில் எழுதப்பட்டிருக்கிறது. இவற்றின் மூலப் பிரதிகளான செப்பேடுகள் இப்போது சென்னை (மியூசியம்) பொருட்காட்சிச் சாலையில் உள்ளன. கி. பி. 1858-ஆம் ஆண்டு செங்கல்பட்டு ஜில்லா கலெக்டரால் அவை மியூசியத்துக்கு அனுப்பப்பட்டன வென்பதைத் தவிர வேறு விவரங்கள் கிடைக்கவில்லை. சென்னை ராஜதானியின் புராதனச் சின்னங்களின் அட்டவணை என்று ஸுவல் துரை எழுதிய நூலிலும் ஜேம்ஸ் பர்ஜஸ், பண்டித எஸ். எம். நடேச சாஸ்திரி ஆகியோர் பதிப்பித்த தமிழ், ஸம்ஸ்கிருத சாசனங்கள் என்ற நூலிலும் இவை இடம் பெற்றுள்ளன.

இந்தச் சாசனங்கள் தமிழ் மொழியிலேதான் உள்ளன; ஆனால் கிரந்த எழுத்தில் எழுதப்பட்டிருக்கின்றன. பொதுவாக நோக்குமிடத்து அவை ஒன்றுபோலவே காணப்பட்டாலும் சிறு சிறு வித்தியாசங்கள் உள்ளன. ஒவ்வொன்றின் தலைப்பிலும் 'ராஜேலில்லா' என்று பாரசீக எழுத்தில் பொறிக்கப்பட்ட முத்திரை இருக்கிறது. ராஜேலில்லா என்பதற்குத் தர்மம் என்று பொருள். அதேபோல யெக்கோல் அப்பாஜி அல்லது எக்கோடி அப்பாஜி என்று வாசிக்கக்கூடிய பெயரைத் தெலுங்கு எழுத்தில் கொண்ட முத்திரை ஒன்று ஒவ்வொன்றின் கடைசியிலும் காணப்படுகிறது.

நாயகர் வீதி யெழுந்தருளு நன்னாளால்

தூய கருவேழு தூபத்தாற்—போயொளிசேர்

வான்மறைக்கக் கண்டானிப் பார்மகளை வண்புகழால்

தான்மறைக்கக் கூத்தன் சமைத்து.

என்றும் பெறுதலா லேரா ரெழிற்புலியூர்

மன்றி னடனுக்கு மாமத்தக்—குன்று

கொடுத்தருளி மண்ணிற் கொடுங்கலிவா ராமே

தடுத்தன்ன் தொண்டையர்கோன் தான்.

தொல்லோர்வாழ் தில்லைச் சுடலையமர்ந் தார்கோயில்

கல்லா வெடுத்தமைத்தான் காசினியில்—[தொல்லை]

மறைவளர்க்க வெங்கலியை மாற்றிவழு வாமல்

அறம்வளர்க்கக் காலிங்க னாய்ந்து.

இந்தச் செப்பேடுகள் சகாப்தம் 1011, அதாவது கி. பி. 1089-ஆம் ஆண்டு கொண்டிருந்தாலும் பொறிக்கப்பட்டுள்ள எழுத்துக்கள் மிகவும் பிற்காலத்தனவாகும். இவற்றைப் போலிச் சாசனங்களாகவே கொள்வர்,

இவை மக்கென்ஸியின் தேன் ஜல்லாக்களின் சாசன அட்டவணையில் சேர்க்கப்பெற வில்லை.

The following six inscriptions are found copied consecutively in the Mackenzie manuscripts; but the place wherefrom they were secured has not been noted there. At the right-hand corner at the top of each inscription it is noted as 'copy of copper-plate grant' in Telugu. The original copper-plates are now deposited in the Government Museum at Madras. The particulars as to wherefrom they were obtained are not also available. They were received in the Museum from the Collector of the Cingaleput district in the year 1858. These have been noticed by R. Sewell in his *List of Antiquities of the Madras Presidency* and included in the *Tamil and Sanskrit Inscriptions* (Archaeological Survey of Southern India, vol. IV) by Jas. Burgess and Paadit S. M. Natesa Sastri.

These inscriptions are in Tamil language; but written in the Grantha script. They are more or less similar in character, but differ in minor details. These bear a seal at the top of the plate in which is inscribed in Persian *Rehēlilla* which means *dharma* or charity and another seal at the end of the inscription in which is inscribed *Yekkōl Appāji* or *Ekkōṭi Appāji* in Telugu.

Though they bear the Śaka date 1011, corresponding to A.D. 1089, the script is very late, more or less 'modern'. These are apparently spurious.

These records also are not included in the *List of Inscriptions from the Southern Districts*.

சாசனம் — 1274]

[D. 2944-8.

Record dated in the Kali year 4190 corresponding to Śaka 1011, Manmatha, Sittirai 22. It states that in the *Chaturvēda-bhūmī bhavana* of the Tonḍaimaṇḍalam on the eastern side of Kāñchīmaṇḍalam Cholaraja Vira Sangudaiyan gave an *agrahāra* to Alagayyar in the Pañcha-nada-stala in Kōnai-kōṭṭam to the north of Aranya river. Rayar who was possessed of the four divisions, viz., chariots,

elephants, horses, and the infantry, of the army destroyed the *agrahāra* of Aḷagayyar, dug a tank and divided the Pañchavarṇa-nādu into four pieces for forest-clearing. The portion allotted named as Kōṇēri Mattavarāya-gōtra in the north and the south-west (*niruti*) directions was 1050 *kuḷi* measured of 64 feet rod and the gold paid by Kōṭṭaiyān for this was 150 *pon*. It is also stated therein that there are stones marked with Kōṇēri-mudrā and the *agrahāra-mudrā*. It also contains the stiputation that the grant is to be enjoyed as long as the sun and the moon last and as long as the earth and the grass (on it) last. It is signed at the end by Narasimhachāri (*svahastalikhitam*) noting that this is of the first sector.

The word *mannavettu* means forest-clearing. The cyclic and the Śaka years do not agree: Śaka 1011 would correspond to the cyclic year Śukla, while that of Manmatha would be Śaka 1037.

This is registered as **Cholas No 6** in the *Catalogue of Copper-plate grants in the Government Museum at Madras*.

ராஜேலில்லா என்ற பாரதீக எழுத்து கொண்ட முத்திரை

கயியுமாணு ஸ்ரீ சதாசுமாராயீவாஹந மகாஸூர ஸ்ரீ  
சூக வெரு உதய ஸ்ரீ வெரு உதய உதய தீ. காணு உதய உதய  
கிழக தொணுணு உதயவெரு உதயவெரு உதயவெரு உதயவெரு  
கொணு உதய கிழககொணு உதயவெரு உதயவெரு உதயவெரு  
ராணு வு(சு)வெருவெருவெரு வடக்கு கொடு கொடு  
வெருவெரு ஸ்[த\*]ருதிரு[ச\*] வீராதிவீராதி வீராதிவீராதி  
ஸ்ரீமாதாஜா சுமகயுமாணு சுமாரா பண்ணார். ரய மரு துரம  
வெருவெரு ராயர் சுமகயுமாணு சுமாரத்தை சுழிச்சுக்  
கொளம் பறிச்ச வெருவெருவெரு நாருசுக்கி உதயவெருவெரு  
தெரு. வுதிநா உதயக்கு நிருதி திக் கொள கொடுநரி  
உதயவெரு மொதிநம் கிழக கொணு வ. சுருச-அடி கொடுநல் சுழி  
சூரு உதயவெருவெரு செல்லு. கொள கெ[ச\*]தெரி முத்திரை கல்வி  
ருக்குது. சுமார முத்திரை [யி\*]ருக்குது. தாஸ்ராயவெருவெரு  
வெருவெரு உதய[ச\*]தி வரைக்கிம் உதயிமா வு[ச\*]உதயவெருவெரு  
அனுவித்துக்கொள்ளவும், யிதக்கு கொட்டையான் குடுத்த பொன்  
மாடு. யித முதலண நரலிஹாஅரி ஸொஸ்த ஸிசிதடி ||

யெக்கோல் அப்பாஜி என்று தெலுங்கு எழுத்து கொண்ட  
முத்திரை

இதன் தமிழ் வடிவம் :

கலியுகாந்தம் ஐஸ் சதாசூய. சாலீவாஹநசகாப்தம் தயக-  
வெல்<sup>1</sup> மந்மத ஐஸ் சைத்ர மாஸ உயஉ-தி. காஞ்சீ மண்டலத்  
துக்கு கிழக்கு தொண்டமண்டல சதுர்வெத பூமவவனத்தில்<sup>2</sup>  
திக்கு-அ. கொணம்-யசூ. கழிவு கொணம்-க. அரண்ய நதிக்கு  
மெற்கு அ(த்ர)ருண்ய பு[த்ர]ர்வஸ்தலத்துக்கு<sup>3</sup> வடக்கு கொரை  
கொட்டம் பஞ்சநதிஸ்[த\*]லத்தில் வீராதிவீரன் வீரசங்குடை  
யான் சோழராஜா அழகய்யருக்கு அக்ர[ஹ\*]ரம் பண்ணார்.  
ரத கஜ தூக பதாதியுடைய ராயர் அழகய்யர் அக்ர[ஹ\*]ரத்  
தை அழிச்சு கொளம் பறிச்சு பஞ்சவார்ண நாடு நாலாக்கி மன்  
னவெட்டாக்கினென்<sup>4</sup>. பிரதிநாம வடக்கு நிருதி திக்கு கொள  
கொநெரி மத்தவராய கொத்திரம் கழிவு கொணம்-வ. கூயச-  
லடி கொலால் குழி சூருய மன்னவெட்டுக்கு செல்லு. கொள  
கொனெரி முத்திரை கல்லுயிருக்குது. அக்ரார முத்திரை[யி\*]  
ருக்குது. தாம்ர சாசன படிக்கு சூர்யசந்த்ராதி வரைக்கும்  
பூமியும் புல்லுமுள்ளமட்டுக்கும் அனுபவித்துக் கொள்ளவும்.  
யிதுக்கு கொட்டையான் குடித்தபொன் ஈடுய. யிது முதல(ண)  
[ணி] நரஸிம்ஹாசாரி சொஸ்தலிகிதம்<sup>5</sup>.

சாசனம்—1275]

[D. 2944-9

Record dated in the Kali year 4190, corresponding to Śaka 1011, Manmatha, Sittirai 22. It states that in the *Chaturveda-bhūmi-bhāvana* of the *Tonḍaimaṇḍalam* on the eastern side of *Kāñchimaṇḍalam*

1. 'செல்' என்பதே இவ்விதம் எழுதப்பட்டிருக்கிறது.
2. 'பூமி பவனத்தில்' என்று வாசிக்க.
3. 'அரண்யபுர ஸ்தலத்துக்கு' என வாசிக்க.
4. 'மன்னவெட்டு' என்பது காடு கொன்று நாடாக்குவதைக் குறிக்கும்.
5. 'ஸ்வஹஸ்த லிகிதம்' என்று வாசிக்க.

இது சென்னை சர்க்கார் பொருட்காட்சிச் சாலையின் செப்பேட்டுச் சாசனங்களின் அட்டவணையில் சோழர் எண் 6-ஆகப் பதிவு செய்யப் பட்டிருக்கிறது.



**Cholaraja Vira Sangudaiyan** (here written by mistake as Vira Gaṅgudaiyan) gave an *agrahāra* to Aḷagayyar in the Pañchanada-sthala in Kōnai-Kōṭṭam to the north of the Aranyapura-sthala to the west of the Aranya river. Rāyar who was possessed of the four divisions, *viz.*, the chariots, the elephants, the horses and the infantry, of the army destroyed the *agrahāra* of Aḷagayyar, dug a tank and divided the Pañchavarṇa-naḍu into four divisions for forest-clearing. The portion allotted to (Uḍaiyān) Kumpan Vanniya-rāyan comprised 7500 *kulī* measured with the rod of 64 feet and the gold paid by Kōṭṭaiyan was one thousand *pon*. It is also stated that on the south-west direction of it there was 1625 *kulī* measured with the rod of 64 feet (belonging to) Veḷḷuḍaiyān Vanniyarāya-gōṭran, 2000 *kulī* (belonging to) Krishṇavēḍu Vanniyarāya-gōṭran to the east of it, 3200 *kulī* (belonging to) Geputi Vanniyarāya-gōṭran to the east of it, and another 3200 *kulī* (belonging to) Tiruveṅḡḍaiyān Vannarāya-gōṭran to the east of it, all these *kulīs* being measured with the rod of 64 feet. The *agrahāra* was called Ponnagiri for which *mudrā* stones were said to exist, It is signed at the end by Narasimbāchāri in his own hand as of the third sector.

This is registered as **Cholas No. 11** in the *Catalogue of the Copper-plate grants of the Madras Government Museum*.

[Vide also the remarks under No. 1274 above]

ராஜேலில்லா என்ற பாரதீக எழுத்து கொண்ட முத்திரை

கயிபுமாதுடி (ஸ்) சதாசுடு பராதிவாஹந பவாஸு: (ஸ்) துடுக  
பெரு உதய (ஸ்) விதினெர ஜாஸம் ௨௮௨ உ தெஜி. காஹிணு  
துக் சிழ்கு தொணணுடி அதுவெஃதஹுதி ஹவநதில் திகு  
அ-க்கு கொண்டு டு. கழிவு கொண்டு...<sup>1</sup> சுருணிய நதிகு<sup>[\*]</sup>கு  
கெக்-ஹுருணியபுரஹுட[து\*]கு வடகு கொடுத்த கொட்ட  
வஹி நதி ஹுதினெ விராஜிவிராஜ விரமம்[செ]யவநு  
பொழராஜா சமகயுருக் சுமுராடி வணார[\*\*] ரய மஜ  
தாரம வஜாஜி யுயவநு ராய[ர\*] சமகயுர[\*\*]கமுராநெ  
சுழிது கொண்டு பரிது வதுணைநாடு நானாதி ஹவெட்டா  
நெநு. ஹவெட்டாசுக் உயெயாநு கும்பநு வஹிராயநெநு

வொ[ஈ\*] கூடாத்தெது. கழிவுகொண[ஈ] வ. கூடுச - றுடி கொறூல்  
கூழி எதூறா உறவெட்டாக்கூ உறெ. யிதூக்கூ நிரித திக்கு வெஹூ  
பெடியாநு வஹியராய கொதிராநு கூழி கூடுச - றுடி கொலா[ஈ\*]  
கூழி தூகூஉட்டு || யிதூக்கூ சிழக்கூ கரஹ்வெடு வஹியராய  
கொதிராநு கூழி கூடுச - றுடி கொறூல் கூழி உதூ || யிதூக்கூ சிழக்கூ  
மெவாடி வஹியராய கொதிராநு கூழி கூடுச - றுடி கொலா[ஈ\*]  
கூழி கூதூஉ || யிதூக்கூ சிழக்கூ திராவெங்குபெடியாநு வஹியராய  
கொதிராநு கூழி கூடுச - றுடி கொறூல் உதூறா || உறவெட்டாக்கூ  
உறெவாடி கூடவாழிதி பொஹ்சிரி சுமார உதூறெக்கூ யிரா  
கூதூ || தாவரஹாஹநவாடிக்கூ ஹியாழிஹாநாழி வறெக்கூ  
ஹியாழி வறெக்கூ உறெக்கூ உறெக்கூ. சுநாவஹிவாழி. வஹவஹ  
நாடூ நாறெக்கூ கொட்டாநு கூடாத்த வொநு தூ || உணாவதூ  
சுணி நாவஹிஹாஹாநி வஹவஹ யிசுதூ.

எக்கோடி அப்பாஜி என்று தெலுங்கில் எழுதப்பெற்ற முத்திரை

இதன் தமிழ் வடிவம் :

கலியுகாத்தம்<sup>1</sup> னு சதூகயி. சாலிவாஹந சகாப்த : னு  
கூடுச-செல் மன்மத னு சித்திரைமாஸம் உயெ வதெதி. காஞ்சி  
மண்டலத்துக்கு கிழக்கு தொண்[ஈ\*]ட மண்டலம் சதூர்வேத  
பூமி பவரத்தில் திக்கு-அ-க்கு கொணம் யகூ. கழிவு கொணம்  
.....<sup>2</sup> அருண்யபுர<sup>3</sup> ஸ்தல[த்து\*]  
க்கு வடக்கு கொணை கொட்டம் பஞ்சநதி ஸ்தலத்திலெ வீராதி  
வீரன் வீரங்கு[ஈ\*]டயான்<sup>4</sup> சோழ ராஜா அழகய்யருக்கு  
அக்ர[ஹ\*]ராம் பண்ணார். ரத கஜ தூரக பதாதி யு[ஈ\*]டய  
வன் ராய[ஈ\*] அழகய்யர் அக்ர[ஹ\*]ரத்தை அழிச்சு கொளம்  
பரிச்சு பச்சவாண்ண நாடு<sup>5</sup> நாலாக்கி மன்னவெட்டாக்கிரென்.  
மன்னவெட்டுக்கு உடையான் கும்பன் வன்னியராயநென்று

1. 'கலியுகாத்தம்' என வாசிக்க.

2. 'கழிவு கொணம் க' என்று பூர்த்தி செய்யவேண்டும்.

3. 'அருண்ய புர' என வாசிக்க.

4. 'வீரங்குடையான்' என்று வாசிக்க.

5. 'பஞ்சவாண நாடு' என்று வாசிக்க.

பெர் குடுத்தென். கழிவு கொணம்-வ. கூயச-லடி கொலால் குழி எசுநூ மன்னவெட்டுக்கு செல். யிதுக்கு நிருதி திக்கு வெள்ளுடையான் வன்னியராய கொத்திரன் குழி கூயச-லடி கொலால் குழி சூகூஉயடு. யிதுக்கு கிழக்கு கிருஷ்ணவெடு வன்னியராய கொத்திரன் குழி கூயச-லடி கொலால் குழி உசு. யிதுக்கு கிழக்கு கெபுட வன்னியராய கொத்திரன் குழி கூயச-லடி கொலால் குழி கூசூஉ. யிதுக்கு கிழக்கு திருவெங்குடையான் வன்னராய<sup>1</sup> கொத்திரன் குழி கூயச-லடி கொலால் உசுநூ. மன்னவெட்டுக்கு செல்லுபடி அளவு மிதி பொன்ன கிரி அக்ர[ஹ\*]ரர முத்திரைக்கல் யிருக்குது. தாம்பர சாசன படிக்கு சூர்ய சந்திராதி வரைக்கும் பூமியும் புல்லும் உள்ள மட்டுக்கும் அனுபவிக்கவும். பஞ்சவாண் நாட்டு நாலுக்கும் கொட்ட[ை\*]டயான் குடுத்த பொன் சூ. மூணுவது அணி நரஸிம்ஹாசாரி ஸ்வஹஸ்த லிகிதம்.<sup>2</sup>

சாசனம்—1276]

[D. 2944-10

Record dated in the Kali year 4190, corresponding to Śaka 1011, Manmatha, Sittirai 22. It states that in the *Chaturveda bhūmi bhavana* of the Tonḍaimaṇḍalam on the eastern side of Kañchīmaṇḍalam, **Cholaraja Vira Sankhudaiyavan** gave an *agrahāra* to Aḷagayyar in the Pañchanada-sthala in Kōnai-Kōṭṭam to the north of the Haruṇyapura [i.e., Aranyapura] sthala to the west of the Aranya river. Rāyar who was possessed of the four divisions, viz, chariots, elephants, horses and the foot of the army, destroyed the *agrahāra* of Aḷagayyar, dug a tank and divided the Panchavarṇa-naḍu into four divisions for forest-clearing. The portion allowed to Tuḷuva Ponnagiri Pal[la\*]va-rāyan comprised 4750 *kuli* measured with the rod of 64 feet and the gold paid by Kōṭṭaiyān was one thousand *pon*.

It is also stated that in the south-east (*agni*) direction, there was 3050 *kuli* of land (belonging to) Vempurattān Velikaraya-gōṭṭan and 6000 *kuli* of land (belonging to) Siyyalapurattān Sivarāya-

1. 'வன்னியராய' என்றே இருத்தல் வேண்டும் போலும்.

2. இது சென்னை சர்க்கார் பொருட்காட்சிச் சாலையின் செட்பேட்டுச் சாசனங்களின் அட்டவணையில் சோழர்கள் எண் 11-ஆகக் கொடுக்கப்பட்டுள்ளது.



கழிவு கொணம் க. அருண்ய நதிக்கு மெற்க்கு ஹருண்ய புர<sup>1</sup> ஸ்தளத்துக்கு வடக்கு கொறை கொட்டம் பஞ்சநதி ஸ்தளத் திலே வீராதி வீரன் வீர சங்[\*]த[ஐ\*]டயவன் சோழராஜா அழகய்யருக்கு அக்ர[ஹ\*]ரம் பண்ணார். ரத கஜ தூரக பதா தியு[ஐ\*]டயவன் ராயர் அக்ர[ஹ\*]ரத்தை அழிச்ச கொளம் பரிச்ச பஞ்ச வர்ண நாட்டு நாலாக்கி மன்னவெட்டாக்கிறென். மன்னவெட்டுக்கு துளுவ பொன்னகிரி பல்வராய<sup>2</sup> னென்று பெர் குறித்தேன். கழிவு கொணம்-வ சுயச-லடி கொலால் குழி சுசுநாருய. மன்னவெட்டுக்கு செல்பாதுக்கு அக்ரி திக்கு வெம்புரத்தான் வெளிகராய கொத்ரன் குழி சுயச-லடி கொலால் குழி சுசுநாருய. யிதுக்கு யீசான்ய திக்கு சிய் யாலபுரத்தான் [சி]வராய கொத்ரன் குழி சுயச-லடி கொலால் குழி சுசு. மன்னவெட்டுக்கு செல்லும்படி அக்ர[ஹ\*]ர முத்தி [ஐ\*]ர க[ல்]யிருக்குது. தாம்ரசாசனபடிக்கி ஸூர்ய சந்த்ராதி வரைக்கும் பூமியும் பில்லும் உள்ளமட்டுக்கும் அனுபவிக்கவும். பஞ்சவர்ண நாட்டு நாலுக்கும் கொட்டையான் குறித்த பொன் ஸு. நாலாவது அணி நரஸிம்ஹாசாரி ஸ்வஹஸ்த லிகிதம்.\*

சாசனம் — 1277]

[D. 2944-11

Record dated in the Kali year 4190, corresponding to Śaka 1011, Manmatha, Sittirai 22. It states that in the *Chaturvēda-bhūmi bhavana* of the Tonḍaimaṇḍalam on the eastern side of the Kāñchīmaṇḍalam Cholaraja Vira Sangudaiyan gave an *agrahāra* to Aḷagayyar in the Pañchanada-sthala in Kōnai-Kōṭṭam to the north of the Aranya-pura stala to the west of the Aranya river. Rāyar who possessed the four divisions, viz., chariots, elephants, horses and infantry, of the army destroyed the *agrahāra* of Aḷagayyar, dug a tank and divided the Pañchavarṇa-nāḍu into four divisions for forest-clearing.

1. 'அரண்ய புர' என்று வாசிக்க.

2. 'பல்லவராயன்' என்று வாசிக்க.

3. இது சென்னை சர்க்கார் பொருட்காட்சிச் சாலையின் செப்பேட் டீச்சாசனங்களின் அட்டவணையில் சோழர்கள் எண் 8(?) -ஆகக் கொடுக்கப் பட்டுள்ளது.

The portion allotted to Periyaṇiyan Periya Kamaṇi Bhūmi-pālakan Perumalaiyan of Periyavarāya-gōtra named it as Tuḷuvai, and contained 6000 *kūḷi* measured with the rod of 64 feet.

After this, the document contains a diagram showing the details of the lands as also the boundaries. Mannamaṇṇaṅgan Mannavēḍu lies to the east, Voḍayān Kumban Vanniyan Mannavēḍu to the south, Ve[\*]ḷuḍaiyān Vanniyan Mannavēḍu to the south-west, Yeluppōḍu Agrahāram to the west and Periya Kōṇēri Mannavēḍu to the north of it. The area of 6000 *kūḷi* seems to have been further divided into 4 portions of six *geḍis* each of 1500 *kūḷi*. The concluding portion of the deed contains the signature of Narasimbāchāri. The gold paid by Kōṭṭaiyān was 500 *pon* in two counts of 250 *pon* each.

This has been registered as Cholas No. 7 in the *Catalogue of the Copper-plate grants in the Madras Government Museum*.

[Vide also the remarks under No. 1274 above.]

ராஜேலில்லா என்ற பாரதீக எழுத்துகொண்ட முத்திரை

கனியுமாணுக்கு வரூஷம் சதா கய ராஜிவாஹந ரகாஷ: ஹி  
தமிக-கூ தெயு உதய ஹி விதினெர லாஸ்டு உயெ வ தெதி.  
காணி ண்ணுடி அதுரவெடிஹுதி ஹவநதில் திகூ அ.  
கொண்டி மக. கழிவு கொண[டி\*] உ சரணு வுரவநு  
திகூ கெகூ சரணுவு[\*ர]வநுதூகூ வடகூ கொடு[கெ\*]ந  
கொடும் வநநதிலி ஹநதிறெ வீராஜிவிரநு வீர[\*]ர[டி\*]மா  
பயவநு ரொழராஜா சமகயுரகூ சும[ஹ\*]ரநு வணர.  
நடி மஜ துரம வஜாதியவபயவர சுமாராதெ சுழிலு  
கொடும் வரிது வநவரணு நாடும் நாராகி ஹவெடும் சூகூ  
நெநு. ஹவெடும் துடும்வெ யெணும் வெரியணியாநு  
வெரியகாணி ஹுதிவாநுநு வெரூவெநுயாநு வெரியவராய  
கொ[\*]திரகெணும் வெரகூயுதெநு. கழுவகொண்டி வ. கயச.  
நுடி கொறூல் கழி சுத ஹவெடும் தெயுடிபி. சுமாராஹாநு  
லாபவிய ச-கூ [கெகூ தெநுகெகூ தெரகூ தெநுகெ[ர]  
கூ கெரகூ வவகெரகூ வடகூ வகிழகூ சூக டகூ அ-கூ  
நுவகொண்டு சுமெயி உயச. மெயி-கூ கழி உரூடு - ஷ

கொழகம் ஊணெழு  
மநு ஊணெழு

யீஸாநதநு வபகெழகம்	யிநிரநு கிழகம்	கூழி தெநுகிழகம்
கூஹெரநு வபகம்	இம்மம்	யெநு தெரகம்
வாயு வபகெரகம்	வாணநு கெரகம்	நிராதி தெநுகெரகம்

கெழகம் மெயி கூ-க்கு கூழி தூநா

வபகம் மெயி  
கூ-ககம் கூழி  
தூநா


ந நுகி தெரக[ா\*]  
மெயி கூ-ககம் கூழி  
தூநா

கெரகம் மெயி கூ-ககம் கூழி தூநா

ஊணெழுக் கூ-ககம் கூழி  
தூ-ஊஸாநதநுககம்  
ஊஸாநதநுககம்  
ஊஸாநதநுககம்  
ஊஸாநதநுககம்  
ஊஸாநதநுககம்  
ஊஸாநதநுககம்  
ஊஸாநதநுககம்

கொடுத்த பொன் உருபு

சூக வொநு ரூ

கொடுத்த பொன் உருபு

வபகம் மெயி கூ-ககம் கூழி தூநா

ஊணெழுக் கூ-ககம் கூழி தூநா

இந்தச் சாசனத்தின் முடிவில் யேக்கோடி அப்பாஜி என்று தெலுங்கு எழுத்தில் உள்ள முத்திரை இருக்கிறதா, இல்லையா என்பது குறிக்கப்பெறவில்லை.

இதன் தமிழ்ப் பாடம் ;


கலியுகாந்தம் வருஷம் சதாசூய. சாலிவாஹர சகாப்தம்  
 ஸ்ரீ சூரிய-க்கு செல்லு மன்மத ஸ்ரீ சித்திரை மாஸம் உயௌ உ  
 தெதி. காஞ்சி மண்டலம் சதுர்வெத பூமி பவநத்தில் திக்கு  
 அ கொணம் ஸ. கழிவு கொணம்\*] உ<sup>1</sup> அரண்யபுர ஸ்த  
 ளத்திக்கு<sup>2</sup> மெற்கு அரண்யபு[ர\*] ஸ்தலத்துக்கு வடக்கு  
 கொறை கொட்டம் பஞ்சநதி ஸ்தலத்திலே வீராதி வீர[ன்  
 வீர\*] ச[ங்\*] கு[மை] டயவன் சோழராஜா அழகய்யர்[க்\*] கு அக்ரர்  
 ரம் பண்ணார். ரத கஜ தூரக பதாதி யளுடையவர் [ராயர்\*]  
 அக்ராரத்தை அழிச்சு கொளம் பரிச்சு பஞ்சவர்ண நாட்டு  
 நாலாக்கி மன்னவெட்டு ஆக்குநென்.<sup>3</sup> மன்னவெட்டுக்கு  
 துளுவை யெனும் பெரியணியான் பெரிய காமணி பூமி பால  
 கன் பெருமலையான் பெரியவராய கெ[ராத்\*] திரமெனும்<sup>4</sup>  
 பெர் குடுத்தென். கழுவ<sup>5</sup> கொணம்-வ. கூயச-லடி கொலால்  
 குழி கூய மன்னவெட்டுக்கு செல்லும்படி அக்ரஹாரம் மாட  
 வீதி ச-க்கு கெழக்கு தென்கெழக்கு தெற்கு தென்மெர்க்கு  
 மெர்க்கு வடமெற்கு வடக்கு வடகிழக்கு ஆக திக்கு அ. குறவ  
 கொணம் ச கெடி உயச. கெடிக்கு குழி உாருய உ.

[இதன் தொடர்ச்சியான பாடம் அடுத்தப் பக்கம் பார்க்க.]

1. 'க' என்றே இருத்தல் வேண்டும்.
2. 'அரண்ய நதிக்கு' என்று இருத்தல் வேண்டும்.
3. 'ஆக்கினென்' என வாசிக்க.
4. 'கொத்திரம் என்று' என்று வாசிக்க.
5. 'கழிவு' என வாசிக்க.



கொழுக்கு மன்ன மணங்கன் மன்னவெடு



கெழக்கு கெடி கூக்கு குழி தூறா

வடக்கு கெடி  
கூக்கு குழி  
தூறா



ந நதிகி தெற்கு  
கெடி கூக்கு  
குழி தூறா

மெற்கு கெடி கூக்கு குழி தூறா

மன்ன வெட்டுக்கு செல்லும்படி தாம்பர சாசனபடிக்கி  
சூர்ய சந்திராதித்ய வரைக்கும் பூமியும் புல்லும் உள்ளமட்டுக்  
கும் அனுபவிக்க. நரவிம்ஹாசாரி லிகிதம். யிதுக்கு கொட்  
டயான் கொடுத்த பொன் டாருய. ஆக பொன் டூா.

ராசராஜா சிவராஜா சிவராஜா சிவராஜா

தெற்கு கொட்டையான் மன்னவெடு  
வன்னியான் மன்னவெடு

யிதுக்கு தென்மேற்கு  
வெள்ளையான் வன்  
னியான் மன்னவெடு.

வடக்கு பெரிய கொடுநரி மன்னவெடும் பரதவாரோ

சாசனம்—1278]

[D. 2944-12]

Record dated in the Kali year 4190, corresponding to Śaka 1011, Manmatha, Śittirai 22. It states that in the *Chaturvēda bhūmi bhavana* of the Tonḍaimaṇḍalam on the eastern side of Kañchīmaṇḍalam, **Cholaraja Vira Sankhudaiyan** gave an *agrahāra* to Aḷagayyar in the Pañchanada-sthala in Kōnai-Kōṭṭam to the north of the Aranyapurasthala to the west of the Aranya river. Rayar who was possessed of the four divisions, viz., the chariots, the elephants, the horses and the foot of the army, destroyed the *agrahāra* of Aḷagayyar, dug a tank and divided the Panchavarṇa-naḍu into four divisions for forest-clearing.

The portion allotted was 1500 *kuli* measured of 64 feet rod and the gold paid by Kōṭṭaiyan was 130 *pon*. It is stated that it had land of Kōnai Mattavarāya-gōtran to the west of the north-east direction. It is signed at the end by Narasimhachari in his own hand (*svahastalikhitam*) as of the first sector.

This has been registered as **Cholas No. 9** in the *Catalogue of the Copper-plate grants in the Government Museum at Madras*. Therein it has been stated that this is a copy of the other copper-plate registered as **Cholas No. 6** (No. 1274 above).

[Vide also the remarks under No. 1274 above.]

ராஜேல்லலா என்ற பாரசீக எழுத்து கொண்ட முத்திரை

கயியுமாஜம் ஹி சதாசுய ஸாயிவாஹத ஸகாஷம் ஹி தயக  
க்கு லெம [ஃ\*] லநய ஹி லெமத, லாஸம் உமெ உ. காணீலெனத்த  
க்கு கிழக்கு தொண லெமத லதவெ- [ஃ\*] லுமீ வவநத்தி [ஃ\*]  
திக்கு-அ-க்கொண்டி யக கழிவு கொண்டி க- ஸதாஸுணத நதிக்கு  
லெமக்கு ஸரணலவலவ- லெமத [ஃ\*] வலகூ கொலெந கொட்டி  
வஹநதிஹி [ஃ\*] வீராதிவீராநு வீராஸம்வெலெயாநு ஸொழ  
ராஜா ஸமகயுராசு ஸமூராதி வணார். ரய மஜ தாஸ வலாதிய  
லெலயவநு ராயநு ஸமகயுரஃ ஸமூரத்தை ஸழிஷு கும்பம் பரிச்ச  
வஹவண- நாய நாயாக்கி லெலவலாக்கிமெந். பூதிநாடி யிஸா  
நதித்துகூ லெமக்கு லெமயு கொலெந லதவராப மொதிநு  
கழிவு கொண்டி-வ கழி கயிச-அடி கொலா [ஃ\*] கழி துநா.  
ஸமூர கதினெக [ஃ\*] யிருக்குதா. தாஸுலாஸநவலிககூ



சாசனம் — 1279]

[D. 2944-13]

Record dated in the Kali year 4190, corresponding to Śaka 1011, Manmatha, Śittirai 22. It states that in the *Chaturvēda-bhūmi bhavana* of the Tondaimaṇḍalam on the eastern side of the Kāñchimaṇḍalam Cholaraja Vira Sangudaiyavan gave an *agrahāra* to Aḷagayyar in the Pañchanada-sthala in Kōnai-Kōṭṭam to the north of the Araṇya-pura-stala to the west of the Araṇya river. Rāyar who possessed the four divisions, viz., chariots, elephants, horses and infantry, of the army destroyed the *agrahāra* of Aḷagayyar, dug a tank and divided the Pañchavarṇa-naḍu into four divisions for forest-clearing.

The portion allotted was 6100 *kuli* measured with the 64 feet rod and named Mannavarāya-gōtram to Tuḷuva Chinnaiyan. The grant then mentions the lands in the different directions. 2750 *kuli* of land (belonging to ?) Akkulaṭṭu Rajavar. In which direction this was situated is not given. But to the east of it lay 3500 *kuli* of Dēva-kanniyān Kanniyarāya-gōtram; 3630 *kuli* of Villuḍaiyan Vilvayarāya-gōtram to the south-east of it; 1800 *kuli* of Madiram-veṭṭān Manniyarāya-gōtram to the north of it; 2150 *kuli* of Aripurandan Ādiyarāya-gōtram to the north-east of it; 6100 *kuli* of Yerra Kōṇēri...varāya-gōtram to the west of it; 4100 *kuli* of Viramuḍaiyan Virarāya-gōtram to the north of it; 6010 *kuli* of KonaKōṇēri Mattavarāya-gōtram to the south-west of it; 4260 *kuli* of Parittipattān Tettavarāya-gōtram to the north of it; 1250 *kuli* of Uppūr Periyān Kōṭṭai Pushparishi-gōtram to the north of it; all these measurements being made with the rod of 64 feet. The amount paid by Kōṭṭaiyan for the land was 1000 *pon*. The document is signed at the end by Narasimhachari as of the first sector.

This has been registered as Cholas No. 10 in the *Catalogue of the Copper-plate grants in the Government Museum at Madras*.

[Vide also the remarks under No. 1274 above.]

ராஜேலில்லா என்ற பாரதீக எழுத்துகொண்ட முத்திரை

சுயியுமான ன்ரு சதாசுயி-பராவிலாஹந ஸகாஷு: ன்ருதிக  
பெல் உருத ன்ரு விதினெரொலாஹம் உயெ வ தி. காணி உணருதகூ  
கிழகூ தொணுணுருடி அதுவெ-ஃடி ஹுவிஹவநத்தில் திகூ அ-  
கூ கொணுடி ய[சு] கழிவு கொணுடி க சுருணய நதிகூ ரெருகூ

ஹரணஜ் வுரலுத்துக்கு வடக்கு கொடுநெ கொட்டம் வஹதஜி  
 ஹுத்துஹு வீராஜிவிரநு வீரா[ஈ\*]மொலெயவநு ரொழராஜா  
 சுழகயூர்து சுழாராஜ வணார[ஈ\*], ரடி மஜ துரம வஜாஜி  
 யுயவவநு ராயர்து சுழகயூர்து சுழாராஜெத் சுழிவா கொடும்  
 வரிவா வஹவர்து நாடும் நாராக்கி உஹவெட்டாக்கிநெநு. உஹ  
 வெட்டாக்கும் துடும் பரிஹணியாநுக்கும் உஹவராய கொத்திர  
 லெநுரம் வெர்து கும்புதெநு. சுழவு கொணடி வ. சுயச.முடி  
 கொறாநு கும்பி சுதா. உஹவெட்டாக்கும் வெல் சுதும்புடும்  
 ராஜவார்து கும்பி சுயச.முடி கொறால் கும்பி உதளாநுடி. யிதாக்கும்  
 கிழகும் தெவகஹியாநு கஹியராய கொத்திர கும்பி சுயச.முடி கொ  
 றாநு கும்பி நதகா. யிதாக்கும் சுயிதீகும் விஹுலெயவநு விஹுராய  
 கொத்திர கும்பி சுயச.முடி கொறாநு கும்பி நதகாநுடி. யிதா[கும்\*]  
 வடகும் உஜிரடி வெட்டாநு உஹிராயகொத்திர சுயச.முடி கொறால்  
 கும்பி துதா. யிதாக்கும் யீராஹஜி சுரிவ-ரஹாநு குஜியராய கொ  
 த்ரடி கும்பி சுயச.முடிகொறால் கும்பி உதளாநுடி. யிதாக்கும் லெநு  
 திக்கும் யெநு கொநெரி . . . . வராயகொத்திர கும்பி சுயச. முடி  
 கொறால் கும்பி-சுதா. யிதாக்கும் வட திதி வீரலுயவநு விரராய  
 கொத்திர கும்பி-சுயச.முடி கொறால்[ஈ\*] கும்பி சத யிதாக்கும்  
 நிரதி திக்கும் கொந கொநெர உதவராய கொத்திர கும்பி சுயச-  
 முடி கொறால் கும்பி சுதா. வடகும் வரிதிவட்டாநு தெத்தவராய  
 கொத்திர கும்பி சுயச.முடி கொறால் கும்பி சதளாசுயி. யிதாக்கும்  
 வடகும் உஹுர வெரியநு கொடுநெ வுஹி . . . கொத்திர கும்பி  
 சுயச.முடி கொறால் கும்பி துதாநுடி. உஹவெட்டாக்கும் வெஹுவடி  
 யொநு...கொநெரி கொந கொநெரி உதிரகும் ரெணு கிழகும்  
 திக்கும் யிராக்கும். சுழார உதிரகும் யிறுக்கும். தாவர  
 ராவந வடிகும் ஸுய-ஜி உஜிராஜி வரெநுக்கு ஹுலியாடி  
 வுஹுடி உஹுடாக்கும் சுநுவவிக்கவுடி. வஹவந-ஹுநாடும்  
 நாராக்கும் கொட்டாநு கும்புத் வொநு து. உதஹுணி நரவிஹா  
 அரி ஹுஹு விநிதடி [ஈ\*]

எக்கோடி அப்பாஜி என்று தெலுங்கில் எழுதப்பெற்ற முத்திரை

இதன் தமிழ் வடிவம் :

கலியுகாந்த ஸு சதாசுடி. சாலிவாஹந சகாப்தஃ ஸு  
 சூக செல்மன்மத ஸு சித்திரை மாஸம் உயஉ உதி. காஞ்சி  
 முண்டலத்துக்கு கிழக்கு தொண்டமண்டலம் சதூர்வ்வெத பூமி

பவனத்தில் திக்கு அ-க்கு கொணம் ம[சு] கழிவு கொணம்] க. அருண்ய நதிக்கு மெற்கு ஹரண்யபுர ஸ்தலத்துக்கு வடக்கு கொறை கொட்டம் பஞ்ச நதி ஸ்தலத்திலே வீராதி வீரன் வீரச[ங்\*]குடையவன் சோழராஜா அழகய்யர்க்கு அக்ராரம் பண்ணார். ரத கஜ துரக பதாதி யு[சை\*]டயவன் ராயர் அழகய்யர் அக்ராரத்தை அழிச்சு கொளம் பரிச்சு பஞ்சவர்ண நாடு நாலாக்கி மன்னவெட்டாக்கினென். மன்னவெட்டுக்கு துளுவ சின்னணியானுக்கு மன்னவராய கொத்திரம் மென்று பெர் குடுத்தென். கழுவ கொணம்-வ. கூயச-லடி கொலால் குழி கூசா மன்னவெட்டுக்கு செல். அக்குளப்பட்டு ராஜுவார் குழி கூயச-லடி கொலால் குழி உசுளாநுய. யிதுக்கு கிழக்கு தெவ கன்னியான் கன்னியராய கொத்ரம் குழி கூயச-லடி கொலால் குழி ஈசுநா. யிதுக்கு அக்னி திக்கு வில்லுடையான் வில்வராய கொத்ரம் குழி கூயச-லடி கொலால் குழி ஈசுசூகாநுய. யிது[க்கு\*] வடக்கு மதிரம் வெட்டான் மன்னியராய கொதிரன் கூயச-லடி கொலால் குழி ஈசா. யிதுக்கு யீசாந்யம் அரிபுரந்தான் ஆதிய ராய கொத்திரன் குழி கூயச-லடி கொலால் குழி உசுளாநுய. யிதுக்கு மெர்க்கு திக்கு யெர்ர கொநெரி...வராய கொத்ரன் குழி கூயச-லடி கொலால் குழி கூசா. யிதுக்கு வடதிக்கி வீரமு [சை\*]டயான் வீரராய கொத்ரின்<sup>1</sup> குழி கூயச-லடி கொலால் குழி சசு. யிதுக்கு நிரதி திக்கு கொந கொநெ[ரி]மத்தவராய கொத்ரன் குழி கூயச-லடி கொலால் குழி கூசுய. வடக்கு பரித்திப்பட்டான் தெத்தவராய கொத்ரின்<sup>1</sup> குழி கூயச-லடி கொலால் குழி சசுஉரகூய. யிதுக்கு வடக்கு உப்புர் பெரியன் கொடை புஷ பஷி<sup>2</sup> ... கொத்ரின்<sup>1</sup> குழி கூயச-லடி கொலால் குழி ஈசாநுய மன்னவெட்டுக்கு செல்லுபடியொன்.....கொநெரி கொந கொநெரி முத்தி[சை\*]ர கல்லு ரெண்டு கிழக்கு திக்குலெ யிருக்குது. அக்ரார முத்தி[சை\*]ர கல் யிறுக்குது. தாம்பர சாசனப்படிக்கு சூர்ய சந்த்ராதிவரைக்கும பூமியும் புல்லும் உள்ள மட்டுக்கும் அனுபவிக்கவும். பஞ்சவர்ண நாடு நாலாக்கும் கொட்[சை\*]டயான் குடுத்த பொன் சூ. முதலணி நரஸிம்ஹா சாரி ஸ்வஹஸ்த விசுதம்.

1. 'கொத்திரன்' என்று வாசிக்க.

2. 'புஷ்பரிஷி...கொத்திரன்' என வாசிக்க.

- இது சென்னை சர்க்கார் பொருட்காட்சிச் சாலையின் சேப்பேட்ச் சாசனங்களின் அட்டவணியில் சோழர்கள் எண் 10-ஆகக் கொடுக்கப்பட்டுள்ளது.

காஞ்சீபுரம்

Kāñchīpuram

The following eighteen pieces are found copied in the original manuscript in continuatoin of the inscriptions from S'riperumbūdūr and followed by another inscription from Kāñchīpuram. The exact place wherefrom these were copied is not stated. It is not also known whether these are inscriptions copied from stone or they only record particulars regarding the *Ālvārs* and *Āchāryas* of the Vaishṇava faith. But as these are preceded and followed by copies of inscriptions, these also are probably copies of inscriptions. If so, they should have been copied either from S'riperumbūdūr or Kāñchīpuram, mostly probaly from the latter place.

The *ślōkas* given in the following are traditional ones known as *avatāraślōkas* and are also found included in the Vaishṇava work called *Jayantimālā*. These are also included in the *Guruparamparā-prabhāvam* known as *Ārāyirappaḍi* by Pinpaḷagiya-perumaḷ Jīyar.

These particulars are found here for ten *ālvārs*. The *Nālāyira-Divyaprabandha* of the Vaishṇavas contains the compositions of twelve persons who are generally called *ālvārs*. But two of them, Āṇḍal and Madhurakavi, are not included in the list of *ālvārs*. The former is classed with the goddess (*pīrāṭṭiyār*) while the latter is classed with the *āchāryas*. Thus only ten is the total number of the *ālvārs* and it is this figure we find in inscriptions also. But here the particulars of Āṇḍal and Madhurakavi are found. Instead, the names of Tiruppāṇālvār and Tirumaṅgai-mannan are left out. The omission is evidently a scribal error.

பின் வரும் பதினெட்டும் மூலப் புத்தகத்திலே ஸ்ரீபெரும்புதூர்க் கல் வெட்டுக்களைத் தொடர்ந்து எழுதப்பட்டுள்ளன. இவற்றுக்குப் பின்னால் காஞ்சீபுரத்துச் சாசனம் ஒன்று இருக்கிறது. எனினும், இவை எந்த இடத்திலிருந்து பிரதிசெய்யப்பட்டவை என்பது குறிப்பிடப்பெறவில்லை. உண்மையில் இவை கல்வெட்டுக்களின் பிரதிகளா அல்லது வைஷ்ணவர்களின் ஆழ்வார், ஆசாரியர்களைப்பற்றிய சம்பிரதாயமான செய்திகளைத் தெரிவிப்பதாக எழுதப்பட்டனவா என்பதே தெரியவில்லை. ஆயினும் முன்னும் பின்னும்

சாசனங்களைக் கொண்டு காணப்படுவதால் இந்தப் பகுதியும் சாசனங்களின் பிரதியாக இருத்தல் வேண்டும் போலும். அவ்விதமாயின், இவை ஸ்ரீபெரும் பூதூரிலிருந்தோ காஞ்சீபுரத்திலிருந்தோ பிரதி செய்யப்பெற்றிருத்தல்வேண்டும். பெரும்பாலும் காஞ்சீபுரத்திலிருந்தே பிரதி செய்யப்பட்டன போலும்.

ஆழ்வாராதியரின் அவதார விவரங்களைத் தெரிவிக்கும் இந்தச் சுலோகங்கள் அவதார சுலோகங்கள் என்று சம்பிரதாயமாக வழக்கில் உள்ளவை. ஜயந்தி மாலா என்ற பெயரில் தொகுப்பாகவும் உள்ளன. இன்னும், பின் பழகிய பெருமாள் ஜீயர் இயற்றிய ஆறாயிரப்படி குருபரம்பரா பரபாவத்திலும் காணப்படுகின்றன.

இவ்விடத்திலே பத்து ஆழ்வார்களைப் பற்றிய விவரங்களே காணப்படுகின்றன. நாலாயிர திவ்யப் பிரபந்தத்திலே பன்னிரண்டு பேர்களுடைய பாசுரங்கள் அடங்கியுள்ளன. அந்தப் பன்னிரண்டு பேர்களையும் ஆழ்வார்கள் என்று பொதுவாகக் கொள்வர். எனினும், ஆண்டாளையும் மதுரகவியாரையும் ஆழ்வார்கள் வரிசையிலே சேர்க்காமல் பதின்மரே ஆழ்வார் என்பது சம்பிரதாயம். சாசனங்களிலும் 'ஆழ்வார் பதின்மர்' என்ற வழக்கே காணப்படுகிறது. ஆண்டாளைப் பிராட்டியாராகவும் மதுரகவியாரை ஆசாரிய வரிசையிலும் சேர்ப்பர். ஆனால் இவ்விடத்திலே இவ்விருவரைப்பற்றிய விவரங்கள் காணப்படுகின்றன; பதிலாக, திருப்பாணாழ்வார் திருமங்கை மன்னன் ஆகிய இருவரைப்பற்றிய விவரங்கள் இல்லை. பிரதி செய்வோர் பிழையால் நேர்ந்த தவறேபோலும்.

சாசனம் — 1280]

[ D. 3302-V-11 ஈயகூ

This record states that Poygaiyar was born (or rather appeared, not born from the womb) in the *saras* (tank-poygai) at Tirvāṇkā in Kañchīpuram on a day corresponding to Dvāpara (*yuga*) year 862900 (expired), Siddhārthi, Aippaṣi, Su. aṣṭami, Tuesday and Śravaṇa as a manifestation of *Pāñchajanya*, i.e., the sacred *śankha* of Viṣṇu. The Dvāpara year would be B. C. 4202.

### பொய்கையாழ்வார் திருவவதாரம்

ஐாவர யுமத்தில் அ லட்சத்து சுயஉகூகா-க்கு மெல் லிவாதி-3 ஸம்வச்சரத்து அற்ப்பசி மாசத்தில் ஸுக்ஷவகூதம் அஷ்டி செவ்வாய்க்கிழமை திருவொண நகூத்திறத்தில் காணீ வுரத்தில் திருவெகூகாவில் பொய்கை யென்கிற ஸரஸில்



சுயொநிஜரூய் ஸ்ரீவாணஜந்ராஸமாய் பெய்கை ஆழ்வார்  
அவதரித்தார்.

சூஜாயி ஸ்ரீஸூநெ<sup>1</sup> ஊவராபெய்  
லிபாசு-காவெய் வஸரெ லாலி லெவெஷ |  
ஸூகூஷஜோ ஹலவாரெ ஸூஹகேஷ-  
விஷ்ணுஜ-நு பூவ காலாரயொழி ||

சாசனம் — 1281]

[D. 3302-V-நாநுக(க)

This record states that Bhutattalvar was born in the flower *Sugandi* at Tirukkāḍalmallai (i.e., Māmallapuram) on the day corresponding to the Dvāpara year 862900 (expired), Siddhantthi, Aippaṣi-  
Śu. navami, Wednesday and Śravishṭa, (i.e., the day next to that on which Poygaiyar appeared) as a manifestation of *Kaumōḍaki*, i.e., the mace of Vishṇu.

பூதத்தாழ்வார் திருவவதாரம்

ஊவர யுமத்தில் அ லகைத்து சுடெககா-க்கு மெல்  
லிபாசு-காவெய் ஸ்வசரசரத்தில் அற்ப்பசி மாசத்தில் ஸூகூவகை  
நவமி புதன்க்கிழமை அவிட்ட நட்சத்திரத்தில் திருக்கடல்  
ம[ல்\*]லையில் திரு சுகந்தி புஜித்திலெ ஸ்ரீ கௌலொடிகி ஸுஸ  
ரூய் பூதத்தாழ்வார் அவதரித்தார்.

லாவெய தலிநு [வ]ஸூலெவ தீண-கோ<sup>2</sup>  
வாரெஸெகூ வு-ரி உயூ<sup>3</sup> நாதஜோ |  
யுதாமுஹானாக ஹுவி ஹுதநாஜ  
கௌலொடிகி ஸூகூயொ[ல்\*]நீரு<sup>3</sup> ||

சாசனம் — 1282]

[D. 3302-V-நாசய]

This record states that Peyalvar was born in the water-lily (*alli*) flower in the sacred well in the temple of Ādikēśava-p-perumāḷ

1. சம்பிரதாயமான பாடத்திலே 'ஸ்ரீ அநுநெ' என்றே காணப் படுகிறது.

2. 'வஸூலெவஜரிஷ' என்பது சம்பிரதாயமான பாடம்.

3. 'பு-ரி ஸூ' என்ற பாடம் வழக்கில் உள்ளது.

at Mayilappūr (in Madras) on a day corresponding to the Dvāpara year 862900 (expired), Siddhārtthi, Aippaśi, Śu. ēkadaśi, Thursday and Satabishaj (i.e., the day next to that of the birth of Bhūtāt-tālvār) as the manifestation of Śrī-nandaka, i.e., the sword of Viṣṇu.

### பெயாழ்வார் திருவவதாரம்

ஶ்ரீவர யு.மத்தில் அ லக்ஷத்து கூடெககா-க்கு மெல் லிவாதி-3 ஸம்வச்சரத்தில் அற்ப்பசி மாசத்தில் ஸுக்ஷவக்ஷ ஷேஸி லஜாமுக்கிழமை சதைய னட்சத்தி[ரத்தி\*]ல் மயிலாப் பூரிலெ ஸூரிகேசவப் பெருமாள் கொவில் திருக்கிணத்திலெ அல்லிப்பூவிலெ ஸ்ரீ நடகாம்பரராஜி பெயாழ்வார் அவதரிச் சார். உ

தநாவி ஜாத<sup>1</sup>ஸுதநாகாயா

உயுரவாரயுஜா<sup>2</sup> லணிகெரவானாகி |

ஹஜா<sup>3</sup>ஹஜா<sup>4</sup> ஹஜா<sup>5</sup>

ஸ்ரீநடகா<sup>6</sup> ஸ்ரீஹஜா<sup>7</sup> ||

சாசனம் — 1283]

[D. 3302-v-நாசமக

This record states that Tirumalisaippiran was born in a Brāhmaṇa family at Tirumaliśai on a day corresponding to the Dvāpara year 862900, Siddhārtthi (the same year in which the first three ālvārs were born), Tai, Sunday and Makhā as a manifestation of Sudarśana (i.e., the discus-chakra) of Viṣṇu and brought up in a family of the fourth class (chaturthavarṇa).

The *tithi* ba. prathamā seems to have been left out.

### திருமுழிசைப்பிரான் திருவவதாரம்

ஶ்ரீவர யு.மத்தில் அ லக்ஷத்து கூடெககா-க்கு மெல் லிவாதி-3 ஸம்வச்சரத்து தை மாசத்தில் ஓயற்றுக் கிழமையும்

1. சம்பிரதாயமான பாடம் 'ஜாதம்' என்பதாகும்.
2. 'ஹஜா' என்ற பாடம் வழக்கில் உள்ளது.
3. 'ஹஜாஹயஜா' என்று வழக்கில் உள்ளது.
4. 'காம்பரம்' எனவும் காணப்படுகிறது.
5. 'ஸூவாடி' என்பது வேறு பாடம்.

உவா நகரத்திறத்தில் திருமெழிசையிலே ஸுஷஸ்திநாஸராய்ப்  
பிரமண வற்றணமாயி அவதரிச்சு பின்பு அதே வணத்  
திலே வள[ர்\*]ந்தார். <sup>1</sup>

ஸிகாதி-நுஷஸுள்ள உகரையிமத  
அவரெ ஐநாயாரா  
கெதாபெ (ஸிநு) ஸவதரளவெ மதவதி அ திநெ  
வஸ<sup>2</sup>விஸெ உவாவெ |  
நகரத்தெ ஹாநுவாரெ உநிவரததயொ  
ஹிஸாரொ உநிநு:  
ஸ்ரீநாநு ப்ராபுவாதார<sup>3</sup> ஜமகுவகரதயெ  
வவ-ஸெநாநெஷி<sup>4</sup>நாநெ<sup>5</sup> ||

சாசனம் — 1284]

[D. 3302-V-11A சமஉ

This record states that Kulasekhara-alvar was born in a *kshatriya* family in the town Kolli on a day corresponding to the Kali year 27 (expired), Parābhava, Māsi, Thursday, Śu. dvādaśi and Punarvasu as a manifestation of the *Kaustubha* of Vishṇu, i.e., the gem worn on His breast.

குலசேகராழ்வார் திருவவதாரம்

கலியுகத்தில் உமே வருஷத்துக்கு மெல் வராஹவ வறுஷத்  
தில் மாசி மாசத்திலே ஷோழக்கிழமை ஸு<sup>1</sup>வகூதம் அடிபரி  
வாநவ-ஸு நகரத்திறத்தில் கொல்லி நகரிலே க்ஷத்ரிய  
வாஸமாயி கள<sup>2</sup>ஸு<sup>3</sup>ஹாஸமாய் அவதரிச்சார்.

கருதிஸெ ஸுவஸவ்யா வதுவமத  
உவெ அ உவாவிலெ  
வவெ-அ<sup>4</sup>அ<sup>5</sup> வராஹவெ ஸு<sup>6</sup>நா<sup>7</sup>ரொ<sup>8</sup>  
வ-ஹெ அ வகூத ஸு<sup>9</sup>அ<sup>10</sup> ||

1. 'கிருஷ்ணபகூத்துப் பிரதமை' என்ற திதி விட்டுப்போயி  
ருக்கிறது.

2. 'ஸவ' என்று வாசிக்க.

3. 'ப்ராவாவதாரம்' என்ற பாடமும் உண்டு.

4. 'ஷிநு' என்றும் பாடம்.

5. சம்பிரதாயமான பாடத்தில் 'அவி' என்று காணப்படு  
கிறது.

அாடிஸ்தாவத்யுதியன் வுநவ-ஸுஸுதிநெ  
 ஸ்ரீதூவத்யொமாமிநெ  
 சூரதம் நஃ கும்புஸெவரகூதிவிவதி  
 ஸ்ரீகள் ஸுஹாதா[ஹ\*]வக் ||

சாசனம் — 1285]

[D. 3302-v-ஈசுமந

It is stated that **Periyalvar** (otherwise known as Vishnu-chitta) was born in a Śōḷiraya brāhmaṇa family at Śrīvilliputtūr on the day corresponding to Kali year 46 (expired), Krōḍhana, Āni, Śu. ēkadaśi, Sunday and Svāti as an incarnation of Garuḍa.

## பெரியாழ்வார் திருவவதாரம்

கலியுகத்தில் சடுக வறுஷத்துக்கு மெல் குறெதன வறு  
 ஷத்தில் ஆனி மாசத்தில் ஸுக்ஷ வகஷ வாகாடிஸி நாயற்றுக்  
 கிழமை ஸூரதீ நட்சத்திரத்தில் ஸ்ரீவில்லிபுத்தூரிலெ சொழி  
 ருய ஸு[ர\*]ஜீண வண-தத்திலெ ஸ்ரீமெரு-பாஸராய் பெரியாழ்  
 வார் அவதரிச்சார்.

ததாஸாவமதெ கருள் யுமவரெ  
 ஸ்வவதரெ கெடாயநெ  
 அணாஸரன் திமும்மதெஹி நவதெ  
 வகெஷ வளகெஷ-வி அ |  
 ஸூரதூம் ஹாஸூரவாஸரெ ஸுஹதியா .  
 வெகாடிஸி நாடிநி  
 ஸ்ரீதாநாவிசுஹதி தினூஜஹிதா  
 ஸ்ரீவிஷ்ணுவிதேநவஃ ||

சாசனம் — 1286]

[D. 3302-v-ஈசுமச

The inscription states that **Andal**, familiarly known as Śūḍik-koḍutta-Nāchchiyar and the daughter of Vishnuchitta or Periyālvār, was born at Śrīvilliputtūr on the 6th day of the month Āḍi, having Chaturthi, Tuesday and Pūram (i.e., Pūrva phalguna), in the cylic year Nāḷa, Kali 97 (expired), from the earth in the *tulasī* flower-garden as an incarnation of Bhūmi-p-piraṣṭiyar, i.e., Bhūdēvī.

The *paksha* śu. has been left out.

**குடிக்குடுத்த நாச்சியார் திருவவதாரம்**

கலியுகத்தில் வறுஷம் கூடு-க்கு மெல் நள வறுஷத்தில்  
ஆடி மாசத்தில் சு உ அது<sup>1</sup> செவ்வாய்க்கிழமை பூர நட்சத்  
திரத்தில் ஸ்ரீ வில்லிபுத்தூரிலே சூனஸீ நடுநவநத்தில் ஹமி  
யிலெ பூமி அங்கிசமாயி குடிக்குடுத்த னாச்சியார் அவதரிச்சார்.

லீகாநாம் ஸாடிம் கருவவமமே  
வஷெ<sup>2</sup>நடாபெய் ராவள  
யாதெ க<sup>3</sup>கூ<sup>4</sup>டகம் வியாவாவலிதெ  
ஷெ<sup>5</sup>ஹநி ஸ்ரீ<sup>6</sup>தி |  
நக<sup>7</sup>செ<sup>8</sup>ய ப<sup>9</sup>ஷெ<sup>10</sup>வதெ கூ<sup>11</sup>தி<sup>12</sup>ஹ<sup>13</sup>வொ  
வாரெ அது<sup>14</sup>சூ<sup>15</sup>தோம் தியள  
மொ<sup>16</sup>டி<sup>17</sup> வா<sup>18</sup>டி<sup>19</sup>ர<sup>20</sup>ஹ<sup>21</sup>டி<sup>22</sup>வி<sup>23</sup>ஹ<sup>24</sup>டி<sup>25</sup> லஹி<sup>26</sup>ர  
ஸ்ரீ வி<sup>27</sup>ஷ<sup>28</sup>வி<sup>29</sup>தூ<sup>30</sup>ஜா ||

சாசனம் — 1287]

[D. 3302-v-நாசயடு

Saint Tondaradippodi-y-alvar, states this record, was born in a *brāhmaṇa* family at Tirumaṇḍanguḍi village as an incarnation of *Vaiṣṇanti-Vanamālā*, i.e., the garland of Vishṇu on Tuesday having Jyēshṭhā, ba. chaturdaśī, in the month of Mārgaḷi of the cyclic year Prabhava, corresponding to the Kali year 283 (expired).

**தொண்டரடிப் [செ\*]ப[ர\*]டியாழ்வார் திருவவதாரம்**

கலியுகத்தில் லா<sup>1</sup>அ<sup>2</sup>அ<sup>3</sup>க்கு மெல் பூ<sup>4</sup>ஹவ வருஷத்து  
மார்கழி மாதத்தில் கூ<sup>5</sup>ஷ<sup>6</sup>வ<sup>7</sup>கூ<sup>8</sup>த்தில் அது<sup>9</sup>சூ<sup>10</sup>சி செவ்வாய்க்  
கிழமை கெட்டை நக<sup>11</sup>செ<sup>12</sup>த்தில் திருமண்டங்குடியிலெ  
பூ<sup>13</sup>ரா<sup>14</sup>ஹி<sup>15</sup>ண வண<sup>16</sup>த்திலெ வெ<sup>17</sup>ஜ<sup>18</sup>ய<sup>19</sup>ணி<sup>20</sup>வ<sup>21</sup>ந<sup>22</sup>மா<sup>23</sup>லை அம்சராய் அவ  
தரித்தார்.

ஷெ<sup>24</sup>ஹ<sup>25</sup>ஸ்ரீ ஸா<sup>26</sup>டி<sup>27</sup>த<sup>28</sup>ரெ பூ<sup>29</sup>ஹவநா-  
கூ<sup>30</sup>ஷ<sup>31</sup>வ<sup>32</sup>கூ<sup>33</sup> ஹ<sup>34</sup>வ<sup>35</sup>ஸ<sup>36</sup>ரெ  
வா<sup>37</sup>ப<sup>38</sup>மா<sup>39</sup>ஹி<sup>40</sup>ணி ஹ<sup>41</sup>லி<sup>42</sup> ஸ<sup>43</sup>உ<sup>44</sup>ந<sup>45</sup>டி<sup>46</sup>வ<sup>47</sup>ஸெ  
ஜெ<sup>48</sup>ஷ<sup>49</sup>ஹி<sup>50</sup>யெ ஸ்ரீ<sup>51</sup>தி |

1. 'சுக்லபகூத்து' என்பது விட்டுப்போயிருக்கிறது.

ஐக்கை கரண உதாதி-ஸீதியியுதெ  
 ஹதாஹி-ரெணுஸுயீ  
 நம்மெஸாஹி-ஸரொர-நெஹகஹுதய:  
 வாவாவதாரம் ஹுளி ||

சாசனம் — 1288]

[D. 3302-v-ராசவக

**Nammalvar** was born in the fourth caste (*chaturthavarna*) at Tirukkurugūr on the forty-third day (of the first year) of the Kaliyuga which corresponded with Śu. Chaturdaśi, Viśākha, Friday in the month of Vaikāśi of the cyclic year Bahudānya, as an incarnation of Sēnai Mudaliyar.

நம்மாழ்வார் திருவவதாரம் .

கலியுகத்தில் சமீப னாளைக்கி மெல் ஸஹயாதய வறுஷம்  
 வையாசி மீர் ஸகுவகஸம் அததி-ஸீ வெள்ளிக்கிழமை விசாகா  
 நகஷத்ரத்தில் கூடக லக்னத்தில் திருக்குருகூரிலே அததி-வண-  
 த்தில் ஸௌத முதலியார் அஸமாக நம்மாழ்வார் அவதரிச்சார்.

ஸ்ரீவிஜ்ஞானஜிநொத ரெஹநி கருள  
 வநெஷ-வகஜாஹயெ<sup>1</sup>  
 லாலெ லாயவ நாலி ஹா-த-வஜிநெ  
 ஐக்கை விஸாவாஹியெ<sup>2</sup> |  
 ருமெ [ஸுக] அததி-ஸீதியியுதெ  
 ஸ்ரீகைகூண்டெ[விஅ\*]  
 சுதிதலாம் ப்ராதி-நஹுக வராகூஸஹநி<sup>3</sup>  
 ஹ-ஸாமெஜாதயம் உநீ || <sup>4</sup>

1. 'ப்ராஜாஹயெ' என்று இருத்தல் வேண்டும்.
2. 'விஸாவாஹியெ' என்று இருத்தல் வேண்டும்.
3. ஸம்பிரதாய பாடத்தில் 'கவி' என்று காணப்படுகிறது.
4. 'ஹாமெஜாதயொஹாஜாஸாடி' என்பது வழக்கில் உள்ள பாடம். மேலேயுள்ளபடி இந்தப் பாதத்தில் எழுத்துக் குறையுள்ளது.

சாசனம் — 1289]

[D. 3302-v-11 சயன்

**Madhurakavi Alvar** was born in a *brāhmaṇa* family at Tiruk-koḷūr on the 15th day of Śittirai in the cyclic year *Isvara* being Friday, Śu. chaturthi (which is a mistake for chaturdaśi, the *tithi* according to the tradition) with the *nakshatra* Chitrā corresponding to the *Dvāparayuga* year 8,83,878 (expired), as an incarnation of Kumudagaṇēśa. The Tamil passage gives the *nakshatra* as *Krittikā* which is not in accordance with the tradition.<sup>1</sup> The *Dvāpara* year according to tradition is 8,63,878 (expired). The figure 8 in the ten-thousandth place is evidently a scribal error for 6.

1. As already stated the details of the dates of birth of Tiruppaṇāḷvar and Tirumaṅgai-mannan are not found in the collection. To have a complete account, the particulars of birth of these two *āḷvārs* as handed down traditionally are given here.

Tiruppaṇāḷvar was born on a Wednesday having *ba*, *dvitīya* and *Rōhiṇī* in the month of *Kārttigai* in the cyclic year *Darmati* corresponding to the *Kali* year 342 (expired) in the *pañchama-varṇa* (*Pāṇa-kula*) at *Uraiyūr* as a manifestation of *Śrīvatsa* of *Vishṇu* (B.C. 2779.)

Tirumaṅgai-āḷvār was born in the *Ka'i* year 337 (expired), *Nala*, *Kārttigai*, *Paurṇamī*, Thursday, *Krittika* (B.C. 2724) in the *Kallār* family (*mlēchcha vamsa* according to the *Guruparamparai*) at *Tiruk-kūraiyaḷūr* as a manifestation of *Śrīkārmuka*, i.e., the bow of *Vishṇu*.

திருப்பாணாழ்வார், திருமங்கைமன்னன் ஆகிய இருவரைப்பற்றிய விவரங்கள் இவ்விடம் விடப்பட்டுக் காண்கின்றன என்பதை முன்னரே குறிப்பிட்டுள்ளோம். எனினும் ஆழ்வார்களைப் பற்றிய விவரங்கள் பூர்த்தியாக இருக்க வேண்டுமென்பதற்காக அவ்விருவரையும் பற்றிய சம்பிரதாயமான அவதாரச் செய்திகளைக் கீழே கொடுத்துள்ளோம்.

கலியுகம் 342-க்கு மேல் தூர்மதி வருஷம் கார்த்திகை மாதம் கிருஷ்ண பக்ஷத்துத் துவிதியை, புதன்கிழமை, ரோஹிணி நக்ஷத்திரம் கொண்ட நாளில் உறையூரில் பஞ்சம வர்ணத்திலே (பாணர் குலத்திலே) ஸ்ரீவத்ஸாம்சராகத் திருப்பாணாழ்வார் அவதரித்தருளினார்.

கலியுகம் 337-க்கு மேல் நள வருஷம் கார்த்திகை மாதம் பூர்ணிமை, விபாழ்க்கிழமை, கிருத்திகா நக்ஷத்திரம் கொண்ட நாளில் திருக்குறையூரிலே மிலேச்ச வம்சத்தில் (கள்ளர் குலத்திலே) ஸ்ரீகார்முகாம்சராப்த் திருமங்கையாழ்வார் அவதரித்தருளினார்.

உயராகவி ஆழ்வார் திருவவதாரம்

அவரயுமத்தில் அலகூத்து அமரக அராமக-க்குமெல்<sup>1</sup>  
ஈசுவர வறுஷம் சித்திரை மீட்டு வராகூவகூத்தில் அதுதூ<sup>2</sup>  
வெள்ளிக்கிழமையும் சுரதிகா<sup>3</sup> நகூசூத்தில் திருக்கொளு  
ரிலை கூஉஉமணைராஃராய் பூரூண வண<sup>4</sup>த்திலை அவதரித்  
தார்.

யாதெ வரவகூரளவெ ஹலகூமகூஜதெ  
அவரவெஷுராபெ<sup>5</sup>  
வெஷு உவெ லிவவெஷுர லிவவவெ  
ராஃவகூ அதுதூ<sup>6</sup>  
விசூவெ ஹம<sup>7</sup>வியெ மூணவ<sup>8</sup> அ லிவ  
பூரூராஸீ ராரெ  
கூவெவாஸீ லிஜெஷு உயராகவிரவ  
உஷு மூஜீவநாய ||

சாசனம் — 1290]

[D. 3302-v-ராசமஅ

பின் வரும் சுலோகங்கள் மூலப்பிரதியிலே 'விமாநம் சுலோகம்'  
என்று குறிக்கப்பட்டுள்ளன. இவை காஞ்சிபுரம் வரதராஜர் கோவில் ஹஸ்தி  
கிரியில் பொறிக்கப்பட்டுள்ள கல்வெட்டுச் சுலோகங்கள். சாசன இலாகாவின்  
இவற்றைப் பிரதிசெய்து ஐந்து தனிச் சாசனங்களாகப் பதிவுசெய்திருக்கிறா  
கள்.

The following Sanskrit verses are given in the original manu-  
script as *vimānam ślokaṁ*. These are found engraved on the 'rock'  
Hastigiri of the Arulāḷapperumāl, i.e., Varadarāja temple at Kāñchī-  
puram. These have been copied and registered as five separate in-  
scriptions by the Epigraphy Department.

1. துவாபரயுகத்து வருஷம் 'எட்டு லகூத்து அறுபத்து மூவாயிரத்து  
எண்ணூற்றொழபத்தெட்டு' என்பது கர்ணபரம்பரையான பாடம்.
2. 'சுதர்த்தசி' என்று இருத்தல் வேண்டும்.
3. 'சித்திரை' என்று இருத்தல் வேண்டும். அதுவே சரியான பாடம்.  
கிருத்திகை என்பது எழுதுவோர் பிழையே போலும்.
4. 'ஃரூராஷெ' என்பது சம்பிரதாயமான பாடம்.
5. 'அரூவெ' என்பது வழக்கில் உள்ள பாடம்,



[அ]

(No. 650 of 1919). [On the south wall of the Tāyar shrine.] A small portion of the verse is wanting and probably some of the details of the date are thus lost. From the verse as it is found, it is seen that Tātachārya, who was otherwise known as Lakshmi-Kumāra, consecrated the high *vimāna* of the Varadarāja temple known as *Kalyāṇakōṭi* erected by him to the Goddess Lakshmi in emulation of the *vimāna* known as *Puṇyakōṭi* of the God, in Śaka 1536 expressed by a chronogram (i.e., A. D. 1614 - 5), Ananda. According to the Annual Report on the South Indian Epigraphy for the year 1920 the details of the date are Mēsha, śu, tritīya, Saturday and Rōhiṇī. The date would correspond the 2nd April A. D. 1614. The *vimāna* was named *Kalyāṇakōṭi* probably as a remembrance of his title *kōṭikanyakādānam*.

வீரநம் ப்ராகம்

தயு ஸ்ரீபெய் ஸகாபெ வாகுமபுயஜநா -

நடிநாநடிவெஷ-3

தும்மெ மளரமளநீ திவிவரஜஜிநெ

[.....]

ஸ்ரீநாநு யுக்ஷீகூலாஸூலிகவிஹவ -

ஸூராதயாபெ-3ாஹுஷிஹி

கருதாரெணை வுணுகொடிஉவி வரஜஉபெ

தும்மகருதாரணகொடி ||<sup>1</sup>

(க)

1 இந்தச் சுலோகத்தில் ஒருபகுதி விட்டுப்போய்க் குறையாக இருக்கிறது. கிடைத்துள்ள பகுதியிலிருந்து லக்ஷ்மீகுமாரர் என்ற பெயரையுடைய தாதா சாரியார் சகாப்தம் 1536 (கி. பி. 1614 - 5-ஆம் ஆண்டு) ஆரந்த வருஷம், வரதராஜர் ஆலயத்தின் விமானமான புண்யகோடியைப் போலத் தாயார் (லக்ஷ்மி தேவி) ஆலயத்துக்கு உயரமான கல்யாணகோடி விமானத்தைக் கட்டி முடித்து அபிஷேகம் பண்ணுவித்தார் என்னும் செய்தி பெறப்படுகிறது. அபிஷேக நாளின் இதர பஞ்சாங்கக் குறிப்புகள் சிதைந்துபோன பகுதியில் இருந்தன போலும். சாசன இலாகாவின் அறிக்கையிலிருந்து அவை மேஷ மாதத்துச் சுக்லபக்ஷத்துத் திரிதியையும் சனிக்குழமையும் பெற்ற ரோஹிணி நாள் என்பது தெரிகிறது. அது கி. பி. 1614-ஆம் வருஷம் ஏப்ரல் மாதம் இரண்டாம் தேதியாகும். தாதாசாரியார் கோடி கன்யாதானம் செய்தவர் என்பதன் நினைவாகவேபோலும் விமானத்துக்குக் கல்யாணகோடி என்று பெயரிடப் பெற்றது.

[ஆ]

(No. 354 of 1919). [On the east side of the 'rock'.] The record states that Tātāchārya who was known as Rama, i.e., the same Lakshmi Kumāra Tātāchārya, constructed the *vimāna* of the temple of Vēṅkaṭapati at Phanipatigiri (i.e., Tirupati) in the year Pramōdūta. The cyclic year should be either the one which coincided with the Śaka year 1552 (A. D. 1630-31) or the previous one in Śaka 1492 corresponding to A. D. 1570-71. Most probably it was the later date. The *vimāna* of the central shrine in the temple at Tirumalai (Upper Tirupati) is even today known as *Ānandanilayam*.

வரோஜாதெ வஷ்டே-3 ஸகராஜமஜாநந திருயம்

விராநம் சுரோணை: மணிபதி, மிரள வொகடவதௌ |

வீரீமெசு நிததி ஸகரவிஸாயாநநஜநகம்

ரராதாதா அாய-3 ஸு-3 பஜலி ஸினை நியதெ ||<sup>1</sup> (2-)

[இ]

It is not possible to identify this record as there are several inscriptions in the temple which are merely described in the Epigraphical Report as containing Sanskrit verses in praise of Tatayadēśika. The present verse states that Tātāchārya, a great scholar, an emperor among muses, was worshipped by the king of the Kārṇāṭa country whose crowns were worn as a garland at the feet of this scholar and that his fame was resplendent at Śrīraṅgam, Kumbhakōṇam, Phanipatisāyanam, Vēṅkaṭadri, Vrishadri, Simhadri, Yādavādri, the summit of Karigiri and other places.

1. ரமா தாதாசாரியார் அதாவது லக்ஷ்மீகுமார தாதாசாரியார் பணிபதிகிரி அதாவது சேஷகிரி என்னும் திருப்பதியில் வேங்கடபதிக்கு ஜகதானந்த நிலயம் என்னும் விமானத்தைப் பிரமோதூத வருஷத்தில் கட்டி முடித்துக் கும்பாபிஷேகம் செய்துவைத்தார் என்ற செய்தியைத் தெரிவிக்கிறது இந்தச் சுலோகம். திருப்பதி விமானம் இப்போதும் ஆனந்த நிலயம் என்றே வழங்கப்பெறுகிறது. சாசனத்தில் குறிக்கப்பட்ட பிரமோதூத ஆண்டு சகாப்தம் 1552 (க. பி. 1630 - 31) அல்லது அதற்கு முந்தியதான சகாப்தம் 1492 (க. பி. 1570 - 71) ஆக இருத்தல் வேண்டும். சகாப்தம் 1552 போலும்.

Phanipatisāyanam may be any one of the following places: Anantaśāyanam or Trivandrum, Gōvindarāja's shrine at Chidambaram or at Tirupati. Most likely it was the Gōvindarāja shrine at Tirupati. Vēnkaṭadri and Vrishadri are the names of two of the seven hills comprised in Tirupati. Similarly Simhadri also is another. But there is a place famous as Simhachalam. Melukote of the Mysore State is also known as yadavadri. Probably Simhadri and Yadavadri are used as the other names of Tirupati itself. Karigiri is the Hastigiri in the Varadarāja temple at Kāñchīpuram.

The statement in the verse that the Karnaṭa king bowed at the feet of this Tātachārya does seem to be an empty boast. It is learnt from the *Prapannāmritam* that Lakshmī Kumāra Tātachārya performed the coronation ceremony of the Vijayanagara king Vēnkaṭa, and that the king "entrusted the whole kingdom to his preceptor and he himself led a life of retirement doing service to him like Kulaśēkhara of old." In the inscriptions of the period he is found mentioned with eloquent titles like the *Vēdamārga-pratishṭhā-chārya Ubhayavedāntasthāpanāchārya* Eṭṭūr Tirumalai Kumāra Tāta-chārya. He was "the Manager General of the temple affairs (*Srī-karya-dhurandhara*) with a staff of subordinates under him." He appears to have lived in kingly splendour at Kāñchīpuram in the latter portion of his life.

ஸ்ரீராமெ கும்ஹகொனெ மணிவதிபயநெ  
வெங்கடாச்சுள் வுஷாச்சுள்  
விஷ்ணுச்சுள் யாடிவாச்சுள் கரிமிரிபரிவரெ  
அாவிநநுஞ்சுலாவஃ |  
ஸ்ரீகக் கண்கோடஹுஞ்ஞனிசகூடஹொ-  
ஜ்ஞரீரஜிதாஹி-  
ஷாதாஅாயெ-ஜோ வடிநெஜா ஜமதி விஜயதெ  
பராபாஅாவ-ஜெளஃ || 1

(உ)

1. கர்நாடக மன்னருடைய மணிமகுடங்களை மாலையாகச் சூட்டப்பெற்ற பாதங்களையுடையவரும், கலைமகளின் அருள்பெற்ற சாரதா ஸார்வபௌமருமான தாதாசாரியாருடைய புகழ் ஸ்ரீரங்கம், கும்பகோணம், பணிபதிசயனம், வேங்கடாத்திரி, விருஷாத்திரி, வலிம்ஹாத்திரி, யாதவாத்திரி, கரிமிரி சிகரம் ஆகிய இடங்களில் பிரகாசிக்கிறது.

பணிபதிசயனம் என்பது சேஷசயனம் என்று பொருள்படும்; அனந்தசயனம் அல்லது திருவனந்தபுரம், கோவிந்தராஜர் பள்ளிகொண்டுள்ள சிதம்

[F]

(No. 475 of 1919). [On the north wall of the 'rock']. Record consisting of two Sanskrit verses stating that the worshipful Kamalananda Tātayya, i. e., Lakshmikumāra Tātāchārya constructed all the necessary *vāhanas* (vehicles) for the God, that he covered the Kalyāṇa-kōṭi and Puṇyakōṭi *vimānas* with thick gold plates and that he dug a tank called Dēvarājārṇava for the god's delight. The vehicles made by him were the elephant, the horse, the serpent, the Garuḍa, Āñjanēya, the *bimbās* of the sun and the moon, the palanquin, the swing, the swan and the lion, all covered with silver and gold. It is stated that he set up the *balipīṭha* for receiving offerings and also made a *kirīṭā* set with precious stones. He endowed a rich village and also made *mandāpa*, *gōpuras*, *prākāras*, etc. and made arrangements for the celebration of festivals which resemble sacrifices.

பரம் அல்லது திருப்பதி ஆகியவற்றுள் ஏதேனும் ஓர் ஊராக இருத்தல் வேண்டும்; திருப்பதியே போலும். வேங்கடாத்ரியும் விருஷாத்ரியும் திருப்பதியில் அடங்கிய ஏழுமலைகளுள் இரண்டாகும். வலிம்ஹாத்ரியும் மற்றொன்று. ஆயினும் வலிம்ஹாசலம் என்று பிரசித்திபெற்ற வேரோர் ஊரும் உண்டு. மைசூர் ராஜ்யத்தில் உள்ள மேல் கோட்டைக்கு யாதவாத்ரி என்னும் வேறு பெயர் உண்டு. எனினும் இவ்விடம் குறிக்கப்பெற்ற வலிம்ஹாத்ரியும் யாதவாத்ரியும் திருப்பதியின் இருவேறு பெயர்களே போலும். கரிகிரி என்பது அத்திகிரி என்னும் காஞ்சீபுரம் வரதராஜர் ஆலயமே யாகும்.

கர்நாடக மன்னர் இவருடைய பாதங்களிலே வணங்கினார் என்று சுலோகத்திலே காணப்படுவது வெறும் புகழ்ச்சி அல்ல. விஜயநகர ஸாம்ராஜ்யத்தின் அரசனான வேங்கடபதி தேவ மகாராயருக்கு இவர் ஆசாரிய புருஷனாக விளங்கியிருக்கிறார். அவ் வேந்தனுடைய மகுடாபிஷேகத்தை இவரே நடத்தி வைத்தார் என்று பிரபந்நாமிருதம் என்னும் நூல் கூறுகிறது. அதன்மீது அரசன் தன் ராஜ்யம் முழுவதையுமே ஆசாரியரான தாதாசாரியாருக்கு அளித்துவிட்டு முன்னாளிலே குலசேகரர் செய்ததுபோல அவருக்குத் தொண்டு புரிவதிலே தன் காலத்தைக் கழித்தானாம். சாசனங்களில் இவர் வேதமார்க்கப் ப்ரதிஷ்டாசாரிய உபய வேதாந்த ஸ்தாபநாசார்ய எட்டார் திருமலை குமார தாதாசாரியார் என்று பல விருதுகளுடன் குறிக்கப்பட்டிருக்கிறார். அவர் தன்கீழ்ப் பலவகை அதிகாரிகளுடன் பூரீகார்ய துரந்தாராக ராஜ்யத்துக் கோயில்களின் நிர்வாகத்தைக் கவனித்து வந்தார் எனவும் தெரிகிறது. அவர் தம் வாழ்நாளின் பிற்பகுதியைக் காஞ்சீபுரத்தில் ராஜ் ஷோகத்துடன் வாழ்ந்து கழித்திருக்கிறார் எனவும் தெரிகிறது.

It is said that the tank Dēvarājarnavam became famous as Tatasamudram. This is the Aiyāṅgarkulam of the present day. He is said to have constructed, in another inscription, a shrine for Hanumān on the bund of the tank, and composed twenty verses in Sanskrit in praise of the deity. This work known as *Hanumat-vimsati* is also found engraved on the walls of the Varadarāja temple at Kāñchīpuram.

வாஹாநு ராவெவ்ய ஸ்வாவெனெ-மே-மேஜஹயமணிநொ.

வெவநதெ யானுநெயள

ஸௌரம் அநு னு ஸிம்ஸம் உணியயஸிஸிகா.

நொஸிகா ஹஸி ஸிம்ஹன் |

ஸிம்ஸம் ஸுயவ-சுணாஹ-சு உணியமண வலிதம்

வாரஸாணம் கிரீடம்

ஹலிஷா கருதாணகொடீம் வநதரதஸிகா

வாஷ்டகம் வாணகொடீடி ||

(ச)

முஜாநு காஸீரத-சுயாநு வரஹவதிஸுஷெ

உணவாநு மொவ-பராணி

புராகாராநு வுக்ஷவாடீம் சு-சுவரநிகரா-

நு-தவாநு டாநகொடீடி |

வலிதம் தாதாஸ்யம் ஸ்ரீவிஹரணஸரஸீம்

ஷெவராஜாண-சாவாவ்யா

வாலீரநஜாஷ்டாகாநு கருயதி கருவா -

நடிநஷா தபாயதி-சு ||<sup>1</sup>

(இ)

1. கமலாநந்த தாதாசார்யார் அதாவது லக்ஷ்மீகுமார தாதாசாரியார் என்பார் வரதராஜர் கோயிலுக்குச் செய்த திருப்பணிகளை விரிவாக எடுத்துக் கூறும் இரண்டு ஸம்ஸ்கிருத சுலோகங்கள் கொண்ட கல்வெட்டு.

வெள்ளியாலும் தங்கத்தாலும், யானை, குதிரை, பாம்பு, கருடன், ஆஞ்சநேயர், சூரிய சந்திர பிம்பங்கள், மணி இழைத்த சிவிகை, ஊஞ்சல், அன்னம், சிங்கம் ஆகிய வாகனங்களைச் செய்து வைத்தார். பலியை ஏற்றுக்கொள்ளப் பவிடீடம் நிறுவினார். மணிகள் இழைத்த கிரீடம் ஒன்றைச் செய்து சமர்ப்பித்தார். கல்யாணகோடி விமானம், புண்யகோடி விமானம் ஆகிய இரண்டையும் கனத்த தங்கத் தகட்டால் மூடினார்.

காசீர்த்துக்குச் சமமான அழகான கிராமம் ஒன்றை வரதராஜர் உபயோகத்துக்காக அளித்தார். இன்னும் மண்டபம், கோபுரங்கள், பிராகாரம்,

[உ]

(No. 363 of 1919). [On the east side of the 'rock']. This record states that Tātāchārya celebrated eleven *tulābhāras* with his eleven beautiful wives and distributed the gold equal to the weight of thirty-two (?) thus obtained among learned men. From the Epigraphical Report it is learnt that he weighed himself separately against gold and silver and used all that wealth in the service of Varadaraja in erecting the *Kalyāṇakōṭi vimāna*.

நொகெஷு அக்ஷு நிஹுநொவி வஹுஷா -

நுங்கார ஸம்பொஸிதெ -

யஜு-ஸ்தெகாஷஸஸிவி-ஸுஷிததநு -

உ-ஸாரொரு-உ-ஸாரொஸுஹ -

அ-அக்ஷுஸகஸுயுள தகாஹுநதநுநா -

ஸுஸ்தாஷஸஸெஸுவாசுஸா -

அக்ஷு அக்ஷிஷு-ஸெஷிஷ தாதயமுரு -

வ-ஸுஷு: கஸும லாஷஸாஸு ||<sup>1</sup>

(க)

விரகுவாடி ஆகியவற்றை நிரமாணித்து வேள்விகளுக்கு நிகரான உற்சவங்கள் நடப்பதற்கும் ஏற்பாடு செய்தார். ஸமுத்திரத்துக்கு ஒப்பான தேவராஜார்ணவம் என்னும் குளத்தையும் தோண்டி வைத்தார். இன்னும் கிணறு, தடாகம் முதலியவற்றையும் தோண்டினார்.

தேவராஜார்ணவம் என்னும் குளம் தாத சமுத்திரம் என்று புகழ் அடைந்ததாம். அதுவே ஐயங்கார்குளம் எனப்படுவதாகும். அதன் கரையிலே அவர் அனுமாருக்கு ஒரு கோயில் எழுப்பியுள்ளார். அன்றி அனுமார் மீது இருபது சுலோகங்கள் இயற்றி இருக்கிறார். ஹனுமத் விம்சதி என்னும் அந்தப் பிரபந்தமும் வரதராஜர் ஆலயத்தின் சுவரிலே கல்வெட்டாகப் பொறிக்கப் பட்டுள்ளது.

1. தாதாசாரியர் தம்முடைய பதினொரு மனைவிகளோடு பதினொருதடவை துலாபாரம் ஏறி அதனால் கிடைத்த முப்பத்திரண்டு எடை தங்கத்தை வித்வான்களுக்குப் பகிர்ந்து அளித்தார் என்னும் செய்தியைத் தெரிவிக்கிறது இந்தச் சுலோகம்.

சாசன இலாகாவின் அறிக்கையிலிருந்து அவர் தனித்தனியே வெள்ளியாலும் பொன்னாலும் துலாபாரம் ஏறி அந்தப் பொருள் முழுவதையும் கல்யாணகோடி, விமானம் நிரமாணிப்பதிலே செலவிட்டார் என்று தெரிய வருகிறது.

சாசனம் — 1291]

[D. 3302-v-மூலம்]

The details of the date of birth of Nathamuni are given here. Nathamuni heads the list of Śrī Vaishṇava āchāryas. He was born in Kali 3924, Śaka 945, Śōbhakrit, Āni, Śu. daśamī, Wednesday and Anurādhā as the son of Īśvara-muni.

The Kali year 3924 coincided with the cyclic year Śōbhakrit; but the Śaka year was 745 (A.D. 823.) The *tiṭhi* Śu. daśamī and the *nakshatra* Anurādhā would not combine in the month of Āni; Śaka 945 would correspond to Kali 4124 and the cyclic year Rudhīrōḍgārīn.

Of the traditional accounts, the *Kōyilolugu* gives the date as Kali 3924, while the *Sannidhi Guruparamparai* gives it as Kali 3624 Śōbhakrit, Āni, Anurādhā.

These verses are also found in the record giving the genealogy of Tatachārya. [Vide Nos. 1296, 1297 below.]

நாயுடைய திருவவதாரம்

கலியுகத்தில் வறுஷம் நடக்காடெசு ஸகாஷு: காசயரு-க்கு  
மெல் சொபகிறுது ஸ்ரீ ஆனிமீ ஸுக்ஷவக்ஷம் ஷபரி புதன்  
கிழமை சுதராயா நக்ஷத்ரத்தில் ஸ்ரீராமநாமமிடுநுடைய  
குமாரர் நாயுடைய அவதரிச்சார். <sup>1</sup>

வரயீமாத கருஷெ ஸுஹஸெ ஸகவத்ரெ |  
ஸொஹக்ஷி வத்ரெ ஶாவெ ஶிஷுநெ ஸுக்ஷவக்ஷமெ ||  
ஷபரி ஸொஶவணிக் ய-காநராயதாரகெ,  
ஜெஷு ஸுதஷதயகெ ஜாதெஷ்ஷரிக்ஷிஸுர: ||  
ஷாஷெஷி ஸிஸொஶா-ஷ உதி நாலகாஸொக்ஷித: | <sup>2</sup>

1. கலியுக வருஷம் 3924-க்குப் பிரபவாதி ஆண்டு சோபகிருது தான் ; ஆயினும் சகாப்தம் 745 (கி. பி. 823) ஆகிறது. அன்றி ஆனி மாதத்திலே சுக்ஷவக்ஷத்துத் தசமியும் அனுஷ நக்ஷத்திரமும் சேரா. சகாப்தம் 945-க்குக் கலி வருஷம் 4124-ம் பிரபவாதி ஆண்டு ருத்திரோத்தகாரியும் ஆகும். நாத முனிகள் பிறந்த கலி வருஷம் 3924-என்றே கோயிலோழுது கூறுகிறது. எனினும், சந்நிதி-குருபரம்பரையில் இது 3624-என்று காணப்படுவதாகக் கிறது.

2. இந்த அவதார சுலோகங்கள் பின்னால் தாதாசாரிய பரம்பரையைத் தெரிவிக்குமிடத்தும் காணப்படுகின்றன. [சாசனம் 1296, 1297-நெ. பார்க்க]

சாசனம் — 1292, 1293]

[D. 3302-V-மருமக, மருமக

This gives the date of birth of Emberumāṇar, the great Śrī Vaishṇava āchārya Sri Ramanuja. It states that he was born in Kali 4126, Śaka 947, Krōdhana, Sittirai 14, Śu. pañchamī, Thursday Ārdra, at Śrīperumbūdūr as the son of Ādikēśava Sōmayāji to his wife Śrīdēvi as a manifestation of Ādiśēsha.

This date is not in conformity with the traditional date. The question is being discussed in a note elsewhere in the book.

[மருமக]

### எம்பெருமானார் திருனட்சத்திரம்

ஸ்ரீவாஹந ஸகாஷ: கராசயெ-க்கு கருஷ்: சகாஉயசு-க்கு  
மெல்ச் செல்லா னின்ற கெராயந வறுஷத்தில் சித்திரை  
மாசத்திலெ யச வ ஸுகரு வகூ வஹி வஜாழக்கிழமை திரு  
வாதிரை நகூத்திறத்தில் ஸ்ரீபெரும்பூதாரிலெ சூடிகெஸவ  
ஸொஉ யாஜிக்கு ஸ்ரீசெவியினுடைய மஹத்திலெ எம்பெருமா  
னார் சூடிஸெஷாவதாரமாக அவதரிச்சார். உ<sup>1</sup>

[மருமக]

### எம்பெருமானார் திருவவதார<sup>2</sup>

ஸ்ரீகெ<sup>2</sup> ஸெவாயநெ வஷெ-  
கருஷெ விரவாவநெ |  
கெராயநாஷெ உயளவாஸெ  
த யொடிஸிழிநெ மகெ ||  
வகெஷ வஷகெஷ-<sup>3</sup> வஹஜா  
தியள ஸமாராவாஸரெ |  
ஸ்ரீஉஜாஷெ<sup>4</sup> உநி ஸ்ரீஉ-  
நாடிகெஸவயஜந: ||  
தகஷ-<sup>5</sup>வதா<sup>6</sup> ஸ்ரீசெவயா  
ஸஜெஜெ தநயொகிஹத<sup>7</sup> |

1. இவ்விடம் கொடுக்கப்பட்டுள்ள விவரங்களுக்கும் சம்பிரதாயமாகக் குறிக்கப்பட்டுவரும் தேதி விவரங்களுக்கும் வேறுபாடு காணப்படுகிறது. இது பற்றி இந்நூலிலே பிறிதோர் இடத்தில் ஆராய்ந்துள்ளோம்.

2. 'ஸகெ' என்று இருத்தல் வேண்டும்,



சாசனம் — 1294]

[D. 3302-V-நாடுயச

This gives the details of the date of birth of **Manavalama-muni**. He was born in Kali 4471, Śaka 1292 (both expressed by chronograms in the Sanskrit verse), Sādhāraṇa, Aippaṣi, Śu. chaturthi, Thursday, having the *nakshatra*, Mūla as second Yatipati, i.e., Śrī Rāmānuja, as a manifestation of Tiruvānantālvār, i.e., Ādi-śēsha. The Tamil portion adds that he was born in the *Ṣoṭṭai kula* and the family known as *gōmaṭha* as the son of Tiruvuḍaiya Perundāsar *alias* Anṇar.

The date would correspond to A.D. 1370, October 24.

The *Tenkalai* Śrī Vaiṣṇavas venerate Maṇavāḷa-māmunī next to Śrī Rāmānuja.

வரு சச்சுராளயக-க்கு சாதாறண வரு  
சாநயக-க்கு சாஉயகயக. <sup>1</sup>

மணவாள மாமுனி திருவவதாரம்

வாஷாஷுவாவாஷ<sup>2</sup> தாயா கருயுமபரநி  
புரையெய சகாஷெ  
வஷெ<sup>3</sup> ஸாயாரணெஷெ<sup>3</sup> ஸஷயிமதத<sup>4</sup>ரு  
வாஷரெதீரஸெஷெ<sup>4</sup> |  
வாஷரெஷெஷெ<sup>4</sup> அத<sup>4</sup>த<sup>4</sup>யா<sup>4</sup> ஸுஷஜந<sup>5</sup> தியெள  
ஸுஷவக<sup>6</sup> ஸுஷக<sup>6</sup>யா  
ஸுஷ<sup>6</sup> த<sup>6</sup>யு<sup>6</sup>வ<sup>6</sup>த<sup>6</sup>யா<sup>6</sup> யதிவதி<sup>6</sup>வ<sup>6</sup>ரெ -  
ரஷஜா<sup>7</sup>த<sup>7</sup>ய<sup>7</sup>ய<sup>7</sup> ||

1. இது என்ன கணக்கு விவரத்தைத் தெரிவிக்கிற தென்பது விளங்கவில்லை.

2. 'வாயாராவம்' என்பது ஸம்பிரதாயமான பாடம்.

3. 'ஸாயாரணாவெ' என்று இருத்தல் வேண்டும்.

4. 'வாஷெஷெ' என்றும் பாடம் உண்டு.

5. 'ஸஷஜநி அ' என்பது சம்பிரதாயப் பாடம்.

6. 'ஸுஷஜ' என்று திருத்தி வாசிக்க.

7. 'நாஜா' என்ற பாடமும் உண்டு.

இன்குறபடியே கலியுகம் பிறந்து லாலாயிரத்து நானூற்று எழுபத்தொரு வருஷத்துக்கு மெல் முன்பு சாதாறண வறுஷத்திலே அற்ப்பசி மாசத்திலே மூலா நட்சத்திரத்திலே உபைய விபூதியும் ஓகந்தறுளிக்கும்படி சொட்டைக் குலத்திலே கொமடமென்கிற குடியையுடையரான திருவுடைய பெருந்தாசுரனார் அணற்று திரு அனந்தாழ்வார் குமாறாக திரு அவதரித்தார். உ<sup>1</sup>

சாசனம் — 1295]

[D. 3302-V-ஈசமக

This gives a list of the sacred places for Śrīvaiṣṇavas, i.e., the Viṣṇu temples at Kāñchīpuram. They are as follows :

Attīyūraṇ—Hastigiri or the Varadarāja temple.

Yathōktakāri—Also known as *Sonna-vannam śeyda perumāl*, i.e., 'the god who acted as he said'. This is referred to Tiruveṇka in the hymns.

Aṣṭabhujam—Same name at present.

Ala[giya] Śiṅgar: Vēlukkai Śiṅgapperumāl temple near Viḷakkoḷi-k-koyil.

Dīpaprakāśar: Viḷakkoḷi-k-kōyil. Also referred to as Tirut-taṅka.

Ulagalandān: Same as Uragam. The three temples Nira-gam, Kāragam and Kārvānam, are also there. Kaḷvar is the name of the deity of the Kārvānam. This is in the inner prakāra of the

1. இந்தத் தமிழ்ப்பகுதி பிள்ளை லோகார்ய ஜீயர் அருளிச்செய்த யதீந் திர ப்ரவணப்ரபாவத்தில் பின்வருமாறு காணப்படுகிறது:

‘என்கிறபடியே கலியுகம் பிறந்து நாலாயிரத்து முந்தூற்று எழுபத்தொரு வருஷத்திற்குப் பின்பு ஸாதாறண வருஷம் ஐப்பசிமாதம் சுக்லபக்ஷத்தில் சதுர்த்தியும் வியாழக்கிழமையும் கூடின திருமூலத்திலே உபய விபூதியும் கொந்தளிக்கும் குடியையுடையரான திகழக்கிடந்தான் திருநாவீறுடையபிரான் தாதர் அண்ணரையருக்குக் குமாரசாகத் திருவனந்தாழ்வார் திருவவ்நரிக் தருளிஞர்.’

இதிலே காணும் கலியப்தம் தவறு ; மேலே உள்ளதே சரியானது.

Ulagalandār temple. Some take Kaḷvar as the deity in the shrine of Ādivaraha within the precincts of the temple of Kānakshi Amman.

Uḷḷavarattavar [Uḷḷavāru urattavar]: Same as Yathōktakāri?

Kachchi-niḷā-[t-tiṅgal]-tuṇḍat-t-emberumān: The shrine of Viṣṇu within the inner *avarana* of the Ekāmbaranātha temple.

Pachchaivaṇṇar: Same name at present.

Pavalavaṇṇar: do.

Paramēśvara Viṇṇagaram: Now known as Vaikuṇṭha-p-perumāḷ temple.

Paṇḍavadūtar: Referred to as Paḍagam in the hymns.

Vijayarāghavan: The name of the deity in the Viṣṇu temple at Tiruppuṭkūḷi.

காஹீவார ஐவடிபெரம்

அத்தியூரான் யயொதூகாரி சுஜஹஜ் அழகிங்கர் தீபப் பிறகாசர் உலகளந்தான் ஊரகம் நீரகம் காரகம் கார்வானம் கள்வர் உள்ளுவால[ை\*]ரத்தவர் கச்சி நிலாத்துண்டத் தெம் பெருமான் பச்சைவண்ணர் பவழவண்ணர் பரமேசுவர விண்ணகரம் பாண்டவதூதர் விசையறகவன். உ<sup>1</sup>

1. அத்தியூர்: சின்னக் காஞ்சிபுரத்தில் இப்போது வரதராஜர் ஆலயம் என்று வழங்கப்பெறுவது.

யதோத்தகாரி: சொன்னவண்ணம் செய்த பெருமான்; திருவெஃகா எனவும் பெயர்.

அஷ்டபுஜம்: இப்போதும் இதே பெயர்.

அழகிய[சு]ங்கர்: வேளுக்கை சிங்கப்பெருமான் கோவில்; விளக்கொளிக் கோயில் சமீபம் உள்ளது.

தீபப்பிரகாசர்: விளக்கொளிக்கோயில்; திருத்தண்கா எனவும் ஆகும்.

உலகளந்தான்: ஊரகம். நீரகம், காரகம், கார்வனம் ஆகிய மூன்றும் அங்கேயே உள்ளன. கள்வர் என்பது கார்வானத்துப் பெருமான் பெயர்.

சாசனம் — 1296, 1297]

[D. 3302-v-<sub>1</sub> ஈடுமெ & ஈடுமெ]

The following two items give the genealogy of the Tatacharya family of Kañchipuram. The members of this family trace their descent from Periya Tirumalainambi, the maternal uncle of the great Vaishṇavite teacher Śrī Rāmaṇuja and one of the five important disciples of Yaṃunārya, i.e., Aḷavandar. It is said "that god Veṅkaṭeśa of Tirupati was very pleased with Periya Tirumalainambi or Śrīśailapūṇa as he was otherwise known, for the paternal care he was taking of the lord's image at Tirumalai and on one occasion the god is said to have addressed him as *mama tāta* (my father); and ever since Periya Tirumalainambi came to be recognised by the the name Tatacharya, a title which his descendants also began to assume." There were several branches of this family, many members of which were holding important positions during the period of the Vijayanagara rule. The present genealogy is of the branch to which Lakshmīkumāra, otherwise known as *Kōṭikanyakādānam* Tatacharya, of Kañchipuram belonged.<sup>1</sup>

உலகனந்தார்தோயில் உள் பிரகாரத்தில் இருப்பது. கள்வர்: காமாட்சி அம்மன் கோயில் உள்பிரகாரத்தில் உள்ள ஆதிவராகப் பெருமான் ஆலயமே இது எனவும் சிலர் கூறுவர்.

உள்ளவாறு உரைத்தவர்: யதோக்தகாரியே (?) ஆவர் போலும்.

கச்சிலாத்திங்கள் துண்டத் தெம்பெருமான்: ஏகாம்பரேசுவர் ஆலயத்தில் உள் ஆவரணத்தில் வடக்குப் பக்கத்தில் உள்ள கோயில்.

பச்சைவண்ணர்: இப்போதும் இதே பெயர்.

பவழவண்ணர்: இதே பெயர்தான் இப்போதும் வழங்குகின்றது.

பரமேசுவர விண்ணகரம்: வைகுந்தப் பெருமான் கோவில்.

பாண்டவதுதர்: பாடகம் எனப்படும்.

விஜயராகவன்: திருப்புக்குழியில் கோயில்கொண்டு எழுந்தருளியிருக்கும் பெருமான்.

1. This genealogy is given in detail in the *Prapannāmritam*. See also *Ep. Ind.*, Vol. XII, p. 162; vol. XIII, p. 2; and *The Tirumalai Tirupati Devasthanam Epigraphical Report*, p. 310.

The genealogy as found in the Tamil portion is as follows :

Śrī Vishṇuvardhana.

His son Śoṭṭai-nambi Gōvindamuni of Śaṭhamarshṇa Rishi (or *gōtra*).<sup>1</sup>

His son Isvaramuni

His son Nāthmuni. He was born in Kaṭṭu-Mannar-kōvil.

(Then) Isvaramuni.

Ālavandar born at Gōvardhanapura on the banks of the Yamunā (*Yamunāṭira*).

He had four sons: (1) Isvara-bhaṭṭar (2) Gōvinda-bhaṭṭar (3) Nāthamuni and (4) Raṅgarājar.

Gōvinda's son Tirumalai-nambi.

Tirumalai nambi had two sons: (1) Tirukkurugaip-pirān piḷḷan and (2) Rāmānuja.

Tirukkurugai-p-pirān piḷḷan

Padmanētrāchārya

Puṇḍarikāksha

Śaṭhakōpa

Padmanētra

Śrīnivāsāchārya

Śrī Narasimbāchārya

Rāmānujāchārya

Narasimbāchārya Tātāchārya. (This was the famous Eṭṭūr Śīngarāchārya who along with his brother Raṅgāchārya went to the court of Virūpaksha, the Vijayanagara king, to whom he later on became the spiritual *guru*).

---

1. This portion of the genealogy may also be taken as follows: Śrī Vishṇuvardhana. His son Śaṭhamarshṇa Rishi. (Then) Śoṭṭai-nambi. (Then) Gōvindamuni.

Tirumalai nambi

Śrīnivāsāchārya

Tātayāchārya

Vēṅkaṭāchārya

Sundarāchārya

Śrīnivāsāchārya

*Pañchamatabhaṅgam* Tātāchārya (otherwise known as) *Kōṭikan-yakāḍānam* Tātāchārya (whose name was) Lakshmīkumāra.<sup>1</sup> He had eleven wives. He refuted the five religions and established his own religion. He had five sons: (1) Tirumalai Tātāchārya (2) Vēṅkaṭavaradāchārya (3) Śrīnivāsāchārya (4) Aḷagarāchārya and (5) Vēṅkaṭāchārya;

Vēṅkaṭavarada dēśika had three wives and ten sons. Three of them, Vīrarāghava-vēdāntāchārya, Tirumalai Tātāchārya and Raṅganāthāchārya were the sons of his first wife. By his second and third wives he had Vīrarāghava Tātāchārya. (Some names seem to be left out here.)

Vīrarāghava Vēdāntāchārya had a son Āchārya through his first wife; and Vēṅkaṭa Varadāchārya and Vēṅkaṭa Vīrarāghava-āchārya by his second wife.

Āchārya had four sons: (1) Śrīnivāsa Tātāchārya (2) Vēṅkaṭavarada Tātāchārya, (3) Vīrarāghava Vēdāntāchārya and (4) Nara-simbāchārya

Śrīnivāsāchārya's son Dēśika.

Vēṅkaṭavarada Tātāchārya's son Śrīnivāsa Varadāchārya.

The Sanskrit portion contains verses giving the details of the dates of birth of these persons from Nāthamuni to Tirukurugari-pīran piḷḷan.

1. T. A. Gopinātha Rao takes the Lakshmīkumāra as the son of *Pañchamatabhaṅgam* Tātāchārya (*Ep. Ind.*, vol. XIII, p. 3); but it is clearly stated here that both the names refer to the same person.



ஹம் தாதாஅய்யு<sup>3</sup>ர் கொடிகாதாந<sup>1</sup> தாதாசாரியர் ஓக்ஷீ கௌ  
 ரர்:அவருக்கு ஓ<sup>2</sup>ிகள் மக. ஸக<sup>2</sup>ர<sup>2</sup> ஸு<sup>2</sup>திவெதாவாய் அஞ்சு மதம்  
 வணிச்சு<sup>2</sup> ஷீத ஷாவநம் வண்ணினர்: அவருக்கு வ<sup>2</sup>சு<sup>2</sup>ர் ஓ:  
 திருமலை தாதாசாரியர், வெங்கிட வரதாசாரியர், ஸ்ரீநிவாஸாசா  
 ரியர், அழகராசாரியர், வெங்கிடாசாரியர். வெங்கிடவரத டேசிக  
 னுக்கு ஓ<sup>2</sup>ிகள் மூனு பெர்; குமாருள் பத்துப் பெரில் வீரராகவ  
 வெதாநாஅய்யு<sup>3</sup>ர், திருமலை தாதாசாரியர், நம்மநாயாஅய்யு<sup>3</sup>ர்,  
 யிவாள் மூனு பெரும் முதல் ஓ<sup>2</sup> கௌ<sup>2</sup>ர<sup>2</sup>ள். நெண்டாவருக்கு<sup>3</sup>  
 மூனாவருக்கு வீரநாவவ தாதாசாரியர். வீரநாவவ வெதாந்தா  
 சாரியருக்கு மூத்தாருக்கு குமாரர் சூஅய்யு<sup>3</sup>ர்; எளையாருக்கு  
 வெங்கிடவரதாசாரியர், வெங்கிட வீரசாரியர்<sup>4</sup>. சூஅய்யு<sup>3</sup>ருக்கு  
 கௌ<sup>2</sup>ர<sup>2</sup>ர் ச: ஸ்ரீநிவாச தாதாசாரியர், வெங்கிட வரத தாதாசாரி  
 யர், வீரராகவ வெதாநாஅரியர், நரஸி<sup>2</sup>வாஅய்யு<sup>3</sup>ர். ஸ்ரீநிவாஸ  
 தாதாசாரியர் கௌ<sup>2</sup>ர<sup>2</sup>ர் டேசிகர். வெங்கிட வரத தாதாசாரியர்  
 கௌ<sup>2</sup>ர<sup>2</sup>ர் ஸ்ரீநிவாஸ வரதாஅரியர்.

[௩௩]

காஹீஸு<sup>2</sup>ரம் தாதாஅய்யு<sup>3</sup>

வம்ஸவரம்வரெ

The genealogy opens with the particulars of Nāthamuni. The verses included here have been given above separately for him. It is possible to take from the chronogram the Śaka year given as 745. This date would be too early for the dates of his successors as given below.

[For a discussion on the date of Nāthamuni, vide No. 1291 above].

1. 'கொடிகாதாந' என்று இருக்கவேண்டும் போலும்.
2. காலஞ்சென்ற து. அ. கோபிநாதராயர் லக்ஷ்மீகுமாரரைப் பஞ்சமத பங்கம் செய்த தாதாசாரியாருடைய மகனாகக் கருதினர். ஆனால் இரண்டு பெயர்களும் ஒருவரையே குறிப்பவை யென்பது இதிலிருந்து தெரிகிறது.
3. இவ்விடத்தில் சில பெயர்கள் விட்டுப் போயிருத்தல் வேண்டும்.
4. 'வெங்கிட வீரராகவாசாரியர்' என்று வாசிக்க வேண்டும் போலும்.



வரஃமாநகருஞ்ஞெ ஸுஹஸ்தெ ஸகவத்ரெ |  
ஸொஹகூஅதரெ லாவெ லியுநெ ஸுக்வக்ஷமெ ||

உஸஜீவொஜ்வணிக் யுகூநுராய தாரகெ |  
ஜஜெ ஸுதஸ்துக் ஜாதெஷ்ஜாஜிகீஸுரஃ |  
அாஉஸெநி ஸிஸொஹஸாய உதி நாலாகரொக்ஷிதஃ || <sup>1</sup>

Then comes the date of birth of his son Isvaramuni. It is Kali 3967, Śaka 788, Vyaya, Kumbha, ba. dvitīya, Tuesday, Hasta and Mēsha lagna.

The Kali, the Śaka and the cyclic years agree (A.D. 866-7); but the other details are irregular.

வீதாஸுமாதெ கருஞ்ஞெ ஷெஹஸ்தாநெ ஸகெ வஜ்யெ |  
வவெஷ்ஜ லாவெ வடெ சுஜெஷ் வகெஷ் கஜஜிநெ தியுள ||

விகீயஜாயாஹ ஷுதாரெ லெஷ்ருமெ ஸ்விராஹகெ |  
உஸரெ லாஸிஸாஸுத யோநாயஜுநெஸுத || <sup>2</sup>

ராஹஸுநி

The date of birth of his son Yāmunāchārya, otherwise known as Ālavandār is then given. He was born in the Kali year 4067, Śaka 888, Akshaya (A.D. 966-7). The traditional date for his birth is Kali 4017, Dēatu, Ādi, Uttirāḍam, Paurṇamī and Tuesday.

1. நாதமுனிகளின் அவதாரச் சுலோகங்களுடன் ஆரம்பிக்கிறது இந்த வமிசபரம்பரை விவரம். இந்தச் சுலோகங்கள் மேலே தனியாகவும் கொடுக்கப் பட்டுள்ளன. கடபயாதி சங்கியைக் கொண்டு இந்தப் பாடத்திலிருந்து அவர் பிறந்த சகாப்தம் 745 எனவும் கொள்ளமுடியும். இவ்வமிசத்தில் பிறந்த மற்றவர்களுடைய ஜனன ஆண்டுகளைக் கவனிக்கும்போது, இது காலத்தால் முற்பட்டதாக இருக்குமோ என்று தோன்றுகிறது.

[இந்நாளின் இதர விவரங்களுக்கு மேலே 1291 நெ. பார்க்க.]

2. அடுத்தபடியாக அவருடைய குமாரர் ஈசுவரமுனியின் அவதாரம் கலி 3967, சகாப்தம் 788, வியவருஷம், கும்பமாதம், கிருஷ்ணபக்ஷத்துத் துவிதியை, செவ்வாய்க்கிழமை, ஹஸ்த நக்ஷத்திரம், மேஷ லக்ஷ்ணமாகும். கலிஆண்டு, சகாப்தம், பிரபவாதி வருஷம் ஆகியவை ஒத்துவருகின்றன (கி. பி. 885-7), மற்றப் பஞ்சாங்க விவரங்கள் ஒத்துவரவில்லை.

ஸூதநீவம் கருயு-மெ  
 டெஹதாநஸூகஸூதா |  
 சுகூத்யொ வஸூரொ ஜாஸ-  
 ஸூதரி: வுனெ-சாஹிஜாயிவ: |  
 தாரகாஅதநா[ஷா\*]யா  
 வஸ-ஸுவஜதம் பவஸ ॥ 1

யாஸுநாஅயத-சீர்

Of his four sons, the first, Isvarabhaṭṭalvar, was born in Śāka 904 (A.D. 982), Chitrabhānu, Chaitra, Ārdra.

வநாயீநெ ஸகெ விசூஹாஹஸூ ஜாஸி வெஹகெ |  
 சூசூ-சாயாம் ய-மூருதெஅ யாஸுநாய ஸுதொஜநி |<sup>2</sup>

ஸஸூரஹட்டாழ்வார்

The second son, Gōvindamuni was born in Śāka 906 (A.D. 984), Taraṇa, Tulā.

ஸகெ தநலய-நவஸூ-தார-ஸூதந்ருவாயு-மெ |  
 விதியொ யாஸுநாஅயத-தநயொ ஜநி ய-மூருதெ ॥ 3

மொவிந-சூநி:

The third son, Nāthamuni, was born in Śāka 908 (A.D. 986), Jaya.

1. அவர் மகன் யாமுநாசார்யரான ஆளவந்தாரின் அவதாரம் கலி 4067, சகாப்தம் 888, அஷ்டய ஆண்டு (கி. பி. 966-7) ஆகும். சம்பிரதாய நூல்களிலே அவர் கலியப்தம் 4017, தாது வருஷம், ஆடிமாதம், உத்திராடத்தில் பிறந்தார் என்று காணப்படுகிறது.

2. அவர் குமாரர் நால்வரில் முதல்வரான ஈசுவரபட்டாழ்வார் சகாப்தம் 904 (கி. பி. 982), சித்திரபானு வருஷம், சித்திரை மாதம், திருவாதிரை நக்ஷத்திரத்தில் பிறந்தார்.

3. இரண்டாம் குமாரரான கோவிந்தமுனி சகாப்தம் 906 (கி.பி. 984), தாரணவருஷம், துலா மாதம் பிறந்தார்.

The Śaka and the cyclic years do not agree. The cyclic year should be Vyaya. If Jaya is intended then the Śaka year would be 916.

ஐநாயிநெஜா . . . க வஷெ-ஃ<sup>1</sup>

ஐயெ கூஹெநு தாரகெ |

தரதீயொ யாஹநாய-ஃஷெ

தநயொஜநி வஹெஹெ ||<sup>2</sup>

நாயஹநி

The next verse is incomplete. Only one half of it is found. It is not known to whom the date, Virōdhin (Śaka 911 or A.D. 989-90), Mithuna, Punarvasu is intended. The word *Śāhāri-mātrah* is given in the original.

விரொயிவதரெ யும ஜாலெ தாரெ வுநவ-ஃஷெ ||<sup>3</sup>

ஸாரிஜா-ஃ

Raṅgaraja, the fourth son of Ālavandār, was born in Śaka 919 (A.D. 997), Hēvīlambi, Mithuna.

யாஹநெய ஸுதஹுயெ-ஃ ராமராஜ-ஃஷெ

யாஜிநெ ஹெவிஸுஸி லியுநாஸுஹவாப-ஃ ||<sup>4</sup>

ராமராஜ:

1. 'ஸகெவஷெ-ஃ' என்று பூர்த்தி செய்யலாம்.

2. மூன்றாமவரான நாதமுனிகள் சகாப்தம் 908 (கி. பி. 988), ஜய வருஷம் பிறந்தார்.

சகாப்தமும் பிரபவாதி ஆண்டும் ஒத்துவரவில்லை; விய ஆண்டாக இருத்தல் வேண்டும். பிரபவாதி ஆண்டு ஜய என்பதே ஆனால் சகாப்தம் 916-ஆதல் வேண்டும்.

3. அடுத்த சுலோகம் பூர்த்தியாக இல்லை. ஒரு பாதி மட்டுமே கிடைத்துள்ளது. விரோதி ஆண்டு (சகாப்தம் 911) இரட்டை மாதம் (ஆனி), புரவசு நாளில் பிறந்த யாரோ ஒருவரைப்பற்றிக் கூறுவது. 'சடாரி மாத்ர:' என்ற தொடர் காணப்படுகிறது.

4. நான்காம் குமாரரான ரங்கராஜர் சகாப்தம் 919 (கி. பி. 997), ஹேவிஸம்பி வருஷம், ஆனிமாதம் பிறந்தார்.

Tirumalai nambi, otherwise known as Śrīśailapūrṇa, was the son of Gōvīṇḍabhaṭṭar. He was born in the Tirumalai, i.e., the Tirupati hills in the Śaka year 923 (A.D. 1001), Plava, Āvaṇi, Anurādhā.

மொளிறுஹட்டர் வுஞ்சூர் திருமலைநம்பி  
அவதாரம் திருமலையிலே.

மொஞ்சூரீநெ ஸகெ வஷெ-3  
ஹவெ லாஸி நஹஸூகெ |  
சுநலுராயொஹுநி ஸுந்தொ  
மொளிறுஹெஜாஹுக் மஹொஃ || 1

ஸ்ரீஸெருவாண-3:

Tirukkurugaippi-āṇ-piḷḷan was the son of Śrīśailapūrṇa or Tirumalainambi. He was born in Śaka 963 (current), Vikrama, Tula, Viśākha. The Christian year would be 1040 A.D.

மீதாயீநெ ஸகெ வஷெ-3  
விசுகெ லாஸி தெளறுகெ |  
விஸாவொஹுநி ஸாஸூத  
தநயம் வாஹ்வாலிநீ || 2

கூரூகாயீஸ:

திருக்குருகைப்பிறுன் பிள்ளான்.

Then another date, Śaka 966 (current), Sublānu, Kārttigai, Āślēsha for another son of Śrīśailapūrṇa, is found. This is evidently the date intended for Rāmānuja, brother of Tirukkurugaippiran piḷḷan.

1. கோலிந்தப்பட்டருடைய குமாரர் திருமலை நம்பி என்னும் ஸ்ரீ சைல பூர்ணர். அவர் திருமலையிலே பிறந்தார். அது சகாப்தம் 923 (கி.பி. 1001), பிலவ ஆண்டு, ஆவணி மாதம், அதுஷ நக்ஷத்திரத்தில் ஆகும்.

2. அவர் குமாரர் திருக்குருகைப் பிரான் பிள்ளான் சகாப்தம் 963, விக்கிரம வருஷம், துலா மாதம், விசாக நக்ஷத்திரத்தில் பிறந்தார்.

ஸகெ தாதாயரெ வஷெ-<sup>1</sup>

ஸுஹாநள ஜாலி காதி-<sup>2</sup>கெ|

சுஸெஷொபு, நி ஜஜெகு ஸ்ரீ-

ஸெருவகுண-<sup>3</sup>காஸுதொ வரஃ|| <sup>1</sup>

ஸ்ரீபெரும்புதூர்

Sriperumbūdūr

இந்தச் சாசனம் எழுதப்பெற்றிருக்கும் ஏடு ஸ்ரீபெரும்புதூரிலிருந்து கிடைத்ததென்று குறிக்கப்பெற்றுள்ளது. இது மக்கென்வியின் உதவியாளர் தயாரித்த பிரதியாகத் தெரியவில்லை. பிற்காலத்தில் சேர்க்கப்பெற்றது போலும். அவ்வூரில் அவதரித்த ஸ்ரீபாஷியகாரர் என்னும் இராமாநுஜ ருடைய ஆலயத்தைச் சேர்ந்தது போலும்.

The palm leaf on which the following document is written is said to have been obtained from Sriperumbūdūr. This does not appear to belong to the original collection of Col. Mackenzie, but seems to have been added to it later. Evidently this belongs to the shrine of Rāmanuja, otherwise known as *Śrī Bhūshyakāra* and as *Uḍaiyavar*, at the place.

சாசனம் — 1298]

[D. 1175-t

This record registers the rights and privileges of the agent (*purushakūri*) of the person whose name is not clear but who was responsible for the purchase of landed property to the shrine, in conducting the affairs of the shrine and the management of the landed property.

.....மாநுஜாயநமகா<sup>2</sup>[1\*] ஸ்ரீ சுவிநாணுகொடி ஸ்ரீராம  
யைகரா யெழுதுருளியிருக்குற ஸ்ரீ பெரும்புதூ<sup>3</sup>[தூ\*]ர் ஸ்ரியுவதி  
யான ஸ்ரீ ஆதிசேசுவப் பெருமாள் திரு.....<sup>3</sup>[அ]வர்

1. திருமலை நம்பியின் மற்றொரு குமாரர் பிறந்த நாளைத் தெரிவிப்பது இந்தச் சுலோகம். சகாப்தம் 966, சுபானு வருஷம், கார்த்திகை மாதம், ஆயில்ய நக்ஷத்திரத்தில் பிறந்த அவர் இராமாநுஜர் என்னும் இரண்டாம் குமாரரே போலும்.

2. 'ஸ்ரீமதே ராமாநுஜாய நமஃ' என்று பூர்த்தி செய்க.

3. 'திருவடிகளுக்கும்' என்று பூர்த்தி செய்க.

திருவடிகளிலே 'சென்றால்' குடையா' மிதாழிப்படியெ  
 சுபெஷபெஷ<sup>1</sup> கெக்கெய்யெ<sup>2</sup>கடி<sup>3</sup>ரதூராய திருவடாழ்வா  
 னுடைய திருவவதார விபெஷமாய் கூவா<sup>4</sup>தூ<sup>5</sup>பூ<sup>6</sup>லா<sup>7</sup>.....<sup>8</sup>  
 முந்தருளியிருக்குற வெம்பெருமான் திருவடித் தாமரைகளுக்  
 கும் ஊமவதா<sup>9</sup>தாரான அம<sup>10</sup>கொத்து வரிகரமும் ஹமவசு  
 ஹமவதா<sup>11</sup>தாராய<sup>12</sup>கெக்கெய்யெ<sup>13</sup>கடி<sup>14</sup>ரதூர[ர\*]யி உடையவர்  
 ஸ[ஹி].....<sup>15</sup>தா<sup>16</sup>விதமா<sup>17</sup> வணர்மொவ<sup>18</sup>தாரங்கள்<sup>19</sup> சுவி<sup>20</sup>  
 ஹமாக நடக்கவெணுமென்று [ஸஹு<sup>21</sup>] ஹவஸ்தி<sup>22</sup> உண்  
 டாக்கிவிக்கிற பய<sup>23</sup>ஃ<sup>24</sup> முன் வச்ச கால் பின்வாங்.....  
 .....<sup>25</sup>டாக்கி<sup>26</sup> வித்த நிலைநின்ற ஹமவதர்களான யின்நின்  
 றாரினருக்குரான<sup>27</sup> உங்களுக்கு னங்கள் அனவரும் வனககண்மக  
 யிருந்து எழுதி<sup>28</sup>க் குடுத்த லய<sup>29</sup>தா<sup>30</sup>பெயும் சுயிகாரமும் என்ன  
 மென்றால்:.....<sup>31</sup>வருமாய் ஹவஸ்தி<sup>32</sup>தியிலே வரப்பட்ட யாத<sup>33</sup>  
 மாவது ரொக்கமாவது உங்கள் வ<sup>34</sup>ர<sup>35</sup>ஷகாரி<sup>36</sup>வமாயெ நடப்  
 பி[க்]க<sup>37</sup> வெண்டியது. சுந்த வ<sup>38</sup>ர<sup>39</sup>ஷகாரி<sup>40</sup> வரவுக்கும் சிலவுக்  
 கும் விவர<sup>41</sup> திருக்.....<sup>42</sup>[க்]குலெ எழுதிவிக்கிறது. அதிலெ  
 தாழ்வு கண்டால் திருக்கெ[ர\*]வில் வாணத்திலெ தெண்டிக்கப்  
 படும். கெக்கெய்ய<sup>43</sup> வ<sup>44</sup>தா<sup>45</sup>கர்களிலெ ஆராவது யிந்த ஓ<sup>46</sup>வ<sup>47</sup>த்  
 துக்கு ஷெ.....<sup>48</sup> அந்த சூலா<sup>49</sup>லியை வாங்கிப் புக[ட்டு] வெறெ  
 யொ<sup>50</sup>தமான சூலா<sup>51</sup>லி [வை\*]வக்கப்படும். யிந்த ஓ<sup>52</sup>வ<sup>53</sup>த்தை  
 யின்னபடி செய்கிறதென்கைக்கி யிந்த கெக்கெய்ய<sup>54</sup> வ<sup>55</sup>தா<sup>56</sup>  
 கர்கள்.....<sup>57</sup>வராயளு<sup>58</sup>டெனெ.....<sup>59</sup> [கெக்கெய்ய<sup>60</sup>ஃ].....<sup>61</sup>  
 .....<sup>62</sup>வெறெ யொருவர்க்கு சிலவிட சுயிகார<sup>63</sup> கூட்டாது.  
 கொவிலாரும் வ<sup>64</sup>ர<sup>65</sup>ஷகாரியு முள்<sup>66</sup>கெய்ய<sup>67</sup>யிருந்து.....<sup>68</sup>  
 கெக்கெய்ய<sup>69</sup> வ<sup>70</sup>தா<sup>71</sup>கர்களும் வ<sup>72</sup>ர<sup>73</sup>ஷகாரியும் உள்க்கையா

1. 'சுபெஷபெஷ' என்று வாசிக்க.
2. 'பிரஸந்தராயெழுந்தருளி' என்று பூர்த்தி செய்யலாம்.
3. 'ஸஹியியிறெ ததூக் காரொவித லாந' என வாசிக்க.
4. 'சுமரம்மொவதாரங்கள்' என்று வாசிக்க.
5. 'பின் வாங்காமல் பூஸ்திதி உண்டாக்கி' என்று பூர்த்திசெய்ய  
லாம்.
6. பாகவதர்களின் பெயர் சரியாக விளங்கவில்லை.
7. 'தரோகம் செய்தால்' எனப் பூர்த்தி செய்யலாம்.

யிருந்து டிரோஹம் பண்ணினால் திருக்கொயிலயிகாரிகளாலே  
தெண்டிக்கப்பட்டும் ஹவ்யூதிக்கி ஏர்ப்பட்டத்தின் மணியக்  
.....டிரோ[\*]ஹம் கண்டால் வ-ஹ-ஷகாரி விவாஹெனெ  
பண்ண சுயிகாரஹண்டு. யிந்த கெஹ்ய-ஹ வஜாவகர்களுக்கு  
வாஹிவஹியியில் அருளப்பாடுகூறங்கள் தெறும். யிவர்க.....  
டுப் பரியட்டம்<sup>1</sup> திருமாலே ஸ்ரீஹ்மொவம் மய-ஹெஹெ நடப்பிக்கப்  
படும். அன்றன்றறும் கெஹ்ய-ஹ வஜாஹ்-ஹகாரி வ-ஹ-ஷகாரி  
யானவன் அளந்தும் நிறுத்து[ம்\*].....வூக்கப்படும்[||\*]

கதிரி

Kadiri

இவ்வூர் மதுரை ஜில்லாவில் திண்டுக்கல் தாலுகாவில் பழைய கன்னி  
வாடி ஜமீனில் அடங்கியதாக இருக்கவேண்டுமென்று தோன்றுகிறது.  
கதிரி என்ற பெயர்கொண்ட ஊர்கள் வேறு சிலவும் தமிழ்நாட்டில் உள்ளன.  
ஆந்திர ராஜ்யத்திலே அனந்தப்பூர் ஜில்லாவிலே கதிரி என்ற ஓர் ஊர்  
இருக்கிறது. அவ்வூரில் உள்ள நரசிம்மஸ்வாமியின் ஆலயம் பிரசித்தமானது.  
அதைப் பின்பற்றியே தமிழ்நாட்டில் இக்கோயில் ஏற்பட்டதுபோலும்.

The place should be situated in the Dindigul Taluk, (included in the  
old Kannivāḍi Zamin) in the Madurai District. There are also some  
other villages in the Tamil country with this name. The place and the  
temple are evidently replicas in the South of the famous Narasimha  
temple at Kadiri in the Anantapur District of the Andhra State.

சாசனம்—1299]

[D. 3240.

Record dated in Kali 4[9\*]05, S'aka 1726, Raktakṣi, Āvaṇi 21,  
registering the grant of the *kāṇiyāṭchi* rights of service as *dāsī* (i.e.,  
dancing girl attached to the temple) in the first (*koṭṭu*) batch in the  
temple of Kadiri Narasimha-p-perumāḷ together with some lands, both  
wet and dry, as *mānya* for the same, to Annam, daughter of Periya  
Kamu who was enjoying the rights of service for a long time previous-  
ly by Malaiyaṇḍi Appaya Nayakkār, the chief of Kannivāḍi. The  
grant is very modern, the year being 1804 A.D.

சொஷ்தி ஸ்ரீ [||\*] விசையாற்புதய சாலீவாகன சகாஹ்த்  
தம் தளாஉயக கலியுக சகாஹ்த்தம் சத[க\*]ராடு யிதின மெல்ச  
செல்லா நின்ற ரத்தாட்சிவரு ஆவணியீ உயகவ ஸ்ரீமது

1. 'இவர்களுக்குப் பட்டுப்பரிவுட்டம்' என்று இருத்தல் வேண்டும்.

கன்னிவாடிக் கதிபதியாகிய மகாராச மானிய ராச ஸ்ரீ மலை யாண்டி அப்பய னாயக்கரவர்கள் ஸ்ரீ கதிரி நறசிங்கப் பெரு மாள் கோவில்த் தாசி முதல்\*]க் கொத்துப் பெரிய காழு மகள் அன்னத்துக்குக் காணியாச்சிப் பட்டயமெனாதிக் குடுத்தபடி காணியாச்சிப் பட்டயமாவது :

தனக்கு முன் னெடுகளும் புறதனமாயி ஸ்ரீ கதிரி நரசிம் மப் பெருமாள் கோவில் முதல்\*]க் கொடுத்துக்காக நஞ்சை புஞ்சை மானியம் விட்டு நடந்து னந்த காரியமாகச்செ யிப் பொது தனக்கு கிரைக்காட்டுக் கிராமத்துப் புலத்தில் புஞ்சை விரை கூ ஸ்ரீ தெத்துக் குளம் புரவில் நஞ்சை உா விரைப் புரவு மானியம் விட்டிருப்பதால் இந்த மானியமும் கோவிலில் முதல்\*] கொத்துக்கு நடக்குர சம்பளமும் வாங்கிக் கொண்டு பெரிய மெளம் சங்கீத மெளம் தன் செவுகமா[க\*]ச்செ அதற் குண்டாகிய சம்பளமும் கோவிலில் வாங்கிக் கொண்டு அந்த செவுகமுஞ் செவிச்சுக்கொண்டு சுகமெ இருக்கவும். இந்தப் பிரகாரம் தனக்குக் கோவிலில் முதல்\*]க் கொத்துக்காக கோவிலில் சம்பளமும் நஞ்சை புஞ்சை நிலமும் விட்டுக் கொடுத்திருப்பதினாலெ யென்றென்றைக்கும் ஆசந்திரார்க்க மாயி புத்திர பைத்திர பாரம்பரையாயி கல்லுங் காவெரியும் புல்லும் பூமியும் உள்ள வரைக்கும் ஆண்டு அனுபவித்துக் கொண்டு சுகமெ யிருக்கவும்.

ஸ்ரீ ராமா வென்னும் மலையாண்டி அப்பய னாயக்கரவர் களென்னும் ஒப்பம்.

மூன்றாம் பாகம் இரண்டாம் பகுதி முற்றம்.

1. 'ஹை' என்பது போன்ற ஒரு குறியீட்டினால் எழுதப்பட்டிருக்கிறது.

2. 'பெளத்திர' என்று வாசிக்க.



## APPENDIX—I—பிற்சேர்க்கை

பின்வரும் மூன்று சாசனங்களுக்கும் கர்னல் மக்கென்ஸியின் உதவியாளர் எடுத்திருந்த பிரதி கிடைக்கவில்லை யென்று தெரிவித்து இவற்றின் சுருக்கம் மட்டுமே மூன்றும் பாகம் முதல் பகுதியில் கொடுக்கப்பட்டுள்ளது. ஆயினும் பிறகு இந்தச் சாசனங்களின் பிரதிகள் கிடைத்தன. அவை இவ்விடம் கொடுக்கப்பட்டுள்ளன.

The text of the following three inscriptions prepared by the assistants of Col. Mackenzie were not available previously and hence summaries alone were given in Part I of Vol. III. The texts have since been traced and are given hereunder.

சாசனம் — 1256]

[D. 2944-சு

[தேவாங்க பாதாள மடத்துக்குச் சிலாசாசனம் எழுதியிருக்கிறதுக்கு விபரம்.]

Stone inscription relating to the *Dēvaṅga-pāṭāla-maṭha*.

Record dated in Śaka 1[4\*]64, Plava, Vaikāśi 10, in the reign of the Vijayanagara king **Achyutadeva Maharaya** registering the sale of land by Maruḷa Siddhayya, evidently a *viraśaiva* of Pāmbūr in Jayāṅkoṇḍaśōḷamaṇḍalam to Dēvaṅga Pattar, a religious head of the Viraśaivas. It stops with the preamble. Particulars of the sale are not found.

The Ś'aka year was current and so the intended date would be Saturday, May 7th, A.D. 1541, though not verifiable. The mention of Jayāṅkoṇḍaśōḷa maṇḍalam, the other name of Toṇḍaimaṇḍalam would suggest that the seller was a native of that area, even though no village with the name of Pāmbūr is known in that area.

The name of the religious head may also be read as Śāraṅgadēva *alias* Dēvaṅga Pattar. There is a Viraśaiva maṭha, the head of which is known as Śāraṅgadēva, in the Kannaḍa country.

சுவத்தி ஸ்ரீ<sup>1</sup> [11\*] சமஸ்த்த திருபுவன பவன வினுத விபு தன மெருவக்கண்ட பாகபற்த்தலண்டம் ஸ்ரீமதுங்களாம்பா தெவற் ஸ்ரீ சண்டணி தெவி னவலித ஸ்ரீ பாதபாம்சாறங்க தவனென தெவாங்க பத்தருக்கு<sup>2</sup>.

சொவஸ்தி[11\*] ஸ்ரீமன் மகா மண்டலெசுவறன் பாஷைக் கித் தப்பவருயகண்டன் மூவருய கண்டன் புறுவதிஷண பஷி உத்திற சதுற் சமுத்திரதிபதி ஸ்ரீ யச்சுதப்ப தேவ மகாராயற் பிறுதிவி ருச்சியம் பண்ணி அறுளா நிண்ட சாலியவாகன சிகாப்தம் ஸ்ரீ ச[ச\*] ஸாயச யிதின் மெல் செல்லா நிண்ட ப்லவ(வ்) ஸ்ரீ வைய்யாசி மீ ய உ செயங்கொண்ட சொழ மண் டலத்துக்கு பாம்பூர் பிறந்தனா மறுள சித்தய்யா தெவாங்க பத்தற்களுக்கு விலைப்பிறமாணம் குடிப்பிவிப்பத்தது [11\*]<sup>3</sup>

சாசனம் — 1257]

[D. 2944-௭

[சாசனம் எவ்விடத்திலிருந்து பிரதி செய்யப் பட்டதென்பது குறிக்கப் படவில்லை. சாசனத்தில் தலைப்பிலே 'தாம்ர சாசன நகல்' என்று தெலுங்கில் எழுதப்பட்டுள்ளது.]

Record dated in Kali 4517, Śaka 1349, Plava, Maṣi, 21, Wednesday, Śu. pañchamī and Rōhiṇī in the reign of the Vijayanagara ruler **Vira Singaraya Deva Maharayar** registering the sale of one half of the village of Vellōḍai, adjoining Kummaṅgalam, otherwise known as Chaturvēdimaṅgalam, which was a *Tiruvēḍaiyāṭṭam* village of Tiruvēṅkaṭam-udaiyān; i.e., Śrī Vēṅkaṭēśa of Tirupati, to the south of the Āraṇi river in the Paiyyur-kōṭṭam, a division of the Chandragiri rājya, comprised in the Tōṇḍaimaṇḍalam *alias* Jayanḱoṇḍaśōḷamaṇḍalam by

1. 'ஸ்வஸ்தி ஸ்ரீ' என்று வாசிக்க.

2. இந்தப் பகுதி வீர சைவர்களுடைய குருக்களான தேவாங்க பத்தருடைய பிரசஸ்தியைக் கொண்டுள்ளது. மிகவும் பிழைபடப் பிரதி செய்யப் பட்டிருக்கிறது. குருக்களுடைய பெயரைச் 'சாரங்கதேவராகிய தேவாங்கப் பத்தர்' என்றும் வாசிக்கமுடியும். கன்னட தேசத்திலே 'சாரங்கதேவ மடம்' என்னும் வீரசைவ மடம் ஒன்று இருப்பதாகவும் தெரிகிறது.

3. சாசனம் இதனோடு நின்றுவிடுகிறது பூர்த்தியாக இல்லை. விலைப் பிரமாணத்தின் விவரம் கிடைக்கவில்லை.

Muttu Nayakkan, son of Anḍiyappa Nayakkan of Vanniyaraya-gōtram and others to Kōṭṭai Periya Bommū Cheṭṭi, a *vaiśya* of Uppa-lagam of the same naḍu, Kōṭṭam and Maṇḍalam for 125 new Paḷa-vērkaḍu (Pulicat) *varāhan*.

The original copper plate is now deposited in the Government Museum at Madras having been received from the Collector of Chingleput and registered as **Private Grant No. 4** in the *Catalogue of the Copper-plate grants*. The cyclic year was Plavaṅga, equivalent to A.D. 1427-8. The other details are irregular.

சுப[!]\*<sup>1</sup> ஸ்ரீமன் மகா மண்டலேசுவர அரிருயல விபாடன் பாஷக்குத் தப்புவருய கண்டன் கண்ட னுடு கொண்டு கொண்ட னுடு கொடாதொன் உத்திர தெவ்சன பச்சமி பூர்வ சத்த சமுத்திரதிபதி<sup>2</sup> ருச ருச பறமெஸ்பர ருசமார்த் தாண்ட ருச கெம்பிற ருச குல திலக துலுக்க தள விபாடன் துலுக்க மொகரந் தாவுத்தொன்<sup>3</sup> அசுர தள விபாடன்(க்) க(டை)க சூறகாறன் கல்லியான பூறுவருதிசுவரன் எக[!]\*ங்க வீரன் [வீர]<sup>4</sup>வினொதன் வீர வல்லாள தெவன் தலை குண்டு கண்டவன் திருபுவ[ன\*]னாருயண அஷ்ட்ட திக்கு மனெபயங்க ரன் அசுவபதி கெசபத சத்தாங்க<sup>5</sup> வயிரி பதிநெட்டு வன்னியர் கள் தலை(க்)குண்டு கண்டன் இகலொக பாலகன் பூலொக புறந் தரன் எம்மண்டலமுங் கொண்ட ராசமாற்த்தாண்டன் வீற லக்ஷமி விசைய லக்ஷமி வரபுத்திரன் ஸ்ரீ வீரங்கருயர் தேவ மகாருயர் பிறிதிவி ருச்சியம் பண்ணி அருளாயி நின்ற கலியு காந்தம் ஓரு சந்நாபன சாலிவாகன் சகார்த்தம் ஓரு தநாசயக-க்கு மெல் செல்லாயி நின்ற ப்லவ<sup>6</sup> ஓரு மாசி மாசம்

1. 'ஸ்வஸ்தி' என்று வாசிக்க.
2. 'உத்தர, தக்ஷிண, பச்சிம, பூர்வ சதுஸ் ஸமுத்திராபதி' என்று வாசிக்க.
3. 'தவிர்த்தோன்' என வாசிக்க.
4. இருதலைப் பகரங்களுக்குள் அடங்கிய எழுத்து மூலத்திலே 'ஷா' என்பது போலவும் தோன்றுகிறது.
5. 'கெசபதி சத்திரபதி' என்பதே இவ்விதம் எழுதப்பட்டிருப்பது போலும்.
6. இது 'பிலவங்க' என்ற இருக்கவேண்டும்.

உமக உ புதன் கிழமையும் பூற்பவகூ பஞ்சமியும் ரொகணி  
 நஷ்சத்திரமும் பெத்த யித்தனாள் எழுதிய விலையாவன<sup>1</sup> கையி  
 எழுத்து: செயங்கொண்ட [சொழ மண்டலமான\*] தொண்  
 [மை\*]ட மண்டலத்தில் சந்தரகிரி ருச்சியத்தில் கிழக்கரையான  
 மெய்க்குன்ற வளனாடான பையபூர் கொட்டத்தில் ஆறணி  
 ஆத்தின் தென் கரையான<sup>2</sup> திருவெங்கடமுடையான்திருவிளை  
 யாட்டு கிரு[ம\*]மான சதுர்வெத மங்கலத்துக்கு பிறிதினும்  
 மான கும்மங்கலத்துக்கு அடுத்த வெள்ளொடையிலிருக்கும்  
 வன்னியரூய கொத்திர ஆண்டியப்ப னாயக்கன் குமாறன்  
 முத்து னாயக்கன் உள்ளிட்டானவரும்<sup>3</sup> எங்கள் காணி  
 காக்க<sup>4</sup> கிரமமான வெள்ளொடை பாதி கிரமம் கொள்வாரெ  
 வென்று மொரை கூற யிம்மொழி கெட்டு யிதற்க் கெதிர்  
 மொழி குறித்தொன் யிம் மண்டலத்தில் யிக் கொணத்தில்  
 யின்ன[ர\*]ட்டில் உப்பளகத்தலிருக்கும் வயிசியரில் கொட்டை  
 பெரிய பொம்மு செட்டி உள்ளிட்டார்<sup>5</sup> னங்கள் கொள்  
 வொமென்று பிற்கூர முரைகூறிய முத்து னாயக்கன் உள்  
 ளிட்டாருனவரும் பி(ன)ர் கூரிய கொட்டை பெரிய பொம்மு  
 செட்டி யிவை யிருதிரவரும்<sup>6</sup> எம்மிலிசைந்து தம்மிலப் பொ....ந்  
 திருமங்கலம் மன்னா மணக்களவா முன்பாக யி...லையாக நிற்ப்  
 செற்த<sup>7</sup> பாசிப்படாத பழவெர்க்காட்டு புது [வறாகன்]' ஈஉரு.  
 யிந்த வறாகன் னாத்து யிருவத்து அஞ்சக்கும் ஈஉ-அடி  
 கொலால் குழி ஈகூஅரு-க்கு பாதிக்கி குழி ஈகூஅஉரு-க்கு  
 கரை கபுரி விலையாக வித்து பொருள் கையிக் கொண்டோம்.

1. 'விலையாவணம்' என்று வாசிக்க.
2. மூலத்தில் 'கரையனை' என்று எழுதியிருப்பதுபோல் தோற்று  
 கிறது.
3. 'உள்ளட்டா ரனைவரோம்' எனக் கொள்க.
4. 'காணியாட்சி' என்று வாசிக்க.
5. 'இவ்விருதரத்தவரும்' என வாசிக்க.
6. 'எம்மில் இசைந்து தம்மில் பொருந்திக் கும்மங்கலம் ஆவணக்களரி  
 முன்பாக இதுவே விலையாக நிச்சயித்த' என்று கொள்ளவேண்டும்.
7. வராகன் என்பது 'வீஉ' என்ற குறியீட்டால் எழுதப்பட்டிருத்  
 து.

யிதுவெ விலையாவதாகவும். யிதுவெ விலைபிறமாணமதாகவும். யிரு(க்)காலாவது முக்காலாவது யிதுவெ விலையாவதாகவும். யிந்த காணிகாவுஷ்யெ<sup>1</sup> தாங்களெ சந்திரதித்தவரைக்கும் தாங்களெ அனுபவித்துக்கொள்ளக்கடவுறாகவும். யிப் பிரம[ர]ணத்துக்கு யிந்த காணிகாவுஷ்யெ<sup>2</sup> யாதொரு கல்லுமில்லை.<sup>3</sup> கலனுளதாயி தொத்தபட்டால் நாங்களெ முன்னின்று கலன் தி[\*]த்து குடுக்க கடவொமாகவும். யிப்படிக்கு சம்மதித்து எங்கள் காணிகாவுஷ்யெ<sup>3</sup> கிறைய சாதனம் பண்ணி கொடுத்தோம் கொட்டை பெரிய பொம்மு செட்டிக்கு(ம்) முத்து னுயக்கன் உள்ளிட்டாரும்ஓம். யிவை கைமண்டாங்கலம் முத்து னுயக்கன் கையி எழுத்து.

யிதுக்கு சாவுஷ்யெ<sup>4</sup> கும்மங்கலம் முத்தியப்ப னுயக்கன்.

சின்னகாமணம் மன்ன நெட்டி முதலியார்.

பெரிய காமணம் நயினியப்ப முதலியார்.

பொன்னகரி பல்லவ வெங்கிட்ட முதலியார்.

யிவர்கள் சொல்ல எழுதின நன்மைக்கி ஊற் கணக்கு சின்னநயினாப்பிள்ளை எழுதின சட்டம். யிந்தச்சட்டப்படிக்கு சயனபரம் தானப்பாசாரி. பொட்ட வெட்டு முத்தியப்ப ந[\*]யக்கன் கையி எழுத்து.

மன்னநெட்டி முதலியார்<sup>5</sup> கையி எழுத்து.

தறனியப்ப முதலியார் கயி எழுத்து.

பல்லவ வெங்கட்ட முதலியார் கையி எழுத்து.

பகயி மனடாங்கம் முத்து னுயக்கன் கையி எழுத்து. ௨

சாசனம் — 1258.]

[D. 2944-14

[இதுவும் ஒரு தாம்ர சாசன நகல் என்று தெலுங்கு எழுத்தில் தலைப் பிலே குறிக்கப்பட்டுள்ளது.]

1. 'காணியாட்சியை' என வாசிக்க.
2. 'கலனும் இல்லை' என்று வாசிக்க.
3. 'காணியாட்சி' என்பதே இவ்விதம் எழுதப்பட்டிருப்பது.
4. 'சாட்சி' என்று கொள்க.
5. 'கூயார்' என்று எழுதப்பட்டுள்ளது.

Record dated in Kali 4319, Śaka 1351, Vikāri, Sittirai 21, Monday, Śu. pañchamī, Rāhīnī in the reign of the Vijayanagara ruler **Vīra Singaraya Raya Deva Maharaya** registering the sale of one half of Krishṇan-ōḍai, adjoining Kummaṅgalam, otherwise known as Chaturvēdimaṅgalam, which was a *tiruvīḍaiyāṭṭam* village of Tiruvēṅkaṭam-udaiyan, i.e., S'ri Vēṅkaṭēśa of Tirupati, to the south of the Āraṇi river in the Paiyyūr-Kōṭṭam, otherwise known as Meykkunra-vaṇaṇḍu [a division] in the eastern *karai* of the Chandragiri-rājya, comprised in in the Jayaṅkoṇḍaśōḷa maṇḍalam *alias* Toṇḍaimaṇḍalam by Munniyappa Nāyakkan, son of Mūkka Nāyakkan of Vanṇiyarāya gōtram and others to Āraṇi Setṭiyappa Setṭi, a *vaiśya* of chinna-Kavaṇa-maṅgalam of the same naḍu, kōṭṭam and maṇḍalam for 115 *Paḷavērkōḍu-pudu-varāhan*.

The original copper-plate is now deposited in the Government Museum at Madras, having been received from the Collector of Chingleput in the year 1858 and registered as **Private No. 5** in the *Catalogue of the Copper-plate grants*. The Śaka equivalent of the cyclic year Vikāriṇ would be 1341 and the Kali 4520. The other details of the date are irregular,

சுப<sup>1</sup> [||\*] ஸ்ரீமன் மஹா மண்டலெஸ்ப[ர]ன் அரியருயல விபாடன் பாஷக்கு தப்புவுருயர கண்டன் கண்டனாடு கொண்டு கொண்டனாடு கொடாதொன் உத்திர தெஷ்ஷின பச்சமி பூர்வ சற்ற சமுற்றிரருதிபதி ருசருச பறமெஸ்பற ருசமாற்த் தாண்ட ருச கெம்பிர ருச குலத் திலக துலுக்க தளவிபாடன் துலுக்க மொகரந் தவுத்தொன் அசுர தளவிபாடன் கடக குறைக்காரன் கலியாண பூருவருதிசுவரன் எக[ர\*]ங்க வீரன் விறவினெதன் விற வல்லாள தெவன் தலை குண்டு கண்ட வன் திரிபுவன் ருயன் அஷ்ட்ட திக்கு மனெ பயங்கரன் அசுவபதி கெசபதி சத்தாங்க வாயிரி பதினெட்டு வன்னியர் கள் தலைகுண்டு கண்டன் னாகலொக பாலகன் பூலொக புரந் திரன் எம்மண்டலமுங் கொண்ட ருசமாற்த்தாண்டன் விற லஷ்ஷிமி<sup>2</sup> விசைய லஷ்ஷிமி<sup>3</sup> வரபுத்திரன் ஸ்ரீவிறச்சிங்கருய ருயர் தேவமகாருயர் பிறிதிவி ருச்சியம் பண்ணி அருளாய்

1. 'ஸ்வஸ்தி' என்று வாசிக்க.
2. 'வீரலக்ஷ்மி' என்று வாசிக்க.
3. 'விசைய லக்ஷ்மி' எனக் கொள்க.

நின்ற கலியுகாந்தம் ஸ்ரீ சதுராயுக சாலிவாகண சகார்த்தம்  
ஸ்ரீ சதுராயுக-கு மெல் செல்லாயி நின்ற விகாரி ஸ்ரீ சித்திரை  
மீழ உயிச வ சொம வாரமும் பூருவ பஷஷ பஞ்சமியும்  
ரோகணி நஷஷத்திரமும் பெற்ற யித்தனாள் எழுதிய விலையா  
வணக்கை எழுத்து. செயங்கொண்ட [சொழி மண்டலமான\*]  
தொண்ட மண்டலத்தில் சந்திரகிரி ருச்சியத்தில் கிழக்கரை  
யான மெய்க்குன்ற வளனாடான பையூர் கொட்டத்தில்  
ஆறணி ஆத்தின் தென் கரையான திருவெங்கடமுடையான்  
திருவிளையாட்டு கிருமமான சதுர்வெத மங்கலத்துக்கு பிறிதி  
மைமான கும்மங்கலத்துக்கு அடுத்த கி[ரு\*]ஷ்ணன் ஓடையில்  
யிருக்கும் வன்னயரூய கொத்திரம் முக்கா னுயக்கன் குமா  
ரன் முன்னியப்ப னுயக்கன் உள்ளிட்டாரவரும்ஓம். எங்கள்  
காணிகாஷ்ஷி<sup>1</sup> கிருமமான கி[ரு\*]ஷ்ணன் ஓடை கிருமம்  
பாதி கொள்ளுவாரொ வென்று முறை கூர யம்மொழி  
கெட்டு யிதற் கெதிர்மொழி கொடுத்தொன் யிம் மண்டலத்  
தில் யிக் கொணத்தில் யின் நாட்டில் சின்ன காவண மங்க  
லத்திலிருக்கும் வயிசியரில் ஆறணி செட்டியப்ப செட்டி உள்  
ளிட்டார்ஓம் னங்கள் கொள்ளுவொமென்று பிற்கூற முறை  
குறிய மு[க்\*]கா னுயக்கன் குமாரன் முத்தியப்ப னுயக்கன்  
பி(ை)ற் கூறிய செட்டியப்ப செட்டியும் யிவை யிருதரவரும்  
எம்மிவி[ரை\*]சந்து தம்மில் பொரிந்தி கும்மங்கலம் மண்ணுமனக்  
கற்.....ஊர்முன்பாக விலையாக நிர்ச்செய்த பாசி படாத பழ  
வெர்க்காட்டு புது ன (வராகன்) ஈட்டு. யிந்த விரகன்  
னாத்து பதினஞ்சுக்கும் ஈடு அடிக் கொலால் [குழி]<sup>2</sup>  
சது-க்கு பாதி [குழி] உது-க்கு கரை ௧9 பஞ் சூ-ம் கிழ[ரை\*]ரயும்  
விலையாக வித்து பொறுள் கைக்கொண்டோம். யிதுவெ  
விலையாவதாகவும். யிதுவெ விலைப்பிரமாணமதாகவும். யிரு(க்)  
காலாவது முக்காலாவது யிதுவெ விலையாவதாகவும். யிந்த  
காணிகாஷ்ஷியை<sup>1</sup> தாங்கனெ சந்திராதித்தவரைக்கும் அனுப  
வித்துக்கொள்ளக் கடவிராகவும். யிப்புரமானத்துக்கு<sup>3</sup> யிந்த  
காணிகாஷ்ஷிக்கி யாதொரு கலனும் யில்லை. கலனுள்ளதாய்

1. 'காணியாட்சி' என வாசிக்க.

2. குழி என்பது மூலத்தில் 'து' என்பதுபோன்ற குறியீட்டால்  
எழுதப்பட்டிருக்கிறது.

3. 'இப் பிரமாணத்துக்கு' என்று வாசிக்க.

தொத்தப்பட்டால் னாங்களே முன் நின்று கலந் தித்து குடுக்கக் கடவொமாகவும். யிப்படிக்கி சம்மதித்து எங்கள் காணிகாஷ்ஷி கிரைய சாதனம் பண்ணி கொடுத்தொம் ஆரணி செட்டியப்ப செட்டிக்கு(ம்) முத்துனாயக்கன் உள்ளிட் டாரு(க்கு)ம் ஓம். இவை னாகமண்...ரங்கம் முத்து னாயக்கன் குமாரன் முத்தியப்ப னாயக்கன் எழுத்து. ௨

யிதுக்கு சாஷ்ஷி கும்மங்கலம் வெள்ளை ரெட்டி னாயக்கன்.

பொன்னபரி முத்தியப்ப முதலியார்.

சின்னகாவனம் மன்ன முத்தியப்ப முதலியார்.

பெரியகாமணம் வெங்கட்ட முதலியார்.

யிவர்கள் சொல்ல ஊர்க்கணக்கு பெரிய நயினா பிள்ளை யெழுதின சட்டம் ச[ய]னவாம முர்த்தியாசாரி.

பொட்ட வெட்டு வெள்ளை ரெட்டி னாயக்கன் கையி எழுத்து. ௨

பல்லவ முத்தியப்ப முதலியார் கையி எழுத்து. ௨

பண்ண முத்தியப்ப முதலியார் கையி எழுத்து. ௨

வெங்கிட்ட முதலியார் கையி எழுத்து. ௨

யிந்த சயிகை மாண்டங்கம் முத்தியப்ப னாயக்கன் கை எழுத்து. ௨



## APPENDIX II

### ADDITIONS AND CORRECTIONS

While checking the inscriptions in the first two volumes of the work with those in the *List of Inscriptions from the Southern Districts* compiled by the assistants of Col. Mackenzie some differences in the details of the records were found between the two. Some of the important differences are given below.

113. This inscription is said to be found on the western side of the stair on the northern steps of the spire 'Vallāḷa-Raya gōpūram' in the temple.

133. The Śaka date is given 1409.

148. The Śaka year is given as 1504.

160. The date of the inscription is given as the 37th regnal year of Rājarajadēva.

195. The Śaka year is given as 1431.

229. The record as per the text published is undated. But the date regnal year 20 is found in the *List*.

251. The record is stated to have been engraved on a stone in the *Mahāmaṇḍapa* in front of the Saundaranāyaki amman shrine in the temple [of Tiruppāṇḍikkoḍumuḍi Āḷuḍaiya-Nāyanār] and dated in the 2nd regnal year of 'Sundara Paṇḍya Kēsarivarma Dēvar,' evidently a Koṅgu Paṇḍya king **Sundara Pandya**.

264. The Śaka year is given as 1427.

280. The Śaka year is given as 1625, while that found in the published text is [126]5.

281. The Śaka year is given as 1627.

302. The Kali year is given as 4632.

368 (g) The Śaka year is given as 1193.

559. The *List* gives the Śaka date as 1299.

612. It is stated that this inscription is dated in the 21st regnal year of the king and registers the grant of some land to god Mahādēvar for the lamp (ceremony).

614. The regnal year of the king is found as the 24th.

701. It is mentioned that the record belongs to the time of **Chokkalinga Nayakkar**, the ruler (*Svāmi Karttākaḷ*) of Madurai.

721. This inscription is said to be found in the village of Talaiyūr.

808. The inscription is said to be of the reign of [the Vijayanagara ruler] **Hariyappa Udaiyar** (Aureyapa Vadeyar) and the cyclic year Sadharaṇa.

884. The Śaka year is given as 1611.

908. The regnal year of the king is given as the 8th.

976. It is stated that the record was found in the village of Chumpika.

989. The Śaka year is given as 1514 though it is not found in the text as printed.

Page 718. Renumber the inscriptions 770 and 771 as 771 and 772

473. This appears to have been copied by the Epigraphy Department and registered as No. 60 of 1909.

1900. 10-ஆம் வரியில் 'தலைநீர் பாடுகால்' என்று இருப்பதை 'தலைநீர் பாடு கால்' என்று வாசிக்க.

### பிற்சேர்க்கை—III

#### சாசனச்சொல் அகராதி

[சாசனங்கள் பெரும்பாலும் முன்னாளிலே நடந்த தான தருமங்கள், நில விக்கிரயங்கள் ஆகியவற்றின் ஆதாரபத்திரங்கள் ஆகும். ஆகவே, அவற்றில் காணும் சொற்கள் பழைய வழக்குக்களையும் அந்நாளிலே அந்த அந்தச் சொற்களுக்கு ஏற்பட்டிருந்த குறிப்பிட்ட பொருளையும் உணர்த்துவன. அவற்றுள் பெரும்பாலானவை இப்போது வழக்கு ஒழிந்து விட்டன. வழக்கில் உள்ள சிலவற்றுக்கும் பொருள் மாறி இருக்கும். முன்னாளில் அவை வழங்கி வந்த பொருளிலேயே இன்றும் வழங்கவில்லை. ஆகவே, சாசனங்களில் காணும் விஷயங்களைச் சரியாக அறிந்துகொள்வதற்கு அத்தகைய சொற்களின் பொருளை விளக்கிக் கூறும் தனி அகராதி ஒன்று அவசியமாகும்.

இந்நூலின் இரண்டாம் பாகத்தில் சில சொற்களை—பெரும்பாலும் அவை அந்நாளில் வழங்கிய வரிகளைப் பற்றியவை—அவற்றின் பொருள் விளக்கத்தோடு அவ்விதம் கொடுத்திருந்தேன். அது ஆராய்ச்சியாளர்களுடைய கவனத்தை மட்டுமே யல்லாமல் வேறு துறையில் உள்ள சிலருடைய கவனத்தையும் ஈர்த்ததாகத் தெரிகிறது.

சாசனங்களில் காணும் சொற்களைக் கூர்ந்து ஆராய்ந்தால், நம் முன்னோர்கள் நடத்தி வந்த வாழ்க்கை, அவர்கள் நாளில் அரசியல் அமைந்திருந்த முறை, அது வளர்ந்த வரலாறு, செயலாற்றிய விதம் முதலிய பலவும் நன்கு விளங்கும். நம் நாட்டு மொழியிலே அரசியல் நடந்து வந்த அந்நாளில் நிர்வாகத் துறையில் வழங்கிவந்த சொற்களும் தொடர்களும் தழிழையே அரசாங்க மொழியாகக்கொண்டு நம் ராஜ்யத்தின் நிர்வாகத்தை அம்மொழியிலேயே நடத்த வேண்டுமென்று விரும்பும் இந்நாளில் பெரிதும் உதவி புரியும்.

இந்நூலில் கொடுக்கப்பட்டுள்ள சாசனச்சொல் அகராதி, “சாசன வழக்கில் கிடைக்கக்கூடிய எல்லாச் சொற்களையும் தொடர்களையும் தொகுத்து அவற்றின் பொருள் விளக்கத்தோடு ஒரு பிற்சேர்க்கையாக” இந்நூலிலே

கொடுக்க வேண்டுமென்று சென்னை அரசாங்கத்தார் 3—8—1954உ யுள்ள தங்கள் எம். எஸ். நெ. 1082 (எடுகேஷன்) உத்தரவில் தெரிவித்திருந்த விருப்பத்திற்கிணங்கத் தயாரித்துக் கொடுக்கப் பெற்றதாகும்.

சாசன வழக்கில் உள்ள எல்லாச் சொற்களையும் இவ்விடம் தொகுத்துக் கொடுத்திருப்பதாகச் சொல்லமுடியாது. அன்றி, இவ்விடம் கொடுக்கப்பட்டுள்ள பொருள் விளக்கத்தையும் முடிந்த முடிபாகக் கொள்ளமுடியாது. 1904-ஆம் ஆண்டு முதல் இதுவரையில் பிரதி செய்யப்பெற்ற சாசனங்களின் பெரும்பகுதி—ஏன், முழுவதும். என்றே கூறலாம்—இன்னும் வெளியாகவில்லை. அவை வெளியிடப்பெற்றால் எத்தனையோ புதிய விஷயங்கள் தெரியவரும். இப்போது அறிந்திருக்கும் விஷயங்களில் சில புதிய விளக்கம் பெறும். நாம் தவறாகக் கொண்டிருக்கும் விஷயங்கள் சிலவும் திருத்தம் அடையும். அந்த நிலையில் தயாரிக்கப்பெறும் சாசனச் சொல் அகராதியே பூர்ணமானதாகவும் நிர்ணயமானதாகவும் இருக்கமுடியும். ஆனால் அவ்விதம் நடப்பதற்கு நீண்ட காலம் பிடிக்கும்; சமீப காலத்தில் நிறைவேறக் கூடியதாகத் தோற்றவில்லை.

எனினும், இப்போது உள்ள நிலையிலும் அத்தகைய அகராதி ஒன்று தேவை என்பது மிகையாது. சாசன வழக்குகளை விளக்கிக் காட்டுவதில் அது ஓர் அளவாவது பயன்படும். அந்த நோக்கத்துடனேயே இந்த அகராதி கூடிய அளவு முக்கியமான சொற்களைத் தொகுத்துத் தயாரிக்கப்பட்டுள்ளது.

இவ்விடம் கொடுக்கப்பட்டுள்ள அகராதியிலே சொற்களுக்குச் சாசன வழக்கிலே காணப்பெறும் பொருள்கள் மட்டுமே கொடுக்கப்பட்டுள்ளன; அவற்றுள்ளும் பெரும்பாலானவை இலக்கிய வழக்குகளில் இல்லாமல் சாசன வழக்கில் மட்டுமே காண்பவை. அவ்விதம் அன்றி எல்லாச் சொற்களையும் சேர்ப்பதாக இருந்தால் மிகவும் விரிந்துவிடும்.]

## சாசனச்சொல் அகராதி

அக்கசாலை : நாணய சாலை

அக்கசாலை வரி : [நாணயங்களை அச்சிடுவதற்காக] நாணய சாலைக்கு இறுக்கும் வரி

அக்கம் : முன்னாளிலே வழங்கிவந்த ஒரு நாணயம் ; நாணய சாலையை யும் குறிக்கும்

அக்கன் : தமக்கையைக் குறிக்கும் மரியாதைச் சொல்

அக்காரவடிசில் : சர்க்கரைப் பொங்கல்

அக்காளி, அக்காளிப் பிரசாதம் : கோயில் பிரசாத வகை; அக்கார வடிசிலே போலும்

அக்கிரசாலை : பிராமணர்களுக்குச் சோறுபோடும் இடம்

அக்கிரம் : கோயிலில் மூர்த்திக்கு நிவேதனப் பொருள் ; அக்காரவடிசிலே இவ்விதம் குறிக்கப்படுகிறது போலும்

அக்கினிஷ்டை : விற்றது

அக்ரமகாதேவி : பட்டமகிஷிகளுள் மூத்தவள்

அக்ரமண்டபம் : கோயிலில் முன் மண்டபம் ; முக மண்டபம்

அகச்சுற்று : கோயிலின் உட்பிராகாரம்

அகநாழிகையார் : கோயில் கர்ப்பகிருகத்தை நிர்வகிப்பவர்

அகட்பரிவாரம் : அரண்மனையிலே பணி செய்யும் பரிவாரம்

அகம்படி : குடும்பம்; குடும்பத்தைச் சேர்ந்தது; உள் துறை; அந்தப்புரம்

அகம்படி உடையான் : குடி, குடிமக்கள் அல்லது குடும்பி

அகம்படிமுதலிகள் : அரண்மனை அந்தப்புரத்தைச் சேர்ந்த அதிகாரிகள் (அகம்படி மற முதலிகள்.....மூவேந்த வேளார்)

அகம்படிப்பெண்டுகள் : அரண்மனை அந்தப்புரத்தில் பணிபுரியும் பெண்கள்

அகமார்க்கம் : முக்குணம்பற்றி வரும் மெய்க்கூத்து ; கோயில்களில் ஆடப்பெறும் நாட்டிய வகை; தெய்வ சம்பந்தம் கொண்டது போலும்

அகரப்பற்று : பிராமணர்களுக்கு இறையிலியாக வழங்கப்பெற்ற நிலம்; அகரத்துக்குச் சொந்தமான நிலங்கள்

அகரப் பிரம்மதேயம் : பிராமணர் குடியிருப்புக்காகப் பெரும்பாலும் வரியில்லாமல் விடப்பெற்ற கிராமம்; அவ்வூர்ச் சபையையும் குறிக்கும்

அகரம் : அக்கிரகாரம் என்பதன் வேறு வடிவம்; அகரப்பிரம்மதேயம் பார்க்கு

அகவினை : இடையூறு

அகழி : சிறு பள்ளம்

அகழிதிருத்துதல் : சிறு பள்ளங்களைத் தூர்த்துச் சமமாக்குதல்  
(பஞ்சைத்திடல் கல்லி அகழி திருத்தி)

அகிதம் : கேடு ; இடையூறு ; தீமை ; தீங்கு ; சில சமயங்களில் அகுதம்  
- எனவும் காணப்படும்

அகை வாய்க்கால் : கிராமங்களில் நிலங்களுக்குத் தண்ணீர் பாயும்  
சிறு கால்

அகோவனம் : பரம்பூமி ; தரிசுநிலம்

அங்கசாலை : நடனசாலை

அங்கதேவதை : பரிவார தேவதை

அங்கமணி : மணப் பெண்ணுக்குக் கொடுக்கும் சீதனப் பொருள்

அங்கமணி திரவியம் : சீதனப் பணம்

அங்கரங்க வைபவம், அங்கரங்க வைபோகம் : சகல உபசாரங்களும்

கூடிய பூசை ; சோடச உபசார பூசை ; ராஜோபசாரம்

அங்கரகூடிகள் : மெய்காவலன்

அங்கவயிச்சியர் : (அங்கு வைத்தியன்) ஆயுள்வேத வைத்தியர்

அங்காடிக்கூலி ; அங்காடிப்பாட்டம் : கடைகளுக்காக இறுக்கும் வரி

அச்சத்தி : அச்சத்தறியே போலும்

அச்சு : முன்னளில் வழங்கிவந்த ஒரு நாணயம்

அச்சத்தி : தறிவகை ; அதற்கு இறுக்கவேண்டிய வரி

அச்சவரி : பொன்வரி என்பர். பொன்னை நாணயமாக அச்சிட இறுக்  
கும் வரிபோலும்

அச்சை : வேதவாக்கியம்

அஞ்சல்து சத்துச் சபை : (அஞ்சு + அஷ்டம் + சத்து + சபை) கிராமச்  
சபை வகை ; ஐந்து, எட்டு உறுப்பினர்களைக் கொண்டவை (ஐம்  
பெருங் குழு, எண்பேராயம் என்பனவே போலும்)

அஞ்ஞாழிக்கால் : ஐந்து நாழிகை அளவு கொண்ட படி

அஞ்சினான் புகலிடம் : துன்புறுவோருக்குப் பாதுகாப்பு அளிக்கும்  
இடம் ; அடைக்கலம் புகும் இடம். அபயம் எனவும் பெறும்

அஞ்சுபஞ்சாலத்தார் : பஞ்ச கம்மாளர் ; கம்மாளர் வகுப்பு ஐந்தைச்  
சேர்ந்தவர்

அஞ்சுவண்ணம் : பஞ்ச கம்மாளர் ; அவர்களுடைய சபை ; கன்னடத்  
திலே ஹஞ்ஜமந் எனப் பெறும்

அட்டவணை : அரசாங்கத்து வருவாயான தீர்வைகளை நிர்ணயித்து  
வசூலிக்கும் பிரிவு ; நிலவரி இலாகா ; அந்தத் துறையின் அதிகாரிகள்

அட்டிற்பேறு : கோயிற் பணியாளரின் விநியோகத்துக்குரிய பிர  
சாதக்கட்டளை

அட்டிற்பேறு : நீர்வார்த்துத் தானம் செய்யப்பெறுவது

அட்டிமுதல் : தானம் கொடுக்கப்பெற்ற சொத்து; அதன் வருமா  
னத்தை மட்டுமே உபயோகித்தல் வேண்டும்

அட்டுக்கிறை : தர்மத்துக்கு அளிப்பவற்றின்மீது விதிக்கும் வரிபோலும்  
அடக்கிராவி : நெல் வகை

அட[\*]ந்தேற்றம் : மொத்தமாக நிர்ணயிக்கப் பெற்ற வரி

அடவி : போர்ப்படை

அடவிமார், அடவுசெய்வார் : நெய்வோருள் ஒரு பிரிவினர்

அடவோலை : அடையோலை பார்க்க (அடைவோலையின் திரிபேபோலும்)

அடிக்காசு : சந்தையில் கடைக்காரர்களிடமிருந்து வசூலிக்கப்பெறும்  
வரி

அடிகள்மார் : (பக்தர்கள்) கோயிலில் நடனம் ஆடும் பெண்டிர்

அடிமைக்காசு : கோயில் ஊழியர்களிடம் வசூலிக்கும் வரி

அடியாள் : வேலைக்காரி

அடியுறை : பாத காணிக்கை; அடியிறை, அடியறை என்பன  
போன்ற வடிவங்களும் காணப்படுகின்றன

அடுக்களைப்புறம் : கோயில் மடைப்பள்ளிச் செலவுக்காக விடப்படும்  
மானியம்

அடுத்தூண் : ஒரு மாதச் செலவுக்கு வேண்டும் பணம்

அடைகுடி : பயிரிடுங்குடி

அடைகுத்துதல் : அடைமானம் வைத்தல்

அடை கொள்ளுதல் : ஒற்றியாகப் பெறுதல்

அடைதறி : கூலிக்கு வேலை செய்யும் தறி

அடைப்படி : அடைமானம்; அடைமானச்சீட்டு

அடைப்பம் : வெற்றிலைச் செல்லம்; வெற்றிலைச் செல்லத்தை ஏந்தி  
யிருப்பவன்; ராஜ சபையிலே அரசார்க்குப் பக்கத்தில் வெற்றிலைத்  
தட்டு முதலியவற்றைக்கொண்டு உடன் இருக்கும் அதிகாரி;  
அடைப்பு எனவும் அடைப்பக் காரன் எனவும் பெறும்

அடைப்பு : அடைமானம் பெற்றுள்ள நிலம்

அடைப்புமுதலிகள் : சபையின் காரிய நிர்வாகிகள்; நில அடைப்பைக்  
கவனிப்பவர் போலும்

அடை முதல் பற்று : குடிசைக்குப் பற்றாக அடைக்கப்பட்ட நிலம்

அடைக்காயமுது : பாக்கு; அடையமுது எனவும் பெறும்

அடையாள் : வேலைக்காரன் (அடையாளம் கொண்டவன்)

அடையேழுதுதல் : கணக்கில் எழுதுதல்.

அடையோலை : அடைமானச் சீட்டு

அண்ணாவி, அண்ணாழ்வி : தமையன்

அணுக்கர், அணுக்கியர் : அரசர் முதலியோரிடம் நெருங்கிப் பணிபுரி  
வோர்; அந்தரங்க ஊழியர்

அணுக்கச் சேவகம் : அணுக்கராகச் சேவை செய்வது

அணுக்க விளக்கு : கோயிலில் மூர்த்திக்குப் பக்கத்தில் எரியும் திரு  
விளக்கு

அத்தியயன விருத்தி : கோயிலில் சுவாமி சந்நிதியில் வேதம் ஓது  
வதற்கு விடப்பெற்ற மானியம் : அத்தியயனாங்கம் எனவும் பெறும்  
அதரஞ் செய்தல் : தடைசெய்தல்

அதிகரண தண்டம் : அதிகரணம் என்னும் நியாயசபை விதிக்கும்  
தண்டம்; அபராதம்

அதிகரணம் : நியாயசபை வகை : பிரதானமான சபையேபோலும்

அதிகாரப்போன் : பொன்னாக இறுக்கும் வரிவகை; அதிகாரவர்த்  
தனையே போலும்

அதிகாரவர்த்தனை : அதிகாரிகளுக்கு வழங்கும் காணிக்கை

அர்த்தஜாமப்புறம் : கோயிலில் அர்த்த ஜாமப் பூசை செய்வதற்காக  
விடப்பெற்ற மானியம்

அறையோலை : பறையறைந்து பிரகடனப் படுத்தவேண்டிய உத்தரவு  
அவனிவேதனம் : பாடி காவல்; ஊர்காவல்

அதிகாரிச்சி : அதிகாரியின் மனைவி; பெண்களிலே அதிகாரப் பதவி  
வகிப்பவரையும் குறிக்கும் போலும்

அதிகாரப் பேறு : அதிகாரிகளுக்கு வழங்கும் காணிக்கை; அதிகார  
வர்த்தனை பார்க்க

அதிகார மேலெழுத்து : கீழ் அதிகாரிகள் இட்ட கட்டளையை மாற்றி  
மேலிடத்தார் அளிக்கும் உத்தரவு

அதிர்காணி : (கிராம நிலங்களில்) காணியாட்சி உரிமை

அதிஷ்டானம் : இருக்கை; ஆசனம்; கோயில் விமானத்தின் அடிப்  
பகுதி

அந்தர வினியோகம் : உள்வரி வகையில் நீக்கப்பெற்ற தொகையை  
ஏற்றுக் கொடுப்பதில் வரும் பங்கு

அந்தராயக் காசு, அந்தராயப் பாட்டம் : அந்தராயம் பார்க்க

அந்தராயம் : உள்வரி; உள்வருமானம்; ஊர்ச்சபை, நாட்டவர் போன்ற  
ஸ்தாபனங்களுக்கு இறுக்கும் வரி



அந்தராள மண்டபம் : அர்த்த மண்டபம்; கோயிலில் முகமண்டபத் துக்கும் கர்ப்ப கிருகத்துக்கும் இடைப்பட்ட பகுதி

அந்திக் காப்பு : கோயிலில் கடவுளுக்கு மாலைக்காலத்தில் செய்யும் பூசை

அபய சாசனம் : புகலிடமும் பாதுகாப்பும் அளிப்பதாகத் தெரிவிக்கும் பத்திரம்

அபயம் : பாதுகாப்பு அளித்தல்; புகலிடம்

அபிஷேகக்காணி : அபிஷேகக் காணிக்கை பார்க்க

அபிஷேகக் காணிக்கை : மகுடாபிஷேகம் ஆனதும் அரசனை நேரில் கண்டு விசுவாசத்தைத் தெரிவித்துச் செலுத்தும் காணிக்கை

அபிஷேக நாமம் : பட்டம் கட்டப்பெறும் காலத்தில் தரிக்கும் பெயர்

அபிஷேகம் : தலையணி வகை; கிரீடம்

அபிஷேக மண்டபம் : திருமஞ்சன சாலை; குளிக்கும் இடம் என்றும் வழங்கப்பெறும்

அபூரி, அபூர்வி : வேதம் வல்லவர்; பெரும்பாலும் தலயாத்திரை செய்யும் பிராமணரை குறிக்கும்; மீமாம்சகரைக் குறிக்கும்போலும்

அபோஹனம் : பாழ் நிலம், தரிசு நிலம் (அகோவனம் போலும்)

அம்பலத்தார் : கிராமப் பொதுச் சபையார்

அம்பலம் : சபை; கிராமச் சபை கூடும் இடம்; சிவபெருமான் கோயில்

அம்பலப் புறம் : சிவன் கோயிலுக்கு விடப்பெற்ற நிலம்; தேவதானம்

அம்புமுதுபாடன், அம்புமுதுவரை : முத்து வகை

அமஞ்சி : கூலி இல்லாமல் வேலை செய்வது

அமரபக்ஷம் : அபரபக்ஷம்; தேய்பிறை

அமரம் : உயர்தர அதிகாரிகளின் நிர்வாகத்தில் விடப்படும் நிலப்பகுதி.

அதிலே அவர்கள் வரி வசூல் செய்து படை திரட்டி வேண்டும் போது அரசனுக்குச் சேவைபுரியத் தயாராக இருத்தல் வேண்டும். அரசாங்கத்துக்குத் திறைப்பணமும் செலுத்தவேண்டும். சிற்றரசுப் பதவி போன்றது

அமரநாயகம் : அமரப்பதவி

அமரமாகாணி : அமரநாயக்கனுக்கு அளிக்கப்பெற்ற நிலப் பகுதி

அமிர்த கணத்தார் : ஊர் நிர்வாகம் செய்யும் கணப்பெருமக்கள்;

கோயில் ரொக்க வருமானங்களைக் கணக்கிடும் சபையார்

அமுது(ப்)படி : அமுதுபடைத்தல்; நைவேத்தியம்

அர்ச்சலா போகம், அர்ச்சலா விருத்தி : கோயிலில் அர்ச்சனை நடைபெறுவதன் செலவுக்காக விடப்பெற்ற நிலம்

அர்ச்சனாவிபவகாணி : கோயிற் பூசகர்களுக்கு விடப்பட்ட இறையிலி நிலம்

அர்த்த சந்திரன் : (பாதி சந்திரன்) திருவாசியின் ஒரு பாகம்; ஓர் ஆபாண வகையையும் குறிக்கும்

அர்த்தாங்கி : மனைவி

அரக்கல் : அரசாங்கத்துக்குச் செலுத்தும் இறையைச் சிறு பகுதி களாகக் கட்டுவதற்கான தவணை

அரசு : காவல் சுதந்தரம்

அரசுப் பேறு : நாட்டுக் காவலுக்காக வசூலிக்கப்பெறும் வரி [மஹா ராஜப் பிரயோசனம் என்று தெலுங்கு நாட்டுச் சாசனங்களில் காணப்பெறுவது இதுவேயாக இருத்தலும் கூடும்.]

அரிகரு : மாகுல்; விளைவு

அரிகூலி : நெற்கதிர் அறுவடையின்போது அரியாகக் கொடுக்கும் கூலி அரிகோழி, அரிசித் துண்டம் : பழைய வரி வகை

அரிசிக் காணம் : அரிசி குத்துவதற்காக இறுக்கும் வரி; கூற்றரிசி எனவும் வழங்கப்படுவது

அரிப்புச்சரி : தொங்கல் ஆபாண வகை

அரிவாணம் : செப்புத் தாலம்

அருந்தோடு : (அருந்து + ஓடு) சாப்பிடும் தட்டுக் கணக்கின்மீது இறுக்கும் வரி

அரையன் : பழைய நாளில் மன்னர் அளித்துவந்த பட்டம்

அல்பயிறை : தானியமாகச் செலுத்தும் ஒரு வரி; சிறுவரி போலும்

அவசரம் : அரசன் பக்கத்திலே இருந்து அவ்வப்போது விஷயங்களை அரசனுக்கு அறிவிக்கும் அரசாங்க உத்தியோகங்களுள் ஒன்று

அவசரவர்த்தனை : அவசரம் என்னும் அதிகாரிக்குச் செலுத்தப் பெறும் காணிக்கை

அவதானம் : அவசானம், முடிவு

அவலமுதுப்புறம் : (அவல் அமுது + புறம்) அவல் நிவேதனத்துக் காகக் கோயிலுக்கு விட்ட இறையிலி நிலம்

அலிக்கிணறு : கோயில் சுவரிலே காற்றோட்டத்துக்காக இடும் துவாரம்

அலிரோதம் : விரோதம் இன்மை; நட்பு

அழகச்சு : ஒரு நாணயம் (அழகன் பெயரால் வழங்கிய அச்சு)

அழகேருதி, அழகேருது காட்சிக் காசு : நல்லெருது பார்க்க

அழிவு : பயிருக்கு நேரிடும் சேதம்

அழிவு : செலவு

அழிவு சேய்வான் : ஊவு செலவுகளை நிர்வகிப்பவன்

அழிவு பிழை : உரியகாலத்தில் செலுத்தாதற்காகக் கொடுக்கவேண்டிய தண்டம்

அழகல் சரக்கு : குப்பை கூளங்களைச் சேகரித்து [எருவாக்குதல் போன்ற] உரிமை போலும்

அள்ளாயம் : சந்தையில் விற்பனைக்கு வரும் சரக்குகளில் ஒரு பிடி அல்லது ஒரு குறிப்பிட்ட அளவு எடுத்துக்கொள்ளும் உரிமை; அள்ளு எனப் பெறுவதும் இதுவே போலும்

அளவர் : உமும் குடிகளுள் ஒரு வகையினர்; உப்பளத்தில் வேலை செய்வோர்

அளவு : நில அளவு, 'ஸர்வே'

அளு : சந்தையிலிருந்து பெறும் வரிவகைகளில் ஒன்று; அள்ளு, அள்ளாயம் என்பவை இதுவே போலும்

அற : முற்றும், முழுவதும்

அறங்காவல் : கோயில் முதலிய தர்ம ஸ்தாபனங்களைப் பாதுகாத்தல்

அறச் சாலா போகம் : அன்னசாலைக்காக வரியில்லாமல் விடப்பட்ட நிலம்; சாலாபோகம் என்றும் குறிக்கப்படும்

அறதேயன் : தர்மங்களைப் பாதுகாத்து நடத்துவோன்

அறவோலை : தர்ம சாசனம்

அறுதிமுறி : தீர்துபோன கணக்குச் சீட்டு

அறுமுறி : உடன்படிக்கைப் பத்திரம் (அறுதிமுறி?)

அறை காவல் : கோயிலில் உக்கிராணத்தின் நிர்வாகப் பொறுப்புள்ள அதிகாரி

அறையோலை : யாவரும் அறிவதற்காகப் பிரகடனப்படுத்தப் பெறும் ஒலை

அன்றாடு நற்காசு : வழக்கில் உள்ளதும் மாற்றுக் குறையாததுமான காசு?

அன்றாள் கோ : அந்தந்தக் காலத்தில் அரசுபுரியும் மன்னன்

அன்வயத்தார் : அந்த வமிசத்தில் பிறந்தவர்

அன்னிய நாமகரணம் : இரவல் பெயரில் காரியம் செய்வது (அன்னிய நாமகரணத் தீட்டுக் கொடுத்த பரிசாவது)

அனாதிபாழ் : நெடுங்காலமாகப் பாழாகக் கிடந்த இடம்

அனுசிதம் : கெடுதி

அனுதாரம் : காப்பு; போஷணை

அனுபந்தம் : உதவி

அனுபோகப் பற்றெழுது : சொத்துக்கு உரிய மூலபத்திரங்களை அனு போகத்தை ஒட்டிப் புதுப்பித்தல்

அனுவர்த்தனை : வர்த்தனை என்ற வகையைச்சேர்ந்த சிறு வரிகள்

அஷ்டபரிபாலனம் : அஷ்ட திக்குப் பாலகர்கள்

அஸ்திகடை : கடும்போர்

அஷ்டபோகம் : நிலத்திலே அனுபவிக்கும் எட்டுவகை உரிமை : விக்  
கிரயம், தானம், வினிமயம், ஜலம், தரு, பாஷாணம், நிதி, நிசேஷபம்  
என்பன. மற்றொரு சாரார் அக்ஷிணி, ஆகாமி, ஜலாமிருதம், பாஷா  
ணம், நிதி, நிசேஷபம், சித்தம், சாத்தியம் ஆகிய எட்டும் என்பர்

[பெண், ஆடை, அணிகலன், போசனம், தாம்பூலம், பரிமளம்,  
பாட்டு, பூவமளி ஆகிய எட்டு என்ற வகையும் உண்டு.]

அன்னியாயவாவ தண்ட இறை : உரிமை இல்லாத ஒரு லாபத்தை  
அடைந்ததற்காகத் தண்டம் விதித்து இறுக்கப்பெறும் வரி

அஷ்டவித பக்தி கிரியை : அர்ச்சனை, வந்தனம், ஸ்மரணம், பாத  
சேவை, ஸ்தவம், பிரதக்ஷிணம், சக்யம், ஆத்ம நிவேதனம் அல்லது  
ஆத்மார்ப்பணம் ஆகிய எட்டும் கொண்ட பூசை

அஷ்டவிதார்க்சனை : நீர், வாசனைப் பொருள், புஷ்பம், தானியம்,  
தூபம், தீபம், நைவேத்தியம், தாம்பூலம் ஆகிய எட்டு வகைகளால்  
பூசிப்பது.

அக்ஷிணி : அஷ்டபோகங்களுள் ஒன்று; இப்போது கிடைப்பவற்றை  
குறிக்கும்

ஆக்கம் : செல்வம்; வருமானம்

ஆக்கப் பேருக்கம் : சீர்திருத்தம் செய்து அதனால் மேலும் உண்டான  
வருமானம்

ஆகாமி : சுவர்ணதாயம்; அஷ்டபோகங்களுள் ஒன்று; இனிமேல்  
கிடைக்கப் போவதைக் குறிக்கும்

ஆச்சன் : தகப்பன்

ஆசந்திரதாரகம் : சந்திரன், நக்ஷத்திரங்கள் உள்ளவரையில்; என்  
றென்றைக்கும்

ஆசந்திராரக்கம் : சூரிய சந்திரர் உள்ளவரையில்; என்றென்றைக்கும்

ஆசாரியபூசனை : குருக்களுக்கு உரிய சம்பாவனை

ஆசிரியக்கல் : தன்னைக் காத்து உதவும்படி பிறருக்கு எழுதி வைக்கும்  
சிலாசாசனம்

ஆசிரியப் பிரமாணம் : தன்னைக் காத்து உதவும்படி பிறருக்கு எழுதிக்  
கொடுக்கும் சீட்டு

ஆசிரியம் : ஆசிரியக்கல் பார்க்க

ஆசீவகக் காச : ஆஜீவக மதத்தினர் முன்னாளில் செலுத்தவேண்டிய  
வரி; ஆசீவக்காச எனவும் பெறும்

ஆசுகவிகள் காச, ஆசுவக்கிடமை : ஆசீவகக்காச பார்க்க

ஆசுவடிமக்கள் : ஆசீவகப் பொது மக்கள்

ஆட்சிப் பாட்டம் : வரி வகை

ஆட்டாண்டு : ஒவ்வோர் ஆண்டும்

ஆட்டுக்கிறை, ஆட்டுவரி : ஆட்டின்மீது விதிக்கப்படும் வரி

ஆட்டைக் காணிக்கை : வருஷந்தோறும் செலுத்த வேண்டிய காணிக்கை ; ஆட்டைச் சம்மாதம் என்பதும் இதுவே போலும்

ஆட்டைக்கோள் : ஆண்டுதோறும் செலுத்த வேண்டிய தொகை

ஆட்டைச் சம்மாதம் : ஆட்டைக் காணிக்கை பார்க்க

ஆட்டைப் பாழ் : வருஷம் முழுதும் தரிசாகக் கிடந்த நிலம்

ஆட்டை வாரியர் : சம்வத்சர வாரியர் ; கிராம நிர்வாகத்திலே சில காரியங்களைக் கவனிப்பதற்காக அந்த அந்த ஆண்டு அமைக்கப்படும் சபையார்

ஆடிப்பச்சை : கார்த்திகைப் பச்சை என்பதுடன் சேர்ந்தே காணப்படும். ஆடிநவிரை என்றும் உள்ளது (நவிரை - நெல்வகை ஒன்று); ஆடிக்குறுவையும் உண்டு. ஆகவே ஆடி மாதத்தில் நெல் அறுவடையாகும் காலத்தில் தானியமாகச் செய்யும் செலவுபோலும்

ஆண்டார் : அடியார் ; பக்தர்

ஆண்டுகள்ளடவு : வருஷ வருமானம்

ஆண்டேழுத்துத் தேவை : ஆட்டைச் சம்மாதமே போலும்

ஆணத்தி : அரசன் உத்தரவை நிறைவேற்றுவோர் (ஆஜ்ஞப்தி என்ற வடமொழிச் சொல்லின் வடிவம்); அரசன் உத்தரவையும் குறிக்கும்

ஆணியம் : நாள்படி ; தினக்கூலி

ஆணைல் : ஆள் நெல்லு பார்க்க

ஆணை : உத்தரவு

ஆணை வாசல் : பிரதான வாசல்; அரண்மனை வாசல்

ஆணைவிலை : அரசன் உத்தரவின்படி செய்த விற்பனை ; ஆக்ஞாகிரயம் எனவும் பெறும்

ஆத்திறைப் பாட்டம் : கால்நடை வரி

ஆதிக்கப் பேறு : அதிகாரவர்த்தனையே போலும்

ஆதிதாசர் : சண்டேசுவார்

ஆதிர சாலை : ஆதலர் சாலை பார்க்க

ஆதிரைப் பிள்ளையார் நோன்பு : திருவாதிரை, பிள்ளையார் சதுர்த்தி முதலிய உற்சவங்களுக்கான செலவுக்கு இறுக்கும் தொகை

ஆதிறைப் பாட்டம் : கால்நடைகளின் மீது விதிக்கும் வரி

ஆதுலர்சாலை : வைத்தியசாலை

ஆமை தவழ் : ஆமை தவழும் நிலம் ; ஆழமான கிணறு

ஆயகம் : ஊர்ச் சபைகளுக்குப் பதிலாகக் கிராம உத்தியோகஸ்தர்கள்  
சிலரைக் கொண்டு கிராம நிர்வாகத்தை நடத்தும் முறை. அந்த  
அதிகாரிகள் ஆயகார் எனப்பெறுவர்

ஆயப்பாடி : கிருஷ்ணன் கோயில் : கோதுலம் எனவும் பெறும்

ஆயம் : வரிகளைப் பொதுவாகக் குறிக்கும் சொல்

ஆயிரத்தளி : அரண்மனை (ஆயிரம் தளிகொண்ட இடம், தளி - அறை)

ஆயோகவர் : கைக்கோளரில் ஒரு பிரிவினர்

ஆரகுடம் : பித்தளை

ஆராட்சி : ஆராய்ச்சி பார்க்க

ஆராய்ச்சி : மேற்பார்வை ; கணக்குப் பரிசோதனை ; அவற்றைச் செய்  
யும் அதிகாரி ; அதற்காக இறுக்கும் சிறுவரி ; காரிய ஆராய்ச்சி  
என்றும் குறிக்கப்பெறும்

ஆராய்ச்சியார் : கணக்குப் பரிசோதனை செய்வோர்

ஆலேபனம் : பூசதல், மேற்பூச்சு

ஆலை : மண்டபம் (உள்ளாலை : உள் மண்டபம்)

ஆவணம் : பத்திரம் ; சீட்டு ; கிரய பத்திரம் ; வீலையாவணம் எனவும்  
ஆகும்

ஆவணக்களரி : பத்திரங்களைப் பதிவுசெய்யும் இடம்

ஆவரணம் : மறைப்பு ; மதிட்சுவர் ; சுற்றலை

ஆழ்வார், ஆழ்வி : தலைவன் ; தலைவி ; மரியாதைக்குரியவரைக் குறிக்கும்  
சொல்.

ஆள் அமஞ்சி : கூலி இல்லாமல் கடமையாக வேலை செய்வது ; குடி  
மராமத்து

ஆள்நெல்லு : நெல்லாக இறுக்கும் வரி வகை

ஆள்வரி : தலை(க்கட்டு)வரி ; மகன்மை

ஆளும்கணம், ஆளும் கணத்தார் : கிராம காரியங்களை நிர்வகிக்கும்  
சபை ; அதன் உறுப்பினர்கள்

ஆற்றங்கரைத் தேவை : ஆற்றங்கரை உடையாமல் பாதுகாக்கும்  
பொறுப்பும் அதற்கான செலவும்

ஆற்றுக்கால் அமஞ்சி : கிராம மக்களைக்கொண்டே ஆற்றுக் கால்களைத்  
திருத்துவது ; கூலி இல்லாமல் அவ்வேலையைச் செய்யும் ஆள்

ஆறிடு படுகை : ஆற்று வண்டல் படிந்து புதிதாக உண்டாகும் படுகை  
நிலம்

ஆற்றுக் குலை : ஆற்றின் கரை ; ஆற்றங்கரைத்தேவையே போலும்

ஆற்றுப் பாட்டம் : ஆற்றங்கரைத்தேவை பார்க்க

ஆனஞ்சு : பஞ்சகவ்யம் ; பசுவின் பால், தயிர், நெய், சாணி, சிறுநீர்  
ஆகிய ஐந்தும் கலந்தது

ஆனவாள் : கோயில் காரியங்களை நடத்தி வைக்கும் அரசாங்க உத்தி  
யோகஸ்தர்

ஆனைச்சாலை : யானைகள் கட்டும் இடம்; அதன் பராமரிப்புக்காக வசூ  
லிக்கப்பெறும் வரியையும் குறிக்கும்

ஆனையாட்கள் : யானைப் படையினர்

இகுத்துவித்தல் : மடையடைத்தல்

இசைக்கிடாய் : [இது கொங்கு நாட்டுச் சாசனங்களிலேதான் காணப்  
படுவது] நல்லெருது, நல்பசு என்பனபோல நற்கிடா என்பதே  
போலும்

இசைகேடு : (இசைவு கேடு) கெடுதி

இசையின் சேல்வி : புகழ் மகள் ; கலைமகளையும் குறிக்கும்

இசையோலை : ஒப்பந்தச் சீட்டு

இசைவுதீட்டு : உடன்படிக்கைப் பத்திரம்

இடங்கசாலை : (டங்கசாலை) அக்கசாலை; நாணயம் அச்சிடும் இடம்

இடங்கை : இடங்கைச் சாதிகள்

இடங்கைவரி : இடங்கைச் சாதியார் செலுத்தவேண்டிய வரி

இடதுறை : சுவர்ணாதய வகை ; இடைத்துறை எனவும் பெறும் ;  
எதைக் குறிப்பதென்று தெளிவாகத் தெரியவில்லை

இடபத் தளியிலார் : கோயிலில் ஊழியம் புரியும் மகளிர்

இடிஞ்சில் : அகல் விளக்குத் தகழி ; மண் அகல்

இடை நாழிகை : கோயிலில் அர்த்த மண்டபத்துக்கும் மகா மண்ட  
பத்துக்கும் இடைப்பட்ட பகுதி

இடைப்பாட்டம் : இடையர் வரி ; இடைப் பூட்சி எனவும் ஆகும்

இடையர் வரி : மாடு மேய்ப்பவர் இறுக்கும் வரி

இடையீடு : அரசாங்க உரிமையாயிருந்து பிறருக்கு மாற்றப்பட்ட  
நிலம்

இடையீடு : பயிரிடும் உரிமை

இடைவட்டை : நடுவில் உள்ளது ; வருஷநடுவில் செலுத்தவேண்டிய  
பொருள் ; இடை வேட்டு என்பதும் இதுவே போலும்

இண்டை : தலையைச் சுற்றி அணியும் சிறு வட்டமான பூ மாலை

இதடக்கு : அணியுறுப்பு வகை ; ஓர் ஆபரணம்

இயக்குதல் : நடத்தி வருதல்

இயற்றண்டம் : (இயல் தண்டம்) சாதாரண அபராதம்

இரத்தக் காணிக்கை : போரில் வீழ்ந்த வீரருடைய வழியினிர்க்கு  
அளித்த மானியம்

இரத்த மானியம் : இரத்தக் காணிக்கை பார்க்க ; உதிரப்பட்டி, நீத்தார் பட்டி, நீத்தார் கோடை என்ற பெயர்களாலும் வழங்கப்பெறும்

இரவுச் சோறு : எச்சோறு பார்க்க

இரவை : இரவு (இரவைக்கு - இராப்பொழுதுக்கு)

இராசகரம் : அரசாங்கம் ; அரண்மனை ; ராஜக்ருஹம் என்பதன் திரிபு

இராசகரகாணிக்கை : அரண்மனைக்கு அந்த அந்தக் காலங்களில் செலுத்தவேண்டிய காணிக்கைப் பொருள்

இராசபோகம் : அரசர்க்கு உரிய பாதுகாவல் வரி

இராசிப்போன் : கலப்பற்ற சுத்தமான தங்கம்

இராசிபாளையம் புள்ளிப்பணம் : பழையநாள் நாணயம்

இராமாநுஜகூடம் : வைஷ்ணவ யாத்நிரிகர்கள் தங்கும் சாவடி

இராயசம் : ஆணைப்பத்திரம் ; இராயச வேலையைக் கவனிக்கும் ஓலை நாயகம் போன்ற அரசாங்க அதிகாரி

இராயச வர்த்தனை : இராயச அதிகாரிகளுக்குக் கொடுக்கும் வர்த்தனை

இரு(க்)கால் : இரண்டு தரம்

இருட்கண்டம் : கழுத்தணி வகை (நீலகண்டம் ?)

இருப்புக் கட்டி : (இரும்புக்கட்டி) பூமியிலிருந்து இரும்பைத் தோண்டி எடுத்து உருக்கி வார்க்கும் தொழிலுக்கான வரி; அன்றி இருப்பைக் கட்டி (இலுப்பைக்கட்டி) யெனக் கொண்டால் இலுப்பைப் பிண்ணுக்கு வியாபாரத்துக்கான வரி

இருபூ : இருபோக சாகுபடி

இல்லரி, இல்வரி : மனைவரியே போலும்

இலக்கை : இருப்பிடம் ; குடியிருப்பு

இலக்கை : ஆடை ; மாதச் சம்பளம்

இலாஞ்சனைப் பேறு : அரசனுடைய முத்திரையைப் பொறிப்பதற்குச் செலுத்தவேண்டிய கட்டணம் ; லாஞ்சனைப் பேறு, இலச்சினைப் பேறு எனவும் குறிக்கப்பெறும்

இலைசுனி : மாணிக்கத்தின் குணங்களுள் ஒன்று

இலைச்செப்பு, இலைத்தட்டு : பூசைப் பாத்திரவகை

இலையமுது : வெற்றிலை

இலைவாணியப் பாட்டம் : வெற்றிலை வாணிகம் செய்வோர் இறுக்கும் வரி

இலைவாணியர் : வெற்றிலை வாணிகம் செய்யும் குடி

இழிக்க : (இணறு) ஆழமாகத் தோண்ட

இழிச்சு : நீக்க ; (வரி) தள்ளிக் கொடுத்து ; இழித்து என்றும் காணப் பெறும்



இளங்கூறு : இளைய பிரிவு ; இளவரசன்

இளங்கோயில் : பாலாலயம் ; கோயிலைப் புதுப்பிக்கும் காலத்தில் விக்கிரகங்களை வைத்திருக்கும் தனி இடம்

[பழைய நாளில் கட்டப்பெற்று வந்த கோயில் கட்டடங்களில் ஒரு வகையையும் குறிக்கும்]

இளஞ்சிங்கவீரர் : நானாதேசிகள் என்னும் வியாபாரக் குழுவினரின் உட்பிரிவு ; படைத் தொழிலில் ஈடுபட்டவர் போலும்

இளவட்டம் : காளைப் பருவத்தினர்

இளைய நயினார் : (இளைய நாயனார்) முருகக் கடவுள்

இளைய வகை : தாயாதிகளில் இளைய பரம்பரை

இறங்கல் : வரி தவிர்த்தல் [அரசாங்கத்தார்க்குச் செலுத்தவேண்டிய வரியைத் தவிர்த்தலை நீங்கல் என்றும், அவ்விதம் அல்லாமல் அந்த வரியை ஊர்ச்சபை, நகரம் போன்ற ஸ்தாபனங்கள் ஏற்றுக் கொள்வதை இறங்கல் என்றும் கொள்வர்]

இறங்குசாத்து : இறக்குமதி ; இறக்குமதி வியாபாரத்தில் ஈடுபட்டுள்ள வியாபாரிகள்

இறங்குசாத்து : (துவஜ அவரோஹணம்) கொடியிறக்கம் ; அதுசமயம் கோயிலில் நடத்தும் விசேஷம் ; இறங்குகையில் செலுத்தும் மரியாதை

இறப்பு : வரி, தண்டம் முதலியவை செலுத்தல்

இறை : அரசாங்கத்துக்கு இறுக்கும் வரியைப் பொதுவாக உணர்த்தும் சொல்

இறைக்கடன் : நிலவரி

இறை காவல் : பின்னால் செலுத்தவேண்டிய வரிக்காக மொத்தமாகச் செலுத்தும் பணம் ; தலையாரிக்கு உரிய வரி என்றும் கூறுவர்

இறைச் சோறு : எச்சோறு போலும்

இறை திரவியம் : பின்னால் ஆண்டுதோறும் இறுக்க வேண்டிய வரி களுக்காக மொத்தமாகச் சேர்த்து முன்னதாகவே செலுத்தும் பணம்

இறைப் புணைப் படுதல் : ஒருவன் செலுத்தவேண்டிய வரிக்காக மற்றொருவன் புணை கொடுத்தல்

இறைப் பொருள் : இறைத் திரவியம் பார்க்க

இறைபோகம் : நிலத்தில் வசூலாகும் வரியைமட்டும், அதாவது மேல் வாரத்தை மட்டும் அனுபவிப்பது

இறையிலி : வரி இல்லாத நிலம்

இறையிலிக்காசு : நிலவரி இல்லாத நிலங்களுக்காக இறுக்கும் சிறு

இறை பேர்ன்றவை ; ஊர்ச் சபையால் இறையிலியாக்கப்பெற்ற நிலங்களின் வரியை ஏற்று ஊரார் கொடுக்கும் பங்கும் ஆகும்

இறையிழித்து: வரி நீக்கி; இறையிழிச்சு என்றும் எழுதப்பட்டிருக்கும்  
இறையிறக்கும் கோல்: வரி விதிப்பதற்காக நிலத்தை அளக்க உபயோ  
கிக்கும் அளவு கோல்

இறைவிழுத்து: இறையிழித்து பார்க்க

இனவரி, இனவரிக்காசு: அந்த அந்தச் சாதியினர் செலுத்தும் வரி;  
ஜாதி ஸித்தாயம் என்று தெலுங்குச் சாசனங்களில் வருவதையும்  
காண்க

ஈக்காலாணி: ஆபாணத்திக்கு இடம் சிறு ஆணி

ஈச்சோப்பி: ஈயோட்டி.

ஈட்டம்: கூட்டம்

ஈரங்கோல்லி, ஈரங்கோள்ளி: வண்ணன்; அவன் செய்யும் தொழிலுக்  
கான வரி

ஈழக்காசு, ஈழக் கருங்காசு: முன்னாளில் வழக்கில் இருந்த நாணய  
வகை; இலங்கையில் வழங்கிவந்தது; கருங்காசு எனவும் பெறும்

ஈழக்கையர்: ஈழவருடைய பெண்டிர்

ஈழச்சேரி: கள்ளிறக்குவோர் வாழும் இடம்

ஈழம்புஞ்சை: கள் இறக்குவோர் வரி

ஈழம்பூட்சி: கள் இறக்குவதற்கு விதிக்கும் வரி

ஈழவர்: கள் இறக்குவோர்

ஈழற்கிழவரி: ஈழம் புஞ்சை பார்க்க

உகட்பார்பொன்: கல்யாணம் போன்ற சந்தோஷ காரியங்களுக்குச்  
செலுத்தும் வரி; கண்ணுலக்காணம் என்பதும் இதுவே போலும்

உகவை: உகட்பார் பொன் பார்க்க

உகிர்ப்புறவன்: நகத்தின்மேல் அணியும் அணிவகை

உச்சம்போழ்து: நடுப்பகல்

உச்சி சந்தி: கோயிலில் நண்பகலில் நடக்கும் பூசை

உசாவடி: சாவடி என்பதன் வேறு வடிவம்; கோட்டம், கூற்றம்  
என்பன போல முன்னாளில் வழங்கிய ராஜ்யப் பகுதியின் பெயர்

உட்கோள்ளுதல்: வரி முதலியன வசூலித்தல்

உட்கோயில்: கோயில் கர்ப்பகிருகம்

உட்கோள்: வரி வசூலிப்பதற்காகும் செலவு போலும்

உட்சேவகம்: கிராமச் சேவகம்; அதற்காகும் செலவு

உட்புரவு: சபை, நாடு முதலிய ஸ்தல ஸ்தர்பனங்களால் இறை  
நீக்கப்பெற்ற நிலம்

உடல் : வருமானத்தை மட்டும் உபயோகிக்கும் நிபந்தனையுடன் இட்ட  
முதல்

உடன்கூட்டம் : அரசனோடு கூடவே செல்லும் மந்திரிகள்போன்ற  
உயர்தர அதிகாரிகள்

உடன்கூட்டத்ததிகாரி : அரசன் பக்கத்தில் இருக்கும் பரிவாரமான  
உடன் கூட்டத்து அதிகாரி

உடன் பாடுவான் : சேர்ந்து பாடுகிறவன்

உடன்வாரம் : மேல்வாரம் குடிவாரமாகப் பிரிக்கப்படாத மொத்த  
மகசூல்

உடனிலைக் குதிரைச்சேவகர் : குதிரையேறிய மெய்காவலர்

உடைபட்டாம் : கரை இடிந்து உடைந்து நீர் நில்லாத குளம்

உடைப் படை : நிலைப் படை

உடையார் : அரசன்; உரியவன்; கோயிலில் எழுந்தருளியிருக்கும் எம்  
பெருமான்

உடையார் சாலை : கோயிலைச் சேர்ந்த சோற்றுச் சாலை

உண்டழிவு : உணவு அளிப்பதற்காகும் செலவு

உண்டி யச்சு : நாணய வகை

உண்ணுழிகை : கர்ப்ப கிருகம்

உண்ணுழிகை உடையார், உண்ணுழிகையார் : கர்ப்ப கிருகத்தில்  
உள்ள கடவுள் ; கர்ப்ப கிருகத்தில் சேவை புரிவோர்

உண்ணுழிகை வாரியம் : கர்ப்பகிருக நிர்வாகத்தைக் கவனிக்கும்  
சபை

உண்ணிலம் : உள்ளே அடங்கிய நிலம்

உத்தமதானி : பிரதிப்பிரயோஜனம் எதிர்பார்க்காமல் தானம் செய்வது;  
தானங்களுள் சிறந்தது

உத்தரமந்திரி : முக்கியமான மந்திரி ; பிரதான மந்திரி

உத்தாரம் : உத்தரவாதம்

உத்தானத் துவாதசி : கார்த்திகை மாதத்துச் சுக்கில பக்ஷத்துத்  
துவாதசி

உதகதாரை : நீரைத் தாரையாக வார்த்துத் தானம் செய்தல் ; உதகம்  
பண்ணி, உதகஞ்சேய்து என்றும் குறிக்கப் பெறும்.

உதக பூர்வம் செய்தல் : தானம் கொடுக்கும்போது நீர் வார்த்துக்  
கொடுத்தல்

உதாசீனவாரியம் : விருப்பு வெறுப்பு இல்லாமல் இரு தரப்புக்கும்  
பொதுவாக நின்று பணிபுரியும் குழு; மத்தியஸ்தர் அடங்கிய சபை

உதிரப்பட்டி : போரில் இறந்துபட்டவர்களின் வழிவந்தோர்க்கு வழங்  
கும் நிலம்; இரத்தக் காணிக்கை

உப்புாயம் : உப்பு வரி

உப்பிஞ்சி : இஞ்சி வகை

உப்புக் காசு : உப்பு வரி

உப்புக் கோச்செய்கை : உப்பு உண்டாக்கி எடுக்கும் அரசாங்க உரிமை

உபத்திரகம் : உபத்திரவம்

உபயநானுதேசி : நானுதேசி என்னும் வியாபாரிகளுடைய குழுவின்  
இரண்டு பெரும் பிரிவுகள்

உபய-பலிசை : (ரொக்கம், தானியம் ஆகிய) இருவகையாகவும் கிடைக்  
கும் வட்டி

உபயம் : பழைய சுவர்ணாதாய வகை; உபய மார்க்கம் என்பதும்  
இதுவே போலும்; அவ்விதமாயின் பெருவழிப் போக்குவாத்திலே  
இறுக்கும் சுங்கமாகக் கொள்ளலாம்

உபயராணுவம் : இரண்டு பிரிவுகள் கொண்ட சேனை

உபாதி : கடமை; இறுக்க வேண்டிய வரி முதலியன; ஒபாதி என்றும்  
காணப் பெறும்

உபாயம் : சாதனம், வழி; உபாயம் என்பதே போலும்

உபானம் : கோபுர விமானத்தின் அதிஷ்டானத்தின் அடிப்படை;  
உபானவரி எனவும் பெறும்

உம்பளிகை : மானியம்; சேவைக்காக விடப்பெற்ற மானிய நிலம்

உரல் வரி : நெல் குற்றும் உரலுக்கு இறுக்கும் வரி

உரிமை : மனைவி

உருத்திர கணம் : சிவனடியார்

உருத்திர கணிகை : சிவன் கோயில் தாசி

உருத்திரர் : சிவனையே பரதெய்வமாக வழிபடுவோர்; சைவர்

உல்கு : சுங்கம்

உல்கூட்டுச் சரக்கு : சுங்கம் வசூலிக்கக்கூடிய பண்டம்

உல்லியக் கூலி : கிணற்றிலிருந்து தண்ணீர் இறைத்துப் பாய்ச்சும்  
நிலத்துக்கு இறுக்கும் வரி

உலகளவு : நாட்டின் நில அளவு

உலகுடைய பேருமாள் : அரசன்

உலவி போன் : சுத்தமான தங்கம்

உலாவு காட்சி : வரி வகை

உவ்வி : தலை; வரி வகை; தலைவரி போலும்

உவச்சக்காணி : கோயிலில் (மத்தளம்) கொட்டும் ஊழியத்துக்கு விடப்  
படும் மானியம்

உவச்ச வரி : (கோயில் பூசை செய்யும்) உவச்சர் கொடுக்கவேண்டிய வரி

உவச்சன் : கோயிலில் (மத்தளம்) கொட்டுவான் ; பூசாரி

உவச்சு : மத்தளத்தின் ஒரு வகை

உவன்றி : நீர்நிலை

உவா : அமாவாசை, பெளர்ணமி ஆகிய இரு தினங்களும்

உழத்தல் : வருந்துதல் ; உழைத்தல்

உழத்தல் : மயங்குதல் ; திகைத்தல்

உழவு காணி : நிலத்தை உழுது பயிரிடுதல்

உழவுகாணியாட்சி : நிலத்தை உழுது பயிர் செய்யும் உரிமை

உழப்பம் : வேலை

உழவுகுடி, உழுகுடி : பயிரிடுங் குடி

உழுதான்குடி : பயிரிடுங்குடி இறுக்க வேண்டிய வரி

உள் பாடன் : கோயில் உத்தியோகங்களுள் ஒன்று

உள்வரி : அந்தராயம்; ஸ்தல ஸ்தாபனங்களுக்கு இறுக்கும் வரி; அவ் விதம் செலுத்தவேண்டிய வரிகளை நிச்சயித்து அரசாங்கம் விடுக்கும் ஒலை

உள்ளாலை : உள் மண்டபம் ; உள் பகுதி

உள்ளிட்டம் : நஷ்டம்

உள்ளிட்டார் : [பெயர் குறிக்கப்பெற்றவர்கள்] உள்பட அனைவரும் ; அந்த வமிசத்தவர்கள்

உள்ளிருப்பு : எதிர்பாராத செலவுகளுக்கெனச் சேமித்து வைத்துள்ள நிதி ; க்ஷேம நிதி

உருவொற்றி : திரும்ப மீட்க முடியாத ஒற்றி (அடைமானம்)

உறுபாதை : சிதைவுறும் சிறுபாதைகளைச் சீர்செய்யும் பொறுப்பு

உறைநாழி : முகத்தல் அளவையில் (அறுபது மரக்கால்போன்ற அளவையான) ஒவ்வோர் உறைக்கும் ஒரு நாழி என்று கூலியாகப் பெறுவது

ஊசிவாசி : தையற்காரர்கள் இறுக்கும் வரி போலும்

ஊடுபோக்கு : ஒரு பயிர்செய்யும் போது அதன் இடையிலே செய்யும் வேறு பயிர் ; அவ்விதம் செய்வதற்கான வரி

ஊத்தைப்பாட்டம் : குளத்திலிருந்து வண்டல் முதலியவற்றை வாரி எடுத்தலால் கிடைக்கும் வருவாய்

ஊத்தையட்டேல் : ஊனமுறுதல் ; தோற்று அவமானப்படுதல்

ஊர் : வேளாண் மக்கள் குடியிருப்பான கிராமம் ; அவ்வூருக்கு அமைந்த சபை

ஊர்க்குடமை : ஊர்ச்சபையினர்க்குச் செலுத்தவேண்டிய கடமை வரி

ஊர்க்கணக்கர் ஜீவிதம் : கிராமக் கணக்கு வேலைபார்ப்போர் வாழ்  
நாளில் அனுபவிக்க விட்ட மானியம்

ஊர்க்கமைஞ்சு : ஊருக்கு அமைந்த ; ஊருக்குப் பொறுப்பான

ஊர்க்கலனை : கிராமத்தின் சிறுதன அதிகாரிகள்

ஊர்க்கழஞ்சு : ஊர்ப் பொதுவாக வைக்கப்பெற்றிருக்கும் நிர்ணயிக்  
கப் பட்டுள்ள எடை ; அதுபற்றிய வரியையும் குறிக்கும்

ஊர்க்கற் சேம்மை : ஊர்ப் பொதுவாக உள்ள நிறைக்கும் உரைகல்  
மாற்றுக்கும் சமமானது (பொன்)

ஊர்க்கீழ் இறையிலி : ஊர்ச்சபையாரால் வரி நீக்கப்பெற்றதும், அரசு  
சாங்கத்துக்கு உரிய அதன் தீர்வையை ஊர்ச்சபையாரே ஏற்று  
இறுப்பதுமான நிலம்

ஊர்காவல் : கிராமத் தலையாரி

ஊர்ச்சரிகை : ஊர்க்கூட்டம்

ஊர்வாரியம் : கிராமக் காரியங்களைக் கவனிக்க நிறுவப்பெறும் சபை

ஊரமை, ஊராண்மை : ஊர்ப்பொதுக் காரியங்களை நிர்வகித்தல்

ஊரவர் : ஊராக அமைந்த ஊர்ச்சபை ; அதன் உறுப்பினர்

ஊராட்சி : கிராம காரியங்களை நிர்வகித்தல்

ஊராள் : கிராமத்தை ஆளும் அதிகாரி

ஊரிருக்கை : ஊரைச்சார்ந்த இடம்

ஊரிடு வரிப்பாடு : கிராமச் சபையான ஊர் விதிக்கும் வரி

ஊரோட்டு : வரி வகை ; எண்பேராயம் என்பதன் தொடர்பு கொண்ட  
தாக இருத்தல் வேண்டும்

ஊரோம் : ஊர் என்னும் கிராமச்சபையாக அமைந்த நாங்கள்

ஊழியம் : பொதுக் காரியங்களுக்கும் அரசாங்க அதிகாரிகளுக்கும்  
சம்பளம்பெறாமல் (அமஞ்சி போல்) செய்யும் ஊழியம்

எக்கடமை : ஏர்க்கடமை போலும்

எக்காளம் : பவனியில் முன்னே ஊதம் காளம் போன்றது

எச்சோற்றுக் கூற்றுநெல், எற்சோற்றுக் கூற்றரிசி : நெல் குத்துபவர்  
களுக்கு இரவில் சோறு இடும் கடமைபோலும்

எச்சோறு : கிராம ஊழியர்களுக்கு இரவில் சோறும் போடும் கடமை ;  
எற்சோறு எனவும் பெறும்

எடுத்துக்கட்டி : சுவர்த் தலைவரிக் கட்டு ; சைப்பிடிச்சுவர்

எடுத்துக்கோட்டி : நெல்லாய வகை ; விவரம் விளங்கவில்லை

எடைவரி : நிறைமேல் விதிக்கப் பெறும் வரி (இடைவரியின் தவறான  
வடிவமா?)

எண்ணெய் (எண்ணை) : எண்ணெய் வியாபாரத்தின்மீது வரி; எண்ணெய் அட்டவேண்டிய நிபந்தனையையும் குறிக்கும்போலும்  
எண்ணெய்ப் பந்தம் : இரவில் நடக்கும் கிராமப் பொதுக்காரியங்களுக்கு வாணியன் விளக்கெரிக்க எண்ணெய் கொடுப்பது  
எதிரடையோலை : அடையோலை எழுதித் தருவோர்க்குக் கொடுக்கும் ஆதரவுச் சீட்டு

எதிராமாண்டு : அடுத்துவரும் வருஷம்

எயில் : கோட்டையாக அமைந்துள்ள ஊர்

எர்க்காடி : ஏர்க்காடி பார்க்க

எரிகரும்பு : அடுப்பு விறகு

எரிமருந்தன் : வெடிமருந்து செய்பவன்

எரிமருந்து : வெடிமருந்து

எருமைப் போன் : எருமைகளின்மீது விதிக்கப்படும் வரி; காசாகக் கொடுக்க வேண்டியது

எல்கை : எல்லை என்பதன் வேறு வடிவம்

எலவை : (எல்வை எனவும் வாசிக்கப் பெறும்) சாவுக்கான வரி; பிணத்தை இடுக்காட்டில் அடக்கம் செய்வதற்கு இறுக்கும் கடமை; துக்கப்புடைவை என்பதும் இதைப்பற்றியதே போலும்

எழுத்து வினியோகம் : கணக்கெழுதும் அதிகாரிகளுக்கு வர்த்தனையாக அளிக்கும் வரி வகை

எழுந்தருளுந் திருமேனி : உற்சவ மூர்த்தி

எறிவீரப் பட்டணம் : எறிவீரர்களுடைய நகரம்

எறிவீரர் : அய்யாவழியைத் தலைநகராகக் கொண்ட நானாடுதேசி என்னும் வியாபாரக் கூட்டத்தாரின் ஒரு பகுதியினர்; போர்ப்படைப் பிரிவைச் சேர்ந்தவர் போலும்

ஏகபோக இறையிலி : வரி இல்லாமல் உள்ள ஏகபோகக் கிராமம்

ஏகபோகம் : ஒரு கிராமத்தைப் பிறருடைய கூட்டு இல்லாமல் தனி மனிதர் ஒருவரே அனுபவிப்பது

ஏகபோகம் : ஒரே சாகுபடியும் ஆகும்; ஒருபு

ஏகாங்கி : குடும்பமின்றித் தனித்து வாழும் வைஷ்ணவ அடியார்; விஷ்ணு கோயில் நிர்வாகத்தைக் கவனிப்பவர்

ஏகாவலி, ஏகாவல்லி : ஒற்றைச்சரம் உள்ள மாலை

ஏணிக்காணம் : ஏணியின்மீது விதிக்கப்பட்ட வரி; கள் இறக்குவோர் போன்ற மாமேறிகள் செலுத்தவேண்டியது போலும்

- ஏத்தம்புலம், ஏத்த பாடம் : (ஏற்றம் புலம், ஏற்ற பாடம்) ஏற்றம் போட்டுத் தண்ணீர் இறைத்துப் பயிர் செய்யும் நிலம்
- ஏந்தல் : பயிர் செய்வதற்கான நீர்பாயும் ஏரி
- ஏர்க்கடமை : உழும் ஏரின்மீது விதிக்கப்பெறும் வரி
- ஏர்க்காடி : ஒவ்வோர் ஏருக்கும் ஒரு காடி நெல்லாக இறுக்கவேண்டிய வரி ; ஏர்க்காணிக்கை எனவும் பெறும்
- ஏர்ப்போன் : ஒவ்வோர் ஏருக்கும் இறுக்கவேண்டிய காசாயவர்க்க வரி
- ஏரி ஆயம் : நீர் நிலைகளிலிருந்து மின்விலை போல் கிடைக்கும் வருவாய்
- ஏரி ஈவு : ஏரியின் பராமரிப்புச் செலவுக்காக அதன் நீர் பாயும் நிலத்தைப் பயிரிடுவோர் கொடுக்கவேண்டிய பங்கு
- ஏரிக்காடி : ஏரியின் நீர் பாய்ச்சும் நிலம் ஒன்றுக்குக் காடி நெல்வீதம் இறுக்கும் வரி
- ஏரிக்கோப்பு : வெள்ளம் வந்த காலத்தில் நீர் நிறைந்து மூழ்கியும் மற்ற நாட்களில் சாகுபடிக்கு ஏற்புடையதுமாக ஏரியின் உள்வாயில் உள்ள நிலம் ; ஏரிநீர்க்கோப்பு எனவும் பெறும்
- ஏரிப்பட்டி : ஏரியின் பராமரிப்புச் செலவுக்காக விடப்பெற்ற நிலம்; ஏரி மானியம் எனவும் பெறும்
- ஏரிமீன் காசு : நீர் நிலைகளின் மீன் விற்பனையால் கிடைக்கும் வருவாய்
- ஏரிமீன் பாட்டம் : ஏரிமீன் காசு பார்க்க
- ஏரிமீன் விலைப்பட்டம் : ஏரிமீன் காசு பார்க்க
- ஏரிமுதல் : வைக்கப்பட்ட நிலத்தையோ பொருளையோ தொடராமல் அதன் வருமானத்தைக்கொண்டே ஏரியின் பராமரிப்பைச் செய்ய வேண்டிய முதல்
- ஏரிவாய் : ஏரியின் வடிகால் பக்கத்தில் புறவாயில் ஏரிக்கோப்புபோல் அமைந்த நிலம்
- ஏரிவாரியம் : ஏரியின் பராமரிப்புக்காக நிறுவப்பட்ட சபை
- ஏலவரிசி : ஏலக்காயின் உள்ளே இருக்கும் அரிசி
- ஏற்றம் : அதிகப்படி, மிகுதி
- ஏற்றக் குறைத்தல் : மிகுதியும் குறைவும்; உயர்வும் தாழ்வும்
- ஏற்றுதல் : குடியேற்றுதல்; ஸ்தாபித்தல்
- ஏற்றுதல் : அதிகப்படுத்தல் ; மேற்கொள்ளுதல் ; கூட்டுதல்
- ஏறுசாத்து : கோயில் உற்சவ காலத்தில் கொடி ஏற்றிச் செய்யும் விசேஷ பூசை ; துவஜாரோஹணம் ; வாகனத்தில் ஏறும்போது செய்யும் மரியாதை
- ஏறுசாத்து : ஏற்றுமதிச் சாக்கு ; ஏற்றுமதி வியாபாரத்தில் ஈடுபடுவோர்



ஐஞ்சகணத்தார் : ஐம் பெருங் குழுவே போலும்  
ஐந்தலை மணி : ஐந்து தனி மணிகளுடைய கொத்துமணி  
ஐயன்பாத்தி : ஐயனார் கோயிலுக்கு விட்ட மானியம்

ஒட்டு : ஒப்புக் கொள்ளுதல் ; உடன்படிக்கை  
ஒட்டுக்காசு : ஒப்புக் கொண்ட காசு ; உடன்படிக்கையின்படி செலுத்த  
வேண்டிய தொகை

ஒடம்படி : உடன்படிக்கை  
ஒடுக்குதல் : பண்டாரத்தில் சேர்த்தல்  
ஒப்புமுத்து : நல்ல உருவம் அமைந்த முத்து  
ஒருதுடை : ஒருதடவை ; ஒருதரம்  
ஒருபூ : ஒரு போகம்  
ஒளிவண்ணற் பாறை : துணி வெளுப்போர் இறுக்கும் வரி  
ஒழிவின்றி : நீக்கல் இன்றி, உட்பட  
ஒழுக்கவி : கோயிலில் நாள்தோறும் படைக்கும் சமைத்த உணவு  
ஒழுகு : நிலத்தின் வரலாறு குறிக்கும் கணக்கு

ஒடாணி : ஆபரணத்திலே மாட்டுவதற்கான ஆணி  
ஒடு : செங்கல் ; சாப்பிடுவதற்கான மண்பாண்டம்  
ஒத்து : அதிகாரம் ; உரிமை  
ஒராணி : இரட்டை  
ஒலக்கம் : அத்தாணிக் காட்சி சபை கூடுதல்  
ஒலக்க மண்டபம் : அத்தாணி மண்டபம் ; சபா மண்டபம்  
ஒலை : உத்தரவு ; அரசன் உத்தரவு  
ஒலைச்சட்டம், ஒலைச்சம்பளம், ஒலைச்சம்மாதம் : ஒலை எழுதும் அதி  
காரிகளுக்குக் கொடுக்கவேண்டிய வர்த்தனை  
ஒலைச் சாதனம் : ஒலையில் எழுதிய பத்திரம்  
ஒலை நாயகம் : அரசன் இடும் உத்தரவுகளை உரியவர்களுக்கு எழுத்து  
மூலம் அறிவிக்கும் அரசாங்கத்துறையின் தலைமை அதிகாரி  
ஒலையெழுத்து : இராயசம்

கங்காணி : கண்காணி பார்க்க  
கங்கில் : காளத்தின் ஓர் உறுப்பு  
கச்சாத்து : கைச்சாத்து பார்க்க  
கச்சகோரம் : பாத்திர வகை ; கச்சோலம், கைச்சோலம் எனப்பெறு  
வனவும் அதுவே போலும்

கசரை : காலேயரைக்கால் பலம்

கசு : கால் பலம்

கட்டணம் : குறிப்பிட்ட வகுப்பினர் சிலர் அவ்வப்போது செலுத்தும் வரிபோன்றது

கட்டளை : கோயிலில் ஒரு விசேஷம் குறித்து ஏற்படுத்தப் பெறும் தர்மம்

கட்டாயம் : (கட்டு + ஆயம்) மொத்தமாக நிர்ணயிக்கப்பெற்ற வரி; அன்றி, நிர்ப்பந்தத்தால் இறுக்கவேண்டிய வரியைக் குறிப்பதாகவும் கொள்வர்

கட்டியாணம் : முன்னாளில் வழங்கிவந்த ஒரு காலியம்; வராகனுக்குச் சமம் என்பர்

கட்டில் : ஆசனம்; (அரசுக்கட்டில்) சிங்காதனம்; படுக்கை

கட்டிலேய்துதல், கட்டிலேறுதல் : சிங்காதனம் ஏறுதல்; மணவினை

கட்டுக்குத்தகை : மொத்தமாக இறுக்கவேண்டிய குத்தகை; பெரும் பாலும் நீண்ட காலம் நீடிக்கும்

கட்டுமுக்கை : கோயிலுக்கு உரிய கடமைகளில் ஒன்று; அறுவடையிலே கட்டுக்கு மூன்று கை வீதம் அரிகளை கொடுப்பதுபோலும்; அரிமுக்கை எனப் பெறுவதும் இதுவே எனலாம்

கட்டுவாங்கம் : மழு; பல்லவர்களுடைய கொடியில் காணும் இலச்சினை

கடகம் : படைவீடு; அரண்வலி கொண்ட கோட்டை

கடமை : அரசாங்கத்துக்குச் செலுத்த வேண்டிய வரிகளைப் பொதுவாகக் குறிக்கும் சொல்

கடமை காரியம் : அரசாங்கத்தின் நிர்வாக அலுவல்

கடமைக்கால் : அரசாங்கத்தார் நிர்ணயித்த அளவு மாக்கால்

கடமைப்பற்று : மேல்வாரத்தை உரியவர்க்குப் பணமாகச் செலுத்தும் கிராமம்

கடவ : கடமையாவதாகவும்

கடவன் : கடமைப்பட்டவன்

கடிகை : பூர்வாங்கக் கல்வி பெற்றவர்களுக்கு மேலும் கல்வி புகட்டும் உயர்தர வித்தியாஸ்தானம்

கடிகை மத்தியஸ்தன் : கடிகையிலே பயிற்சிபெற்று அங்கீகாரம் பெற்ற மத்தியஸ்தன்; பெரும்பாலும் ஊர்ச்சபைத் தலைவன்

கடிகை மாபாடன் : தலைமை வாத்தியக் காரன்; முன்னாளில் அரசர் வழங்கிவந்த பட்டம்

கடிகையார் : கடிகை என்னும் நிலத்தைச் சேர்ந்தவர்

கடிகையார் : அரசன் ஆணையைப் பறையறைந்து அறிவிப்போர்.

கடைக்காட்சி : கண்காணித்தல்

கடைக் கூட்டல் : முடிவுகட்டி வருவித்தல் (பொலியூட்டுப் பொன் கடைக்கூட்ட வந்தார்க்கு நிசதி இரண்டு சோறு கொடுப்போ மாளேம்)

கடைக்கூட்டு : காரிய நிருவாகம்

கடைக்கூட்டிலக்கை : கடைக்கூட்டுவார் வசிப்பதற்கான இடம்

கடைக் கூட்டுத் தானத்தார் : கோயில் அதிகாரிகள்

கடை கூட்டுத் தானத்தார் : நானாதேசி வியாபாரிகளைக் குறிப்பிடும் பெயர்களுள் ஒன்று; அவர்களிலே ஒரு பிரிவினர்போலும்

கடைத் தொழில் : பதக்கத்தில் ஒருபாகம், கடைசல் பிடிக்கப்பட்டது போலும்

கடைநீர் : கடைசியாக உள்ள நிலத்துக்குப் பாயும் தண்ணீர்

கடைப்பாட்டம் : அங்காடிப் பாட்டம் எனக் கொள்வர்; கடைசித் தரமான வரியையும் குறிக்கும்; கடைப்பூ எனவும் ஆகும்

கடைப் பூ : கடைசியான மூன்றாம் போகம்

கடையடைக்காய் : விற்பனைக்குக் கொணர்ந்த பாக்கின் மீது இறுக்கும் வரி போலும்

கடையிறை : கடைசித்தரமான, அதாவது மிகவும் குறைவான வரி; (வருஷ) முடிவாகக் கொடுக்கும் வரியையும் குறிக்கும் போலும்; கடைப்பாட்டம் எனவும் கொள்வர்

கடையீடு : அரசனது முடிவான உத்தரவு; கீழ் அதிகாரிகளின் உத்தரவும் ஆகும்

கடையூறு : முடிவாக வரும் தடை; முடியாத தடை

கண் காட்டுவான் : குருடருக்கு வழிகாட்டுபவன்

கண்காணி : மேற்பார்வை; மேல் விசாரணை செய்வோன்; மேற்பார்வை செய்வதற்காக இறுக்கும் வரி

கண்காணிக் கணக்கர் முதல் : கண் காணிப்போர் செலவுக்காக இடும் முதல்

கண்காணி நாயகம் : மேற்பார்வை யிடுவோர் தலைமை உத்தியோகம்

கண்காணிமாடெல்லு : மேற்பார்வையிடுவோருக்கு நெல்லாக இறுப்பது

கண்டகம் : வேலி, 'ஏக்கரா' போன்ற நில அளவு

கண்டகசோதனை : துஷ்ட நிக்கிரகம்; குற்றம் புரிபவர்களைத் தண்டித்தல் (ஜடிலவரமன் பராந்தக பாண்டியனுடைய ஆணைமங்கலம் செப்பேடுகளையும் கௌடில்பரது அர்த்த சாஸ்திரத்தையும் பார்க்க)

கண்டத்துடர், கண்டநாண் : கழுத்தணிவகை

கண்டன் : வீரம் மிகுந்தவன்

கண்டப்படை : கட்டடத்தின் அதிஷ்டானத்தில் அடிப்படை

கண்டம் : முகமண்டபப் பகுதி ; அதிஷ்டானத்தின் ஒரு பாகம்

கண்டழிவு : எதிர்பாராத செலவு

கண்டு : கழுத்தணியான மாலையில் பதக்கம் போன்ற ஓர் உறுப்பு

கண்டுழவு : அரசனது சொந்த நிலம்

கண்ணுலக் காணம் : கல்யாணத்துக்காகச் செலுத்தும் வரி ; கல்  
லாணக் காணம், கல்லால காணம் எனவும் குறிக்கப் பெறும்

கண்ணுடி : முகம் பார்க்கும் கண்ணுடிக்கான வரி ; முகம் பார்வை  
என்றும் காண்பது ; பரத்தையரிடமிருந்து வசூலிக்கப் பெற்றது  
போலும் ; கன்னட சாசனங்களில் பெதபினுகு (அதாவது மேனி  
மினுக்குபவள்) என்று காணப் பெறுவதை ஒப்புநோக்குக

கண்ணுறு : பாசன வாய்க்கால்

கண்ணிட்டுக்காணம் : கண்காணிப்போருக்குக் கொடுக்க வேண்டிய  
தொகைபோலும் (கரிசலாங்கண்ணி என்னும் மருந்துச்செடியைப்  
பயிரிடுவதற்காகச் செலுத்தும் வரியெனவும் இதைக் கொள்வர்)

கண்மலர் : விக்கிரகங்களுக்கு அணியும் விழிமலர் போன்ற ஆபரணம்

கண்மாளர் : கம்மாளர்

கணக்கக்காணி : கிராமக் கணக்கர்களுக்கு விடும் மானிய நிலம்

கணக்கப்பேறு : கிராமக் கணக்கர்களுக்கு நெல்லாக இறுப்பது

கணகன் : கணக்குப் பிள்ளை

கணப்பெருமக்கள் : ஊர்க்காரிய நிர்வாகிகள்

கணபோகம் : அவர் அவர் தனித் தனிப் பகுதிகளை அனுபவிக்காமல்  
முழுவதையும் கூட்டாக அனுபவித்து மொத்தத்தில் அவர் அவருக்கு  
உரிய பங்கைப் பெறுதல்.

கணுசாரம் : பிச்சை ஏற்போர் இறுக்கும் வரி

கணிமுற்றாட்டு : கணத்தார் அனுவிப்பதற்காக ஸர்வமானியமாக  
விடப்பெற்ற கிராமம் ; கண்போகத்தில் உள்ள முற்றாட்டுக் கிராமம் ;  
(ஜோஸ்யர்களுக்கு விடும் மானியமாகக் கருதுவர் சிலர்)

கத்திக்காணம் : ஆயுத வரி ; ஆயுதம் தரிப்பதற்கா அல்லது தயாரிப்ப  
தற்கா என்பது விளங்கவில்லை

கதலிகை : ஒட்டியாணம் போன்ற ஆபரணத்தின் ஓர் உறுப்பு

கதர்க்காணம் : கதிராகக் கொடுக்கும் வரி

கந்மி (கருமி) : அதிகாரி ; பணியாட்களுக்கு மேற்பட்ட பதவி  
கொண்டவர்

கப்பம் : தொழிலாளர்கள் சிலர் அவ்வக்காலங்களில் செலுத்துவது  
 கம்பி : காதணிவகை  
 கம்மாணர் : கம்மாளர்  
 காண்ம் : நாட்டு நிவாகத்திலே உள்ள குற்றங்குறைகளைக் காணும்  
 பெரிய அதிகாரி (விஜயநகர ஆட்சிக் காலத்தில் வழக்கில் இருந்தது)  
 கர்த்தாக்கள் : மதுரை நாயக்க மன்னர்களைக் குறிப்பிட்ட பட்டப்  
 பெயர்  
 கர்ப்பூரவிலை : கோவில் நிலங்களைப் பயிரிட்டு அனுபவிப்பதற்காக  
 அவற்றின் வரியையும் சேர்ந்து மொத்தமாகக் கொடுக்கும் பணம்.  
 கரகிராமம் : அரசாங்கத்துக்கு வரி செலுத்தும் (ரயத்துவாரி) தனிக்  
 கிராமம்  
 கரடிகை : ஓர் ஆபாண உறுப்பு  
 கரடு : ஒருவகை முத்து  
 கரண்டிகை : மகுடத்தின் ஒருவகை ; மகுடத்தின் ஒருபாகம்  
 கரண்டிகைச்செப்பு : சுண்ணாம்புச் செப்பு  
 கரணம் : பத்திரம் ; சீட்டு ; கணக்கன்  
 கரணம் : வழக்குகளை விசாரிக்கும் நியாய சபைகளுள் ஒருவகை ; அதி  
 கரணம் என்பதற்குத் தாழ்ந்தது என்பர்  
 கரணத்தார் : கரணம் என்னும் நியாய சபையின் உறுப்பினர்  
 கரணிக்கசோடி : கணக்கர் வரி  
 கரணத்திரம் : வீடு கட்டக் கூடிய மனை  
 கரி : பயிர் தீய்ந்து போனது  
 கரிவி (கருவி) : நாவிதர் கத்தி  
 கரு : மண்மேடு  
 கருக்கு : தங்கம் வெள்ளி முதலிய பாத்திரங்களில் பொறித்த சித்திரம்  
 கருஞ்செய் : புன்செய் நிலத்திலே முன்னால் பயிரிடாத நிலம் ; கழனிப்  
 புன்செயினின்றும் வேறான காட்டுப் புன்செய்  
 கருஞ்செய் : நன்செய் எனவும் கொள்வர்  
 கருவி பணம் : ஆபுதங்களின் மீது வரி ; நாவிதர் செலுத்த வேண்டி  
 யது போலும்  
 கருவூலவரி : பொக்கிஷத்தின் காவலுக்கும் விலையுயர்ந்த பொருளை  
 அதிலே வைத்துப் பாதுகாத்தற்கும் இறுக்கும் வரி  
 கரை : பங்கு, விகிதாசாரம்  
 கரைக்கூறு செய்வார் : கிராமங்களிலே அவர் அவர் அனுபவிக்க  
 வேண்டிய நிலங்களைப் பிரித்துக் கொடுக்கும் பொறுப்பு வாய்ந்தவர்

கரைநிலம் : அவ்வப்போது ஊராரிடம் மாற்றி மாற்றி அனுப்புகத்  
தகுக் கூறுபோட்டு ஒப்படைக்கப்படும் நிலம்

கரையீடு : அடைமானம்

கல்லறை : பொக்கிஷங்களை வைப்பதற்குப் பூமியின்கீழ்க் கட்டப்  
பெற்றுள்ள இரகசிய அறை

கல்லாணக் காணம், கல்லாலகாணம் : கண்ணுலக் காணம் பார்க்க

கல்யாணத் திருமேனியாதல் : அரோகதிடகாத்திர ராதல்

கல்லித்திருத்துதல் : மேடான நிலத்தை வெட்டித்திருத்துதல்

கல்லூரி : கோயிலில் சுற்றுத் தாழ்வாரம் ; திருச்சுற்றலை

கலசப்பாணை : தூப கலசம் : தூபக் கால்

கலசமாட்டுதல் : கலசத்தால் திருமஞ்சனம் செய்வித்தல் ; கும்பா  
பிஷேகம்

கலபை, கலாபம் : கலகம்

கலம் : சாப்பிடும் பாத்திரம்

கலம் : பத்திரம் ; ஆதரவுச் சீட்டு

கலம், கலன் : வில்லங்கம்

கலனை : தொழிலாளர்கள் ; அவர்களுடைய சங்கம்

கலிங்கவாரியம் : கலிங்கு, அனை போன்றவற்றைக் கவனிப்பதற்காகக்  
கிராமச் சபையாரால் அமைக்கப்பட்ட குழு

கவர் : ஆற்றுக் காலில் பிரியும் கிளை

கழஞ்சு : முன்னாளில் வழங்கிய பொன்னாணயம் ; அதன் எடையையும்  
குறிக்கும்

கழனிக்குளம் : நன்செய் நடுவில் உள்ள குளம்

கழனிப் புன்செய் : காட்டுப் புன்செயினின்றும் வேறான புன்செய் நிலம்

கழனிவாரியம், கழனிவாரியப் பெருமக்கள் : விவசாயத்தைக் கவனிக்  
கும் ஊர்ச் சபையார்

கழைந்து : கழஞ்சு என்பதன் வேறு வடிவம்

களர்ப்பாழ் : உப்புப் படிந்த பாழ் நிலம்

களரி : விசாரணை ஸ்தலம் ; சபை ; கச்சேரி

களாவம் : இடையணி ; ஒட்டியாணம் போன்றது

கற்கவி : கதவுநிலையின் மேலே இடப்பட்டிருக்கும் பாவுகல்

கற்காரம் : கருங்கல்லால் ஆன கட்டடம்

கற்கிடை : கல்லால் ஆன வட்டம் ; செங்கல் சூளை

கற்படுத்தல் : கல்லால் தளம் போடுதல்

கற்பதித்தான் : சிலாசாசனம் செய்தவன்

கரணதண்டம் : கரணம் என்னும் நியாய சபையால் விதிக்கப் பெற்று

அதற்குச் செலுத்தவேண்டிய அபராதத் தொகை

கற்பற்று : மாணிக்கத்தின் குற்றம்

கற்பித்தல் : பிரதிஷ்டை செய்தல்

கற்றளி : கற் கோயில்

கன்று மேய் பாழ் : கிராமத்தில் கால்நடை மேய்வதற்கான நிலம்

கன்னக்காணன் : கன்னான்

கன்ன புஷ்பம் : மலர் போன்றதும் காதில் அணிவதுமான ஆபரணம்

கன்னாடு, கல்நாடு : இறந்தவர் ஞாபகார்த்தமாகக் கல் எழுப்புதல்

கன்னாரிறை : கன்னாநத் தொழில் செய்வோர் செலுத்தும் வரி

காகபிந்து : கரும்புள்ளி

காகவிருந்தம் : வைரத்தின் வகை

காசாயக்குடி : ஊர்ப்பொதுவேலை செய்வதென்னும் நிபந்தனையின்

மேல் கிராம மனைக்கட்டில் குடியிருக்கும் குடிமக்கள்

காசாயம் : காசாக இறுக்கும் வரிவகைகளின் பொதுப்பெயர் ; காசாய

வர்க்கம் என்றும், காசு வர்க்கம் என்றும் குறிக்கப்பெறும்

காசுகடமை : ரொக்கமாக இறுக்கும் வரி

காசுகல் : தங்கம் முதலியவற்றை நிறுக்கும் எடை

காசுகொள்ளா இறையில் : ஒருவகை வரியும் இல்லாமல் அளிக்கப்

பெற்ற நிலம்; வரிநீக்கிய நிலத்துக்குப் பின்னால் இறுக்கவேண்டிய

வரிக்காக மொத்தமாகச்சேர்த்து முதல் கொள்ளாத நிலத்தையும்

குறிக்கும்

காசு கொள்ளா ஊர்க்கீழ் இறையில் : எந்த வரியும் இல்லாமல் அளிக்கப்

பெற்ற நிலம்; அந்த வரியை அரசாங்கம் நீக்காமல் கிராமசபையே

இழித்து அந்த வரிக்குறையைச் சபையாரே ஏற்பதற்கும்

காட்சி : காணிக்கை; கையுறை

காட்சி எருதுக் காசு : நல்லெருது பார்க்க

காட்டப் பெறுதல் : ஆதாரமாக எடுத்துக்காட்டுவது; பாத்தியதை

கொண்டாடுதல்

காட்டாள் காசு : முன்னாளில் வழங்கிய வரிவகை; காடுகாவல் என்று

வழங்கியது இதுவேபோலும்

காடுகாவல் : காடுகளைப் பராமரிப்பதற்காக இறுக்கும் வரி [காடு .

என்னும் சொல் இடுகாட்டையும் குறிக்கும்]

காடுகோள் : விளைநிலம் காடுமண்டிப்போதல்

காடுதரிசு : செடிகள் முளைத்த தரிசு நிலம்

காணம் : முன்னாளில் வழங்கிய நிறை ; ஒரு நாணயம் ; பாகம் அல்லது பங்கு

காணி : பரம்பரை உரிமை ; அதுபவிக்கும் உரிமை ; காணியாட்சி பார்க்க

காணி : ஒரு நிறை

காணிக்கடன் : நிலவரி ; காணிக்கூலி என்பதும் இதுவே போலும்

காணிக்கை : அரசனுக்கும் சில அதிகாரிகளுக்கும் செலுத்தவேண்டிய கையுறை

காணிப்பற்று : ஒருவருக்கு உரிமை உள்ள கிராமம் அல்லது நிலம்

காணிப்பிடிபாடு : நிலச்சாகுபடிக்கான உரிமைப் பத்திரம்

காணிமாறுதல் : உரிமை நிலத்தை இழத்தல்

காணியாண்மை, காணியாட்சி : பரம்பரையாக அதுபவிக்கும் உரிமை

காணிவிலை : உரிமையை விற்றுக் கொடுத்தல்

காணிவேட்டி : முன்னாளில் வழங்கி வந்த வரிவகைகளுள் ஒன்று ; வேட்டி என்பதன் ஒரு பிரிவு போலும் ; விளை நிலங்களிலே குழி வெட்டுவது போன்றதாக இருக்கலாம்

காந்தருவி : பாடுபவன்

காமக்காட்டம் : சிவன் கோயிலில் பார்வதிக்கெனத் தனியாக அமைந்துள்ள அம்மன் சந்நிதி

காமம் : கிராமம் ; காமக்காணி, காமக்கிழான் போன்று சேர்ந்துவருவதிலே காண்க

கார் : ஐப்பசி-கார்த்திகையில் அறுவடையாகும் நெல் ; மழைக்காலத்தில் பயிர் செய்யும் நெல் ; அதன் அறுவடைக்காலம்

கார்த்திகைக்காசு, கார்த்திகைக்காணிக்கை, கார்த்திகைப்பச்சை, கார்த்திகையரிசி : கார்த்திகையில் அறுவடைக் காலத்தில் அளிப்பது ; ஆடிப்பச்சை பார்க்க

கார்மறு நிலம் : இருபேரக சாகுபடி உள்ள நிலம்

காரணவன் : கணக்கன் ; காரணிகன், கரணத்தான் எனவும் பெறுவன் காரளத்தல் : நெல் அளத்தல்

காராண்கிழமை, காராண்மை : பயிரிடும் உரிமை ; அதற்கான வரி

காரணிக்கஜோடி : கணக்கர் செலுத்தும் குறைந்த வரி

காரிய கர்த்தா, காரியத்துக்குக் கடவர் : ஒருவருக்காகக் காரியத்தை நிர்வகிப்போர் ; ' ஏஜண்ட் '

காரியவாராய்ச்சி, காரிய வாராய்ச்சிப்பேறு : தணிக்கையாளர்க்கு இறுக்கும் வரி ; ஆராய்ச்சி பார்க்க



கால்படை : சுவரின் அடிப்பகுதி

கால்வட்டம் : கால்அணி வகை

காலத்தேவை : முன்னாளில் வழங்கிவந்த வரிவகைகளுள் ஒன்று; என்னவென்பது விளங்கவில்லை

காலப் போல்லாங்கு : கெட்டகாலம்; காலதோஷம் எனவும் பெறும்

கால் அளவு கூலி, காலளவுப்பாட்டம் : நிறுத்தல் அளவுக்கு விதித்து வந்த வரி

கால்அளவு கோல் கூலி : நில அளவுக்கு விதித்துவந்த வரி

காலுக்கழுத்து : கணைக்கால்

காவணம் : சோலை; நந்தவனம்

காவல் கட்டணம் : தலையாரி வரி

காவிதி : முன்னாளில் அரசர் அளித்துவந்த ஒரு பட்டம்; கணக்கர்

காவிதிமை : கணக்கு வேலை

காளி கணத்தார் : காளிகோயில் நிர்வாகத்தைக் கவனிக்கும் சபையார்  
காஹளம், காஹளி : எக்காளம் போன்ற வாத்தியம்

கிடாரம் : கொப்பரை

கிடை : வேதம் ஒதும் குழாம்; வேத பாடசாலை

கிடைப்புறம் : வேதம் ஒதுவிப்பதற்காக விட்டப்பட்ட நிலம் அல்லது கிராமம்

கிம்புரிமுகம் : ஆபரண முகப்பின் ஓர் உறுப்பு

கிரமவித்தன் : வேதத்தின் கிரமபாடத்தில் வல்ல பிராமணன்

கிராம கண்டகர் : கிராமத்தின் நலனுக்கு விசேஷிகள்; கிராமத் துரோகிகள் எனவும் பெறுவர்

கிருகுலம் : சில்லறையாக விற்பனை செய்யும் பொருள்களின் மீது இறுக்கும் வரி அல்லது சுங்கம்; கிருகூல விசேஷம் எனவும் பெறும்; கூலம் என்பதையும் பார்க்க

கிளிக்கத்தி : கத்திவகை

கீழ்க்கலனை : கிராமத்தொழிலாளி

கீழ்க்குமிழி : ஒரு வரயக்காலின் நீர் அதன் குறுக்கே செல்லும் மற் றொரு வரயக்காலின் கீழாகச் செல்லும்படி அமைந்த கட்டடவேலை

கீழ்ப்பாதி : குடிவாரம்

கீழிறை : சிறு வரிகள்; கடைசித் தரங்களில் இறுக்கும் வரிகளும் ஆகும்

கீழிறைப்பாட்டம் : மீன்பாட்டம் போன்ற சிறு வரிகள்

கீழீடு : கீழ்க்குத்தகை ; சார்த்த நிற்றல் ; மற்றொன்றுக்குக் கீழ்ப் பட்டது

கீற்றுவரி : கீற்று வேய்ந்த குடிசைகளுக்கான வரி

குதை : துறவிகள் வாழும் மடம்

குச்சி : குச்சில், தர்ப்பை போலும் (குடமும் குச்சியும் கொண்டு கோயில் புகுவான்)

குச்சுக்காணம் : குபவர் தாங்கள் செய்யும் பாணைகளுக்குக் கொடுக்க வேண்டிய தொழில் வரி ; திரிகைஆயம் பார்க்க

குடதேவர் : அகஸ்தியர்

குடநாழி : ஒரு குடத்துக்கு ஒரு நாழி விதம் இறுக்கும் வரி

குடப்படை : உட்கோயிலின் அடி மட்டத்தில் உள்ள கட்டடப்பகுதி

குடமுழா : குடம் போன்ற வடிவுடையதாக உள்ள பெரிய முழவு வாத்தியம்

குடவர் : விஷ்ணு கோயிலில் பணி புரிவோருள் ஒரு பிரிவினர் ; கிருஷ்ணனை வழிபடுவோர் போலும் ; மாடு மேய்ப்பவராகவும் இருத்தல் கூடும் ; கோடவர் எனவும் பெறுவர்

குடவறை : நிலவறை ; கோபுரத்தில் உள்ள சிற்றறை

குடவிளக்கு : பூசை வேளையில் குடம் போன்ற விளக்கு எடுத்து நாட்டியம் ஆடிக்கொண்டே உருத்திர கணிகையர் காட்டுவது

குடவோலை : குடத்தில் இட்ட ஓலைச்சீட்டு ; அவ்விதம் இட்டுச் சபையாறைத் தேர்ந்தெடுத்தல்

குடிக்காகு : குடிமக்கள் கொடுக்கும் வரி ; குடிக்காணம் ; குடிப்பணம் என்பனவும் இதுவே போலும்

குடிநைக்கல் : நிர்ணயமான எடைக்கல் ; குடிநற்கல் எனவும்படும்

குடிநீங்கா இறையிலி : ஏற்கெனவே உள்ள குடிகளையும் அவர்களுடைய உரிமையையும் நீக்காமல், மேல் வாரத்தை மட்டும் அதுபவிப்பதாக வரி நீக்கிக் கொடுக்கப்பட்ட கிராமம் அல்லது நிலம்

குடிநீங்காத் திருவிடையாட்டம் : ஏற்கெனவே உள்ள குடிகளை நீக்காமல் விஷ்ணு கோயிலுக்கு அளிக்கப்பெற்ற கிராமம்

குடிநீங்காத் தேவதானம் : ஏற்கெனவே உள்ள குடிகளை நீக்காமல் கோயிலுக்கு அளிக்கப்பெற்ற கிராமம்

குடிநீங்கி(ய)தேவதானம் : பழங்குடிகளை நீக்கிக் கோயிலுக்கு அளித்த நிலம் அல்லது கிராமம் ; இதனால் கோயிலே மேல்வாரம் கீழ்வாரம் ஆகிய இரண்டையும் அதுபவிக்கமுடியும்

குடிமை : நிலவரி நீங்கலாக, அரசாங்கத்துக்கு இறுக்கும் மற்ற வரி களைப் பொதுவாகக் குறிக்கும் சொல் [நாட்டின் குடியாக வாழ்வ தற்கு இறுக்கும் வரிப்பணம்]

குடிமைப்பாடு : ஊழியம்; ஊர்ப்பொதுவேலை

குடியிருக்கை : கிராமத்தில் குடிகள் வாழும் இடம்

குடியிலார் : குடிகள்

குடினை : குடி நற்கல்; நிர்ணயிக்கப்பெற்ற நிறையையுடைய எடைக் கல்

குடும்பு : ஊரின் பகுதி; அதனால் குடும்பு வாரியம் : ஊரிலே அந்த அந்தப் பகுதிக்கான சபைக்குழாம்

குண்டு : உருண்டையான பொன் மணி

குண்டு : குதிரை

குண்டிகைக்கல் : சமணர் கோயில்களுக்குச் சொந்தமான பள்ளிச் சந்த நிலங்களின் எல்லையைக் குறிக்கக் கமண்டலத்தின் உருப் பொறித்து நாட்டும் கல்

குணவியது : மேன்மையானது

குணவியன் : மாணிக்க வகைகளுள் ஒன்று

குத்தலரிசி : குற்றித்தீட்டிய அரிசி

குத்துக்கால் : தடை

குதம்பை : காதணி வகை

குதிரைச் சேவகன் : குதிரை வீரன்

குதிரைப்பந்தி : குதிரை கட்டும் இடம்; அதற்கான வரி; குதிரை வரி, குதிரைமாற்று, குதிரைவிலாடம் எனவும் பெறும்

குதிரைமாற்றம் : முன்னாளில் வழங்கிவந்த ஒரு நாணயம்; குதிரை உருவம் பொறிக்கப்பட்டது போலும்

குப்பி வயிரம் : வைர வகை

குமரகச்சாணம் : முன்னாளில் வழங்கி வந்த வரிவகை; முருகக் கடவு ளின் கோயிலுக்காக இறுக்கவேண்டிய (ஒரு கட்டியாணம்) பொன் வரி எனக் கொள்ளலாம்

குறிழி : நீர் ஊற்று; மதகு; ஒரு வாய்க்காலின் நீர் அதன் குறுக்கே செல்லும் மற்றொரு காலின் கீழாகச் செல்லும்படி அமைந்த கட்டிடவேலை

குமரவர்க்கம் : அரசாளும் ராஜகுடும்பத்துக் குமாரர்களாகத் தங்களைக் கருதும் சிற்றரசர்கள்

குமுதப்படை : கர்ப்பகிருக மதிலின் அடிப்பாகம்

குரத்திகள் : சமண மதத்திலே ஆசாரிய பதவி வகிக்கும் பெண்

குரவடிகள் : சமண மதத்தின் ஆசாரியர்

குரப்பு வெட்டி : பழையநாள் வரிவகை ; வெட்டி என்னும் இனத்தைச் சேர்ந்தது ; பாசனக்கால்களை அணைத்து நீர் திருப்பும் வெட்டிவேலை போலும்

குரால் பசு, குராற் பசு : கபிலை நிறப் பசு

குலை : எழுப்பிய கரை ; வரம்பு

குலைவெட்டி : நீர்க்கால்களின் கரைகளை வெட்டிச் சீர்செய்வது

குழிவரியேற்றுதல் : நிலத்துக்கு வரி விதித்தல்

குழிவு : மாணிக்கக் குற்றங்களுள் ஒன்று

குளக்கீழ் : அந்தக் குளத்தின் பாய்ச்சலில் உள்ள பூமி

குளப்பிரமாணம் : குளம், அதனை அநுபவிக்கும் உரிமை ஆகியவற்றின் விற்பனை

குளவடை : ஏரி குளங்களை அநுபவிக்கும் உரிமை ; அவற்றிலிருந்து கிடைக்கும் வருவாய்களையும் குறிக்கும்

குளிக்கும் இடம் : அபிஷேக மண்டபம் பார்க்க

குளிகை : முன்னாளில் வழங்கி வந்த நாணயம் ; கோளகை எனவும் பெறும் ; உருவத்தைக் கொண்டு பெயரிடப்பட்டதுபோலும்

குளிர்ந்த நீர் : இரத்தினங்களிலுள்ள நீரோட்டம்

குற்றத்தண்டம் : செய்த குற்றத்துக்குரிய தண்டனை ; அதற்காகச் செலுத்தும் பணம்

குற்றநெல் : நெல் குற்றுவதற்கு உரிய கடமை

குற்றேற்றம் : சிறு ஏற்றம்

குறங்கு : சிறு வாய்க்கால்

குறி : கிராமச்சபை

குறு கூலி : நெல் குத்துவதற்கான கூலி

குறுணிப்பாடு : குறுணி நெல் விதைப்பாடுள்ள நிலம்

குறுமடல் : விபூதி வைக்கும் சிறிய மடல்

குறைவறுப்பு : அரண்மனைக்கு உபசாரமாக அனுப்பும் பண்டச்சமை

குன்றி : குன்றுமணி, பொன் நிறுக்கும் எடை

குனிப்பம் : நாட்டிய வகை ; சந்திக்குனிப்பம் பார்க்க

கூத்தம்பலம் : அரண்மனை அல்லது கோயிலில் உள்ள நாடக அரங்கம்

கூலம் : தானிய வியாபாரம் ; தானியங்களுக்கு விதிக்கும் வரி

கூலிச்சேவகன் : கூலிப்படையாளன்

கூற்றரிசி : குற்றநெல் பார்க்க ; கூற்று நெல்லு எனவும் பெறும்

கூற்றன்வாய் : தலைமதகு  
 கூற்றுநெல்லு : கூற்றரிசி பார்க்க  
 கூறடைத்தல் : பகுதி பகுதியாகப் பிரித்து ஒப்படைத்தல்  
 கூறுசெய்வான் : காரியங்களை வகைசெய்து நிர்வகிப்பவன்  
 கூறுதல் : விலை கூறுதல் ; ஒருவன் தன் பொருளுக்கு நிச்சயித்த விலை  
 யைத் தெரிவிப்பதை முற்கூறுதல் என்றும், அதை வாங்குபவன்  
 ஏற்றுக்கொள்வதைப் பிற்கூறுதல் என்றும் கொள்வர்  
 கூண் : பெரும்பாத்திரம் ; அதில் சமைத்த நிவேதனப் பொருள்

கேடுபாதை : சீர்கேடு அடைந்த பாதைகளைச் செப்பனிட்டு நல்ல  
 நிலைமையில் வைத்திருக்கவேண்டிய கடமை

கேட்போர் : பாடம் கேட்போர் ; பாடம் சொல்லுவோர் ; சாத்திரர்  
 பார்க்க

கேள்வி : அரசன் வாய்மொழியாக இடும் உத்தரவுகளைக்கேட்டு உரிய  
 வர்களுக்கு அனுப்பும் அதிகாரி ; நிர்வாக அதிகாரி

கேள்விமுதலி : அரசன் உத்தரவைப்பெறும் பொறுப்பு வாய்ந்த அரண்  
 மனை அதிகாரி

கேள்விவரி : அரசன் உத்தரவுகளை எழுதும் வரிப் புத்தகம்

கைக் கணக்குமுதல் : விவரம் விளங்க வில்லை

கைக்கழுத்து : முன் கை ; மணிக்கட்டு

கைக்காறை : ஒரு வகைக் கையணி

கைக்கோள்ளுதல் : ஏற்று நிர்வாகித்தல்

கைக்கூலி : லஞ்சம்

கைக்கோளமுதலி : கைக்கோளரின் தலைவர்

கைக்கோளர் : தோள் வலி மிகுந்த காலாட்படையினர் ; கோயில்  
 ஊழியர்களுள் ஒரு வகையினர் ; நெய்வோர் [அடவி என்ற சொல்  
 லும் போர்ப் படையினரையும் நெய்வோரையும் குறிக்கும். போர்  
 வீரர்களுக்கும் நெசவாளிக்கும் என்ன தொடர்பு என்பது விளங்க  
 வில்லை. கைக்கோளர் என்ற சொல் கையால் உழைப்பவர் என்று  
 பொருள்படும்]

கைங்கரியபரர் : கோயிலில் பணி விடை செய்வோர் ; உபயகாரர்

கைச்சாத்து : கையெழுத்திட்ட ரசீது

கைத்தடி : ஒப்பம் இடுவதற்குக் கையெழுத்துப் போடாமல் இடும்  
 குறி ; தற்குறி

கைத்தீட்டு : கையெழுத்திட்ட உடன்படிக்கை ; சிறுகுறிப்பு

கைப்போட்டு : கையில் அணியும் ஓர் ஆபரணம்

கைபிடி : கையிற் பெற்றுக்கொண்ட பொருள்

கைம்மாட்டாங்கு : தற்குறி; கைத்தடி பார்க்க

கையாளித்தல் : ஒப்படைத்தல்

கையாறு : கண்ணி வாய்க்கால்

கையீடு : பணம் செலுத்திய ரசீது

கையுருவிச்சுவர் : கைப்பிடிச்சுவர்

கையுறை : பெரியோர்களைக் காணச் செல்லும்போது அவர்களுக்கு அளிக்கும் காணிக்கை

கையெழுத்து : தீர்மானித்து எழுதிக் கொடுத்த பத்திரம்

கையெழுத்தோலை : எழுதிக்கொடுத்த பத்திரம்; கடன் சீட்டு

கையேற்பு : பிச்சைக்காரர் வரி; தெலுங்குச் சாசனங்களிலே காண

சாரம் என்று காண்பது; முட்டி என்பதையும் பார்க்க

கைவட்டகை : பாத்திரவகை

கைவளர : பரவ

கைவாசி : சந்தை விற்பனைக்கு வந்த நெல் போன்ற பண்டங்களில் ஒரு கையெனக் கொள்ளும் உரிமை; அள்ளு என்பதைப் பார்க்க

கைவிலை : அப்போதை விலை

கைவினைக்குடி : கைத்தொழில் செய்து வாழ்வோர் [கைஜீதம் என்றும் சொல் தெலுங்கு நாட்டுச் சாசனங்களிலே கூலிப்படையைக் குறிக்கும்]

கோக்குவாய் : ஆபரணத்திற் செருகும் பூட்டு

கோட்டகாரம் : நெல்களஞ்சியம்; கோட்டாரம்

கோட்டி மத்தளம் : பெரிய மத்தளம்

கோட்டைக்கூலி : கோட்டையை ஆமணக்கு விதையெனக் கொள்ளலாம்; ஆயினும் இது கோட்டைக்கூலியே போலும்

கோடவர் : கோயிற் கொத்துக்களுள் ஒரு பகுதியார்; குடவர் எனவும் காணப்பெறும்

கோடி : அரைஞாண்

கோடிக்கடமை : கொடிவேலி என்றும் சித்திர மூலம் என்றும் வழங்கப் பெறும் மருந்துச் சரக்கைப் பயிரிடுவதற்கான வரியாகக் கொள்வர்; எனினும் இது கோடிக்கடமையே யாகும் போலும்; செங்கோடிக்காணம் என்பதையும் பார்க்க

கோடுக்கன் : மகன் (கொடுகு என்னும் தெலுங்குச் சொல் பார்க்க)

கொத்து : பிரிவு; ஊழியர் வகை

கொதி : பிரசாதம்; கோயிலில் நிவேதனத்துக்கான சோறு

- கோழு : ஏர்க்கொழுவின் மீது இறுக்கும் வரி  
 கோழுந்து : மருக்கொழுந்து  
 கோழுவாரம் : பயிரிடுவோனுக்கு உரிய வாரம்  
 கோள் : சிறு நிறையளவு  
 கோள்கை : பாத்திரவகை ; கோள்கலம் என்பதே போலும்  
 கோள்கை : விக்கிரகங்களுக்கு இடம் கவசம்  
 கோள்முறைப்பாடு : காணிக்கைபோல் கிரமமாகக் கொள்ளும் வரி  
 கோள்வரி : நெல்லாய வகை ; வசூல் செய்வதற்கான செலவைச் சரிக்  
 கட்டுவதற்குப்போலும்  
 கொற்றிலக்கை : கொற்றும் இலக்கையும் ; அதாவது சோறும் தங்கும்  
 இடமும்  
 கொற்று : உணவு  
 கோட்டகம் : பரந்து ஆழமான நீர்நிலை  
 கோட்டைக்கூலி : கோட்டையின் பராமரிப்புக்காக வசூலிக்கப்பெறும்  
 வரி ; கோட்டை மகமை எனவும் பெறும்  
 கோடம் : சிகரமாகச் செய்யப்பெற்ற கிரீடத்தின் பாகம்  
 கோப்பதவாரம் : அரசுக்கு உரிய இறை  
 கோமளம் : மாணிக்க வகை  
 கோமுகம் : பசுவின் முகம்போல் செய்யப்பெற்ற நீர்விழும் வாய்  
 கோமுறை : அரசிறை  
 கோயில் கேள்வி : கோயில் காரியங்களை நிர்வகிப்பவன்  
 கோயில் வாசி : அரண்மனைக்கு உரிய சில் இறை  
 கோயில் வாரியம் : கோயில் காரியத்தை நிர்வகிப்பதற்காக ஊர்ச்சபை  
 யினர் அமைக்கும் குழு  
 கோயிற்கொத்து : அரண்மனை அல்லது கோயில் பணியாட்கள்  
 கோல் கூலி : அளவு கோலுக்கான வரி  
 கோல் நிறை கூலி : கோலால் நிறுத்து விற்கும் பொருள்கள் மீது வரி  
 கோவணவர் : கோயிலில், முக்கியமாக விஷ்ணு கோயிலில், ஊழியம்  
 புரிந்தவர்களுள் ஒருவகையினர் ; துறவிகள் போலும்  
 கோலிக்கல் : அரண்மனை  
 கோவை : முன்னாளில் வழங்கிய பொன் நாணயம்  
 கோள்கை : குளிகை பார்க்க  
 கோளோலை : அரசன் உத்தரவு

சக்கத்து : முத்துவகை

சக்கரக்கல் : ஆழிக்கல் பார்க்க

சக்கரக் குளிகை : முன்னுளில் வழங்கிவந்த ஒரு நாணயம்; சக்கரப் பணம் என்பதும் இதுவே போலும்

சக்கரகாணிக்கை : குயவர் இறுக்கும் வரி; திரிகை ஆயம் எனவும் பெறும்

சக்கரம் : ஆஞ்ஞா சக்கரம்; அரசன் ஆணை; அந்த ஆணையை நிறைவேற்றும் அதிகாரி (சோழன் சக்கரம்)

சக்கரவாளம் : உலகத்தைச் சூழ்ந்திருப்பதாகக் கருதப்படும் மலை  
சகரையாண்டு : சகாப்தம்

சங்கரப்பாடியார் : செக்கார்; எண்ணெய் வியாபாரம் செய்வார்

சஞ்சீவராயர் : அனுமார்

சட்டப்பெருமக்கள் : சட்டர்களுக்குள்ளே நிறுவப்பெற்ற சபையின் உறுப்பினர்கள்

சட்டம் : மாணிக்க வகை

சட்டர் : பிரம்மசாரிகள் : கோயில், அதன் அங்கமான சாலை ஆகிய வற்றை நிர்வகிப்போர்; சாத்திரர் என்பதையும் பார்க்க

சட்டிச்சோறு : கோயில் வேலைக்காரர்களுக்குக் கொடுக்கும் உரிமைப் பிரசாதம்

சடங்கலி : வேதத்துக்கு உரிய ஆறு அங்கங்களையும் அறிந்தவன்

சண்டப்பிரசண்டர் : விஷ்ணு கோயிலில் உள்ள துவராபாலகர் இருவர்  
சண்டாளப்பேறு : பழைய நாளில் வழங்கி வந்த கடமை வகை; சண்டாளர்களிடமிருந்தோ அவர்களுக்காகவோ வசூலிக்கப்பட்டது போலும்

சண்டேசுரப் பேருவிலை : சிவன் கோயில் நிலங்களை விற்கும்போது கொடுக்கப்படும் நிலவிலை; சிவனுடைய ஆதிதாசர் ஆன சண்டேசுரப்பெருமான் பெயரால் விற்கப்படுவது

சண்டை : செண்டை என்னும் வாத்திய வகை

சண்பங்காறை : தாலியின் உருவகை

சத்திமுகம் : அரசனது ஆணைப்பத்திரம்

சத்தியஞான தரிசனிகள் : சைவசமயத்தின் ஒரு பிரிவைச் சார்ந்தவர்; மெய்கண்டார் சந்தானத்தாரே போலும்

சத்திமுற்றம் : ஊரிலே சக்தியாகிய தூர்க்கை போன்ற பெண் தெய்வத்துக்குத் தனியாக எழுப்பப்பெற்ற கோயில்

சதாசேவை, சதாசேவை : நித்திய ஊழியம்



சதிரம் : சதுரம் என்பதன் வேறு வடிவம்

சதிரவாசகன் : கெட்டிக்காரத்தனமாக, சதுரமாகப் பேசுபவன்

சதுப்பேதிமங்கலம், சருப்பேதிமங்கலம், சதுர்வேதிமங்கலம் : (நாலு) வேதம் தெரிந்த பிராமணர்களின் குடியிருப்பான கிராமம்; பெரும்பாலும் இறையிலியாக வழங்கப்பட்டிருக்கும்

சதுர்வேதி பட்டத் தானப் பெருமக்கள் : பிராமணர் குடியிருப்புக் கிராமங்களில் வேதம் வல்லார்களைக் கொண்ட சபை

சதுராலே : ஊரிலே சபை கூடும் இடம்; நாலுகால் மண்டபம்

சந்தானம் : சந்ததி; சிஷ்ய பரம்பரை

சந்ததிப்பிரவேசம் : தலைமுறை வழியாக

சந்தானச்சாபம் : சந்ததி இல்லாமல் போகும்படி இடம் சாபம்

சந்தானிக சைவாசாரியர் : (சந்தான குரவர்) சிஷ்ய மரபில் வந்த சைவாசாரியர்

சந்தி : காலையிலும் மாலையிலும் கோயிற்கால பூசை; குறிப்பிட்ட சிலர் வைத்த நிவந்தங்களுக்காக அவர்கள் பேரில் நடக்கும் பூசைக்கட்டளை  
சந்திக் குனிப்பம் : கோயிலில் பூசை நேரத்தில் தேவடியார் ஆடும் நடன வகை; குனிப்பம், சந்திக்கூத்து ஆகியவை பார்க்க

சந்திக்கூத்து : கோயிலில் சுவாமி முன்பாகத் தேவடியார் ஆடும் கூத்து; சாந்திக்கூத்து, சந்திக்குனிப்பம் என்பனவும் இதுவே போலும்

சந்தியா தீபம் : பகலும் இரவும் கூடும் வேளையில் கோயிலிலே ஏற்றப் பெறும் விளக்கு; பெரும்பாலும் மாலையிலே தான் ஏற்றப்படுவது; காலையில் போடுவதும் உண்டு

சந்திராதித்தவல், சந்திராதித்தவற், சந்திராதித்தவத் : சந்திர சூரியர் உள்ளவரையில்

சந்திவிக்கிரகப் பேறு : கிராம மத்தியஸ்தனுக்குக் கொடுக்கும் கட்டணம்; பத்திரம் எழுதுவோர்களுக்குக் கொடுக்கப்பெறுவதாகவும் கொள்வது உண்டு

சந்திவிக்கிரகி : சண்டை, சமாதானம் ஆகியவற்றைக் கவனிக்கும் அராசாங்க அதிகாரி; மந்திரி; பத்திரம் எழுதுவோரையும் குறிக்கும்

சந்திவிளக்கு : சந்தியா தீபம் பார்க்க

சந்தை முதல் : சந்தையில் வியாபாரிகளிடமிருந்து கொள்ளும் வரி

சப்த சந்தானம் : மகனைப் பெறுவதால் அடையக்கூடிய பயனை அளிப்பனவாகக் கருதப்பெறும் ஏழு நற்காரியங்கள்; அவை, குளம் தோண்டுதல், தன நிகேஷபம், அக்கிரகாரம் அளித்தல், கோயில் எழுப்புதல், நந்தவனம் அமைத்தல், கவிஞரைக்கொண்டு தூல் இயற்றுதல்,

சத்திரம் ஏற்படுத்தல் ஆகிய ஏழுமாம் என்பர் ஒரு சாரார்; மறு வகையில் ஒருவன் தன் வாழ்நாளிலே வழிவழியே தன் புகழை நிலை பெறச்செய்ய இயற்றவேண்டிய ஏழு நற்காரியங்கள் எனக் காணப்படுகிறது; அவை, மகப்பேறு, தூல் இயற்றல், பொருள் திரட்டல், நந்தவனம் அமைத்தல், கன்னியாதானம், கோயில் நிர்மாணம், குளம் தோண்டுவது ஆகிய ஏழுமாம்; சப்தசந்ததி எனவும் பெறும்

சப்பத்தி : தட்டை முத்து; சப்படி என்பதும் இதுவே போலும்

சபாமஞ்சிக்கம் : சபையாருக்கு உரிய தரிசு நிலம்; சபைப்போது, ஊர்ப்போது, ஊர்மஞ்சிக்கம், சபாமத்யமம் எனவும் பெறும்

சபாமாற்றம் : சபையின் உத்தரவு; சபையின் பதில்

சபாமாற்றம் சொல்லுதல் : சபையார் தீர்மானத்தைத் தெரிவித்தல்

சபாவிலை, சபைவிலை : சபையின் உத்தரவால் பகிரங்கமாக நடக்கும் விற்பனை; ஊர்ச்சபையார் நடத்தும் விற்பனைக்கு நிச்சயித்த விலைப் பொருள்

சபாவினியோகம் : கிராமச் சபையினால் இறை நீக்கப்பெற்ற நிலங்களின் வரிப்பணத்தை ஊரார் ஏற்று இறுப்பதிலே வரும் பங்கு; சபையார் செலவுக்கான பணத்துக்கு இறுக்கும் பங்கு

சபை : அகரம், பிரம்மதேயம், சதுர்வேதி மங்கலம் போன்ற பிராமணர் குடியிருப்புக் கிராமங்களுக்கு அமைந்த சபை; குறி என்று குறிக்கப்பெறுவதும் இதுவே

சம்படம் : வழிநடை உணவு; சம்பளம், சம்மாதம் எனவும் வரும்; ஓலைச்சம்படம் என்பதுபோல் காணப்பெறும்; சம்மாதநியோகம் பார்க்க

சம்பிரதி : தலைமைக் கணக்கன்; கோயில் நிர்வாகி

சம்பிரத்தி : பிராப்தி; பேறு; அடையத்தக்கது

சம்மாதநியோகம் : ஓலைச்சம்மாதமே யாகும்

சம்வத்சரவாரியம் : ஆண்டுதோறும் தெரிந்தெடுக்கப்படும் கிராம நிர்வாக சபை; சம்வத்சர கிராம காரியம் எனவும் பெறும்

சமஞ்சஸம் : ஒப்பு; ஒத்திருத்தல்

சமஞ்சிதன் : கிராமம் அல்லது கிராம சபையின் கணக்கன்; கோயில் வேலைக்காரன்

சமயதர்மம் : அவர் அவர் தொழிலுக்கு உரிய தர்மம்; முக்கியமாக நானூதகி, சித்திரமொழி ஆகிய குழுவினர்களுடைய சாசனங்களில் காண்பது

சமய பத்திரம் : உடன்படிக்கைப் பத்திரம்

சமய முதலி : சமயத் தலைவர் ; மக்களின் சமீப ஒழுக்கத்தைக் கண் காணித்து அவர்களுடைய பிழைகளை எடுத்துக் காட்டித் தண்டிக்கும் அதிகாரம் பெற்ற தர்மத்தின் காவலர்

சமயாசாரர் : மக்களின் சமய ஒழுக்கத்தைக் கண்காணிப்பவர் ; சிவ சமயத்தைச் சார்ந்தவர்

சமர் : பட்சபாதம் இல்லாத நடுநிலை

சமரமுத்தீரன் : போரில் காட்டிய வீரத்துக்காக முன்னாளில் அரசர் வழங்கிய பட்டப்பெயர்

சமுதாயத் திருமுகம் : அரசன் முதலியோர் பல வகுப்பினர்க்கும் பொதுவாக விடுக்கும் உத்தரவு

சமுதாயப் பிராத்தி, சமுதாயப் பிராப்தி : குடிசன் பொதுவாக அனுபவிக்கும் நிலங்களிலிருந்து கிடைக்கும் வருவாய் ; அதேபோல ஊர்ப் பொதுவில் செய்யும் செலவு ; இவற்றில் அவர் அவர் பங்கு

சமுதாயம் : கணபோகம் வாய்ந்த கிராமம்

சமுதாயம் : கிராமப் பொது ; கோயில் நிர்வாகம் செய்வார் கூட்டம்

சமைதல் : அமைதல் ; சேர்தல்

சமைப்பு : தர்மத்துக்காகத் தானம் அளிக்கப்பட்டது

சய பத்திரம், ஜய பத்திரம் : விவாதத்தின் முடிவில் தீர்ப்பாக அளிக்கப் பெறும் வெற்றிப் பத்திரம்

சர்வசிரப் பிரதானி : மற்றவர்களுக்கு மேலான தலைமைப் பிரதானி

சர்வ நாயகர் : ராஜாங்கக் காரியங்களை நிர்வகிக்கும் பிரதம அதிகாரி ; பிரதான மந்திரி

சர்வமானியம் : எந்தவிதமான தீர்வையும் இல்லாமல் அனுபவிக்கப் பெறும் நிலம் ; முற்றாட்டு

சர்வாதிகாரி : அரசாங்கத்தின் எல்லாக் காரியங்களையும் நிர்வகிக்கும் பிரதான மந்திரி

சரணத்தார் : வேதத்தின் அந்த அந்தச் சாகையை ஒதுபவர்

சர விளக்கு : ஒன்றன்மேல் ஒன்றாக அடுக்கித் தொங்கவிடப்படும் கோயில் விளக்கு

சரஸ்வதி பண்டாரம் : புத்தகசாலை

சரிகை : கூடுதல் (ஊர்ச்சரிகை : ஊர்க்கூட்டம்); சாரிகை என்றும் காணப்படும்

சரிவாரம் : விளைபொருளிலே மேல்வாரம் கீழ்வாரம் இரண்டையும் சமமாகக் கொள்வது

சரீரம் : ஆள் ; தனிநபர்

சருகூடை : (சருகு கூடை) கிராமப் பொது நிலங்களிலிருந்து உலர்ந்த சருகுகளை அரிக்கும் உரிமை

சலகை : ஒரு தானிய அளவு ; அந்த அளவு விதைப்பாடுள்ள நிலம்

சலாகை : முன்னாளில் வழங்கிய நாணய வகை ; சலாகையச்சு, பழஞ் சலாகை யச்சு, புரீயக்கி பழஞ்சலாகை யச்சு எனவும் பெறும்

சலாபம் : முத்துக் குளித்தல்

சலாவணம் : (ஆவண சலாவணம்) சிராவணம் பார்க்க

சவக்கம் : சதுர வடிவம் உள்ள வைரம்

சவார்ண லிருத்தி : பத்திரம் எழுதும் தொழில்

சவி : சரமணிக்கோவை

சவைக் கடமை : கிராம சபையாருக்கு இறுக்கவேண்டிய வரிகள்

சவைக் கணக்கு : கிராம சபையின் கணக்கர்

சல்லேகனை : சமண மதத்தவர் பட்டினினோன்பு இருந்து உயிர் துறத்தல்

சவையார் : கிராம சபையார்

சவைவாரியர் : சபாவாரியர் ; கிராம சபையின் நிர்வாகக் குழுவினர்

சாங்கம் : முழுதும் ; பத்திரமாய்

சாக்கைக் கூத்து : சாக்கையர் ஆடும் கூத்து

சாகா மூவாப் பேருரு : இறத்தலும் மூப்பும் இல்லாமல் நிரந்தரமாக இருக்கவேண்டிக் கோயிலுக்கு விட்ட கால்நடை ; சாவா மூவாப் பேராடு பார்க்க

சாக்கைக்காணி : கோயிலில் பூசையின்போது கூத்து நடத்தும் சாக்கையருக்கு அளித்த மானியம் ; நிருத்தியபோகம் எனவும் படும்

சாசன பத்தர் : அரசன் வழங்கிய சாசனத்துக்குக் கட்டுப்பட்டவர் ; சாசனம் பெற்றவர்கள்

சாசுவதியம் : சாசுவதம்

சாட்டு வரி : மேய்ச்சல் பூமிக்கான வரிபோலும்

சாத்த கணத்தார் : ஐயனா் கோயில் காரியங்களை நிர்வகிப்பவர்

சாத்தண்டம் : கொலை செய்ததற்கு விதிக்கும் தண்டனை

சாத்தியம் : அஷ்டபோகங்களுள் ஒன்று ; விளைபொருளை அனுபவிக்கும் உரிமை

சாத்திர மாணி : சாத்திரனாகிய மாணவப் பிரம்மசாரி

சாத்திரர் : சட்டர் பார்க்க

சாத்துக்கூறை : திருப்பரிவட்டம் ; விக்கிரகங்களுக்கு அணியும் ஆடை

சாத்துப்படி : கோயில் விக்கிரகங்களுக்குச் செய்யும் அலங்காரம்

சாத்வீக தானம் : பிரதிப் பிரயோஜனத்தை எதிர்பார்க்காமல் அளிக்  
கப்பெறும் தானம் ; அதனால் நீரோடு அட்டிக் கொடுக்கப்பெறாமல்  
அளிக்கப்படுவது

சாதகக் குடி : ஆயுள் முழுவதும் ஊழியம் புரிவதாக ஏற்றுக்கொண்ட  
குடிமக்கள்

சாதி சித்தாயம் : இனவரி பார்க்க

சாந்திக்காரன் : (மலைநாட்டு வழக்கிலே) கோயில் பூசை செய்வோர் ;  
சாந்திசெய்வான், சாந்தியடிகள் எனவும் பெறுவர்

சாந்திக்கூத்தன் : கோயிலில் சாந்திக்கூத்து ஆடுபவன்

சாம்போகன் : கணக்கன் ; சேனபோகும் பார்க்க

சாமந்தன் : மந்திரி ; சிற்றரசன்

சாமி : சுவாமி ; அரசன்

சாரடை : [குளவடை என்பதனோடு சேர்ந்தே காணப்படும்] பொது  
நிலங்களை அனுபவிக்கும் உரிமையைக் குறிப்பது போலும் ; சர  
வடை என்று குறிக்கப்பெறுவதும் இதுவே. மாவடை, மரவடை  
ஆகிய சொற்களையும் கவனிக்க

சாரிகை : கூட்டம் ; சரிகை பார்க்க

சாலாபோகம் : அன்ன சாலைக்காக வரியில்லாமல் விடப்பெற்ற நிலம்  
அல்லது கிராமம் ; அறச்சாலாபோகம் என்றும் குறிக்கப்பெறும்

சாலிகைத்தறி, சாலியத்தறி : சாலியர் உபயோகித்த தறி ; அதற்கான  
வரியையும் குறிக்கும்

சாலியநகரத்தார் : சாலிய வியாபாரிகளுக்காக அமைந்த சபையார்

சாலியர் : துணி நெய்வோருள் ஒரு வகையார்

சாலை : உணவு அளிக்கும் அறச்சாலை : அதனோடு இணைந்துள்ள பாட  
சாலையையும் குறிக்கும்

சாவடி : உசாவடி பார்க்க

சாவாமுவாப்பேராடு : இறத்தலும் மூப்பும் இல்லாமல் நிரந்தரமாக  
நிலைத்திருக்கும் ஆடு ; கோயில்களுக்கு அளிக்கும் ஆடுகளையே இவ்  
விதம் குறிப்பர் ; [சாவினாலோ மூப்பினாலோ ஆடுகளின் தொகை  
குறையும்போது குட்டிகளைக்கொண்டு குறையை நிறைத்து, கோயி  
லுக்குச் செலுத்த வேண்டிய நெய் முதலியவற்றை முட்டாமல்  
செலுத்தவேண்டியதற்கு உதவும்]

சாவி : மணி பிடிக்காமல் பழுதான பயிர்

சாவேறு : பகையாசனைச் சூழ்ந்து காக்கும் படைமீது ஊட்டுத்துச்  
செல்ல முபன்று அந்நிலையில் உபிர்துறத்தலையே விரதமாகக்  
கொண்ட வீரர்

சாற்றுப்படி : சாத்துப்படி பார்க்க

சாற்றுவரி : (சாறு - பதனீர்) கள் இறக்கும் மரங்களிலிருந்து கள்ளோ  
பதனீரோ இறக்குவதற்கான வரி

சான்றார் : கள் இறக்குவோர்

சானி : மனைவி ; பிராமண ஸ்திரீகளின் பட்டப்பெயர்

சிகரம் : கோபுர விமானங்களின் உச்சி

சிங்கபாதம் : சிங்கத்தின் பாதம் போல அமைக்கப்பட்டிருக்கும் பாத்  
திரத்தின் பாதம்

சிங்காரத் தோப்பு : உத்தியான வனம்

சிடுக்கு : மகளிர் ஆபரண வகை

சித்தம், சித்தி : நில அனுபோகத்தில் அஷ்டபோகங்களுள் ஒன்று ;  
நிலத்தில் விவசாயம் செய்யும் உரிமை

சித்தாந்தம் : சைவ சமயம்

சித்தாயம் : நிர்ணயித்து அறுதியிட்ட வரி [விஜயநகர மன்னர்களின்  
ஆட்சிக்காலத்தில் இது பொன்னாக இறுத்துவந்த சிறு வரிகளைக்  
குறித்து வந்தது]

சித்திரமேழி : உழவுத்தொழில் பூண்ட வேளாண் மக்களுடைய பெருஞ்  
சபை; அவர்களுடைய சின்னமான கலப்பை; அந்தச் சின்னம்  
பொறிக்கப்பட்ட எலலைக்கல்

சித்திரைக்கார் : சித்திரை மாதத்தில் அறுவடையாகும் நெல்வகை

சிதாரி : கோயிலில் தூபம் இடுவதற்கு உபயோகமாகும் ஒருவகைப்  
பண்டம்

சிப்பம் : சிறு மூட்டை

சிமயம் : இமயமலை

சிரத்தாமந்தர் : அபிமானத்தால் கோயில் தருமங்களைச் சிரத்தையோடு  
பார்ப்பவர்

சிரப் பிரதானி : தலைமைப் பிரதானி

சிராவணம், சிராவணை : ஆவணம், நிலக்கிரயபத்திரம்; சிராவணபத்திரம்  
எனவும் பெறும்

சிரியக்கி பழஞ்சலாகையச்சு : சலாகை பார்க்க; சிரியக்கியச்சு எனவும்  
பெறும் (புரீயகூழி பழஞ்சலாகை அச்சு)

சிரிவயண்ணவர், சிரிவயிண்ணவர் : ஸ்ரீவைஷ்ணவர்

சிரீமுகம் : ஸ்ரீமுகம் ; திருமுகம்

சிரோவார்த்தனை : சிவலிங்கத்தின் உச்சிப்பகுதி

சில்துடிமை : ஊர்ச்சபை போன்ற ஸ்தல ஸ்தாபனங்களுக்கு இறுக்  
கும் சிறு வரிகள்

சிலந்தி : கோமேதக வகை

சில்லந்தராயம் : உள்வரிப் பிரிவைச் சேர்ந்த சிறு வரிகள்

சில்லாயம், சில்லிறை, சில்வரி : சில்லறை வரிகள்

சிலாலேகை : கல்வெட்டு ; கல்லில் பொறித்த எழுத்து

சிவந்தநீர் : முத்தின் சிவந்த நீரோட்டம்

சிவப்பிராமணர் : சிவன் கோயிலில் பூசை செய்யும் பிராமணர் ; ஆதி  
சைவர்

சிவப்புச்சிலை : கெம்பு ; சிவப்பு ரத்தினம்

சிவப்புத் தோய்ப்பார் : துணிகளுக்குச் சாயம் இடுவோர்

சிவபண்டாரி : சிவன் கோயில் பொக்கிஷத்து அதிகாரி

சிவயோகி : சிவனடியார்

சிவன் : சிவ பக்தருக்கு வழங்கிய பட்டப்பெயர்

சிவிகைப்புறம் : (கோயிலில்) பல்லக்குச் சேவைக்கான செலவுக்கு  
விடப்பட்ட நிலம்

சிற்றாயம் : சிறு வரிகள்

சிறகு : தெருவின் ஒரு பக்கத்தில் உள்ள வீடுகளின் ஒழுங்கு ; தெருப்  
பக்கம்

சிறப்பு : கோயிலில் நடக்கும் விசேஷ பூசை

சிறப்புக்கட்டளை : கோயிலில் ஏற்படுத்தப்பட்ட நைவேத்தியப் படித்  
தரம்

சிறு அபராதம் : சிறு குற்றங்களுக்கு விதிக்கும் தண்டனை

சிறுகாலைச்சந்தி : கோயிலில் உதய காலத்தில் செய்யும் பூசை

சிறுகாலைச்சிறப்பு : கோயிலில் விடியற்காலையில் நடக்கும் பூசை  
சமயம் செய்யும் நைவேத்தியம்

சிறுதுடிவாரம் : நிலத்தை உழுது பயிரிடுவதில் உழவனுக்குக் கிடைக்  
கும் பங்கு

சிறுகங்கம் : தலைச்சமைபோன்ற சிறு சமைகளுக்கு வருவிக்கும் சுங்  
கம் போலும்

சிறுதரம் : அரசாங்க அதிகாரிகளில் சிறிய தரத்தில் உள்ளவர்கள்

சிறுதனம் : அரசாங்க அதிகாரிகளுள் சிறுதரம் வகிப்போர் [சோழர் களுடைய ஆட்சிக்காலத்தில் அரசாங்க அதிகாரிகள் பெருந்தனம், சிறுதனம் என இரு பிரிவுகளாக இருந்தனர். ஒவ்வொரு பிரிவும் பெருந்தரம் சிறுதரம் என மறுபடியும் பிரிக்கப்பட்டிருந்தது. இம் முறை சிறுதனத்துப் பெருந்தரம் என்று ஓர் அதிகாரி குறிக்கப் படுவதிலிருந்து விளங்கும்]

சிறுதனம் : சொந்தப்பணம் ; தனக்கே உரிமையான நிதி ; சிறுவாடு

சிறுப்பிள்ளை : அரண்மனை ஊழியன் ; வேலையாள்

சிறுபடுகண் : ஆபரண உறுப்பில் தொங்கும் வகை

சிறுபாடிகாவல் : [பெரும்பாடிகாவலினின்றும் வேறானது] ஊர்க் காவல்

சிறுபாடு : சிறிய உபயம்

சிறுமுறி : செய்தி அறிவிக்கும் லிகிதம் ; சிறு மதிப்புள்ள சில்லறைப் பத்திரம்

சிறுமுறிக்காசு : சிறு பத்திரங்களுக்காக இறுக்கும் காசு

சிறுவேட்டை : கிராமப் புறங்களில் சிறு துஷ்டமிருக்கங்களை ஒழிக்க வேட்டை ஆடுவது

சின்னப்பிள்ளையாண்டான் : அடைப்பம் என்னும் அரசனுடைய அதிகாரியின் கீழ் ஊழியம் செய்பவன் ; அரண்மனை ஊழியன்

சின்னம் : திருச்சின்னம் ; காளம் போன்ற வாத்தியம்

சின்னம் : ஒரு நாணய அளவு ; மிகவும் குறைவானது போலும்

சின்னம் : சில்வானம் ; சொச்சம்

சினகரம் : சைனக்கோயில்

சீகாரியம் : ஸ்ரீகாரியம் ; கோயில் காரிய நிர்வாகம்

சீகாரியக் கண்காணி : கோயில் நிர்வாகத்தை மேற்பார்ப்போர்

சீகாரியப் பேறு : காரிய நிர்வாகம் செய்வாருக்குக் கொடுக்கப்பெறுவது

சீதனக்காணி : சீதனமாகப்பெற்ற நிலம்

சீபண்டாரம் : ஸ்ரீபண்டாரம் ; கோயில் பொக்கிஷம்

சீபலி : ஸ்ரீபலி ; கோயிலில் நாள்தோறும் சோற்றால் இடும் பலி [ஹவிர்பலி எனவும் படும் ; தீயேந்சோறு என்பதும் இதுவே] ; பலி பூசைக்காகக் கோயிலிலே சுற்றி எழுந்தருள்செய்யும் சிறு விக்கிரகம் ; பலி இடும்போது கோயிலைச் சுற்றி விக்கிரகத்தோடு வலம் வருதல் ; ஸ்ரீபலி நடத்த இறுக்கும் வரி



சீபலி கோட்டுவார் : கோயிலில் தினசரி பலி பூசையின்போது இசைக் கருவிகளை வாசிப்போர்

சீபலிபோகம் : கோயிலில் ஸ்ரீபலி நடத்தும் செலவுக்காக விடப்பட்ட நிலம்; சீபலிப்பட்டி எனவும் பெறும்

சீபாதந்தாங்கிகள் : கோயிலில் விக்கிரகங்களை வாகனத்தோடு கட்டித் தாங்கிச் செல்பவர்; சீபாதம் எனவும் பெறுவர்

சீமாவிவாதம், சீமைவிவாதம் : (நாட்டின்) எல்லையைப்பற்றிய வழக்கு

சீமுகம் : ஸ்ரீமுகம்; அரசனிடமிருந்து வந்த ஓலை

சீயர் : ஜீயர்; விஷ்ணுகோயில் நிர்வாகப் பொறுப்பு வகித்த வைஷ்ணவ சந்நியாசி

சீர்மை : சீமை; நாட்டின் பகுதி

சீருத்திரர் : ஸ்ரீருத்திரர்; சிவனடியார்; சிவன் கோயில் நிர்வாகக் குழுவின் பகுதி

சீவனசேஷம் : ஜீவனத்துக்கு உரியது

சீவிதம், சீவிதப்பற்று, சீவியம் : ஜீவிதம் பார்க்க

சங்ககால : சங்கம் வகுவிக்கும் இடம்

சங்கம் : 'கலத்தினும் காலினும் வரும் பண்டங்கட்கு இறை'

சுட்டிட்டிகை : (சுட்ட இட்டிகை) சுட்ட ஓடு; செங்கல்; சுட்டோடு என் பதும் இதுவேயாகும்

சுடர்நிலை : விளக்குத் தண்டு; விளக்கைத் தாங்கி நிற்கும் கட்டை

சுகோட்டுப்பாட்டம் : பிணங்களை எரிப்பதற்கான மயான வரி

சுடு : சும்மாடு

சுப்பிரம் : முத்துக்குற்றத்துள் ஒன்று

சுப்பிரயோகம் : ஒரு நதியின் பெயர்; வடபெண்ணை என்பர்

சுமை : தலையில் சுமந்து விற்போர் இறுக்கும் வரி

சுரம் : காடு [சுரம்போக்கி : காட்டுக்குத் தூரத்தி; சுரம் இறக்கி என வும் பெறும்]

சுரி : ஆபரணத்தின் உறுப்பு

சுருட்டிக்காரன் : அரசர் பவனியில் சுருட்டி என்னும் சாமரம் போன்ற எடுபிடி விருது எடுத்துச்செல்பவன்

சுருதிமான் : மக்களின் சமூகம் பற்றிய காரிய நிர்வாகம் செய்வோர்; கேள்வி என்பாரின் வேறு பெயர்

சுருளமுது : தாம்பூலம்

சுரோத்திரியம் : சுருதி அதாவது வேதம் வல்ல பிராமணர்களுக்கு வரியில்லாமல் அளித்த நிலம் அல்லது கிராமம்

சுவந்திரம் : சுதந்திரம் ; கிராமத் தொழிலாளர்க்குச் சேரவேண்டிய நெல், சோறு போன்ற உரிமை

சுவர்ணதாயம் : காசாக, பொன்னாக இறுக்கும் வரி வகைகள்

சுவாமி : அரசன் ; உரியவன்

சுவாமியம் : சொத்துரிமை

சுவாமிலாரம் : மேல் வாரம் ; சொந்தக்காரனுக்கு உரிய பங்கு

சுவாஸ்தியம் : பரம்பரையாக அனுபவிக்கும் உரிமை

சுற்று : சுற்று வட்டம் ; சுற்றளவு

சுற்றுக்கல்வாரி : கோயிலில் கர்ப்ப கிருகத்தைச் சுற்றிப் பிராகாரம் போல் அமைக்கப்பட்ட கட்டடம்

சுற்றுப் பேழை : சுருள் அடுக்காக அமைந்த பேழை

சுனை : மலைகளின் பிளவுகளில் தங்கும் நீர்நிலை

சூலக்கல் : சிவன் கோயிலின் நிலத்து எல்லையைக் குறிக்க நடும் சூல உருவம் பொறித்த கல்

சூலக்கால் : சூலக்குறி பொறிக்கப்பெற்ற சிவன் கோயில் அளவை மரக்கால்

சூலத்தாபனம் : சிவன்கோயில் நிலத்து எல்லையைக் குறிக்கச் சூல உருவம் தாங்கிய கல்லை நடுவது

சூலவரி : சிவன் கோயிலுக்காக இறுக்கப்பெறும் வரிபோலும்

சூலத்தீறை : பரத்தையர் செலுத்திய வரி [கன்னடக் கல்வெட்டுகளிலே இந்தப் பொருள்களில்தான் வழங்குகின்றது]

சேக்காயம் : எண்ணெய் ஆடும் செக்கு வரி ; சேக்கீறை, சேக்குக் கடமை எனவும் பெறும்

சேக்குமன்றாடி : முன்னாளில் வழங்கிவந்த ஒரு வரி வகை ; செக்கு சம்பந்தப்பட்டதாக இருத்தல் வேண்டும்

சேக்குவாணிகர் : செக்காடும் வாணிகர்

சேங்கோடிக்காணம் : செங்கோடி என்றும் கொடிவேலி என்றும் சித்திரமூலம் என்றும் வழங்கும் மருந்துச்செடிக்கான வரி எனக் கொள்வர் ; கோடிக்காணம் என்பதைக் காண்க

சேங்கோல் : செம்பொன் ; சுத்தமான தங்கம்

சேட்டியார் மகமை : வியாபாரிகள் இறுக்கும் மகமை

சேட்டியிறை : வியாபாரிகள் இறுக்கும் வரி ; சேட்டிறை எனவும் பெறும்

சேண்பகக்குளிகை : முன்னாளில் வழங்கிவந்த நாணய வகை ; சம்புவராயர் அச்சிட்டு வழங்கியது போலும்

சேந்நீர் : தெளிந்த நீர்

சேந்நீர் பொதிவி : நல்ல நீர் ஓடும் கால்

சேப்புக்கால் திருச்சிற்றம்பலமுடையான் : திருச்சிற்றம்பலமுடையான் என்ற பெயர் கொண்டதும், செம்பினால் ஆனதுமான அளக்கும் பாத்திரம்

சேப்புத் திருமேனி : செம்பினாலாகிய விக்கிரகம்

சேப்புப்பத்திரம், சேப்புப் பட்டயம் : செப்பேடு ; தாம்ர சாசனம்

சேம்பாதி : சரிபாதி

சேம்மருதர் : நல்ல விவசாயிகள்

சேம்மை : சமம் ; ஒப்பு ; சுத்தம்

சேம்மை பண்டாரக்கல் : சரியான எடை கொண்டதாகக் கஜானாவில் உள்ள நிறைக்கல்

சேய்தார் பொன் : சுத்தமான தங்கம்

சேய்யும்படி : உத்தரவு ; ஆணை

சேயல் : ஆபரணத்தில் மணியைத்துச் செய்யும் இழைப்படவேலை

சேருவாடி : சிறுவாடு ; சிறுகச் சிறுகச் சேர்த்த பணம்

சேல்ல : முடிய

சேவ்வரியாடு, சேவரியாடு : ஆடு வகை ; செம்மறியாடு என்பதே போலும்

சேவ்வாரம் : சம வாரம் ; பாதி வாரம்

சேவீடு : ஆழாக்கில் ஐந்தில் ஒரு பாகமாகிய அளவு

சேறுவு : செறு ; வயல்

சேன்னடை : கோயிலில் நித்தியப் படித்தரம்

சேன்னீர் வெட்டி : நீரோடும் கால்வாயை அவ்வப்போது வெட்டிச் சீர் செய்ய வேண்டிய கடமை ; சேன்னீர்மஞ்சி என்பதும் இதுவே போலும்

சேகண்டி : சேமக்கலம்

சேணியர் : நெய்வோருள் ஒரு வகையார் ; தொழிற் குழுவினர்

சேர்வை : ஊழியம்; ஊழியர்களுக்கு வரியில்லாமல் விடப்பட்ட நிலம்;  
ஊழியர் மானியம்

சேரி : ஊரில் ஜனங்கள் வாழும் இடம்; பார்ப்பனச்சேரிபோல் வரு  
வது காண்க

சேவகக்காசு : போர் வீரர்களின் செலவுக்கும் பராமரிப்புக்குமாக  
இறுக்கும் காசு; போர் வீரர்களிடமிருந்து வசூலிப்பதும் ஆகும்

சேவகத்தேவை : அரசனோ உயர்தர அதிகாரிகளோ கிராமங்களுக்கு  
விஜயம் செய்யும்போது அவர்களுக்குச் சேவகம் செய்வதற்காக  
ஆட்களை அனுப்புவதும், அந்தச் செலவுக்கான வரிப்பணத்தையும்  
குறிக்கும்

சேவகன் : போர் வீரன்

சேனகணம் : சமண மதத்தினருள் ஒரு குழுவினர்; சேனன்வயர்  
எனவும் பெறுவர்

சேனாபதியாழ்வார் : சேனை முதலியார்; விஷ்வக்சேனர்

சேனாபதிப் பெருவிலை : விஷ்ணு கோயில் நிலங்களை விஷ்வக்சேனர்  
பெயரால் கிரயம் செய்வது; அதற்கான விலைப்பொருள்

சேனாபோவன், சேனைபோகம் : கணக்குப்பிள்ளை

சேனையங்காடிகள் : வியாபாரிகளுள் படையோடு செல்லும் ஒருவகை  
யினர்; துணி வியாபாரிகளுள் ஒரு பிரிவினர்

சைவாசாரிய கேஷத்திரம் : சைவாசாரியர்களுக்கு வரியில்லாமல் அளிக்  
கப்பட்ட நிலம்

சைவகலாலய சக்கரவர்த்தி, சைவசக்கரவர்த்தி, சைவகுளாமணி,  
சைவாதிராயர் : சைவ ஆசாரியர்களுள் சிலருக்கு முன்னுளில் அர  
சர் வழங்கிய பட்டப்பெயர்கள்

சோக்கத்தளியிலார் : சிவன் கோயிலைச் சார்ந்த தேவரடியாரில் ஒரு  
வகையார்; சோக்கம் என்னும் ஆட்டத்தை ஆடுபவரே போலும்

சோக்கம் : சுத்த நிருத்தம் எனப்படும் நாட்டிய வகை

சோர்க்கஸ்திராதல் : இறந்து போதல்

சோருவம் : ஸ்வரூபம்; மலையாளத்து நம்பூதிரிகள் அரசர் முதலி  
யோரின் ஸ்தாவர சொத்து

சோனவரி : சுவர்ணவரி என்பதன் வேறு வடிவம்; சுவர்ணாதாயம்  
ஆகும்

சோசியார் திருவடி : அரசாங்க உத்தியோகஸ்தருள் ஒருவர்; அரசாங்க ஜோதிஷரே போலும்

சோடி : மிகக் குறைந்த விகிதத்தில் வரி இறுப்பதாக அளிக்கப்பெற்றுள்ள இனும் வகை; ஜோடி பார்க்க

சோபானம் : படிக்கட்டு; கோயில் கட்டடத்தின் அடிப்படை

சோம சித்தாந்தம் : சைவ சமயத்தின் உட்பிரிவுகளுள் ஒன்று

சோமாசி, சோமயாஜி : சோமயாகம் செய்தவன்

சோழியக்காசு : முன்னாளில் வழங்கி வந்த ஒரு காசு; ஒரு பணத்தின் நூற்றில் ஒரு பாகம் எனக் கருதப்படுவது

சோற்றடைப்பு : அன்னதானக் கட்டளை

சோறு மாட்டு : எச்சோறு பார்க்க; சோறுமாட்டம், சோறுமாடு எனவும் குறிக்கப்பெறும்

சோனகச்சிடுக்கு : முன்னாளில் பெண்கள் அணிந்துவந்த ஓர் ஆபரணம்

சௌஸ்தி : தருமக்கொடை (ஸ்வஸ்தி என்று ஆரம்பிக்கும் சாசனம் என்பதன் திரிபேபோலும்)

சூடு : நாடு என்பதன் வேறு வடிவம்

சூபகம் : நினைப்பூட்டுவதற்காக எழுதிவைத்த குறிப்பு

சூயிறு : மாதம்; சௌரமானக் கணக்கின்படி கொள்ளும் மாதம்

சூழி : நாழி என்பதன் வேறு வடிவம்

டங்க சாலை : தங்க சாலை; நாணய சாலை

தகட்டுக்குழை : கழுத்தணி வகை

தச்சத்துலாம் : ஏற்ற வகைக்கு வழங்கிவந்த வரிபோலும்

தச்சாசாரியம் : தச்சர்களிடையே தலைமைப் பதவி; ஸ்தபதி, சிற்பாசாரியர் போன்ற பதவி

தச்சாசாரியக்காணி : கோயிலில் தச்சாசாரியர் கவனிக்கவேண்டிய வேலைகளுக்கான உரிமை; அதற்கான மானியம்

தச்சக்கிரிபை : கோயிலில் பழுதுபார்ப்பது முதலிய வேலைகளைச் சிற்பாசாரியார்கள் கவனிப்பது

தசபந்தம் : வரியிலே பத்தில் ஒரு பங்கைக் குளம் வெட்டுவது போன்ற பொதுக் காரியங்களுக்காக ஒதுக்குவது; அந்தத் தொகைக்கு ஈடான வருவாயைக் கொடுக்கும் நிலத்தைத் தனியாக ஒதுக்குவது; குளம் முதலிய நீர்நிலைகளை வெட்டுவோர் அதன் ஆயக்கட்டில் பத்

கிலே ஒரு பங்கை அனுபவிப்பதமாகும்; தசவந்தம் எனவும் பெறும்

தட்டவே : (தட்டு அடைவு) அவ்வப்போது கிடைக்கும் வருவாய் போலும்

தட்டம் : உண்கலம், தாம்பாளம்

தட்டழி : சேமக்கலம் போன்ற ஒருவகை வாத்தியம்; தத்தளி என்பது இதுவே போலும்; தட்டாழி எனவும் பெறும்

தட்டாழி கொட்டி : கோயிலில் ஸ்ரீபதி நடக்கும்போது சேமக்கலம் போன்ற வாத்தியத்தில் இசையெழுப்புவோர்

தட்டார் பாட்டம் : (பொற் கொல்லர்கள்) தட்டார்கள் இறுக்கும் வரி;

தட்டாரப் பாட்டம் எனவும் ஆகும்

தட்டுக்காயம் : (தட்டுக்கு ஆயம்) தட்டொலி என்பதே போலும்;

தட்டுக்காணம் என்பதும் இதுவேபோலும்

தட்டுப் புழுது : புனுகு சட்டம்

தட்டோலி : (தட்டார்பாட்டம் என்பதோடு சேர்ந்தே காணப்படும்)

கம்மாளரிலே வேறு வகையினரான கொல்லர் போன்றவர் பட்டறை

வைத்து வேலை செய்வதற்கு இறுக்கும் வரி போலும்

தட்டோளி : உலோகத் தட்டால் ஆன முகம் பார்க்கும் கண்ணாடி

தடலிக் கட்டேல் : இரத்தினத்தைப் பொன்னில் பதிக்கும் வேலைப்பாடு

தடி : நெல்வயல்; விளைநிலப் பகுதி

தடி : கையெழுத்துப் போடத் தெரியாதவன் அதற்குப்பதிலாக இடும் அடையாளம்

தடிப்பதக்கு : தடி நிலத்துக்குப் பதக்கு வீதம் நெல்லாக இறுப்பது

தண்டக்காணம் : தண்டம் என்பதேபோலும்

தண்டக் குற்றம், தண்டங் குற்றம் : தண்டம், குற்றம் ஆகிய இரண்டும்;

குற்றம் என்பது இழைத்த குற்றத்துக்குச் செலுத்தும் அபராத

தொகை; தண்டம் இதா வகையான அபராதத் தொகை; தண்ட

கூற்றம் எனவும் காணப்பெறும்

தண்டநாயகம் : படைத் தலைமையாகிய உத்தியோகம்; அந்தப் பதவி

வகிப்பவன் தண்டநாயகன்

தண்டப் பதேல் : அபராதம் விதிக்கப் பெறுதல்

தண்டப் பொருள் : அபராதமாக வாங்கும் பொருள்

தண்டம் : அபராதமாக விதிக்கப்பட்ட வரி

தண்டல்மேனி : வரி வசூலிப்பவன்; தானியமாக வரி வசூலிக்கும் போது அதில் ஏற்படக்கூடிய குறைவுக்காகச் சேர்த்துக் கொடுப்பதும் ஆகும்

தடிமாறும் குதிரைச் சேவகன் : அரசன் போர்ப்படையைச் சேர்ந்த  
தற்குறி அல்லது முத்திரையிடும் குதிரை வீரன்  
தண்டலிலக்கை : வரி வசூலிக்க வருவோர் தங்கியிருத்தல்  
தண்டவாணி : பொன் மாற்று அறிய உதவும் ஆணி ; உரைகல்  
தண்டற் கடமை, தண்டலிற் கடமை : வரி தண்டுவோர்க்கு இறுக்கும்  
கடமை ; வரி தண்டுவோர் இறுக்கும் வரியாகவும் கொள்வர்  
தண்டாளர் முதல் : வரி வசூலிப்பவர் தங்கள் வசூலுக்கு வைத்திருக்  
கும் கணக்கு  
தண்டிகை, தண்டு : பல்லக்கு  
தண்டிகை ஜீவிதம் : பல்லக்குச் சுமப்பவர்களுக்காக வரியில்லாமல்  
விட்ட நிலம்  
தண்டு : போர்ப்படை ; படையெடுத்துச் செல்லல்  
தண்டு : கோயில் வாகனம் பல்லக்கு முதலியவற்றைக் கட்டித் தூக்கு  
வதற்கான கோல் ; வாரை  
தண்டுதல் : வசூலித்தல் ; தண்டல் எனவும் காணப்பெறும்  
தண்டேடுப்பார் : பல்லக்குச் சுமப்பவர்  
தண்டேறுதல் : பல்லக்கில் ஏறுதல்  
தண்டேசுரப் பெருவிலை : சண்டேசுரப் பெருவிலை பார்க்க  
தண்டேசுரன், தண்டேசுரன் : சண்டேசுரன்  
தண்ணீர்க்காணம் : தண்ணீர் வரி என்பதேயாகும்  
தண்ணீர்ப்பட்டி : தண்ணீர்ப் பந்தல் தர்மத்துக்கு விடப்பெற்ற நிலம்  
தந்ததி : சந்ததி ; பரம்பரை  
தந்திரபாலன் : சேனைத் தலைவன்  
தந்திரம் : படை (காலாட்கள் கொண்டது)  
தந்திரி : படைத்தலைவன் ; கோயில் அர்ச்சகர்  
தந்திரியார் : போர்ப்படையைச் சேர்ந்தவர் ; படைக்கானவர் என  
வும் பெறுவர் ; கோயில் அர்ச்சகர்களையும் குறிக்கும்  
தந்மி, தர்மி : கோயில் காரியங்களை நிர்வகிப்போர்  
தந்மி எழுதி, தந்மி ஊதி : ஊர்ச்சபையின் பெருங்கூட்டம் கூடுவதைக்  
காளம் ஊதி அறிவிப்பது  
தபசி : தவம்புரிவோர் ; துறவிகள் ; தவசி எனவும் குறிக்கப்பெறுவர்  
தம்பம் : விளக்குத் தண்டு

தம்பிராட்டி : தலைவி ; அரசன் தேவி

தம்மம் : திரமம் என்னும் நாணயம்

தய்யான், தையான் : தையற்காரன்

தயித்திரியக் கிடைப்புறம் : வேதத்தில் தைத்திரிய சாகை ஒதுவார்க்கு  
அளித்த மானிய நிலம்

தயிரமுது, தயிரமிர்து, தயிரமுர்து : கடவுளுக்குப் படைக்கும் தயிர்

தர்மதானம் : புண்ணியம் பயக்கும் கொடை

தர்மபத்தர் : (தர்மத்துக்குக் கட்டுப்பட்டவர்) தருமவிசாரணை செய்வோர்

தர்ம வாணியர், தன்ம வாணியர் : நியாயமான விலைக்கு வியாபாரம்  
செய்வோர்

தர்மாசனம் : தரும சபை : நியாய விசாரணை ஸ்தானம்

தரகு, தரகுபாட்டம் : தரகரிடமிருந்து கொள்ளும் வரி

தரமிலிநிலம் : தீர்வைத்தரம் நிர்ணயிக்கப் பெறுத நிலம்

தரவிடு நெல் : (கூலியாகக்) கொடுக்கும் நெல்

தரவு : உத்தரவு ; கட்டளை ; நிர்ப்பந்தித்து வசூலித்தல்

தரவு கொள்ளுதல் : ரசீது பெறுதல் ; வரி முதலியவற்றின் நிர்ப்பந்த  
வசூல்

தரவுசாத்து : சோழர் ஆட்சியில் தரவுஇடும் அரசாங்க அதிகாரி

தரா : எட்டுப் பாகம் செம்பும் ஐந்து பாகம் காரீயமும் கலந்து செய்  
யப்படும் உலோகம் ; பித்தலை

தரிசனகாணிக்கை : பெரியோரைக் காண்கையில் அளிக்கும் காணிக்கை

தரிஸாபள்ளி : கிறிஸ்தவர் கோயில் ; மாதாக் கோயில்

தரிப்பறுதி : (கிராமத்தில்) தங்காமல் துறந்து செல்லல்

தருப்பு : குறைந்த மதிப்பு உள்ள ஒரு வகை வெள்ளைக்கல்

தருமாசனத்தார் : நீதி வழங்குவோர்

தலக்காவல் : ஸ்தலம் காவல் புரிவது ; ஊர்க்காவல்

தலத்தார் : கோயில் அதிகாரிகள் ; கோயில் அர்ச்சகர்கள்

தலவகாரம் : சாம வேத சாகைகளுள் ஒன்று ; தலவகார சாமம் எனவும்  
பெறும்

தலைக்கரை : வயலையோ ஏரிகுளங்களின் கரையையோ அடுத்துள்ள  
நிலம்

தலைக்கோலி : ஆடி முதிர்ந்த கணிகை

தலைச்சம்மாடு : தலைப்பாரம் ; தலைச்சம்மாடு ; பொறுப்பு

தலைநீர் : முதல் மடைப் பாய்ச்சல்



தலைப்பிறை : சுக்கில பக்ஷத்துப் பிரதமை

தலைப்பேழை : ஏரி அல்லது வாய்க்காலின் தலைப்பு மதகு

தலைமாறு : பரிவர்த்தனை

தலையாரிக்கம் : கிராமத் தலையாரிக் காவலுக்குச் செலுத்தும் வரி ;

தலையாரிக்காணம் என்பதும் இதுவே போலும்

தலையீடு : தலைப்பில் உள்ளது ; ஆரம்பத்தில் இருப்பது

தலைவாய் : பிரதான வாசல் ; முகப்பில் உள்ள மதகு

தலைவாய்ச்சேரி : முகப்பில் உள்ள ஊர்ப்பகுதி

தவளைவாய் : ஆபாண வகை

தவனசெட்டி : செட்டி வகையினர்

தவனம், தவனகம் : மருக்கொழுந்து

தவிர்த்து : நீக்கி ; இல்லாமற்செய்து

தவுக்கை : தட்டு வகை

தழையிடுவார் : கோயிலில் வில்வம் திருத்துழாய் முதலிய பச்சிலைத் திருப்பணி செய்வார்

தள அதிகாரி : தளவாய் ; படை அதிகாரி

தளபாடம் : சேனை ; சேனைக்கு வேண்டிய உபகாணங்கள்

தளவாய் : படைத்தலைவன்

தளவிசை : தளவரிசை ; கல் பரப்பு

தளவிருத்தி : கோயில்களின் பராமரிப்புக்காக விடப்பெற்ற நிலம்

தளி : கோயில்

தளிகை : உண் கலம் ; ஓர் அளவு கொண்ட ரைவேத்தியப் பிரசாதம்

தளிகைச் சிறப்பு : கோயிலில்செய்யும் விசேஷ ரைவேத்தியம்

தளிச்சேரி : கோயிலைச்சேர்ந்த தேவரடியார் வசிக்கும் தெரு

தளிச்சேரிப் பெண்டுகள் : தளிச்சேரியில் வசிக்கும் தேவதாசிகள்

தளித்தல் : நீர் தெளித்தல்

தளிப்பரிவாரம் : கோயில் சிப்பந்திகள் ; கோயில் பரிவாரம்

தளியிலார் : தேவரடியார் ; கோயில் ஊழியம் செய்யும் பெண்டிர்

தளைக்காணம் : மரம் ஏறுவோர் உபயோகிக்கும் தளைக்கான வரி

தற்குறிமாட்டெறிதல் : கையெழுத்துப் போடத் தெரியாதவன் தன் அடையாளம் இடுதல் ; அதற்குச் சாட்சி போடுதல்

தறிக்கடமை, தறியிறை : துணி நெய்வோர் தறிக்காக இறுக்கும் வரி

தறிதளை : தறிக்கடமை பார்க்க ; தளைக்காணமாகவும் இருக்கலாம்

தறிப் புடவை : தறி நெய்வோன் புடவையாக இறுக்கும் வரி ; தறிக்  
கூறை என்பதும் இதுவேயாகும்

தன்ம சாதனம் : தருமத்துக்கு அளித்த நிலத்தின் பத்திரம்

தன்மதாவளர் : தன்மவாரியப் பெருமக்கள் பார்க்க ; தன்ம வாணிகர்  
எனவும் கொள்வர்

தன்மப் பலிசை : நியாய வட்டி

தன்ம வாணிகர் : நெறிதவறாமல் நியாயமாக வாணிகம் செய்பவர்

தன்மவாரியப் பெருமக்கள் : அறநிலயங்களை மேற்பார்க்கும் சபையோர்

தன்மி எழுதுதல், தன்மி ஊதுதல், தர்மி எழுதுதல் : கிராமச் சபைக்  
கூடத்தைக் கூட்டுவதற்குக் காளம் ஊதி அறிவித்தல் (தம்-ஒலி  
யெழுப்பு என்னும் வடமொழிச் சொல்லடியாகப் பிறந்தது)

தன்னேற்றம் : தன்னைச் சேர்ந்த இனத்தார்

தனிச் செய்கை : பிறருடன் சேராமல் தான் ஒருவனாகவே செய்யும்  
விவசாயம்

தனிசு : கடன்

தனிநகர், தனிநகரம் : நிர்வாக விஷயத்தில் தனி உறுப்பாக விளங்கும்  
பெரிய வியாபார ஸ்தலம்

தனியாளர் : மேற்பார்வை இடுபவராகக் கொள்ளலாம் ; அதனால்  
தனியாட்பேறு என்பது அத்தகையாருக்கு உரிய வருவாய் ஆகும்

தனியூர் : நிர்வாகத்திலே தனி உறுப்பாக விளங்கும் பெரிய ஊர்

தக்ஷிண்புஜம் : வலது கை ; நம்பிக்கை வாய்ந்த அதிகாரி

தாக்கி : சாட்சியின் வேறுவடிவம்

தாங்கல் : பாசனத்துக்கு உபயோகமாகும் குளம்போன்ற நீர்நிலை

தாசரி : மக்களின் சமய ஒழுக்கத்தைக் கண்காணிப்போர் ; வைஷ்ணவ  
சமயத்தைச் சார்ந்தவர்

தாடிப்படை : மதிலின் மேல்பகுதியில் உள்ள பாகம்

தாமம் : பூமாலை ; தொங்கல் எனவும் பெறும்

தாரம் : பித்தளை ; தூர என்பதன் வேறு வடிவம்

தாராதத்தம் : நீரைத் தாரை வார்த்துத் தானம் கொடுத்தது

தாரைத்தாள் வட்டில் : ஒருவகைப் பாத்திரம்

தாலம் : பண்டாரம் , கஜானா

தாலச்சேம்மைபொன் : கஜானாவினால் நிர்ணயிக்கப்பெற்ற மாற்றுடைய  
சுத்தமான தங்கம்

தாலிமணிவடம் : தாலியோடு மணிகள் சேர்ந்த மங்கிலியக்கொடி  
தாழக் கூட்டுக் கம்பி : ஆபரண வகை  
தாளிம்பம் : நெற்றியில் அணியும் ஓர் ஆபரணம்  
தான இறையிலி : வரி நீக்கித் தானம் செய்யப்பெற்ற நிலம் அல்லது  
கிராமம்

தானத்தார் : கோயில் அதிகாரிகள் ; கோயிலில் பூசை செய்வோர்  
தானம் : தேவஸ்தானத்தின் சுருக்கமான ஸ்தானம் ; கோயில்  
தானமானம் : ஸ்தானத்தினால் ஏற்படும் பெருமை  
தானமானியம் : மானியமாக விட்ட நிலத்தின்மீது வசூலிக்கப்பெறும்  
வரி

தானிகர் : ஸ்தானீகர் ; கோயிற்காரியங்களைக் கண்காணிப்பவர் ; பூசை  
செய்வோர்

தானிகராயர் : கோயில் ஸ்தானீகர் ; பூசை செய்வாருள் தலைவர்  
தானியவர்க்கம் : தானியமாக இறுக்கப்பெறும் வரிவகைகள்  
தானைத் திருப்பட்டிகை : விக்கிரகத்தின் அரையாடை (முன்தானை)யின்  
மேல் அணியும் ஆபரணம்  
தானைத் தூக்கம் : திருப்பட்டிகை அணியின் உறுப்பினுள் ஒன்று

திங்கட் காசு : மாதம் தோறும் தண்டிவந்த ஒரு பழைய வரி ; திங்கட்  
சோறு, திங்கள் மோகம், திங்கள் நெய் என்று காணப்படுவனவும்  
இவ்விதமே யாகும் ; மாதப்படி என்பதையும் பார்க்க

திட்டர் : திட்டு

திணைக்களம் : இலாநா ; நிர்வாகத் துறை

திநாரம் : முன்னாளில் வழங்கிவந்த ஒரு வகைப் பொன் நாணயம் ;  
யவனர்கள் நாட்டிலிருந்து முதலில் வந்தது

திரங்கல் : முத்துக் குற்றவகை

திரமம் : முன்னாளில் வழங்கி வந்த ஒரு நாணயம் ; கிரேக்க நாட்டி  
லிருந்து முதலில் வந்தது

திரள் மணிவடம் : ஒருவகை மாலை

திராசம் : மாணிக்கக் குற்றங்களுள் ஒன்று

திரிகாலம் : காலை, உச்சி, மாலை என்ற மூன்று வேளை

திரிகை : குயவன் மண்பாண்டம் செய்யும் சக்கரம்

திரிகை ஆயம் : குயவர் திரிகையின் மீது இறுக்கும் வரி

திரிசூலக்கல் : சிவன் கோயில் நிலத்து எல்லையைக் குறிக்கத் திரிசூலம்  
பொறித்து இடும் எல்லைக் கல்

திரிசூலக் காசு : கோயிலுக்கு இறுக்கும் வரி ; சூலவரி என்பதும்  
இதுவே

திரு : சோதிடம் கூறுவான்

திரு : மாங்கலியம்

திருக்கண்டவாணி : கழுத்து அணி வகை

திருக்கண்ணமடை : அரிசி, சர்க்கரை, வாழைப் பழங்களால் ஆக்கப்  
பட்ட இனிய உணவு ; சர்க்கரைப் பொங்கல் வகை

திருக்கண்ணுக்கு : சுவாமியின் விக்கிரகத்தை மண்டபப் படிக்கு  
எடுத்துச் செல்லுதல்

திருக் கலச முடித்தல் : சும்பாபிஷேகம்

திருக்காவணக்கால் : உரிமைப் பத்திரம் ; ஆதரவுச் சீட்டு ; தோரண  
ஸ்தம்பம் எனவும் ஆகும்

திருக் குகை : துறவிகள் வாழும் இடம் ; மடம்

திருக் கேட்டைக் கிழத்தி : மூதேவி ; ஜ்யேஷ்டாதேவி

திருக்கைக் கோட்டி, திருக்கையோட்டி : கோயிலில் திருமுறை ஒதும்  
மண்டபம் ; அங்கே திருமுறை ஒதுவார் திருக்கைக் கோட்டி யோது  
வார் எனப் பெறுவர்

திருக்கை வழக்கம் : கோயில் நித்தியப் படித்தரம் ; பிரசாத விநியோக  
மும் ஆகும்

திருக்கோசகம் : கோயிலில் அம்மன் விக்கிரகத்துக்குச் சாத்தும் கொய்  
சகும் போன்ற அணிவகை

திருக்கோடுக்கு : ஆபரணவகை

திருக்கோள்கை : ஆபரணம் ; விக்கிரகத்துக்கு இடம் கவசமும் ஆகும்

திருக் கோற்ற வாய்தல் : அரண்மனை

திருச்சந்தம் : அணிவகை

திருச்சரி : அணி வகை

திருச்சுற்றலயம் : கோயில் பிரகாரத்தில் உள்ள நடைமண்டபம்  
அல்லது பரிவார தேவதைகளின் ஆலயத் தொகுதி

திருச்சுற்றலை, திருச்சுற்று மண்டபம், திருச்சுற்று மாளிகை, திருச்சுற்று  
மாலு : கர்ப்ப கிருகத்தைச் சுற்றிப் பிராகாரமாக அமைந்துள்ள  
கட்டடம்

திருச்செந்நடை : கோயிலில் அமுதுபடித்தரம்

திருச் செந்நெல் நடை : கோயிலில் சிவப்பு அரிசி (சம்பா)ச் சாதம்  
நிவேதிக்கும் நடப்புச் செலவு

திருஞானப்புறம் : தேவரம் முதலியவை ஒதுவதற்கு விட்ட நிலம்

திருஞானம் : கோயிலின் சந்நிதியில் ஓதும் தேவாரம் போன்ற பாடல்  
 திருஞானம் பெற்ற பிள்ளையார் : திருஞானசம்பந்த நாயனார்  
 திருத்து : காடு திருத்திச் சாகுபடிக்குக் கொண்டந்த நிலம்  
 திருத்துதல் : மேற்பார்த்தல்  
 திருத்தோப்பு : கோயிலுக்கு உரிய நந்தவனம் ; திருந்தவனம் எனவும்  
 பெறும்  
 திருநட்டக் கணப் பெருமக்கள் : கோயில் அதிகாரிகளுள் ஒரு சாரார் ;  
 கோயில் ஊழியம் புரியும் இசைவல்லார் குழுவின சபையார்  
 திருநடைமாளிகை : கோயில் பிரகாரத்தைச் சுற்றியுள்ள மண்டபம்.  
 திருநமனிகை : கோயிலில் மூர்த்திக்குச் செய்யும் அபிஷேகம்  
 திருநயனம் : கோயில் மூர்த்திக்கு அணிவிக்கும் கண்மலர்  
 திருநல்லியாண்டு : சுபகரமான ஆட்சி வருஷம் ; திருநலியாண்டு என  
 வும் பெறும்  
 திருநகூத்திரம் : பிறந்த நகூத்திரம் ; ஆண்டு  
 திருநாமக்காணி, திருநாமத்துக்காணி : சிவன் கோயிலுக்கான தேவ  
 ஸ்தான நிலம் ; கோயிலின் பெயரில் உள்ள நிலம்  
 திருநாள் தேவை : திருவிழாச் செலவு; திருநாள் காணிக்கை என்பதும்  
 இதுவே போலும்  
 திருநாற்கட்டிற்சாலை : மஞ்சம் ; கட்டில்  
 திருநிறஞ்சேய்தல் : கோயில் மூர்த்திக்குப் பொன்முலாம் இதேல்  
 திருநெற்றித்திரணை : கோயில் விக்கிரகத்தின் நெற்றியில் இடும்  
 ஆபரணம்  
 திருப்பட்டம் : திருமுடி ; கோயில் மூர்த்தியின் நெற்றியில் இடும்  
 ஆபரணம்  
 திருபட்டிகை : விக்கிரகத்துக்கு அணியும் அரைப்பட்டிகை வகை  
 திருப்படிக்கரகம் : திருமஞ்சன நீர் வைக்கும் பாத்திரம்  
 திருப்பரிசட்டம் : விக்கிரகத்துக்குச் சாத்தும் ஆடை ; பரிவட்டம்  
 திருப்படிமாற்று : கோயில் மூர்த்திகளுக்கு நிவேதிப்பதற்கான  
 பொருளைத் தயாரிக்க வேண்டிய அரிசி முதலிய பண்டங்கள்  
 திருப்படிமாறுதல் : நிவேதனத்தைத் தயாரித்தல்  
 திருப்படைவீடு : கடவுள் கோயில் கொண்டுள்ள இடம்  
 திருப்பணி : கோயிற் கைங்கரியம்  
 திருப்பதியம் : திருப்பதிகம்  
 திருப்பள்ளிக் கட்டில் : சிங்காதனம்  
 திருப்பள்ளித் தாமம், திருப்பள்ளித் தொங்கல் : கோயில் மூர்த்திகளுக்  
 குச் சாத்தப்படும் மாலை

திருப்பாவாடை : ஆடைமேல் கோயில் மூர்த்திக்குப் படைக்கும்  
 நிவேதனம்; அவ்விதம் படைக்கும் ஆடையையும் குறிக்கும்;  
 அரசன் முதலியோருக்கு மரியாதையாக அளிக்கும் எடுபிடி.

திருப்பிறை : சிவபெருமான் விக்கிரகத்துக்குத் தலையில் சூட்டும் பிறை  
 போன்ற ஆபரணம்

திருப்புகை : கோயிலில் இடும் தூபம்

திருப்புதியது, திருப்புதியது : குடிமக்கள் முதல் விளைவைக் கோயிலுக்  
 குக் கடமையாகச் செலுத்துவது

திருப்புறக்குடை : சுவாமிக்குப் பின்புறமாகப் பிடிக்கும் குடை

திருப்புறக்கோடை : பின்பக்கத்து முற்றம்

திருப்பூமண்டபம் : கோயிலில் மாலை தொடுக்கும் இடம்

திருப்போனகம் : சுவாமிக்கு நிவேதனம் செய்யும் அமுது

திருமஞ்சன சாலை : கோயிலில் விக்கிரகத்தை வைத்து அபிஷேகம்  
 செய்யும் மண்டபம்

திருடடவளாகம்; திருமடை விளாகம் : கோயிலைச் சுற்றியுள்ள இடம்  
 திருமதில் : கோயிலின் சுற்று மதில்

திருமந்திரக்கோடி : கோயில் உற்சவகாலத்தில் உபயோகிக்கப் பெறும்  
 கொடிச் சீலை

திருமந்திரம் : கோயில்

திருமந்திரபோனகம் : நிவேதனம்

திருமந்திர போனப் புறம் : கோயில் நைவேத்தியத்துக்காக விடப்பெற்ற  
 நிலம் அல்லது கிராமம்; மடைப்பள்ளிப்புறம் என்பதும் இதுவே

திருமந்திரவோலை : அரசன் உத்தரவுகளை உரிய துறைகளுக்கு  
 ஒலைமூலம் அனுப்பும் அதிகாரி; கடிதப் போக்குவரத்தைக் கவனிக்  
 கும் அதிகாரி

திருமந்திரவோலை நாயகம் : அரசாங்கத்தின் ஒலை யெழுதும் துறையின்  
 தலைமை அதிகாரி

திருமலை : சிவன் கோயில் கர்ப்பகிருகம்; விமானம்

திருமாளிகைச் சுற்று : திருச்சுற்றுமலை பார்க்க; திருநடைமாளிகை

திருமாளிகைப் பத்தி : கோயில் திருமதிலை ஒட்டி உட்புறமாக அமைந்  
 துள்ள கட்டடங்கள்; மண்டபம்; சுற்றுக் கோயில்கள்

திருமாளிகைப்பிள்ளை : கோயில் காரியங்களை நிர்வகிப்பவன்

திருமாளிகைப் பிள்ளையார் : சண்டேசுவரர்

திருமுகக்காணம் : அரசன் முதலியோரிடமிருந்து வரும் திருமுகக்  
களைச் சமந்து வருவோர்க்குக் கொடுக்கும் வரி

திருமுகத் தேவை : திருமுகக் காணம் பார்க்க

திருமுகம் : ஸ்ரீமுகம்; அரசன் முதலியோரிடமிருந்து வரும் செய்தி ;  
அரசாணை

திருமெய்காப்பான், திருமெய்காப்பு : கோவில் மெய்காவல் ; கோயில்  
காப்பான்

திருமெய்ப்பூச்சு : கோயில் மூர்த்திகளின் மேல் பூசும் வாசனைப்பூச்சு

திருமெழுக்கு : கோயிலை மெழுகுதல்

திருமேற்கட்டி : கோயில் மூர்த்தி எழுந்தருளியிருக்கும் இடத்தில்  
கட்டியிருக்கும் மேல்விதானம்

திருமேற்கோயில் : ஊருக்கு மேற்கே அமைந்துள்ள விஷ்ணு ஆலயம்

திருமேற்பூச்சு : திருமெய்ப்பூச்சு பார்க்க

திருமேனி : விக்கிரகம்

திருமேனிகாவல் : கோயில் காவல்

திருவக்கிரம் : நிவேதனம்

திருவட்டமணி, திருவட்டமணிவடம் : கழுத்தணி ; மாலை வகை

திருவடி : முனிவர் ; திருவாங்கூர் அரசன்

திருவடிக்காறை : காலணி வகை

திருவடிதேசம் : திருவாங்கூர்ச் சீமை ; திருவடி ராஜ்யம் என்பதும்  
இதுவே

திருவடிநிலை : விக்கிரகபீடம்

திருவடிபிடித்தல் : கோயில் பூசை செய்தல்

திருவடிபிடிப்பான் : கோயில் அர்ச்சகர்

திருவடிமார் : மலை நாட்டிலே அரசர், பிராமண அதிகாரிகள், மடத்தலை  
வர், கோயில் அர்ச்சகர் முதலியோருக்கு வழங்கிய சிறப்புப் பெயர்

திருவணுக்க வாசல் : கர்ப்பகிருகத்தின் வாசல்

திருவமுது : நிவேதன உணவு

திருவரங்கிருந்த பெண்கள் : கோயிலில் நடனம் ஆடும் தேவரடியார்

திருவரங்கு : கோயிலில் உள்ள பிரதான மண்டபம் ; ரங்க மண்டபம்

திருவாண்டேழுத்திதேல் : அரசன் முடிசூடிய காலம் தொட்டு வருஷக்  
கணக்கிட்டுச் சாசனங்களில் எழுதுதல்

திருவாணை : அரசன் ஆணை

திருவாய்க்கேள்வி : அரசன் வாய்மொழியாக இடும் உத்தரவுகளைக்  
கேட்டு உரியவர்களுக்கு எழுத்துமூலம் அனுப்பும் அதிகாரி; அரசன்  
ஆணையையும் குறிக்கும்

திருவாய்ப்பாடி : கிருஷ்ணன் கோயில் ; கோகுலம் எனவும் காணப் பெறும்

திருவாராதனை : திருவாராதனம் ; கடவுள் பூசை

திருவாழிக்கல் : விஷ்ணுகோயில் நிலங்களின் எல்லையைக் குறிக்க நடும் சக்கர முத்திரை கொண்ட கல்

திருவானிலை : கருவூர்ச் சிவலாயம்

திருவிடையாட்டம் : விஷ்ணுகோயில்களுக்கு அளிக்கப்பெற்ற தேவ தான நிலம் அல்லது கிராமம் ; விஷ்ணுகோயில் ஸ்ரீகாரியம்

திருவிடு : தானசாசனம்

திருவிடைப்பற்று : திருவிடையாட்டம் பார்க்க

திருவிருப்பு : கோயில் அமைந்துள்ள இடம் ; கோயில் கட்டடம்

திருவிரையாக்கலி : சிவபெருமான் பெயரால் இடம் ஆணை

திருவிழாப்புறம் : கோயில் உற்சவங்களுக்காக விடப்பெற்ற நிலம்

திருவிளக்குடையார் : கோயிலில் விளக்கு ஏற்றுவோர்

திருவிளக்குக்குடி : கோயிலில் விளக்கு எரிக்கும் கடமை ஏற்று அதற் கான மானிய நிலத்தை அனுபவிக்கும் குடிமக்கள்

திருவீதி நாயகர் : உற்சவ மூர்த்தி

திருவீதிப்பந்தம் : சுவாமி புறப்பட்டு வீதிவலம் வரும்போது பிடிக்கும் தீவட்டி

திருவுடம்பு : திருமேனி ; விக்கிரகம்

திருவுண்ணாழி, திருவுண்ணாழிகை, திருவண்ணாழிகை : கர்ப்பகிருகம் ; உண்ணாழிகை பார்க்க

திருவுலகளத்தல் : நிலத்தை அளந்து கணக்கிடுதல்

திருவுழுத்து : அணி வகை

திருவெழுத்துச்சாத்துதல் : கையெழுத்து இடுதல்

திரைக்காசு : முன்னாளில் வழங்கிவந்த வரிவகை

தியதி : தேதி ; நாள்

திறம் : என்பது ஆடு, என்பது பசு, என்பது எருமை கொண்ட மந்தை

தீட்டு : கையெழுத்திட்ட சீட்டு ; எழுதிக்கொடுத்த ஒலை

தீட்டுக்குறி : எழுதிக்கொடுத்த ஒலைச்சீட்டு

தீண்டல் : வயல்

தீண்டாச்சேரி : தொடக்கடாத சாதி மக்கள் வாழும் இடம்

தீப்போக்குச்சேம்போன் : புடமிடப்பெற்ற சுத்தமான தங்கம்

தீபமாலை : சரவிளக்கு



தீயேறிசோறு : ஹவிர்பலி ; கோயிலில் அக்கினி வளர்த்து, அன்  
னத்தை ஓமம் செய்து இடும்பலி ; அதற்காக வசூலிக்கும் வரி  
தீர்க்கமானியம் : கோயில் மூர்த்தியை நீராட்டுவதற்காக அளித்த  
மானியம் ; நீண்டகாலம் நிலைநிற்க வேண்டிய மானியம் என்றும்  
கொள்வது  
தீவுகரிவு : பயிர் முதலியன தீய்ந்து போய்க் கேடுறுதல்

துக்கை : தூர்க்கை  
துஞ்சிய : உயிர் துறந்த  
துடவு : ஒரு முகத்தல் அளவு  
துடவை : விளைநிலம் ; வயல்  
துண்டகவிஷயம் : தண்டகாரணியம் ; தொண்டை மண்டலம்  
தர்வாயகம் : வசவு ; இழிசொல்  
துரவு : பாசனத்துக்கு உதவும் பெரிய கிணறு  
துரு : வேதம் முதலியவற்றைத் திருப்பிக்கூறும் சந்தை வகை  
துரையின்னற்போன் : ஒரு நாணய வகை  
துல்லியம் : சரியானது என்று ஒப்புக்கொள்ளப்பட்டது ; சரியான  
பிரதி  
துலாக்கூலி : நிறுத்து எடைபோடுவதற்கான வரி ; துலாபார வரியும்  
ஆகும்  
துலாபாரம் : அரசர்போன்றவர் தராசில் ஒரு தட்டில் ஏறி நின்று மறு  
தட்டில் அவர் எடைக்குச் சமமான பொன்னையும் மணியையும் இட்டு  
நிறுத்து, அந்தப் பொன்னையும் மணியையும் தர்மத்துக்கு வழங்கல்  
துலாபாரவரி : அரசர் துலாபாரம் ஏறுவதற்காக இறுக்கும் வரி  
துளைநிறை, துளைநிறை செட்போன், துளைநிறை போன் : சுத்தமான  
பொன்  
துக்கம் : நிறை ; நிறுத்தல்  
துக்கம் : தொங்கலைக்கொண்டு முன்னாளில் வழங்கிவந்த ஓர் ஆபரணம்  
துக்குத்தலரிசி : நன்றாகக் குத்திச் சுத்தம் செய்த அரிசி  
துசிப்படை : கொடிப்படை ; போர்ப்படையில் முன்னதாகச்செல்வது ;  
துசிப்படை எனவும் பெறும்  
துசகத்தறி : பாசறைக்கு வேண்டிய கூடாரத் துணி முதலியவற்றை  
நெய்யும் தறி ; அதற்கான வரி  
துபி : ஸ்தூபி ; கோயில் விமானத்தின் உச்சி  
தும்பு : மதகு ; வாய்க்கால் ; நீரோடும் கணவாய்  
தும்பு : ஒரு முகத்தல் அளவு

தேண்டகுற்றம், தேண்டந்தீர்வை : அபராதமாக விதிக்கும் வரி

தேற்றி : மேட்டிடம்

தேற்றியம்பலம் : கிராமசபை கூடும் மேட்டிடம்

தேன்னம்பழம் : தேங்காய் நெற்று

தேசகாலம் : வேளை ; பொழுது

தேசவாளி : கிராமம் முதலியவற்றை, தேசத்தை ஆளும் அதிகாரி

தேவகர்மி, தேவகன்மி, தேவர்கன்மி : கோயிலில் சுவாமி காரியம் பார்ப்போர்

தேவகுடிறை : கோயிலின் ஆதிக்கியத்தில் வாழும் குடி

தேவகுலம் : கோயில்

தேவதானம் : கோயிலுக்கு விடப்பட்ட இறையினி நிலம்

தேவடிமை : தேவரடியார், வேலைக்காரி

தேவரடியார் : மாகேசுவர சைவர்

தேவரடியார் : கோயிலில் பணிபுரியும் பெண்டிர்

தேவாரதேவர் : ஆன்மார்த்த பூசைக்கு உரிய மூர்த்தி

தேவாரம் : கோயில்

தேவை : காரியம் ;

தேன்பயில் பொதும்பு : தேன் கூடுகட்டியிருக்கும் மரப் பொந்து

தேஜமானியம் : அஷ்டபோகம் உள்ளிட்ட நிலத்தின் பூர்ண உரிமை ;

தேஜஸ்வாமியம் எனவும் பெறும்

தைஞ்சை : தஞ்சை ; தஞ்சாவூர்

தைப்புமுத்து : முத்து வகை

தைவியம் : தெய்வச்செயல்

தோக்கைக்குன்றி : சாகுபடி நஷ்டம்

தோடையல் : தோளில் அணியும் பூமாலை

தோண்டர்சீர் பரவுவார் : திருத்தொண்டத் தொகையின் ஆசிரியரான சுந்தரமூர்த்தி சுவாமிகள் ; பெரிய புராண ஆசிரியரான சேக்கிழார்

தோண்டு : அடிமைத்தனம்

தொழிற்பட்டிகை : மகளிர் அரையில் அணியும் பட்டிகை என்னும் ஆபரண வகை, கடைசல் தொழில் கொண்டது

தொறு : அடிமையாள்

தொறு : பசுக்கூட்டம்

தொறுநிலை : பசுக்கள் கட்டும் கொட்டம்

- தோட்டக்கூறு : தோட்டத்துக்குத் தகுதியான நிலம்  
 தோட்டப்புரவு : தோட்டக்கால் நிலத்தின்மீது இறுக்கும் வரி  
 தோட்டவாரியப் பெருமக்கள் : தோட்டங்களைக் கண்காணிக்கும் சபை யினர்  
 தோணிக்கடமை : தோணிக்கு வாங்கும் வரி  
 தோரணக்கால் : திருவாசிக்கால்  
 தோரை : நான்கு விரல் உள்ள நீட்டல் அளவு  
 தோரணகாணிக்கை : வீதிகளில் தோரணமிட்டு அலங்கரிப்பதற்கான செலவு  
 தோலோட்டு : முன்னாள் வரிகை ; உலர்ந்த தோல் பற்றியது போலும்  
 தோளாச்செவியர் : தோளில் இடிக்கும்படியாக வடிந்த காதையுடைய ஒருவகை மக்கள் ; லம்பகர்ணர் என்பார் இவரே போலும்  
 நக்கன் : சிவன் கோயிலில் நாட்டியம் ஆடும் தேவாடியார் (நக்னமாக நடனம் செய்ய வேண்டியவன்)  
 நகரக்கல் : வியாபாரிகளின் சபையார் வைத்திருக்கும் எடைக்குச் சரியான எடைக்கல்  
 நகரங்களிலார் : வியாபாரிகளின் சபையைச் சேர்ந்தவர்கள்  
 நகரசுவாமி : வியாபாரிகள் தலைவன்; அவர்களுடைய சபைக்குத் தலைமைப் பதவி வகிப்பவன்  
 நகரத்தார் : வியாபாரிகள் ; அவர்களுடைய சபையைச் சேர்ந்த நிர்வாகிகள்  
 நகரம் : வியாபாரிகளின் சபை  
 நகரவனுச்சை : நகரத்தாருடைய உத்தரவு  
 நங்கனை : ஒட்டியாணம் போன்ற ஆபரணத்தின் ஓர் உறுப்பு  
 நட்டவக்காணி : நட்டுவக்காணி பார்க்க  
 நட்டவம் : நட்டுவம் என்பதன் வேறு வடிவம்; மாணவர்களுக்கு நாட்டியம் கற்றுக் கொடுத்து அவர்கள் நடனமாடுவதை மேற்பார்த்தல்  
 நட்டுப் பாழ் : நாற்று நட்டபிறகு பயிர் பாழான நிலம்  
 நட்டுவக்காணி : கோயிலில் நட்டுவம் பார்ப்போருக்கு அளிக்கப் பெற்ற இறையிலி நிலம்  
 நட்டுவத் துரவு : நட்டுவத் தொழில்  
 நடவல் : பிடுங்கி நடப்பெற்ற நாற்று  
 நடை : கோயில் ; கோயிலில் நடக்கும் தினசரி பூசை  
 நடைமாளிகை : கோயிற் பிராகாரம் ; திருச்சுற்றலை  
 நடைமாளிகை மண்டபம் : கோயிலிலே கர்ப்ப கிருகத்தைச் சுற்றி அமைக்கப்பட்டுள்ள கிட்டடம்

நத்தம் : கிராமத்தில் குடியிருப்புக்கான இடம்

நத்தப் பாழ் : மக்கள் குடியிருப்பு இல்லாத கிராமம்; குடியிருப்புப் பாழ் அடைந்த கிராமம்

நந்தாவிளக்கு : இடையறாமல் எப்போதும் எரியும் விளக்கு; நந்தா விளக்கு, நொந்தா விளக்கு எனவும் பெறும்

நந்துதல் : பழுதடைதல்; அழிந்து போதல்; குறைவடைதல்

நம்பி : கோயில் பூசை செய்பவர்

நம்பிராட்டியார் : அரசன் தேவி

நம்பு : கோயிலில் பூசை செய்யும் தொழில்; ஆகவே நம்புசெய்வார் : கோயில் பூசை செய்பவர்

நமன மண்டபம், நபன மண்டபம் : (ஸ்நபன மண்டபம்) கோயிலில் அபிஷேக மண்டபம்; திருமஞ்சன சாலை

நயினார் : நாயனார்; பெரியோர்; மரியாதை தெரிவிக்கும் ஒரு சொல்

நரபதி : [மானிடர் தலைவன்] சோழ மன்னர்களும், விஜயநகர அரசர்களும் தரித்திருந்த விருது; அவர்களுடைய காலாட்படையின் பெருக்கத்தைக் குறிப்பதாக ஏற்பட்டது போலும் (அகவபதி, கஜபதி என்பன போன்ற விருதுகளை ஒப்பு நோக்குக)

நரவாகன சக்கரவர்த்தி : விஜயநகர மன்னர்களின் விருதுகளுள் ஒன்று; நரபதி என்பதை ஒட்டி எழுந்தது போலும் (நரவாகனன் என்பான் உதயண குமாரனான ஒரு காவிய புருஷனும் ஆவான்)

நல்கிடா, நற்கிடா : கிராமத்திலே காட்சியாக வைக்கப்பட்டுள்ள கிடாவின் பராமரிப்புச் செலவுக்கான வரி

நல்பசு, நற்பசு : கிராமத்தில் காட்சியாக வைக்கப்பெற்றுள்ள பசுவின் பராமரிப்புக்கான வரி; நல்லாவு, நல்லா எனவும் பெறும்

நல்லேருது : கிராமத்தில் காட்சிக்காக வைத்திருந்த எருது; பொலி எருதாகவும் பயன்பட்டது போலும்; அதன் பராமரிப்புக்கான செலவு : அழகேருதுக் காசு, காட்சி எருதுக் காசு என்பனவும் இதுவே

நல்லேருமை : கிராமத்திலே காட்சியாக வைத்திருந்த எருமையின் பராமரிப்புச் செலவுக்கான வரி

நவகருமம் : ஜீர்ணோத்தாரணம்; புதுப்பித்தல்

நவரை, நவிரை : ஒருவகை நெல், ஆடிமாதத்தில் அறுவடையாவது போலும்; ஆடிநவிரை என்று காணப்படுவது

நாகு : பசு முதலியவற்றின் கிடாரிக்கன்று

நாட்டாமை, நாட்டாண்மை : தலைமைப் பதவி; நாட்டின் நிர்வாகத் தலைமை

நாட்டுக் கணக்கு வரி : நாடு என்னும் பகுதியின் தீர்வைக் கணக்குகளை எழுதுவதற்கான செலவுக்கு இறுக்கும் வரி ; நாடு என்னும் பகுதிக் கெனக் கொள்ளாமல் இராஜ்யம் முழுவதுக்குமே கொள்வதும் உண்டு

நாட்டுக் காணிக்கை : நாடு என்னும் சபையாருக்குச் செலுத்த வேண்டிய காணிக்கை ; அந்தச் சபையார் அரசாங்கத்தாருக்குச் செலுத்தும் காணிக்கையும் ஆகும்

நாட்டிருவமுது : (நாள் திருவமுது) கோயிலில் காலையில் நடக்கும் பூஜை நைவேத்தியம்

நாட்டு நீங்கல் : அரசாங்கத்தின் வரிப் புத்தகத்திலிருந்து நீக்கி நாடு என்னும் பிரிவுக்கான சபையாரின் வரிப் புத்தகத்துக்கு மாற்றப் பட்டது ; அதனால் அந்த வரியை நாட்டுச் சபையார் உபயோகித்துக் கொள்ளலாம்

நாட்டுப் பண்டாரம் : ஜில்லா கஜானா

நாட்டுபாதி : (நாடு உபாதி) நாடு என்னும் பகுதிக்கு அமைந்த சபைக் குச் செலுத்தவேண்டிய கடமைகள்

நாட்டு வினியோகம் : நாடு என்னும் பிரிவின் சபையார் செலவுக்காக அந்தப் பகுதியில் வாழ்வோர் விகிதாசாரப்படி இறுக்கவேண்டிய தொகை

நாடன் மஞ்சள் : மஞ்சளில் ஒருவகை ; சமையலுக்கு உபயோகப் படும் கறிமஞ்சள்

நாடாட்சி : நாட்டின் நிர்வாகம்

நாடு : இறந்தவர் பொருட்டு கல் நடுவது

நாடு : நாட்டின் ஒருபாகம், கோட்டம் கூற்றம் போன்றது ; அதன் நிர்வாகத்தைக் கவனிப்பதற்காக அமைந்த சபையையும் குறிக்கும்

நாடு கண்காட்சி : நாடு என்னும் பிரிவின் நிர்வாகத்தைக் கண் காணித்தல்

நாடு காவல் : கிராமக் காவலினின்றும் வேறானதாக நாடு என்னும் பிரிவின் காவலை மேற்கொள்வது ; அதற்கான வரியையும் குறிக்கும்

நாடுகூறு : நாட்டின் விளைநிலங்களைத் தரம் பிரித்து நிர்ணயிக்கும் அதிகாரி

நாடு தலையாறிக்கம் : நாடு காவல் என்பதே ; நாடு என்னும் பிரிவின் காவலைச் செய்வதற்கான வரி

நாடுவகை : நாட்டை அளந்து வரி விதிப்பதற்காக அதில் உள்ள பூயிரிடும் நிலங்களின் தரத்தை நிர்ணயித்தல்

நாடு வாரியம்: நாடு என்னும் பிரிவின் நிர்வாகத்தைக் கவனிக்க  
அமைக்கப்பெற்ற சபைக் குழு; நாட்டுவாரியம் எனவும் பெறும்

நாமடந்தை, நாமகள் : சாஸ்வதி தேவி

நாயகத்தனம்: நாட்டின் தலைமை நிர்வாகப் பதவி; அமரநாயகம்  
என்னும் பதவி; அமரம் என்பதும் இதுவே

நாராச நாழி: முன்னாளில் கோயிலில் வழங்கிவந்த அளவு நாழி;  
இரும்பால் செய்யப்பட்டது போலும்; நாராய நாழி எனவும்  
பெறும்

நாவிசம்: நாவிதத் தொழில்; ஆகவே நாவிசன்: நாவிதன்

நாளதினாலே: அந்த நாளிலே

நாற்காலி: நான்கு கால்களைக் கொண்ட ஆசனம்

நானுதேசி: விபாபாரிகளின் பெரிய சங்கம்; அய்யாவழியைத் தலைமை  
யிடமாகக் கொண்டு தென்னாடு முழுவதும் மல்லாமல் கடல்  
கடந்த பிரதேசங்களிலும் வாணிகம் செய்துவந்த கூட்டத்தார்

நிசதம், நிசதி: நாள்தோறும்

நிசீதிகை: சமண மதத்தார் பட்டினி நோன்பு பூண்டு உயிர் துறத்தல்;  
அத்தகையோருக்கு எழுப்பிய ஞாபகச் சின்னத்தையும் குறிக்கும்  
நித்தநிமந்தம், நித்தவிவந்தம்: கோயிலில் நாள்தோறும் பூசை நடத்து  
வதற்கான திட்டம்

நித்தியல்: நாள்தோறும்

நிதி: அஷ்டபோகத்தில் ஒன்று; நிலத்தின் செல்வத்தை அறுபவிக்  
கும் உரிமை

நிமந்தக்காரர்: கோயில் ஊழியர்கள்; உபயகாரரும் ஆவர்

நிமந்தப்புறம்: கோயிலில் குறிப்பிட்ட கட்டளையை நடத்துவதற்காக  
விட்ட நிலம் அல்லது கிராமம்

நிமந்தம், நிபந்தம், நிவந்தம்: கோயில் நிர்வாகத்திற்கான திட்டம்

நியதி: நிசதி என்பதன் வேறு வடிவம்; நாள்தோறும்; சிற்சில சமயங்  
களில் எப்போதும் எனவும் பொருள்படும்

நியாயங்களிலார்: நியாய சபை உறுப்பினர்

நியாயத்தார்: நியாய சபையார்

நியாயத்தார்: நியாயம் வழங்கும் சபையார்

நியாயம்: ஒரே வகையான தொழிலை மேற்கொண்டவர்களுடைய  
சபை

நியோகம்: அரசன் உத்தரவு; அதனைத் தாங்கிச்செல்லும் அதிகாரி

நிர்த்தமாராயன் : நடனத்தில் வல்லவனுக்கு முன்னாளில் அரசன் அளித்த பட்டம்

நிர்வாக சபை : காரியத்தை நடத்தும் குழுவினர்

நிருத்திய போகம் : கோயிலில் நடனமாடுவோருக்கு விட்ட மானிய நிலம்

நிருபச்சம்மாதம் : ஓலைச்சம்பட்டம் பார்க்க

நிருபம் : ஓலை; அரசன் அல்லது அவன் அதிகாரியிடமிருந்து எழுத்து மூலம் வந்த உத்தரவு

நிலக்கூலி : சந்தையில் விற்பனைக்கு வரும் சரக்குகளுக்கு ஒவ்வொரு பொதிக்கும் வசூலிக்கும் அரிசி

நிலச்சீவிதம் : ஊழியர்களுக்குச் சம்பளத்துக்குப் பதிலாக ஜீவிதமாக அது போகத்துக்கு நிலம் அளித்தல்

நிலம் அளவுபடிப் பேருமக்கள் : நிலம் அளவு செய்யும் (ஸர்வே செய் யும்) அதிகாரிகள்

நிலமகள், நிலமடந்தை, நிலமங்கை நாச்சியார் : பூமிதேவி

நிலமடக்குதல் : பயிரிடும் நிலத்தைத் தரவாரியாகப் பிரித்தல்

நிலமுதல் : பயிரிடும் நிலத்தைப் பற்றிய விவரம் அடங்கிய கணக்கு

நிலை : தூண்; விளக்கின் தண்டு; தீபக்கால்

நிலைக்களம் : வரி வசூல் செய்யும் கச்சேரி

நிலைப்படை : நிரந்தரமான, ஸ்திரமான சைனியம்

நிலைப்பந்தம் : தெருக்கோடி போன்ற குறிப்பிட்ட இடங்களில் இரவு நேரத்தில் வெளிச்சம் கொடுப்பதற்கென நிரந்தரமாக அமைக்கப் பட்ட பந்தம்

நிலைப்பொலியூட்டு : நிரந்தரமாகக் கிடைக்கும் வட்டி; நிலத்தின் மீது கடன் கொடுத்தோ ஆற்றுக்கால் தோண்டுவது போன்ற வேறு வேலை களில் செலவிட்டோ ஆண்டுதோறும் நிலையான வருவாய் கிடைக்கு மாறு முதலை உபயோகித்தல்

நிலைமைத்தீட்டு : அரசர்கள் செய்துகொள்ளும் ராஜ்ய உடன்படிக்கை

நிலையாணி : ஆபரணத்தின் ஆணி; ஓடாணியினின்றும் வேறானது

நிலையாள் : நிரந்தரமான வேலைக்காரன்

நிலையிறை : ஒரே விதமான மாறுத வரி

நிவந்தம் : கோயில் ஊழியர்களில் அவர் அவர்க்கு உரிய பணி; கோயில் தினசரி செலவுத் திட்டமும் ஆகும்

நிறைச்சளவு : குறைவில்லாமல் சரியாக நிறைந்த அளவு

நிறையெடுத்தல் : நிறுத்தல்

நின்றயம் : நிர்ணயம் என்பதன் வேறு வடிவம்

நின்ற நாழி : நிர்ணய நாழி ; முத்திரை நாழி

நினைப்பு : ஞாபகக் குறிப்பு

நிகேஷம் : அஷ்டபோகத்துள் ஒன்று ; புதையலை எடுத்து அனுபவிக்கும் உரிமை

நீங்கல் : பொதுவாக இறை நீக்குவதைக் குறிக்கும் ; எனினும் இது அரசாங்க வரிப்புத்தகத்திலிருந்து நீக்கப்பெறினும், நாடு போன்ற இதர ஸ்தாபனங்களின் வரிப் புத்தகத்துக்கு மாற்றப்பட்டதாகும் ; அவ்விதம் மாற்றல் பெற்ற ஸ்தாபனங்களின் செலவுக்குப் போவது நீர்க்காணம் : பாசன நீருக்கான வரி ; நீர்விலை என்பதும் அதுவே போலும்

நீர்க்கோவை : நீர்க்கோப்பு ; வரிநீர்க்கோப்பு பார்க்க

நீர்தேளித்தல் : கோயில் கட்டிக் கும்பாபிஷேகம் செய்தல்

நீர் நிலம் : கொல்லை நிலத்தினின்றும் வேறானது ; நன்செய்ப் பயிர் செய்யும் நிலம்

நீர்நி(ை)லக்காசு : ஏரி குளம் போன்றவற்றின் பராமரிப்புக்கான வரி

நீராணிக்கம் : கிராமத்தில் பாசனத்துக்கு நீரை முறையாக விடும் பொறுப்பு ; அதை மேற்பார்வையிடும் அதிகாரி

நீராணிக்கவரி : நீராணிக்கத்துக்காக இறுக்கும் வரி ; நீராணி வரி எனவும் பெறும்

நீர்வியார் : நானாதேசி என்னும் வியாபாரிகளில் ஒரு குழுவினர் ; ராஜராஜப்பெருநீர்வியார் என்பது போன்ற பெயருடன் விளங்கியவர் ; கடல்கடந்து வியாபாரம் செய்தவர் போலும்

நீர்விலை : தண்ணீர் வரி

நூலாயம் : துணி நெய்வதற்கான நூல் மீது இறுக்கும் வரி

நூலேற்றம் : கோயிலில் நடக்கும் துவஜாரோஹணம்

நெட்டாள் : வெட்டி என்பதனோடு தொடர்பு கொண்டது ; கிராமப் பொது வேலைக்கு அது முடியும் வரையில் வறையறையில்லாமல் ஆள் அனுப்பி முடிக்கவேண்டிய கடமை ; அந்த ஆளுக்கான செலவும் ஆகும்

நெய் : நெய் வியாபாரிகள் இறுக்கும் வரி ; நெய்விலை என்பதும் இதுவே ; எண்ணெய் என்பதையும் பார்க்க

நெய்தாங்கி : தீபஸ்தம்பம்



நெய்யாடுதல் : கோயிலில் உள்ள விக்கிரகத்துக்கு நெய்க்காப்பு இடுதல்

நெல்முதல் : வரிக்காக இறுக்கப்பெறும் நெல் ; அதன் விவரம்  
அடங்கிய கணக்கு ; இன்னும் வட்டி பெறுவதற்கு நெல்லாக விடப்  
பெற்ற முதலையும் குறிக்கும்

நெல்லாயம் : நெல்லாகவே இறுக்கும் வரிவகை ; நெற்கடமை என  
வும் பெறும்

நெல்லிக்காய் முத்து : ஒருவகை மாலை

நெல்லூர் மாடை : முன்னாளில் நெல்லூரினிருந்து வழங்கப்பெற்ற  
ஒரு நாணயம் ; நெல்லூர்ப் புதுமாடை என்றும் காணப்பெறும் ;  
கண்ட கோபாலன் மாடை என்பதும் இதுவேயாகும்

நெற்கூறுசாலை : நெல் குத்தும் இடம்

நெற்போலிசை : நெல்லாக இறுக்கும் வட்டி

நோந்தா விளக்கு : நந்தா விளக்கு பார்க்க

நோக்கிமாடை : முன்னாளில் வழங்கிவந்த நாணயம்

நோக்குதல் : கண்காணித்தல் ; மேற்பார்வை

நாபகவாடி : அரசாங்கத்தாராலோ ; நிலத்தின் சொந்தக்காரராலோ  
அறுவடைக்குச் சிறிது முன்னதாகப் பயிரைக் காக்க அனுப்பப்  
பெறும் காவல்காரன் ; அவனுக்குச் சம்பளமாக விடப்பெறும் நிலம்  
காக்குநாயக விளாகம் எனப்பெறும்

நடுவிருக்கை : அரசாங்கத்துக்கும் குடி மக்களுக்கும் நடுவில் இருந்து  
உதவிசெய்யும் அதிகாரிகள் ; பொதுநலத்தோட்பு அதிகாரிகள் ;  
மத்தியஸ்தரும் ஆகும்

பக்க வாத்தியர் : வாய்ப்பாட்டுக்குத் துணையாக நிற்கும் இசைக்கருவி  
யாளர்

பக்கிணம் : பசுணம் ; பணியாரம்

பக்கிழம் : பசுநம் ; பட்சம்

பக்தாதாயம் : நெல்லாக இறுக்கும் தீர்வை ; நெல் வருவாய்

பகலிருக்கை : நாளோலக்க மண்டபம் ; அரசன் சபா மண்டபம்

பகுற்றுதல் : சமமாகப் பங்கிடுதல் ; சரியாகப் பிரித்தல்

பங்களப்படை : பதர்போன்ற கூட்டுப்படை, புதிதாக நிறுவியது

பச்சை : இனா ; காணிக்கை ; நன்கொடை ; சாமான்களாகக் கொடுக்  
கப்பெறுவது

பச்சைப் பணம் : சாமான்களாகக் கொடுக்கும் பச்சையைப் பணமாக  
அளிப்பது ; பச்சைப் பாட்டம் என்பதும் இதுவே

பசலை மரம் : பயன் தரும் மரம்

பசான், பசானம் : சித்திரை மாதம் அறுவடையாகும் நெல்; இவ்வகை நெல்லின் அறுவடைக் காலம்

பசித்து வாழ்தல் : ஏழையாக வாழ்க்கை நடத்தல்

பசங்கூட்டு : சுண்ணாம்புச் சாந்து

பஞ்சக்கம் : ஐவர் கூடிச்செய்த முடிவு

பஞ்சகம்மாள் : தட்டார், கன்றார், சிற்பி, தச்சர், கொல்லர் என்ற ஐவகைக் கம்மாள்

பஞ்சகவ்லியம் : ஆனஞ்சு பார்க்க

பஞ்சபத்திரம் : சுவாமிக்குப் படைக்கும் நைவேத்திய வகை; பஞ்ச பசுபியம் என்பதே போலும்

பஞ்சமாசத்தம், பஞ்சமஹாசப்தம் : சிற்றரசர் போன்றவர்களுக்கு உரிமையுள்ள ஐவகைப் பறை [செண்டை, திமிலை, சேகண்டி, கைத் தாளம், காளம் என்னும் ஐவகையாகக் கொள்வர். தத்தளி, மத்தளி, காடிகை, தாளம், காஹளம் என்னும் ஐவகை என்பர் மற்றொரு சாரார்]

பஞ்ச திரவியம் : கோயிலில் அபிஷேகத்துக்கான ஐந்து பொருள்கள்

பஞ்சரம் : விமானத்தின் சுவரில் காணும் மாடம்; கூடு எனவும் பெறும்

பஞ்சரத் திருவிளக்கு : கோயிலில் ஏற்றும் விளக்கு வகை; பஞ்சரம் அல்லது கூடுபோல் அமைந்துள்ள சரவிளக்கு

பஞ்சவமுது : பஞ்சாமிர்தம்

பஞ்சவர் : பாண்டியர்

பஞ்சவாரம் : பஞ்சவாரவாரியம் எனவும் ஆகும்

பஞ்சவாரம் : அரசாங்கத்துக்குச் சேரவேண்டியதான, விளைவிலே ஐந்தில் ஒரு பங்கு எனவும் கொள்வர்

பஞ்சவாரவாரியம் : கிராம காரியத்தைக் கவனிக்கச் சபையால் நியமிக்கப்பெறும் ஐந்து குழு

பஞ்சவார வூரீடு வரி : கிராமச் சபையின் நிர்வாகக் குழுவான பஞ்சவாரவாரியத்தாரால் விதிக்கப்பெற்ற கிராம வரி

பஞ்சாசாரியர் : சிவன் கோயிலில் பூசை செய்வோர்

பஞ்சாமிர்தம் : வாழைப்பழம், திராசை, சர்க்கரை, தேன், நெய் ஆகிய ஐந்தும் சேர்ந்த அபிஷேகப் பண்டம்

பஞ்சால அச்சு : முன்னாளில் வழங்கிய நாணயம்; பஞ்சாலத்தார் அடித்து வழங்கியது போலும் பஞ்ச சலாகை அச்சு என்று காணப்பெறுவதும் இதுவே

பஞ்சாளர், பஞ்சலத்தார், பஞ்சாளத்தார் : பஞ்ச கம்மாள்

பஞ்சப் பீலி : பஞ்சின்மீது இறுக்கும் வரி; பஞ்சபிலி எனவும் பெறும்  
பட்டசாலியன் : நெய்வோருள் ஒரு பிரிவினர்; பட்டு நெய்வோர்  
போலும்

பட்டடை வரி : நெல் பட்டடைக்காக, நெல் அடிக்கும் களத்துக்காக  
இறுக்கும் வரி

பட்டணஸ்வாமி : நானாதேசி எனப்படும் வியாபாரக் குழுவின் நகரத்  
தலைவன்; அவனுக்கு வழங்கிய பட்டப் பெயர்

பட்டப்பாழ் : சாகுபடியில்லாத நிலம்

பட்டம் : நெற்றியில் அணியும் பொன் தகடு

பட்டமார் : கோயில் பூசை செய்வோர்

பட்டயகாணிக்கை : தாமிர சாசனம் பெறுவதற்கு இறுக்கும்  
காணிக்கை

பட்டயம் : தாமிர சாசனம்

பட்டவிருத்தி : கல்வி வல்ல பிராமணர்க்கு இறையினியாக விடப்பெற்ற  
நிலம்; பட்டவிருத்தி மானியம் எனவும் பெறும்

பட்டாடை ஆயம் : பட்டுத்துணியின்மீது இறுக்கும் வரி

பட்டாடை நூலாயம் : பட்டு நூலின்மீது இறுக்கும் வரி

பட்டாரகர் : கடவுள்; ஞான குரு

பட்டாரிகை : தூர்க்கை

பட்டாவளப்பட்டு : பட்டுவகை

பட்டாவளி : பட்டம்பெற்ற குருமாரின் தலைமுறை வரிசை

பட்டிக்காடி : ஒரு பட்டி நிலத்துக்கு ஒரு காடி வீதம் இறுக்க  
வேண்டியது போலும்; பட்டிக்கால், பட்டிப்போன் என்பனவும்  
இவ்விதமே ஆகும்போலும்

பட்டிகை : மேகலை

பட்டிகைக்காணம் : ஒரு பட்டிகைக்கு ஒரு காணம் வீதம் இறுப்ப  
தரகலாம்; பட்டயக் காணிக்கை என்பதாகவும் கொள்ளலாம்

பட்டித்தண்டம் : கிராமத்தார் இறுக்கவேண்டிய தண்டப்பணம்  
போலும்

பட்டிறைப்படுத்தல் : வரிபோன்றவை செலுத்தப்படாமல் பாக்கி விழுதல்

பட்டோலைக் காசு : திருமுகக் காசு பார்க்க

படகம் : ஒரு நில அளவு

படங்கழி : முன்னாளில் வழங்கிய வரிவகை; எதைக் குறிப்பதென்பது  
தெரியவில்லை

படப்பு : வீட்டின் புழைக்கடை ; வீட்டின் பக்கத்துள்ள இடம் (மனை யும் மனைப் படப்பும்)

படர் : சொந்தச் சேவகன் ; போர் வீரன்

படலிகை : ஓர் அளவு

படாகை : உட்கிடை கிராமம்

படிக்கம் : அபிஷேக நீர் முதலியவற்றை ஏந்தும் பாத்திரம்

படித்தரம், படித்தனம் : கோயிலின் தினசரி செலவுக் கட்டளை

படிவிஞ்சனம் : கோயில் நித்தியப் படித்தரத்தில் வியஞ்சனப்பொருள்

படுகலம் : கடன் பட்டதற்கு எழுதிக் கொடுக்கும் பத்திரம்

படைக்கலம் : போர் புரியும் ஆயுதங்கள்

படைநாயகம் : சேனைத் தலைமை

படை நிலை : படைகள் தங்கியிருக்கும் இடம்

படைப்பணம் : சேனையின் பராமரிப்புக்காக இறுக்கும் வரி ; தண்ட மாக இறுப்பதுபோலும் ; போர்ப்படையினர் இறுப்பதாகவும் கொள்ளலாம் ;

படைப்பற்று : படையின் அனுபோகத்தில் உள்ள நிலம் ; பாளையம் ; நாட்டின் காவலுக்கான படைகள் தங்கியிருக்கும் இடமும் ஆகும்

படையழிவு : பயிர்களுக்குப் படைவீரர்களால் நேரிடும் சேதம்

பண் : வயல் ; பயிரிடும் நிலம்

பண்குறுணி : ஒரு வயலுக்குக் குறுணி வீதம் இறுக்கும் வரி

பண்ட வெட்டி : வெட்டி வகை ; கோயில் நிலத்துக்கானதுபோலும்

பண்டாடு பழநடை : நீண்ட காலமாக நடந்து வரும் வழக்கம்

பண்டாரக் கண்காணி : கஜானா அதிகாரி ; பொக்கிஷத்து அதிகாரி

பண்டாரக்கல் : அரசாங்கப் பொக்கிஷத்தில் உபயோகிக்கும் நிறை

பண்டாரவாடை : அரசனுக்குச் சொந்தமான கிராமம் அல்லது நிலம்

பண்டாரவாரியம் : கோயில் விசாரணைச் சபையார்

பண்டாரி : கஜானா அதிகாரி

பண்ணிக்கக் கூலி : செய்து முடித்த காரியத்துக்கான கூலி

பணம் : வீரபாஞ்சாலத்தார் என்னும் தொழிற் சபையின் உறுப்புக் களான தனிக் குழாம்

பணவர்க்கம் : காசாகச் செலுத்தவேண்டிய வரிகள்

பணவாசி : பணத்தின் தேய்வு கழிவுக்காக இறுப்பதுபோலும்

பணிக்கோத்து : கிராம ஊழியர்கள் ; அவர்களுக்காக வருஷிக்கும் வரி

பணிமகன் : வேலையாள்

பத்திரகடம் : பூர்ண கும்பம்

பத்தேட்டுக் குத்தரிசி : நன்கு குத்திக் தீட்டிய அரிசி

பதிபாதமூலம், பதிபாதமூலத்தார், பதிபாதமூலப்பட்டுடையார், பதிபாதமூலப்பஞ்சாசாரியர் : சிவன் கோயிலை நிர்வகிப்பதற்காகப் பூசை செய்வோரைக் கொண்ட சபை ; மூலபரிஷத் என்பதும் இதுவே போலும்

பதியார் : கோயிலைச் சேர்ந்த ஊழியர் ; பதியிலாரே போலும்

பதியிலார் : கோயிலைச்சேர்ந்த கணிகையர்

பதினறுமார் : பதினாறு பேர் கொண்ட கோயில் விசாரணைச் சபை

பதுவாரம் : நிலப் பரிவர்த்தனைக்காக அளிக்கப்பெறும் வரி ; மாறுதலுக்கான வரி ; பதுவாரம் எனவும் பெறும்

பபரப்பெறுதல் : அரசாங்கத்தாரால் திரும்ப எடுத்துக்கொள்ளப் பெறுதல்

பயிற்றுதல் : நிலத்தைச் சாகுபடிக்கு ஏற்பத் திருத்திப் பண்படுத்தல்

பயிரேற்றி : பயிர் செய்து ; விளைவித்து

பரக்கூலி : சமை கூலி

பரதேசி : வெளியார் ; வெளிநாட்டார் ; நாணுதேசி என்னும் வியாபாரக் குழுவில் ஒரு பிரிவினர் ; வெளிநாட்டு வியாபாரம் செய்வோர்

பரப்பு : வரிக்கணக்கு ; பரப்பு எனவும் படும்

பரம்பர் : உழவர் குடிவகை

பரம்பு : வரிக் கணக்கு ; பரப்பு எனவும் படும்

பரமக்கன்கல் : உடன் கடடை ஏறியவளுக்காக நட்ட கல்

பராவிவைத்தல் : நேர்த்திக் கடனாக அளித்தல்

பரிக்கிரகத்துப் பெண்டுகள் : கோயில் பணிப் பெண்கள்

பரிகரம் : உபகரணம் ; தேவையானவை ; பரிவாரம்

பரிகாரம், பரிஹாரம் : விலக்கு

பரிகாரன் : வேலைக்காரன்

பரிசிட்டம் : பரிவட்டம் பார்க்க

பரிசு : வகை, விவரம் ; பரிது எனவும் பெறும்

பரிமாறுகிற : வழக்கில் இருக்கிற ; நடமாட்டத்தில் உள்ள (பணம்)

பரிவட்டம் : ஆடை ; விக்கிரகத்துக்குச் சாத்தும் கூறை ; கோயிலில் தரிசிப்போர் தலையில் மரியாதையாகக் கட்டும் கடவுள் ஆடை ; பரியட்டம் எனவும் பெறும்

பரிவாரக் கொத்து, பரிவாரக் கொந்தம் : கோயில் புணியுள்ளர்கள்

பரும்புடவை : ஆடை வகை

பருமுனைவராகன் : முன்னாளில் வழங்கிய நாணய வகை

பலகாயம் : மிளகு, கடுகு போன்று கறிக்கு உதவும் பண்டங்கள்

பலதளி : பல மூர்த்திகளுக்கும் சந்நிதிகள் கொண்ட கோயில்

பலவரவை : பல வழியில் சில்லறையாகச் சேர்ந்தது

பலி : கோயில் பூசையின்போது தீ வளர்த்துச் சோற்றை ஓமம் செய்வது

பலிசை : வட்டி ; பொலிசை எனவும் காணப்பெறும்

பலித்தாலம் : ஸ்ரீபதி நடத்துவதற்கு உபயோகிக்கும் தட்டு

பவிழிய சரணத்தார் : ரிக் வேதத்தைச் சேர்ந்தவர் ; பேளழிய சரணத்தார் எனவும் பெறுவர்

பவிஷ்யக்கிடைப்புறம் : ஒருவர் கிராமத்திலேயே வசித்துப் பாடம் சொல்லுவதற்காக வரியில்லாமல் அளிக்கப்பட்ட நிலம்

பழம்புள்ளி மாடை : முன்னாளில் வழங்கிவந்த நாணய வகை

பழமுதல் கண்காணி : கோயில் மேற்பார்வையாளன்

பள்ளி : சமணர் கோயில் ; பௌத்தர் கோயில்

பள்ளிச் சந்தம் : சமணர் பௌத்தர் கோயில்களுக்காக வரியில்லாமல் விடப்பெற்ற நிலம் அல்லது கிராமம்

பள்ளித்தாமம், பள்ளித்தோங்கல் : கோயில் மூர்த்திக்கு அணிவிக்கும் சூமாலை

பள்ளிப்பீடம் : ஆசனம் ; சிங்காதனம்

பள்ளிச் சிவிகை : கோயில் உற்சவத்தில் மூர்த்தி எழுந்தருளும் பல்க்கு

பள்ளி விளாகம் : சமணர் பௌத்தர் கோயிலைச் சுற்றியுள்ள குடியிருப்புப் பகுதி

பளிக்கு வயிரம் : வைர வகை ; பளிங்கு என்பதே போலும்

பளிங்கு : புஷ்பராகம்

பற்றடை : தொழிற்சாலை

பற்றுமுறி : ரசிது ; பெற்றுக்கொண்டதற்கு ஒப்பம்

பறைத்தறி : துணி நெய்யும் தறிவகை ; அதற்கான வரியையும் குறிக்கும்

பறைத்துடைவை : பறையர்க்கு விட்ட மானியம் ; பறைமை என்பதும் இதுவே போலும்

பறையிறை : முன்னூளில் காசாக இறுத்து வந்த வரி; பறையரிட  
மிருந்து வசூலிக்கப்பெற்றதுபோலும்; அவர்களுக்காக இறுக்கப்  
பெற்றதாகவும் கொள்ளலாம்

பன்றியாழ்வார் : விஷ்ணுவின் வராஹாவதாரம்

பனம் பற்று : பனந் தோப்பு

பனிநீர் : பன்னீர்

பஸ்தி : சமணர் கோயில்; ஜைனர் ஆலயம்

பாக்கம் : சிறுமூட்டை

பாகவதநம்பி : வைஷ்ணவ அடியார்

பாகுவலயம் : தோள்வளை

பாசனம் : (பாஜனம்) சாப்பிடும் பாத்திரம்

பாசி : ஏரி, குளம் முதலிய நீர்நிலைகளிலிருந்து மீன் முதலிய வரு  
வாய் வகைகள்; மச்ச மாகூல்

பாசிப்படை : திடீரென்று தாக்கும் பலம் வாய்ந்த சேனை

பாசிப்பாட்டம் : மீன் பிடிப்பதால் கிடைக்கும் வருவாய்; மீன்பாட்டம்  
எனவும் ஆகும்

பாட்டநெல் : ஒப்பந்தப்படி குத்தகைக்காரனால் சொந்தக்காரருக்கு  
அளக்கப்படவேண்டிய நெல்

பாட்டம் : வரி; தொழில் வரிபோலும்

பாட்டமாளன் : வரி வசூலிக்கும் அதிகாரி; உழவுப் பாத்தியதை  
உடையவன்

பாட்ட விருத்தி : பாட்டமீமாம்ஸையின் பிரவசனத்துக்காக விடப்  
பெற்ற நிலம்; பட்டவிருத்தி எனவும் கொள்வர்

பாட்டிமை : பிரதமை திதி

பாடகம் : மகளிர் காலில் இடும் ஆபரணம்

பாடகம் : வயலின் தளை; விளைநிலப் பகுதி

பாடவரி : உலோகத்தால் ஆன முகம் பார்க்கும் கண்ணாடிக்கு இறுக்  
கும் வரி

பாடவியம் : ஒருவகை வாத்தியம்

பாடன் : இரத்தினம், உலோகத்தகடு முதலியவற்றின் ஒளி

பாடி(க்)காவல் : கிராமக் காவல்; அதற்கான வரியையும் குறிக்கும்

பாடிவேட்டை : கோயில் உற்சவங்களுள் ஒன்று; பாரிவேட்டை  
எனவும் பெறும்

பாடு தாங்குதல் : துணை நிற்கல்

- பாண்டிவரி : மாடு கட்டி ஒட்டும் வண்டிக்கான வரிபோலும் ;  
 பாணிச்சாய் : கள் போன்ற முத்து நிறம்  
 பாத சாலம் : காலணி வகை  
 பாதபாசம் : காலணி வகை  
 பாத புஷ்பம் : பாத காணிக்கை  
 பாதவக்காணி : கோயில் வேலைக்காரர்களுக்கு உரிய படித்தர நிலம்  
 பார்க்கோல் : கட்டியக்காரன் ஏந்திவரும் தடி ; கட்டியத் தடி  
 பார்ப்பனச் சேரி : பிராமணர் குடியிருப்புப் பகுதி  
 பாரக்கூலி : சாமானை எடுத்துப் போவதற்கான கூலி  
 பாரசிவன் : பாரசவன் என்பது போலும் ; ஆயுதம் தரித்தவன் ;  
 போர்வீரன்  
 பாரதப்புறம், பாரதவிருத்தி : மகாபாரதம் படித்துக் கதை சொல்லு  
 வதற்காக விட்ட நிலம்  
 பாரதவர் : மீன் பிடிப்போர் ; பரதவரே போலும்  
 பாரதாயன் : பாரதவாஜ கோத்திரத்தைச் சேர்ந்தவன்  
 பாரிசுஞ் செய்தல் : பொறுப்பாக்குதல் ; ஒப்படைத்தல்  
 பாருபத்தியம் : நிர்வாகம்  
 பாவாடை : திருப்பாவாடை பார்க்க  
 பாழி : ஜைனர் கோயில் ; பள்ளி ; மலைக்குகை  
 பாற்படுத்தல் : நேர்மையாக நடத்திவைத்தல் ; கிரமமாக நிர்வகித்தல் ;  
 ஒழுங்கு செய்தல்  
 பாறைக்காணம் : வண்ணான் தோய்க்கும் கல்லுக்காக இறுக்கும் வரி ;  
 வண்ணான்பாறை எனவும் பெறும் ; பாறையை உடைத்துச் சல்  
 லிக்கல் செய்வதற்கான வரியாகவும் கொள்வர்  
 பாஷாணம் : அஷ்டபோகத்துள் ஒன்று ; பாறை நிலமும் அதனால்  
 கிடைக்கும் பொருளும் ஆகும்  
 பாஷிய விருத்தி : ஸ்ரீபாஷ்யம் எனப்படுவதும் வேதாந்த சூத்திரத்  
 துக்கு இராமானுஜர் எழுதியதுமான விசிஷ்டாத்துவைத பாஷியம்  
 விளக்கிச் சொல்லுவாருக்கு விட்ட மானிய நிலம்  
 பிங்காளம் : உலோகத்தால் ஆன ஒருவகைப் பாத்திரம்  
 பிஞ்சு : ஆபாணத்தில் பிஞ்சுபோன்ற உருவத்தில் அமைந்துள்ள  
 உறுப்பு  
 பிச்சதேவர் : சிவபெருமான் ; பிஷாடன மூர்த்தி ஆகும் ; பித்தன்  
 எனவும் கொள்ளலாம்



- பிடாகை : படாகை ; உட்கிடை கிராமம்
- பிடாநாழி : புதாநாழி பார்க்க
- பிடாரர் : பட்டாரகர் ; சிவபெருமான் ; குருவையும் குறிக்கும்
- பிடாரிப்பட்டி : பிடாரி கோயிலுக்காக விடப்பட்ட நிலம் ; பிடாரி விளாகம் எனவும் குறிக்கப்பெறும்
- பிடி குழ்ந்து : பெண் யானை சுற்றி வர ; தானம் அளிக்கப்பெற்ற கிராமம் அல்லது நிலத்தின் எல்லையைச் சுற்றி வந்து நிர்ணயிப்பது
- பிடிபாடு : ஆதாரச் சீட்டு ; ஆதாவு
- பிடிவிளக்கு : கைப்பிடி கொண்ட தீபம்
- பியர் : பெயர் என்பதன் வேறு வடிவம்
- பிரசண்ட காணிக்கை : (பிரசண்டம்—கடுமையான, பயங்கரமான) படைப் பணம் என்பதனுடன் சேர்ந்து காணப்படுகிறது ; படை வரியில் ஒரு வகை
- பிரசத்தி : பிரசித்தி ; பிரகடனம் செய்தல் ; பறையறைந்து அறிவித்தல்
- பிரசாதப்படுதல் : அனுக்கிரஹம் செய்ததைப் பெற்றுக்கொள்ளுதல் ; அளித்ததை ஏற்றல் ; அரசன் ஆணையை ஏற்றல்
- பிரசாதம் செய்தல் : அனுக்கிரகித்தல் ; அளித்தல் ; அரசாணை
- பிரசிஷ்யன் : சிஷ்யனுடைய சிஷ்யன் ; சிஷ்ய பாம்பரையையும் குறிக்கும்
- பிரட்டன் : பிரஷ்டன் ; நெறியினின்றும் வழுவிவவன்
- பிரதானி ஜோடி : குறைந்த விகிதத் தீர்வையில் மந்திரிகளுக்கு அளிக்கப்பெற்ற இனம் கிராமம்
- பிரதிகிரகம் : தானம் அளிப்பதை ஏற்றுக்கொள்வது
- பிரபாவளி, பிரபை : திருவாசி
- பிரமதானம் : பிராமணர்களுக்கு வழங்கிய தானம்
- பிரமதேயம் : பிராமணர்களுக்குத் தானமாக வழங்கப்பெற்ற கிராமம் ; அகரப்பிரமதேயம் எனவும் பெறும் (அகரம்—வரியில்லாதது)
- பிரமதேயக் கிழவர் : பிரமதேயக் கிராமங்களின் சொந்தக்காரர் ; அத்தகைய கிராமங்களின் அதிகாரி எனச் சிலர் கொள்வர்
- பிரம மாராயன் : பிராமண மந்திரிக்கு அளிக்கப்பெற்ற பட்டப்பெயர்
- பிரம மேதம் : புனிதமானவர்களுக்கு நடைபெறும் ஈமச்சட்டிக்கு வகை
- பிரமாணம் : பத்திரம் ; ஆதாவுச்சீட்டு
- பிரமாதம் விளைதல் : உயிர் போதல் ; இறத்தல்

பிரம்மதி ராஜர், பிரம்மதி ராயர், பிரம்மராயர் : மந்திரிகளிலே பிரம்மணர்களாக உள்ளவர்களுக்கு அளிக்கப்பட்டு வந்த சிறப்புப் பெயர்

பிரவேசகம் : துழைவு

பிரஹரம் : மாணிக்கக் குற்றங்களுள் ஒன்று

பிராணாந்திகம் : ஆயுள் முடியும் வரையில்

பிராப்தி : அடைவது ; பேறு ; பிராப்தி, ப்ராப்தி எனவும் காணப் பெறும்

பிராமண ராசக்காணம் : பிராமண புரோகிதர்கள் அரசருக்கு இறுக்க வேண்டிய வரி ;

பிரீதிப் பிரமாணம் : அன்பினால் அளிக்கும் நிலத்துக்கு உரிய பத்திரம் பிறும்மத்தானம், பிரம ஸ்தானம் : ஊரில் பிராமணர்கள் குடியிருக்கும் பகுதி ; ஊர்ச்சபை கூடும் இடம்

பிறும்மபுரி, பிரமபுரி : அகரப் பிரமதேயமே போலும்

பிள்ளைகள் தனம் : இராஜ குடும்பத்து இளைய பரம்பரையைச்சேர்ந்த வர்களைக் கொண்டு உருவாகிய அதிகார வர்க்கம்

பிள்ளையார் நோன்பு : விராயக சதுர்த்தி ; கோயிலில் அந்த உற்சவத்தை நடத்தி வைப்பதற்காக விடப்பெற்ற மானியம் அல்லது இறுக்கப்பெறும் பணம் ; பிள்ளையார் நோன்புத் தேவை, பிள்ளையார் நோன்புப்பச்சை எனவும் குறிக்கப்பெறும்

பிள்ளை வரி : குமாரர் அல்லது பிள்ளைகள் (இராஜகுமாரர்) என்று குறிக்கப்பெறும் சிற்றரசர் (அதிகாரி) வர்க்கத்தாருக்காக இறுக்கும் வரி ; குமார கச்சாணம் என்பதும் இதுவே போலும் ; (கல்யாண புரத்திலிருந்து அரசாண்ட மேலைச் சாளுக்கிய சாசனங்களில் காணும் குமார விருத்தி என்பதை ஒப்பிட்டுக் காண்க)

பிற்கூறுதல் : முற்கூறியதை ஏற்றுச்சொல்லுதல் ; ஆமோதித்தல் ; ஒப்புக்கொண்டதைத் தெரிவித்தல்

பின்தோன்றல் : தம்பி

பீடலிகைவாரி : கோயில் அதிகாரிகளுள் ஒருவர் ; நிர்மாலியத்தை அகற்றும் பொறுப்பு வாய்ந்தவர் போலும்

புக்தி : அனுபவித்தல் ; புத்தி எனவும் எழுதப்பெறும்

புட்டகம் : ஆடை, சீலை

புட்டக வரி : சீலை விற்பைச் செலுத்தவேண்டிய வரி

- புடவை, புடைவை : ஆடை ; துணி  
 புண்ணிய கணப்பெருமக்கள் : தர்மங்களையும் அவற்றின் நிலங்களை  
 யும் நிர்வகிக்கும் சபையார்  
 புணை : பிணை ; ஆள் ஜாமின்  
 புதாழி : புதாநாழி பார்க்க  
 புதாநாழி : முன்னாளில் வழங்கிவந்த வரி வகை ; ஒவ்வொரு வீட்டு  
 வாசல் நிலையைக் கணக்கிட்டு நாழிசெல்லாக வசூலிக்கப்பெற்றது  
 போலும்  
 புதியது, புதியது : அறுவடையானதும் புதுநெல்லைக் கடவுளுக்குப்  
 படைப்பது  
 புதுவது : புதியது  
 புதுவரி : புதியதாக ஏற்படுத்தப்பெற்ற வரி  
 புரட்டன் : ஏமாற்றுபவன் ; பொய்யன்  
 புரவரியார் : அரசுறைக் கணக்கர்  
 புரவு : நிலவரி ; அரசுறை ; இக் கணக்கு அடங்கிய புத்தகம்  
 புரவுவரி, புரவரி : அரசாங்கத்து வரிக்கணக்கு ; அதை நிர்வகிக்கும்  
 அதிகாரி  
 புரவு நெல் : நெல்லாக இறுக்கும் வரிவகை ; அவ்விதம் வசூலிக்கப்  
 பெற்ற நெல்லையும் குறிக்கும்  
 புரவு பொன் : பொன்னாக இறுக்கும் வரி ; அவ்விதம் வசூலித்த பொன்  
 னையும் குறிக்கும்  
 புருஷாகாரம் : மானிட உருவம்  
 புரையிடம் : தோப்பு  
 புரோகிதக்காணியாட்சி : புரோகிதராக இருக்கும் பரம்பரை உரிமை  
 புல்லந்தி : மேய்ச்சல் தரையில் மேயும் மாடுகளைப் பற்றியதுபோலும் ;  
 திருட்டு மேய்ச்சலுக்கு வசூலிக்கும் தண்டமாக இருக்கலாம்  
 புலவரி : (புலம் + வரி) நிலத்தின் வரி எனப் பொருள்படும் ; ஆயினும்  
 புலவரி என்றே வாசிக்க வேண்டும் எனத் தோன்றுகிறது  
 புலமானியம் : புலியைக்கொன்ற ஒருவனுக்கு விட்ட மானிய நிலம்  
 புழு குடமை : கோயில் மூர்த்திக்குப் புனுகுசட்டம் இடுவதற்காகும்  
 செலவுக்கு இறுக்கும் பணம் ; புழுகுவரி எனவும் பெறும்  
 புழுதிபாடு : தரிசு நிலம்  
 புள்ளடிக்கல் : எல்லைக்கல்  
 புள்ளி : ஈபர் ; குறிப்பிட்டவன்  
 புள்ளிக்குளிகை வராகன் : முன்னாளில் வழங்கிய நாணய வகை

- புள்ளிச்சோறு : சோறு ஊட்டவேண்டிய கடமை  
 புளியிட்டும் கறி : புளிக்கறி ; புளி சேர்த்துச் செய்யும் கறி  
 புறக்கடமை : தர்மத்துக்காக விடப்பட்ட நிலங்களின் மீது இறுக்கம் வரி ; உள்வரியினின்றும் வேறானது ; புறவரி எனவும் ஆகும்.  
 புறக்கடித்தல் : வெளியேற்றத்தல்  
 புறக்கலனையார் : வேறு கிராமத்தில் தொழில் நடத்துவார்  
 புறக்கழனியார் : வெளியூரில் நிலம் உள்ளவர் ; உழுது பயிரிடும் நிலம் ஓர் ஊரில் இருக்க வேறு ஊரில் வாழ்வார்  
 புறக்குடி : பண்ணையாள் அல்லாத குடியானவன் ; தர்மத்துக்கான நிலத்தைப் பயிரிடுபவன் ; வெளியூர் சென்று சாகுபடி செய்பவன்  
 புறக்கோடை : கோயிலின் வெளிப்புறம்  
 புறக்கோயில் : வெளியே உள்ள கோயில் ; பரிவார தேவதைகளின் ஆலயம் ; சுற்றுக்கோயில்  
 புறணி நாடு : எல்லைப்புறமாக உள்ள நாடு  
 புறத்தடியார் : (அகத்தடியாரினின்றும் வேறானவர்) கோயில் முதலிய வற்றின் அடியார் ; தேவரடியார்  
 புறம் : ஒரு குறிப்பிட்ட தர்மத்துக்காகப் பெரும்பாலும் வரியில்லாமல் விடப்பட்ட நிலம் அல்லது கிராமம்  
 புறம்படி : நகரின் புறப்பகுதி  
 புறம்பு : புறக்கடமையே போலும்  
 புறவாயம் : புறவரி ; பெரும்பாலும் காசாக இறுக்கப்படுவது  
 புறவெட்டி : கிராமத்து நலனுக்காக அதன் எல்லைக்குவெளியே செய்ய வேண்டிய பொது மராமத்து வெட்டி வேலை  
 புன்பயிர் : புன்செய் 'நிலத்தில் சாகுபடி செய்வதற்கு ஏற்ற பயிர் ; நெல் நீங்கலாக மற்றவகைப் பயிர்  
 புன்னீர் : கழிவு நீர்  
 புனக்குளம் : மழைத் தண்ணீர் தேங்கி நிற்கும் குட்டை  
 புஷ்கரப்பத்திமடல் : திருநீறு வைக்கும் மடல்  
 புஷ்பத் தளிகை : கோயில் வழிபாட்டில் மலரைச் சமர்ப்பித்தல் ; மலர்த்தட்டம்  
 புஷ்யராகம் : புஷ்பராகக் கல்  
 பூச்சியாளுதல் : இலை முதலியவற்றை அரிக்கும் பூச்சிகள் மிகுத் திருத்தல்  
 பூசகன் : பூசகன் ; கோயில் பூசை செய்வோன்

பூட்சி : வரி

பூட்டைக்கிணறு : நீர் பாய்ச்சுவதற்கான ஏற்றம் அமைத்த கிணறு

பூமகள் : லக்ஷ்மி; பூமிதேவி

பூமிப்பிராட்டி : பூமிதேவி

பூமிபுத்திரர் : வேளாண் மக்கள்; சித்திரமேழிப் பெரிய நாட்டவர்  
என்னும் சபையைச் சேர்ந்தவர்

பூர்வாசாரம் : முன்னாள் வழக்கம்

பூரிக்குத்தலரிசி : நன்கு குற்றித் தீட்டிய அரிசி

பூரிச்சேரல் : நெல் வகை; பூரிநெல் என்பதும் இதுவே போலும்

பூவிவோன் : கோயிலுக்குப் பூப்பறித்துக் கொடுப்பவன்

பூஜாவிருத்தி : கோயில் பூசை செலவுக்காக மானியமாக விடப்பட்ட  
நிலம்

பெண்டாட்டி : பெண்மகள்; ஸ்திரீ; வேலைக்காரி

பெண்டுகள் : பெண்மக்கள்

பெண்பள்ளி : பெண்துறவிகள் தங்குமிடம்

பெத்திரி வீடு : பண்டகசாலை, கிடங்கு (தொழிற்சாலை என்று பொருள்  
படும் Factory என்பதன் வேற்று வடிவம் போலும்: உலாந்தாக்  
காரருக்குத் தஞ்சை மன்னன் எக்கோஜி அளித்த செப்புப்பட்டயம்)

பெரிய தேவர் : சோழர் ஆட்சியில் இறந்துபோன அரசரை அவருக்குப்  
பின் வந்தவர்கள் இவ்விதம் குறிப்பது வழக்கம்; பெரிய பெருமாள்  
எனவும் பெறுவர்

பெரிய பெருமாள் : பெரியதேவர் பார்க்க; அரசர்களுக்கு மேல் அரசு  
னான பேர் அரசன் அல்லது சக்கரவர்த்தியாகவும் கொள்வர்

பெருங்குறி, பெருங்குறிச் சபை, பெருங்குறி மகாசபை : அகரப்பிரம  
தேயக் கிராமத்துச் சபையின் பொதுக்கூட்டம்; மகாஜன சபை  
என்னலாம்

பெருந்தரம், பெருந்தனம் : அரசாங்க அதிகாரங்களில் உயர்ந்த  
தரத்தார்; சிறுதரம் பார்க்க

பெருந்திணை : நல்ல வமிசத்தில் பிறந்தவர்; சோழர்கள் ஆட்சியில்  
நாட்டின் பிரமுகர்களுக்கு அரசன் வழங்கிய பட்டப்பெயர்

பெருந்திருவமிர்து : கடவுளுக்குப் பெரிய அளவில் படைக்கும் நிவே  
தனம்

பெருநகரத்தார் : வணிகர்

பெருநான்கெல்லை : கிராமம் அல்லது பெரிய நிலத்தாக்கின் எல்லை;  
சிறுநான்கெல்லையினின்றும் வேறுபடும்

பெரும்படி : உத்தேசமாக இடும்மதிப்பு

பெரும்பத்து, பெரும்பற்று : சர்க்காருக்கு உரிமையான நிலம்

பெரும் பாடிகாவல் : (சிறு பாடிகாவலினின்றும் வேறுனது) நாடு  
முதலிய பெரிய பகுதியின் காவல்

பெரும்பூ : முக்கியமான பயிர் ; பெரும் போகம் ; அதனின்றி கிடைக்  
கும் வருமானம்

பெருமக்கள் : முதியோர் ; ஒரு சபை அல்லது நிர்வாகக் குழுவின்  
உறுப்பினர்கள்

பெருமானடிகள் : முன்னாளிலே தெய்வத்தையும் அரசரையும் குறித்து  
வந்த மரியாதைச் சொல்

பெருமுதியன் : கோயில் அதிகாரிகளுள் ஒருவன்

பெருவளவாய் : நீர்பாயும் பெரிய ஆற்றுக்கால்

பெருவாயன் : கூடை

பெருவாயில் : பிரதானவாசல் ; கோபுரம்

பெருமுறி : சம்பளம்

பேதை பாதம் : விக்கிரகத்தின் காலில் அணியும் ஆபரணம்

பேர்க்கடமை : தலைவரிபோலும் ; ஆள்வரி, பேர்வாசி என்பனவும்  
இதுவே

பேர்ப்பன் : பெரிய தகப்பன் ; தகப்பனுக்கு அண்ணன்

பேரி : முரசு, நகரா போன்ற பறை வாத்தியம்

பேரிளமையார் : நானுதேசி வியாபாரக் குழுவினரில் ஒரு சாரார் ;  
கோயிலில் தேவகாரியம் பார்க்கும் மகளிர் ; தேவரடியார்

பேறு : பதவிக்கு உரிய காணிக்கைபோன்ற வருவாய் ; சம்பளத்துக்குப்  
பதிலாக அளிக்கப்பெறும் நிலம்

பைங்கிணறு : குட்டை

பைசாரம் : பிரதேசம்

பொக்கிசம் : கஜானா ; கோயில் பொக்கிஷத்து அதிகாரி

பொத்தகம் : புத்தகம் ; வரிப்புத்தகம் ; வரிக்கணக்கு

பொதிகூலி : தலைச்சுமை எடுத்துவரும் கூலி

பொதுவாள் : கோயில் நிர்வாகம் செய்பவன்

பொல்லாப்பு : ஆசேஷபணை ; எதிரிடை

பொலிகை, பொலிசை : பஸிசை, வட்டி

பொலிசையூட்டு : வட்டிக்கு விடுதல், வட்டி கொடுத்தல் ; பொலியூட்டு  
பார்க்க

போலிமுறை நாகு : சினைப்படுவதற்கு ஏற்ற நிலையில் உள்ள கிடாரிக் கன்று

போலியூட்டு : பொலிசையூட்டு; நிரந்தரமான வருவாயை அளிப்பதற் காக ஸ்தாவர சொத்துக்கள் மீது கடன் கொடுத்தோ, வாய்க் கால் குளம் போன்ற நீர்நிலைகளைச் செப்பனிட்டோ முதலை வட்டிக்கு விடுவது

போற்பூ : ஸ்வர்ண புஷ்பம்; சில குறிப்பிட்ட சந்தர்ப்பங்களில் பள்ளி மாணவர்கள் தேர்ச்சி பெற்றதைக் குறிக்க அளிப்பது; கோயில் பூசையிலும் உபயோகிப்பது

போற்றை : சிறுமலை; கற்பாறை; சிறுகாடு; புதர்

போன் : முன்னாளில் வழங்கிய தங்க நாணயம்; மாடை எனவும் பெறும்; கழஞ்சு என்பதும் இதுவே என்பர்

போன்பண்டாரம் : கோயிலில் நகை முதலியவற்றைப் பாதுகாக்கும் கஜானா

போன்பண்டாரவாசல் : கஜானா

போன்மாளிகை : அரசன் வாசம் செய்யும் அரண்மனை; முக்கியமாகக் காஞ்சிபுரத்தில் இருந்த அரண்மனை

போன்வர்க்கம் : பொன்னாக, காசாக இறுக்கவேண்டிய வரிவகை

போன்வரி : பொன்னாக இறுக்கும் வரி; பொன்னை நாணயமாக அச்சிடுவதற்கான வரியும் ஆகும்; போன்வரி மாடை என்பதும் இதுவே

போன்னூல் : பொன்னுலாகிய நூல்; விக்கிரகத்துக்கு இடம் பொன்னூல் ஆன பூணூல் போலும்

போகஆயகம் : அனுபோகத்துடன் கூடிய நில அடைமானம்

போகபத்திரம் : அனுபோக அடைமான பத்திரம்; அது தீர்ந்த பிறகு விடுதலை எழுதிக்கொடுப்பதும் ஆகும்

போகம் : குறிப்பிட்ட சில ஊழியம் செய்வோருக்குச் சம்பளத்திற்குப் பதிலாக அனுபோகத்துக்கு அளிக்கும் நில மானியம்

போகியார் : காதற்கிழத்தி; (மனைவியைக் குறிப்பதாகவும் கொள்வர்)

போசர் : (போஜகர்) அனுபோக உரிமை வாய்ந்தவர்; சொந்தக்காரர்

போதுதல், போதுகிறது : போதல், போகிறது என்பவற்றின் பழைய வடிவங்கள்

போர்த்தனிப்பூவை : போர்ச் சயப்பாவை; போர்மகள்; வீரலக்ஷ்மி, விஜயலக்ஷ்மி

போனகை குருத்து : கடவுளுக்குப் படைக்கும் நிவேதனத்துக்கு இடம்  
வாழை துனி இலை ; தலைவாழையிலை  
போனகம் : கடவுளுக்குப் படைக்கும் உணவு

மக்கட் சேவகம் : ஊழியம் ; அதைச் செய்வோன் மக்கட்சேவகன் ;  
அவனுக்கு அளிக்கப்பட்ட மானிய நிலம் மக்கட் சேவகப் பேறு  
எனப்பெறும்

மக்கட்பேறு : புத்திரரைப் பெறுதல் ; அதற்கான வரியையும் குறிக்கும் ;  
குடிமக்கள் என்ற நிலையின் கடமையைக் குறிப்பதாகவும் கொள்ள  
லாம் ; மக்கட் சேவகப்பேறு எனவும் ஆகும் போலும்

மக்களையனார் : (மக்கள் நாயனார்) அரசனுடைய மகன்

மகதாகம் : மிகுந்த தாகம் ; இறந்தபின் ஆன்மா கடந்து செல்ல  
வேண்டிய நாகவகைகளுள் ஒன்று

மகப்படி : கோயில் செலவுத் திட்டத்தில் ஒன்று ; மக நக்சத்திரத்தில்  
நடத்தும் உற்சவச் செலவுபோலும்

மகமை, மகன்மை, மகண்மை : வியாபாரச் சரக்குகளின் விலை  
அளவு ஆகியவற்றுக்கு ஒரு விகிதாசாரம் வைத்து வியாபாரிகள்  
தாமாகவே கோயில் சத்திரம் போன்ற தர்ம ஸ்தாபனங்களின்  
செலவுக்காக அளிக்கும் வரி

மகரசங்கிரமணம், மகரசங்கிராந்தி : தைமாதப் பிறப்பு

மகரம் : மகர வடிவில் உள்ள குழை ; காதணி ; மகர குண்டலம்

மகன்மை : ஆண்மக்கள் வரி

மகாசபை : கிராமத்தின் எல்லா மக்களும் சேர்ந்து நடத்தும் கூட்டம் ;  
மஹாஜன சபை

மகாசாகை : மரத்தின் முக்கியமான கிளை

மகாசாமந்தன் : சிற்றரசுப்பதவியில் உள்ள மந்திரி

மகாதந்திரம் : சேனையின் நிர்வாக சபை

மகாதேவி : பட்டத்தரசி

மகாதோரணம் : கோயிலில் அலங்காரமாக ஏற்றும் தீபவகை ; மகர  
தோரணம் என்பதே போலும்

மகாநகரம் : பெரிய வியாபார ஸ்தலம் ; அவ்வூரின் வியாபாரிகள் சபை

மகாநாடு : வியாபாரிகளின் கூட்டம்

மகாநியோகம் : அரசன் ஆணை ; அதனைத் தாங்கிச் செல்லும் அதிகாரி

மகாப்பிரதானன் : பிரதானிகளின் தலைவன் ; சேனைத்தலைவன் ; மஹாப்  
பிரதானி எனவும் குறிக்கப் பெறுவன்

மகாப்பிரபு : பெரிய தனவந்தன் ; வியாபாரிகளின் தலைவன்



மகாபரதவிருத்தி : மகாபாரதம் வாசித்து விளக்கிக் கூறுபவர் அனு  
பவிக்க விட்ட மானியம்

மநாபூதகடதானம் : தானவகையில் ஒன்று

மகாமண்டபம் : கோயிலில் அர்த்த மண்டபத்தை யடுத்துள்ள பெரிய  
மண்டபம்

மகாமண்டலேச்வரன் : ராஜ்யப் பகுதியை நிர்வகிக்கும் சிற்றரசன் ;  
மகாமண்டலிகள் எனவும் பெறுவன்

மகாமாத்திரர் : முதன் மந்திரி

மகாவட்டவியவஹாரி : வியாபாரிகள் தலைவன் ; பண லேவாதேவிக்  
காரன் ; வட்டிக்குப் பணம் கொடுப்போர் தலைவன்

மகாவிரதன், மகாவிரதி, மாவிரதி : சைவசமயத்துள் ஒரு பிரிவான  
மாவிரதம் என்பதைச் சார்ந்த அடியார்

மகாவிலஸ்தை : மகாசபை செய்த விவஸ்தைபோலும் ;

மகாஜனம் : கிராம மக்கள் அனைவரும் சேர்ந்த கூட்டம்

மகேச்வரர், மாஹேச்வரர் : சிவனடியார் ; கோயில் நிர்வாகத்தில்  
பொறுப்புள்ள சிவனடியார் சபை

மகேச்வரபெருந்தனத்தார் : சிவனடியார் ; பாசுபதர்போலும்

மங்கலம் : சதுர்வேதி மங்கலம் என்பதன் குறுகிய வடிவம் ; பிராமணர்  
குடியிருப்புக்காகப் பெரும்பாலும் வரியில்லாமல் விடப்பெற்றகிராமம்  
மங்கிலியம் : தாவி

மச்சாழ்வி : மைத்துனன் என்பதன் வேறு வடிவம் ; மனைவியின்  
சகோதரன் ; சகோதரி கணவனும் ஆகும்

மஞ்சள்காப்பு : கோயில் மூர்த்திகளுக்கு மஞ்சளை அரைத்து விழுதைச்  
சாத்துவது

மஞ்சாடி : இரண்டு குன்றுமணிகள் கொண்ட எடை ; அந்த எடை  
யுள்ள பொன்

மஞ்சிக்கம் : ஊர்ப்பொதுவில் பயிரிடாமல் உள்ள தரிசு நிலம்

மட்டத்தாரை : கூர்மையில்லாத விளம்பு கொண்டது

மட்டத்தாரைச்சப்படி : மழுங்கிய விளிம்புகொண்ட தட்டை வைரம் ;  
மட்டத்தாரைச் சவக்கம் என்பதும் இதுவேபோலும்

மட்டம் : சிறியது

மட்டப்பூ : அணி உறுப்புகளுள் ஒன்று, தொங்கும் வகை

மடப்புறம் : மடத்துக்கு விடப்பெற்ற இறையிலி நிலம்

மடம் : பிரமசாரிகளும் துறவிகளும் வாழும் இடம் ; துறவிகளுக்கும்  
தவசிகளுக்கும் உணவு இடும் சத்திரம்

மடவளாகம், மடைவிளாகம் : கோயிலைச் சூழ்ந்துள்ளதும், கோயில்

பரிவாரத்தார் குடியிருப்பதுமான இடம்

மடாபத்தியம் : மடத்தின் அதிபதிப் பொறுப்பு ; மடத்தின் நிர்வாகம்

மடை : சமைத்த சோறு ; நைவேத்தியம்

மடைப்பள்ளி : கோயிலில் சமையல் செய்யும் இடம்

மடைப்பள்ளிப் புறம் : கோயில் அடுக்களைச் செலவுக்காக விடப்பெற்ற நிலம் அல்லது கிராமம்

மடைப்போக்கு : மதகிவிருந்து நீர் பாய்வது

மண்டகம் : மண்டபம்

மண்டபக்கோத்து : கோயில் பரிவார வகை

மண்டலம் : நாட்டின் பெரும்பகுதி (சோழமண்டலம்)

மண்டலமுதன்மை : மண்டல நிர்வாகத்தின் தலைமைப்பதவி ; அதை வகிப்பவர் மண்டல முதலியார் எனப்பெறுவர்

மண்டல முதன்மைப்பேறு : மண்டலாதிபதியின் அனுபோகத்துக்கு விடும் நிலம், அல்லது அவனுக்காக இறுக்கும் வரி

மண்டலிகள் : மண்டலத்தை ஆளுவோன் ; மண்டலேச்வரன் எனவும் பெறுவன்

மண்டையவியன் : மாண்டவிய கோத்திரத்தைச் சேர்ந்தவன்

மண்ணான் : ஹரிஜனங்களின் வண்ணான்

மண்பாடு : மண்ணால் எழுப்பிய வரம்பு ; மண்ணால் ஆன கரை

மண்மதில் : மண்ணால் எழுப்பிய கோட்டைச்சுவர் ; அதன் பாதுகாப்புக்காக இறுக்கும் வரியும் ஆகும்

மணவாட்டி : மனைவி

மண்டி : மாணவி ; பெண் சிஷ்யை

மணிக்கலம் : கல் வைத்து இழைத்த ஆபரணம்

மணிக்கிராமம் : வியாபாரிகளின் குழுவில் ஒருவகை ; அவர்கள் வாழும் நகரம்

மணியம்பலம் : ஓலக்க மண்டபம் ; ராஜ சபை

மத்தியக்கன், மத்தியஸ்தன் : நடுநிலை வகிப்பவன் ; பெரும்பாலும் கிராமத்தலைவன்

மதலை : மகன்

மந்தவாடை : இளவாடைக் காற்று

மந்திர போனகம் : நிவேதன உணவு

மந்தைகண்டேற்றம் : மந்தையின் மேய்ச்சலுக்கான பூமியும் அதனைச் சார்ந்த இடமும் ; அவற்றை உண்டாக்குவது போலும்

மந்தைப் பணம் : கிராமங்களில் கால்நடைகளின் மேய்ச்சல் பூமிக்காக இறுக்கும் வரி

மயிலாப்பில், மயிலார்ப்பில் : மயிலாப்பூரின் பழைய பெயர்  
 மரக்கடமை : மரங்களின் மீது இறுக்கும் வரி  
 மரமச்சாதி விலை : மரம், மீன் முதலியவற்றால் கிடைக்கும் வருவாய்  
 மரமஞ்சாடி : பயன்தரும் மரத்துக்கு மஞ்சாடி வீதம் இறுப்பது  
 மரவடை : பயன் தரும் மரங்கள் ; அவற்றை அனுபவிக்கும் உரிமை;  
 மரவிடை எனவும் பெறும்  
 மரியாதி : எல்லை ; வரம்பு ; வீதம் ; மர்ஜாதி, மரிசாதி, மருசாதி என்பன  
 போன்ற வடிவங்களிலும் காணப்படும்  
 மரு : மருக்கொழுந்து ; கொழுந்து எனவும் பெறும்  
 மருத்துவப்பேறு : கிராம வைத்தியனுக்கு வரியில்லாமல் விட்ட மானிய  
 நிலம்  
 மல்லாயி மகமை : முன்னாளில் வழங்கி வந்த வரிவகை ; பொருள்  
 விளங்கவில்லை ; சந்தை மகமை போலும்  
 மலர் : ஆயுதம் முதலியவற்றின் தலையில் உள்ள குமிழ்  
 மலைகுனிய நின்றான் : திருப்பதியில் உள்ள வேங்கடேசப்பெருமான்;  
 அவன் கோயிலில் வழங்கும் எடை அளவு முதலியன  
 மலையாண் விளக்கு : கோயிலில் ஏற்றும் விளக்கு வகை  
 மலையாள முதலி : மலைவாழ் மக்கள் தலைவன்  
 மழு : பழுக்கக் காய்ச்சிய இரும்பை ஏந்தி நிரூபிக்கும் முறை  
 மறமாணிக்கர் : பொன் அமராவதியைச் சுற்றியுள்ள பிரதேசத்தில்  
 வாழும் வீரர் வகுப்பார்  
 மறு, மறுவு : இரண்டாம் போகம் ; மறுபடியும் சாகுபடி செய்வது  
 மறுகால் தலை : வடிகால் மதகு  
 மன்றம் : மன்று பார்க்க  
 மன்றாடி : இடையர்  
 மன்றாடி வாரியம் : கோயில் காரியங்களை நிர்வகிக்கும் சபை (மன்றாடி-  
 அம்பலக்கூத்தாடும் சிவபெருமான்)  
 மன்று : சபை ; நியாய சபை ; ஊர்ப்பொதுவிடம்  
 மன்றுதல் : தண்டம் விகித்தல்  
 மன்றுபாடு : நியாய விசாரணை சபைக்கு இறுக்கும் அபராதப் பணம்  
 மன்னனார் : விஷ்ணு  
 மனிச்சம் : மனிதன்  
 மனைக்கடையான் : மனையிலேயே கடை வைத்து வியாபாரம் செய்  
 பவன்

மனைப்படப்பு : மனையைச் சுற்றியுள்ள இடம் ; மனைப்படப்பை என  
வும் பெறும்

மனைப்பணம் : வீட்டு வரி ; மனைவரி எனவும் படும்

மனையிறை : வீட்டு வரி

மனைவாணீளம் : மனையின் நீண்ட வால் வீச்சு

மனுவாறு : மனுகீதி வழியே

மா : இருபதில் ஒரு பாகம் ; நில அளவு, நிறுத்தல் அளவு

மாங்காய் நாண் : மாங்காய் மாலை

மாசாத்துநாயன் : வியாபாரிகள் தலைவன் ; முன்னூளில் வெளிநாட்டு  
வியாபாரம் செய்துவந்த பெரிய வியாபாரிகளுக்கு அரசன் அளித்த  
பட்டப்பெயர்

மாசுமறு : குற்றம் ; மாசும் மறுவும்

மாட்டறிதல் : கையெழுத்துக்குச் சாட்சி போடுதல்

மாட்டு : இணைந்த, உரிய, சேர்ந்த

மாட்டுக்கறை : மாடுகள் மீது இறுக்கும் வரிபோலும்

மாடக்கோயில் : மேட்டிடம், கட்டுமலை, உயர்ந்த உபபீடம் ஆகியவற்றின்  
மீது கட்டப்பெற்ற சிவன் கோயில் ; ஒன்றுக்கு மேற்பட்ட தளங்  
களையுடையதாகவும், குறுகிய வழியுள்ளதாகவும் இருக்கும் எனக்  
கொள்வர்

மாடலீதி : கோயிலைச் சுற்றியுள்ள வீதி

மாடாபத்தியம் : மடாபத்தியம் பார்க்க

மாடோணிக்கை : ஊருக்கு விஜயம் செய்யும் அதிகாரிகள் முதலா  
னோர் உபயோகத்துக்கு மாடு அளிக்கும் கடமை

மாடை : முன்னூளில் வழங்கிய பொன் நாணயம் ; கழஞ்சு எனவாம்

மாடைக்கூலி : பொன்னை நாணயமாக அச்சடிப்பதற்கான கூலி

மாணி : மாணவன் ; பிரமசாரி ; கோயில் காரியம் பார்க்கும் பிரம  
சாரி

மாணிக்கத்தார் : கோயிலைச்சேர்ந்த பெண்கள் ; தேவரடியார்

மாணிக்கப்பண்டாரம் காப்பான் : கோயிலின் ரத்தினம், நகை முதலிய  
வற்றைக் காக்கும் அதிகாரி

மாத்தால் : மா ஒன்றுக்கு இவ்வளவு என்று

மாதப்படி : மாத மாதம் இறுக்கும் வரிவகை ; மாதம், மாதார்க்கம்

மாதார்க்கை எனவும் பெறும் ; திங்கள்சோறு பார்க்க

மாந்தோட்டுப் பச்சை : பச்சைக்கல் வகை

மாப்பட்டை : முன்னுளில் வழங்கிவந்த காசாய வகை; கிராமங்  
களில் மந்தைக்கான வரியாக இருக்கலாம்; மரப்பட்டை எனக்  
கொண்டால் மரங்களை விற்கும் தொழிற்சாலையாகக் கொள்ளலாம்

மாப்பணம் : முன்னுளில் வழங்கிய ஒரு நாணயம்; மாவுக்குப் பணம்  
வீதம் அளிப்பதையும் குறிக்கும்

மாப்பதக்கு : மாவுக்குப் பதக்கு வீதம் அளிப்பது

மாமகம் : முன்னுளில் வழங்கிவந்த வரிவகை; மகாமகவரி எனக்  
கொள்வர்; மார்க்கம் என்பதே தவறாக எழுதப்பட்டிருப்பது  
போலும்

மாமடி : மாமனைக் குறிக்கும் மரியாதைச் சொல்

மாபூலாதாயம் : மாபூலாக அடையவேண்டிய வருவாய்

மாயிலட்டி : சோழர் ஆட்சியிலே அந்தப்புரப் பெண்களுக்கு வழங்கிய  
மரியாதைச் சொல்

மார்க்காதாயம் : சாலைவழியே செல்லும் சரக்குக்கு இறுக்கும் சுங்கம்;  
வழி ஆயம் எனவும் படும்

மாராயன் : தலைவன் என்பதைக் குறிக்க முன்னுளில் அரசன் வழங்கிய  
பட்டப்பெயர்

மாவடை, மாவிடை : கிராமத்தில் கால்நடை அடையும் இடம்;  
அதனை உபயோகிக்கும் உரிமை

மாவிறை : அரசனுக்கு உரிய வரி; மாவிந்தக்கடமை என்பதும்  
இதுவேபோலும்

மாளிகைக்கோல் : அரண்மனை அங்கீகாரம் பெற்ற அளவுகோல்

மாளிகை நாயகம் : அரண்மனை விசாரணை உத்தியோகத் தலைமை

மாற்றம் : பதில்; உத்தரவு; தீர்மானம் (சபாமாற்றம்)

மாழி : பொன் மாற்று

மானதண்டம் : மானதண்டு; அளவைக்கோல்

மானபோகம் : மானிய நிலங்களை அனுபவித்தல்

மானவட்டில் : முகத்தல் அளவுக்கான பாத்திரம்

மீலாடு : மலையமான் நாடு; மலாடு எனவும் பெறும்

மீளகுத்தரகு : மீளகு வியாபாரத்தின் தரகாக இறுக்கும் வரி

மீகை : (மேல்கை) மேலோங்கியகை; மேலெடுத்தகை

மீயாட்சி : நிலம் முதலியவற்றின் மேல் அதிகாரம்; மேல்வார உரிமை;  
தாராண்மையினின்றும் வேறுனது

மீயாளுங்கணம் : மேலதிகாரம் செய்யும் குழு; அதன் உறுப்பினர்  
மீயாளுங்கணத்தார் எனப்பெறுவர்

மீன்கடமை : மீன் பிடித்தற்கு உரிய வரி; மீன்பாட்டம் எனவும்  
பெறும்

மீன்பயில் பள்ளம் : மீன் உள்ளதான நீர்நிலை

முக்கால்வட்டம் : கோயில்

முக்குடைக்கல் : சமணர் ஆலயத்துக்குச் சொந்தமான நிலத்தின்  
எல்லையைக் குறிக்க நடும் மூன்று குடையின் உருவம் பொறித்த  
எல்லைக்கல்

முக்கை : மூன்றுகை; அரிமுக்கை என்பதுபோல் வருவதைக்  
காண்க

முத்தியார் : பிறருக்காகக் காரியங்களை நிர்வகிப்பவன்; காரியகர்த்தா

முககட்டணம் : கட்டட முகப்பு

முகட்டுக்கால் : மேட்டுமடையின் கால்

முகந்துடைத்தல் : முகத்தை சுஷ்வரம் செய்தல்

முகம்பார்வை : கண்ணாடி; அதற்காக இறுக்கும் வரி

முகமண்டபம் : முன்மண்டபம்; கோயிலின் முன் மண்டபம்

முகவேட்டி : சோழர் ஆட்சிக்காலத்திலே அரசாங்கத்துறைத் தலைவன்;  
அந்த அந்தத் துறையின் ஒலைகளை நிர்வகிப்பவன் போலும்

முட்டாவாள் : இடையறாமல் தொடர்ந்து பொதுவேலை நடப்பதற்கு  
ஆள் அளிக்கும் கடமை; அதற்கான செலவையும் குறிக்கும்

முட்டி : முட்டாவாள் என்பதே போலும்

முட்டி : முஷ்டி; கைப்பிடியில் அடங்குவது; பிச்சை; கையேற்பு  
என்பதே போலும்; விஷம் தீர்க்கும் மந்திர சிகிச்சை வகையும்  
ஆகும்

முட்டுதல் : தடைப்படுதல்

முட்டையாள் : முட்டாவாள் பார்க்க

முடங்கு : நிலத்தின் ஒரு மூலையில் நீண்டிருக்கும் பாகம்

முத்தாவணம் : முன்னாள் விற்பனை வரி

முத்திராவதாரம் : காதில் இடும் ஆபரணவகை

முத்திரை கர்த்தா : அரசாங்கம் அல்லது கோயில் முத்திரை வைத்  
திருக்கும் அதிகாரி; காரியகர்த்தா; நிர்வாகி

முத்திரைச் சங்கு : சங்கின்வகை; முத்திரை பொறிக்கப்பட்ட சங்கு

முத்திரைவாங்கி : முத்திரைகளைப் பரிசோதிப்பவன்; நிலவரி இலாக்  
காவில் எல்லைக் கற்களைப் பரிசோதிக்கும் ஓர் அதிகாரி

முத்துவட்டம் : உருண்டையான முத்துவகை  
 முதல் : பத்திரம்; ஆதரவுச் சீட்டு  
 முதல் : மூலதனம்; வட்டியை மட்டும் உபயோகித்துக் கொள்வதற்  
 காக இட்ட பொருள்; சேமிக்கும் பொருள்  
 முதல்தீர்த்தம் : கோயிலில் சேவிப்போர் கோஷ்டியில் முதல் முதலாகத்  
 தீர்த்தம் பெறும் மரியாதை உரிமை  
 முதல் பாவாடை : வெளியே செல்லும்போது முன்னே துணியிரித்துச்  
 செய்யும் மரியாதை; அதைச் செய்யும் வேலைக்காரத் தலைவன்  
 முதல் மரியாதை : கோஷ்டியினரில் முதலில் மரியாதை பெறும்  
 உரிமை; முன்மரியாதை எனவும் பெறும்  
 முதலி(யார்) : தலைவன்; பெரியோர்  
 முதலிப்பிள்ளை : தலைமை முதலிப்பதவியில் உள்ளவனுக்கு அடுத்த  
 படியாக உள்ளவன் போலும்  
 முதற்படைக் கலனையார் : நானாதேசி என்னும் வியாபார்க்குமுவினரின்  
 ஒருவகையார்; வியாபாரப் பண்டங்களைக் காக்கச்செல்லும் படை  
 யினர், அதிலும் முன்னணிப் படையைச் சேர்ந்தவர் போலும்  
 முதற்பாவாடை : தலைமை வேலைக்காரன்; முதல்பாவாடை பார்க்க  
 முதற்றிரமம் : (முதல்திரமம்); காசாக இறுக்க வேண்டிய வரிவகை;  
 எதைக் குறிப்பதென்று விளங்கவில்லை; திரமம் என்பது ஒரு  
 நாணயவகை  
 முதுக்கள் : முன்னோர்  
 முதுகண் : காப்பாளன்; பாதுகாப்பு அளிப்பவன்  
 முதுதறை : பாழ் நிலம்; அனாதி தரிசு  
 முப்பாடு வட்டம் : முக்கால் வட்டமே போலும்  
 முலைவிலை : பரிசுப்பணம்; மணப் பெண்ணுக்குக் குழந்தைப் பருவத்  
 திலே தாய்ப்பாலூட்டி வளர்த்ததற்காகத் திருமணத்தின் போது  
 அவள்தாய்க்கு மணமகன் கொடுக்கும் பணம்  
 முழுவரிசை : முழு விகிதம்  
 முள்ளடி சின்னம் : முன்னாளில் வழங்கிவந்த வரிவகை; துப்புக்  
 கொடுப்பதற்காக அளிப்பது போலும்  
 முளைப்பயறு : முளையுடன் கூடிய பயறு; ஒருவகைப் பணிகாரம்  
 முற்காவலுடைய பாடிகாப்பான் : காவல்புரிவோருள் ஓர் அதிகாரி  
 முற்கூறுதல் : முதலில் சொல்லுதல்; விலையை நிச்சயித்துக் கூறுதல்;  
 பிரோணை செய்தல்  
 முற்றாட்டு : ஸர்வ மானியம்; எந்தவரியும் இல்லாமல் அளிக்கப்பட்டது  
 முறி : பத்திரம்; கையெழுத் திட்ட சீட்டு

முறிவு : வைரக் குற்றத்துள் ஒன்று

முன்பிலாண்டு : முன் சென்ற வருஷம்; கடந்த ஆண்டு

முன்மாலை : கோஷ்டியில் முதல்மாலை அணிவிக்கும் மரியாதைக்கான உரிமை

முன்னிடம் பணம் : பின்னால் வசூல் செய்துகொள்வதாக முதலில் கொடுக்கும் பணம்; முன்பணம்

முனைவீரக்கோடியார் : நானாதேசிகளுள் ஒருவகையார்; போர்த் தொழிலைக் கொண்டவர்; வியாபாரப் பண்டங்களைக் காக்கச்செல்லும் படைப்பகுதியினர்

முன்னோடுக்கு : முன்னாலே செலுத்தியது

மூக்கு : பாத்திரத்தின் வாயில் மூக்குப்போல் உள்ள உறுப்பு

மூக்குவட்டகை : மூக்குப்போன்ற விளிம்பு கொண்ட கிண்ணம்

மூங்கில்வரி : மூங்கில்மீது இறுக்கும் வரி

மூத்ததிகாரம் : தலைமை அதிகாரம்

மூலத்தானம் : கோயில் கர்ப்ப கிருகம்

மூலபருடை, மூலபரிஷத் : சிவன் கோயில் நிர்வாகத்தை நடத்தி வந்த முக்கிய சபை; மூலபருடை, மூலபருஷை, மூலபரிஷை எனப் பல விதமாக எழுதப்பெறும்

மூலபிருத்தியர் : சிவபெருமானுடைய முக்கிய ஊழியரான ஆதிசண்டேசுவரர்; சண்டேசுர நாயனார்

மூலம் : ஆதாரபத்திரம்; ஆதரவுச் சீட்டு

மேய்க்காட்டு : நேரில் வந்திருத்தல்

மேய்காவல் : பாதுகாப்பாளன்

மேய்தாங்கி : ஆசனம்

மேய்மட்டு : நட்புவத்துக்கு மிருதங்கம் அடிக்கும் உரிமை; மேய்மட்டுக் காணி எனவும் பெறும்

மேய்யாட்சி : மீயாட்சி என்பதன் வேறு வடிவம்

மேய்வேறு : தனித்தனியாய்

மேழுக்கடிகள் : கோயிலை மெழுகிச் சுத்தம் செய்யும் அடியார்

மேழுக்கு : கோயிலை மெழுகிச் சுத்தம் செய்தல்; கோயில் மூர்த்திக்குச் சந்தனம் புனுகு முதலியவற்றைச் சாத்துதல்

மேழுக்குப்புறம் : கோயில் மூர்த்திக்குப் புனுகுசட்டம் சாத்தும் செலவுக்காக விட்ட மானியம்; கோயிலை மெழுகுவதற்கு விடப் பெற்ற இறையிலி நிலம் எனவும் கொள்வர்



- மேட்டுநிலம் : உயர்வான பூமி; மேட்டேற்றம் என்பதும் இதுவே
- மேடுகல்வதல் : மேட்டு நிலத்தை வெட்டிச் சமமாக்குதல்
- மேய்ப்பான் : அடக்கியாளுபவன்; கண்காணிப்பவர் போலும்; மனை  
மேய்ப்பான் கொள்ளும் இறை என்பது கட்டடங்களைப் பார்வை  
யிடும் அதிகாரிக்கான வரி அல்லது உரிமை என ஆகும்
- மேர்வை : மேரை பார்க்க
- மேராழி : முன்னாளில் வழங்கிய வரிவகை; மேரை என்பதேபோலும்
- மேரை : அறுவடையான மாசூலில் கிராம அதிகாரி ஊழியர்களுக்காகக்  
களத்தில் பிரித்துக்கொடுக்கும் பங்கு
- மேல்சாந்தி : கோயிலின் தலைமைப் பூஜகர்
- மேல்வாரம் : நிலத்தின் விளைவில் சொந்தக்காரனுக்கு உரிய பங்கு
- மேல்வெட்டப்பேறு : பல கிராமங்கள் கொண்டதான நாட்டின் பெரும்  
பகுதிக்கு வேண்டிய பொது வேலைகளின் செலவுக்காக விடப்பெற்ற  
மானிய நிலம் அல்லது கிராமம்
- மேலடி : தானியமாகச் செலுத்தும் இறை
- மேலெழுத்து : தலைமை ராயச அதிகாரி; கீழ் அதிகாரியின் உத்தரவை  
அங்கீகரித்து மேல் அதிகாரி இடும் கையெழுத்து; தலைமைக்  
கணக்கர்; தணிக்கையிடும் அதிகாரி
- மேலோடி : மேல் வாரம்
- மேற்கோயில் : ஊருக்கு மேற்கே அமைந்திருக்கும் கோயில் ஆன  
விஷ்ணு கோயில்
- மேற்பாடிகாவல் : பாடிகாவலுக்கு மேற்பட்டதான நாடு காவல்;  
பாடிகாவலின் தலைமை அதிகாரி
- மேற்பாதி : மேல்வாரம்
- மேனடைநீர் : அதிகப்படியாக உள்ள நீர்
- மேனிப்போன் : ஆள் வரி போலும்
- மேனீர் : மழைத் தண்ணீர்
- மைச்சுனன் : மைத்துனன் என்பதன் வேறு வடிவம்
- மோக்கிழம் : மோட்சம்
- மோர்வியம் : முகவினை
- மோனப்பாட்டம் : முன்னாளில் வழங்கி வந்த வரி வகை; எது என்ற  
விவரம் தெரியவில்லை
- மோக்கிச்சு : பழைய நாளிலே கொங்கு நாட்டில் வழங்கிய நாணயம்;  
யகூயியின் உருவம் கொண்டதுபோலும்; பூரீயக்கி பழஞ்சலாகை  
யச்சு என்பது போன்ற பலவிதமான பெயர்களில் குறிப்பிடப்படும்

யக்கிப்பட்டி : யக்ஷி தேவதையின் வழிபாட்டுக்காக இறையிலிபாக  
அளிக்கப்பட்ட நிலம்; பள்ளிச்சந்தவகை  
யந்திரம் : அணைகட்டி நீரைத் திருப்புவது போன்றவற்றுக்கு அமைக்  
கும் சாதனம்

யாகசாலை, யாகமண்டபம் : கோயிலில் வேள்விநடத்தும் மண்டபம்  
யாத்திராதானம் : அரசன் போர்மீது செல்வதற்குமுன் வெற்றி கிட்ட  
வேண்டி அளிக்கும் தானம்  
யாதவராயன்பணம் : முன்னாளில் வழங்கிவந்த நாணயம்; யாதவராய  
வமிசத்தார் அச்சிட்டது  
யாழ்வல்லான் : யாழ் என்னும் இசைக் கருவியில் வல்லவனுக்கு முன்  
னாளில் அரசர் வழங்கிய பட்டப்பெயர்  
யாளிக்கால் : யாளி உருவத்தில் அமைத்த பாத்திரத்தின் பாதம்  
யானைச்சாலை : யானைகட்டும் இடம்; அதன் பராமரிப்புக்கான செல  
வுக்கு இறுக்கும் வரி; ஆனைச்சாலை பார்க்க

ரங்கமண்டபம் : கோயிலின் உள் மண்டபம்  
ரத்தக்காணிக்கை : இரத்தக்காணிக்கை பார்க்க  
ரத்தமானியம் : இரத்தமானியம் பார்க்க  
ரத்காரர் : சிற்பாசாரிகள்; அவர்களுடைய சபையும் ஆகும்  
ரக்ஷகர் : பாதுகாவலர்; ஊர்க்காவலர்  
ரக்ஷாபோகம் : விளைவிவிருந்து ஊர்க்காவலுக்காகக் கொடுக்கவேண்டிய  
பங்கு

ராகுத்தராயன் : குதிரை வீரர்களின் தலைவன்  
ராசகர உபாதி : அரண்மனைக்கு இறுக்க வேண்டியவை  
ராசகரம், ராஜகரம் : இராசகரம் பார்க்க  
ராசகரவிறை முறைமை : அரசாங்கத்துக்குச் செலுத்தவேண்டிய பல  
வகை வரிகள்  
ராசகாரியபண்டாரம் : ராஜ்ய நிர்வாகச் செலவுக்கான கஜானா; ராஜ்ய  
நிர்வாகத்துக்கான சபையாகவும் கொள்வர்  
ராசகாரியம் : அரசாங்க ஊழியம்  
ராசகுலம் காணிப்பற்று : ராஜகுடும்பத்தைச் சேர்ந்தோர் அனுபவாகத்  
தில் உள்ள நிலம் அல்லது கிராமம் (தேவதானம், பிரமதேயம்,  
பள்ளிச்சந்தம் ஆகியவற்றுடன் சேர்ந்து காணப்படுவது)  
ராசிப்பேன் : கலப்பற்ற அத்தமான தங்கம்  
ராமாநுஜ கூடம் : வைஷ்ணவ யாத்திரிகர்கள் தங்கும் சாவடி

ராயசம் : எழுதுவது ; ஆணைப்பத்திரம் ; இராயச வேலைபைக்  
 கவனிக்கும் ஒலை நாயகம் போன்ற அரசாங்க அதிகாரி  
 ராயசஸ்வாமி : இராயசர்களின் தலைவன்  
 ராயசவர்த்தனை : இராயச அதிகாரிக்கான வர்த்தனை  
 ராஜ்யம் : மண்டலம்போன்ற நிலப்பகுதி  
 ராஜத்ரோஹம் : அரசாங்கத்துக்கு விரோதமாக நடக்கும் குற்றம்  
 ராஜபண்டாரம் : அரசாங்கத்தின் கஜானை  
 ராஜவேச்யபுஜங்கர் : எதிரிகளின் நாட்டைக் கைப்பற்றிய அரசன்  
 கொண்ட விருது  
 ராஜன்யர் : அரசாங்க அதிகாரிகள்  
 ராஜஸ்வம் : அரசனுக்கு உரியது  
 ராஜாவர்த்தம் : ஒருவகை ரத்தினம்

ரிஷபத்தளியிலார் : சிவன் கோயில் தேவாடியாருள் ஒரு பிரிவினர்  
 ரிஷிசமுதாய(த்தார்) : சமணர்களிலே துறவிகளாக உள்ளோர்

ருத்திரகணம் : உருத்திரகணம் பார்க்க  
 ருத்திரகணிகை : சிவன்கோயில் தேவாடியார் ; உருத்திர கணிகை  
 பார்க்க  
 ருத்திரமாகேச்வரர் : ருத்திரர் மாஹேச்வரர் என்று குறிக்கப் பெறும்  
 இருவகைச் சிவனடியார்கள் ; சிவன் கோயில் நிர்வாகத்தைக் கண்  
 காணிக்கும் குழுவினர்  
 ருத்திரர் : உருத்திரர் பார்க்க

ரேகை : முன்னாளில் வழக்கில் இருந்த பொன் நாணயம்  
 ரேகைப்பொன் : சுத்தமான தங்கம்

லட்சணம் : பத்திரம்

லாஞ்சினைப்பேறு : இலாஞ்சனைப்பேறு பார்க்க

வக்ஷாணிக்கு மண்டபம் : சாஸ்திரம் புராணம் முதலியவை விரித்து  
 உரைக்கப்படும் மண்டபம்  
 வக்காணித்தல் : சாஸ்திரம், புராணம் முதலியவற்றை விரித்து உரைத்  
 தல்  
 வகை செய்கிறவர், வகை செய்வார் : நிலத்தின் தரம் அளவு முதலி  
 யவற்றை ஒழுங்கு செய்து தீர்வை விதிக்கும் அதிகாரி

- வகைசெய்தல் : நிலத்தின் தரத்தை நிர்ணயித்து வரி விதித்தல்
- வகைந்த காசு : நிலத்தை வகைசெய்வதற்கான தீர்வை ; நிலத்தைப் பிரித்து அளவிடுவதற்கான வரி ; வழக்கு முடிப்பதற்கான கட்டணமும் ஆகும்
- வகைப் பேறு : நிலம்வகை செய்வார்க்குக் கொடுக்கவேண்டியவை
- வகையறுத்தல் : வழக்குத் தீர்த்தல் ; நிலத்தின் தரத்தை அறுதியிடுதல்
- வங்கிசம், வங்கிஷம் : வம்சம் ; வங்சம் எனவும் காணப்பெறும்
- வச்சிரப்படை : கோபுரத்தின் அடிநிலைக் கட்டடம்
- வசந்த மண்டபம் : தோட்டத்தின் நடுவில் உள்ள மண்டபம் ; வஸந்த உற்சவம் கொண்டாடும் இடம்
- வட்டம், வட்டன் : தோறும் (ஆட்டை வட்டம் : ஆண்டுதோறும்)
- வட்டம் : முத்துவகை, உருண்டையாக உள்ளது ; ஓர் ஆபரணம்
- வட்டம் : நாணயமாற்றம் செய்வதற்குக் கூலி ; தரகு தள்ளுபடி
- வட்ட வியவஹாரி : நானுதேசிக் குழுவின் முக்கியஸ்தன் ; பணத்தை வட்டிக்குக் கொடுப்பவன் ; ரொக்க லேவாதேவிக்காரன் ; நாணய செட்டி
- வட்டிநாழி : முன்னாளில் வழங்கிவந்த வரிவகை ; நாழிகை வட்டில் எனக் கொள்ளமுடியுமா ? நிலத்துக்கு நீர் பாய்வதற்கான நாழிகையைக் கணக்கிட்டு அதன்படி செய்வதற்குக் கொடுக்கும் வரியாக இருக்கலாம்
- வடக்குவாசல் செல்வி : ஊரின் வடபுறத்து எல்லைத் தெய்வமான காளி
- வடம் : மாலையின் சரம் ; மணிவடம் ; தேர் இழுக்கும் கயிறு
- வடுகவழி, வடுகப்பெருவழி : ஆந்திர தேசம் ; ஆந்திராபதம் என்பதன் மொழி பெயர்ப்பு ; வடக்கு நோக்கிச் செல்லும் சாலையாகக் கொள்வர் (தக்ஷிணாபதம், உத்தராபதம் என்பவை நோக்குக)
- வடுகவாளி : காதில் அணியும் ஆபரணம்
- வண்ணாரப்பாறை, வண்ணன்வரி : துணி வெளுப்போர் இறுக்கும் வரி
- வண்ணைக்கும்பிட்டார் : சேரமான் பெருமாள் நாயனார்
- வணிதம் : கூற்றம், நாடுபோன்ற ராஜ்யப் பிரிவு (விஜய நகர ஆட்சியில் வழக்கில் இருந்தது) ; வடிகம் எனவும் காணப்பெறும்
- வத்தன், வத்தநாயன் : வத் தாஜன்
- வத்தினை : வர்த்தனையின் வேறு வடிவம்

வதி : வழி, வீதி

வயக்கால் : ஆற்றுக்காலிலிருந்து வயலுக்கு நீர் பாயும் சிறு கால்

வயிராவி, வயிராகி : சிவன்கோயிலில் ஊழியம் புரியும் துறவி (காலக் கிரமத்தில் சிவன்கோயில் காவலாளனைக் குறிப்பது)

வயித்தியலிருத்தி : வைத்தியனுக்கு விட்ட மானிய நிலம்

வர்த்தனை : குறிப்பிட்ட அதிகாரிகள் ஊழியர் முதலியோருக்கு மானியமாக அளிக்கப் பெறுவது

வரகிராமம் : கோயில், மடம், பிராமணர் முதலியோருக்குத் தர்மத்துக் காக அளிக்கப்பெற்ற கிராமம்

வரக்கூலி : நெல் முதலியவற்றை எடுத்து வருவதற்கான வண்டிச் சத்தம், சமைகூலி

வரத்து : எல்லை

வரத்து : எழுதிவந்த ஒலை ; உத்தரவு

வரத்து : வருவாய்; வரிமுதலியவை தண்டல்

வரணம் : சபையின் உறுப்பினராக நியமனம் ; தேர்ந்தெடுத்தல்

வரவை : வருல் செய்தது ; வரி ; வருவாய்

வராகப்பணம் : வராக உருவம் பொறித்த பணம்

வராஹன்புள்ளிக்குளிகை : முன்னாளில் வழங்கிய நாணயம்

வராகமுத்திரை : அரசாங்கச் சின்னமான வராஹம் (பன்றி) உருவம் பொறித்த எல்லைக்கல்

வராகன் : முன்னாளில் வழங்கிய பொன் நாணயம் ; வராஹ உருவம் பொறித்தது

வராச்சின்னம் : ஒரு பின்ன அளவு

வரி : தீர்வை ; அரசிறை ; தீர்வைக் கணக்கு ; தீர்வை நிர்ணயித்து எழுதிவரும் ஒலை

வரிக்கற்றை : கூரை வேய்வதற்கு உதவும் புல், வைக்கோல் கற்றை

வரிக்கூறுசேய்வார், வரிக்குக்கூறுசேய்வார் : தீர்வையை நிர்ணயித்து விதிக்கும் அதிகாரிகள்

வரிக்கோலம் : கோயிலில் ஆடும் ஒருவகைக் கூத்து (மகளிர் மார்பில் சந்தனத்தால் இடும் கோலமான தொய்யிலின் பகுதி ; மகளிரை அழகுபடுத்துவதை நடனமாடி எடுத்துக் காட்டுவதாக இருக்கலாம்)

வரிசை : ராஜசபை, கோயில் முதலிய இடங்களில் அளிக்கப்பெறும் சிறப்பு ; மரியாதை

வரிசை : நிலத்தைப் பயிரிடும் குடிகளுக்கு உரிய பங்கு

வரிசை : கிராம சபை முதலியவற்றின் கட்டணம் ; தீர்வைக் கணக்கு

வரிசையிலிட்டபடி : வரிக்கணக்கில் கண்டபடி ; தீர்வைத் தரத்தின் பிரகாரம்

வரிசோறு : சோறிடும் கடமை

வரிப்பாடு : வரிவிதித்தல் ; தீர்வைகள்

வரிப்புள்ளி : வரிக்கணக்கு வகை

வரிப்போத்தக நாயகம் : அரசாங்க வரிக்கணக்கை நிர்வகிக்கும் துறை ; அதன் தலைமை அதிகாரி

வரிப்போத்தகம் : அரசிறைக் கணக்கு ; அதை எழுதும் அதிகாரி

வரியிலார் : வரிக் கூறுசெய்வார் பார்க்க

வரியிலிடுதல் : அரசிறைக் கணக்கில் எழுதுதல்

வரியிலீடு : அரசிறைக் கணக்கில் ஏற்றுதல்

வரியோலை : தீர்வைபை நிர்ணயித்து இடும் ஒலை ; செலுத்த வேண்டிய தீர்வைக்கு அனுப்பும் ஒலை ; ஒப்பந்தச் சீட்டு

வருஷகாணிக்கை : ஆண்டுதோறும் செலுத்த வேண்டிய காணிக்கை

வருதினி : சேனை

வரை : முத்துக் குற்றங்களுள் ஒன்று ; கோடு விழுந்தது

வலங்கை : வலங்கைச் சாதியார்

வலங்கை இடங்கை மகன்மை : வலங்கை இடங்கைச் சாதியார் கொடுக்கவேண்டிய தீர்வை ; அவர்களில் படைக்கலம் ஏந்தக்கூடிய ஒவ்வொரு ஆண்மகனும் செலுத்தவேண்டியது போலும்

வலத்துக்கை : வலங்கைச் சாதியார்

வழக்குமுறி : பிராது

வழிக்கண்ணூர் : வழிவந்தோர் ; சந்ததியார்

வழிச்செவ்வை : சாலை ; நன்றாக உள்ள பாதை

வழிநடைக்கிடும் பணம் : சாலை, வழி முதலியவற்றைச் செப்பனிடுவதற்கான வரி

வழிபாட்டுப்புறம் : கோயில் நித்திய பூசை செலவுக்காக விட்ட மானிய நிலம் அல்லது கிராமம்

வழியாயம் : சாலையில் செல்லும் சரக்குகளுக்கு வசூலிக்கும் சுங்கம் ; மார்க்காதாயம் என்பதும் இதுவே

வழியிலார் : சந்ததிகள்

வழியேச்சமறுதல் : வமிசம் அற்றுப்போதல் ; சந்ததி அற்றுப்போதல்

வழுதியச்சுவர்க்கம் : பாண்டிய நாட்டு நாணயத்தால் இறுக்கவேண்டிய வரி வகைகள்

வழுவாத நூழி : சரியான அவை கொண்ட படி  
 வழுவதல் : குறைதல்  
 வள்ளான் வகை : வெள்ளான் வகை பார்க்க  
 வளஞ்சியர் : நானாதேசிக் குழுவின் பகுதியார் ; வியாபாரிகள் ; பனிஜி  
 கர் எனவும் பெறுவர்  
 வளாகம் : இடம் ; பிரதேசம் ; விளாகம் எனவும் எழுதப்பெறும்  
 வளிதம் : வணிதம் பார்க்க  
 வறட்சாவி : மழையில்லாமையால் பயிருக்கு ஏற்பட்ட கேடு  
 வன்பாட்டம் : தீய்வு கரிவு காலத்திலும் குறையாமல் அளக்கவேண்  
 டிய குத்தகை நெல்  
 வன்னியப்பற்று : படைப்பற்று ; படை வீரர் அனுபோகத்தில் உள்ள  
 நிலம்

வாச்சியம் : வாத்தியம் ; இசைக்கருவி  
 வாச்சியமாராயன் : வாத்திய சங்கீதத்தில் வல்லவனுக்கு முன்னுனில்  
 அரசர் வழங்கிய பட்டப்பெயர் ; கோயில் மேளகாரர் தலைவன்  
 வாசல் : அரண்மனை வாசல் ; அதன் பொறுப்பை வகிக்கும் அதிகாரி  
 வாசல் : ராஜ சபை ; அரசன் ஆஸ்தானம்  
 வாசல் கணக்கன், வாசல் கரணிகம் : அரண்மனைக் கணக்கன்  
 வாசல் காணிக்கை : அரண்மனைக்குச் செலுத்தும் காணிக்கை ; வாசல்  
 என்னும் உத்தியோகஸ்தனுக்குச் செலுத்துவதும் ஆகும்  
 வாசல்காரியம், வாசல் நீர்வாழும் : வாசல் என்னும் அரண்மனை உத்தி  
 யோகம் ; அதை வகிப்பவன் வாசல் முதலி எனவும் பெறுவன்  
 வாசல் குழிப்பணம் : முன்னுனில் வழங்கிய வரிவகை ; வீட்டு வாசலைக்  
 கொண்டு கணக்கிட்டது போலும்  
 வாசல்திரமம் : வீட்டுவாசல் வரி ; வாசல் பணம் என்பதும் இதுவே  
 போலும்  
 வாசலில்போந்த குடிமை : அரண்மனைக்கு, நிலவரி நீங்கலாக, இறுக்க  
 வேண்டிய இதர வரிகள்  
 வாசல்வினியோகம் : வாசல் என்னும் அதிகாரிக்குக் கொடுக்க  
 வேண்டிய வர்த்தனை ; கட்டணம்  
 வாசி : வீதம் ; நாணயவட்டம் ; தேய்வு காய்ச்சல் முதலியவற்றால்  
 ஏற்படும் குறைவு  
 வாடாக்கடமை : திட்டமான, மாறாத வரி ; நிரந்தரமான வருவாய்  
 வாடாக்கடன் : நிரந்தரமாக உள்ள கடன்

வாடிகா : ஒரு நில அளவு ; வேலிநிலம் போன்றது

வாத்தி : பள்ளிக்கூட வாத்தியார்

வாமனக்கல் : தர்மத்துக்கு அளித்த நிலத்தின் எல்லையைக் குறிக்க  
நடும் எல்லைக்கல்

வாமனமுத்திரை : விஷ்ணுகோயில் நிலத்தின் எல்லையைக் குறிக்க  
இடும் சங்கு சக்கர உருவம் பொறித்த எல்லைக்கல்

வாய்க்கால் பாட்டம் : வாய்க்காலை நல்ல நிலைமையில் வைத்திருப்பதற்காக வெட்டிவேலை முதலியவற்றுக்காக இறுப்பது

வாய்க்கேள்வி, வாய்க்கேள்வியார், வாய்க்கேட்பார் : அரசன் வாய் மொழியாக இடும் உத்தரவைக் கேட்டு அதை உரியவர்களுக்கு எழுத்துமூலம் அனுப்பும் அதிகாரி

வாய்த்தலை : வாய்க்காலின் தலைப்பு மதகு ; தொடங்கும் இடம்

வாய்த்தலைப்படி குலையரையர்கள் : வாய்க்கால் தலைப்பு, மதகு, கரை முதலியவற்றை நிர்வகிக்கும் குழுவைச் சேர்ந்தவர்கள்

வாய்தல் : வாசல்

வாயினம் : வாணிகம் ; வியாபாரம்

வாரககாணம் : விவசாயத்துக்கு முன்பணம் கொடுப்பதற்காகப் பின்னால் வட்டியாகச் சேர்த்து வசூலிப்பது

வாரம் : வேதத்தை ஒதும் வகை

வாரம் : தீர்வை

வாரம் : விளைவில் பங்கு

வாராவைகள் : வசூலாகாதவை என்று தள்ளிப் பின்னால் வசூல் ஆனவை

வாரியப்பேருமக்கள் : கிராம நிர்வாகத்துக்கு அமைக்கப்பட்ட சபையின் சிறுகுழாம் ; அதன் உறுப்பினர்கள்

வாரியம் : கிராமச் சபையின் குழாம் ; அதை நடத்துவோர் வாரியம் செய்வார் எனப்படுவர்

வாரியன் : மேற்பார்வையாளர்

வாலக்காணம் : மனையின் வால்வீச்சுக் கணக்கில் இடும் கட்டணம் ; வாலவரி, வாலமஞ்சாடி என்பனவும் இதுவே போலும்

வாள்பெற்ற கைக்கோளர் : கைக்கோளப் படையின் வாள் வீரர்கள்

வாளகம் : வெட்டிவோர்

வாளகிரி : சக்கரவாளகிரி

வாளால்வழிதிறந்தான்குளிகை : வாளால் வழிதிறந்தான் என்னும் சிறப்புப் பெயர் தாங்கிய முதலாம் ஜடாவர்மன் சுந்தர பாண்டியன் என்பவன் வழங்கிய நாணயம்



வள்ளிலார் : வாள் வீரர்

வான்பயிர் : நன்செய், புன்செய்ப் பயிரில்லாத கொடிக்கால் வாழை  
கரும்பு முதலிய தோட்டப்பயிர்

வானவாரி : மழைத் தண்ணீர்

வாஸ்துகிருத்தியம் : கட்டடவேலை

வாஸ்துபரிவாரம் : மனைக்கொல்லை ; மனைப்படப்பு

விக்கிரமத்தொழில் : போர்த்தொழில் ; பராக்கிரமம்

விக்குப்தி : அரசனிடம் ஒன்றை மரியாதையோடு தெரிவித்தல் ; அரச  
னிடம் விண்ணப்பங்களை எடுத்துரைக்கும் அதிகாரி

விகாரி : விசாரி ; புரோஹிதர்

விச்சாத்தி : வித்யார்த்தி ; மாணவன்

விச்சாதரன், விச்சாதிரன் : வித்தியாதரன்

விசக்காணம் : கிராமவிளையில் வியவன் ஆன கிராமத்தலைவனுக்கு  
உரிய பங்கு

விசம், விசதம் : விகிதம்

விசம் : செலவு

விசிகை : ரவிக்கை, மார்க்கச்சு

விசேஷாயம், விசேஷாதாயம் : அதிகமான இலாபம் ; பிரத்தியேகமான  
வரித் தொகுதி

விஞ்சனம் : வெஞ்சனம் பார்க்க

விட்டவன்விழுக்காடு : கோயிலில் பூசைக்கட்டளை ஏற்படுத்தியவனுக்கு  
நிவேதனப்பொருளில் உரிய பங்கு ; அவன்சார்பாக வேறு ஒரு  
வருக்கோ பலருக்கோ அளிக்கப்பெறுவதையும் குறிக்கும் ; விட்ட  
விழுக்காடு எனவும் பெறும்

விடங்கு : அரைப்பட்டிகை முதலிய ஆபரணங்களின் உறுப்பு

விடுதல் : கொடுத்தல், அளித்தல், தானம் பண்ணுதல்

விடுதீட்டு : தானபத்திரம்

விடுபேறு : பிறர்க்குத் தானமாக விடப்பெற்ற நிலம்

விடேல்விடுகு : பல்லவ அரசன் சிறப்புப் பெயர் ; பல்லவ அரசன்  
ஆணையையும் குறிக்கும்

விடைப்பேர், விடைப்பேறு : கால்நடைச் செல்வம் ; அதற்கான வரி  
யெனவும் கொள்வர் ; அரசன் உத்தரவு பெறுவதற்கு அளிக்கவேண்டி  
யவை

விடைபோர் : கால்நடையைக் கவர்வதற்காக நடத்தும்போர் ; ஆனிரை  
கவர்தல்

விடையதிகாரி(கள்), விடையில் அதிகாரி(கள்) : அரசன் உத்தரவுகளை  
விடுக்கும் அதிகாரிகள்

விண்ணகரம் : விஷ்ணுகிருகம் ; விஷ்ணு ஆலயம்

விண்ணப்பம் : அரசன் முன் பணிந்து கூறும் அறிவிப்பு ; கடவுள்  
முன் பாசரம் ஒதுதல்

வித்தியாஸ்தானம் : வித்தியாசாலை

வித்தியானுபோகம் : பாடசாலைக்காக விட்ட மானியம்

வித்துப்பாடு : ஓரளவு விதை விதைப்பதற்குத் தேவைபான நிலம்

வித்துவசனம், வித்துவஜ்ஜனம் : புலவர் கூட்டம் ; வித்துவான்கள்  
அடங்கிய சபை

விதம் : மாதிரி ; வகை

விதரம் : இரத்தினவகையில் ஒன்று

விப்ரவிநோதி : மாயாஜால வித்தைபுரியும் பிராமண வகுப்பினர்

விப்ரவிநோதிவரி : விப்ரவிநோதிகள் பராமரிப்புக்காக விதிக்கும் வரி

விபூதி, விபூதிகாணிக்கை : சிவன்கோயிலில் சுவாமி தரிசனத்தின்  
போது பத்தர்கள் விபூதிமடலில் இடும் காணிக்கை ; பின்னாலில் இது  
அரசுக்கு உரிய வரியாக மாறியது

விமானம் : கர்ப்பகிருகம் ; கர்ப்பகிருகம் உள்ளிட்ட கோயில்

வியாக்யானவிருத்தி : சாஸ்திரம் புராணம் முதலியவற்றை விரித்து  
உரைப்பார் வாழ்க்கைச் செலவுக்காக விட்ட மானியம்

வியாகரணதான மண்டபம் : திருவொற்றியூர்க் கோயிலில் உள்ளது ;  
வியாகரணத்தைச் சிவபெருமானே உண்டாக்கினார் என்பதற்காக  
அதை விரித்துரைக்கும் சிவன்கோயில் மண்டபம்

வியாபாரிகரத்தார் : வாணிகர் சபை

வியாழம், வியாழவட்டம் : குருவின் சாரத்தைக்கொண்டு கணக்கிடும்  
பன்னிரண்டு வருஷ வட்டம் ; அந்த அந்த இராசியில் குரு இருப்பது  
மேஷவியாழம் என்பதுபோல் குறிக்கப் பெறும்

விரக்தன் : தீவிரமான சைவமதத்தை மேற்கொண்டுள்ள துறவி

விரதம் : சங்கற்பம் ; தீர்மானம்

விரவுநிலம் : கலப்பு நிலம்

விருத்தி : ஜீவனத்துக்காக விடப்பட்ட மானிய நிலம்

விருத்துப்பட்டிகை : விருத்தியாக அளிக்கப்பட்ட நிலமேபோலும் ;  
அவ்விதம் நிலம் அளிக்கப்பெறாத சமயம் அதன் வருவாய்க்குச்  
சமமாக வருவிக்கப்பெறும் கட்டணம்

விருந்தம், விருந்தனை : உறவினர் ; மனைவி

விருந்தாட்டு : சோறிடும் கடமை

வில்பணம் : வில் அம்பு முதலியவற்றுக்காக இறுக்கும் வரி; விற்பனை வரியாகவும் கொள்ளலாம்; விற்பணம் என்றும் எழுதப்பெறும்; வில்வரி என்பதும் இதுவே

வில்லவர் : வில்வீரர்; சேரர்

வில்லாளிகள் : வில் வீரர்கள்

வில்லக்குவான் : தடுப்பவன்; மாற்றுபவன்

வில்லையுதல், விலையுதல் : கிரயம் செய்வதாக விலையையும் பகிரங்கமாகத் தெரிவித்தல்; ஏலம் கூறுதல்

விலைசிராவணை : விலையாவணம் என்பதே

விலைத்தண்டம் : விற்பனையை ஒட்டி இறுக்கப் பெறும் தண்டம்

விலைத்தரவு : கிரய சாசனம்

விலைத்திரவியம் : விலைப் பொருள்

விலைப்பிரமாண இசைவுதீட்டு : விற்பனைக்காக இருதரப்பாரும் ஒப்புக் கொண்டு எழுதிய சீட்டு

விலைப்பிரமாணக்கச்சாத்து : விற்பனைக்கான கிரயசாசனத்தில் பணம் பெற்றுக் கொண்டதாகக் கையெழுத்திடுவது; கிரயசாசனம்

விலைப்பிரமாணம் : விலையாவணம்; கிரயசாசனம்

விலைப்பொருள் : விலையாக நிச்சயித்த கிரயப் பொருள்

விலையாவணக்களரி : கிரயசாசனங்களைப் பதிவுசெய்யும் அரசாங்கக் கச்சேரி

விலையாவணம் : கிரய சாசனம்; விலையோலை என்பதும் இதுவே

விவஸ்தை, வியவஸ்தை : முடிவு; ஒழுங்குமுறை

விவாகப்பணம் : கல்யாணத்துக்காக இறுக்கும் வரி; கண்ணுலக்காணம் பார்க்க

விழாப்புறம் : கோயிலில் திருவிழா நடத்துவதற்காக விட்ட மானிய நிலம்

விழுதல்; கழிதல்

விழு : விஷம்; சித்திரை ஐப்பசி மாதப் பிறப்புகள்

விழுக்காடு : வீதம்; பங்கு

விளக்குக்குடிமக்கள் : கோயில் விளக்கு ஏற்றும் பணியைக் கொண்டு அதற்கான மானியத்தை அனுபவிக்கும் குடிமக்கள்

விளக்குதல் : ஆபரணத்தில் உள்ளது போலப் பொடிவைத்துப் புற்ற வைத்தல்

விளக்குமாடம் : விளக்கு வைக்கும் சுவர் புரை; கோயிலில் விளக்கு ஏற்றும் இடம்

விற்கண்டம் : கட்டடத்தில் வில் போல் வளைவாக உள்ள பாகம்

விற்காயம் : வில்பணம் என்பதன் வேறு பெயரே போலும்

விற்பிடி : கிரய சாசனம்; அதற்கான குறிப்பு

வினாப்போக்குதல் : கேள்வி கேட்டல்

வினியோகம் : உபயோகம்; செலவு; அதற்கான கட்டணம்

விஜயஸ்தம்பம் : வெற்றித் தூண்

விஜயாபிஷேகம் : வெற்றிவீரனாக நடத்தும் மகுடாபிஷேகம்

விஷ்ணுகிருகம் : விஷ்ணு ஆலயம்

விஷயம் : நாட்டின் நிர்வாகப் பகுதி, மண்டலம் போன்றது

விஷ்விருத்தி : விஷ்வைத்தியனுக்காக விட்ட மானியநிலம்; விஷ்ணுர போகம் என்பதும் இதுவே

வீசக்கணக்கு : கணக்கு வகை; பிஜகணிதம் போலும்

வீட்டுத்தேவை : நாட்டுத் தேவையினின்றும் வேருனது; ஊர்ச்சைபக் குரிய வரிவகை

வீட்டோடும் கூட்டோடும் : வீடுமுழுவதும்; வீட்டாரும் சுற்றத்தாரும்

வீடாயிருத்தல் : தங்கியிருத்தல்

வீணைக்காணி : கோயிலில் பூசைவேளையில் வீணைவாசிக்கும் உரிமை; அதற்கான மானியம்

வீர(க்)கல் : இறந்துபட்ட வீரார்க்கு எழுப்பிய கல்; நடுகல் பார்க்க

வீரக்கோடியார் : நானாதேசிகளில் ஒருவகையார்; படைத்தொழிலில் ஈடுபட்டவர்

வீரகணத்தார் : வீரர் சமூகம்; ஜைனரில் ஒரு பிரிவையும் குறிக்கும்

வீரசம்பன்துளிகை : சம்புவராயர் அச்சிட்டு வழங்கிய நாணயம்

வீர சாசனம் : வீரார்க்கு அளிக்கும் நிலமானியம்

வீரசேஷை : வீரக்கல்லுக்காக இறுக்கும் வரி போலும்; இறந்த வீரரின் வமிசத்தார் வாழ்க்கைக்கு விட்ட மானியம்

வீரணுக்கன் : அரசனுக்குப் பக்கத்தில் இருந்து தொண்டு செய்யும் வீரன்

வீரபஞ்சரன் காசு : முன்னாளில் வழங்கிய நாணய வகை

வீரபட்டணம் : நானாதேசிகளில் ஒரு பிரிவினர் வாழும் நகரம்

வீரபட்டம் : வெற்றிக்கு அறிகுறியாக நெற்றியில் அணியும் பொன் தகடு

வீரபண்ணிகர் : வீரவளஞ்சியர் பார்க்க

வீரபாஞ்சாலர் : பதினெட்டுவகைத் தொழிலாளர்; அவர்களுடைய மகாசபை

வீரபோகம் : வீரர்களுடைய அனுபோகத்துக்கு விட்ட மானியம்

வீரமலை : ஒருவனுடைய வெற்றியைப் புகழ்ந்து பாடும் பாமாலை; அவ்வகைப் பாடல்கள் வெண்பாவாக அமைந்தால் வீரவேண்பா மலை எனப்பெறும்

வீரமுடி : வீரனாக அபிஷேகம் செய்யும்போது தறிக்கும் கிரீடம்

வீரவளஞ்சியர் : துணிவுடன் வாணிகம் நடத்தும் வளஞ்சியர்

வீராபிஷேகம் : வெற்றியின் முடிவில் வீரனாக நடக்கும் மகுடாபிஷேகம்

வேச்சமுது : சமைத்த உணவு

வேஞ்சனபண்டாரம், வேஞ்சனம் : சமைத்த கறியுணவு; கறிக்கு உதவும் பண்டம்

வேட்டாள் : வெட்டியே போலும்

வேட்டி : வழி, பாதை

வேட்டி : ஊரிலே பொதுக் காரியங்களுக்கு, பொது மராமத்து வேலைகளுக்குக் கூலி இல்லாமல் செய்யும் ஊழியம்; அதுபற்றி ஊர்ச்சபைக்கு இறுக்கும் கடமையும் ஆகும்

வேட்டிக்காசு : வேதனை பார்க்க; வேட்டிப்பாட்டம் என்பதும் இதுவே போலும்

வேட்டிச்சோறு : கிராமத்தின் வெட்டிவேலை செய்பவர்களுக்குச் சோறிடும் கடமை

வேட்டித்தனியாள் : வெட்டிவேலை மேற்பார்வை இடுபவன்போலும்

வேட்டிநிலை : வாய்க்கால் வெட்டு, வழியைச் செப்பணிடுதல் போன்ற கிராமப் பொது வேலைகளுக்குக் கூலியில்லாமல் செய்யும் வேலை

வேட்டிப்புடவை : வெட்டிக்கு ஆண்டுதோறும் அளிக்கும் ஆடை

வேட்டிப்பேறு : வெட்டிவேலை செய்பவருக்கு உரிய பேறு

வேட்டியாள் : வெட்டி பார்க்க

வேட்டிமுட்டாவாள், வேட்டிமுட்டையாள் : கிராமத்தின் பொது வேலைக்கு அது முடிவடையும் வரையில் இடையறாமல் (முட்டாமல்) வேலை செய்வதற்கு அனுப்பப் பெறும் ஆள்

வேட்டிவரி : வெட்டிக்காசு பார்க்க

வேட்டிவேதனை, வேட்டிவேதினை : வேதனை புரர்க்கு

வேண்ணெய்க்கூத்தன் : கிருஷ்ணபகவான்

வேள்ளாட்டி : பணிப்பெண்; வேலைக்காரி (பின்னாலில் ஆசைக் கிழத்தி  
யான வைப்பாட்டியையும் குறிக்கும்)

வேள்ளான் : உழுது பயிரிடுவோன்

வேள்ளான் இறை : பயிர் இடுவதற்கான வரி

வேள்ளான்வகை : வேளாண் மக்களுக்கு உரிய நிலம், கிராமம்  
முதலியன; ரயத்துவாரி வகையைச் சேர்ந்தது

வேள்ளான்வெட்டி : வயலில் குழி வெட்டுவது போன்ற வெட்டி  
வேலை

வேள்ளிலைப்பற்று : வெற்றிலைக் கட்டு

வேள்ளிலையமுது, வெற்றிலையமுது : கடவுளுக்குப் படைக்கும் தாம்  
பூலம்

வேளிச்சப்பாடு : ஆவேசம் வந்து குறி சொல்லுவது

வேளுங்கு : ஒருவகை மரம்

வேள்ளாவாசி : நெடுவட்டி, சாதாரண வட்டி

வேள்ளாவாரி : (நிலம் வெள்ளாவாரி எனவும் காணப்படும்) வெள்ளம்  
போன்ற காலங்களில் நிலத்தில் வண்டல் படிந்து மேட்டிட்டுப்  
போவதை பின்னால் வாரிச் சமன் செய்வது; அதற்கான வரியையும்  
குறிக்கும்

வேன்றாமங்கோடுத்தல் : போரில் தோற்றவனுக்கு வெற்றியடைந்த  
அரசன் பெயரைச் சூட்டுதல்

வேஜ்ஜம் : மாணிக்கக் குற்றத்துள் ஒன்று, துவாரமுள்ளது போலும்

வேகாரி : வெட்டி என்பதனுடன் சேர்ந்தே காணப்படும்; கட்டாய  
மாகச் செய்யவேண்டிய ஊழியம்; வேசாரி, வேசாலி என்ற உருவங்  
களிலும் காணப்படும்

வேட்கோன் : குயவன்

வேண்டுகோள் : அரசனுக்கோ அரசாங்க அதிகாரிகளுக்கோ அனுப்பும்  
விண்ணப்பம்; மனு; அதற்காகச் செலுத்தும் வரி வேண்டுகோள்  
வரி எனவும் பெறும்

வேண்டட்டிகள் : வேண்டு என்னும் பகுதியின் அரசன்

வேதலிருத்தி : வேதம் ஒதுவதற்கான செலவுக்கு விட்ட மானிய நிலம்

வேதனம், வேதனை, வேதினை : (பெரும்பாலும் வெட்டி என்பதனுடன்  
சேர்ந்தே காணப்படும்) கூலி, சம்பளம்

வேதினை : வேதினை என்றே வாசிக்க வேண்டும் போலும்

**வேய்நெல்(ஹ) :** மூங்கில் அரிசி; அதைச் சேகரித்தல்; அரசருக்கு அதைக் காணிக்கையாக அளித்தல்

**வேயதிகாணம் :** கூரை வேய்ந்த வீட்டிற்கான வரி போலும்; மாடி வீட்டிற்கான வரி என்றும் கொள்ளலாம்

**வேர்வாளி :** முன்னுளில் வழங்கிவந்த காதணி வகை

**வேலாதுர்க்கபாலர் :** கடல் துறைமுக அதிகாரி

**வேலிக்காசு :** முன்னுளில் வழங்கிவந்த வரிவகை; வேலி நிலத்துக்கு எனக் கொடுக்கவேண்டியது போலும்; வேலிப்பயறு என்பதும் இதுபற்றியதே

**வேலிக்குழிப்பணம் :** வேலிக் காசே போலும்

**வேலிநாயகம் :** கிராமத்திலே பயிரிடும் நிலங்களைக் கண்காணிக்கும் அதிகாரி

**வேள்புலம் :** சாளுக்கிய தேசம்

**வேளம் :** அரண்மனையின் அந்தப்புரம்; பட்டமகிஷிகள் அல்லாத அரசனுடைய மற்றத் தேவிகள் இருக்குமிடம்; அந்தப்புர ஊழியம்; அவ்விதம் பணிபுரிவோர்

**வேளார்படை :** வேளாருடைய படை; வேளைக்காரரோடு ஏதோ ஒரு வகையில் தொடர்பு உள்ளது போலும்

**வேளான்(ர்) :** முன்னுளிலே அரசியல் அதிகாரிகளுக்குச் சோழமன்னர்கள் வழங்கிய சிறப்புப் பெயர்; அவர்கள் ஆதியில் வேளத்தைச் சேர்ந்தவர்கள் போலும்; பெரும்பாலும் அவர்கள் திறமைவாய்ந்த அதிகாரிகளாகவே காணப்படுவர்

**வேளைக்காரர் :** அரசருக்கு வேளைப்படி உரிய பணியைச் செய்வதாக ஏற்றுக்கொண்டு அவ்விதம் செய்ய இயலாதபோது உயிரை மாய்த்துக் கொள்வதாக விரதம் பூண்டவர்; வீரமும் விசுவாசமும் நிறைந்தபடை

**வைகல் :** தங்குதல்

**வைச்சமுது :** வெச்சமுது பார்க்க

**வைச்சமுது மண்டபம் :** கோயில் மடைப்பள்ளி

**வைசியவாணிய நகரத்தார் :** வணிகர்களுள் ஒரு பிரிவினரின் சபை

**வைத்தியபாகம், வைத்தியபோகம் :** ஊரிலே நிரந்தரமாகத் தங்கி வைத்தியம் செய்பவருக்காக ஒதுக்கப்பட்ட மானிய நிலம்; வைத்திய விருத்தி எனவும் பெறும்

**வைத்தியபுரந்தரன் :** வைத்தியம் வல்லானுக்கு முன்னுளில் அரசர் வழங்கிய பட்டப்பெயர்

வைப்பு : வேம்பு

வையகத்தார்கல் : நிர்ணய எடை உள்ளதும் ஊர்ச்சபையின் பராமரிப்பில் இருப்பதுமான எடைக்கல்

ஐகதி, ஐகதிப்படை : கோயில் கருங்கல் கட்டடத்தில் அஸ்திவாரத்தின் மேற்பகுதி

ஐங்கமன் : வீரசைவரிடையே ஆசாரியப் பதவி வகிப்பவர்

ஐயபத்திரம் : விவாதத்தில் வெற்றியைக் குறிக்கும் பத்திரம்; விவாதத்தீர்ப்பு; வழக்கின் முடிவு; ஐயரேகைப்பத்திரம் எனவும் பெறும்

ஐயபாலர் : வாணிகருள் ஒருவகையினர்

ஐயஸ்தம்பம் : வெற்றித்தூண்

ஐலபலித்திரம் : அபிஷேக காலத்தில் விக்கிரகத்துக்கு அணியும் ஆடை

ஐலயந்திரம் : யந்திரம் பார்க்க

ஐன்மக்காணி : பிறப்புரிமை; ஜன்மபூமி பார்க்க

ஐன்மபூமி : தானம் அளிக்கப் பெற்ற நிலம்; பெரும்பாலும் ஜீவதசை உள்ளவனாயில் அனுபவிப்பதற்காக அளிக்கப் பெறுவது

ஐனப்பிரதானி : நாட்டை ஆளும் மந்திரி

ஐந்தக்குடி : தங்கள் வாழ்நாள் முழுவதும் கோயில்போன்ற இடத்தில் ஊழியம் செய்வதாக ஏற்றுக்கொண்ட குடிமக்கள்

ஐாதகதக்ஷிணை : கிருஷ்ணன் பிறந்த நாளில் வித்துவான்களுக்குத் தக்ஷிணையாக வழங்கும் சம்மானம்

ஐானி : சானி என்பதன் வேறு வடிவம்

ஐீஷ்ணு : விஷ்ணு

ஐீயங்கார், ஐீயர் : வைஷ்ணவத் துறவி; பெரும்பாலும் கோயில் நிர்வாகத்தை மேற்கொண்டிருப்பவர்

ஐீவனம் : வாழ்க்கை நடத்துவதற்குத் தேவையானது; ஜீவனோபாயம்; அதற்காக அளித்த நிலம்; ஜீவனசேஷம் எனவும் பெறும்

ஐீவிதக்காரர் : ஜீவிதப் பற்று நிலத்தை அனுபவிப்பவர்

ஐீவிதம் : சில குறிப்பிட்ட ஊழியங்களுக்குச் சம்பளத்துக்குப் பதில் அனுபோக பாத்தியதை மட்டும் உள்ளதாக அளிக்கப்பெற்ற நிலம்; ஜீவியம் எனவும் பெறும்

ஐீவிதப்பற்று : ஜீவிதமாக அடைந்து அனுபவிக்கப் பெறும் நிலம்

ஐோடி : குறைந்த விகிதத் தீர்வையில் அளிக்கப்பட்ட மானிய நிலம்

ஐோனகன் : முகம்மதியன்



ஸ்ரமணன் : ஜைன சந்நியாசி; பௌத்த பிக்ஷு

ஸ்ரீகாரியக் கண்காணி : சீகாரியக் கண்காணி பார்க்க

ஸ்ரீகாரியம் : சீகாரியம் பார்க்க

ஸ்ரீகோயில் : கர்ப்பகிருகம்; கோயிலைப் பக்தியுடன் தெரிவிப்பதும் ஆகும்

ஸ்ரீசந்தம் : நகைவகை

ஸ்ரீபண்டாரம் : சீபண்டாரம் பார்க்க

ஸ்ரீபண்டாரி : கோயில் பொக்கிஷத்தை நிர்வகிக்கும் அதிகாரி

ஸ்ரீபலிப்பட்டி : கோயிலில் பலிபூஜை நடத்துவதற்காகவிட்ட மானிய நிலம் அல்லது கிராமம்

ஸ்ரீபாதங்கள் : துறவிகளைக் குறிக்கும் மரிபாதைச்சொல்

ஸ்ரீபாதந்தாங்கி : சீபாதந்தாங்கி பார்க்க

ஸ்ரீபீடம் : கோயில் விக்கிரகங்களின் பீடம்

ஸ்ரீமாஹேச்வரர் : சிவனடியார்; கோயில் நிர்வாகத்தில் பங்கு உள்ள குழுவினர்

ஸ்ரீயக்கி பழஞ்சலாகை யச்சு : சலாகை பார்க்க

ஸ்ரீயாஞ்ஜை : அரசன் ஆணை

ஸ்ரீருத்திரர் : சீருத்திரர் பார்க்க

ஸ்ரீவிமானம் : கர்ப்பகிருகம்; விமானம் பார்க்க

ஸ்ருதிமான் : கேள்வி வல்லார்; சமூகத் தலைவர்

ஷட்காலம் : விடியல், காலை, உச்சி, சந்தி, ராத்திரி, அர்த்த சாமம் ஆகிய ஆறு காலங்களில் நடக்கும் கோயில் பூஜை

ஷஹர் : (பாரசீகச் சொல்) நகரம்

ஸ்கந்தாவாரம் : விஜயஸ்கந்தாவாரம் எனவும் படும்; வெற்றியோடு அரசன் பாடி இறங்கியிருக்கும் இடம்

ஸ்தலக்காவல் : தலக்காவல் பார்க்க

ஸ்தானீகன் : தானிகர் பார்க்க

ஸ்தூபிக்குடம் : விமானத்தின் உச்சியில் வைக்கும் கலசம்

ஸ்நபனம் : திருமஞ்சனம்; அபிஷேகம்; நமன மண்டபம் பார்க்க

ஸ்வர்ணதாயம் : சுவர்ணதாயம் பார்க்க

ஸ்வஸ்திஸ்ரீ : சாசனத் துவக்கத்தில் உள்ள மங்கலச் சொல்

ஸ்வாமிவாரம் : சுவாமிவாரம் பார்க்க

ஸுததம் : எப்போதும்

ஸந்ததி ப்ரவேசம் : சந்ததிப் ப்ரவேசம் பார்க்க

ஸந்தியா தீபம் : சந்தியாதீபம் பார்க்க

ஸமஸ்த ப்ராபதி : எல்லா வருவாய்களும்

ஸமிஞ்ஞை : (அடையாளம்) கையெழுத்து

ஸமுதாயம் : கோயில் காரியத்தை நிர்வகிக்கும் சபை; சமுதாயம் பார்க்க

ஸமுதாயத் தானம் : கோயில் காரியத்தை நிர்வகிக்கும் சபையின் உறுப்பினர் பதவி

ஸர்வமான்யம் : சர்வமானியம் பார்க்க

ஸர்வஸ்வம் : எல்லாப் பொருள்களும்

ஸர்வஸ்வஹரணம் : சொத்து முழுவதையும் பறிமுதல் செய்தல்

ஸவரண விருத்தி : பத்திரம் எழுதும் தொழில்

ஸாதனம் : சாசனம்; ஆதாரம்

ஸாமந்தன் : சாமந்தர் பார்க்க

ஸித்தாந்தம் : (முடிந்த முடிவு) சைவ மதம்; ஜைன மதத்தையும் குறிக்கும்

ஸேனாபதி : சேனாபதியாழ்வார் பார்க்க

ஸேனாபதிப் பெருவிலை : சேனாபதிப் பெருவிலை பார்க்க

ஸோபானம் : படி : கோயில் கட்டடத்தின் அடிப்பாகம்

ஹரிதினம் : சனிக்கிழமை; ஏகாதசியையும் குறிக்கும்

ஹவீர்பலி : சீபலி பார்க்க

ஹளஹளம் : மாணிக்க வகை

ஹுதஞ் செய்தல் : ஆஹுதி செய்தல்; ஹோமம் செய்தல்

ஹேத்திரபாலர் : கிராமதேவதை; ஊரைக் காக்கும் தெய்வம்

### பித்குறிப்பு:

எச்சோறு : சோறு இடும் கடமையைக் குறிப்பதாகக் கல் வெட்டுக் களிலே புள்ளிச்சோறு, திங்கட்சோறு, வெட்டிச்சோறு, வரிச்சோறு என்பவைபோல் பலவகைச் சொற்கள் காணப்படுகின்றன. ஆகவே இச் சொல் 'எவ்வகையான சோறும்' என்றே பொருள்படுமா வென்று எண்ணத் தோன்றுகிறது.

# THE TAMIL PALAEOGRAPHY

## I. INTRODUCTORY

There are many languages in our country and each language has its own script. In South India alone, we have four languages, viz., Tamil, Telugu, Malayālam and Kannaḍa with their respective scripts. Besides, we have the Grantha script, a variety of Tamil, used in the Tamil-nāḍu for writing Sanskrit. In addition, to these there is also another language, Tuḷu, with no script of its own, but using the Kannaḍa script.<sup>1</sup> All these scripts attained their present shape and form only some three centuries ago, after the introduction of printing. The present forms of these five scripts are given in the table below.

Roman	Tamiḷ	Grantha	Malayālam	Telugu	Kannaḍa
a	அ	𑌀	അ	అ	ಅ
ā	ஆ	𑌁	ആ	ఆ	ಆ
i	இ	𑌂	ഇ	ఇ	ಇ
ī	ஈ	𑌃	ഈ	ఈ	ಈ
u	உ	𑌄	ഉ	ఉ	ಉ
ū	ஊ	𑌅	ഊ	ఊ	ಊ
ṛ	...	𑌆	ഠ	ఋ	ಠ
ṝ	...	𑌇	ഠ	ౠ	ౠ
ḷ	...	𑌈	ഭ	ౡ	ౡ
ē	எ	...	എ	ఎ	ఎ
ē	ஏ	𑌉	ഐ	ఏ	ఏ
ai	ஐ	𑌊	ഐ	ఐ	ఐ
o	ஓ	....	ഒ	ఒ	ఒ
ō	ஔ	𑌋	....	౩	౩
au	ஔ	𑌌	ഓ	౪	౪
k	க	...	...	...	...
ḥ	...	...	...	...	...

1. A variety of script derived from the Grantha and known as Tuḷu is sometimes used in the area, to write Sanskrit works; but no book in the Tuḷu language is found in that script.

Roman	Tamil	Grantha	Malayalam	Telugu	Kannada
k	க	क	ക	క	ಕ
kh	...	ख	ഖ	ఖ	ಖ
g	...	ग	ഗ	గ	ಗ
gh	...	घ	ഘ	ఘ	ಘ
n	ந	न	ന	న	ನ
c	ச	च	ച	చ	ಚ
ch	...	छ	ഛ	ఛ	ಛ
j	...	ज	ജ	జ	ಜ
jh	...	झ	ഝ	ఝ	ಝ
ñ	ஞ	ञ	ഞ	ఞ	ಞ
t	த	ट	ത	త	ತ
th	...	ठ	ത	థ	ಥ
d	...	ड	ദ	ద	ದ
dh	...	ढ	ഢ	ధ	ಧ
n	ண	ण	ണ	న	ನ
t	த	त	ത	త	ತ
th	...	थ	ത	థ	ಥ
d	...	द	ദ	ద	ದ
dh	...	ढ	ഢ	ధ	ಧ
n	ந	न	ന	న	ನ
p	ப	प	പ	ప	ಪ
ph	...	फ	ഫ	ఫ	ಫ
b	...	ब	ബ	బ	ಬ
bh	...	भ	ഭ	భ	ಭ
m	ம	म	മ	మ	ಮ
y	ய	य	യ	య	ಯ
r	ர	र	ര	ర	ರ
l	ல	ल	ല	ల	ಲ
v	வ	व	വ	వ	ವ
s	...	स	ശ	స	ಸ
ś	...	श	ശ	ష	ಷ
h	...	ह	ഹ	హ	ಹ
l	ள	ह	ഹ	...	...
l	ழ	...	...	...	...
r	ற	...	...	...	...
ṛ	ன	...	...	...	...

Though apparently each script appears different from the others, all these five have close affinities.

In general appearance, the Grantha and the Tamil scripts appear alike. The characters for *u*, *ū*, *ka*, *ṇa*, *ta*, *na*, *ya* and *va* are common to both of them, while the differences between the characters for *a*, *ā*, *i*, *o*, *au*, *ṭa*, *ra*, *la*, and *ḷa* in both of them are very little.

Between the Grantha and the Malaiyālam scripts, there is no real difference, excepting that the straight lines and angles in the characters of the former are smoothened and written cursively in those of the latter.

The Telugu and the Kannaḍa scripts are practically identical. It is only the *talai-k-kattu* or the top-line that distinguishes one from the other. The *talai-k-kattu* of the Kannaḍa script is a horizontal line with a small hook at the right turning upwards, while that of the Telugu script is an angular stroke with the vertex downwards. If this *talai-k-kattu* is removed, the similarity between the Grantha and the Malaiyālam scripts on one hand and the Telugu and Kannaḍa scripts on the other will become easily apparent.<sup>1</sup>

A closer comparison will reveal that the forms of the letters *i*, *o*, *ya*, *ra*, *la* and *va* are almost the same in all these five scripts.<sup>2</sup> The form of *ai* in both the Telugu and the Kannaḍa scripts closely resembles that of the Tamil script.

It will thus be seen that the similarity between the several scripts now prevalent in Southern India is traceable even in their present form. In the earlier inscriptions, this affinity

---

1 The Tamil form of the vowel letter *a* is similar to that of the Nāgari script (अ) and this will be more visible if the top-line of the Nāgari letter is removed.

2 A word of caution is necessary here. In comparing the letters of one script with those of another, the forms should not be mutilated to the dictates of fancy. If this is carried too far, any script can be derived or made to look similar to any other. (*Proceedings of the Fourth All-India Oriental Conference*, vol. II, p. 626, n. 2)

is much more clear. It may therefore be concluded that one was derived from another or that all of them were derived from a common source and that they developed independently. In fact, a single script which was in use throughout India in those far off days was developed in different parts of India into different kinds of scripts after undergoing various changes.

The early inscriptions of India are found in two scripts, Brāhmī and Kharoṣṭhī. Brāhmī was usually written from left to right,<sup>1</sup> while Kharoṣṭhī was written from right to left. These two scripts differ not only in the directions in which they are written, but also in various other ways, as in their forms, etc. Further Kharoṣṭhī was in use in a portion of North-Western India and that too during the period anterior to the fifth century A.D., after which it disappeared. Brāhmī was in use throughout India including the region, where Kharoṣṭhī was also used simultaneously.<sup>2</sup>

It is this Brāhmī that is the parent of all the present Indian scripts.

Before proceeding to a systematic treatment of the evolution of the script, it is necessary for us to understand the reasons for the various changes in the different stages of the evolution. The quickness of the hand and the aesthetic instinct of the scribe as also the materials on which the records were written are the three forces which largely influenced the evolution.

Inscriptions were, in ancient days, incised on stone and copper. But palm-leaves also were largely used for writing. It is

1: Brāhmī inscriptions written in the reverse direction and also in the "boustrophedon" style, i.e., one line from left to right and the other from right to left have also been discovered though rarely. But the generality of the Brāhmī inscriptions are from left to right.

2 Of the inscriptions found in North-Western India, the area now included in Pakistan, anterior to the fourth century A.D. some are in Brāhmī and some in Kharoṣṭhī.

difficult to write horizontal strokes on these palm-leaves and as such, curves slowly take the place of these straight lines. Similarly it is difficult to incise curves on stone and it is natural for such curves and circles to become angular and straight lines. For example, *ta* was written in Brāhmī in the shape of a semi-circle as in (a) of Fig. 1; later on this semi-circular line became angular with two arms as in (b).




Fig. 1

Persons who write on palm leaves with stilus generally complete each line at one stretch. They would not lift the writing instrument for each letter. Thus, the scribe not inclined to lift his hand every time a letter ends and a fresh one begins, introduces many unwarranted strokes, which by force of sheer




Fig. 2

repetition come in the long run to be regarded as parts of the original letter itself. For instance, *ka* which is written in Brāhmī as in (a) of Fig. 2 will while writing on the palm-leaves be as in (b), the lower end of the vertical stroke being connected with the cross stroke. While writing *ta* and *ka* together, it will become as in (c) where the end of the first letter is connected with the beginning of the second letter by dragging on the instrument on the palm-leaf.

Again, the scribe in his desire to write quickly, slowly introduces some changes in the forms of the letters unconsciously. *Ki*




Fig. 3

was written in Brāhmī as in (a) of Fig. 3. When writing quickly, it became as in (b). In course of time, when the vowel symbol became separated from the consonant, it changed shape as in (c) and later on the symbol was shifted to the right of the letter as in (d).

Thus many are the changes that were made by the scribes without deliberate intention.

Then there is also the aesthetic instinct of the scribes. With a view to make the letters appear more pleasing to look at, the

scribe sometimes takes the trouble and introduces new elements in the forms; angular strokes in the place of curves and *vice versa*. The letter *ba* which was written in Brāhmī as in (a) of Fig. 4 underwent the several changes shown in (b). It will be seen from them that this extra effort involved in so doing was only for the supposed artistic effect.<sup>1</sup>



(a) Fig. 4 (b)

And lastly, there is one more circumstance which necessitated the evolution. We generally write these letters in one stroke from left to right; some of us write this stroke clockwise and some others counter-clockwise. Generally, the Grantha and the Tamil are written clockwise while the Telugu and the Kannaḍa (as well as the Vaṭṭeḷuttu variety of Tamil which is now extinct) counter-clockwise.

It will not be practicable to write straight-line strokes while writing counter-clockwise. That is probably the reason why the scripts written that way are cursive. The Grantha and the Tamil which are generally written clockwise have many straightlines.

The contact of the Tamil people with foreigners was also responsible to a certain extent for the evolution. That this influence cannot be underestimated will be clear from the fact that the numerals previously in use in South India have almost, nay completely, disappeared and the 'Arabic' numerals have come into use.

Now that printing has come to stay, we can confidently say that the scripts have attained the standard forms and that they are not likely to undergo further changes by way of evolution.

1. Mostly, the inscriptions on stone employ these artistic modes of writing. There is an inscription in the Kailāsanātha temple at Kāñchīpuram, which outwardly appears only as a floral design, but which contains concealed in the design letters which make up the inscription.



## II. THE BRAHMI INSCRIPTIONS OF TAMIL-NADU

The epigraphical records of Tamiḷ-nāḍu are generally found written in one or more of the following three scripts, the Grantha, the Tamiḷ and the Vaṭṭeḷuttu. Of these, the last two are used in writing inscriptions in the Tamiḷ language while the first one, the Grantha, is used for writing Sanskrit records and words of Sanskrit origin used in the records of the Tamiḷ language.

In this connection, one point has to be made clear. The term *Tamiḷ script* is used in this work to denote the present Tamil script and the previous forms from which it has been derived. Though the *Vaṭṭeḷuttu script* was used to write records in the Tamiḷ language, it was known separately by that name even in those days and the same appellation has been followed here also.

Inscriptions in the Grantha and the Tamiḷ scripts are found in the Tamiḷ country only from the beginning of the seventh century A.D., while those in the Vaṭṭeḷuttu script are found only from the middle of the eighth century A.D. Earlier than these, we have inscriptions written in the Brāhmī characters of the period of the Mauryan emperor Aśōka. There are also a few records, like the Tirunātharkunru epitaph, (No. 239 of 1904 of the Madras Epigraphical collection) i.e., the *niśīdhikai* of the Jaina monk *āchārya* Chandra-nandi who died fasting for fifty-seven days, etc. falling in the intervening period; but these are not many and are insufficient to fill in the gap.

The inscriptions of Aśōka are the earliest epigraphical records in the whole of India. Brāhmī was fully developed then and even at that time it was divided into two forms, the 'northern' and the 'southern' varieties. Some memorial tablets and coins assignable to the pre-Aśōkan period have also been recovered in Northern India.<sup>1</sup> The writing found on them are in the Brāhmī script. It will thus be seen that the Brāhmī script was in use in our country even earlier than the days of Aśōka.

---

1. The record on relic receptacle in the *stūpa* at Piprahwa on the Nepal frontier (*JRAS*, 1906, 149) and the legend on the Eraṇ coin are assigned to periods anterior to Aśōka, *circa* 450 and 400 B.C. respectively.

The Brāhmī inscriptions of Tamil-nāḍu are mostly found in the districts of Madurai, Rāmanāthapuram, Tirunelvēli and the southern portion of the Tiruchirāpallī district. They are generally of one or two lines found incised on the overhanging boulders, beds or the eaves of the natural caverns known as *Pañcha-pāṇḍavar-paḍukkai* at the hill-tops or slopes of those hills. The characters in which these inscriptions are written, as already stated, are assignable to the period of Aśōka.

It is considered that those caverns and the beds therein were occupied by the Buddhist *bhikkus* or the Jaina *munis* in those days and that the inscriptions found in them record the cutting of the beds and the donation of the same by some pious devotees of those recluses.

These inscriptions have not been satisfactorily read and interpreted. Photographic copies of the ink-impressions of these records were published in the *Annual Reports on South Indian Epigraphy* for the years 1912, 1915 and 1918. It was also mentioned in the report for the year 1918 that Sri Rama Prasad Chanda was then engaged in the study of these records. But nothing further has been heard of. The late Rao Sahib H. Krishna Sastri offered tentative readings of these records in his paper presented to the *First All-India Oriental Conference* held at Poona in the year 1919 and Sri K. V. Subrahmanya Aiyar improved on the same and interpreted them as Tamil inscriptions in the *Third Oriental Conference* held at Madras in 1924. The late Dr. C. Narayana Rao did not agree with the readings of the latter scholar as Tamil and criticised them strongly in his paper presented to the *Tenth Oriental Conference* held at Tirupati.<sup>1</sup>

As all the scripts now prevalent in Tamil-nāḍu have been evolved from Brāhmī and as these inscriptions in the Brāhmī script are the earliest epigraphical records recovered in the Tamil-nāḍu, it is essential that we should study these Brāhmī records and analyse their contents, though they are yet to be satisfactorily

---

1. Dr. T. V. Mahalingam, Professor of Archaeology in the University of Madras is now engaged in a fresh study of these inscriptions.

read and interpreted. The following are the peculiarities of the script used in them.

1. Of the hard consonants, *ka*, *ca*, *ṭa*, *ta* and *pa*, only the first or primary letters as found in the Tamil alphabet, i.e., the *varga-prathamās* of the Sanskrit alphabet, are found.

2. The soft varieties or the third letters of these consonants, i.e., the *varga-tritīyas* of the Sanskrit alphabet, are absent.

3. Of the aspirated varieties, i.e., the second and the fourth letters of these consonants, only the letter *ṭha*, or according to some scholars *dha* also, is found and the others are not met with.

4. *śa* and *ṣa* are also not found. Only *sa* is occasionally met with.

5. Among the vowels, *ai* and *au* are not found; similarly the vowels *ṛ* and *ṝ* of the Sanskrit alphabet, as also the *anusvāra* (*aṁ*) and the *visarga* (*aḥ*) are absent.

6. Sri K. V. Subrahmanya Aiyar says that "in the case of combined consonants the occurrence of short *e* and short *o* deserves special attention, the two being the special characteristics of the Dravidian alphabets." (*Proceedings and Transactions of the Third Oriental Conference*, p. 283). But it has not been possible to make out this difference between the short and long in the vowels *e* and *o* from their photographs published.

7. In addition, some symbols which are not found in the Brāhmī inscriptions of the other parts of India, also occur in these records. These symbols are representations of characters not found in the language in which the Brāhmī inscriptions of the other parts of India have been written.

It is to be noted at the outset that the Brāhmī script of these inscriptions bears close relation to the script of the records found at Bhaṭṭiprōlu in the Krishṇa district of the Āndhra country, which though resembling very much the script of the Aśōkan period, belongs to the 'southern variety' of the Brāhmī, termed as Drāviḍī, and which has been assigned palaeographically to the period earlier than 200 B.C.

But there is one important difference between the Bhaṭṭiprōlu script and that of the others. In all the inscriptions of the north, pure or vowelless consonant is not usually written as a separate character; but as a joint character, *dvandvākṣara*, with the succeeding vowelless consonant. As such, the form of a consonant found separately will always be taken as having inherent the vowel *a* and that additional symbol will be added to it only to denote the long *ā*.




Fig. 5

Thus, in Brāhmī, the symbol of a cross as shown in (a) of Fig. 5 represents the consonant *ka* and only to denote the long vowel *ā*, i.e., *kā*, a short horizontal stroke is added to it as in (b). But in the script found at Bhaṭṭiprōlu, the form as found in (b) represents the consonant *ka* with the inherent short *a*, and another short hanging line to the right of the top-stroke is added to denote *kā*, with the long *ā*, as given in (c). Thus we have to take that in the script of Bhaṭṭiprōlu, the symbol of the consonant found as a separate character without the addition of any other sign as in (a) of Fig. 5 denoted the pure or vowelless consonant.

The *Tolkāppiyam*, the earliest Tamil grammar extant, says that the character of a pure consonant will have a dot added to it (*meyyin-iyarkai pulli-y-oḍu nilaiyal*).<sup>1</sup> This procedure is found adopted in writing Tamil even to this day, even though in epigraphy, this is observed only on very rare occasions, the *pulli* or *virāma* being generally conspicuous by its absence. But this is only a scribal peculiarity.

Thus, if the character of a consonant is written with a dot on it, it will represent a vowelless consonant in the Tamil language :

but in the northern languages it will represent the consonant with the *anusvāra* added to it. Thus the letter in Fig. 6 will have to be read as *k*, a pure consonant even without the inherent *a*, in Tamil while it will represent *kaṁ* in Sanskrit and its allied languages. The Bhaṭṭiprōlu script devised a way to satisfy both these, evidently not being accustomed to the use of ligatures.



Fig. 6

1. *Tolkāppiyam*, *Ēḷuttadhikāram*, *sūtra* 15.

This peculiarity is found also in the Brāhmī inscriptions of Tamiḻ-nāḍu. It may be that we have not so far come across with the formation of letters having the  $\bar{a}$  long added to the consonant as in (c) of Fig. 5 above; but we have consonants with two horizontal strokes instead of one as in the usual Brāhmī, added to

W E  
(a)

Fig. 7

C H  
(b)

denote the  $\bar{a}$  long. And we also find the vowelled consonants sometimes written not as one letter, but as two separate letters, with the consonant and the vowel side by side. Thus to denote  $y\bar{u}$  we have the symbol for  $ya$  first and then the vowel  $\bar{u}$  as in (a) and for  $t\bar{u}$  we have  $ta$  and  $\bar{u}$  as in (b) of Fig. 7. This will clearly show that in these Brāhmī records, the consonant letter without the addition of any vowel-sign is to be treated as a vowelless consonant (without the inherent  $\bar{a}$ ). This suits the context on many occasions.

The following (Fig. 8) are the new symbols found in the Brāhmī inscriptions of Tamiḻ-nāḍu

•• § •• § •• § •• § •• §  
i ii iii iv v vi

Fig. 8

**Fig. i of 8 :** This symbol is not found in the northern inscriptions of the period anterior to the Christian era. But it is found in the Kṣātrapa, the Śātavāhana as also the Gupta inscriptions, where it has been read as  $\bar{i}$ , assigning the long value. This is found in the Tamiḻ inscriptions of the 8th century A.D. and there also it is read likewise as  $\bar{i}$ . In the Brāhmī inscriptions of Ceylon which are assignable to the same period as those of South India, this symbol occurs; but there it has been read as short  $i$  and the same value, short  $i$ , has been assigned to this symbol in reading these records.

In the Aśōkan inscriptions, the vowel short  $i$  is found written with three dots arranged in the form of a triangle (as the modern Tamiḻ letter  $\bar{a}y\bar{t}am$ ). Similar form occurs in the Brāhmī records of Tamiḻ-nāḍu where it is read as long  $\bar{i}$ .

This change in the evaluation of the short and long *i* is interesting if not intriguing. It may be explained as follows : In the northern Brāhmī while three dots denoted the short *i*, the longer one *ī* was written with the addition of one more dot, four dots arranged in the form of a square. The *sūtra* of the *Tolkāppiyam*, that in writing, the pure consonants will have a dot added to it, has already been referred to. The next *sūtra*<sup>1</sup> is *ekara okarat t-iyarkaiyum-arre* (Likewise the nature of *e* and *o*). From this it will be evident that the short *e* and *o* will also have dots added to them. There are also other *sūtras* in the same work that forms of further shortened *i*, *u* and *m*, each having only half a *mātrā*, i.e., only half the sound length of the short vowels and consonants, will also have dots added to them.<sup>2</sup> It will thus be seen that in writing the Tamil language the addition of a dot to the form of *i* denotes the shorter form of it, while in the northern Brāhmī, it denotes the longer form. Probably the above change was effected in conformity with this southern principle.

**Fig. ii :** About this, Mr. Krishna Sastri has noted as follows: "The formation of this letter is very peculiar. Its similarity with the Kalsi Aśōkan *ja* given in Buhler's Tafel II-15, 2 is very slight. One can venture to say that it is somewhat like the modern Tamil *la*." (*Proceedings and Transactions of the First Oriental Conference*, p. 366, fn. 7) This has been read as *la* and this value suits the place of its occurrence.

**Fig. iii :** This looks very much like the Brāhmī character *la* with a little difference, the addition of a hook-like stroke to the right arm and is taken to represent the lingual *la* peculiar to the Dravidian languages. It is to be noted that *la* occurs in the Bhaṭṭiprōlu script also ; but there its form is somewhat different.

**Fig. iv :** This is a curious one and resembles a badly shaped *tu*. It occurs several times in these epigraphs. The only letter in Tamil that is allied in sound to *ta* which has no equivalent in Sanskrit and for which a new symbol had to be devised in writing these Brāhmī records is the Dravidian *za*.

1. Ibid, *sūtra* 16

2. M. Raghava Aiyangar : The article *Tolkāppiyānārum pulḷi-y-ēluttukkaḷum* in his book *Ārāycci-t-toguti*.

**Fig. v :** This symbol which looks like an 'inverted J' occurs frequently in our inscriptions. This is also seen in the Bhaṭṭi-prōlu inscriptions where it has been assigned the value of long *nā*. But in the Brāhmī inscriptions of Tamiḷ-nāḍu, the symbol for *na* found in the other Brāhmī records is also seen. In one inscription both this symbol as well as the Aśōkan *na* are found. As such, this symbol should be taken as distinct from *na*, but having a sound value equal to it, i.e., *na* peculiar to the Tamiḷ script.

**Fig. vi.** This symbol is found in the Brāhmī inscriptions secured from Pugaliyūr near Karuvūr in the Tiruchirāpaḷli district which are somewhat later in date to those found in the Madurai, Rāmanāthapuram and Tirunelvēli districts. It resembles very much the letter *na* of the Vaṭṭeḷuttu script. At Pugaliyūr, along with this symbol, we find the symbol as in (v) of Fig. 8, as also one or two others which may be considered as intermediary forms between them. All these have been assigned the value *na*.

The following table shows the forms of the Brāhmī letters of these inscriptions incorporating the above values. It will be seen therefrom that only Tamiḷ letters are found in these inscriptions. The last two columns at the right give the forms of letters not belonging to the Tamiḷ alphabet found therein, while the two rows at the bottom give the variant forms of individual letters found in these records. The letters in these two rows are :

First row : *a, ko, tu, ti, pi, ya, lā, vā, ra, na, na*

Second row : *te, pā, ya, ri, ru, u, u*

The peculiarities of the Brāhmī script of these epigraphs are as follows :

#### Vowels

In the Aśōkan inscriptions, the letter *a* appears like the 'Inverted K' with the two arms joined. Even though this form is found in these records, majority of the letters has both the arms as two separate angular lines diverging in the opposite directions, above and below.

#### Consonants

*ṭha* is found used in places where *ṭṭa* should have been used.





*ma* is written in the Aśōkan inscriptions as a circle below with the two perpendicular arms above. But in these records it is written in the form of a broad tube opening upwards with a cross-bar in the middle.

*ya*, though having three arms, is found written in the northern Brāhmī with the middle arm too long, like an anchor. It is true that similar form occurs rarely in our records; but the most common shape is to have all the three arms of equal height.

The character to which the value *dha* has been assigned occurs only once in these records and it looks more or less (practically) as the vowel *e* in shape.

As already stated, there are many forms for *ra* and *na* which fact may be taken either as clearly showing that these two characters had just then been introduced to the Brāhmī script and had not attained a standard form or that they had been in use for a long time and thereby had attained these forms by evolution.

### *Medial vowels*

It has already been noticed that in the northern Brāhmī, the long *ā* is indicated by the addition of a horizontal stroke at the right to the top of the character; here we find sometimes two such strokes to denote long *ā*.

Medial *i* is generally denoted by the addition of two straight lines, one horizontal and the other vertical opening upwards; sometimes the angle is found smoothened, thus forming a sort of curve.

Medial *o* is formed by a line at the top of the character projecting both to the left and to the right; sometimes it is found as two separate lines, one at the right and the other on the left.

### III THE BRAHMI AND THE ARCHAIC GRANTHA

We have already stated that after these Brāhmī records no inscriptions are found in Tamil-nāḍu upto the beginning of the 7th century A.D. But still, as the Grantha, the Tamil and the Vaṭṭeluttu scripts, were evolved from the Brāhmī, it is necessary to study their evolution.

The changes that took place in writing the Brāhmī script were not much and there was not any appreciable difference in the script upto the 4th century A.D. As such this script anterior to *circa* 350 A.D. has been designated as Brāhmī and inscriptions in this script are found in the Vēṅgi country of the Āndhra State.

So far as the scripts of the Tamiḻ country are concerned we may trace the evolution of the Brāhmī script in the following order: Aśōkan inscriptions (*col.* I), Bhaṭṭiprōlu inscriptions (*col.* II), the records of the Kṣātrapa and Sātavāhana kings (*col.* III), the epigraphs found at Amarāvati, Jaggayyapēṭṭah, Nāgārjunakoṇḍa, etc. places (*col.* IV), and the Prākṛit charters of the Pallava kings (*cols.* V and VI).

The scripts used in the inscriptions of the period later than *circa* 350 A.D. are known by such names as Archaic Grantha, Archaic Telugu, etc. *Cols.* VII and VIII show the characters in the Archaic Grantha.

To study the evolution of these scripts it is necessary to compare the individual letters through the different periods.

**Col. I**—Siddhāpura edicts of Aśōka; *circa* 250 A.D. (*EI*, vol. II; *CII*, vol. I) The character in line 11 is supplied from the *Trial alphabets* of the masons found at Gaya and assignable to the period of Aśōka. (English version of Buhler's *Indian Palaeography*, Appendix to *IA*, vol. XXXIII, p. 35) Line 49 is taken from the Kalsi edict of Aśōka (*EI*, vol. II) while line 50 is from the Mathurā Pillar inscription.

**Col. II**—Bhaṭṭiprōlu inscriptions; *circa* 200 A.D. (*EI*, vol. II) Line 49 from the Hathigumpha inscription of the Kalinga king Khāravēla, (*EI*, vol. XX) while the line 50 is from the Bharhut Stūpa record.

*kha* (8) is a straight line with a hook at the top towards the left.

*ga* (9)—In the northern variety, the two arms are joined angularly at the top, thus taking the shape of a triangle without the base; but here the vertex at the top is smoothened and made cursive as semi-circular.

*gha* (10)—The tripartite form of the northern variety is not found; instead a new form is shaped with the addition of a hook to the right of *ga*.

*ca* (12)—The straight line at the right is projected even below.

*ja* (14, 45)—The horizontal stroke in the middle is absent.

*ḍa* (24), *dha* (25), *bha* (30) and *ṣa* (37) have changed sides so as to be convenient for writing from left to right.

*ma* (31) has been turned upside down.

*ra* (33), instead of being a zigzag line, is found as a straight line.

*la* (34) is different from the similar character of the northern variety.

*ḷa* (40) is a new character not found in Northern Brāhmī, but still different in shape to that of Tamil-nāḍu.

**Col. III**—Girnār inscription of the Kṣatrapa ruler Rudra-dāman; circa 150 A.D. (*Archaeological Survey of Western India* by James Burgess, vol. II)

The characters of this inscription though found in the Kathiawar region belong to the southern variety of Brāhmī and resemble very much those found in Vēṅgī. Very likely, the rule of the Śātavāhana kings on the east coast of the Dakhan was responsible for this.

The vertical lines of *a* (1), *ā* (2), *ka* (7), *ṇa* (16) and *ra* (33) as also of the medial *u* and *ū* are elongated and have small hook-like inward curves at the end.

*kha* (8)—The knob at the bottom has become a triangle.

*ḍa* (19)—has the lower portion made into a semi-circle.

*ba* (29)—The left side of the square has an indent in the middle.

The right arm of *la* (34) has begun to incline to the left.

The lower portion of *pa* (27) and *ha* (39) which are open above, have begun to bulge towards the left.

	I	II	III	IV	V	VI	VII	VIII
1	a	a	a	a	a	a	a	a
2	ā	ā	ā	ā	ā	ā		ā
3	i		i	i		i		
4		u		u		u	u	
5	e		e	e	e	e	e	e
6		o		o	o		o	o
7	ke	kā	ka	ka	ka	ku	ka	ka
8	kho	kha	kha	khā	kha	kha	khi	khī
9	ga	gā	gu	gi	gī	gu	gu	gi
10	ghe	gha	gha	gha	gho	gha		
11	ṇa						ṇga	
12	ca	ca	ca	ca	cī	ca	cā	ca
13	cha	cho	cha	cha	chi	ccho	ccha	cchā
14	jā	ja	jā	jī	jo	jo	ja	ji
15				jhi				
16	ṇā		ṇa	ṇu	ṇa	ṇa	ṇcha	jṇa
17	ṭa	ṭo	ṭa	ṭi	ṭa	ṭi	ṭṭa	ṭṭi
18	ṭhi	ṭho	ṭha	ṭho	ṭho	ṭha		
19	ḍe		ḍa	ḍa	ḍe	ḍi	ṇḍa	ṇḍa
20	ḍhi		ḍha	ḍha	ḍhā	ḍha		
21	ṇā	ṇī	ṇā	ṇa		ṇā	ṇe	ṇā
22	ti	tā	to	to	ta	tū	ta	to
23	the	tha	thā	tha	tha	thi	thā	thā
24	dī	dā	da	de	dā	dū	da	da
25	dha	dha	dhi	dha	dha	dha	ddha	dhi
	I	II	III	IV	V	VI	VII	VIII

# KEY TO PLATE 2

I	II	III	IV	V	VI	VII	VIII	
na	na	nū	na	na	nu	na	na	26
pa	pu	pī	pu	pa	pi	pau	pau	27
pha	phā	pha	pha	tpha	pha	pha	pha	28
bā	bū	ba	bo	ba	be	bu	ba	29
	bho	bhi	bha	bhā	bhā	bha	bhū	30
mai	ma	ma	mū	ma	mo	ma	me	31
yā	yā	yau	yā	ya	yā	yī	ya	32
ra	ra	ra	rū	ra	ru	ra	rai	33
le	la	la	lo	la	lo	lai	lai	34
vi	va	vai	va	va	vi	va	va	35
śa	śā	śa			śro	śa	śa	36
	ṣi	ṣi				ṣa	ṣā	37
sū	se	sra	sa	sa	sa	sa	sa	38
he	ho	hā	hī	hā	hā	hu	hā	39
	ḷi	ḷi	ḷā			ḷū	ḷū	40
kye		kṣa		mha	ṇḍam	kṣa	kṣi	41
sva		rttha		ke	ke	bhyu	nu	42
cya		lya		mmo	ñca	bhū	śrī	43
kram.		ṣṭra			ttha	jña	rū	44
	nā		ja	ja	bhra	de	pū	45
	ṇo		i	lo	bhya	lo	grā	46
	jū		ku	i		m	rmna	47
			tu	da		po	yyā	48
ja	ai		ai					49
i	ū							50
I	II	III	IV	V	VI	VII	VIII	

	I	II	III	IV	V	VI	VII	VIII	I	II	III	IV	V	VI	VII	VIII	
1	✕	✕	✕	✕	✕	✕	✕	✕	1	1	1	1	1	1	1	1	26
2	✕	✕	✕	✕	✕	✕	✕	✕	1	1	1	1	1	1	1	1	27
3	::	::	::	::	::	::	::	::	6	6	6	6	6	6	6	6	28
4	2								6	6	6	6	6	6	6	6	29
5	0		0	0	0	0	0	0	✕	✕	✕	✕	✕	✕	✕	✕	30
6	2		2	2	2	2	2	2	✕	✕	✕	✕	✕	✕	✕	✕	31
7	+	+	+	+	+	+	+	+	1	1	1	1	1	1	1	1	32
8	✕	✕	✕	✕	✕	✕	✕	✕	1	1	1	1	1	1	1	1	33
9	^	^	^	^	^	^	^	^	1	1	1	1	1	1	1	1	34
10	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	35
11	6								6	6	6	6	6	6	6	6	36
12	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	37
13	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	38
14	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	39
15									6	6	6	6	6	6	6	6	40
16	6		6	6	6	6	6	6	6		6	6	6	6	6	6	41
17	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	42
18	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	43
19	6		6	6	6	6	6	6	6		6	6	6	6	6	6	44
20	6		6	6	6	6	6	6	6		6	6	6	6	6	6	45
21	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	46
22	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	47
23	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	48
24	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	49
25	6	6	6	6	6	6	6	6	::	6							50

**Col. IV**—Nāgārjunakoṇḍa inscriptions of the Ikṣvāku ruler Śrī Vira Puruṣadatta; *circa* the first half of the 3rd Century A.D. (*EI*, vol. XX) The characters in lines 19 and 20 are those taken from the Jaggayyapēṭṭāh inscriptions of the same king (*Arch. Survey of Southern India* by James Burgess, vol. I) while that of line 49 is from the Allūru inscription (*ARSIE*, 1924).

The script appears well-developed. Two varieties of the script were in use then : one beautiful to look at with the vertical lines at the right fully elongated (represented by the first forty lines of the plate) and the other not so ornamental but as could be accommodated in a square with the arms not unduly elongated (as seen in last few lines of the plate from line 45).

As already pointed out the ornamental variety is of the type of the Gīrnār inscriptions (*col.* III). The vertical lines of the letters mentioned there are similarly elongated here also (1, 2, 7, 16, 27, 31 and 33). In addition we find the vertical lines of *jha* (15, not found at Gīrnār) and *la* (34) as also of the medial *i* (9, 15 and 17) are similarly elongated with a curve at the end. Sometimes these curves are fully rounded either inward or outward.

Both *ta* (22) and *na* (26) are written alike.

Of the less ornamental variety the symbol for medial *u*, instead of being a straight downward-stroke, appears as a curve to the right.

Two variant forms (3 and 46) are found in writing the vowel *i*. There is a crescent-shaped line in the form in line 46, instead of the third dot at the right. The later forms were developed only from this. Evidently this shape was obtained by joining the two dots at the right in the southern form of *i* having four dots in the form of a square.

Similarly there are two forms of *ja* (14 and 45). The latter one evidently belongs to the Bhaṭṭiprōlu variety.

*ai* (49)—This is a new form not found in the northern Brāhmī and has no relation to that found in column. II. But it is the same as the trident *ai* of the Vaṭṭeḷuttu script.

**Col. V**—This and the next column, though belonging to the time of the Pallava king Śivaskandavarman, are different from each other and are given from two different charters of the monarch. The letters of this column are taken from the Mayidavōlu plates of the ruler (*EI*, vol. VI), *circa* 300 A.D., with the exception of lines 6, 10, 20, 28, 47 and 48 which are from the Koṇḍamuḍi plates of the Brihatpālāyana king Jayavarman (*Ibid*).

These also are of the Bhaṭṭiprōlu type.

*e* (5) is like the Tamil form.

As in Nāgārjunikoṇḍa, here also we have two forms of *ja* (14, 45)

*ḍa* (19), *da* (24) and *na* (26) are all written alike and they have to be differentiated only according to the context.

*sa* (38) has been formed by two slanting upward curves one below the other and heavy at the left with hooks opening upwards at the lower ends.

*ma* (31) also consists of two parts : one slanting curve as found in *sa* with an egg-like pendant joined to it at the right.

The straight line with the hook at the right of *ha* (39) found in the Brāhmī has been relegated to the bottom here.

**Col. VI**.—Hīrahaḍagaḷḷi grant of the same king (*EI*, vol. I) This variety is more curvilinear.

The symbol of medial *o* in *lo* (34) appears as a loop.

*śa* (36)—The middle downward stroke is converted into an horizontal one and attached to the left arm.

The letter *ḍa* in the ligature *ṇḍam* (41) has a tail at the right.

**Col. VII**.—The Pīkīrā plates of the Pallava king Simhavarman (*EI*, vol. VIII); later half of the 5th century A.D. Lines 1, 4 and 5 are from the Uruvapallī plates of the Pallava Yuvamahārāja Viṣṇugōpa (*IA*, vol. V) ; 8, 11 and 40 from the Māṅgaḷūr plates of Simhavarman (*Ibid*) and line 6 from the Oṁgōḍu plates of the same king (*EI*, vol. XV).

These characters appear like the 'Box-headed' variety of the Dakhan and are formed squarely sometimes with a knob as the head of a nail at the top (vide particularly the Uruvapallī plates).



*ta* (22) is written with a loop at the bottom while *na* (26) has no such loop, even though sometimes both are written alike.

*tha* (23)—The centre dot has become a hook and attached to the circle on the right side.

Similar change has taken place to the middle line of *śa* (36) and *ṣa* (37).

The final *m* is written very small as in line 47.

The sign for the medial vowel *i* (8) has become a complete circle while that of *ī* appears as a coil.

The medial *u* (9 and 42) and *ū* (40, 43) are written in two ways.

**Col. VIII**—The Chendalūr plates of the Pallava monarch Kumāraśiṣṇu (*EI*, vol. VIII); beginning of the 6th century A.D., with the lines 2, 6 and 8 from the Oṃgōḍu plates of the Pallava ruler Skandavarman (*Ibid*, vol. XV).

The *talai-k-kattū* found in the previous forms is absent and these letters resemble more or less the earliest Grantha script of Tamiḷ-nāḍu.

The vertical lines of *a* (1), *ā* (2), *ka* (7), and *ra* (33, 44) and of the medial vowel *u* (40, 42, 45) have been doubled.

The right side of the vowel *e* (5) has become crescent-shaped.

The bulge to the left of *pa* (28, 45), *ṣa* (37) and *ha* (39) is not so prominent and is fast disappearing.

The above detailed consideration will bring out the following as the special features in the evolution of the script in this **Formative period** :

(i) The top portions of individual letters were thickened, even though this was not seen much in the Aśōkan Brāhmī, and this developed later on as the *talai-k-kattū*.

(ii) To suit the convenience in writing the letters from left to right some changes were made in their forms. They are ;

(a) Letters like *e*, *da*, *dha*, *ṣa*, etc. which were heavy at the right changed sides and became heavy at the left.

(b) Some portions only of *śa* and *ṣa* were similarly changed.

(iii) The unequal vertical lines of *pa*, *ya*, *ṣa*, and *ha* were equalised.

(iv) The vertical lines of *a*, *ka*, *ra*, *la*, etc. were elongated and ended with an inward hook, which facilitated the formation of the double line of the later period.

(v) Letters like *pa*, *ha*, etc. which were open above developed a bulge to the left at the bottom.

(vi) The dots of *i* and *tha* became loops attached to the line at the right.

(vii) The vertical lines of the medial vowel symbols *i* and *u* were elongated up and down respectively and ended with a hook at the end.

It is also to be noted that the Brāhmī inscriptions of the Telugu country have some forms not found in the northern Brāhmī. Among them the form of *ai* may be mentioned specifically.

#### IV. THE GRANTHA SCRIPT

We have already stated that both the Grantha and Tamil scripts appear alike even in their modern forms. The evolution of these two scripts were also more or less similar.

Grantha is the name applied to the script used in the Tamiḷ-nāḍu for writing the Sanskrit language. The word Grantha denotes in Sanskrit a literary work. Evidently the script used for writing the Sanskrit works derived the same name.

At one time it was prevalent throughout South India. When the Malaiyāḷam language began to freely borrow words as well as the rules of grammar from Sanskrit, this script was adopted for writing that language and was known as *Ārya-eḷuttu*. That a similar adoption for writing was also made in the Tuḷu country has been referred to already. Subsequent to that, the use of the Grantha script has been confined to the Tamiḷ-nāḍu proper.

The Nāgari script, though not unknown,<sup>1</sup> was used more in the Tamiḻ country only after the establishment of the Vijayanagara empire, when their inscriptions, mostly copper-plate grants and that in the northern districts, were incised in the Nāgari script. And its use further increased after the advent of the Mahrathas. With the spread of Hindi, the national language, using the Nāgari script, in the south, the Grantha script has almost ceased to exist and probably some years hence, there may not be persons able to read the script.

The evolution of the Grantha script in the South may be divided into four periods; the archaic, the transitional, the mediaeval and the modern.

*A. The Archaic Variety:* This belongs to the period anterior to circa 700 A.D. and is of the same variety as found in Vēṅgī. The inscriptions of the Pallava king Mahēndravarmān and his successors (cols. I, II, III and V) are typical. The script, with the exception of col. I, being mostly ornamental and florid could not have been in everyday use; probably they were intended only for incising inscriptions.

**Col. I**—This and the next column belong to the time of the Pallava king Mahēndravarmān in the first quarter of the 7th century A.D. Two forms, one ordinary and the other ornamental, were in use in his time. This column gives the ordinary form and are taken from his Maṇḍagapaṭṭu (*EI*, vol. XVIII), Mahēndravāḍi (*Ibid.*, vol. IV), Śiyamaṅgalam (*Ibid.*, vol. VI) and Daḷavānūr (*Ibid.*, vol. XII) inscriptions.

**Col. II**—This is the ornamental type of the time of the same king found in his Tiruchirāppaḷḷi rock-cut temple inscriptions. (*SII*, text in vol. I and plate in vol. II; see also *The Pallava Antiquities* by G. Jouveau-Dubreuil, vol. I).

---

<sup>1</sup> There are Nāgari inscriptions of earlier period in the south, e.g. the Kailāsanātha temple inscription of Rājasimha from Kāñchipuram, the Atiraṇaṇḍēśvara cave temple Pallava inscription at Māmalla-puram (*EI*, vol. XII), the Paliyam plates of the Āy king Vikramaditya Varaguṇa of the South Travancore (*TAS*, vol. I), etc.

**Col. III**—Inscriptions in the Dharmarāja *ratha* at Māmalla-puram of the Pallava kings Narasimhavarman I, the victor of Vātāpi and his son Paramēśvaravarman I, in the second and third quarters of the 7th century A.D. (*EI*, vol. X).

In this, most of the curves have been converted as straight lines.

**Col. V**—Inscriptions of the Pallava king Rājasimha in the Kailāsanātha temple at Kāñchīpuram (*SII*, text in vol. I and plate in vol. II) and at Māmallapuram (*EI*, vol. XIX); *circa* 700 A.D. These records, though chronologically later than the script given in column IV, show earlier forms. It is seen from the inscriptions of Rājasimha in the Kailāsanātha temple at Kāñchīpuram that four kinds of script were in use during his time as will be evident from an inscription of his incised in all these four kinds round the base of the temple. One is Nāgari and the other three are the Grantha. Two varieties of the ornamental script were prevalent then and this will be evident in comparing *ga* (10, 46), *ja* (15, 17) *ṇa* (20, 22), *ba* (30, 49), and *śa* (37, 47).

This ornamental type appears to have fallen into disuse after the period of Rājasimha. It is found that in this type *e* (5), *ca* (13), *va* (36), etc. were written more or less similar and that was probably one of the reasons for its disappearance.

The chief features in the evolution of the script in the period are as follows :

(i) The vertical lines of *a* (1), *ā* (2), *ka* (5) and *ra* (34) as also in the medial *u* symbols (II—18, 27) had become doubled.

(ii) In the Archaic Grantha illustrated in the previous plate, we found that the form of the vowel *i* in the southern type was unsettled then (vide IV-46 and V-47 of plate 2). It is now found that the two upper dots of this letter (II-3 of the present plate) were joined by a line with a dip in the middle and this was later on joined to the dot at the bottom right by another vertical line. (III-3). That even this was only tentative will be seen later on.

(iii) *kha* (9)—The loop at the bottom became open upwards with a bulge to the left.

(iv) *e* (5—I, V) and *tha* (24—I, III, V) also became slightly opened up.

(v) The symbols for the media vowels  $\bar{a}$  (I—17, 18),  $e$  (II-23) and  $ai$  (II-37) as well as those for  $o$  and  $au$  became separated from the consonants, but were written as close to them as possible.

(vi) The symbol for the medial vowel  $\bar{a}$  was generally a downward strike at the right of the consonant (II—24, 41); but it was also written as a zigzag line going upwards at the right (I—17, 18) and on many occasions both these varieties were found used at the same time. The lower end of the upward stroke had a hook turning to the left (V—8, 20) which was the precursor of the double line found later and sometimes a cup-like base (V-18).

(vii) The sign for the medial vowel  $\bar{i}$  (III-44) became a semi-circle with a loop at the left end.

*B. The Transitional Variety*: The inscriptions for about three centuries roughly between 650 A.D. and 950 A.D. may be classified as of this variety. The records of the Later Pallavas of the Nandivarman dynasty, the Pāṇḍyas of Madurai upto the time of their conquest by the Chōḷas and of the Chōḷas upto the time of their expansion under Rājārāja I belong to this variety. (cols. IV and VI to IX).—These appear mostly of the type used for writing on palm-leaves with stilus.

**Col. IV.**—The Kūram plates of the Pallava king Paramēśvaravarman I; *circa* 680 A. D. (*SII*, text in vol. I, plate vol. II; also *EI*, vol. XVII.)

The symbol for the medial vowel  $\bar{a}$  (V—18, 32) is found written in both the ways.

**Col. VI.**—The Kaśākkudi plates of Nandivarman Pallavamalla; *circa* 750 A. D. (*SII*, vol. II). This also is of an ornamental variety.

**Col. VII.**—The Taṇḍantōṭṭam plates of the same king; *circa* 780 A.D. (*Ibid*).

**Col. VIII.**—This and the next column are taken from two different grants of the Pāṇḍya king Jaṭilavarman Parāntaka, who ruled at Madurai about the same time. This column is from his Veḷvikkudi plates (*EI*, vol. XVII). The signs of the *upadmānīya* (44), the *jihvāmūliya* (45) and the *anunāsikā* (43) are to be noted.

Col. IX.—The Madras Museum plates of the same king (IA, vol. XXII).

Of the characters in the Kūram plates (col. IV), the signs for *u* (4), *e* (5), *ja* (15), *ṇa* (22), *ba* (30), *bha* (31) and *sa* (39) are much developed. It is improbable that this development took place within the short interval of about fifty years between the times of Mahēndravarmā I and Paramēśvaravarman I as it would have required at least a century and possibly even more. Further, the evolution is not in the nature of that of the scripts in Vēṅgī, but of the Tamiḻ script, e.g., the letters *u*, *ṇa*, *ya*, etc. As such it might even be said that these characters belong to a variety independently evolved in the Tamiḻ country. But, with the available materials, it is not possible to determine when it became separated from the Brāhmī or the Archaic Grantha.

The main features in the evolution of the script during this period are as follows:

(i) The letters came to be written with single strokes running from left to right and from top to bottom.

(ii) As such, the top line of *i* (3) came to be joined to the bottom dot at left (VI-47) and later on connected to the right side dot by a line. The same process was also found in *ṇa* (12), *ja* (15) and *ba* (30) where the right end of the top was connected to the left end of the bottom line, which necessitated the disappearance of the line at the left making it a hook or circle at the beginning.

(iii) When commencing the letter at the top with a downward stroke, the thick head became a horizontal line, or a hook at the left.

(iv) *e* (5), *kha* (9), *ca* (13), *cha* (14), *dha* (26), and *va* (36) were fully opened up.

(v) To begin the letter at the top additional downward strokes were added at the beginning of *ga* (10), and *śa* (37)

(vi) When *cha* (14) became opened up, the loop at the bottom had to end with a flourishing curve at the right, which necessitated the bulge at the left of this letter as well as of *ca* (13) to become angular and pointed.

(vii) The loop attached to the line at the right in *tha* (24) and *sa* (38) were transferred to the end of the line at top, facing left in the former and right in the latter.

(viii) To make it convenient to write in one stroke from left to right the vertical line at the top of *bha* (31) as well as of *sa* (39) was transferred to the beginning at the left.

(ix) *ta* (18), *ḍa* (20) and *da* (25) had tails added to them at the end as flourish.

(x) The bottom line of *ḍha* (21) became a curve with an indenture in the middle, thus making it two.

(xi) The bottom line of *ha* (40) became straight without any bend and this made it look like *bha* (31) and it became therefore necessary to write the right side of *bha* at a lower level and also elongating the middle line of *ha* to differentiate the two.

(xii) The vowelless consonants occurring at the end of sentences had dots either at the top or at the right (following the Tamil method) which came to be written with a flourish (cf. *t* in IV-43, VII-45 and *m* in 45).

(xiii) The symbols of the medial vowels *a*, *e*, *ai*, *o* and *au* became fully separated from the consonants.

(xiv) The right symbol of the medial vowel *au* (VIII-31) became distinct and new.

*C. The Mediaeval Variety* : The inscriptions of the Imperial Chōlas of Tañjāvūr from about 950 A.D. to 1250 A.D. belong to this variety and are represented in *cols.* X to XIV.

**Col. X.**—The Anbil plates of Sundara Chōla; *circa* 960 A.D. (*EI*, vol. XV).

**Col. XI.**—The Larger Śinnamanūr plates of the Pāṇḍya king Rājasimha of about the same period (*SII*, vol. III).

**Col. XII.**—The Kāñchipuram inscription of the time of Rājaraja Chōla I (and the Telugu Chōḍa chief Jaṭachōḍa Bhīma); Śaka 993 or A.D. 1001-2. (*EI*, vol. XXI).

**Col. XIII**—The Tiruvālaṅgādu plates of Rājendra Chōla I; *circa* 1025 A.D. (*SII*, vol. III.)

	I	II	III	IV	V	VI	VII	VIII
1	a	a	a	a	a	a	a	a
2	ā			ā		ā	ā	ā
3		i		i	i	i	i	i
4				u	u	u	u	
5	e	e		e	e	e	e	
6		ṛ					ṛ	
7							o	
8	ka	ku	ko	ku	kā	kṛ	kṛ	ku
9	kha	khaḥ		khe	khai	kha	kha	kha
10	gu	gu		gu	gu	gu	gaiḥ	gu
11	gha		gha	gha	gha	gha	gho	ghri
12		ṅka	ṅku		ṅka	ṅga		
13	cu	ca		cū	ca	ca	ca	ca
14				ccha	ccha	cha	cchā	
15	ja	ja	ja	ji	jī	ja	ja	ja
16								
17	jñā	jñā		ñca	ñja	jñā	jñā	ñja
18	ṭā	ṭu		ṭā	ṭā	ṭe	ṭe	ṣṭa
19						ṣṭha	ṣṭha	
20	ḍa	ḍa		ḍga	ṇḍā	ḍu	ṇḍa	ṇḍa
21								ḍha
22	ṇa	ṇa	ṇaḥ	ṇa	ṇa	ṇa	ṇa	ṇa
23	ta	te	trai	to	tu	tu	tau	ta
24	tha	thā	sthi	thi	tha	tha	rttha	sthā
25	da	dī	dra	dī	da	da	da	dai
	I	II	III	IV	V	VI	VII	VIII



# KEY TO PLATE 3

IX	X	XI	XII	XIII	XIV	XV	XVI	
a	a	a	a	a		a	a	1
ā	ā	ā	ā	ā	ā	ā	ā	2
i	i	i		i	i	i	i	3
u	u			u		u	u	4
	e	e	e	e	e		e	5
					ṛ		ṛ	6
						om̐		7
ku	ka	ki	ku	ku	ku	ka	ka	8
khyā	khā	kha	kha	kha	khi	kha	kha	9
ga	ga	ga	ga	ga	ga	ga	ga	10
gha	ghā	gha	gha	gha	ghṛa	gha	ghi	11
						ṇa		12
ca	ca	ca	ci	ca	co	ci	ca	13
cchā		ccha		ccha		ccha	cchi	14
ja	ja	ja	jaḥ	ja	ja	ja	ja	15
							jha	16
jñā	ñca	jñā	ñja	ñja	jñā	ñja	jñā	17
ṭā	ṭa	ṭi	ṭa	ṭa	ṭa	ṭa	ṭa	18
ṣṭha	ṇṭha	ṭha	ṭha	ṭha		ṭha	ṭha	19
ṇḍa	ḍa	ḍa	ḍa	ḍa	ḍa	ḍa	ṇḍa	20
ḍhā	ḍha	ḍhā					ḍha	21
ṇa	ṇi	ṇa	ṇa	ṇa	ṇa	ṇa	ṇa	22
ti	ta	ta	ti	tai	tā	ta	taḥ	23
tha	tha	thi	tha	tha	sṭha	tha	the	24
dau	da	dau	dā	dau	dā	da	dā	25
IX	X	XI	XII	XIII	XIV	XV	XVI	

(Continued)

(Continued)

	I	II	III	IV	V	VI	VII	VIII
26	dha	dhā	dhi	dha	dhū	dha	dha	dhi
27	na	nu	no	nu	ne	no	nā	no
28	pa	pe	pa	pau	pa	pa	pa	pā
29				pha		pha		pha
30	bu	ba		bā	ba	bu	ba	ba
31	bha	bhi	bhā	bhā	bhū	bhu	bhū	bhau
32	ma	ma	me	mā	ma	ma	mu	ma
33	ya	ya	ya	ya	ya	yū	ya	yu
34	ra	ro	ru	rū	ra	ru	ru	rū
35	lo	lī	lo	lau	la	li	lya	lī
36	vi	va	va	vi	vi	vai	va	va
37	śa	śai	śā	śa	śa	śa	śa	śe
38	ṣa	ṣa		ṣu	ṣa	ṣa	ṣa	ṣā
39	sa	sa	sa	sai	sa	sau	sa	sau
40	ha	ha	hā	hra	ha	ha	hī	hī
41		lā	lī	la		le	lā	la
42	kṣi	kṣa			kṣa	kṣi	tṣi	kṣa
43		ru		t	śrī	kru		ṃya
44	gra	kra	śrī	ṃ	ṃ	ṃ	ṃ	ḥpā
45	lle	llo		rjji	lla	lla	t	ḥku
46	tte	lya	tya	kka	gu	śī	jāḥ	ṃ
47	dru	tu		dru	śa	i	tṭa	tkṛ
48	ṇai	ṇa		dyā	bha	rṇṇa	ndra	śrī
49	ṇa	la		ppa	bra		tte	tya
50	rmmā	kku			tya	kkah		nā
	I	II	III	IV	V	VI	VII	VIII

# KEY TO PLATE 3.

IX	X	XI	XII	XIII	XIV	XV	XVI	
dhi	dha	dhe	dhi	dhi	dhī	dhi	dha	26
na	na	na	na	nī	na	na	nu	27
pu	pe	pū	pa	pa	pu	pu	pu	28
	sphu	•sphi		sphu		pha	phu	29
bra	bu	be	ba	ba	bu	ba	ba	30
bha	bha	bho	bhī	bha	bhū	bha	bha	31
ma	ma	mā	ma	ma	mau	ma	mai	32
ya	ya	ya	yū	ya	yaḥ	ya	ya	33
ro	ru	rī	rū	rū	ru	rā	ru	34
la	la	la	la	la	la	la	la	35
vī	va	vā	vai	vā	vai	va	va	36
śa	śa	śā	śa	śa	śi	śa	śi	37
ṣu	ṣu	ṣyaḥ	ṣa	ṣa	ṣa	ṣa	ṣa	38
sa	sī	sa	sū	sa	su	sū	sa	39
hā	he	ha	ha	hī	ha	hī	ha	40
ḷi	ḷi	ḷa	ḷa	ḷa	ḷa	ḷa	ḷi	41
tṣa	tṣa	tṣa	tṣa	kṣa	kṣi	kṣa	kṣa	42
dbha	nda	kṛ	hra	kṛ	kra	bhra	nṛ	43
lla	lla	nva	kṛ	ḥpa	kṛ	kṛ	nda	44
tta	ntu	ttu	rṇṇa	mma	t	t	kḷ	45
ṁ	ṁ	ṁ	śva	dda	nda	tva	nva	46
kṛ	nū	lla	tu	hu	tu		t	47
rgga	ndra	rṇṇa	gyau	bhu	ṇya	yyaḥ	tya	48
jya	ryya	strā	nta	ṇḍa	nra	kḷ	rcca	49
ṇo				tya		ū	rvva	50

IX X XI XII XIII XIV XV XVI



	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV	XV	XVI	
26	௦	௧	௨	௩	௪	௫	௬	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	26
27	௧	௨	௩	௪	௫	௬	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	27
28	௨	௩	௪	௫	௬	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	28
29																	29
30	௩	௪	௫	௬	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	30
31	௪	௫	௬	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	31
32	௫	௬	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	32
33	௬	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	33
34	௭	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	34
35	௮	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	35
36	௯	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	36
37	௧௦	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	37
38	௧௧	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	38
39	௧௨	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	39
40	௧௩	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	40
41	௧௪	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	41
42	௧௫	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	42
43	௧௬	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	43
44	௧௭	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	௩௨	44
45	௧௮	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	௩௨	௩௩	45
46	௧௯	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	௩௨	௩௩	௩௪	46
47	௨௦	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	௩௨	௩௩	௩௪	௩௫	47
48	௨௧	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	௩௨	௩௩	௩௪	௩௫	௩௬	48
49	௨௨	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	௩௨	௩௩	௩௪	௩௫	௩௬	௩௭	49
50	௨௩	௨௪	௨௫	௨௬	௨௭	௨௮	௨௯	௩௦	௩௧	௩௨	௩௩	௩௪	௩௫	௩௬	௩௭	௩௮	50

**Col. XIV.**—The Śevilimēdu stone inscription of Vikrama Chōla; 1134 A.D. (*EI*, vol. VI).

The important features of the evolution in this period are :

(i) The downward strokes of *ga* (10), *bha* (31) and *ha* (40) enċing at the right were drawn back as a bottom stroke to the left.

(ii) The small openings at the right of *kha* (9), *ca* (13), *tha* (24), *dha* (26) and *ba* (30) had become fully opened up.

(iii) The upper portion of *ma* (32) closed up and looked like the Arabic numeral 8.

(iv) *ya* (33)—The curve and the loop at the left disappeared and it got back its old tripartite form.

(v) The horizontal top lines of *ka* (8), *ta* (23), *na* (27) and *ra* (34) were sometimes bent down on the left side.

(vi) The tail of *ta* (18) became pronounced and prolonged.

(vii) *la* (41) became top-heavy with a short tail.

(viii) The loop of the symbol for the medial vowel *i* was transferred to the right end from the left.

**D. The Modern Variety :** The inscriptions from about 1250 A.D. belonging to the Imperial and the Later Pāṇdyas and the rulers of the Vijayanagara empire are in scripts more or less like the modern ones. The last two columns give specimens of this variety.

**Col. XV.**—The Raṅganātha temple inscription from Śrīraṅgam of Jaṭavarman Sundara Pāṇḍya; *circa* 1260 A.D. (*EI*, vol. III).

**Col. XVI.**—The second Daḷavāy Agrahāram plates of the Tirunelvēli Pāṇḍya king Varatuṅgarāma Pāṇḍya; (Śaka 1510) 1588 A.D. (*TAS*, vol. I)

From the foregoing study it will be evident that the evolution of the Grantha script in the Tamiḷ country took place as follows :

(i) Changes introduced in the letters like *na*, *ja*, *ba*, *bha* and *sa* in the attempt to write them in a single stroke running from left to right.

(ii) Opening of letters like *e*, *ca*, *tha*, *dha*, *ba* and *va* at the top.

(iii) Addition of a downward stroke at the beginning to *ga* and *śa*.

(iv) To the letters *ga*, *ṭa*, *ḍa*, *ta*, *da*, *na*, *bka* and *ha* which ended with small lines at the end, tails running to the left were added.

(v) Addition of another vertical line at the beginning of *ka*, *ṭa*, *na* and *ra*.

(vi) Creation of loop at the left of the other letters beginning with a straight line.

(vii) The symbols of the medial vowels became fully separated.

It is also to be noted that the Grantha included the Tamil letter *ḷa* in its alphabet and also did not adopt the forms for the vowel letters *i*, both long and short, of the northern Brāhmī but adopted the Tamil form.

## V. THE TAMIL SCRIPT

As already stated, inscriptions in the Tamil script are found only from the beginning of the seventh century A.D. Upto the beginning of the eleventh century A.D. inscriptions in this script are found only in the northern portion of Tamil-nāḍu, i.e., the Tondai-nāḍu, the Chōḷa-maṇḍalam and the Koṅgu-deśa. In the extreme south, i.e., the Pāṇḍya country, the Vaṭṭeḷuttu was in use. But with the occupation of the Pāṇḍya country by the Chōḷas after conquest in the closing years of the tenth century A.D. the Tamil script came to be used there also. And afterwards it has been in use throughout the Tamil country. During the hey-day of the Chōḷas as also of their successors, the Pāṇḍyas, we have inscriptions in this script in some parts of the Mysore country, Nellore District in the Andhra State and in Ceylon. Occasionally we find Tamil inscriptions even at Viśākhaṭṭinam of the Āndhra State and at Puri in the Orissa State.

Scholars have designated this script as the *Grantha-Tamiḻ*. Even in the records of the Pāṇḍya country and the West Coast where the Vaṭṭeḷuttu script was used for writing the records in the Tamiḻ language and the Grantha script for the Sanskrit portion, Tamiḻ words occurring in the Sanskrit portion were written only in this Tamiḻ script and not in the Vaṭṭeḷuttu. This will be clear from the Larger Śinnamanūr plates of the Pāṇḍya king Rājasimha (SII, vol. III). From this it can be surmised that even in those days, the Grantha and the Tamiḻ scripts were considered as one.

If the Tamiḻ script of the Kūram plates of the Pallava king Paramēśvaravarman I (col. II of plate 4) is compared with the Grantha script of the same (col. IV of plate 3), it will be found that *u*, *ṭa*, *ṇa*, *ta*, *na*, *ya* and *va* as also the symbols of the medial vowels *ā*, *i*, *ī*, *e* and *o* are similar. There is also no difference in the letters *ka*, *ra*, and the symbols of the medial vowel *u*, except that the vertical lines are single in the Tamiḻ script, while they are doubled in the Grantha. Further, the forms of *ṇa* (17 in cols. V to VII of plate 3) and the vowel *o* are similar to both of them.

The forms of the other letters are slightly different from those of the Grantha.

#### Vowels :

The vertical lines of *a* and *ā* are single and not doubled and the left portion of the body of these letters is not so cursive as in the Grantha.

The form of *i* short appears as if it was obtained by connecting the three dashes in IV-3 of plate 2 by a single line clockwise from top to bottom.

*e*—This form was evidently obtained by writing it in a single line (vide: V-5 of plate 2).

The shape of *ai* was not derived from the trident form of the South Indian variety, but was obtained by writing the northern form (in II-49 of plate 2) in a single line from left to right.



*Consonants :*

The development of *ṇa* was similar to that of the Grantha letters *ṇa*, *ja* and *ba*, in writing it from left to right by a single line.

*ca* is the same as in the Brāhmī.

The two unequal arms of *pa* in the Brāhmī had been made of equal height.

The form of *ma* was derived from the Brāhmī of the Tamil-nāḍu. The horizontal line in the middle (plate 1) was slowly transferred to the right arm (I-19 in plate 4) and this later on became an inward hook at the right of the same.

The form of *la* was obtained by reducing the height of the right arm.

*ḷa* and *ra* were derived from the old forms of the Tamil-nāḍu Brāhmī (plate 1). The several curves and loops of *ḷa* were harmonized so as to facilitate writing it from left to right in a single stroke and the pendent at the right bottom of *ra* was removed.

The form of the letter *ḷa* was obtained from that of plate 1 by fully elongating the vertical line at the right and transposing it to the end of the letter, while that of *ṇa* was derived from the last letter given in the first column at the bottom of the same plate.

While discussing the Grantha script of the Kūram plates of Pallava Paramēśvaravarman, it was pointed out that the script might have been developed from the Brāhmī independently in Tamil-nāḍu. And when we look into the forms of the earliest available Tamil script, it is possible to conclude that they also developed similarly in that part of country itself in consonance with the evolution of the Grantha.

The evolution of the Tamil script may be classified roughly into three stages : the archaic, the middle and the modern varieties.

**A. The Archaic Variety :** The inscriptions of the Pallava kings and their subordinates, as well as of the first rulers of the Chōḷa family, up to *circa* 900 A.D., may be grouped under this head. The first seven columns represent the scripts in use in this period.

**Col. I**—The Vallam rock inscription of Pallava Mahēndra-varman I; first quarter of the 7th century A.D. (*SII*, vol. II).

**Col. II**—The Kūram plates of Pallava Paramēśvaravarman I; *circa* 680 A.D. (*SII*, text in vol. I and plate in vol. II).

**Col. III**—The Tiruvadigai stone inscription of Paramēśvara-varman II; *circa* 730 A.D. (No. 53 of the Madras Epigraphical collection for 1903; text in *SII*, vol. VIII; plate not published).

**Col. IV**—This and the next column illustrate two different kinds of the script current in the days of Nandivarman Pallava-malla. This column gives the letters from his Kaśākkudi plates; *circa* 755 A.D. (*SII*, vol. II). These are of an ornamental variety.

The form of the *āytam* (37) deserves notice.

**Col. V**—The Tiruvallam stone inscription of the same king; *circa* 795 A.D. (*SII*, vol. III).

**Col. VI**—The Śendalai inscriptions of Perumpiḍugu Muttarai-yan *alias* Śuvaran Māran of about the same time. Highly ornamental variety (*Journal of the South Indian Association*, vol. II).

**Col. VII**—The Lālgudi inscription of Nripatuṅgavarman belonging to the closing years of the 9th century A.D. (*SII*, vol. V). Line 4 is from the Vēlūrpāḷaiyam plates of Nandivarman III (*Ibid*, vol. II), while 40-42 are from the Tirupparappu copper-plate grant (*TAS*, vol. I). The form of *ai* (8) is from the Uttaramērūr inscription of the Chōḷa king Parāntaka I. (*EI*, XXII).

The peculiarities in the evolution of the Tamil script in this period are :

(i) Vowelless consonants were generally dotted above, as also the short *e* and *o* (*col.* VI) as required in the rules of Tamil grammar already referred to.

(ii) The small hook-like curves at the left of the vowels *a* (1) and *ā* (2) were slightly altered so as to be convenient in writing them clockwise.

(iii) The symbol denoting the length in the vowel form of *ā* (6) was separated from the main letter and written like that of *ā* long.

(iv) The bottom loop of *ca* (12) was not completed but left with an opening above.

(v) Similarly, the loop of *ma* (19) stood hanging without touching the bottom line.

(vi) *ya* (20) was written in both the ways, the tripartite as well as the looped one.

(vii) The symbols of the medial vowels *ā*, *i*, *ī*, *e* and *o* became separate from the consonants.

(viii) The symbols of *u* in *tu* (VI-35; V-36), *nu* (II-36; IV-36) and *lu* were noted in two ways. The form with the line slanting to the right at the bottom was old; yet both of them were used simultaneously.

(ix) Both *mu* (33) and *lu* (34) were written alike; but to distinguish them the downward stroke of *lu* was lengthened.

(x) The two spirals placed one above the other before a consonant to denote the medial vowel *ai* in the Grantha were placed side by side, so close that sometimes they appeared as one symbol with two loops like the modern one. But the symbols attached to the letters like *ṇa*, *la* (III-37), *ḷa* and *ṇa* which begin with loops were different.

(xi) As in the Grantha, the thickness on the head of the vertical strokes at the beginning of letters tended to become a horizontal line to the left.

*B. The Middle Variety:* The inscriptions of the Imperial Chōlas from the beginning of the tenth century A.D. to circa 1250 A.D. may be classed as belonging to this variety. Cols. VIII to XII illustrate this variety.

	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV
1	1	2	3	4	5	6	7	8	9	10	11	12	13	14
2	15	16	17	18	19	20	21	22	23	24	25	26	27	28
3	29	30	31	32	33	34	35	36	37	38	39	40	41	42
4	43	44	45	46	47	48	49	50	51	52	53	54	55	56
5	57	58	59	60	61	62	63	64	65	66	67	68	69	70
6	71	72	73	74	75	76	77	78	79	80	81	82	83	84
7	85	86	87	88	89	90	91	92	93	94	95	96	97	98
8	99	100	101	102	103	104	105	106	107	108	109	110	111	112
9	113	114	115	116	117	118	119	120	121	122	123	124	125	126
10	127	128	129	130	131	132	133	134	135	136	137	138	139	140
11	141	142	143	144	145	146	147	148	149	150	151	152	153	154
12	155	156	157	158	159	160	161	162	163	164	165	166	167	168
13	169	170	171	172	173	174	175	176	177	178	179	180	181	182
14	183	184	185	186	187	188	189	190	191	192	193	194	195	196
15	197	198	199	200	201	202	203	204	205	206	207	208	209	210
16	211	212	213	214	215	216	217	218	219	220	221	222	223	224
17	225	226	227	228	229	230	231	232	233	234	235	236	237	238
18	239	240	241	242	243	244	245	246	247	248	249	250	251	252
19	253	254	255	256	257	258	259	260	261	262	263	264	265	266
20	267	268	269	270	271	272	273	274	275	276	277	278	279	280
21	281	282	283	284	285	286	287	288	289	290	291	292	293	294
	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV

	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV	
22	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	22
23	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	23
24	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	24
25	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	25
26	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	26
27	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	27
28	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	28
29	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	29
30	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	30
31	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	31
32	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	32
33	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	33
34	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	34
35	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	35
36	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	36
37	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	37
38	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	38
39	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	39
40	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	40
41	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	41
42	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	42

PLATE 4.

I II III IV V VI VII VIII IX X XI XII XIII XIV

1	a	a	a	a	a	a	a	a	a	a	a	a	a	1	
2		ā	ā	ā	ā	ā	ā	ā	ā	ā	ā	ā	ā	2	
3		i	i	i	i	i	i	i	i	i	i	i	i	3	
4						ī	ī		ī		ī			4	
5			u	u		u	u	u	u	u	u	u	u	5	
6		ū	ū	ū	ū		ū			ū	ū		ū	6	
7		e	e	e	e	e	e	e	e	e	e	e	e	7	
8						ai	ai		ai		ai	ai		8	
9		o	o			o	o	o	o	o		o	o	9	
10	kā	ko	kū	ko	ko	ko	ke	ka	kai	ka	ko	ka	ka	kai	10
11	n	na	n	na	n	n	n	na	na	na	na	na	na	na	11
12	ca	ca	ce	ca	ce	ca	co	ca	ce	ca	ce	ca	ce	ce	12
13		ñ	ñ	ñ	ña	ña	ña	ña	ña	ña	ña	ña	ña	ña	13
14	tu	ta	ta	ta	ta	tā	ti	ti	ti	ti	tī	ti	ta	ti	14
15	ṇa	ṇa	ṇa	ṇa	ṇ	ṇa	ṇa	ṇa	ṇa	ṇa	ṇa	ṇi	ṇa	ṇa	15
16	tu	ta	ti	ta	ta	ta	ta	ta	ta	tī	ta	ta	ti	ti	16
17	na	na	nā	nā	na	na	nā	nā	nā	nā	na	ne	nā	nā	17
18	pa	pa	po	pa	pa	pa	pa	pe	pā	pe	pū	pa	pa	po	18
19	ma	ma	m	mā	mā	m	mi	ma	ma	ma	ma	ma	ma	ma	19
20	ye	ya	ya	ya	yā	yi	ya	yā	yu	ya	ya	ya	ya	yu	20
21	ra	ra	ru	re	ra	ru	rai	ru	ru	rai	rai	rai	rai	ru	21

I II III IV V VI VII VIII IX X XI XII XIII XIV

# KEY TO PLATE 4

I II III IV V VI VII VIII IX X XI XII XIII XIV

22	la	la	la	la	li	le	la	la	la	la	la	la	la	22
23	va	va	ve	va	va	vā	va	vi	vī	va	vu	va	va	23
24		l	la	l	la	la	la	la	la	la	la	la	la	24
25	li	l	l	lu	la	lū	la	la	la	la	lu	la	la	25
26		ra	r	rā	rā	rā	ra	ra	ra	ri	ra	ra	ra	26
27	n	n	nā	na	na	n	na	na	na	na	na	na	na	27
28	yā	pa		nā	nā	nā	nā			nā	nā	nā	nā	28
29	ti	ti	ti	ri	ti	nū	nū			tu	tu	tu	tu	29
30	ku	nī	ka	nī	kī	cī	cu	kū	ku	ku	ku	rā	ku	30
31	ce	ku	yū	ku	ku	ku	tu	tu	tu	kū	ru	ku	kū	31
32	po	cū	cū	yū		kū		nu	nu	lū	nu	nū	tū	32
33		mu	mu	mu	mu	mu	mu	mu	mu	mu	mu	mu	mu	33
34		lu	lu		lu	lu	lu	lu	lu	lu	lu	lu	lu	34
35		ru	ru	tu	ru	tu	tu	tu	tu	tu	tu	nai	lai	35 ✓
36		nū	nū	nū	tu	tū	ru	ru	rū	rā	rā	ru	ru	36
37		na	lai	k		tū	vū	vū	pū	lu		pu	yū	37
38		lai	tai	lai	lai	lai	nai	lai	lai	lai	lai	lai	lai	38
39		tu	tu	tu	tu	tu	tu	tu	tu	tu			tu	39
40		po	rā		po	po	cu	po		to				40
41		vū	nū			nai	cū		nta		nta			41
42		na	tu			ne	nā		kka					42

I II III IV V VI VII VIII IX X XI XII XIII XIV

**Col. VIII**—This and the next column give specimens from two different inscriptions of Rājarāja Chōla I. This column is from his records in the Brihadīśvara temple at Tañjāvūr; 1011 A.D. (*SII*, vol. II).

**Col. IX**—The Mēlpāḍi Chōlēśvara temple inscription of the same king; 1014 A.D. (*Ibid.*, vol. III). These are of an ornamental type and very much resemble the script of the Larger Leiden plates. (*EI*, vol. XXII)

**Col. X**—The Tiruvālaṅgāḍu plates of Rājendra Chōla I; *circa* 1025 A.D. (*SII*, vol. III).

**Col. XI**—The Tirukkaḷukkunṅam stone inscription of Kulōttuṅga Chōla I; 1112 A.D. (*Ibid.*).

**Col. XII**—The Tirukkaḷar plates of Kulōttuṅga Chōla III; 1204 A.D. (*Ibid.*).

The chief features in the evolution of the Tamil script in this period are :

(i) The *pulli* or dot of the short *e* and *o* as well as of the vowelless consonant was dropped out.

(ii) The signs for the medial vowels *i*, short and long, were written alike without any difference. Where this difference was made clear, *i* long had a loop at the end on the right. (XI-14).

(iii) Similarly *mu* and *lu* were written alike.

(iv) The downward stroke which came to an end at the right in *ta* and *na* was drawn below to the left as a tail.

(v) The vertical line at the end of *ṇa* and *ṇa* was elongated.

(vi) The lower end of the vowel letter *i* was prolonged so as to form a circle round the letter.

(vii) The symbol for the length in the vowel letter *ū* became a separate form.



(viii) *ya* again attained its tripartite form.

(ix) The ends of *ca* and *ma* were joined to the adjacent lines, thus completing the loop.

(x) The horizontal line at the top of *ka*, *ca*, *ta*, *na* and *ra* as well as of the sign for the medial vowel *ā* long had a vertical line attached to it at the left hanging down.

(xi) There was no difference between the consonant *ra* and the sign for the medial vowel *ā* long.

*C. The Modern Variety* : The inscriptions from *circa* 1250 A.D. belonging to the Pāṇdyas of the Second empire as well as their successors, the rulers of the Vijayanagara empire and their subordinates belong to this variety and the letters have practically attained the modern form. The last two columns illustrate this variety.

**Col. XIII**—The Kunrattūr stone record of Rājanārāyaṇa Śambuvarāyan; 1343 A.D. (No. 195 of 1930; not yet published).

**Col. XIV**—The Śrīraṅgam stone inscription of the Vijayanagara ruler Achyutadēvarāya; 1534 A.D. (No. 260 of 1930, unpublished).

It is said that the *kombu* or the semi-circular line with two loops, one at either end (G), in the medial vowels *ē* and *ō* long was invented by the Italian missionary, Rev. Beschi, otherwise known as Viramāmuniyar. But T.A. Gopinātha Rao says that "this is not the case; it is found in several inscriptions prior to Beschi". (*TAS*, vol. I, p. 202, *fn*). The distinction between the long and the short in the symbols for the medial vowels *e* and *o* without the addition of a dot, is also found in the Vaṭṭeḷuttu records.

It can also be seen that among the South Indian scripts, the evolution or the changes undergone by the Tamiḷ script to attain its present shape from that of the seventh century A.D. is the least, especially if we compare the evolution of Telugu-Kannada script for the same purpose.

## VI. THE VATTELUTTU SCRIPT

This script is also known as *Tekkan-Malaiyālam* and *Nanā-mōna*<sup>1</sup>. Inscriptions in this script are mostly found in the Pāṇḍya country, some portions of the Koṅgu country, (parts of the Coimbatore District) adjoining the Pāṇḍya territory and the Kēraḷa region. Occasionally records in the script are found in other areas also. Such inscriptions are not entirely in the Vaṭṭeluttu; but mixed with the Tamiḷ characters. And Vaṭṭeluttu was not also known to have been in normal use in those regions. We shall speak of them later.

This script was used in the Pāṇḍya country only up to the time when the region was finally conquered by the Chōḷas and annexed to their dominion. Even after that it was current in the Kēraḷa region. When the Malaiyālam language began to incorporate more of Sanskrit words, it was found necessary to use a script having all the letters of the Sanskrit alphabet and the Grantha script came to be used naming it as the *Ārya-eḷuttu*. Even then, ordinary people using the common language without such admixture of Sanskrit words did not use the *Ārya-eḷuttu*, but the Vaṭṭeluttu which became debased and was known as *Kōl-eḷuttu*. This *Kōl-eḷuttu* was used by the Muslims of Malabar, known as the Moplahs, till recent times.

As this variety was written with more cursive lines, it was known as *Vaṭṭeluttu* and *Vaṭṭam*. These names are found even in epigraphs. When Parākrama Pāṇḍya renovated the central shrine of the Kurṛalanāthasvāmin temple at Kurṛālam (Courtallam) he ordered that the inscriptions found on the walls of the same should be copied before dismantling the structure and re-engraved

---

1. In common parlance, this word represents the spelling *na* and *mō*, i.e., *namō*, which is probably a contraction for *namōttu-sintam* (*namōstu-siddham*), the auspicious words with which the initiation of small boys in education commences. Evidently, even after the introduction of the Tamiḷ script in the Pāṇḍya country, education of pupils commenced only with this script.

on the walls after renovation. A record of the king in the temple mentioning the above narrates that the "inscriptions being in *Vaṭṭam*, were copied in the *Tamiḻ* script." (*Tirumalai jīṇṇak-kai[yāl uttā\*]raṇam paṇṇina[vi\*]ḍattu tirumalaiyir kalvetṭu Vaṭṭam* = āgaiyāl Tamiḻāga-p-paḍi-y-eḍuttu—No. 454 of 1917) T. A. Gopinatha Rao states that one of the inscriptions there mentions that when the central shrine, which had become dilapidated, was repaired, "all the writing, except the *Vaṭṭam* (*Vaṭṭeḷuttu*) which could not be read, was re-engraved on the wall" (*TAS*, vol. I, p. 286). If it is correct, it will be evident that this script not only fell into disuse in the Paṇḍya country, but also that there were no persons who could read it then.

As already stated, inscriptions in this script are found only from the middle of the eighth century A.D. It was fully developed and distinct even then. In the latter day records, letters like *ṇu*, *lu*, *tu* and *ru* were written alike; but in the earlier ones, each letter had a distinct form and as such they were easily readable. In the 15th and 16th centuries, letters like *na*, *pa*, *ma*, *ya*, *la* and *va* were written alike and as such those records had to be read assigning values to the characters depending on the context. This was probably one of the reasons for disappearance of this script.

If we compare the earliest varieties of the *Vaṭṭeḷuttu* (cols. II to IV of plate 5) with the *Tamiḻ* script of the same period (col. IV of plate 4) it will be seen that *ī*, *ka*, *ṇa*, *ṇa*, *ra*, *la*, *va*, *ḷa* and *ḷa* have the same form in both of them, while the difference in the forms of *a*, *u*, *o*, *ca*, *ṭa* and *ya* between the two is negligible.

The differences between these two scripts are as follows :

*Vowels* :

*a* (1) and *ā* (2) : Only the horizontal line in the middle had become curved as a semi-circle in the *Vaṭṭeḷuttu*.

*i* (3) : This was probably obtained by writing all the three dashes of the Brāhmī form by a single stroke, first connecting the two left-side dashes and then the right one.

	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV	
1	4	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	1
2	பூ	பூ	பூ	பூ	பூ	பூ	பூ	பூ	பூ	பூ	பூ	பூ	பூ	பூ	2
3	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	3
4	ஃ				ஃ				ஃ				ஃ		4
5	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	5
6		உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	6
7	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	7
8	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	8
9	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	9
10	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	10
11	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	11
12	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	12
13	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	13
14	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	14
15	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	15
16	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	16
17	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	17
18	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	18
19	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	19
20	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	ஃ	20
21	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	உ	21
	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV	

	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV	
22	ல	ல	ல	ல	ல	ல	ல	ல	ல	ல	ல	ல	ல	ல	22
23	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	ப	23
24	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	24
25	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	25
26	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	26
27	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	27
28	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	28
29	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	29
30	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	30
31	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	31
32	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	32
33	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	33
34	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	34
35	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	35
36	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	36
37	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	37
38	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	ற	38
39	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	ழ	39
40	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	ஶ	40
41	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	ஸ	41
42	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	ஹ	42
	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV	

I II III IV V VI VII VIII IX X XI XII XIII XIV

1		a	a	a	a	a	a	a	a	a		a	a	1	
2	a	ā	ā			ā	ā	ā	ā	ā	ā	ā	ā	2	
3		i	i	i	i	i	i	i	i	i	í	i	i	3	
4		ī				ī		i		ī		ī		4	
5		u	u	u		u	u	u	u	u		u		5	
6				ū		ū	ū	ū	ū	ū	ū		ū	6	
7		e		e	e	e	e	e	e	e	e	e	e	7	
8	ai			ai	ai	ai								8	
9		o		o		o	o	o		o	o		o	9	
10	ka	ka	ki	ko	ki	kai	kai	ko	ka	kā	kā	ka	kā	ka	10
11		ña	ñ	ña		ña	ñ	ña	ñi	ña	ña	ña	ña	ña	11
12	ca	cū	ca	cū	cā	ce	cū	ce	cā	ca	ci	ce	ci	ca	12
13		ñe	ña	ñ		ña	ña	ña	ñu	ñi	ñu	ña	ña	ña	13
14		ṭai	ṭi	ṭo	ṭā	ṭai	ṭo	ṭai	ṭai	ṭū	ṭai	ṭa	ṭi	ṭā	14
15		ṇu	ṇ	ṇai	ṇa	ṇū	ṇū	ṇa	ṇu	ṇa	ṇa	ṇa	ṇā	ṇi	15
16	ta	tai	ta	te	ta	tai	te	ta	tā	to	to	ta	te	ta	16
17	na	nī	n	nā	nū	nī	nā	ni	ne	nā	ni	na	na	ni	17
18	pa	pū	pi	pū	pu	pū	pai	pā	pū	pū	pu	pī	pa	pe	18
19	ma	ma	mā	mai	ma	mā	mu	mu	mū	mū	me	mā	mu	ma	19
20		yu	ya	ye	yu	ya	ya	yu	yu	yi	yi	yi	yā	yo	20
21	ra	ru	ra	rai	rai	rai	ri	rai	ro	ru	rū	ra	rū	ri	21

I II III IV V VI VII VIII IX X XI XII XIII XIV

# KEY TO PLATE 5

I II III IV V VI VII VIII IX X XI XII XIII XIV

22	la	la	la		li	li	la	la	li	li	la	lu	la	22		
23	vū	va	vo		va	vi	ve	vu	vu	ve	ve	vu	vu	va	23	
24	la	lo		lu	lu	lu	lu	la	lo	lai	lu	lu	lu	li	24	
25		li	li	li	lu	la	la	la	lū	lu	lu	la	lu	la	25	
26	ra	rā	ra	rā	ri	ro	rā	ra	rā	ri	rā		ra	ra	26	
27	na	na	na	na		nu	nu	u	na	na	na	na	na	na	27	
28		nā	tā	nā		nā	nā	nā	nā	nā	nā		nā	nā	28	
29	ti	lai	ki	lai		lai	lai	lai	lai	lai	lai	kā	ti	ru	29	
30	cī	ni	nī	ro		vī	ko	ko	ro	ke	ko	co	ke	ke	ke	30
31		ku	ku	ku		ku	ku	kū	ku	ko		kai	kai	kai	ti	31
32		kū	mū	ni		ni	ni		cū	kō	ku	kū	ko	kō	ko	32
33	te	po	ce	nū		mū	re		ke	lai	lai	lai	co	co	ce	33
34	kai	a	tai	le		vai	vai	lai	kai	kai	kai	nō	ku	ku	ku	34
35	no	ya	ko	ya		co		lo	lo	nē	lo	lo	rā	cai	kū	35
36		nō	cai	nō		mo	nō	nō	nō	nō	nō	nō	ru	tu	tu	36
37		lai	nu	lū		mu	k		mu	lū	lū	lu	nai	tai	vū	37
38		nai	ne	nai		nai	nai		nai	lu	nu	nu	yo	lai	lu	38
39		rai	rai	lū		lu	lu		lu	yo	nai	nai		pū	ti	39
40		ko	nai	lai		lai	po	po	po	po	po	po		lo	te	40
41		tu	tu	po		po			pō	tu	tū	tu	po	po	po	41
42		rū		tū		tū	tu	tū	tū	ru	ru	ru	tu	tu	tu	42

I II III IV V VI VII VIII IX X XI XII XIII XIV

*u* (5): The downward slanting line of the Tamil script became horizontal line with a curve in its middle. Sometimes it even went slanting upwards on the right.

*ū* (6): The sign of length attached as a horizontal stroke on the right of the loop at the top in the Tamil form was transferred to the right end of the tail in the Vaṭṭeḷuttu form to facilitate writing in one line from left to right counter-clockwise.

*e* (7): This was obtained from the triangular form of the Brāhmī, here slightly bent to the left and having hooks at the extremities.

*ai* (8): This was developed from the trident form specially designed for the South as already pointed out.

#### *Consonants:*

*ṭa* (14): The vertical crescent-like form in the Tamil script became horizontal, opening upwards.

*na* (15): The two semi-circles placed side by side in the Tamil script were transposed above and below, probably caused by writing in a slanting manner.

*ta* (16), *na* (17): Small hooks are found at the beginning of both these letters. The middle loop of *ta* in the Tamil form is not found in the Vaṭṭeḷuttu where the bottom line is well drawn to to the left, while the vertical line of *na* has become cursive to the left counter-clockwise.

*pa* (18), *ma* (19): These two have small hooks at the beginning. The loop of *ma* has been transferred to the end at the right.

*ya* (20) has got two forms one like the Tamil and the other by writing the tripartite one commencing with middle line counter-clockwise.

*ra* (26): This is the same form as that of Tamil. Only the end has been drawn as a line to the left at the bottom.

*ṇa* (27) is the same as one of the forms in the Brāhmī of the Tamil-nāḍu. (vide : plate 1, bottom row).



*Signs for the medial vowels :*

*ā* : The short horizontal stroke at the top of the letter to right denoting the *ā* long became slowly bent downwards in the Tamil script and later on became a vertical line; but in the Vaṭṭeḷuttu, it remained horizontal sometimes turning upwards.

*i* : The semicircular curve opening to the left at the top of the letter in the Tamil script was added to the side at the right in this script, thus opening upwards.

*e* : The short horizontal stroke to the left at the top of the letter in the Brāhmī remained in the same form; only it was written slantingly from the bottom going up to the right. When added to the letters like *ka* and *ra*, having the vertical lines as the primary form, it began with a small loop.

*ai* : This was denoted in the Tamil script with two curves placed side by side; but in the Vaṭṭeḷuttu it had only one. Only the letters like *ka* and *ra*, to which one loop was added to the left to denote the medial vowel *e* as mentioned above, had two loops added.

*o* : As in the Tamil script, it had the *e* symbol before and the *ā* symbol added to it after.

Thus the special features in the evolution of the Vaṭṭeḷuttu script from the Brāhmī during the period anterior to about 700 A.D. were as follows :

(i) The letters were written from left to right by a single stroke and generally counter-clockwise.

(ii) The letters were mostly slanting to the left.

(iii) Vertical lines were not used except where they were the principal parts of the letters like *ī* (4), *ka* (10) and *ra* (21) or where they were the right ends of the letters like *a* (1) and *ḷa* (25).

(iv) The horizontal lines became semi-circles with a dip in the middle; vide : *a* (1), *u* (5), *ṇa* (11), etc.

(v) The vertical downward strokes at the beginning of the letters like *pa* (18) and *ma* (19) had small hooks open below at the left.

(vi) The horizontal strokes at the end of the letters, e.g., *na* (17), turned upwards as hooks open above.

(vii) The small downward strokes at the right of letters like *ta* (16), *ra* (26) and *na* (27) were drawn to the left at the bottom as horizontal lines.

It will be seen from the above that the Vaṭṭeḷuttu script also was evolved from the Brāhmī, like the Grantha and the Tamil scripts. But scholars sometimes tried to postulate different theories on the origin of this script.

The late Mahāmahōpādhyāya Dr. Hara Prasad Sastri thought that this script was derived from the Kharoṣṭhī of which it had been the only derivative prevalent in this country. (*JBORS*, vol. I, p. 58). He had not given the reasons which prompted him to come to this conclusion. But this could not have been possible. We have already mentioned that the Brāhmī and the Kharoṣṭhī scripts differ greatly among them, having nothing common between them. On the other hand, we have shown above that the Vaṭṭeḷuttu was derived from the Brāhmī.

Dr. Burnell thought that it was independent of the Aśōkan characters and that it should have had its origin in one of the 'many derivatives from the Phoenician alphabet.' (*ESIP*, pp. 49-52). He considered that the Vaṭṭeḷuttu was in use in the Tamil country long before the advent of the Sanskrit influence and as such it could not have had the Brāhmī as its parent.<sup>1</sup> But he did not also fail to notice the similarities between the two.

---

1. The several views of Dr. Burnell on this subject have been ably refuted by Dr. Caldwell in his *Comparative Grammar of the Dravidian Languages* (p. 9) and by Prof. P. Sundaram Pillai in his *Some Mile-stones in the History of Tamil Literature*. But epigraphy had not far advanced when Dr. Burnell wrote,

Dr. Buhler did not agree with the above, but held that the Vaṭṭeḷuttu was derived from the Brāhmī. However he advanced a second hypothesis about its nature. "The Vaṭṭeḷuttu may be described as a cursive script, which bears the same relation to the Tamil as the modern northern alphabets of the clerks and merchants to their originals, *e.g.*, the Mōḍi of the Marāṭhās to the Bālbōdh and the Takarī of the Dogrās to the Śārādā." (*IA*, vol. XXXIII, App. p. 75).

If so, the Vaṭṭeḷuttu should have been only a variation of the Tamil script without an independent evolution. But when we compare the growth of these two scripts, the similarities and the differences between them, it will become clear that both of them were independently evolved from the Brāhmī. Further, no inscription in the Tamil script has been found in the Pāṇḍya country before *circa* 1000 A.D. when it was finally subjugated by the Chōlas. All the inscriptions found in that area are in the Vaṭṭeḷuttu. And this script was also in use subsequently in the Malai-nāḍu which had not passed directly under the Chōlas. As such, the Vaṭṭeḷuttu may be defined as a script 'independently evolved from the Brāhmī, and in use in the Pāṇḍya country and the Malai-nāḍu in the earlier days and later in the Malai-nāḍu alone.'

From a study of the available inscriptions, the evolution of this script may be divided into three stages: the earlier, the middle and the later ones.

*A. The Earlier Variety:* The inscriptions up to *circa* 950 A.D. and belonging to the Pāṇḍyas of Madurai upto the time of the Chōla conquest are of this variety and are illustrated in the first seven columns of Table 5.

**Col. I**—The Tirunātharkunru stone record (No. 239 of 1904; plate in *TAS*, vol. I, p. 231).

This is probably the earliest inscription available in the Tamil country after the Brāhmī records. No evidences are available to fix its date. Palaeographically it may be assigned to *circa* 400 A.D.

As no other inscription earlier than the seventh century A.D. has been recovered so far, it is not possible to definitely state whether this record is to be treated as belonging to the Tamil script or the Vaṭṭeḷuttu. The late T. A. Gopinatha Rao included this under both the varieties; but the forms of the letters *ai*, *ma*, *na* and *ṇa* clearly show that it belonged to the Vaṭṭeḷuttu.

**Col. II**—This and the succeeding two columns illustrate the letters used in three different records of the time of the Pāṇḍya king Neḍuñjaḍaiyan, otherwise known as Jaṭilavarman Parāntaka, who ascended the Madurai throne in *circa* 760 A.D. This column is from his Madras Museum Plates (*IA*, vol. XXII).

The Vaṭṭeḷuttu is generally found written slanting to the left. But the letters of this record are upright. We have also a few other records written similarly. At one time it was thought that the inscriptions with upright characters were earlier than those having the slanting ones. It cannot be definitely postulated like that. It is true that the upright variety is found only in the earlier records. But both the varieties were in use simultaneously.

**Col. III**—The Āṇaimalai stone inscription of the same king. (*EI*, vol. VIII).

**Col. IV**—The Vēlvikkudi plates of the same ruler. (*Ibid.* vol. XVII).

**Col. V**—The Aivarmalai stone record of the Pāṇḍya king Varaguṇa; (Śaka 792) 870 A.D. (No. 705 of 1905, still unpublished).

**Col. VI**—The Tiruccendūr stone inscription of the same king; (*EI*, vol. XXI).

The form of *āytam* (37) in this record deserves comparison with that found in the Kaśākkudi plates of Nandivarman Pallava-malla. (IV-37 of plate 4).

**Col. VII**—The Larger Śinnamanūr plates of the Pāṇḍya king Rājasimha; the first half of the tenth century A.D. (*SII*, vol. III).

The peculiarities in the evolution of the script in this period are :

(i) The vowelless consonants are found dotted on many occasions. Similarly the short *e* and *o* are occasionally treated. (IV-14, 19).

(ii) *ya* (20) is found written in two ways : one is the tripartite form as in *cols.* II and IV and the other is the looped form of *col.* III. The loop is generally on the inner side.

(iii) The symbol for the medial vowel *i*, though added to the right of the main letter, is sometimes placed at the top also. (III-25).

(iv) The symbol for the medial vowel *ū* (long) in the letters like *lū* (37-IV), *cū* (12-II), *rū*, and *vū* (23-II) is found attached at the bottom to the vertical lines.

(v) The loop at the right of *ma* is not completed in this variety also as in the Tamil script.

(vi) A small hook open upwards is found at the commencement of the symbol for the medial vowel *e*.

*B. The Middle Variety.* The inscriptions of the period from *circa* 950 A.D. to *circa* 1350 A.D. are of this variety. The early records of the Chōlas found in the Pāṇḍya country after their conquest of the region are in the Vaṭṭeḷuttu. Even the earlier inscriptions of Rājārāja I are in this script. The Tamil script came into general use in this region only during later years of his reign. Even in the Malai-nāḍu, before the introduction of the Ārya-eḷuttu, only this script was in use.

And probably because of the contact with the Chōlas and of their influence, some of the peculiarities of the Tamil script, especially in the addition of symbols for the medial vowels, have been adopted. (vide : *no* (36) in *cols.* VII and VIII). *Cols.* VIII to XI give specimens of this variety.

**Col. VIII**—The Āṇaimalai inscription of the Chōla ruler Parāntaka I; 939 A.D. (*SII*, vol. III).

**Col. IX**—The Tirukkāḍittānam inscriptions of Bhāskara Ravivarman of Vēṇāḍu; first half of the eleventh century A.D. (*TAS*, vol. II).

**Cols. X, XI**—The Kollūr Maṭham copper-plate grant of Udaya Mārttāṇḍavarman; (Kollam 364) 1188 A.D. The earlier portion was written by one person and the later portion by another. These two exhibit different varieties and these two columns represent them (*TAS*, vol. IV).

The important features in the evolution of the Vaṭṭeḷuttu during this period are :

(i) The lower ends of the letters *ṇa* (15), *ta* (16), *ra* (26) and *ṇa* (27) were drawn further so as to join the places of commencement, thus making them fully circular.

(ii) The cross bars of the letters *ko* (VIII-10) and *cā* (IX-12) were elongated further to denote the symbol of lengthening at the right, instead of showing it separately.

(iii) *ṇā* (28)—Its old form fell into disuse and a new form was evolved, adding the symbol for the medial vowel *ā* long to the letter *ṇa*.

(iv) Two variant forms were used for *lu* (IX—37, 38).

(v) With the disappearance of dots, to denote the long and short of the medial vowels *e* and *o*, changes were made in the symbols of the short by the addition of a bend to denote the long as in *ko* (IX-30) and *kō* (IX-31) or of a stroke as in *po* (VIII-40) and *pō* (VIII-41).

*C. The Later Variety* : Inscriptions later than *circa* 1350 A.D. are of this variety. This gradually absorbed the peculiarities of the Malaiyāḷam script. This will be clear from the last two columns. The last three columns illustrate this variety.

**Col. XII**—The Kalpātti stone record; *circa* 15th century A.D. (*EI*, vol. XV).

**Col. XIII**—The Pāliyam plates registering the agreement between the King of Cochin and the Dutch East India Company (*Lēnda-Kummañji*); (Pudu-Vaippu Era 322) 1663 A.D.; (*TAS*, vol. I).

**Col. XIV**—The Minchirai Maṭham copper-plate grant; 1770 A.D. (*Ibid.*).

In this variety the consonants *na*, *pa*, *ya* and *va* as also their vowelled forms were all written alike. Again *na* and *lai* were also written similarly. So also *ka* and *cha* had no difference between them. This was probably the main reason for its disappearance.

There are two main difficulties in dealing with the inscriptions in the Vaṭṭeḷuttu script. One of them is that we do not have many dated inscriptions in this script and the other is that different methods were adopted in this script for the addition of the symbols for the medial vowels, without any uniformity as in other scripts. Special forms also were used for certain vowelled consonants.

The Vaṭṭeḷuttu or its derivative, the *Kōl-eḷuttu*, is not in use now.

## VII. MIXED SCRIPTS

It has already been noticed that some inscriptions in the Vaṭṭeḷuttu script are found even outside the Pāṇḍya country and Malai-nāḍu. These are recovered from Oddappaṭṭi (Nos. 211 and 212 of 1910) and Hanumantapuram (*EI*, vol. VII) in the Salem District and Hebbiṇi in the Mulubagal taluk of the Kolar District in the Mysore State (*Ibid.*). Even though they are in the Vaṭṭeḷuttu, some forms of the Tamiḷ script are found in them. The letter *ṭā* (VI-8 of plate 6) is such a form.

Similary, some Vaṭṭeḷuttu forms are seen in the inscriptions in the Tamiḷ script recovered from the same area. Such records are found at Kīḷmuṭṭukkūr (*Ibid.*, vol. IV) and Kulidikk; (*Ibid.*, vol. XXI) in the North Arcot District and at Baṅgavāḍi in the Mulubāgal taluk of the Kolar District in the Mysore State (*Ibid.*, vol. VII).





These inscriptions exhibiting the features of both the Vaṭṭeḷuttu and the Tamiḷ scripts generally belong to the period anterior to *circa* 950 A.D., and they are found in the territorial divisions known as the Gaṅgavāḍi, the Vāṇakappāḍi and the North Koṅḡu, *i.e.*, in the modern Districts of Salem, North Arcot and Kolar. Some stray records from the outlying parts of the Pāṇḍya country and the Toṇḍai-maṇḍalam also exhibit these features.

The following table gives the specimens of this variety.

**Col. I**—The Tirukkaḷukkunṅam stone inscription of the Pallava ruler, Narasimhavarman I, the victor of Vātāpi; *circa* 650 A.D. (No. 65 of 1909, plate in *ARSIE*, 1933).

This is in the Tamiḷ script of the type found in the inscriptions of his father Mahēndravarmān I (cf. *col* II of plate 4), but exhibits the features of the Vaṭṭeḷuttu as in *ci* (6).

**Col. II**—The Kuḷidikki inscription of Vijaya Nandiśvaravarman; *circa* 795 A.D. (*EI*, vol. XXI).

**Col. III**—The Kiḷmuṭṭukkūr inscription of a ruler Narasimhavarman; *circa* 9th century A.D. (*EI*, vol. IV).

This king was taken as belonging to the Gaṅga family; but he seems to be a later member of the Pallava dynasty.

**Col. IV**—The Hanumantapuram inscription of the Pallava ruler Vijaya Isvaravarman; *circa* 9th century A.D. (*Ibid.*, vol. VII).

**Col. V**—The stone record of Kōḍai Mayindan from Malaiyaḍippaṭṭi of the former Puḍukkōṭṭai State; *circa* 900 A.D. (*The Journal of the South Indian Association*, vol. II).

It will be rather difficult to treat the scripts of these inscriptions as belonging to a separate variety instead of classifying the records as belonging to either the Tamiḷ or the Vaṭṭeḷuttu script. If such mixed features of both these scripts are found only in one or two records we may treat them as due to scribal mistakes. But when these are found in the records of a specific period in a particular region it becomes necessary and desirable to treat them as of a separate variety. Further, in view of

the presence of the Vaṭṭeḷuttu in this region, it is possible to postulate as follows :

It cannot be said that the use of the Vaṭṭeḷuttu in that region was due to the influence and control of the Pāṇḍyas over the area. These records were not issued either by the Pāṇḍyas or by their subordinates. We do not also know of any Pāṇḍyan occupation of the area then. It is therefore to be presumed that the Vaṭṭeḷuttu script was in use throughout the Tamil country in the earlier days, that it fell into disuse after the introduction of the Grantha-Tamil by the Pallavas in their dominion, but that it continued to exist in the Gaṅgavāḍi, the Vāṇakappādi and the North Koṅgu portions which were not directly under the Pallava rule, even though the other script was slowly gaining preference. The above proposition will gain support from the Tīrunātharkuṇṇu epitaph and the Vaṭṭeḷuttu features found in the Tirukkaḷukkunram record of Pallava Narasimhavarman I.

#### VIII. THE NUMERALS

The numerals also should be taken as included in writing. There is a Tamil maxium *Enṇum Eluttum kaṇṇena-t-tagum* (The numbers and the letters to be considered as the two eyes). These two generally go together.

Several methods had been adopted for denoting the numbers in inscriptions and manuscripts. Of these *Aṅka-palli*, *Akṣara-palli*, *Bārakhaḍi*, *Bhūtasaiṅkhyā* and *Kaṭapayādi* are the most important.

The system of expressing the numerals with significant words, connoting fixed numbers, like the *nayana* (the eyes) for two and the *Vēdas* for four, is called the *Bhūtasaiṅkhyā*.

The *Kaṭapayādi* is the system in which each of the consonant letters of the Sanskrit alphabet beginning with *ka*, *ṭa*, *pa*, and *ya*, is assigned the number consequently from 1 to 9 and 0.

These two systems are found used in inscriptions and in both of them the units are mentioned first, then the tens and so on progressively.

The system of *Bārākhaḍi* is also known as the *Dvādaśākṣari* and the *Siddha-mātrikā* and it is found used only in the manuscripts. In this, each of the vowels is assigned the number consecutively from one to twelve.

The above three are explained in detail elsewhere (in the section *South Indian Epigraphy*) in this book.

Of the other two, *Aṅkapalli* is the name of the decimal notation and *Akṣarapalli* is the name of the system in which certain letters are used to denote numbers.

Numerals are usually found used in inscriptions while giving the date of the grant and also in the grant portion describing the money or land pertaining to the same. But in the Tamil inscriptions of the earlier period, the numerals were not denoted by figures, but expressed in words, like *Ko Vijaya Nandivikkirama parumarṅku yāṇḍu Arupattonrāvadu*. [In the Sixty-first year (in the reign) of king Vijaya Nandivikrama varma—*EI*, vol. XVIII, p.121]. But the figures for the numerals are found in the records recovered from the Vēṅgi in that period. In the Tamil inscriptions of the ninth and tenth centuries A.D., the date is expressed in both the words and figures like *Kō-Rājakesarippanma[r\*]jkkū yāṇḍu 8 Eṭṭāvadū* [In the 8 Eighth year (in the reign) of king Rājakesarivarman—*SII*, vol. XIII, No. 187].

It was only in later times that the dates as well as the numbers occurring in the body of the records were denoted entirely by figures. In the copper-plate grants numerals are used for numbering the plates also and they are found in the left hand margin or at the top, generally near the holes made for stringing them.

There are two main differences in the figures for the numerals found in the Tamil records and those in other parts and languages.

I. In the numerals found in the Tamil script we have separate forms for ten, hundred and thousand, in addition to those for the unit figures from one to nine. So to denote twenty, two hundreds or two thousands, the figure for two is given first followed by the symbol for ten, hundred or thousand respectively. (௨௦, ௨௦௦, ௨௦௦௦).

But in the North, there are also separate figures for every ten from twenty to ninety. And for writing two hundreds or two thousands the symbol for hundred or thousand is given first and one short stroke is placed by its side as close to it as possible. Similarly for writing three hundreds or three thousands, the symbol for hundred or thousand is placed first and then two additional strokes likewise. But from four hundreds or four thousands onwards, the figure of the respective number like four or five is added to the symbol of hundred or thousand.

II. In the North Indian inscriptions dating from *circa* 600 A.D. the numerals are given in the decimal notation, just as we write now. This is known as the *Aṅkapalli*. In the earlier records the cypher was written in the form of a mere dot. It became a circle only in the later records. This system has not been adopted in the Tamil inscriptions and as such no cypher is found here. Further in the Tamil records the numerals do not have place values. The figure for 2495 is found written as in the bottom row of Table 7 using symbols for thousand, hundred and ten.

In the Tamil epigraphs, symbols are also found for fractions of unit. They are seen mostly in the records of the Chōlas and to some extent in the inscriptions of the Pāṇḍya rulers. The signs for  $\frac{3}{4}$ ,  $\frac{1}{2}$ ,  $\frac{1}{4}$ , and  $\frac{1}{8}$  as found in a record of 1204 A.D. are given in Table 7. In addition, there are symbols for many other fractions going upto  $\frac{1}{320}$ th part of a unit.

One thing has to be mentioned here. In the earlier records occasionally we find the date denoted by two or three methods, mixed up. For example, in the Chicacole (Śrīkākuḷam) plates of the Kālīṅga king Dēvēndravarmān (*EI*, vol. III) the date 183 is first given in words. Then it is again given as follows: the symbol for hundred, the symbol for eight assigning it the decimal value thus becoming eighty (and not the figure for eighty as should have been given) and lastly the syllable *lo* standing for *loka* meaning three according to system of *Bhūṭasaṅkhyā*. In the same grant for the numeral twenty, denoting the day of the month, the figure for two is given first assigning it the decimal value followed by the cypher having the shape of a dot,

The evolution of the Tamil numeral forms is illustrated in Table 7.

**Col. I**—The Nāsik inscriptions of the Śātavāhana rulers Gautamīputra Śatakarnī and Vāsiṣṭīputra Śrī Puṣumāyī; *circa* 100-150 A.D. (*Arch. Survey of Western India* by James Burgess, vol. IV).

**Col. II**—The Nāgarjunakoṇḍa inscriptions of the Ikṣvāku ruler Śrī Vira Puruṣadatta; 3rd century A. D. (*EI*, vol. XX).

	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV
1	~	~		~	~	~			+	+	+	+	~	~
2	=		~	~	~	~	~	~	~	~	~	~	~	~
3	≡	≡	~			~	~	~	~	~	~	~	~	~
4	+	+	+	+	+	+	+	+	+	+	+	+	+	+
5	+	+		+	+	+	+	+	+	+	+	+	+	+
6	+	+		+	+	+	+	+	+	+	+	+	+	+
7	+	+		+	+	+	+	+	+	+	+	+	+	+
8	+	+		+	+	+	+	+	+	+	+	+	+	+
9	+	+		+	+	+	+	+	+	+	+	+	+	+
10	+	+		+	+	+	+	+	+	+	+	+	+	+
100	+	+		+	+	+	+	+	+	+	+	+	+	+
1000	+	+		+	+	+	+	+	+	+	+	+	+	+
	~	~	~	~	~	~	~	~	~	~	~	~	~	~
	~	~	~	~	~	~	~	~	~	~	~	~	~	~

TABLE 7

**Col. III**—The British Museum plates of the Pallava queen Cārudēvi; *circa* 300 A. D. (*Ibid.*, vol. VIII).

**Col. IV**—The Maṭṭepāḍu plates of king Dāmōdharavarman of the family known as the Ānanda-gōtra; *circa* 4th century A. D. (*Ibid.*, vol. XVII).

**Col. V**—The Pīkīrā plates of Pallava Simhavarman; the latter half of the 5th century A.D. (*Ibid.*, VIII).

**Col. VI**—The Madras Museum plates of the Pāṇḍya monarch Jaṭilavarman Parāntaka; *circa* 770 A.D. (*IA*, vol. XX).

**Col. VII**—The Larger Śinnamanūr plates of Rājasiṃha Pāṇḍya; the first half of the 10th century A.D. (*SII*, vol. III).

**Col. VIII**—The Uttaramērūr stone inscription of Pārthivēndra-varman; third quarter of the 10th century A.D. (*Ibid.*).

The figure 2495 given in the bottom row is also from this record.

**Col. IX**—The Tiruvālaṅgāḍu plates of Rājēndra Chōḷa I; *circa* 1025 A.D. (*Ibid.*).

**Col. X**—The Kollūr Maṭham plates of the Vēṇāḍu ruler Udaya-Mārttāṇḍavarman; 1188 A.D. (*TAS*, Vol. IV).

**Col. XI**—The Tirukkāḷar plates of Kulōttuṅga Chōḷa III; 1204 A.D. (*SII*, vol. III). The figures for the fractions at the bottom row are given from this record.

**Col. XII**—The Puḍukkōṭṭai plates of the Later Pāṇḍya kings of Tirunelvēli, Śrīvallabha and Varatuṅgarāma; (Śaka 1504) 1583 A.D. (*TAS*, vol. I).

The short horizontal stroke which denoted 1 at first is found to have also a vertical cross-line added to it, thus taking the shape of the modern mathematical symbol for plus (+), by the 10th century A.D. It is not known how this came to happen. In the earlier inscriptions, short horizontal strokes are used on many occasions to denote the end of sentences or verses. Evidently the vertical cross-line was added to it to distinguish the numerical figure from the punctuation mark.

The figures for the numerals 2 and 3 were evidently obtained by writing the two or three horizontal dashes in one stroke from left to right.

It is not possible to trace the development of the symbols for hundred and thousand as specimens of them are not found in the earlier records. Still it may be inferred from the available materials.

A perusal of the plate will show that the Tamil numerals also were evolved from the Brāhmī, like the Grantha, the Tamil and the Vaṭṭeḷuttu scripts.

The last two columns of the plate give the specimens of the *Akṣara-palli*.

**Col. XIII**—The Vēlvikkudi plates of the Pāṇḍya king Parāntaka Neḍuñjaḍaiyan; *circa* 775 A.D. (*EI*, vol. XVII).

**Col. XIV**—The Anbil plates of Sundara Chōḷa; third quarter of the 10th century A.D. (*Ibid.*, vol. XV).

We have already said that in this system certain specified letters are used to denote the numbers. The letters used in South India to denote the numbers from one to ten are as follows: *na*, *nna*, *nya*, *ṣkra*, *jhra*, *ha*, *gra*, *pra*, *dra* and *ma* respectively. To denote eleven they write the letters *ma* and *na* (as *mana*). There are also separate letters for every ten from twenty to ninety and also for hundred and thousand.

This system is not in use now in the Tamil-nāḍu, but is still used in Malabar for numbering the leaves of manuscripts. The Malaiyāḷam script does not have separate letters for *na* and *na* as in Tamil; but uses the form *ṇ* as common for both. This is the figure we have for the numeral 1 in the Vēlvikkudi plates, while it is *ṇa* in the Anbil plates.

This system is used in North India only for numbering the leaves of manuscripts. The figures in the earlier manuscripts resemble the numerals of those days. But in the later day manuscripts the forms of these letters differ very much from the forms of the numerals then in use.

Some scholars consider the figures for the numerals found in the early inscriptions and coins as really letters having numerical values assigned to them arbitrarily. They therefore think that

the Indians originally used only certain letters assigning them numerical values and as such they had not invented signs for the numerals and that later on they adopted the forms of those letters or ligatures as the numerical signs.

This is not correct. The scholars who postulated the above proposition did not explain why only certain letters, of which many were ligatures (*dvandvākṣaras*), should be chosen for the purpose. If this theory had been correct, then the letter values of the numbers should be uniform. But this is not so. In North India the number four is represented by the letter *ṅka* while in the South it is the letter *ṣkra*. Similarly the letter *o* has the value of nine in the North while the letter *dra* has that value in the South. Thus the letters having the numerical values differ from place to place. But when written in the scripts of the particular regions, the forms for the respective numerals are very similar.

It will thus be seen that the position was the other way round. Originally the numerals were not represented with certain letters assigning numerical values to them. But when the numerals had to be expressed by the authors of literary compositions in the middle of verses, they sometimes came to use the letter having the approximately nearest form to the numeral. This is best illustrated by a verse in Tamil attributed to the poet Kālamēgha, wherein he addresses a person *eṭṭēkāl-lakṣaṇamē*, i.e., eight and a quarter *lakṣaṇas*, to call him as *ava-lakṣaṇa* or ugly, as in the Tamil numerals, eight has the shape of the vowel letter *a* and a quarter is denoted by the letter *va*.<sup>1</sup> This is how Malayagiri, the Jaina commentator of the 11th century A.D., denoted the number four as *ṅka-śabda* (the word *ṅka*) (*IA*, vol. VI, p. 47). The *Akṣara-palli* is therefore a later creation.

The Tamil numerals, it will thus be seen, have been derived from the Brāhmī.

---

1. It may also be noted in this connection that in the Tantric and astronomical works, the sun is represented by the letter *tha*. In Brāhmī this letter had the form of a circle with a dot inside. This is the well-known symbol denoting the sun all the world over.



## IX. HISTORY OF THE ART OF WRITING.

We have thus seen that the Tamil script as well as the Grantha and the Vaṭṭeḷuttu used for writing the inscriptions in Tamil-nāḍu have been derived from the Brāhmī script and that the oldest epigraphical records of the Tamil country are in Brāhmī. Then what was the script current in the area during the days of the earliest extant Tamil grammar, the *Tolkāppiyam*? Was it the Brāhmī or was there any other script, not now known?

The author of the *Tolkāppiyam* does not specify the forms in which the letters were written in his days. He simply says, *tollai vaṭivina ellā-v-eḷuttum* (All the letters are of ancient linear form). Yet he specifies the letters which had dots (*pulli*) added to them. These are the vowels short and long of *e* and *o*, both primary and medial, further shortened forms of *u*, *i* and the vowelless *m* (*kurriyal-u-karam*, *kurriyal-i-karam* and *makara-k-kurukkam*), the last answering to the description of *anunāsika*, and also the *āytam* which may be taken as something like a *jihvāmūliya* and *upadmānīya*.

Five of the vowels, *a*, *i*, *u*, *e* and *o*, have both the short and long forms. Of these, in writing the first three (*a*, *e* and *u*), additional symbols are attached to the shorter forms to denote the long. But for the other two, *e* and *o*, instead of following the above procedure, dots are added to the long forms to denote the short. Phonetically shorter forms are the primary ones and the longer ones are their development. So it is but natural to add symbols to denote the longer forms distinguishing them from the shorter ones and this has been followed in the case of the first three. Only the *e* and *o* are exceptions and the grammarian mentions only these two specifically.

As such we have to conclude that the script prevalent in those days was derived from another designed for a language which had no short *e* and *o*. Sanskrit and its allied languages have only long *ē* and *ō* and in the Aśōkan Brāhmī, we have only the longer forms of *ē* and *ō*. So it will become evident that the Brāhmī was the script that was prevalent in the Tamil-nāḍu in the days of *Tolkāppiyam*.

Then the question of the origin of the Brāhmī script would naturally arise. Before discussing that problem it is necessary to know about the origin of the art of writing in general.

Writing may be defined as the art representing one's ideas by tracing some symbols on a paper, parchment or like material for the purpose of conveying the same to another, making him understand it without spoken words or for his own remembrance of it at some later date. Like all other arts, writing also has a long history of development.

The history and development of the art of writing the entire world over, among peoples of all races, whether occupying contiguous regions of the same continent separated from one another only by a mountain barrier or developing their civilization in antipodal countries in far distant continents, seem to have progressed along lines of growth practically identical with each other.

The evolution of writing is traced to two distinctive stages, picture-writing and phonetic-writing and each of these into two again. The successive stages in the evolution have been broadly stated as follows :

1. Rude hunters' pictures.
2. Use of a picture to represent the sound of its name or some conventional object.
3. Syllabic symbols, *i.e.*, breaking down of the picture into mere sound-signs.
4. Alphabetic characters.

At the beginning, whenever a person wanted to inform another of any thing, it was done orally direct or through a messenger and where this was not possible, it was done through pictures drawn. Such occasions, in those days when civilization had not far advanced and the human wants were limited, were probably few and the matters they wanted to inform as such might have been simple things connected with their everyday life. Still when they were employed, whether as memory jogs for the scribe himself or for the transmission of messages to a distant fellow tribesman, the pictures simply recalled the objects to the mind; the special and particular meaning of the record had to be devised through a process of mental equation.

This is best illustrated by a letter in the form of a picture (Fig. 9) sent by a Cheyanne Indian of America named Truth-following-his-Wife, to his son, Little-Man, asking him to return home, and notifying him of his sending him fifty-three dollars for this purpose. (*Annual Report of the Smithsonian Institution*, Washington, for the year 1882-83). "It very clearly shows, over the head of the figure to the left, the turtle following the turtle's wife, united with the head of the figure by a line, and over the head of the other figure, also united by a line to it



Fig. 9.

is a little man. Also over the right arm of the last mentioned figure is another little man in the act of springing or advancing toward Truth-following-his-Wife, from whose mouth proceed two lines, curved or hooked at the end, as if drawing the little figure towards him. It is suggested that the last mentioned part of the pictograph is the substance of the communicaton, i.e., 'come to me', the larger figures with the name totems being the persons addressed and addressing. Between and above the larger figures are fifty-three round objects, intended for dollars."

In course of time with the attainment of a higher degree of civilization, it became necessary to express actions and abstract qualities. This is best expressed by the following picture.

Fig. 10 is an inscription painted on a cliff near Lake Superior, Canada. This records an expedition across Lake Superior, led by a chief Meda or magic maker who is shown on horseback with his magical drumstick in his hand. There were in all fifty-one men in five canoes (sixteen in the first, nine in the second, ten in the third, eight each in the fourth and the fifth canoes). The




Fig. 10.

first canoe was commanded by Kishkemunasee, the Kingfisher, whose totem is drawn above the canoes. Their reaching the other side is shown by the land-tortoise, a well-known symbol of land. That the crossing took three days to be completed is shown by the picture of three suns under the arching sky. The bird Migazee, the eagle, placed in front of the chief, is the symbol of courage.

This shows that some of the pictures have come to mean not the real ones, but some conventionalised objects. The tortoise is placed to represent land and so it is no longer a mere imitation of the object, but has become an emblem or symbol. Similarly the bird kingfisher is drawn to mean not a real bird, but a man of that name. This gives the first step towards phonetic writing, the principle of which was to make a picture stand for the sound of a

spoken word. Such symbols are largely found in China and Egypt. Thus a pair of legs is shown for walking, eye for sight, hand for power, arms for valour, and so forth.

In some languages consisting of monosyllables, like the Chinese, one word has many different meanings. To indicate in which sense the word has been used it was necessary to add some sign to it. To meet this they derived an ingenious plan of making compound characters or "pictures and sounds" in which one part gives the sound and the other gives sense. Thus

舟 游 游  
ship basin loquacity

Fig. 11.

in Chinese, the word *chow* has various meanings as ship, fluff, flickering, basin, loquacity, etc. Fig. 11 gives the characters for the sound *chow* with the meanings ship, basin and loquacity. The first character in the figure contains the figure of ship, while the second has the sign of water added to it to show that the word means a basin. The third has the character for speech joined to it to make it give the sense of loquacity.

The above represents the stages of picture-writing. In course of time the picture drawn to represent an object, came to denote the sound of the word instead of the object itself.

The next move in the evolution is like the child's game of *rebus*, that is writing words 'by things'. Thus if one writes the word 'waterman' by a picture of a water-jug and a man, this is drawing the meaning of the word in a way hardly beyond the American Indian's picture of the kingfisher. But it is very different when in a child's book of puzzles one finds the drawing of a water-can, a man being shot, and a date fruit, thus representing in *rebus* the word

pa te noch te

Fig. 12

'can-di-date'. The old Mexican and Egyptian writings give ample proof to this system of writing. Fig. 12 gives the Latin word *pater noster* written by the old Mexicans in the spelling of their language when they were Christianised. Thus they painted

a flag (*pan*), a stone (*te*), a prickly pear (*noch*) and again a stone (*te*) which were together pronounced *pa-te-noch-te*, in a way that was tolerably exact for them who had no *r* in their language.

Even this was found by the primitive man difficult to be continued. So, some of these signs were selected and they were cut down to express particular sounds from which the present alphabets were reduced. For example, the Egyptian word for mouth is *ro*. The mouth or outline of an open mouth was always used whenever they wanted *ro* or *r*. This gives an idea how the phonetic characters were reduced to mere alphabets.

The Egyptians, even after they had brought into use some figures as phonetic characters or letters, only trusted to them in part and never had the strength of mind to rely on them entirely, but combined with signs of old pictures as well. Even where words were spelt by their sounds, they had in addition what are called determinatives, which are pictures to confirm or explain the meaning of the spelt word. Fig. 13 gives an example of all these devices. It means, "I (am) the Sun-god coming forth from the horizon against his enemies." Here part of the pictures of animals and things are letters to be read into Egyptian words.










								
N	sun	god	P	horizon	R	X	enemy	F
K	one	R	M	T one		F	plural	
one		walk				T		
nuk	ra	netar	per	em	xut	er	xeftu—f	
I	sun	god	coming	from	horizon	against	enemies—his	
		forth						

Fig. 13.

But others are still real pictures, intended to stand for what they represent. The sun is shown by his picture, with a one-mark below and followed by the battle-axe which is the symbol for divinity, while further on comes a picture of the horizon with the sun on it. Beside these, some of the figures are determinative pictures to explain the words; the verb *per*, to walk, being followed by an explanatory pair of legs, and the word *xeftu*, enemies, having

the picture of an enemy after it, and then three strokes, the sign of plurality.

It may be that we are not able now to see the originals of the various characters which are used in the several alphabets. But the series of evolution in writing to suit the convenience and ease of the scribe have made them meaningless forms. In Fig. 14 will be found a few modern Chinese characters with several




Fig. 14.

examples as far as we now can judge in progressive order of development of the archaic pictures that served for written characters in the ages before conventional writing had developed. The modern character which is given on the right, at the end of the series, bears but a slight resemblance to the earliest one.

Historical and archaeological facts substantiate the belief that this evolution is practically universal. Although carried out in

symbols and signs greatly varying from each other, every great original system of national writing seems to have progressed along the same lines of development. This is best seen from Fig. 15 giving selected specimens of the earliest picture and the final conventionalised symbol of bird, fish, vase, son, gale, star and axe of

## EGYPTIAN WRITING



## CHINESE WRITING



Fig. 15

the Egyptian and the Chinese scripts. It will be seen that while the nature of transformation is quite the same in both, the ultimate symbols, except in a few individual cases, are wholly dissimilar in the two systems of writing.

One would naturally expect to find these pictographs and their subsequent developments in India also. But we do not find any such, with the exception of those discovered at Mohenjo-daro and Harappa on the study of which scholars have not yet come to a definite conclusion. Not only that. The classical literature in Sanskrit and various other languages so far made available to the scholarly world do not throw any light on this problem, not to speak of the pictographs and their subsequent developments. They all say that the script was created by Brahmā, the god of creation and refer to writing as a Divine art. But curiously enough, there are some stray references to prehistoric and pictographic writings in Ancient Tamil Literature.

The old commentary on the *Yāpparūṅkalam*, a work on Tamil prosody, mentions while commenting on the last *sūtra* of



the work, what a scholar should be familiar with mentioning the various kinds of writing and quotes the following *sūtras*.

*uruve unarve oliye tanmai-y-ena*  
*ira vagai y-eluttum ir-irand-āgum.*

The letter or writing is divided into four kinds, *uruvu*, *unarvu*, *oli* and *tanmai*; the first two forming one group and the second two another.

*kāṇa-p-paṭṭa-v-uruvam ellām*  
*māna-k-kāṭṭum vagaimai nāḍi*  
*vaḷuvil oviyan kaivinai-pōla*  
*elutappaduvalu uruvelutt-āgum.*

This *sūtra* describes the first variety *uruveluttu*. "That which is written like the handiwork of a fault-less artist (painter) by way of portraying in a grand manner the pictures of all objects just as seen is *uruveluttu*." This clearly shows that the author intended to convey the idea of picture-writing by this *sūtra*. The definition of the second, *unarveluttu*, is as follows :

*koṇḍa-v-ōr kuriyāl koṇḍa-v-atanai*  
*uṇḍenr- unarttuvalu unarvelutt-āgum.*

"That which signifies the existence of an object conceived (by drawing) a sign or symbol conventionalised to denote the same is *unarveluttu*." This definition fits in exactly with the second stage in the evolution of writing shown above.

*iṣai-p-paḍu pullin elāal-pōla-c-*  
*cevipṭulan-āvalu oli-y-elutt-āgum.*

"That which is audible to the ear like the musical note of a sweet singing bird is *oli-eluttu*." We can safely say that this is the sound-sign or syllabic symbol And the last variety is given the definition we usually find in the grammars for the alphabetic characters.

*mutar karanamum tunai-k-karanamum*  
*tunai-k-karanattoḍu toḍariya-v-unarvum*  
*avarroḍu puṇarnda-v-agattelu valiyin*  
*miḍarru p-pirant-iṣappadu tanmai y-eluttu.*

“That sound which is born in the neck by the air produced (or raised) from the inside (of the body in the effort) combined with the primary cause, the secondary cause and the sense-perception associated with the secondary cause is the *tanmai-y-eluttu*.”

It is not known wherefrom the commentator extracted the above *sūtras* for quotation and who was the author of them.<sup>1</sup>

The commentary of Mayilaināthar on the Tamil grammar *Nannūl* gives another set of *sūtras* which are also quoted in the introduction (*pāyiram*) to the commentary on *Ilakkana-k-kottu* of Svāminātha Dēśikar in the 17th century A.D. There the names of these four divisions are different and are called *vaḍivu*, *peyar*, *tanmai* and *muḍivu*. The *sūtras* are as follows :

*vaḍivu-peyar tanmai-yuṇ muḍivu nāṅkā*  
*nāḍaiṭeru nāvalar nāḍiya-v-eluttē.*

“The *eluttu* or writing sought after by *nāvalar*, the masters of the tongue (i.e., poets or scholars) are of four kinds, *vaḍivu*, *peyar*, *tanmai* and (*uṇ*) *muḍivu*”.

The first variety *vaḍiveluttu* is defined as follows :

*katpulan-illā-k-kāḍavulai-k-kāttum*  
*śaṭṭakam pōla-c cevippula v-oliyai*  
*uṭkoḷark-idum urubām vaḍiveluttē.*

“The *vaḍiv-eluttu* is the form (picture) given to bring to mind the sound audible (to the ear) like the form given to denote the god not perceptible to the eye.”

The next variety *peyar* :

*vaḍivu mudan mummaiṭin vaḷaṅgum eluttir*  
*paḍu-pala pakutikk-idupeyar peyarē.*

“The *peyar-eluttu* is the name given to the several component parts of the three varieties of letters (or writing) current in three-fold (varieties) beginning with *vaḍivu*.

1. It is also possible to take the first two of the above four as referring to the written form and the second two to the speech form of the individual letter,

The third is *tanmai y-eluttu* :

*tāna muyarci tarakkola-c-cevipṇulan*  
*āya-v-oli tanmai-y-elutt-āgummē*

“The *tanmai-y-eluttu* is the sound which is audible to the ear and produced with the place (*sthāna*) and effort.”

The last is *unmuḍiveluttu* :

*uruvamudan mummaiyoḍ onriya-v-iyalpai*  
*maruva-v-ulan tunivad-unmuḍiv-elutte*

“The (*un*)*muḍiv-eluttu* is that which is decided in mind in combination of the nature united with the three-fold (qualities) beginning with the form (*vaḍivu*).”

These are probably explanatory of the four kinds of *eluttu* mentioned in the *nighaṇṭus*. The Tamil *nighaṇṭu Divā-karam* which is assigned to the eighth century A.D. has the following :

*peyar-eluttu muḍiv-eluttu vaḍiv-eluttu-t-tanmai*  
*eluttēna v-eluttin peyar-iyambināre*

while another *nighaṇṭu*, the *Piṅgalandai*, gives :

*vaḍivuṇpeyar tanmai muḍivu nāṅk-elutte*.

Both these mention the four names, *vaḍivu* (form), *peyar* (name), *tanmai* (nature or quality) and *muḍivu* (finite). Only the order is changed. But it is clear that the authors of the *sūtras*, whoever they have been, were familiar with the successive stages in the evolution of writing.<sup>1</sup>

1. It is true that four phases of speech-sound, *parā*, *paśyanti*, *madhyamā* and *vaikharī* are described in Sanskrit Grammars, “*parā*, being that phase of the *śabda-brahman*, the undifferentiated primordial sound manifested at *mūlādhāra* or sacral plexus, *paśyanti* being that phase which is manifested at the navel and which is cognisable to Yōgins, *madhyamā* being that phase which is manifested at the heart and *vaikharī* being that phase which is manifested at the vocal organs as the articulated sound.” But these are not the ones described in the *sūtras* quoted above.

This will be further evident from 'the fact' that the word *eluttu* in Tamil denotes not only the script or letter, but also a painting. We have many instances in classical Tamil literature where the word *eluttu* has been used to indicate a painting (*Pari-pāḍal*, verse 19; *Kuruntogai*, verse 89). It will be seen from this that the ancient Tamils treated painting also as included in writing.

### Note on further references to the Pictographs in Tamil Literature

After citing the *sūtras* referring to the four stages in the development of the art of writing mentioned above, the old commentary on the *Yāpparunḱalam* (circa 11th century A.D.) writes as follows : \*

\* யாப்பருங்கலவிருத்தியில் காண்பது பின் வருமாறு :

[மகடூஉ, ஆ, பிடி, குமரி, கன்னி, பிணவு, முடுவன் என்றின்ன சிலவெழுத்தும்] அ க ச ட த ப ய முதலிய வாய்வெழுத்தும், அ ச ல வ ர ற ய முதலிய இராசி யெழுத்தும், கார்த்திகை முதலிய நாளெழுத்தும், தோப<sup>1</sup> முதலிய நால்வகை எழுத்தும், சாதி முதலிய தன்மையெழுத்தும், உச்சாடன<sup>2</sup> முதலிய உக்கிரவெழுத்தும், சித்திர காரடம் முதலிய முத்திரவெழுத்தும், பாகியல்<sup>3</sup> முதலிய நால்வகை யெழுத்தும், புத்தேள் முதலிய நாற்கதியெழுத்தும், தாது முதலிய வொளி<sup>4</sup> யெழுத்தும், மாகமடையம்<sup>5</sup> முதலிய சங்கேதவெழுத்தும், கலி<sup>6</sup> முதலிய சங்கேதவெழுத்தும், பார்ப்பான் வழக்காகிய பதின் மூன்றெழுத்தும், என்று இத்தொடக்கத்தனவும், கட்டுரையெழுத்தும், வச்சிர முதலிய வடிவெழுத்தும், மற்றும் பல வகையாற் காட்டப்பட்ட எல்லா எழுத்தும் வல்லார்வாய்க் கேட்க.

இருதலைப் பகரத்திற்குள் அடங்கிய பகுதி அச்சப் பிரதியில் காண வில்லை. பழைய எட்டுப் பிரதி ஒன்றில் கண்டதாகப் பண்டித மு. இராகவையங்கார் கூறுவர் (ஆராய்ச்சித் தொகுதி, பக்கம் 139). அன்றி, பின்வரும் பாடபேதங்களும் அவர் கொடுத்தனவே.

1. தோபதம், தேர் பதம்.
2. முச்சடரண.
3. பரசினாகிய.
4. யோனி.
5. மாக மடையம்,
6. கலி,

"The *āya-eluttu* like *a, ka, ca, ta, pa* and *ya*; the *irāsi-eluttu* like *a, ca, la, va, ra, na* and *ya*; the *nāl-eluttu* like the *kārttikai*; the four kinds of letters like *tōṇam*, the *taṇmai* letters like the *cāti*; the *ugra* letters like the *uccāṭaṇam*; the *muttira-v-eluttu* like the *cittira-kāruḍam*; the four kinds of letters like the *pākiyal*; the *nārkaṭi* letters like the *puttē!*; the *oḷi-y-eluttu* like the *tātu*; the *saṅkēta* letters like the *mākta-maṭaiyam*; the *saṅkēta* letters like the *kali*; thirteen letters of the *pārppān-valakku* (brāhmaṇa usage); and so forth (commencing with this), the *katturai-y-eluttu*, the *vaḍiv-eluttu* like the *vacciram* (*vajra*) and all the other letters denoted in so many ways, learn (or should be learnt) through the (mouths) of experts."

The above passage, though full of scribal errors and variant readings, is still interesting. It narrates fifteen kinds of *eluttu* and these have not been explained anywhere.<sup>1</sup>

It is to be noted in this connection, that the Buddhist and Jaina literature of which we shall speak in the next chapter mention also the names of several scripts prevalent in this country in the pre-Christian era. The Jaina *sūtras* mention the names of the following eighteen.

1. Bāmbhī (Brahmī)
2. Yavanālī or Yavaṇāliya
3. Dosapuriya (or Dosapurisa)
4. Kharotthi (Kharoṣṭhī)
5. Pukkharasariyā
6. Bhōgavaiyā
7. Paharaiya (or Paharaiyā)
8. Uya-āmtarikkhiyā (Uyāmitara Kariya)
9. Akkharapiṭṭhiyā (Akkharapumṭṭhiyā)
10. Tēvanaiyā (or Vēnaiyā)
11. Gi(ni?)nhaiyā (or ṇhinittiyā)
12. Aṃkalivi (or Amkalikkha)
13. Gaṇitalivi (or Ganiyalivi)

1. This was originally discussed by me more than twenty years ago in a paper *The Pictographs in Tamil Literature* read and discussed in *The Archaeological Society of South India* at Madras on the 18th December 1935.

14. Gamdhavva-livi
15. Ādamsalivi (or Āyasa-livi)
16. Mahēsari (or Māhassari)
17. Dāmili
18. Polimdi

The above names are in Prākṛit and they have also variant forms. The bigger list in the Buddhist work *Lalitavistara* contains the following sixty-four names which are in Sanskrit.

- |                          |                                |
|--------------------------|--------------------------------|
| 1. Brāhmī                | 34. Cakralipi                  |
| 2. Kharōṣṭhī             | 35. Vāyumaru lipi              |
| 3. Puṣkarasāri           | 36. Bhaumadēva lipi            |
| 4. Aṅga lipi             | 37. Antarikṣa lipi             |
| 5. Vaṅga lipi            | 38. Uttarakurudvīpalipi        |
| 6. Magadha lipi          | 39. Uparagaḍa lipi             |
| 7. Maṅgalyalipi          | 40. Pūrvavidēha lipi           |
| 8. Maṇuṣyalipi           | 41. Utkṣēpa lipi               |
| 9. Aṅguliya lipi         | 42. Nikṣēpa lipi               |
| 10. Śakarīlipi           | 43. Vikṣēpa lipi               |
| 11. Brahmavallīlipi      | 44. Prakṣēpa lipi              |
| 12. Drāviḍa-lipi         | 45. Sagara lipi                |
| 13. Kanarīlipi           | 46. Vajra lipi                 |
| 14. Dakṣiṇalipi          | 47. Lēkhaṇapratiḷekha lipi     |
| 15. Ugralipi             | 48. Anudruta lipi              |
| 16. Samkhyalipi          | 49. Śāstravartā lipi           |
| 17. Anulōmalipi          | 50. Gaṇāvartā lipi             |
| 18. Urdhva-dhanur lipi   | 51. Utkṣēpavartā lipi          |
| 19. Daradalipi           | 52. Vikṣēpavartā lipi          |
| 20. Khasyalipi           | 53. Pādālikhita lipi           |
| 21. Cīna lipi            | 54. Dviruttarapada—            |
| 22. Hūṇa lipi            | Sandhīlikhita lipi             |
| 23. Madhyakṣara-Vistara- | 55. Daśōttarapada—             |
| 24. Puṣpa lipi           | lipi Sandhīlikhita lipi        |
| 25. Dēvalipi             | 56. Adhyaharīṇi lipi           |
| 26. Nāgalipi             | 57. Sarvarutsamgrahaṇi lipi    |
| 27. Yakṣalipi            | 58. Vidyānulōma lipi           |
| 28. Gandharvalipi        | 59. Vīmīṣṭa lipi               |
| 29. Kinnara lipi         | 60. Rṣitapastapta lipi         |
| 30. Mahōragalipi         | 61. Dharaṇīprēkṣaṇa lipi       |
| 31. Asuralipi            | 62. Sarvaśuṣadha niṣyanda lipi |
| 32. Garuḍalipi           | 63. Sarvasārasaṃgrahaṇi lipi   |
| 33. Mṛgacakralipi        | 64. Sarvabhūta rudgrahaṇi lipi |

A perusal of the above lists will show that there are many names therein which are identical to those found in the Tamil commentary and a careful study would show that both of them are complementary to one another. Let us take up the study of the terms found in the Tamil commentary one by one.<sup>1</sup>

(i) *āya-v-eluttu* : The word *āyam* means income, profit, etc. In epigraphy and literature it is used also to denote the taxes, tolls or customs. Evidently the term represented the symbols or signs marked on merchandise on which tolls or customs duties were leviable. There is mention of one variety of script (*livi*=*lipi*) known as *Āyasa* or *Ādamsa*, which sometimes is taken to mean bitten, that is, incised or otherwise marked with an iron instrument by deriving it from *aya* or iron. But in view of the Tamil commentary it may be derived from the word *āya*. Thus these two seem to be related.

(ii) *irāsi-y-eluttu* : The word *rāsi*, among other things, represents the zodiacal signs. We know in astronomy and astrology, various symbols are used to denote the particular zodiacal houses and the planets. It is also known that these two branches of science were far advanced even in ancient times and this would certainly have necessitated the use of some such symbols or signs. Evidently these are the symbols referred to here.

(iii) The third is *nāl-eluttu* : The word *nāl* at present denotes a day. In former times it had the meaning of an asterism or star. It may even be said that the meaning of day was derived from the other meaning of star. This will be evident from the popular saying in Tamil, *nāl enna śeyyum, kōl enna śeyyum*? (What will the star do and what will the planet do?). Kārttikai is the stellar constellation Pleiades and it is also known that this *nakṣatra* was the starting point in calculation in ancient days. This item also should therefore be taken as relating to astronomy and astrology.

---

1. According to Pandit M. Raghava Aiyangar the following is found at the beginning of this passage in one of the manuscripts, though it is not found in the printed edition: "Some letters like *magadūu*, *ā*, *piḍi*, *kumari*, *kanni*, *piṇavu*, *muḍuvān* etc." The words *magadūu*, *kumari* and *kanni* represent the women in three stages, fully grown woman, young girl and adolescent; *ā* is a cow; *piḍi* is the female of the elephant, deer, etc.; *piṇavu* is the bitch, sow, she-yak, etc. while *muḍuvān* is a bitch. Thus all these are the names of the females of the several species.

The Buddhist list given above mentions *gaṇita-lipi*, *gaṇāvarta lipi* and *saṃkhyā lipi* or *aṅkalipi* connected with mathematics and astronomy, though what exactly each meant cannot be made out at present except by way of conjecture.

(iv) Then comes *tōṣam*. This word, it seems, has variant forms read variously as *tēr-ṭaṭam*, *tōṣaṭam*, etc. But the printed edition has only *tōṣam*. This seems to be the Tamil form of the Sanskrit word *sthōba*, which means the additional sounds or letters employed in chanting the *Sāma Vēda*. These are not usually found printed in the texts of the *Vēdas*, but used only while chanting them. There are three modes of chanting the *Sāmavēda*, reciting the bare text (*ṛk*), reciting the text combined with the *sthōba* and chanting the *sthōba* alone without the text. We have elaborate rules in the *Sāma-tantra* in this respect. That some symbols were used in the manuscripts of the *Vēda-saṃhitas* to denote the modes of chanting will be evident from the use of marks for *udātta*, *anudātta*, *svarita* and *pracaya* in the manuscripts. It is also known that there are different modes of singing the same verse (*ṛk*) in the different *vēdas*. Probably 'the four kinds like the *sthōba*' mentioned by the commentator refer to the four different systems of symbols used for the four *vēdas* respectively.

(v) The word *taṇmai* means the nature or quality and the other word *cāti* (*jāti*), the caste or class. Probably there were separate symbols in early days to denote the different classes into which the several things or materials were divided according to the nature or quality of each. It is also to be noted in this connection that the works on Tamil prosody known as the *pāṭṭiyal*, of which there are a few and all of them later than the date of this commentary, classify the letters of the alphabet as belonging to any one of the four traditional *varṇas* like the *brāhmaṇa*, *kṣatriya*, and so forth following the division of the society then prevalent. This is probably due to the fact that the real sense in which the commentator had used this term was then unknown having been forgotten.

The Buddhist list mentions several *lipis* as *gandharva-lipi*, *nāga lipi*, *yakṣalipi*, *kinṇaralipi*, *garuḍa lipi*, etc.

(vi) The *ugra-v-eḷuttu*. The word *ugra* denotes fiery or ferocious and the word *ucchāṭana* signifies the incantation of *mantras* repeatedly. These are mainly used in the *tantrik* worship and other rites relating to it where several mystic symbols are used. Evidently this has a reference to such symbols. The *ugra-lipi* is also mentioned in the Buddhist list given above, where it is sometimes taken as the script



prevalent among the tribal people known as the Ugras. But the Tamil commentary clearly indicates this term as relating to the Tantrik symbol. The variant reading of *muccūṭaraṇai* for *ucchāṭana* does not make any sense.

(vii) The *muttira-v-eḷuttu* like the *cittirakāruṭam* : The expression *muttira-v-eḷuttu* would mean the three varieties of letters. But what *citra-kārūḍam* means is not known. It is suggested that this may be read as the *muttirai-y-eḷuttu*, i.e., the letters of the *mudrās*. Similarly the expression *cittirakāruṭam* does not make any sense. Probably it is to be read as the *citra-karaṇam* which would then mean artistic expression of hands which are also known as *mudrās*. These are used extensively in dancing and in playing the percussion instruments of music like the *mridaṅga*.

(viii) *pākiyal* : This word is used in the Tamil work *Peruṇ-kathai*, a version of the *Bṛihad-kathā*, as the language of the *māhouts* in training elephants. That such a system existed in those days is vouched in the Tamil work *Jivaka-cintāmaṇi* and the commentary of Naccinārkkīṇiyar on the *Pattuppāṭṭu*. Even to-day, we find an unwritten language among such trainers in India. Four varieties of scripts have been mentioned as allied to this. We are at present unable to say what these four represent.

(ix) *puttēḷ* means the celestials, and *nār-kati* the four *gatis* (mode of transmission). We also hear of *Dēva-gati*, *manuṣya-gati*, *asura-gati* and *naraka-gati*. Probably these four are intended here. But what exactly the symbols portrayed or how they were used is not known. The Buddhist list mentions an *antarikṣadēva lipi*, the script of the gods of the sky.

(x) *Dhātu* means the minerals, metals and red ochre, while *ōḷi* means brightness and secrecy. It is possible that this refers to secret writing by means of some minerals which may not show themselves openly. There are many references to such writing in the *Arthaśāstra* of Kauṭilya and various other works. Alternately, it may mean writing which is made bright by the use of mineral colours. But the former seems to be the intended one. Or, is it possible that this denotes the classification of the minerals in the same way as the elements are classified in the modern Chemistry? An alternative reading *yōni* has been suggested for the word *ōḷi*. The word *yōni* has to be taken as used in the sense of birth. In the works of Jaina cosmology, even the minerals are classified according to colours and assigned different births or *yōnis*.

(xi and xii) These two refer to two varieties of *saṅkēta* writing which means a conventionalised or suggestive form of cryptic writing without plainly expressing it. There are such writings in every branch of science and there are many *paribhāṣās* or code-words for each one. The *saṅkēta lipi* is also mentioned in the lists given above.

The word *mākamataiyam* has variant readings *mākamadiyam*, *māśu-matiyam*, *māśu-madaiyam*, etc. Probably *mākha madiyam* is the form, in which case *mākha* means the sky and *madiyam* the moon. These two denote the numerals, cypher and one respectively, according to the *Bhūtasāṅkhyā*. We have already seen that this system is used in epigraphy frequently to denote the dates. The other system adopted in the dating of inscriptions is the *kaṭapayādi*. Originally the dates in this system were expressed in the Kali era and only later on it was changed to the Śaka era. Evidently the *saṅkēta* letters like the *kali* mentioned by the commentator represent this usage. There is a variant reading of *kavi* for *kali* in which case it would mean such cryptic usages in poetry.

(xiii) The thirteen letters of Brahmaṇa usage evidently refer to some letters of the Sanskrit language. In the word-numeral system of *Bhūtasāṅkhyā*, thirteen is referred to as *aghōṣa*, the surd consonants. Evidently they are the intended letters. Varieties of scripts known as *Brahmavalli lipi* and *Bhaumadēva lipi* (script used by the gods on the earth, i.e., the *brāhmaṇas*) are also mentioned.

The commentator classes these thirteen varieties in one group and then goes on to describe two other kinds.

(xiv) Of these the first is *kaṭṭurai-y-eluttu*. The word *kaṭṭurai* though now denotes only essays, or *Belles-Lettres*, meant in the earlier days figurative language or pithy, sententious expression: The northern list gives *śāstrāvarta lipi* as the name of a script.

(xv) *vaḍiv-eluttu* denotes, as we have seen above, evidently the pictograph and *vajra*, the thunder-bolt. A variety named *vajra lipi* is mentioned in the list of scripts found in the Buddhist work.

With the exception of the last two which probably mean the alphabetic and pictographic writings respectively, all the other thirteen refer to special signs and symbols which were used in writing but which did not find place in the Tamil alphabet.

## X. THE ANTIQUITY AND ORIGIN OF THE BRAHMI.

The Brāhmī script was fully developed from the earliest times we know of. But the period when it attained the complete and standard form is not known. However, from early literature it is found that different kinds of scripts were even then prevalent in the country.

The early Jaina works, *Samavāyāṅga sūtra* (traditional date circa 300 B.C.) and *Paṇṇāvaṇā sūtra* (traditionally, 168 B.C.) mention that eighteen kinds of scripts were then in use in the country.<sup>1</sup> Among the Buddhist works the *Mahāvastu* gives a list of thirty names, while the *Lalitavistara*<sup>2</sup> states that sixty-four kinds of scripts were in use in the country in the days of Buddha and gives their names. The numbers eighteen, thirty, sixty-four, etc., are considered auspicious and some scholars hold the view that these numbers should not be taken seriously. Still these clearly show that many varieties of scripts were in use in the land even in those early days.

Many of the names given in the those lists are identical. Of them the following four seem to be important and historically true.

1. Brāhmī or Bambhī
2. Kharoṣṭhī or Kharoṭṭhī
3. Drāviḍi or Ḍāmili
4. Yavaṇāṇiyā or Yavaṇāliyā

In addition to these the Jaina list has the name of another Puṣkarasārī or Pukkarasārīyā. Pāṇini's grammar, Āpastamba's *Dharmasūtra* and other works mention Puṣkarasādi or Pauṣkarasādi as one or several ancient teachers of *Dharmaśāstras* and *Vyākaraṇa*.

---

1. The *Bhagavatsūtra*, another Jaina work, has *Namō Bambhīye liviye* (Salutation to the Brāhmī script).

2. It is a work in Sanskrit dealing with the life of Lord Buddha. It is not possible to fix its date exactly. But as it was translated into the Chinese in 308 A.D., it must belong to a time at least one or two centuries earlier.

It is possible that Puṣkarasārī was the alphabet newly invented or an existing one modified by a member of the group. From this it can be taken that the names in the list are genuine.

Of the four mentioned above, *Yavanāṇḍiyā* is evidently the writing of the Yavanas or Greeks and identical with *Yavanāṇi* mentioned by Pāṇini and explained as such by his commentator Patañjali. Kharoṣṭhī was used in the North Western parts of India and that too before *circa* 400 A.D., after which it disappeared completely. These two varieties were not known in South India. So these two are not included in our study here. Foreign scholars think that Drāviḍī was the southern form of the Brāhmī, like those at Bhaṭṭiprōlu. We shall revert to it later.

According to the tradition of both the Hindus and the Jainas writing was invented by Brahmā and the scripts were his creation. This view is also found recorded by Yuan Chwang, the Chinese pilgrim who visited this country in the middle of the seventh century A.D. The Chinese encyclopaedia *Fa-Wan-Shu-lin* states that the Indian script running from the left to the right (Brāhmī) was the creation of Brahmā (*Fan*) and it was the best of the scripts.

It is probable that this story was the outcome of the name Brāhmī being given to this script or it may be due to the custom of attributing the origin of a particular thing, of which nothing is known, to the creator Brahmā. The image of Brahmā in the rock-cut temple at Bādāmi (Vātāpi) of *circa* 580 A.D. holds in one of his hands a bundle of palm-leaves. The *Nārada-smṛiti*, a redaction of the *Manusamhitā* and the *Vārttika* of Brihaspati on *Manu* also mention the above. Relying on the above some scholars believe that the Brāhmī script originated in India itself.

But some of the western scholars maintain that it was not invented in this country, but borrowed from some foreign source. Al Bērūnī, the Arabian traveller of the 11th century A.D. says that the Hindus had once forgotten the art of writing, and through a divine inspiration, it was rediscovered by Vyāsa, the son of Parāśara and the author of the *Mahābhārata* and the eighteen *purāṇas*. This story is sometimes taken by those scholars as indicating that the script was derived from a foreign source.

Believing that the Brāhmī script should have been borrowed by the Indians from a foreign country, scholars have sought to identify the place from which it might have been borrowed.

Terrain de la Couperie thought that the original source of the Brāhmī is to be sought in the Chinese picture-writing. It is well known that the Chinese writing had not attained the alphabetic stage, while the Brāhmī had fully developed. As such this theory need not be discussed. In fact, nobody seems to have bestowed serious thought over it and it was discarded long ago.

Wilson hazarded the guess that "Aśoka's Buddhists derived their letters from Greek or Phoenician models". Princep and others took the first view that Brāhmī was derived from the Greek alphabet, while scholars like Weber and others postulated a Phoenician origin to Brāhmī. But the chronological and philological difficulties are very formidable and have never been successfully answered. It cannot be said that the Phoenician and the Brāhmī scripts are in the relation of the parent and the child.

Deecke thought that it was derived from the Assyrian Cuneiform through the South Semetic (which was also the parent of the Sabaen or Himyaritic script) as an intermediate step, and Tylor held the view that a lost South-Arabian alphabet, the predecessor of the Sabaen, was its parent. To connect the Brāhmī with the Assyrian Cuneiform is too fanciful to be seriously considered. Further the Sabaen characters of a period earlier than the second century B.C. have not been recovered so far and, the earlier writing found there is like the Phoenician alphabet. Again, there is great difference phonetically also between the Brāhmī and those scripts.

Halevy maintained that it was derived from a mixture of Aramaic, Kharoṣṭhī and Greek letters of the last quarter of the fourth century B.C. But we know that the Brāhmī script had been in existence even before that period.

Finally, Buhler derived the script from the North Semetic. He was the greatest champion of this theory and even today his opinion finds favour with many of the foreign scholars who believe that Western Asia and Egypt were the homes of civilization

and culture. Dr. David Diringer, a recent writer on the subject, also advocates the same theory (*The Alphabet*, pp. 336-7). "All historical and cultural evidence is best co-ordinated by the theory which considers the early Aramaic alphabet as the prototype of the Brāhmī script. The acknowledged resemblance of the Brāhmī signs to the Phoenician letters also applies to the early Aramaic letters, while in my opinion there can be no doubt that of all the Semetics, the Aramaean traders were the first who came in direct communication with the Indo-Āryan merchants."

It is generally accepted that the Kharoṣṭhī script was derived from the North Semetic. But the Brāhmī for which the same parentage is sought to be fixed and the Kharoṣṭhī differ very much from each other.

The marked characteristics of the Kharoṣṭhī may be enumerated as follows :

(1) The letters are generally thin and long, more or less slanting to the right, with appendages attached to their upper parts.

(2) The letters are very irregular in shape and size, and many forms are confusingly similar.

(3) The script is clearly cursive.

(4) There are very few looped forms.

(5) The script always runs from right to left.

On the other hand the following are the chief characteristics of the Brāhmī as given by Buhler himself.

(1) The letters stand up-right.

(2) The letters are made up of regular lines and loops.

(3) The letters hang down, unlike the Kharoṣṭhī which are top-heavy.

(4) Most of the vowel signs are added at the top in the shape of horizontal lines.

To these we may also add :

(5) It is generally written from left to right.

(6) And finally, the script is distinctly monumental and decorative.

From this it does not appear very probable that two such fundamentally different alphabets could have been derived from the same source, especially when we bear in mind the fact that they were both needed for the same purpose and practically the same language.

To overcome this difficulty it has been suggested that while Kharoṣṭhī came overland through Gāndhāra, the Brāhmī came by the sea through Babylon *via* the Persian Gulf. It is also accounted for by the fact that one was a 'clerk's alphabet' also used by the merchants while the other had been elaborated by the learned Paṇḍits.

Scholars postulating the same North Semetic source to both the Brāhmī and the Kharoṣṭhī scripts are not able to derive the same letter in both from the same original source. In Kharoṣṭhī, all the vowels were derived from the letter *Aleph*, the first in the Semetic alphabet. But in the Brāhmī, only the first two, *a* short and long, were derived from the letter *Aleph*; the vowel *e* from the deep glottal Semetic letter '*Ain*', and the vowels *i*, *ī* and *ai* were in turn derived from this *e*; while the vowels *u*, *ū* and *o* were derived from the Semetic letter *Vau*. Similarly, the consonant *gha* of the Kharoṣṭhī was derived from the Semetic letter *Gimel* while that of the Brāhmī from the Semetic *Cheth*. Further phonetically the originals and the derivatives differ very much. In the Sanskrit language the vowel *e* is the derivative (*guṇa*) of the vowel *i*; and while it is so, to say that the letter of the vowel *i* was derived from that of *e* would certainly be not acceptable. To say that the accurate and even 'pedantic' phoneticians of India, evolved the Brāhmī from the Semetic in complete disregard of phonetics clearly makes a very large demand on our credulity.

Thus among the several theories advocating foreign origin to the Brāhmī script none is found satisfactory or acceptable. Finally there is the theory of the indigenous origin of the script.

This theory was first suggested by Lassen and was strongly upheld by Cunningham and others. But subsequently, no serious notice was taken of this opinion and there was not much support for this among the scholars many of whom held that Egypt, Sumeria and Babylon were the home-land of ancient civilization and culture. They decided that the Brāhmī script could not have been the indigenous product of India and advanced the following three important objections against such a contention.

(i) A fully developed and an almost perfect alphabet like the Brāhmī is impossible without long preceding years of growth. No such evidence is available.

(ii) The practical uniformity of the Brāhmī script in the inscriptions of Aśoka clearly points to the absence of variety in the script. If it had been indigenous, its origins must be taken back to quite a hoary antiquity, and in that case we might naturally expect quite a large variety of scripts in those days. This also is absent.

(iii) The Brāhmī script falls into groups based on the written forms of the letters and this will show that it contains letters which have been obviously derived from others. These derivatives represent sounds which had no original forms, and will thus clearly show that the script was borrowed from a script which had no letters representing such sounds and that additional forms had to be invented to write them.

Of the above the first two can no longer be maintained.

I. It is true that at the time when the above proposition was made no writing earlier than those in the Brāhmī had been found in India. Since then, numerous seals and other objects with pictographs have been recovered from Mohenjo-daro and Harapppa. K.P. Jayasval even claimed a connecting link between the pictographs and the Brāhmī in the record from Vikramkhōle in Central India (*IA*, vol. LXII). We have also seen above that



references to pictographs and sound signs are found in early Tamil literature. Further, references to the *Kaṇ-ṇ-eḷuttu* in the *Śilappadikāram* and to the various other symbols and signs in the commentary on the *Yāpparuvāḱalam* have also been noticed. This objection cannot therefore be maintained any longer.

II. As regards the other, it has already been pointed out that even in the days of Aśoka there had been several varieties of the Brāhmī script falling into two distinctive groups, the northern and the southern. That several other kinds of script were then prevalent in the country is known to us from literature. It may be that inscriptions in those varieties have not been recovered. But we have the records of Bhaṭṭiprōlu. Further, we have not so far traced any record of an earlier antiquity in the Tamiḷ-nāḍu, but it does not mean that writing was then unknown here. It is possible that such records have been lost due to various reasons or await discovery.

III. The third objection will appear to a certain extent formidable.

Fig. 16 gives the Brāhmī script arranged in groups, in accordance with their written form. A scrutiny of this will bring out the following characteristics of the script.

(i) The short and long vowels are obviously connected, long ones being formed with the addition of a symbol to the short ones.

(ii) Of the vowels, only *a*, *i* and *u* are the primary ones; the *guṇa* vowels, *e* and *o*, are obtained from the corresponding simple ones, *i* and *u* respectively.

(iii) The *vrddhi* vowel *ai*, though obtained from the *guṇa* vowel *e* in the Northern Brāhmī, appears to be connected with the corresponding consonant *ya* in the south.

(iv) The aspirated form of the consonants are derivable from the corresponding unaspirated ones. It may even be said that the *vargga* letters are derived from the primary ones.

(v) The cerebrals and dentals are closely connected with each other. In the case of *ṭha* and *tha*, the only difference is the addition of a dot in the centre of the former. The late Mahāmāhō-

padhyāya Dr. Hara Prasad Sastri says that in the Pali language, as it was current in the days of Lord Buddha, there was no

1	𑀓 𑀔	1. a ā
2	𑀕 𑀖 𑀗 𑀘 𑀙	2. i ī [i] e ai
3	𑀚 𑀛 𑀜	3. u ū o
4	𑀝 𑀞	4. ka kha
5	𑀟 𑀠 𑀡 𑀢	5. ga gha [gha] ha
6	𑀣 𑀤 𑀥	6. ca cha śa
7	𑀦 𑀧	7. ja jha
8	𑀨 𑀩 𑀪 𑀫 𑀬 }	8. ṭa ṭha ḍa ḍha
9	𑀭 𑀮 𑀯 𑀰 }	9. ta tha da dha
10	𑀱 𑀲 𑀳 𑀴 𑀵 [𑀶]	10. na ṇa ña ña [ṇa]
11	𑀷 𑀸	11. pa pha
12	𑀹 𑀺 𑀻 𑀼	12. [ma] ma ba bha
13	𑀽 𑀾 𑀿	13. ra la va
14	𑀿 𑀻	14. ya [ai]
15	𑀼 𑀽	15. ṣa sa

Fig. 16

difference between the dentals and cerebrals and that it had only one in the place of both of them.

(vi) The nasals are all obviously connected.

The above will show that the Brāhmī script was designed not for the Sanskrit language, but for a language in which among the vowels, the three, viz., *a*, *i* and *u*, are the primary ones, and in which among the hard consonants only the primary or the first ones remain and the *vargga* letters are absent, and that later on when the script was adapted for the Sanskrit and its allied languages, special forms had to be invented for the additional sounds. Among the Indian languages these characteristics are found only in the Tamil language.

Then is it possible that the Brāhmī script was originally intended for the Tamil language ?

The earliest writing known in India is that discovered in the Indus Valley at Harappa and Mohenjodaro. It is generally believed by some scholars that the Indus Valley civilisation was pre-Aryan, and therefore non-Aryan, or the Dravidian. They therefore surmised that the people, their language and the script of the pre-historic Indus Valley were Dravidian. The main difficulties in accepting this view are :

(i) The pictographic scripts of the Indus Valley are not found elsewhere in India.

(ii) We do not know anything about the proto-Dravidian language spoken or written in the days of the Mohenjodaro, the fourth or third millenium B.C.

(iii) And the earliest specimen of writing posterior to the Indus Valley script is found in Northern India and not in the South where the bulk of the Dravidian people live.

It is possible to contend as against the above that a large number of pieces of prehistoric pottery inscribed with written signs which are probably alphabetic in value have been discovered in the erstwhile Haiderabad State (*The Journal of the Haiderabad Archaeological Society*, 1917, pp. 57 ff; also *Sir Asutosh Mookerjee Silver Jubilee volume III* (Orientalia), 1, pp. 493 ff.), and also of ancient coins with similar signs in the Tirunelveli district, the extreme south of the peninsula (*Mysore Arch. Report*, 1935). But it should be noted that these pottery marks have not been satisfactorily worked out. These do not bear much resemblance to the Indus Valley signs and their phonetic values are not known. It is also said that no excavation in the south and intermediary regions has revealed such material (epigraphic or otherwise) of such antiquity as to be connected with the Indus Valley. But recent excavations have shown that the Harappa sites occur further south in Saurāshṭra (*Indian Archaeology, A Review*, 1954-55). Further, references to prehistoric writing are found in Tamil literature and not in any other language in the whole of this sub-continent.

Some scholars do not think the pictographic writing of the Indus Valley as the parent of the Brāhmī. On the basis of the resemblance between the Indus Valley script on one hand and the Sumerian, Minoan and the Elamite on the other, many scholars are inclined to suggest that the Indus Valley script was imported into India from Western Asia. (L. A. Waddell, *The Indo-Sumerian Seals Deciphered*). The values of the Sumerian characters are known. But they do not fit in with those found in India. Further these signs are also found in the Easter Islands on the South American coast. We have seen above that the pictographic writing all the world over should have been evolved on the same lines and it is therefore no wonder that similarities of form are found in the specimens of pictographs wherever found even from lands far distant apart. But these can be interpreted only through the language and culture of the respective countries.

Even the direction in which the Indus Valley script is written has not been satisfactorily decided. The majority of the scholars opine that it is written from right to left. But the Rev. H. Heras, the strongest advocate of theory of the the Tamiḻ origin for this script, read them from left to right.

Even taking it for granted that it was from right to left it cannot be viewed as a serious obstacle in holding that these signs were the parents of the Brāhmī. We have one or two early specimens like the Eraṇ coin with the writing from the right to left.

Before proceeding further with the question of determining the language for which the Brāhmī script was designed, it is necessary to know about the language in which the earliest Brāhmī inscriptions are written. The Aśōkan inscriptions which are the earliest records are in the Prākṛit language. In fact all the early inscriptions recovered so far in India are in the Prākṛit language. Sanskrit appeared to take its place from the first or second century A.D. in the North Western portion of India and then gradually subsequent in other areas. Even then Prākṛit lingered on for some time and its influence was clearly perceptible in early Sanskrit inscriptions. It finally disappeared from *circa* the fourth century A.D. The very fact that Prākṛit was employed for writing inscriptions even in South India, as evidenced

by the Aśoka edicts found at Māski, Siddhapura, Brahmagiri, Yerragudi and Rājula-Mandigiri and by the early charters of the Pallavas of Kāñchī, would clearly show that it was the official language of the administration.

The *Paṇṇavaṇā-sutta*, already referred to, divides the Āryas into nine classes, the sixth of which is the *bhāsāriya* 'Āryan by language.' It is said of them: 'They are Āryan by language who speak the Ardhamāgadhi language (the Prākṛit in which Mahāvira is said to have preached the Jaina religion) and with whom the Brāhmī script is customary.' This implies that the Prākṛit was written in the Brāhmī script.

To decide whether this script could have been designed for the Prākṛit language it is necessary to know more about this language and also whether it exhibits the peculiarities pointed out above.

Prākṛit is not the name of a single language. Several languages are grouped as belonging to the variety of Prākṛit which in the wide sense also includes *Pālī*, the language of the early Buddhist literature. *Mahārāṣṭrī*, *Saurasēnī* and *Māgadhi* are the best known of them. It is generally considered that these represent the dialects spoken in the respective areas: *Mahārāṣṭrī* in the Mahratta country in the south, *Saurasēnī* in the Madhya-dēśa (the middle country) or Śūrasēna, the region round Mathurā (Muttra), and *Māgadhi* in the Magadha in the east.

Mārkaṇḍeya (circa 17th century A.D.), the author of *Prākṛita-sarvasva*, divides Prākṛit into four classes: *bhāṣā*, *vibhāṣā*, *apabhramśa* and *paiśāca*. The *bhāṣā* group includes Mahārāṣṭrī, Saurasēnī, Māgadhi and other dialects. As *vibhāṣā*, he mentions sub-dialects, Śākārī (based on Māgadhi), Cāṇḍālī, Śābarī and the like. He mentions twenty-seven varieties as *Apabhramśa* or later development of the Prākṛit which had in the meanwhile become literary and rigid. It is generally taken that these *Apabhramśa* varieties formed the starting point for the modern North Indian dialects. We shall speak of *Paiśāci* later.

Of the three important Prākṛits mentioned above, *Saurasēnī* is the ordinary Prākṛit of the Sanskrit dramas and is the nearest to classical Sanskrit. But *Mahārāṣṭrī* is regarded as the Prākṛit

*par excellence*. The Prākṛit grammars also give the rules for this dialect first. For others, their special rules are given and then 'the rest is like Māhārāṣṭrī' (*śeṣam Māhārāṣṭrīvat*).

Prākṛit language is freely used in Sanskrit dramas. Strictly Sanskrit dramas are not in that language alone, but are Sanskrit-Prākṛit ones. The hero and the characters representing learned men speak in Sanskrit while the others do in Prākṛit. Even here we find a convention. Female characters and the *vidūṣakas* are made to converse in Śaurasēnī, while Māhārāṣṭrī is the corresponding verse dialect. Māgadhī is used by the menials, foreigners and the like. But this convention too does not seem to be strictly observed by the authors. They also confuse the dialects, so that Māgadhī appears almost the same as Śaurasēnī. This mixture of languages in the Sanskrit dramas has been much discussed.

These dialectical differences appear to have existed even in the third century B.C. and this becomes clear from the inscriptions of Aśōka which have different versions. The word *lekhāpita* appearing in his First Rock Edict at Girnār is found as *likhapita* at Mansēhra, *likhāpita* at Jaugada and *likhapitu* at Shāhbāzgarhī. But still the edicts were understandable in all those places. We may therefore take it that in spite of these dialectical variations, the Prākṛit of Aśōka's inscriptions was read and understood throughout the country in his days.

The earliest recorded Prākṛit is that found in the inscriptions of Aśōka in the third century B.C. But the inscriptions are not included in the study of literature. Then the extant Prākṛit literature comprises the Pālī Canon of the 'Southern' or Hinayāna Buddhists, the Prākṛit Canon of the Jainas, the Prākṛit of Lyrics, Epics and Plays and the Prākṛit Grammars.

The Pālī *Tipitaka* or 'Triple-Caskets' as also the *Jātakas* or the Birth stories of the Buddha contain the oldest surviving scriptures of that religion.

The oldest Jaina books are in the *Ardha-Māgadhī*. The older books called *Pūrvas*, on which these redactions were based, have

completely disappeared. The non-Canonical works of the Śvetāmbara Jains are in what is designated as the *Jaina Mahārāṣṭrī*. The language of the works of the Digambara Jains is termed as the *Jaina Śaurasēnī*. The oldest *Kāvya* work in the Jaina literature is the *Paūmacariya*, which gives a version of the Rāmāyaṇa and is assigned to the 3rd century A.D.

Of the Epics, the *Setubandha*, otherwise known as *Rāvāṇa-vahō* or *Dahamuhavahō* is a work of such excellent technique that it has often been ascribed to Kālidāsa. The *Gauḍavahō* by Bappaī-rāa celebrates the conquest of Bengal by Yaśovarman of Kanauj about the end of the seventh century A.D. There are also other later works.

The *Sattasāī* (or *Saptaśatakam*) of Hāla is the most important collection of lyrics. This anthology with various recensions comprises seven hundred verses by many poets. One commentary gives 112 names, while another gives 384. This is considered as very important for the study of *Mahārāṣṭrī*.

Of the dramas, we have already referred to the use of Prākṛit in the Sanskrit dramas. A purely Prākṛit play in which even the hero speaks in that language is exceptional. A well-known instance is the *Karpūra-mañjari* by Rājaśekhara.

The author however thinks it well to explain why no Sanskrit has been used. In the Prologue, the *sūtradhāra* reflects: "Then why has the poet abandoned the Sanskrit language and undertaken a composition in Prākṛit?" His assistant replies in *Mahārāṣṭrī*: "Sanskrit poems are harsh: but a Prākṛit poem is very smooth, the difference between them in this respect is as great as that between man and woman."

The word *prākṛtam* is generally derived from *prakṛti* and has two lines of meaning: (a) the more precise meaning of something belonging to or derived from a *prakṛti*, i.e., the original form of anything as opposed to a *vikṛti* its modification (In Sāṃkhya Philosophy *prākṛta* means what is derived from *prakṛti*, the original element); (b) the looser meanings of 'natural, ordinary, vulgar, provincial', etc.

Grammarians and Rhetoricians of later days explain *prākṛtam* as derived from *prakṛti*, i.e., Sanskrit : *prakṛtiḥ saṁskṛtam, tatrabhavam tata āgatam vā prākṛtam* : 'The basis is Sanskrit. That which has its origin in it, or is derived from it, is called Prākṛit.' And in the study of the Prakrit language practically we take Sanskrit forms as the basis and derive Prakrit forms therefrom. As such the above explanation is perfectly intelligible even if it be not historically correct. But modern philology insists on an important reservation: Sanskrit forms are quoted as the basis in as far as they represent the old Indo-Aryan forms, but sometimes the particular Old Indo-Aryan form required to explain a Prākṛit word is not found in Sanskrit at all or only in a late work and obviously borrowed from Prākṛit.

Almost all the Prākṛit grammars so far obtained are in the Sanskrit language composed after Prākṛit had ceased to exist as the official language, yielding its place to Sanskrit. These grammars have been written by the authors from their stand on the Sanskrit grammar, being generally meant for the students of Sanskrit in the study of the Prākṛit portions of the dramas. Even in this, scholars have recognised the existence of two schools belonging respectively to the west and the east, the former sometimes being called the School of Vālmiki and the latter that of Vararuci. These two schools differ from each other in many respects. It is no wonder that the authors are often mutually inconsistent as the language had become dead then. They are sometimes unable to demonstrate the actual difference between two dialects.

A perusal of these grammars would show that their authors have treated Prākṛit as an artificial language of debased or corrupt Sanskrit to be put in the mouth generally of female characters and of low or unrefined characters figuring in the Sanskrit dramas. The rules of phonetical changes, which sometimes appear to have been extended to the extremities, also point to the same. But the real situation seems to be the other way round.

Prākṛit had been the official or court language for at least five or six centuries and the inscriptions belonging to the period ranging from the 4th century B.C. to the 3rd century A.D. were



written in this language. As such it should have attained a high level of diction and expression. The royal charters would have been written couched in clear, precise and unambiguous terms. But we find even short records interpreted differently by scholars. A copper-plate inscription containing only four lines of writing in the Brāhmī characters of *circa* 3rd century B.C. recovered from Sohgaūrā in the U P. has been interpreted by Buhler (*IA*, vol. XXV), Fleet (*JRAS*, 1907), Barua (*ABORI*, vol. XI) and Jayaswal (*EI*, vol. XXII) in four different ways. This would show that we have not yet correctly understood this language, at any rate that of the inscriptions.

These Prākṛit grammars so far obtained do not explain all the peculiarities of the language used in inscriptions.

In the Hirahadagalli Prākṛit grant (*EI*, vol. I) of the early Pallava king Śivaskanda varman, the gift of lands to some Brāhmaṇas is expressed in ll. 11-12 as *Bappasvāmihi...puvvandat-tam* immediately followed with the list of donees and the shares given to each. This has been translated as "was formerly given by the great king, the lord Bappa" correcting *svāmihi* into *svāminā*. The word *Bappa* was taken by some scholars to mean the father thus making the inscription registering the gift made by the father of the donor. Another scholar took the word to mean the king himself. But really the word *Bappa* is the Prākṛit form of the Tamil word *Pārppān* meaning a Brāhmaṇa and this is clear from the Pullūr plates of Nandivarman Pallavamalla. It is also to be noted that the Prākṛit grant is an order issued by the king to his officers and others intimating them of the land-grant made already. So the portion has to be translated as 'had been granted already to the Brāhmaṇas' taking the word *svāmihi* as *svāmiki* or *svāmikku* in the dative case as in Tamil.

At the opening of the same grant the portion mentioning the issue of the order by the king to his officers has the expression in l. 7. which is read by Buhler as *bhaḍamanusāṇa [kaḍha...ō]* Dr. D. C. Sircar (*Select Inscriptions*, vol. I, p. 438) has read the doubtful portion as *kaḍha* so and suggested the reading *bhaḍa-manusā āṇavēti*. It is to be read as *kaḍhale* with the Dravidian *la*. We have seen that in the Brāhmī inscriptions of the Tamil

country the aspirated form *ṭha* has been used for *ṭṭa*, on the analogy of which this has to be read as *kaḍḍaḷe* or the Tamil word *kaṭṭalai*.

We thus find many Dravidian forms and usages in the Prākṛit inscriptions and this aspect has not been studied seriously so far with the intensity it deserves.

There are some important differences between this language and Sanskrit which will deserve consideration.

(i) Prākṛit is a simple language with a simple grammar capable of being understood by everybody.

(ii) It has only the singular and the plural as in Tamil. (No dual number as found in Sanskrit.)

(iii) Among the vowels, *r*, *l*, as also *ai* and *au* are absent. In the cases of *e* and *o*, they have both the forms, short and long.

(iv) Of the consonants, *śa* and *ṣa* are not generally used and only *sa* takes their place.

(v) The Dravidian *ḷa* is also found.

*Paiśāci* is another dialect very archaic in character. The *Vaḍḍhakathā*, original of the famous *Bṛihat-kathā*, was composed according to the story by Guṇāḍhya in *Paiśāci* taking a vow that he would not thereafter use in his life either Sanskrit or Prākṛit. No work written in this dialect is now available to us. It is said that the chief peculiarity of this dialect is the substitution of surd mutes for sonants: *Tāmōtara* for *Dāmōdara*, *nakara* for *nagara*, *rācā* for *rāja*, *kantappa* for *kandarppa*, *kiri* for *giri*, etc. Further *ṇa* becomes *na*, *ḷa* becomes *ḷa*, and *ya* is retained in this language.

The language of the edicts of Aśoka from Shāhbāzgarhī (near Peshawar in Pākistan) is said to agree with this in a number of particulars. It is therefore considered that it should be connected with the Dard and Kāfir languages of the Hindu Kush.

But Guṇāḍhya, the author, the only person known so far to have written in this language, was a South Indian and the book was also composed in the Vinḍhya forests in the Dakṣhān. It is

even possible to ascribe a South Indian origin to the entire cycle of stories contained therein.

There is a popular story in Tamil in which Auvaiyār, the famous poetess, is said to have turned out to be an ignoramus at the hands of a rustic boy. The old lady, during one of her peregrinations, one day happened to rest in the cool shade of a jaumoon-plum (*nāval* or *jambū*) tree during the hottest part of the day. She found some shepherd boys on the top of the tree plucking and eating its fruits. She also wanted some fruits to quench her thirst and so she asked the boys for the same. But she was perplexed when one of them, evidently their leader, asked her whether she wanted the fruit hot or cold. She understood this enigma only when the boys made the fruits fall on the sands below. The 'hot' was the fully ripe one as it had to be eaten after blowing it with the mouth to remove the sands sticking into the pulp of the ripe fruit, the skin of which was very thin and got damaged by the fall. There was no necessity for blowing the unripe fruit and it had only to be wiped out to remove the dust before it was eaten and so it was 'cold.'

This well-known incident is found mentioned in the *Brihat-kathā* also. But there the victim was not the poetess Auvaiyar, but Mūladēva, another character, equally important, witty and intelligent. There the scene was laid on the outskirts of the city of Pāṭaliputra and the fruit was mango and not *nāval*. This change in the name of the fruit takes away much of the interest and makes the story quite tame, as, unlike the *nāval* or jaumoon-plum, it is not usual to blow with the mouth a mango before eating it.

Evidently, the change is due to the translation and it is possible that the original contained the incident as prevalent in the South with the *jambū* as the fruit in question.

Another point also has to be noted. The names of the several characters who figure in the collection as we now have are not those given to them by the author. They have all been translated into Sanskrit by the authors of the redactions. This becomes clear when we compare the names occurring in the *Kathāsarit-sāgara* and the *Brihatkathā-māñjarī*, where one lady-character is named Kanakaprabhā in one, and Hēmaprabhā

in the other. Both of them, of course, mean the same thing, Golden lustre. One thing becomes clear. Guṇāḍhya's original did not have the Sanskrit names for its characters. They were in the language of the original *Paiśāci*, coined to signify the special characteristics of the persons, thus making them translatable and at the same time capable of similar expression.

This work is classed with the great Epics, the Rāmāyaṇa and the Mahābhārata, by the previous authors like Bāṇa and others. One of the verses in the *Saptaśati* has: "We salute, says Gōvardhana, the authors of the Rāmāyaṇa, of the Mahābhārata and of the *Brihat-kathā*." But even the original name of this book is not known. The form of *Vaḍḍha-kathā* is found in the inscriptions of the Western Gaṅga king Durvinita, early in the 7th century A.D. He is said to have composed a version of it in Sanskrit and that book also is not available. We have to depend on the Kāshmirian Sanskrit summaries by Kṣēmendra, Sōmadēva and Budhasvāmin. But it is very doubtful whether *Vaḍḍhakathā* was the original name as the *Paiśāci* language did not have the sonants, but only the surd mutes. (It is to be noted that the form *Atṭha-kathā* is found in the Buddhist literature.)

The stories of the *Pāñcatantra* are also found included in this work. Even in the *Pāñcatantra* itself, the story is set in the southern country (*Dākṣiṇātya janapada*) on the banks of the river Gōdāvarī.

Considering the above, it is possible to suggest that the original of Guṇāḍhya was composed in a language of the south, most probably in the Dravidian language.

We have already seen that the Sanskrit grammarians generally treat *Paiśāci* as one of the Prākṛit languages, even though some authors do not take it as a group by itself with its sub-dialects. This is in complete variance with and quite contradictory to the statement in the *Brihat-kathā*. There Guṇāḍhya is said to have taken a vow not to use Sanskrit or Prākṛit and then written the story in the *Paiśāci*. It should therefore have been quite distinct from both the Sanskrit and the Prākṛit languages.

Bhōjadēva, in his *Sarasvatikanthābharana*, says that high personages (in the dramas), who appear not in just the highest roles, should speak in a language which is Sanskrit and *Paiśācī* at the same time,—a favourite sport in *bhāṣāślēṣa* which is all the more easy in *Paiśācī*, because of all the Prākṛit dialects it has the closest relation to Sanskrit.

We thus get a very confused account of this language. But one thing emerges clear. Unlike the other Prākṛit languages, the *Paiśācī* was considered as a highly refined and civilized language fit to be spoken by the cultured.

Grammarians recognised two sub-dialects of the *Paiśācī* : *Kaikēya-Paiśācī* and *Cūḷika-Paiśācī*. It is also said that there were eleven varieties of it named according to the countries wherein each was used. One list gives Kāñcī, Pāṇḍya, Pāñcāla, Gāuḍa, Māgadha, Vṛācaḍa, Dakṣiṇātya, Śaurasēna, Kaikēya, Śābara and Drāviḍa while another has Pāṇḍya, Kēkaya, Bāhlika, Sahya, Nēpāla, Kuntala, Gāndhāra and four other countries, the names of which are in corrupt forms, Sudēṣa, Bhōṭa, Haiva and Kanōjana.

Broadly taken, according to these grammarians, South India and the north-western regions of India (at present included in Pākistan) near the Hindu Kush in addition to some outlying parts were the areas wherein the *Paiśācī* was prevalent. The Brāhūi language of the Baluchis is known to be of Dravidian stock. It is therefore quite possible to conclude that the *Paiśācī*, one of the Prākṛits according to the grammarians, was a language belonging to the Dravidian group, very likely Tamiḷ itself.

*Paiśācī* is also referred to as *Bhūtabhāṣā*, 'the language of the goblins'. Of these two names, it is not known which is earlier though the former has been more popular. Daṇḍin refers to it only as the *Bhūtabhāṣā*. The word *bhūta*, like the other word *prakṛiti*, also means 'element'. Would it not be possible that *bhūtabhāṣā* was the earlier name of the language indicating that it was the basis for the Prākṛit ?

Nami sādhu commenting on Rudraṭa's *Kāvyaḷamkāra* derives the word Prākṛit from *prakṛti* in the sense of natural speech free from the rules of grammarians, or from *prak-kṛta*, (created in former times). "Like the waters of rain they too had formerly but one form, but on account of the difference of the respective countries and the (grammatical) modifications, they have become multifarious and divided into Sanskrit and other languages." Prākṛit has therefore been made by him the basis also of Sanskrit.

Two other South Indian languages also claim themselves to be Prākṛits. Telugu is one and its early grammarians name their language as such. *Dhakkī*, one of the Prākṛit dialects in which the vowel *u* often appears at the end of a word, is, according to Mārkaṇḍeya, a Drāviḍa *vibhāṣā*. This peculiarity is found largely used in Telugu. Kannaḍa is the other. An inscription from Bādāmi of the time of the Western Cālukya monarch Vijayāditya, bearing the date Śaka 621 or 699 A.D., contains towards the end which is damaged some verses in the Kannaḍa language which is there called the Prākṛit language. (*IA*, vol. X).

The best of the Prākṛits is the Mahārāṣṭrī, of the south. The *Sattasāi* of Hāla, an important anthology and the best specimen of the *Mahārāṣṭrī* contains many verses for which parallels are found in the early Tamiḷ literature known as the Saṅgam classics. It is said that some of the verses in the *Sattasāi* are best understood and appreciated only with a deep study of these Saṅgam classics and that these two serve as complementary to each other. It is further stated that the *Sattasāi* has many linguistic forms and usages which are peculiarly Dravidian.<sup>1</sup>

---

1. In passing we may also point out that Tamiḷ literature has contributed much to Sanskrit and this flow can be seen even as late as *circa* 1100 A.D. The small collection of fifty love-lyrics in Sanskrit known as the *Caura-pañcāśikā* is generally attributed to Bilhaṇa, the Kashmirian poet in the court of the Western Cālukya monarch Vikramāditya VI. (This Cālukya had married the daughter of the Cōla king Virarājendra). Sometimes the collection is attributed to an unknown poet named Caura or Cōra, taking the clue from the title. The poems in the collection are of the type

The special features of the Prākṛit languages we have noticed above are found in the Tamil language and these also satisfy the peculiarities of the language for which the Brāhmī script was designed.

Probably, the Prākṛit in its original form was a South Indian product, synthesizing the Dravidian language to make it understood throughout the country. In course of time more of Sanskrit element came to be introduced in it, which process entirely changed the complexion of the Prākṛit and gave rise to several dialects.<sup>1</sup> By way of modern analogy we may cite the basic Hindi as an example of the original Prākṛit. The attempt now made by some scholars to Sanskritise the Hindi instead of making it more elastic, absorbing words from the local languages as is necessary, was evidently carried out in the case of the Prākṛit also, which made it more rigid which led to its disappearance.

Can we therefore postulate that the Brāhmī script was originally designed for a language like Tamil and that it was later on adopted for the Prākṛit language when it was evolved to serve as a common language for the different areas and peoples of the country?

---

found in Tamil literature belonging to that branch known as *kalavū* in the theme *Ahapporū*, i.e., the initial stages of love when the lovers meet in secret (stealthily) and foster their affection (which culminates in their marriage after which their affection is treated under the heading *karpu* or chastity). The Tamil word *kalavū* and the Sanskrit one *cōra* are synonymous. It will be seen that not only the theme but also the title of this Sanskrit collection was borrowed from Tamil.

The Sanskrit word *anēka* (lit. not one) meaning 'many' is Dravidian in form and conception absorbed through Prākṛit. Strictly, this word in Sanskrit means either two or many. The Jaina religion is known as the *anēkānta-vāda* where the word means many. In religion and logic the terms used are always precise and unambiguous. This usage would therefore have been possible only with the language which has no special form for the dual.

1. It is not possible to discuss this question here at greater length with fuller details. That has to be done separately.

One objection could be raised against this theory and that is with regard to the absence of special symbols for the short *e* and *o* which are considered as peculiar to the Dravidian languages. Prākṛit also has both the short and long in *e* and *o*; but these are not distinguished in the inscriptions where they are generally taken as long, following the practice in Sanskrit. In fact, the Sanskrit influence is clearly perceptible in the extant Prākṛit inscriptions.

Once again we may cite a modern analogy. There is a move for a common script for the whole of this country. When this happens, the other scripts will disappear, and one or two generations later we may not have persons conversant with those scripts. This is what we actually see in the case of the *Grantha* script, a variety of Tamiḻ script, used previously in this part of the country for centuries to write Sanskrit. After the advent of the *Dēvanāgarī* script, the *Grantha* script has disappeared and even the Manuscript libraries find it difficult to get persons who can copy in it. For adopting a single script for the whole country special symbols have to be invented or signs added to the existing ones to represent the peculiar sounds of the other languages, including the short *e* and *o*, *ḷa* and the like.

In conclusion, the above discussion on the origin and the antiquity of the Brāhmī script may be summarised as follows:

The Brāhmī script was not borrowed from any foreign source. It was developed in this country only. Most probably the Indus Valley pictographic script was its parent. But the values of the individual symbols of that script is not yet known and there is no likelihood of the values being settled unless and until some bilingual record or some other unimpeachable evidence is obtained. But this much seems clear. The Brāhmī script was originally devised for the Dravidian language and later on adopted for Prākṛit which was evolved as a common language and which was more close to the Dravidian. Later on when Sanskrit elements were introduced into the Prākṛit and it became more Sanskritised, additional symbols had to be introduced to suit the needs of the new letters and in the course of this process, some symbols not required for the Sanskritised Prākṛit got eliminated. And finally when it became the official language it spread throughout the



length and breadth of the country with royal authority behind, and displaced the then existing varieties of the script. It should be noted side by side here that no inscription in the other co-existing scripts has been found so far. It is from this Brāhmī script that all the existing scripts of the country including the *Dēvanāgarī* have been obtained by evolution.

## XI. CONCLUSION

The above discussion on the evolution of the South Indian scripts may be summed up as follows :

The earliest inscriptions found in the Tamiḻ country are in the Brāhmī script of *circa* third century B.C. This Brāhmī script should have been designed for a Dravidian language very likely the Tamiḻ which was the oldest and primary language of the group and later on adopted for Prākṛit when it was evolved synthesizing the Dravidian languages and made the common language of the whole country. By the the process of evolution it slowly became roundish and took the shape of the *Vatteluttu* which at one time, in the early centuries of the Christian era, was prevalent throughout the Tamiḻ area.

The Pallava monarchs of Kāñchipuram, who succeeded the Śātavāhanas of the Dakhan and who had the Prākṛit initially and Sanskrit subsequently, as their official language spread their sway in the south, they introduced the Brāhmī script in the shape it was then prevalent in the Dakhān which slowly became the Pallava-Grantha script. Their official documents in Tamiḻ language also were written in the same script. Thus these two formed one variety and they had practically the same evolution. When the Pallava rule was later extended to the Chōḷa-nāḍu, these scripts were introduced there also. The *Vatteluttu* continued to exist in the other portions of the Tamiḻ country; but the Grantha script was used to write Sanskrit.

When the Chōḷas took over the Pallava empire, they continued the Grantha and Tamiḻ scripts and when they extended their sway over the Pāṇḍya country, the Tamiḻ script was introduced in that area displacing the *Vatteluttu*, which thereafter existed only in the Malai-nāḍu which did not come under the

direct rule of the Chōlas. This *Vatṭeluttu* later on became debased as the the *Kōleluttu* (when Malaiyālam language was Sanskritised and the Grantha script came to be used with the name *Ārya-eluttu*) and finally became extinct.

On the decline of the Chōlas and the Pāṇḍyas, when the Tamiḷ country came under the rule of the Vijayanagara empire, they introduced the *Nāgarī* script to write Sanskrit and this received fillip with the advent of the Mahratta rulers. Now the Grantha script has almost disappeared yielding place to the *Dēvanāgarī* and only the Tamiḷ script has survived. It is also to be noted that when compared with the other scripts which were all evolved from the Brāhmī, changes undergone by the Tamiḷ and the Grantha scripts in their evolution to attain their present form were not much and these were made mostly to make them appear beautiful.

---

[*Note*—The dates of the Siddhapura Edicts of Aśōka and the Bhaṭṭiprōḷa inscriptions given under the headings, Cols. I and II in page 1514 above are to be read as *circa* 250 B.C. and *circa* 200 B.C. respectively.]

## ANNEXURE

[The inscriptions, being mainly records of transactions in olden days, contain a large number of expressions and words current in those days. Many of these words have become obsolete and the few which still survive have changed their meaning and do not convey the same sense which they had in those days. It is therefore quite necessary that a special glossary is required to explain their correct import.

In the second volume of this work a few terms, mostly names of the different taxes, were given with their meanings. This appears to have attracted the attention not only of the research scholars, but also of persons in other walks of life. A close study of these inscriptions will reveal not only the technical terms and expressions employed in the administration of the country but also the nature of the administrative machinery current in those days, as well as its growth. A collection of these terms will be helpful in understanding correctly the life of our fore-fathers, and will also serve as a guide in the new set up of introducing Tamil as the state language. This glossary has been prepared in accordance with the direction of the Government of Madras who expressed the desire in their order No. Ms. 1082, Education dated the 3rd August 1954 that "all the available inscriptional terms and phrases should be published as an appendix" to this volume.

It cannot be said that the list is exhaustive. The meanings given for some of the terms are only tentative and may require modification in the light of future investigations, when the texts of the thousands of inscriptions, the bulk of which copied from the year 1904 onwards still remains unpublished, are made available to the scholars for study. A more complete and satisfactory glossary could be prepared only after the publication of all the inscriptions. But this will take a long time to be accomplished.

In the meanwhile, the preparation of a glossary with the available materials will go a long way in the elucidation of the meaning of the inscriptions.]

## EPIGRAPHICAL GLOSSARY

- abhaya* : place of security to persons in distress; also known as  
*añjinān-pugal-iḍam*
- abhayaśāsana* : charter of security ; deed offering protection
- abhishēka-k-kāṇi* : s. a. *abhishēka-k-kāṇikkai*
- abhishēka-k-kāṇikkai* : presents offered to a king on his coronation
- abhishēka-manḍapa* : hall where ceremonial baths are performed; coronation hall; also referred to as *tirumañjanaśālai* and *kulikkum-iḍam*
- abhishēka-nāma* : name or title assumed by a king on his coronation
- āchandrārkkam* : as long as the moon and the sun last; in perpetuity
- āchandra-tārakam* : as long as the moon and the stars last; in perpetuity
- āchārya-pūjanai* : honorarium to priests
- achchai* : Vedic hymn
- āchchan* : father
- achcha-tari* : s.a. *achchu-t-tari*
- achchu* : a coin current in olden days
- achchu-k-kattū* : bund; field with ridges; land divided into beds to get water for cultivation
- achchu-t-tari* : a variety of loom ; tax payable on looms
- achchu-vari* : probably s.a. *pon-vari*; duty payable for minting gold into coins
- aḍai-kuḍi* : cultivating tenant
- aḍai-kuttu* : to mortgage
- aḍai-koḷ* : to take on mortgage
- aḍaimudal-parru* : land leased out to tenants
- aḍai-p-paḍi* : pledge; deed of mortgage
- aḍaiḍḍam* : betel-box; betel-bearer; person having custody of the betel-box; officer in personal attendance on the king performing that function; also referred to sometimes as *aḍaiḍḍu*
- aḍaiḍḍu* : land held in lease
- aḍaiḍḍu-mudaligaḷ* : executive officers of an assembly evidently charged with leasing of lands
- aḍaiyāl* : servant
- aḍai-y-elututal* : to enter into an account
- aḍai-y-ōlai* : lease deed; agreement for farming out
- aḍakkirāvi* : a kind of paddy

- adarañ-śeydal* : to make obstruction  
*aḍarndērram* : consolidated rent  
*aḍavimār* : a class of weavers  
*aḍavōlai* : s.a. *aḍai-y-ōlai*  
*aḍavu-śeyvār* : s.a. *aḍavimār*  
*adhikāra-mel-eḷuttu* : revisional order  
*adhikaraṇa* : one grade of law courts, probably the chief court  
*adhikaraṇa-danḍam* : fine imposed by the *adhikaraṇa*  
*adhikāra-p-pēru* : evidently the presents offered to an officer  
*adhikāra-p-pon* : probably s.a. *adhikāra-varṭtanai*  
*adhikāra-varṭtanai* : customary payments made to an officer at stipulated periods  
*adhikārichchi* : wife of an officer; may also denote a woman holding official position  
*adhishṭhāna* : the base of the *vimāna* in a temple; seat  
*adhyayana-vritti* : tax-free land endowed for the service of reciting the Vēdas in temples  
*adhyayanāṅgam* : s.a. *adhyayanavritti*  
*ādikka-p-pēru* : probably s.a. *adhikāra-p-pēru*  
*adirkāṇi* : proprietary right in the village lands  
*aḍigalmār* : (lit. devotees) women dancers maintained in temples  
*aḍimai-k-kāśu* : fee collected from temple servants  
*aḍi-k-kāśu* : tax collected from stall-keepers in markets  
*āḍi-p-pachchai* : always mentioned along with *kārttigai-p-pachchai*. We also find *āḍi-navirai* (*navirai* : a variety of paddy). So the term may be taken to mean the perquisites payable in grain in the month of Āḍi probably on harvest  
*ādirai-p-pāṭṭam* : tax on cattle  
*aḍiyāl* : woman-servant  
*aḍukkalai-p-puṇam* : endowment for kitchen expenses of a temple  
*āgāmi* : one of the eight kinds of rights in the property; future benefits  
*agambaḍi* : household (mostly referred to in connexion with royalty)  
*agambaḍi-mudaliḡ* : officers attached to the household establishment in the palace  
*agambaḍi-p-peṇḍuḡal* : maid-servants in the household establishment of a king

- agambaḍi-udaiyān* : citizen, subject, *kuḍi*, *kuṭumbi* or *kuḍimakkal*  
*agamārga* : a variety of dance performed in the presence of the gods in temples, probably on some religious topic  
*aganāligaiyār* : those in charge of the *garbha-griha* of the temple  
*agara-brahmadēya* : village gifted to *brāhmaṇas*; also known as *agaram* and *brahmadēyam*  
*agaram* : s. a. *agrahāra*; *brāhmaṇa* village  
*agara-p-parru* : land gifted to *brāhmaṇas*; land attached to *agaram*  
*agali* : small pits  
*agali-tiruttu* : to fill in small pits and level the ground (for cultivation)  
*aga-p-parivāram* : household attendants in the palace  
*agnishṭhai* : firewood  
*agramahādēvi* : chief queen of a king  
*agramaṇḍapa* : front hall of a temple  
*agōvanam* : waste land  
*ahai-vāykkāl* : branch channel flowing to fields in the village  
*ahitam* : damage; injury  
*akavinai* (*aghavinai*) : hindrance; obstruction  
*akkālī*, *akkālī-prasādam*, *akkārāḍiyal* : a kind of food-offering to god in temples; probably s. a. *akkāravaḍiṣil*  
*akkam* : a coin current in olden days; mint  
*ākkam* : income, wealth  
*akkan* : elder sister; term of respect to denote her  
*ākka-p-perukkam* : improvements made; also the income therefrom  
*akkāravaḍiṣil* : rice food boiled in milk with sugar and ghee  
*akkaśālai* : mint  
*akkaśālaivari* : tax payable to the mint [for minting coins]  
*akshiṇi* : actual privileges (one of the eight rights of ownership)  
*akutam* : s. a. *ahitam*  
*alagachchu* : a coin current in olden days  
*alag-erudu*, *alagerudu-kāṭchi-k-kāṣu* : see *nal-l-erudu*  
*āl-amañji* : workman pressed into service without wages.  
*alavar* : a class of cultivators (probably related to *alam* : salt-pan)  
*alavu* : survey (of land)

- ālēpana* : anointing; coating the image with unguent  
*ālī-k-kal* : boundary stone of the lands of Viṣṇu temple, marked with the emblem of *chakra* (discus)  
*alivu* : expenses, expenditure  
*aḷivu* : damaged crops  
*aḷivu-piḷai* : fines imposed on defaulters (lit. crime of destruction)  
*aḷivu-śeyvān* : person looking after the income and expenditure of an institution  
*aḷḷāya-mānyam* : right to receive a handful of grain [or a prescribed quantity of an article sold in market as wages for measuring ?]  
*āl-nel* (*āṇel*) : tax payable as paddy  
*alpamirai* : minor tax payable in grain  
*aḷu* : a variety of market dues; probably s.a. *aḷḷu* and *aḷḷāya-mānyam*  
*aḷugal-śarakku* : evidently, the right of collecting the refuse and waste thrown in the village  
*ālum-gaṇa* : executive committee looking after the day to day affairs of the village on behalf of the *sabhā*  
*ālum-gaṇattār* : members of the above committee  
*āḷvār, āḷvi* : lord, chief  
*āl-vari* : poll-tax  
*āmai-taval* : (place) where the tortoise creeps, i.e., deep well  
*amañji* : s. a. *āl-amañji*  
*amaram* : tract of land assigned to military officers in which they were entitled to collect only certain revenues with the obligation to raise a contingent of army ready for service whenever called upon and also pay tribute to the king  
*amara-māgāṇi* : estate given to an *amara-nāyaka*  
*amara-nāyakam* : the office of the *amaram*  
*amara-paksha* : s.a. *apara-paksha*; dark fortnight  
*ambalam* : village assembly; shrine of Naṭarāja or the dancer in hall; Śiva temple  
*ambala-p-puram* : land given to meet the expenses of Śiva temple  
*ambalattār* : members of a village assembly  
*ambumudupāṭan, ambumuduvurai* : varieties of pearl  
*amirta-gaṇattār* : (s.a. *amrita-gaṇattār*) members of the committee for the management of village affairs; members in charge of the cash receipts of a temple  
*amudu-(p)-padi* : food offering to god  
*anādi-pāl* : ruins from immemorial time

- āṇai* : (Skt. *ājñā*) order, imprecation  
*āṇai-ch-chālai* : elephant stable; also the tax payable for maintenance of the same  
*āṇai-vāsāl* : main entrance; also the palace gate  
*āṇaivilai* : sale by royal order, also referred to as *ājñākṛayam*  
*āṇai-y-āṭkal* : elephant corps  
*āṇ-añju* : s.a. *pañcha-gavya*; the five products of the cow, viz., milk, butter, curds, urine and dung  
*āṇatti* : s.a. *ājñapti*, executor of the order; also denotes royal order  
*āṇavāl* : State officer managing a temple  
*āṇḍār* : devotees  
*āṇḍ-eluttu-t-tēvai* : an ancient tax the exact nature of which is not clear  
*āṇḍukaḷ-ṭ-aḍavu* : annual income  
*aṅgaḍēvatai* : attendant deity to a superior god; s. a. *parivāra-dēvatā*  
*aṅgāḍi-k-kūli*, *aṅgāḍi-p-paṭṭam* : tax on bazar, shop, etc.  
*aṅgamaṇi* : property owned by woman  
*aṅgamaṇidravyam* : dowry  
*aṅgarāṅgavaibhava*, *aṅgarāṅgavaibhōgam* : worship to include all kinds of enjoyments  
*aṅgarakshaka* : body-guard  
*aṅgaśālai* : theatre; (cf. also *aṅkaśālai*)  
*aṅga-vayichchiar* (*aṅga+vaidya*) : physician  
*āṇiyam* : daily allowance, batta  
*aṅjashṭa-śattusabhai* (*añju+ashṭa+sattu+sabha*); *añjashṭa-sabhai* : village committee of five and eight members (probably s. a. *aim-peruṇ-kūlu*, and *eṇ-pēr-āyam*?)  
*añjinān-pugal-iḍam* : place of security to persons in distress; s.a. *abhaya*  
*añju-pañchālattār* : s.a. *pañchakammāḷar*; the five artisan classes  
*añjuvaṇṇam* : the five artisan classes; known as *hañjamana* in Kannada inscriptions; sometimes taken as a form of the Arabic word *anjuman*  
*aṅkaśālai* : probably the place where duels are fought  
*aṇṇāvi*, *aṇṇālvi* : elder brother  
*aṇṇāli-k-kāl* : measure of five *nāḷi*  
*aṇṇiya-nāmakaraṇam* : benami; doing things in another's name



- anniyāya-vāva-daṇḍa-irai* : evidently denotes the penal tax imposed on some unauthorised item of occupation or enjoyment
- anrāḍu-narkāśu* : current good coin; coin (having specified fineness of the metal) then current
- anrāl-kō* : the monarch for the time being
- antara-viniyōgam* : individual share to make up the shortage in the total revenue occasioned by the grant of exemptions of *antarāyam* or *ulvari*
- antarāla-maṇḍapa* : that portion of the temple connecting the *garbhagriha* and the *mukha-maṇḍapa* ; also known as *ardhamanḍapa*
- antarāyam* : [internal revenue], taxes levied by the local body ; also known as *ulvari*
- antarāya-k-kāśu, antarāya-p-pāṭṭam* : internal taxes, minor taxes like the profession tax, etc. payable to the village assembly
- anti-k-kāppu* : evening service performed in a temple
- anubandham* : help
- anubhōga-p-parr-olugu* : renewal of title-deeds according to the enjoyment
- anuchitam* : evil; damage
- anukkar, anukkiyar* : personal attendants, servants always in immediate presence of a noble
- anukka-ch-chēvagam* : service as personal attendants
- anukka-vilakku* : lamp near the chief deity in a temple
- anutāra* : protection, guardianship
- anuvarttanai* : class of contingent dues which come under the head *varttanai*
- anwayattār* : persons belonging to the same lineage
- aparamparā-balivadam* : free from the supply of bullocks in succession (cf. *nallerudu* ?)
- apōhanam* : waste; without cultivation (cf. *agōvanam*)
- apūri, apūrvin* : *brāhmaṇas* well versed in the Vēdas; mostly such pilgrims visiting holy shrines; probably refer to *Mīmāṃsakas*
- ara* : in full, completely
- ara-ch-chālābhōgam* : tax-free land given to and set apart for the maintenance of feeding-houses
- arai kaval* : person in charge of the store-room in a temple
- araiyan* : title conferred by the king in olden days
- arai-y.ōlai* : order proclaimed by beat of tom-tom; proclamation

- arakkal** : an instalment of land-tax  
**āraṇḍa** : brass  
**araṇkāval** : wardenship of temples and other charities  
**arāsu** : privileges allowed to watchmen  
**arāsu-p-pēru** : fee collected for the performance of police duties in the districts (is it the same as *mahārāja-prayōjana* mentioned in the inscriptions of the Telugu country ?)  
**ārāṭchi** : s.a. *ārāychchi*  
**aratēyan** : one who manages charitable endowments  
**ara-v-ōlai** : deed of gift  
**ārāychchi** : cess paid for the superintendence of transactions ; also known as *kāriya-v-ārāychchi*  
**ārāychchiyār** : auditors, examiners of accounts  
**archanā-bhōga, archanā-vritti** : land set apart for meeting the expenses of worship (*archanā* in particular) in the temple  
**archchanā-vibhava-kāṇi** : rent-free land granted to temple-priests  
**ardha-chandra** : (half-moon) a part of the *tiruvāṣi* ; also a variety of ornament  
**ardhajāma-p-puram** : land set apart for conducting the midnight worship in temples  
**ardhāṅgi** : wife  
**ārīḍu-paḍugai** : land formed by the silting up of the river near the bund  
**arīkaru** : produce from the land  
**arīkōḷi, arīṣi-t-tuṇḍam** : taxes in olden days, the exact nature of which is not clear  
**arīkūḷi** : dues evidently payable in handfuls of stalk harvested  
**arīḍu-ch-chari** : a variety of pendant ornament  
**arīṣi-k-kāṇam** : tax for husking paddy into rice, evidently the same as *kūrrarīṣi*  
**arivāṇam** : copper-tray, platter, food offering presented in the tray  
**ārṇākarai-t-tēvai** : tax for keeping in repair the river-bund  
**ārṇu-k-kulai** : (lit. river-bund) tax to repair the breach of the river-bund  
**ārṇukkāl amāṇji** : free labour to keep in good repair the channel from the river  
**ārṇu-p-pāṭṭam** : probably s.a. *ārṇākarai-t-tēvai*  
**arūdi-muri** : cancelled deed  
**aru-muri** : deed of agreement, lease-deed (s.a. *arūdi-muri* ?)

- aruntōḍu* : (eating-plate) a tax payable evidently on the number of eating plates in feeding houses.
- ashta-bhōgam* : eight kinds of rights in enjoying landed property, mentioned as *vikraya*, *dāna*, *vinimaya*, *jala*, *taru*, *pāshāṇa*, *nidhi*, and *nikshēpa* in one place and as *nidhi*, *nikshēpa*, *jalāmṛita*; *pāshāṇa*, *akshinī*, *agāmi*, *siddha* and *sādhya* in another place
- ashta-paripālanam* : deities of eight cardinal points; s.a. *ashta-dik-pālakas*
- ashta-vidha-bhakti-kriyā* : eight aspects of worship including *archanā*, *vandana*, *smaraṇa* *pādasēvana*, *stava*, *pradakṣiṇa*, *sakhya* and *ātmanivēdana* or *ātmarpaṇa*
- ashta-vidh-ārchana* : eight-fold worship with water, scents, flowers, grain, incense, lamps, food and betel
- āsīriyam* (*āsraya*), *āsīriya-k-kal* : inscriptional document by which a person submits to another's protection
- āsīriya-p-pramāṇam* : document of the above
- astikaḍai* : heavy fighting; fierce battle
- āśuvaḍimakkal āśupodumakkal* : the Ājivakas
- āśuvikal-kāśu*, *āśuva-k-kaḍamai*, *āśuva-k-kāśu* : tax payable by the Ājivakas (*Āśuvi-Ājivaka*)
- ataikkāy-amuḍu* : betel-nut; also referred to as *aḍaiyamuḍu*
- atavi* : troops
- ātchi-p-pāṭṭam* : probably, a succession tax
- ātirai* : lit. *ārdrā*; probably the expenses for the *ārdrā* festival in the month of Mārgaḷi
- ātira-sālai* : s.a. *ātula-sālai*
- atiyurai* : offerings made at the feet of a high personage; written differently as *aḍiyirai*, *aḍiyarai*, etc.
- āṭṭai-k-kāṇikkai* : annual contribution or presents
- āṭṭāṇḍu* : every year
- āṭṭai-ch-chammādam* : probably s.a. *āṭṭai-k-kāṇikkai*
- āṭṭai-k-kōl* : yearly payment
- āṭṭai-p-pāl* : cultivable land left waste throughout the year
- āṭṭai-vāriyam* : annual committee for supervising the management of village affairs; s.a. *samvatsara-vāriyam*
- aṭṭavanai* : department of revenue in the state; revenue accounts; officer in charge of the same
- aṭṭimudal* : properties gifted of which only the income should be spent and the property kept in tact

*aṭṭir-pēru* : endowment for distribution of food (to the servants of a temple)

*aṭṭir-pēru* : gift with libation of water

*ā-t-tirai-p-pāṭṭam* : tax on cattle

*aṭṭanaikkāl* : a kind of stand or pedestal (probably of eight legs)

*āṭṭukk-īrai, āṭṭirai* : tax on sheep; also known as *āṭṭu-vari*

*aṭṭukkirai* : tax on charities

*ātular* : disabled or destitute person

*ātula śālai* : hospital

*avadāna* : (*avasāna*) termination, end

*aval-amudu-p-puram* : land endowed to a temple for the offering of *aval* (rice flake) to the god

*āvana-k-kaḷari* : place where documents like the sale-deeds, etc. are registered; registration office

*āvaṇam* : document, mostly sale-deed; also known as *vilai-y-āvaṇam*

*avani-vēṭanam* : s.a. *pāḍikāvāl*

*āvaraṇam* : shelter, covering, *prākāra* wall round the temple

*avasara* : officer of the royal household having the duty of bringing to the notice of the king anything that demanded his immediate attention

*avasara-varṭtanai* : presents payable to an *avasara*

*avikkīṇaru* : small hole like ventilator on the wall of a temple

*avirōdham* : not inimical, amicability

*āyakam* : administration of a village by a group of officers, called *āyagār* (village officers and servants)

*āyam* : general term denoting taxes [lit. income]

*āyap-p-pāḍi* : shrine for Kṛṣṇa; also known as *Gōkulam*

*āyira-t-taḷi* : palace (lit. building with one thousand rooms) *taḷi* room

*āyōgavar* : a sect of weavers

*bali* : offering to god of flower, fruits, rice, etc. uncooked; generally referred to also as *Śrībali*.

*bhaṇḍāri* : officer in charge of the treasury

*bhāratavar* : prob. *paratavar*, fishermen

*Bhārṣia-vritti* : land set apart for expounding the *Mahābhārata*

*Bhāshya-vritti* : land set apart for meeting the expenses of expounding the *Śrī Bhāshya* of Rāmanuja.

*bhaṭa* : personal servant; soldier

*bhaṭṭa-vritti* : tax-free land (*inam*) set apart for support of *brāhmaṇas*; also called *bhaṭṭa-vritti-mānyam*

*bhaṭṭāraka* : deity; spiritual preceptor

*bhaviṣya-k-kiḍai-p-puram* : tax-free land set apart to enable a person to reside permanently in a village and teach

*bhēri* : a musical instrument

*bhōgam* : tax-free land set apart for the enjoyment of a person for the performance of specified services; s. a. *mānyam*

*bhōga-āyakam* : mortgage by possession

*bhōga-patra* : lease deed; as well as the deed of its re-conveyance

*bhōgi(yār)* : mistress, concubine

*Bkujabalan-māḍai* : a coin current in olden days

*brahmadēya* : village given as gift, mostly tax-free, to *brāhmāṇas*

*brahmadēya-k-kilavar* : sole owner of the *brahmadēya* village

[This word is sometimes taken to mean the head-man or chief of a brahmadeya village; but it does not seem to convey the correct conception of the term.]

*brahmādhiraṇja* : title of distinguished *brāhmaṇa* military commander; also referred to as *brahmādarāya*

*brāhmaṇa-rāṣa-k-kāṇam* : tax payable by the *brāhmaṇa* (*purōhita*) to the king

*brahmapuri* : probably s.a. *agara-brahmadēya*

*brahmarāja, brahmarāya* : *brāhmaṇa* minister

*brahmasthāna* : *brāhmaṇa* quarters of a village

*chakra-kāṇikkai* : tax paid by potters; also known as *tirigai-āyam*

*chaṇḍēśvara* : traditional executive of the Śiva temple; referred to also as *Ādi-dāsa*

*chaṇḍēśvara-p-peruvilai* : sale price of land purchased from the Śiva temple. [lit. sale price of Chaṇḍēśvara, the traditional executive of the Śiva temple.]

*chandrādityavat, chandrādittaval, chandrādittavar* : as long as the moon and the sun last; in perpetuity

*chāṭtra* : see *śaṭṭar, śāttirar*

*chaturvēdi-bhaṭṭa-t-tāna-p-perumakkaḷ* : general assembly of the Vedic scholars in a *brāhmaṇa* village

*chaturvēdimāṅgalam* : village owned by the *brāhmaṇas*, mostly tax-free; also called *māṅgalam*; written as *śarupṭṭēḷimāṅgalam* in Tamil

- chatuś-sālai* : meeting hall  
*chāvāḍi* : s.a. *uśāvādi* : territorial division  
*chēri* : residential quarter; division; ward  
*cheru* : plot of land; field  
*chinnam* : a coin current in olden days  
*chinnam* : bugle; trumpet  
*chinna-p-pillaiyāṇḍān* : junior servant under the king's *aḍaiṇṇam*  
*chitramēli* (*Śittiramēli*) : agricultural corporation of the *Vellālas*  
  
*daḷa-adhikāri* : s.a. *daḷavāy*  
*daḷavāy* : *sēnāpati*; military commander  
*damma* : an old coin; *drachma*  
*dakṣiṇa-bhujā* : (lit. southern hand) right hand; the trusted lieutenant  
*dāna* : gift (in preference to sacrifice)  
*dāna-iraiyili* : gifted tax-free land  
*dāna-p-puram* : land set apart for the maintenance of charity  
*daṇḍa-k-kāṇam* : amount imposed as fine  
*daṇḍam* : fine or penalty imposed  
*daṇḍam, daṇḍu* : army  
*daṇḍa-nāyaka* : army officer; military commander; also referred to as *daṇḍanātha*  
*daṇḍaṇ-kurram* : fine and penalty imposed  
*daṇḍu, daṇḍikai* : palanquin  
*daṇḍikai-jivitam* : tax-free land given to palanquin-bearers for enjoyment during life-time  
*danma-paliśai* (*dharma-paliśai*) : equitable interest; standard and legitimate rate of interest  
*danmavāriyar dharmavāṇiyar* : the just merchants  
*danmi-eludutal, danmi-ūdal* : to proclaim (in the village) by the blowing of horn or bugle (from *dham*—to make noise by blowing) also written as *dhanmi-eludutal, dharmi-eludutal*  
*dānyādāya* : tax payable in grains  
*daśabandha* : tax or cess levied to keep in good repair the source of water supply, like the tank, etc.  
*dāsari* : s.a. *samayāchārya*  
*davana-ch-cheṭṭi* : a merchant class

*daśa-kriyai* : work of the architects who were to look after the repairs of temples

*dēvabhōga* : land given for the enjoyment of temples

*dēvadāna* : village or land gifted to a temple

*dēvadāna-iraiyili* : tax-free land gifted to temple

*dēvadāya* : s.a. *dēvadāna*

*dēvāgrahāra* : s.a. *dēvabhōga*

*dēvakanmi-p-pēru* : land for the enjoyment of the temple servants

*dēvar-aḍiyāl* : maid-servant (courtesan) attached to a temple

*dēvāram* : temple

*dēva(r)kanmi* : servant of god; temple servant; executive in charge of the temple affairs

*dēva-vritti* : land set apart for the support of temple

*dharma-dāna* : gift for charity; generally of some land tax-free

*dharma-dāna-uvachcha-aḍimai* : slave presented as a gift to a temple to serve as drummer

*dharma-k-kattalai-eḍai* : weighment according to the standard weight and ascertained by some neutral person

*dharma-k-kattalai-t-tulai nirai* : s.a. *dharma-k-kattalai-eḍai*

*dharmāsana* : seat of justice; law court

*dharmāsana-bhaṭṭar* : brāhmaṇas versed in law assisting in a *dharmāsana*

*dharma-vāriyam* : committee looking after the chartiable endowments and institutions

*dharma-vritti-iraiyili* : tax-free land gifted for the propagation or the conduct of some charity

*dharmikaḷ* : body or commission managing endowments

*dināram* : a coin in olden days; *dinar*, *denarius*

*dirgamānya* : land set apart for the supply of water and for the holy bath

*dirghika* : bath; a long or oval pond

*dramma* : a coin current in olden days; *drachma*, *dirham*

*dukka-p-puḍavai* (*dukkha-p-puḍavai*) : probably a shroud; cf. *elavai*

*duritam* : famine; disturbance

*echchōru* : free food to the village labourers in the night; also referred to as *erchōru*

- eḍai-vari* : tax on weights (is it *iḍai-vari* ?)
- eḍir-ām-āṇḍu* : [lit. opposite year] next, succeeding year
- eḍir-iḍai-y-ōlai* : counter document given to the executant
- eḍuttu-k-katti* : coping, covering course of a wall; parapet wall
- eḍuttu-k-kolṭi* : a tax in olden days the exact nature of which is not clear
- ēkabhōga-iraiyili* : tax-free land or village in the sole enjoyment of a single-owner
- ēkabhōgam* : sole possession and enjoyment of the village by a single person (without any joint owner)
- ēkabhōgam* : single crop; s.a. *oru-pū*
- ēkāṅgi* : single person; one who has no family, especially the Vaish-  
ṇava devotee in charge of temples
- ēkāvali, ēkāvalli* : necklace of a single string
- e-k-kaḍamai* : probably s.a. *ēr-k-kaḍamai*
- ekkālām* : trumpet
- elavai* : [read also as *ēlvai*] evidently death-duty; fee for crematorium
- ēla-v-ariśi* : cardamon seed
- elgai* : (s.a. *ellai*) boundary
- elund-arulun-tirumēni* : idol of a temple which is carried about in procession
- eluttu-viniyōgam* : tax or dues payable as *eluttu* for the village-  
accountant to be apportioned among the villagers
- ēndal* : irrigation tank
- ēṇi-k-kāṇam* : ladder tax evidently levied on toddy-drawers
- eṇney* : tax levied on oil-trade; obligation for the supply of oil
- eṇney-p-pandam* : supply of oil and torch when the common affairs  
of the village are conducted during nights
- erchōrru-k-kūrrariśi* : also referred to as *echchōrru k-kūrrunel* :  
probably free food in the night to persons who husk paddy
- ēri-āyam* : income from fishing in the tank etc.; amount payable  
by the owners of the fields irrigated by the tank for its upkeep
- ēri-ivu* : share in the expenses of the maintenance of the tank
- ēri-k-kāḍi* : one *kāḍi* of paddy on every field as tank duty
- eri-karumbu* : firewood
- eri-kōppu* : land adjoining a tank, which in times of flood would be  
covered with water and in other times available for cultivation;  
also known as *ēri-nīr-k-kōppu*



- ēri-mānyam* : tax free land set apart for the maintenance of tanks;  
also known as *ēri-p-paṭṭi*
- erimarundan* : manufacturer of gun-powder
- erimarundu* : gun-powder
- ēri-mīn-pāṭṭam* : income from the sale of fish in the tank
- ēri-mīn-vilai-p-paṇam* : money realised from sale of fish in the tank;  
also known as *ēri-mīn-kāśu*
- ēri-mudal* : land or money set apart of which the income alone to  
be utilised for the maintenance of the tank
- ēri-p-paṭṭi* : land set apart for the maintenance of tank
- ēri-vāriyam* : village committee in charge of the tank
- ēri-vāy* : land adjoining the outlet from a tank which in times of flood  
would be covered with water and at other times available for  
cultivation
- eri-vīra* : lit. warrior adept in throwing (javelin, etc.); member  
of a guild, probably of a military nature, forming part of the  
parental institution of *nānādēśi* of Ayyavole
- eri-vīra-p-paṭṭanam* : mercantile town
- ēr-k-kadamai* : tax on plough
- erikkaḍi* : probably s.a. *ēr-p-pon*
- ēr-k-kāṇikkai* : s.a. *ēr-p-pon*
- ēr-p-pon* : evidently the tax to be paid in cash for each plough
- ērra-k-kuraittal* : (be it) in excess or in diminution; more or less
- ērram* : increase; additional; excess
- ērrī* : to colonize; populate; to establish
- ērrī* : to add to; increase; to undertake
- erumai-p-pon* : tax payable on buffalo
- ēru-sāttu* : extra worship in connection with the *dhvajārōhaṇam* at  
the commencement of a festival
- ēru-sāttu* : export of merchandise; merchants engaged in the export-  
trade
- eyil* : fortified town
- ētta-p-pāḍam, ēttampulam* : land irrigated by means of lifts
- gadyāṇa* : a coin, probably equal to a *varāha* or pagoda
- gaṇa* : group of persons; community, religious guild
- gaṇabhōgam* : joint tenure of a village or villages by a number of  
persons

- gana-p-perumakkaḷ* : elders of the *gana* managing its affairs  
*ganattār* : people belonging to a *gana*  
*gana-vāriyam* : committee managing the affairs of the *gana*  
*gana-vāriya-p-perumakkaḷ* : elders of the committee *gana-vāriyam*  
*gaṇḍan* : warrior  
*ghara-kshētra* : building site  
*ghaṭikā* : educational institution of advanced studies; university;  
 probably s.a. *śālai* and *māhāśālā*.  
*ghaṭikai-madhyasta* : intermediary officer having the authority of, or  
 recognised by the *ghaṭikā*  
*ghaṭikai-mārāyan* : head musician; a title conferred in olden days  
*ghaṭikaiyār* : members of the *ghaṭikā* managing its affairs  
*ghaṭikaiyār* : those who inform the public by beat of tom-tom of the  
 orders of the kings and other officers  
*gōkulam* : temple for Kriṣṇa  
*gō-prachāra-bhūmi* : grazing-ground; s.a. *kanru-mēy-pāl*  
*grāma-drōhi* : traitor to the village  
*grāma-kaṇṭaka* : enemies of the village security  
*grāma-kārya* : village business  
*grāma-parihāra* : obligatory dues of the village  
*guhāi* : lit. cave; monastery  
*guttagai* : s.a. *kuttagai*  
  
*hari-dina* : Saturday; *ēkādaśī*  
*havir-bali* : *bali* offered with cooked food; s.a. *tī-y-eri-sōru*; (also the  
 tax payable for meeting the expenses of conducting the same)  
  
*ichchōppi* : whisk for flies, fly-flapper  
*iḍaba-t-taliyilār* : s.a. *riṣabha-t-taliyilār*  
*iḍaḍakku* : a part in jewels  
*iḍatorai (iḍaitturai)* : a tax in olden days the exact nature of which  
 is not clear  
*iḍai-nāḷigai* : passage between the *ardhamanḍapa* and the *mahā-*  
*manḍapa* in a temple  
*iḍai-p-pāṭṭam* : tax on herdsmen  
*iḍai-p-pūṭchi* : tax imposed on or undertaken by cattle-breeders; s.a.  
*iḍai-p-pāṭṭam*  
*iḍaivaṭṭai* : that which is in the middle

- iḍaivēṭṭu* : something obtained other than the main object  
*iḍaiyar-vari* : tax on shepherds  
*iḍaiyiḍu* : tenancy right  
*iḍaiyiḍu* : interim order  
*iḍaṅgai* : left hand class  
*iḍaṅgai-vari* : tax paid by the members of the *iḍaṅgai* community  
*iḍiñchil* : hollow portion of the lamp; earthen lamp  
*iguttuvittal* : closing, as by a sluice  
*i-k-kāl-āṇi* : rivet in an ornament, as small as a fly's leg  
*īla-ch-chēri* : quarters inhabited by toddy-drawers  
*īlakkaiyar* : fem. of *īlavar*  
*ilai-ch-cheppu, ilai-t-taṭṭu* : metal vessel or plate in the shape of a leaf used in worship  
*ilaiṣuni* : a white speck in the ruby; a property in the ruby  
*ilaivāṇiya-p-pāṭṭam* : tax on the sellers of betel-leaves  
*ilaivāṇiyar* : those engaged in the trade of the betel leaves  
*ilai-y-amudu* : betel leaves  
*īlaiya.nāyanār* : god Subrahmanya  
*īlaiya-vagai* : junior branch  
*ilakkai* : residence; residential quarters  
*ilakkai* : cloth; monthly wages  
*īla-k-kāṣu, īla-k-karunkāṣu* : Ceylon coin; also referred to as *karunkāṣu*  
*īlam-puñjai* : tax for toddy-drawing; s.a. *īlam-pūṭchi*  
*īlam-pūṭchi* : tax on toddy-drawers  
*īlāñjanai-p-pēru* : fee for affixing the royal seal; also referred to sometimes as *lāñjanai-p-pēru* and *lāñjinai-p-pēru*  
*īlāñ-chiṅga-vīrar* : (lit. warrior with the valour of youthful lion) member of a guild, probably of a military nature, forming part of the parental institution of *nānādēsi* of Ayyavōḷe  
*īlaṅkōyil* : s.a. *bālālayam*; temporary shrine to lodge the images of gods when repairing temples; small shrine, probably of single room wherein the images of all the gods are lodged  
*īlar-kaḍi-vari* : probably s.a. *īlampūṭchi*  
*īlavar* : toddy drawers  
*īlavaṭṭam* : younger generation

*ilichchu* : to grant remission as taxes; to pull down, dismantle, as a building; also found as *ilittu*

*ilikka* : to be dug or sunk as a well

*illari* : probably s.a. *ilvari*

*ilvari* : house-tax

*inavari, inavari-k-kāsu* : communal tax, payable in coin; cf. *jāti-siddhāya* in the Telugu inscriptions

*iṇḍai* : short circular garland worn round the head

*irai* : a general term denoting the revenue and the taxes to be paid to government

*irai-bhōgam* : enjoyment of the revenue; *mēlvāram*

*irai-ch-chōru* : probably s.a. *echchōru*

*irai-dravyam* : amount payable in commutation of the taxes payable [on landed property]

*irai-kāval* : amount of deposit which yielded interest per annum equal to the tax due on the land; (sometimes taken as tax for police duties)

*irai-k-kaḍan* : land-tax

*irai-p-poruḷ* : s.a. *irai-dravyam*

*irai-p-punai-p-paḍutal* : to stand security for the payment of tax by a person

*irai-viluttu* : s.a. *irai-y-ilittu*

*iraiyili* : tax-free; exempt from government taxes

*iraiyilittu* : to exempt from payment of taxes; also written as *irai-yilichchu*

*iraiyili-k-kāsu* : amount paid compounding the taxes, for making the land tax-free; (may also be taken as the amount payable to meet the shortage in the revenue occasioned by the grant of exemption from tax on certain lands)

*irai-y-irukkum-kōl* : rod for measuring land for the purpose of fixing the tax

*iraṅgal* : exemption, generally applied to *irai*, thereby meaning exemption from taxes

*iraṅkolli* : washerman; tax payable by washerman; (also as *iraṅkolli*)

*iraṅgu-sāttu* : extra worship in connection with the *dhvaja-avarōhana* at the conclusion of the festival

*iraṅgu-sāttu* : import of merchandise; merchants engaged in the import trade

*irāsi-p-pon* : pure gold

*iratta-k-kāṇikkai* : 'blood-present'; endowment of rent-free land for the support of the descendants of warriors killed in battle

*iratta-mānya* : s.a. *iratta-k-kāṇikkai*

*iravai* : night; *iravu*

*iravu-ch-chōru* : s.a. *echchōru*

*irāyaśam* : s.a. *rāyasam*

*iru(k)kāl* : twice

*iruppu* : payment of tax or debt

*iruppu-k-kaṭṭi* : (lit. block of iron) probably a tax for prospecting and mining iron ore; [may also be taken as the cake of the mahua seeds after expressing the oil, largely used as soap, in which case it will mean the tax for the manufacture and sale of such cake.]

*iru-pū* : double crop; two crops of cultivation

*iruṭ-kaṇṭam* : an ornament worn round the neck (*nīlakaṇṭha* ?)

*iśaikēḍu* (*iśaivukēḍu*) : damage

*iśai-k-kiḍāy* : literally 'beautiful ram'; dues to be paid for the ram kept for show; cf. *aḷag-erudu-k-kāśu*

*iśaivu-tiṭṭu* : deed of agreement

*iśaiyin-śelvi* : goddess of fame; muse

*iśai-y-ōlai* : a deed of compact

*iṭaṅka-sālai* (*taṅka-sālā*) : mint

*iṭṭam* : assemblage

*iyakkutal* : to conduct

*iyarranḍam* (*iyal+daṇḍam*) : ordinary fine

*jana-pradhāni* : probably a\*minister governing the people

*jaṅgama* : priests of the Lingayat or Vīraśaiva sect

*janma-bhūmi* : gift of land, most probably made for the life time of a person

*janma-k-kāṇi* : s.a. *janma-bhūmi*

*jātaka-k-kuḍi* : persons who have undertaken to serve, as the temple, etc., for their life-time

*jaya-pālas* : a class of merchants

*jaya-patra* : lit. certificate of victory [in a dispute]; judgment copy; also referred to as *jayarēkhapatra*

*jīvanam* : maintenance

*jivita-k-kārar* : persons in enjoyment of lands in the *jivitam* tenure

*jivitam* : assignment of land, mostly tax-free, for enjoyment during the life time of the assignee, evidently as salary in return for some service

*jivita-p-parru* : land or village granted in lieu of salary for an office holder

*jīyar* : ascetic or *sannyāsin* looking after the affairs of the temple

*jñāpakam* : remembrancer, memorandum of events and happenings

*jōḍi* : small quit-rent; also written as *sōḍi*

*kachchāttu* : s.a. *kaichchāttu*; receipt for payment

*kachchōlam* : small metal vessel for holding rice, sandal-paste, etc.

*kachchukōram* : a kind of vessel (cf. *kachchōlam*, *kaichchōlam*)

*kadalikai* : a part of the ornament like the girdle

*kaḍaikkāṭchi* : supervision

*kaḍaikkūṭṭu* : management

*kaḍai-k-kūṭṭu-t-tānattār* : one of the different names by which merchants of the *nānādēśi* are mentioned; temple authorities

*kaḍai-k-kūṭṭ-ilakkai* : residence or quarters for the persons who manage the affairs

*kaḍai-nīr* : water taken to a field which is to be irrigated last

*kaḍai-p-pū* : the last (or the third) crop

*kaḍai-i-tolil* : a part of pendant, probably having scroll-work

*kaḍai-y-aḍaikkāy* : evidently tax on arecanuts brought for sale

*kaḍaiyiḍu* : final endorsement; final order of a king or authority; sometimes denotes the orders of a subordinate authority

*kaḍai-y-irai* : the lowest rate of tax (final payment of the tax)

*kaḍaiyūru* : insurmountable difficulty; final obstruction

*kaḍamai* : revenue; tax to be paid to government in kind

*kaḍamai-k-kāl* : authorised measure of capacity

*kaḍamai-p-parru* : land or village paying the share of the produce to the State or land-lord in coin and not in kind

*kaḍavan* : one who is under obligation

*kaḍavatu* : that which should be done; duty

*kadir-k-kāṇam* : tax paid in sheaves of corn

*kāḍu-kāval* : tax for the preservation and maintenance of forests

*kāḍukōl* : cultivable land covered with jungle growth

*kaḍai-p-pāttam* : probably s.a. *kaḍai-p-pū*; also taken as the tax on shops or the dues at the lowest rate.

*kaḍamai-kāryam* : affairs relating to the state and its revenue

*kāḍu-tariṣu* : waste land with bushy growth

*kāhaḷam, kāhali* : trumpet; bugle

*kai-k-kaṇakku-mudal* : its exact nature is not clear

*kai-k-kaluttu* : wrist

*kai-k-kārai* : bracelet; arm-ring

*kaikkōḷar* : (lit. those who work with their hands) warriors of renown; weavers; also a class of temple servants [It is also to be noted that another word *aṭavi* means troops as well as weavers. What exactly is the connection between the warriors and the weavers is not known]

*kaikkōḷa-mudali* : head of the *kaikkōḷar*

*kai-k-kolludal* : to undertake

*kai-k-kūli* : bribe

*kaimmāṭṭāngu* : handmark of illiterate person

*kainkarya-parar* : servants in a temple

*kai-piḍi* : money or thing received on hand

*kai-t-taḍi* : mark of hand as signature by an illiterate person

*kai-t-tiṭṭu* : document; record; agreement; hand-note

*kai-valara* : to spread

*kai-vāsi* : right to receive handfuls of the articles like paddy, etc. brought for sale in markets

*kai-vilai* : current price

*kai-vinai-k-kuḍi* : artisan class (dist. from *ulavu-kuḍi* and *kāśāya-k-kuḍi*)

*kaiyālittal* : to hand over possession

*kai-yāru* : (lit. small river) field channel

*kai-y-elutt-ōlai* : promissory note

*kai-y-eluttu* : written document in pursuance of the agreement reached

*kai-y-ērpu* : probably tax on beggars; cf. *gāṇāchāram* in the inscriptions of the Telugu country

*kaiyiḍu* : receipt for remittance

*kaiyurai* : presents; giving as extra

*kai-y-uruvi-ch-chuvar* : parapet wall

*kākabindu* : black dot

*kalāba, kalabai* : raid, invasion, disturbance

- kāl-alavu-kōr-kūli* : fee for the use of the measuring rod  
*kāl-alavu-kūli* : toll on articles measured by capacity; also known as  
*kāl-alavu-p-pāṭṭam*  
*kalaiṇdu* : s.a. *kalaiṇju*  
*kalam* : eating plate  
*kalam* : document  
*kalam, kalan* : encumbrance  
*kalanai* : professional caste group  
*kalani-k-kūḷam* : tank amidst cultivable lands  
*kalani-p-puṇjai* : dry-field as distinct from *kāṭṭu-p-puṇṣey*  
*kalani-vāriyam* : village assembly that looks after cultivable lands;  
its members referred to as *kalani-vāriya-p-perumakka!*  
*kalaiṇju* : a gold coin current in olden days; also the equivalent weight  
*kāla-p-pollāngu* : evil times, bad time; also *kāla-dōṣham*  
*kalari* : court of justice; office  
*kalai-p-pāl* : brackish waste  
*kalasam-āṭṭudal* : bathing the god with consecrated water; consecra-  
tion  
*kalasa-p-pānai* : censer  
*kāla-t-tēvai* : a tax in olden days  
*kalāvam* : girdle  
*kāli-gaṇattār* : committee for the temple of Kali  
*kalīnga-vāriyam* : committee looking after the sluice  
*kalīngu* : sluice  
*kallāl-kāṇam, kallāṇa-k-kāṇam* : s.a. *kaṇṇāla-k-kāṇam*  
*kal-l-arai* : underground secret chamber for storing valuables  
*kalli-t-tiruttudal* : to lower the level of a field and render it fit for  
cultivation  
*kallūri* : verandah round the shrine; s. a. *śurrālai*  
*kal-nāḍu* : hero-stone; setting up of hero-stone  
*kāl-padaḍai* : lower tier of the wall  
*kāl-vaḍam* : ornament worn on the foot strung with pearls  
*kālu-k-kaluttu* : ankle  
*kalyāṇa-t-tirumēni-y-ātal* : to become sound in life and limb  
*kāma (gāma-grāma)* : village; used in the compounds like *gāma-k-*  
*kāni, gāma-k-kilavan*, etc.  
*kāma-k-kōṭṭam* : shrine of the goddess Parvatī as an adjunct of the  
Śiva temple in the same compound.



- kambi* : kind of ear-ring, evidently made of wire
- kammāṇa* : s.a. *kammāḷa*
- kaṇakan* : (*gaṇaka*) village accountant
- kāṇam* : a weight current in olden days; share; a coin in olden days
- kaṇḍakam* (*khaṇḍaka*) : a land measure
- kaṇḍalivu* : unforeseen expenses
- kaṇḍam* : a portion of the *mukhamanḍapa*
- kaṇḍan* : s.a. *gaṇḍan*
- kaṇḍa-p-paḍai* : basement panel in a building; tier of the wall near the ceiling
- kāṇḍaruvi* (*gandharva*) : songstress
- kaṇḍu* : pendent in an ornament like the necklace
- kaṇḍulavu* : private lands of a king
- kaṇakka-k-kāṇi* : land set apart for the village account
- kaṇakka-p-pēru* : tax, payable in kind, for the upkeep of the village accountant
- kaṇgil* : a part of the trumpet
- kāṇi* : right of possession; hereditary right; see *kāṇi-y-āṭchi*
- kāṇi* : a weight
- kāṇikkai* : presents or customary payment as offering to the king and other high officials
- kāṇi-k-kūli* : share payable
- kāṇi-mārudal* : to dispossess a person of his land
- kaṇi-murrūtṭu* : land or village free of all taxes (*sarvamānya*) and in the enjoyment of several persons in common (*gaṇa*); but sometimes taken as the tax-free land given to astrologers
- kāṇi-p-piḍipādu* : lease deed for cultivation
- kāṇi-p-parru* : village or land in full ownership
- kāṇiveṭṭi* : probably s. a. *veṭṭi*
- kāṇi-vilai* : sale of tenancy right
- kāṇi-y-āṇmai* : s.a. *kāṇiyāṭchi*
- kāṇiyāṭchi* : hereditary ownership or enjoyment
- kaṅgāṇi-mā-nellu* : dues, payable in paddy, for supervision work
- kaṅkāṇi* : same as *kaṅkāṇi*
- kaṅkāṇi* : supervisor; tax in kind for such supervision
- kaṅkāṇi-k-kaṅakkar-mudal* : land set apart for meeting the expenses of supervision
- kaṅkāṇi-nāyakam* : office of the chief supervisor

- kaṇ-kāṭṭuvān* : one who leads the blind  
*kaṇ-malar* : ornament made of gold or silver resembling the eye and put on the idol  
*kanmi* (*karmi*) : official; officer as distinct from servant  
*kaṇṇāḍi* : looking glass; tax on the users of the same; see *mugam-pārvai*; probably a tax on prostitutes; also cf. the tax *bedabinugu* (meaning coquettes fond of show) of the Kannaḍa inscriptions.  
*kannāḍu* : see *kal-nāḍu*  
*kanna-k-kāṇan* : brazier  
*kaṇṇiṭṭu-k-kāṇam* : evidently fee for the supervision or *kaṇkāṇi*; sometimes taken as tax on the plant *kariśarāṇkaṇṇi* used in medicine  
*kaṇṇāla-k-kāṇam* : tax on marriage  
*kanna-pushpam* : ear-ornament in the shape of a flower  
*kanuār-irai* : profession tax payable by brazier  
*kaṇ-ṇ-āru* : irrigation water-course leading to a paddy field, as a stream issuing from a sluice  
*kanru-mēy-pāl* : pasture land of the village  
*kaṇṭaka-sōdhanai* : criminal justice [see the Madras Museum plates of Jaṭilavarman Parantaka Paṇḍya and the *Aṛihaśāstra* of Kauṭilya]  
*kaṇṭha-t-tuḍar, kaṇṭa-nāṇ* : kind of necklace  
*kappam* : periodical and customary payments by persons engaged in some professions  
*kār* : paddy crop raised in the winter season; a variety of paddy harvested in the months of *Aippaṣi-Kārttigai*; also denotes the period of the *kār* harvest.  
*kaṇḍikai* : component part of an ornament  
*kaṇḍu* : a variety of pearl  
*karai* : division; share  
*karai-k-kūru-śeyvār* : those who look after the equitable distribution of lands among the villagers  
*karai-nilam* : land subject to periodical re-distribution amongst cultivators  
*kara-grāma* : revenue or ryotwari village  
*karaiyīḍu* : tenure holding the village in common; enjoyment of the individual share  
*karakshētra* : (*ghara* +) building site  
*kār-aḷattal* : to measure paddy  
*karaṇam* : document; accountant

- karaṇam* : a grade of law court, lower in rank to *adhikaraṇa*  
*karaṇa-dandam* : fine imposed by the *karaṇam*  
*karaṇam* : the imperial censor  
*kāraṇavan* : accountant; also referred to as *kāraṇika* and *karaṇattār*  
*karaṇḍikai* : a variety of crown; name of a special part of the crown  
*karaṇḍikai-ch-cheppu* : small metal box for keeping quick lime to be used with betel  
*karaṇikka-jōḍi* : *karaṇam*'s quit-rent  
*kārāṇ-kilamai* : occupancy right in a field  
*kārāṇmai* : tenure with hereditary right of enjoyment; cultivation right; tax for the same; also known as *kārāṇ-kilamai*  
*kara-vrunda* : a variety of diamonds  
*kari* : failure of crops  
*karivi* : implement; razor of the barber  
*kār(i)ya-karttā* : agent; also known as *kār(i)yattukku-k-kaḍavar*  
*kāriya-p-pēru* : probably s.a. *kāriya-v-ārāyechchi*  
*kāriya-v-ārāyechchi* : cess paid for superintendence of transaction; s.a. *ārāyechchi*  
*karkāram* : stone work  
*karkavi* : eaves of stones over the door-way  
*karkidai* : brick-kiln  
*kār-marū-nilam* : double crop land  
*kar-paḍuttal* : To pave with stones  
*kar-padittān* : person who inscribed the record  
*karparru* : unpolished ruby adhering to the ore ; one of the defects in the ruby  
*karpittal* : installing, as a deity in a temple  
*karppūra-vilai* : sale-price paid for temple lands ; price paid for cultivation rights of temple lands and in commutation of the taxes thereon  
*karrali* : temple built of stone  
*karttākkaḷ* : title by which the Nāyaka rulers of Madurai were referred to in their inscriptions  
*kārttigai-k-kāsu*, *kārttigai-k-kāṇi* *kārttigai-p-pachchai*, *kārttigai-y-ariśi* : payments in kind in the month of Kārttigai (during harvest ?); cf. *āḍi-p-pachchai*  
*karu* : mound of earth

- karukku* : engraving, carving, embossed work
- karuñ-chey* : dry land; uncultivated waste; *kāṭṭu-p-punsey* as distinct from *kalani-p-punsey*
- karuvi-panam*, *karivi-p-panam* : tax, in coin, on implement, probably on barbers
- karuvūla-vari* : fee for the safe-custody of precious articles in the treasury; it may also be taken as the fee for the watch of the treasury
- kāśāyam* : tax and dues payable in coin; also known as *kāśāya-vargam* and *kāśu-vargam*
- kāśāya-k-kudi* : tenants occupying house-sites in the village free of rent in return for common village service.
- kaśu* : measure of weight equal to  $\frac{1}{4}$  *palam*
- kāśu-kaḍamai* : tax payable in coin
- kāśu-kal* : standard weight for weighing jewels
- kāśu-kollā-iraiyili* : land exempted from all kinds of taxes
- kāśu-kollā-ūr-k-kiḷ-iraiyili* : land exempted from taxes, not by the state, but by the village assembly undertaking to make good the loss in revenue to the state
- kaṭakam* : fortified place; cantonment; military camp
- kāṭchi* : presents offered to a great person when seeing him
- kāṭchi-y-erudu-k-kāśu* : tax probably on bulls kept for show
- kaṭigai-kalattu-k-kōl* : measuring rod, evidently authorised by the *ghaṭika*
- kaṭṭalai* : endowment for some special services in a temple, distinct from the one for general upkeep and maintenance
- kāṭṭāl-kāśu* : tax in olden days the exact nature of which is not clear
- kaṭṭanam* : periodical presents made to superiors by their subordinates
- kāṭṭa-p-perudal* : to demand production and lay claim
- kaṭṭāyam* : consolidated amount payable as dues (of the minor taxes); also written as *kaḍḍāyam*; sometimes taken as the compulsory payment of certain dues
- katti-k-kānam* ; tax on weapons like sword, etc., (tax on arms ?); may also mean tax on the profession of manufacturing sword or arms
- kaṭṭil* : throne
- kaṭṭu-kōḍage* : grant of a piece of tax-free land watered by the tank, canal or well which he constructed; s.a. *daśavanda*

*kattu-k-kuttagai* : fixed rent when farming out the land; consolidated payment of rent

*kaṭṭumukkai* : [lit. three handful in a bundle] a contribution payable to temple, evidently of three handfuls for every bundle of paddy stalks harvested; cf. *arimukkai*

*kāvalgār* : policeman

*kāvaṇam* : garden ; grove; tope

*kavar* : branch, as of a channel

*kāvidi* : title conferred on noble in olden times; accountant

*kāvidimai* : accountant's work

*keḍu-pādai* : [lit. damaged-path]; probably the obligation to keep the pathways and roads in good repair

*kēḷvi* : (lit. hearing) the officer who hears the oral orders and issues instructions accordingly or the chief executive

*kēḷvi-mudali* : an officer of the king's household, evidently charged with the duty of obtaining king's orders on petitions

*kēḷvi-vari* : register of royal commands

*kēṭpōr* : students qualified to study; see *śāttirar*

*kidāram* : cauldron; boiler

*kīl-iḍu* : sub-tenancy; sub-ordinate or subsidiary

*kīli-k-katti* : a kind of knife

*kīl-irai* : minor taxes; may also be taken as the tax at lower rate

*kīl-irai-p-pāṭṭam* : small cesses and taxes like *mīn-pāṭṭam*, etc.

*kīl-k-kalanai* : village artisans; subordinate group

*kīl-k-kumili* : syphon in the bed of a channel; see also *kumili*

*kīl-p-pādi* : (lit. lower half) tenant's share of the crop

*kimpuri-mugam* : ornamental knob, as part of a jewel

*kīrru-vari* : tax on thatched shed

*kirukula* : commercial tax or toll on retail articles; also referred to as *kirukūla-viśēsham*; cf. *kūlam*

*kōḍam* : tapering portion of the crown

*koḍavar* : a class of temple servants; also written as *kuḍavar*

*kodi* : [lit. boiling] food offering to the deity

*koḍi* : waist-string

*koḍi-k-kaḍamai* : taken to mean the tax for the cultivation of the medicinal plant *koḍi-vēli*, otherwise known as *chitramūlam*; most probably it is *kōḍi-k-kaḍamai* meaning the tax on new cloth; cf. *tiru-p-pudiyidu*

*koḍukkan* : son; cf. Tel. *koḍuku*

*koḍukula savaiyār* : a class of *dhūltas*, envoys

*koḷkuvāy* : hook of a clasp in an ornament

*koḷ* : a small measure of weight

*kōḷakai* (*gōḷakai*) : a coin, probably circular in shape, current in olden days; referred to also as *kuḷigai*

*koḷkai* : a kind of vessel; probably *koḷkalam*

*kōl-kūli* : tax for measuring, either for linear measurement or weighing

*kōl-nirai-kūli* : tax on articles measured by weight

*koḷmurai-p-pāḍu* : dues customarily received

*koḷu* : tax on plough share

*koḷundu* : a sweet smelling plant, *marukkoḷundu*

*koḷuvāram* : cultivator's share of the produce

*koḷvari* : tax in kind evidently for collection

*kōmalam* : a kind of ruby

*kōmukam* (*gōmukha*) : gargoyle as in the form of cow's head, projecting from the pedestal of *linga*

*kō-murai* : revenue due to the king

*kō-p-pada-vāram* : tax due to the king

*korrilakkai* : probably *korru* and *ilakkai* meaning food and residence

*korru* : food; provision made for the same

*kōṭṭai-k-kūli* : lit. wages on nuts; most probably it is *kōṭṭai-k-kūli* meaning the charges for the upkeep of the fort; cf. *kōṭṭai-magamai*

*kōṭṭagam* : sheet of water, large and deep

*kōṭṭagāram* : granary; cf. *kōṭṭāram*

*kōṭṭai-magamai* : tax for the maintenance of the forts

*kōṭṭi-maddālam* : big drum of the *maddāla* variety

*kottu* : part; division; classes of servants

*kōvai* : a gold coin current in olden days

*kōvaṇavar* : lit. those wearing clouts; a class of temple servants, especially in Viṣṇu temples; probably religious recluses

*kōvikkal* : palace

*kōvil-kēḷvi* : temple manager

- kiḍai* : scholars in the *Vēdas*; institution where *Vēdas* are taught
- kiḍai-p-puram* : tax-free land endowed for the promotion of Vedic studies
- kōyil-kottu* : palace or temple servants; *kōyil parivāra-k-kottu*
- kōyil-vāriyam* : committee managing a temple
- kōyil-vāsi* : minor taxes payable to the palace
- krama-vittan* : brāhmaṇa well-versed in the *krama* method of reciting the *Vēdas*.
- kuchchi* : probably *kuchchil* or *kuśa* grass
- kuḍa-dēvan* : sage Agastya as pitcher-born
- kudambai* : a kind of ear-ring
- kuḍamulā* : loud sounding drum, large and hemispherieal or pot-like in shape
- kuḍa-nāli* : one *nāli* for every pot
- kuḍa-p-paḍai* : horizontal section above the basement of the inner shrine of a temple
- kuḍavar* : a class of persons doing service in Viṣṇu temple, probably followers of the cult of Kriṣṇa; possibly also cowherds; see *koḍavar*
- kuḍavarai* : underground cellar; small room in the *gōpura*
- kuḍa-vilakku* : pot-shaped lamp waved before the god during worship by dancing woman to the accompaniment of music and dance
- kuḍa-v-ōlai* : election by ballot in the form of palm-leaf strips and cast in pot
- kuḍi-k-kāṇam* : fee paid by tenants; probably *kuḍi-k-kāṣu* and *kuḍi-p-paṇam* are the same
- kuḍimai* : general term denoting all the taxes, with the exception of land revenue, payable to the state for the protection it offers of the civil rights; tenancy tax.
- kuḍimai-p-pāḍu* : service; common work of the village
- kuḍinai, kuḍiñai-k-kal* : standard weight; also known as *kuḍi-nar-kal*
- kuḍiṇiṅgā-iraiyili* : tax-free land or village without evicting the existing tenants, thus making the grantee enjoy only the proprietary right and the *mēlvāram*
- kuḍi-ṇiṅgā-t-tēvadāna* : endowment to a temple, of lands already in the occupation of cultivating tenants

*kudīnīngā-t-tiruvīḍaiyāṭṭam* : land or village endowed to a Viṣṇu temple without evicting the existing tenants, thus making the temple enjoy only the proprietary right

*kudī-nīṅgi(ya)-dēvadāna* : land or village endowed to a temple after removing the previous tenants, thus making the temple enjoy both the proprietary and cultivating rights

*kudirai-ch-chēvagan* : cavalier

*kudirai-mārru* : a coin with horse-emblem

*kudirai-p-pandi* : place where horses are kept; stable; tax for the same

*kudirai-vari* : tax on horses; also known as *kudirai-mārru*, *kudirai-v-ilāḍam*; probably s.a. *kudirai-p-pandi*

*kudirai-v-ilāḍam* : (lit. horse-shoe) fee for shoeing horses; probably connected with *kudirai-p-pandi*

*kudiyilār* : tenants

*kudī-y-irukkai* : residential quarters of the village

*kudumbu* : division; ward; hence *kudumbu-variyaṁ* : divisional or ward committee

*kulai* : artificial bank, bund, dam

*kulai-veṭṭi* : *veṭṭi* or the obligation of free labour to keep the bund in good repair

*kula-k-kil* : land or tract of land watered or irrigated by a tank

*kūlam* : tax on grains and pulses; cf. *kirukulam*

*kulaḥpramāṇam* : sale of tank and its rights

*kulaḥavai* : enjoyment of the tank and its income

*kūli-ch-chēvakam* : mercenary soldier

*kūlikai (gūlikā)* : a coin current in olden days; s.a. *kōḷakai*

*kūlirndā-nir* : fine water, as in gems

*kūlivari-y-ērrutal* : to levy land-tax

*kūlivu* : (lit. depression) a flaw in the ruby

*kumara-kachchāṇam* : (*kumara-gadyāṇa*) a tax payable in coin, probably for the maintenance of the temple of Kumāra or Subrahmaṇya

*kumāra-varga* : subordinate chieftains who consider themselves as (sons) of the family of the ruling chief

*kumilī* : s.a. *kīl-k-kumilī*

*kumuda-p-paḍai* : bottom part of the wall in the sanctuary of the temple



- kūn* : [lit. cauldron] food offering to a deity  
*kuṇaviyadu* (*guṇaviyadu*) : that which is superior  
*kuṇaviyan* (*guṇaviyan*) : a kind of ruby  
*kunḍigai-k-kal* : stone with the emblem of a pitcher planted to mark the boundary of the lands of the Jaina temple  
*kuṇḍu* : globular gold bead  
*kuṇḍu* : horse  
*kunippam* : a variety of dance  
*kunri* : [lit. red seed of crab's eye] a weight for weighing gold  
*kuppi-vairam* : a species of diamond  
*kūr-aḍaittal* : to divide into lots and assign the lots to individuals  
*kurai-varuppu* : head-load of articles intended for the palace  
*kurangu* : small channel, probably connecting two bigger ones  
*kurappu-veṭṭi* : obligation of keeping in good repairs the channel-bunds  
*kurār-paśu*, *kurāl-paśu* : tawny cow  
*kuravaḍigal* : Jaina teacher  
*kurattigal* : Jaina preceptress  
*kuri* : assembly of the village; s.a. *sabhā*  
*kūrran-vāy* : main sluice  
*kūrrariśi* : obligation of husking paddy of the temple into rice and the charges to be met for the same  
*kur-r-ēram* : small picottah  
*kurru-nel*, *kūrru-nellu* : tax for husking paddy, payable in kind  
*kurra-t-taṇḍam* : fine and penalty for offences committed  
*kūrudal* : to cry out, as the price  
*kurru-kūli* : wages for husking paddy; probably same as *kurru-nel*; see also *kūrrariśi*  
*kurru-maḍal* : small receptacle for sacred ashes  
*kuruni-p-pāḍu* : land requiring one *kuruni* of paddy to sow it  
*kūru-śeyvār* : lit. those who apportion; committee leasing lands  
*kuśa-k-kāṇam* : tax on potters; also known as *tirigai-āyam*  
*kuttagai* : contract of lease  
*kuttal-ariśi* : husked rice; see *kūrrariśi*  
*kūttamōalan* : theatre hall in temple or palace  
*kuttukāl* : obstruction, impediment, hindrance

*lakṣhaṇa* : document, deed

*lāñjanai-p-pēru* : s.a. *ilāñjanai-p-pēru*

*mā* : one-twentieth of a *vēli*, land measurement; also a measure of weight

*machchālvi* : *māithunan*; wife's brother; elder sister's husband

*māḍai* : a gold coin current in olden days

*maḷai* : food offering to a deity; boiled rice

*māḍai-k-kūli* : tax, evidently for minting gold into coins

*maḍai-p-palli* : kitchen

*maḍai-p-palli-p-puram* : village set apart for the expenses of temple kitchen

*maḍai-p-pōkku* : sluice; flood-gate

*māḍa-k-kōyil* : temple with narrow passage built on mounds

*madalai* : son

*māda-p-paḍi* : allowances payable monthly; also known as *mādārik-kam*, *mādam* and *mādārikkai*

*maḍappuram*, *maḥa-p-puram* : land or village endowed to a *maḥa*

*māḍāpatyam* : management of the affairs of a *maḥa* and temple; also *maḍāpatyam*

*maḍavaḷāgam* : residential quarters around a temple; written also as *maḍaviḷāgam*

*māḍavidī* : main street around a temple

*madhyasta* : neutral person, mostly village headman

*māḍu-kāṇikkai* : obligation of supplying draught cattle to the visiting nobles by the tenants

*magamai*, *magnmai*, *magaṇmai* : small portion of the income or of the value of articles of merchandize collected as voluntary contribution by the merchants from among themselves for the maintenance of temples and other specified charities

*maganmai* : poll-tax

*mahābhārata-vritti* : land endowed for expounding the *Mahābhārata*

*mahābhūtagaṭa dānaṁ* : a kind of gift

*mahadāham* : great-thirst; the *naraka* or hell which a soul is supposed to pass through after death on the way to the other world

*muhādēvi* : chief queen

*mahājana* : the brāhmaṇa residents of the entire village; all the members of the village assembly; general body of the assembly *sabhā*

*mahāmaṇḍalēśvaran* : governor in charge of the province; also known as *mahāmaṇḍalīkan*

*mahāmaṇḍapa* : large pillared-hall next to the *ardha-maṇḍapa* in a temple

*mahā-mātra* : senior minister

*mahānāḍu* : the general assembly of the mercantile community

*mahānagaram* : merchants guild of the great city

*mahāniyōga* : king's order; royal command; officer bearing the same

*mahappaḍi* : an item of expenditure in temple, probably for *māgha* festival

*mahāpradhānan* : senior councillor of the king, usually in those days also a military officer; s.a. *mahāpradhāni*

*mahāsabhā* : general body meeting of the *sabhā*; meeting of the *mahājanas* in session

*mahāsākhai* : main branch of a tree

*mahāsāmanta* : vassal chief, sometimes holding positions as minister or governor

*mahātantra* : army council; grand council or the great assembly of the army

*mahā-tōraṇam* : a variety of temple lamp; probably to be read as *makara tōraṇam*

*mahā-vaḍḍa-vyavaḥāri* : the great banker; chief merchant; head of the mercantile guild

*mahāvīratana* (*mahāvratin*) : follower of a sect of Śaivism; an ascetic of the *Kālāmukha* sect

*mahāvvyavasthai* : probably *mahāsabhaivivasthai*; the regulations framed by the *mahāsabhā*

*mahēśvara* : followers of the Śaiva religion; congregation of Śaiva devotees having a voice in the management of the affairs of a Śiva temple

*mahēśvara-p-perundarisanattār* : Śaiva devotees, probably the followers of the Pāśupata sect.

*maichchunan* : (*maichhuna*) wife's brother; elder sister's husband

*makkaḷ-chēvakam* : personal service; hence one does who personal service is *makkaḷ-chēvakan* and the office *makkaḷ-chēvaka-p-pēru*

*makkaḷ-pēru* : obligations due by a citizen; dues payable to a temple; poll-tax ? or *makkaḷ-Śēvaka-p-pēru* ?

*makkaḷ-āyanār* (*makkaḷ-nāyanār*) : king's son

*makāram* : ear-ring shaped like a *makara*

- makara-saṅkrānti*, *makara-saṅkramaṇa* : entrance of the sun into Capricorn; commencement of the month Tai
- malai-kuṇṭiya-niṇṇār* : god Vēṅkatēśa on the Tirupati hills
- malaiyāḷa-mudali* : chief of a tribe of hillmen
- malaiyāṇ-viḷakku* : a kind of lamp
- malar* : knob or head in a weapon
- māḷigai-k.kōl* : a measuring rod authorised by the palace
- māḷigai-nāyakam* : office of the chamberlain in the palace
- mallāyi-maghamai* : probably a customary collection in the market the exact nature of which is not clear
- maḷu* : ordeal of red-hot iron
- māmaḍi* : maternal uncle; father-in-law
- māmagam* : a tax in olden days payable in cash probably for the great *māgha* (mahā magha) festival; probably it is *mārgam* written incorrectly
- māmūl-ādāyam* : customary payment
- mānabhōgam* : enjoyment of the *mānya* lands
- māna-daṇḍam* : rod of the unit of length for measuring land
- manai-k-kaḍaiyān* : one who keeps a shop in his house-site
- manai-p-paḍappu* : house garden; also known as *manai-p-paḍappai*
- manai-p-paṇam* : house tax; also known as *manai-vari*
- manai-vāṇḷam* (maṇai+val+ṇḷam) long piece of land at the back of the house
- maṇāṭṭi* : woman disciple
- maṇai-y-irai* : house-tax
- manai-y-irai-śōru* : free food to be supplied
- māṇavattil* : measuring cup
- maṇavāṭṭi* : wife
- mandai-kaṇḍ-ērram* : creation of the grazing ground in a village
- mandai-p-paṇam* : tax on cattle grazing in the village common
- maṇḍaiyaviyan* : person belonging to the *māṇḍavya-gōtra*
- maṇḍakam* : s.a. *maṇḍapa*
- maṇḍalam* : territorial division; province
- maṇḍala-mudanmai* : leadership or governorship of a province, its governor or chief being known as *maṇḍala-mudaliyār*
- maṇḍala-mudanmai-p-pēru* : fee for presents offered to the ruler or chief of the territorial division, *maṇḍalam*
- maṇḍalika* : ruler of a *maṇḍala*; also referred to as *maṇḍalēśvara*

- maṇḍapa-k-kottu* : temple servants  
*maṇḍa-vāḍai* : gentle northern breeze  
*māṇḍōṭṭu-p-pachchai* : a kind of emerald  
*maṅgalam* : brāhmaṇa village; shortened form of *chaturvēdi-maṅgalam*  
*māṅgūy-nāṇ* : necklace having mango-shaped pieces  
*maṅgiliyam* : ornament *tāli* worn round the neck of married woman  
 with her husband living as marriage badge  
*māṇi* : lit. *brahmachāri*; disciple; celebrates assigned for service in  
 temples  
*maṇichcham* : individual  
*maṇigrāmam* : mercantile guild  
*maṇi-k-kalan* : ornament set with stones  
*maṇikka-panḍāram-kāppār* : keeper of the treasury (mostly of  
 precious stones) in the temple or palace.  
*māṇikkattār* : dancing women attached to temples  
*maṇi-ṛ-ambalam* : audience hall  
*maṇjādi* : a weight equal to two *kunri-maṇi* in weighing gold  
*maṇjal-kāppu* : holy bath of deity with turmeric  
*maṇjikkam* : uncultivated land near a village; poromboke land  
*maṇ-madil* : lit. high wall or rampart made of mud; tax for the  
 erection and upkeep of such a wall  
*maṇṇān* : washerman for Harijans  
*maṇṇanār* : god Viṣṇu  
*maṇ-pāḍu* : earthen mound; ridge of earth  
*māppadakku* : payment at the rate of one *padakku* or two *kurunṇi* for  
 every *mā*  
*māppaṇam* : a coin current in olden days ; a tax payable at the rate  
 of one *paṇam* for every *mā*  
*māppaṭṭaḍai* : tax in olden days, probably for penning of cattle; may  
 also be read as *mara-p-paṭṭaḍai* meaning timber depot referring to  
 the tax payable for the same  
*maṇṇādi* : shepherd  
*maṇṇādi-vāriyam* : committee looking after the affairs of the temple,  
 evidently of Śiva (maṇṇādi—Naṭarāja)  
*maṇṇam* : hall; popular assembly  
*maṇṇu* : court of justice  
*maṇṇu-dal* : to fine, punish  
*maṇṇu pāḍu* : fine or penalty imposed by court of justice

- mantra-pōnakam* : a variety of food offering to god
- manu-v-āru* : according to the code of Manu
- mara-k-kaḍamai* : tax payable for trees
- mara-machchādi-vilai* : usufructory income from trees, fisheries etc.
- mara-māṇikkar* : a class of warriors inhabiting the region about Pon-Amarāvati
- mara-māñjāḍi* : tax of one *māñjāḍi* on each useful tree
- maravaḍai* : enjoyment of the usufructs of fruit bearing trees; also written as *maraviḍai*
- mārāyan* : a title bestowed by a king
- mārgāḍāyam* : toll on the articles in transit
- māri* : degree of fineness of gold; *mārru*
- maṇjāḍi* : customary dues
- maṇiyādi* : manner; way; extent; limit; also written as *marjādi*, *maṇisādi*, *maruśādi*, etc.
- mārram* : orders; instructions
- maru* : fragrance plant, marjoram, as distinct from *kolundu* commonly known as *marukkolundu*
- maru*, *maruvu* : second crop
- marukāl-talai* : drainage sluice
- maruttuva-p-pēru* : tax-free land given to a village physician
- māsāttu-nāyan* : merchant-prince; chief of the traders; also a title conferred by the king in olden days on the chief merchant
- māśu-maru* : spot, fault
- maṭha* : place where pilgrims and religious mendicants and *tapasvins* are fed
- māttāl* : at the rate of per *mā*
- maṭṭam* : small
- maṭṭappū* : a pendant in a jewel
- maṭṭ-aridal* : to sign a document as witness; be witness to a transaction
- maṭṭa-t-tārai* : smooth edged, as a diamond
- maṭṭa-t-tārai-ch-chappaḍi* : flat diamond with smooth edges; *maṭṭa-t-tārai-ch-chavakkam* is also probably the same
- mattiyakkan* : s.a. *madhyasta*
- māṭṭu* : belonging to; relating; fr.m
- māṭṭu-k-karai* : tax, probably on cattle, cows and buffaloes

*māvaṇṇai* : land where village cattle are penned and the right of using the same; also written as *māviṇṇai*

*māvinda-k-kaḍamai* : tax payable to the king

*mā-v-irai* : probably *māvinda-k-kaḍamai* is the same

*mayilāppil* : ancient name of Mylapore (Mayilāppūr), a part of Madras

*māyilatti* : a term of respect applied mostly to womenfolk in the royal harem

*mahāprabhu* : the great banker; senior merchant; the title by which the leader of the *nānādēśi* merchant community was designated in olden days

*mēḍ-ērram* : high land

*mēḍu-kalludal* : to level down, digging the high ground

*mēlaḍi* : taxes paid in kind

*mēl-eluttu* : senior clerk; chief of the accountants; auditing officer; instructions of a superior officer; signature of the higher officer approving the orders of his subordinate

*mēl-oḍi* : s. a. *mēlvāram*

*mēl-śānti* : chief priest in a temple

*mēl-veṭṭa-p-pēru* : land or village the revenue of which was set apart to meet the expenses of public works (*veṭṭi*) of the district

*mēlukku-aḍigal* : servants who clear and wash the floor with cow-dung in a temple

*mēlukku* : smearing the floor with cow-dung mixed with water; smearing the idol with unguent

*mēlukku-p-puṇam* : land, mostly tax-free, set apart for people sweeping and washing the floor in a temple and also for applying fragrant paste to the image of the deity

*mēlvāram* : share in the produce due to the proprietor

*mēṇaṇṇai-nīr* : surplus water

*mēni-p-pon* : poll-tax; tax on individual

*mēnīr* (*mēl-nīr*) : rain water

*mērai* : a portion of the crop harvested given at the threshing floor to certain village officers and servants as perquisite

*mēvāḷi* : probably s.a. *mērai*

*mērvai* : a share of grain from each harvest to a village officer

*mēṇ-kōyil* : the temple of Viṣṇu, being situated to the west in a village

*mēṇ-pādi* : s. a. *mēlvāram*

- mēr-pāṇi-kāval* : policing duty of the larger division of the territorial area, *nāḍu*
- mēṭṭu-nilam* : [lit. high land] evidently tax payable for the cultivation of such high grounds
- mey-k-kāṭṭu* : personal attendance
- meykāval* : [lit. body-guard] watchman, guard of a temple
- meymaṭṭu, meymaṭṭu-k-kāni* : right of beating the small drum (*mṛidaṅga*) as an accompaniment to dancing
- mēyppān* [lit. shepherd, grazier] a supervisor; probably related to *kaṇ-kāni*; cf. *manai-mēyppān-kolḷum-irai* : the tax for the supervisor of houses or building-supervisor
- mey-tāṅgi* : seat
- mey-vēru* : individually
- meyyāṭchi* : s.a. *mīyāṭchi*
- mī.kai* : uplifted arm; upper hand
- milāḍu* : s. a. *malāḍu*; the country ruled over by the Malaiyamans; also known as *naḍuvil-maṇḍalam*
- milagu-taragu* : brokerage fee on pepper trade
- mīn-kaḍamai, mīn-pāṭṭam* : income from fishing
- mīn-payil-paṭṭam* : ditches where fishes breed
- mī-y-āḷuṅgaṇa* : committee appointed by the *sabhā* to exercise control of overlordship
- mī-y-āḷuṅgaṇattār* : members of the supervising body
- mī-y-āṭchi* : proprietorship; overlordship; *mēlvāram* of land
- mōkkilam* : (*mōksha*) salvation
- mōnampāṭṭam* : a tax prevalent in olden days, the exact nature of which is not clear
- mōrviyam* : a kind of reed-pipe; *mukhavīṇai*
- mudal* : fund; capital yielding interest; stock; store
- mudali(yār)* : chief
- mudali-p-piḷḷai* : evidently the junior of the chief *mudali*
- mudal-mariyāḍai* : first preference in doing the honours in a temple; also referred to as *muṇ-mariyāḍai*
- mudal-pāvāḍai* : chief servant waving cloth in front of a noble
- mudal-tīrtha* : honour of receiving holy water first in a congregation in a Viṣṇu temple
- muḍaṅgu* : jutting part of a field
- mudar-pāvāḍai* : an honour; paraphernalia; s.a. *mudal-pāvāḍai*



- mudar-ṣaḍai-kalanaiyār* : one of the sections of the *nānāḍēśi*, evidently men of military occupation
- mudarriramam* : (mudal tiramam) a tax payable in cash, the exact nature of which is not clear; *tiramam* is the coin *drachma*
- muddirai-karttū* : keeper of the seal; the agent or manager
- mudukaṇ* : guardian, warden
- mudukkaḷ* : ancestors
- mudu-tarai* : barren land; waste
- muga-maṇḍakā* : *mukha-maṇḍāpa*; front hall in a temple
- mugam-pārvai* : looking glass; see *kaṇṇāḍi*
- mugan-tuḷaittal* : to shave one's face
- mugaṭṭu-k-kāl* : high level channel
- muka-kattānam* : porch; also *darśana-kāṇikkai*
- mukavetti* : designation of an officer, head of a department, probably in charge of communications of that particular branch, in the days of the Chōḷa rule
- mukkai* : three handfuls; cf. *arimukkai*
- mukkāl-vaṭṭam* : temple
- mu-k-kuḍai-k-kal* : boundary stone with the emblem of triple parasol to mark the limits of the lands belonging to a Jaina temple
- mūḷku* : [lit. nose] spout in a pot; hence *mūḷku-vaṭṭagai* basin with nose-shaped lip
- mukṭiyār* : agent
- mūla-bhṛitya* : Chāṇḍēśvara, as the chief servant of Śiva
- mulai-p-payaru* : a kind of preparation made of green gram
- mulai-vilai* : bride price; money given by the bridegroom to the mother of the bride for having nourished the bride with breast-milk during her infancy
- mūlam* : original; document of a title to the property or right
- mūlaparuḍai* (*mūla-parishad*) : chief assembly (of the Śiva temple); variously written as *mūlaparaḍai*, *mūlaparishai*, *mūlaparushai*, *mūlapariḍai*, etc.
- mūlattānam* : (*mūlasthāna*) central shrine in a temple; god in the same
- mūḷḷaḍiśinnam* : a tax prevalent in olden days, the exact nature of which is not clear [payment for clue in detection ?]
- mūḷu-varisai* : at the full rate
- munai-vira-koḍiyār* : [lit. ensign bearers in front of the army] one of the sections of the *nānāḍēśi*, evidently military men

- munbil-āṇḍu* : previous year  
*mūṅgil-vari* : tax on bamboos  
*mun-mālai* : garland offered to a person first in preference to others  
 in a temple as honour  
*mun-n-iuḍm-panam* : amount spent in advance on any work to be  
 recovered later ; advances recoverable  
*mun-n-oḍukku* : that which is first paid  
*mupṭṭāḍu-vaṭṭam* : (of the temple)  
*muri* : document; deed  
*murivu* : a flaw in diamonds  
*mur-kāval-uḍaiya-pāḍi-kāppān* : one grade of police officer  
*mur-kūrutal* : to proclaim, announce, as a sale; proposition  
*murrūṭṭu* : tax-free land endowed for exclusive enjoyment ; *sarva-*  
*mānya*  
*mūtt-adikāram* : supreme authority  
*muṭṭā-v-āl* : [always expressed along with *vetti*] probably supply of  
 free labour without hindrance till the work is completed  
*mutṭāvaṇam* : a tax prevalent in olden days, probably on the sale of  
 pearls  
*muṭṭi* : s.a. *muṭṭā-v-āl*  
*muṭṭi* : (*mushṭi*-handful) probably alms; cf. *kai-y-ērpu*  
*muttirai-ch-changu* : a variety of conch; conch marked with seal  
*muttirai-vāṅgi* : (*mudra*+) examiner of seals; subordinate officer in  
 the revenue departmet  
*muttirāvatāram* : an ear-ornament  
*mutṭudal* : to be hindered, prevented, interrupted  
*muttu-vaṭṭam* : a kind of round pearl  
  
*naḍai* : temple ; also daily worship in a temple  
*naḍa(i)māligai-maṇḍapam* : circumambulatory passage round the  
 central shrine in a temple  
*nāḍan-maṇjaḷ* : a kind of turmeric, mostly used in cooking  
*nāḍ-āṭchi* : administration of a country  
*naḍaval* : transplanted crop  
*nāḍu* : planting of a stone  
*nāḍu* : a territorial division; the local assembly to govern the civic  
 affairs of the division *nāḍu*

- nāḍu-kal* : stone planted to mark the spot of a hero's death
- nāḍu-kāval* : policing duty of the territorial division *nāḍu*; also the tax payable by the residents in the division for the same
- nāḍu-kaṅkāṭchi* : supervisory officer in charge of the territorial division *nāḍu*
- nāḍu-kūru* : settlement officer
- nāḍu-talaiyārikkam* : police-tax of the *nāḍu*; s.a. *nāḍu-kāval*
- nāḍu-vagai* : surveying the country and determining the classification of the land
- nāḍu-vāriyam* : committee to look after the civic affairs of the division; also written as *nāṭṭu-vāriyam*
- nāḍuvirukkai* : liaison officer; public relations officer; also a *madhyastha*
- nagaram (nakhara)* : guild of merchants; a mercantile town
- nagara-k-kal* : stone kept as standard weight by the merchants-guild
- nagaraṅgalilār* : residents in a mercantile city; also the members of the assembly *nagaram*
- nagara-svāmin* : headman of the merchants
- nagarattār* : members of the mercantile guild; merchant-men
- nagara-vanuchchai* : order of the council of the citizens of the mercantile town
- nāgu* : heifer
- nakkan* : dancing woman attached to temple (being required to dance naked)
- nāl-adinālē* : on the particular day
- nal-kiṭā, nar-kiṭā* : cess for the upkeep of the show-ram
- nal-l-erudu* : cess for the maintenance of a model bull, which was probably also used for breeding purposes; cf. *alagerudu-k-kāśu, kāṭchi-erudu-k-kāśu*, etc.
- nal-l-erumai* : maintenance of the specimen buffalo; cf. *nal-l-erudu*
- nal-paśu, nar-paśu* : maintenance of the specimen cow; also referred to as *nal-l-āvu* and *nal-l-ā*; cf. *nal-l-erudu*
- nā-maḍandai, nā-magal* : goddess Sarasvatī
- namana-maṇḍapam (napana-maṇḍapa, snapana maṇḍapam)* : bathing hall in a temple; *tirumañjana-śālai*
- nambi* : temple priest
- nambirāṭṭiyār* : queen
- nambn* : office of temple priest; hence *nambu-śeyvār* : temple priest

- nānālēśi* : the great mercantile organisation which originally had its headquarters at Ayyavole
- nandā-vilakku* : perpetual or ever-burning lamp; also written as *nondā-vilakku*, *nundāvilakku*, etc.
- nandu* : perishing, decay, decline
- naṅganai* : part of a girdle
- narapati* : [lit. lord of men or king] special title borne by the Chōla monarchs, Vijayanagara rulers, etc. in view of the large infantry they possessed; cf. the titles *aśvapati* and *gajapati*
- nārāṣa-nāli* : a kind of measure used in temples, probably made of iron; also written as *nārāya-nāli*
- naravāhana-chakravartin* : a title of the Vijayanagara monarch; probably modelled from the other title *narapati*
- nār-kāli* : four-legged seat
- nattam* : residential quarters in a village
- natta-p-pāl* : village with no residential quarters; deserted village
- nāttāmai*, *nāttānmai* : headship; headmanship
- nāttava-k-kāṇi* : s.a. *nāttuva-k-kāṇi*
- nāttavam* : profession of training pupils in dancing and directing their dance; s.a. *nāttuvam*
- nāttiruvamudu* (*nāl-tiru-v-amudu*) : morning offerings to the deity
- nāttu-k-kaṇakku-vari* : tax payable for the maintenance of the revenue accounts of the division *nāḍu* or the country as a whole
- nāttu-k-kāṇikkai* : presents payable to or by the assembly *nāḍu*
- nāttu-niṅgal* : removal of the taxes from the state revenue registers, having been transferred to the *nāḍu* for its own use
- nāttupāti* : (*nāḍu*+*upādi*) the obligations to be met and payable to the local assembly of the *nāḍu*
- nāttu-p-pāl* : field in which the crop has become withered after transplantation
- nāttu-p-panḍāram* : district treasury
- nāttuva-k-kāṇi* : tax-free land set apart for the maintenance of dance-masters of temple
- nāttuva-t-turavu* : profession of training pupils in dancing
- nāttu-viniyōgam* : individual share payable to make up the shortage in the total revenue by the grant of exemptions granted by the assembly *nāḍu*
- nava-karumam* : renovation; repairs
- navarai*, *navirai* : a variety of paddy

*nāviṣam* : barber's profession

*nāviṣan* : barber

*nāyaka-t-tanam* : the office of the *nāyaka*, governor; s.a. *amaram*

*nayinār (nāyanār)* : lord; master; term of respect

*nel-l-āyam* : tax payable in paddy; also known as *ner-kaḍamai*

*nelli-k-kāy-muttu* : a kind of necklet

*nellūr-māḍai* : a coin current in olden days and issued from Nellore; also known as *nellūr-p-pudu māḍai*; *Gaṇḍagōpālan-māḍai*

*nel-mudal, nelli-mudal* : paddy paid towards the tax; the register maintained for such collections; also the grain-principal of a perpetual loan

*ner-kuru-śālai* : place where paddy is husked

*ner-poliṣai* : interest payable in paddy

*net!āl* : seems to be connected with *veṭṭi*; probably free labour in the nature of public works in the village without time or other limit

*ney* : tax on the traders in ghee; s. a. *neyvilai*; cf. also *eṇṇey*

*ney-tāṅgi* : lamp post

*nēy-y-āḍudal* : bathing the image of the deity with ghee

*nidhi* : treasure-hoard; one of the eight kinds of enjoyment

*nikshēpam* : treasure-trove; one of the eight kinds of enjoyment of the landed property

*nila-ch-chivitam* : grant of land as *jivitam*

*nilai* : pillar; the standard of the lamp

*nilai-irai* : fixed tax

*nilai-k-kaḷam* : office for collection of revenue

*nilaimai-t-tittu* : political compact

*nilai-p-paḍai* : standing army

*nilai-p-pandam* : a kind of torch, probably fixed at certain places (like street corners) to shed light

*nilai-p-poliyūttu* : permanent interest; lending money on some landed property or investing it on some permanent structure so that it may yield regular income annually

*nilai-y-āl* : permanent servant

*nilai-y-āṇi* : fixed pin in jewels, as distinct from *ōḍāṇi*

*nila-k-kūli* : rice collected by merchants on each *podī* brought for sale in the market

*nilam-aḍakkudal* ; to classify arable lands according to quality

*nilamagaḷ, nilamaṇḍai, nilamaṅgai-nachichyār* : goddess of Earth

*nilam-aḷavuṇḍi-ṇ-perumakkaḷ* : survey officers

*nila-mudal* : land-register

*nimandam nivaṇḍam, nibandha* : arrangement for the conduct of affairs in a temple

*nimada-k-kārar* : temple servants; persons who have made specific endowments to temple; also as *nivaṇḍa-k-kārar*

*nimanda-ṇ-puram* : land endowed for specific service in the temple

*niṇaiṇṇu* : remembrancer

*niṅgaḷ* : removal, generally applied to *irai*, thereby meaning that the taxes were removed from the state revenue registers, having been transferred to some other agency for its own use; also referred to as *nikkudal*

*niṇṇayam* : s.a. *niṇṇaya*; settlement; agreement; decision; fixing up

*niraich-ch-aḷavu* : full and correct measure

*nirai-y-ēḍuttal* : to weigh

*nirāṇikkam* : superintendence of the regulation of water-courses in the village

*nirāṇikka-vari* : tax for the supervision of the regulation of water supply in a village

*nirāṇi-vari* : s.a. *nirāṇikka-vari*

*nir-k-kāṇam* : water-cess; also known as *nir-vilai*

*nir-k-kōvai* : water-spread; probably s.a. *ēri-nir-k-kōṇṇu*

*nir-ṇ-ila(i)-k-kāsu* : tank-cess

*nirtta-mārāyan* : title conferred in ancient days on dancing master

*nirupa* : written order; communication from the king or other superior

*nirūpa-ch-chambaḍam* : s. a. *ōlai-ch-chammādam*

*nirvāha-sabhai* : managing or executive committee

*nir-vilai* : water-cess

*niśadam, niśadi* : daily

*niśidigai* : death by fasting of a Jaina; denotes probably the memorial set up for such a person

*nitta-nimandam* : daily routine of offerings in a temple

*nittiyal* : daily

*nivaṇḍa* : allotted duties of servants in temples; temple expenses

*niyadi* : daily; s.a. *niśadi*; sometimes will mean always

*niyāyattār (nyāyattār)* : committee of justice

*nīr-nilam* : arable and irrigable land, where wet crops grow, as distinct from *kollai-nilam*

*nīrāviyār* : assembly of the *nānādēsi* merchants naming it like *rāja-rāja-p-peru-nīrāviyār*, probably to denote their connection with overseas trade

*niyāya* : body or association of persons having the same duties or interests

*niyāyaṅgaḷilār* : members of the *niyāya*

*niyōgam* : appointment; authority; also the officer bearing the same

*nōkki-māḍai* : fee in coin, *māḍai* paid for supervision

*nōkkudal* : to supervise

*nondā-vilakku* : ever-burning or perpetual lamp

*nrityabhōga* : s.a. *śākkai-k-kāṇi*

*nūl-āyam* : tax on cotton thread, intended for weaving cloth

*nūl-erram* : ceremony of the *dhvajārōhaṇam* in a temple

*nyāyattār* : judges ; members of the court of justice

*nāyakavāḍi* : watchman stationed by the state or landlord to keep watch over the crops during harvest and some time previously; the *inām* granted to such persons was known as *kākkunāyaka-viḷāgam*

*oḍampaḍi* : agreement; contract; s. a. *uḍanpaḍikkai*

*ōḍāṇi* : sliding pin in jewel

*ōḍu* : brick; tile; eating plate made of earth

*oḍukku* : to remit or pay into the treasury; to deposit in the store-house

*ōlai* : [lit. plam-leaf] order from the king or the person in authority

*ōlai-ch-chādanam* : document written on palm-leaf

*ōlai-ch-champaḍam* : wages paid to the messenger who brings the *ōlai* to meet his expenses on the way ; also written as *ōlai-ch-chambaḷam*, *ōlai-ch-chammādam*, etc.; s.a. *nirūpa-ch-chambaḍam*

*ōlai-nāyaka* : chief secretary ; senior officer who looks after correspondence

*ōlai-y-ēluttu* : clerkship

*ōḷi-vanṇār-pārai* : tax payable by the washerman calculated on the number of washing stones used by each person

*ōḷiv-inri* : without exclusion of; inclusive of

*ōḷakkam* : durbar hall; assembly of state; audience

*ślakka-maṇḍapa* : place of assembly

*olugu* ; record containing particulars of the ownership, etc. of lands

*olukkavi* : cooked food offered to god daily in a temple

*ottu* : authority; requisite qualification

*ottu* : to agree; agreement

*ottu-k-kāśu* ; amount agreed to be paid

*oppu-muttu* : well shaped pearl

*ōraṇi* : pair

*oru-pū* : single crop

*oru-tudai* : once; on a single occasion

*pachchai* : present or offering

*pachchai-p-panam* : payment in cash towards the obligation of *pachchai* payable in kind; also referred to as *pachchai-p-pāṭṭam*

*paḍāgai, piḍāgai* : hamlet

*paḍagam* : a measure of land

*paḍai-k-kalam* : weapon of warfare

*paḍai-nāyakam* : command of the army

*paḍai-p-panam* : tax for the maintenance of army unit or fee from the army; also known as *paḍai-k-kāṇikkai*

*paḍai-p-parru* : military tenure

*paḍai-y-alivu* : destruction, mostly of the agricultural crops, caused by the march of troops

*paḍalikai* : a measure of quantity

*pāḍan* : lustre of precious stones and metals

*paḍan-kālī* : obligation to be met in olden days the exact nature of which is not clear

*pāda-pāśam* : a foot-ornament

*paḍappu* : backyard of the house; space adjoining the house

*pāda-pushpa* : s.a. *pāda-kāṇikkai*

*pāda-raṭchai* : (*pāda-rakshā*) shoes; sandals

*pāda-śāyalam* : an anklet

*pādava-k-kāṇi* : land given as wage for temple service

*pāḍavari* : tax probably on metallic mirror

*paḍikkam* : vessel for receiving water used for bathing an idol

*pāḍi(-k-)kāval* : watch or the police duties of the village; also the contribution for the same



*padinarumār* : committee of sixteen persons, managing the affairs of a temple

*padi-pāda-mūlam*, *padi pāda-mūla-p-paṭṭ-uḍaiyār*, *padi-pāda-mūla-p-pañchāchāryar* : executive committee in charge of a Śiva temple, probably composed of temple priests

*padi-t-tanam* : daily allowance for expenses in a temple

*pādi-vēṭṭai* : a temple festival, *pārivēṭṭai*

*pādi-viñjanam* : articles other than rice for the preparation of food-offerings, as in a temple

*padiyār* : temple servants, mainly women

*padiyilār* : probably s.a. *padiyār*

*paḍu-kalam* : deed of debt

*pāḍu-tāṅgutai* : to support another's action or deed

*paḍuvāram* : fee payable for exchanging landed property; transfer-fee; also written as *paḍavāram*

*pagal-irukkai* : council hall, durbar

*pāgavata-nambi* : (bhāgavata nambi) Vaishṇava devotee

*pagurru* : equal distribution

*paiṅkiṇaru* : small-pond

*paiśāram* : locality or neighbourhood

*pājanam* : *bhājana*; a vessel, probably eating-plate

*pākkam* : small bundle

*pakka-vādyar* : those who play upon musical instruments in accompaniment to music

*pakkilam* : *paksha*; lunar fortnight

*pakkiṇam* : *bhakshana*; confection

*paktātāyam* : revenue in paddy

*pākuvalayam* (*bāhu-valaya*) : armlet

*pala-kāyam* : sundry spices as pepper, etc. used in preparing curry

*paḷam-puḷḷi-māḍai* : an ancient coin

*paḷamudal-kaṅkāṇi* : temple supervisor

*pala-tali* : temple in which the images of several deities are housed

*pala-varavai* : lands acquired bit by bit in a village

*pāḷi* : Jaina temple; s.a. *paḷḷi*

*paḷiṅgu* : topaz; *pushparāga*

*paḷiṅgu-vaira* : a species of diamond

*pali-t-tālam* : a kind of plate used in offering *bali*

- paḷḷi* : temple of a religion other than the Hinduism, like the Jaina, the Buddhist, the Christian, the Muhammadan, etc.
- paḷḷi-t-tāmam, paḷḷi-t-toṅgal* : garland of flowers for idol
- paḷḷi-ch-chivigai* : palanquin belonging to a temple
- paḷḷi-p-piḍam* : throne; seat for the king
- paḷḷi-ch-chandam* : tax-free village or land endowed to a Jaina temple
- paḷḷi-viḷāgam* : streets round a Jaina temple
- paṇ* : land, field
- paṇam* : individual group constituting the craft-guild *Vira-Pāñchā-lattār*
- paṇam-parru* : palmyra tope
- paṇa-vargam* : class of taxes payable in cash; s.a. *kāśāya-vargam*
- paṇa-vāsi* : discount payable for the exchange of coins; amount payable to make up the wear in the coin
- pañchāchārya* : temple priest
- pañcha-dravyam* : the five articles used in bathing an idol
- pañcha-gavyam* : s.a. *ān-añju*
- pañcha-kammālar* : the five castes of artisans, gold-smith, black-smith, brass-smith, carpenter, and stone-mason
- pañchakkam* : [lit. five persons] decided by five persons
- pañchāḷar, pañchalattar, pañchālattār* : s.a. *pañcha-kammālar*
- pañchāmrita* : mixture of five delicious subjects, usually, plantain, honey, sugar, ghee and grape for anointing idols
- pañchāla-v-achchu* : a coin current in olden days, probably struck by the *pañchālattār*
- pañcha-mā-śattam* : s.a. *pañcha-maha-śabda*; the five musical instruments entitled to be used to a noble [These are named as *chen-ḍai, timilai, śēgaṇḍi*, cymbals and *kāḷam* in one place and as *tattali maddali, karaḷikai*, cymbals and *kāḷam* in another place]
- pañcha-patra* : [lit. vessel made of five metals] offerings of food-stuffs, made along with cooked rice, to a deity; probably. *pañcha-bhakshya*
- pañchara-t-tiruviḷakkam* : a variety of lamp kept for burning in a temple
- pañcha-v-amuḍu* : s.a. *pañchāmritam*
- pañchavar* : Pāndyas
- pañcha-vāram* : five branches in the administration of a village, each looked after by a committee called *pañchu vāra-vāriyam* in some big places

*pañcha-vāram* : also taken as one-fifth of the produce due to government as land-revenue

*pañcha-vāra-v-ūr-idu-vari* : tax levied by the *pañcha-vāriyam* (the five committees) of the local assembly (*ūr*)

*pañchu-p-pīli* : tax on cotton; also referred to as *pañju-pīli*

*paṇḍ-āḍu-pala-naḍai* : ancient or immemorial custom

*paṇḍāra-k-kal* : stone of standard weight used in the treasury

*paṇḍāra-k-kaṇkāni* : treasury officer; supervisor of the treasury

*paṇḍāravāḍai* : land belonging to the state; crown land

*paṇḍa-veṭṭi* : a variety of *veṭṭi*, probably for the temple lands

*paṇḍivari* : probably tax on cart-drawn by bull

*pāṇi-ch-chāy* : colour resembling that of toddy found in a variety of pearls

*paṇi-k-kottu* : village servants; cess collected for their maintenance

*paṇi-magan* : servant

*paṇi-nir* : rose water

*pañjāram* : window like ornamental work on the wall of a temple; *kūḍu*

*paṇkaḷa-p-paḍai* : newly enlisted army, useless as chaff

*paṇ-kuruni* : cess payable at the rate one *kuruni* of the produce for each field

*paṇṇikka-k-kūli* : wage for the thing accomplished

*paṇri-y-ūlvār* : god Viṣṇu as *varāha-avatāra*

*pāradāyan* : one belonging to the *bhāradavāja-gōtra*

*paradēsi* : foreigner

*pārai-k-kānam* : tax on (washing) stone payable by washerman; sometimes taken as the tax on quarries

*paraimai* : probably *parai-t-tuḍai*, a village perquisite

*parai-t-tari* : a variety of hand-loom; the tax for the same

*parai-y-irai* : a tax, payable in cash, probably for tom-tom

*para-k-kūli* : wages for carrying (probably *bharat*)

*pāra-kūli* : (*bhāra*+) cartage; freight; carrier's charges

*paramakkaṇ-kal* : *sati* stone

*parampar* : a class of cultivators

*parampu* : revenue account

*parappu* : s.a. *parampu*

*pāraśiva* : probably *pāraśava*; one who wields a weapon; a soldier

*pārata-p-puram* : s.a. *bhārata-vritti*

*parāvi-vaittal* : to make an offering to a deity in fulfilment of a vow

*paridu, pariśu* : manner, mode

*parihāra* : redemptions

*parikāra* : servant

*parikara* : requisites of a village

*parikkirattu-p-peṇḍugal* : maid servants of the temple or palace

*parimārudal* : to be in circulation; in current usage

*pāriśaṇ-śeydal* : to entrust to the care of

*pariśaiṭṭam* : s.a. *parivaṭṭam*

*pariśu* : manner; mode

*pariśu* : small boat; *pariśal*

*parivāra-k-kondam, parivāra-k-kottu* : group of servants in the temple or palace

*parivaṭṭam* : honour done in a temple with a cloth, generally silk, tied round the head to a noble [lit. garment]

*pariyaṭṭam* : s.a. *parivaṭṭam*

*pār-k-kōl* : staff of honour

*pār-paḍuttal* : (pāl+) to conduct in the right path; to be well-arranged

*pārppana-ch-chēri* : residential quarters where brāhmaṇas live in a village

*parradai* : workshop

*parru-muri* : acknowledgment of receipt

*parum-puḍavai* : a variety of cloth

*parumuḷai-varāhan* : a coin current in olden days

*pārupatya* : supervision, management; hence *pārupatyagārār* : manager

*paśalai-maram* : fruit-bearing tree

*paśān, paśānam* : kind of paddy harvested in Chittirai; harvest time of this paddy

*pāśanam* : dish or eating plate; *bhājana*

*pāshāṇam* : one of the eight kinds of enjoying the landed property; rocky soil and its products; mineral products

*pāśi* : [lit. moss] fishery

*pāśi-p-paḍai* : strong and storming army

*pāśi-p-pāṭṭam* : tax on fishing; s.a. *mīnpāṭṭam*

*paṣittu-vāḷdal* : to live in indigent circumstance

- pasti (basti)* : Jaina temple; *vasati*  
*paṣuṇ-k-kūṭṭu* : ground lime paste  
*pāṭaka* : anklet, worn by woman  
*pāṭakam* : portion of a field  
*pāṭaviyam* : a variety of musical instrument  
*pāṭṭāḍai-āyam* : tax on silk cloth  
*pāṭṭāḍai-nūl-āyam* : tax on silk thread used for weaving silk cloth  
*pāṭṭāḍai-vari* : tax probably for the use of the threshing floor  
*pāṭṭam* : tax or rent, payable probably for the industry or profession  
*pāṭṭam* : a jewel  
*pāṭṭam-ālan* : officer in charge of revenue collections; cultivator; lessee  
*pāṭṭamār* : temple priests  
*pāṭṭana-svāmi* : chief or leader of the mercantile community of a town  
*pāṭṭa-nel* : paddy to be paid by the tenant to the land-lord as per terms of lease  
*pāṭṭa-p-pāl* : waste land  
*pāṭṭārikai (bhāṭṭārikā)* : goddess Durgā  
*pāṭṭa-śāliyan* : a class of weavers, probably of silk cloth  
*pāṭṭavala-p-pāṭṭu* : a kind of silk  
*pāṭṭāvali* : succession list of spiritual heads, as among the Jains  
*pāṭṭa-virutti* : *bhāṭṭa-vritti*  
*pāṭṭayam* : grant inscribed on copper-plate  
*pāṭṭaya-kāṇikkai* : fee for the issue of royal character  
*pāṭṭ-ettu-k-kutt-ariṣi* : well cleaned rice  
*pāṭṭi-k-kāḍi* : tax payable in grain at the rate of one *kāḍi* for each *pāṭṭi* of land  
*pāṭṭi-k-kāl* : similar tax payable in cash at the rate of one fourth (of a *panam* ?) for each *pāṭṭi* of land  
*pāṭṭigai-k-kāṇam* : obligation to pay at the rate of one *kāṇam* for each *pāṭṭigai* of land; very likely it is the same as *pāṭṭayak-kāṇikkai*  
*pāṭṭimai* : first day of the fortnight; *prathamā*  
*pāṭṭi-p-pon* : tax payable in coin  
*pāṭṭira-kaḍam* : *bhadra-ghaṭa*; pot filled with water and sanctified by rites  
*pāṭṭirai-p-paḍutal* : to fall into arrears in payment of the revenue  
*pāṭṭi-t-taṇḍam* : punitive tax (?) of the village

*paṭṭōlai-k-kāśu* : s.a. *tirumuk-k-kāśu*

*pāvāḍai* : cloth spread on ground for persons of distinction to walk on; also food offering on a large scale spread over a cloth in front the deity

*pavīṭiya-charaṇa*, *pauliya-charaṇa* : Rig-Vēdins

*payara-p-perudal* : to resume, as by the state

*payir-erri* : to cultivate; to make the plant grow

*pēḍaipādam* : an ornament for the leg of an idol

*peṇḍāṭṭi* : woman, woman servant

*peṇḍugal* : women; plural of *peṇḍāṭṭi*

*peṇ-palli* : nunnery

*pēr-apṇan* : father's elder brother

*pēr-ilamaiyār* : middle aged women attached to temple

*periya-dēvar* : (lit. the great king) the name by which the ruling monarch refers to the king or kings who ruled before him; also referred to as *periya-perumāl*

*periya-perumāl* : s.a. *periya-dēvar*; sometimes taken as paramount sovereign emperor

*pēr-k-kādamai* : (lit. duty on name) poll tax; s.a. *āl-vari*; also known as *pēr-vāśi*

*pēru* : anything obtained; benefit; reward; food

*perumakkal* : members of an assembly or committee, as great men

*perumān-aḍigal* : a term of reverence by which both the god and the king were referred to in olden days

*perumpaḍi* : rough calculation; approximation.

*perum-pāḍi-kāval* : police duties of a larger area, as distinct from the *śīru-pāḍi-kāval* for the village

*perum-parru* : land the proprietary right of which lies with the state

*perum-pū* : the annual produce of a land

*peru-mudiyan* : a temple official

*perumuri* : wages

*peru-nagarattār* : merchants

*peru-nānk-ellai* : boundaries, as of a village or a large block of land

*peruṇ-kuri*, *peruṇkuri-sabhā* : the general assembly of the village; *mahājana-sabhā*; also known as *peruṇkuri-mahāsabhā*

*perun-tanam* : superior officers, like the heads of departments

*perun-taram* : officials of the higher grade

[During the days of the Chōla rule, the official heirarchy was divided into two classes, *perun-tanam* and *śiru-tanam*, each of which was again subdivided as *perun-taram* and *śiru-taram*. This will be evident from an officer being described in a record as *śiru-tanattu-p-perun-taram*, i.e., *perun-taram* of the *śiru-tanam*.]

*perun-tinai* : [lit. great-lineage] a title conferred in olden times by kings on nobles

*perun-tiru-v-amirdu* : food offering to god on a large scale

*peru-valavāy* : big channel

*peruvali* : highway; trunk road

*peru-vāyan* : basket

*peruvāyil* : main entrance; *gōpura*

*petliri-viḍu* : factory-house (vide Ekōji's copper-plate grant to the Dutch)

*pichcha-dēvar* : Śiva as *bhikshāṭanamūrti* or as madman

*piḍāgai* : hamlet

*piḍā-nāli* : s.a. *pudā-nāli*

*piḍārar* : god Śiva; also a term of respect denoting a spiritual preceptor; *bhaṭṭāraka*

*piḍāri-p-paṭṭi* : tax-free land granted to a temple of the village-goddess *Piḍāri*; also referred to as *piḍāri-viḷāgam*

*piḍilikai-vāri* : an officer of the temple, probably entrusted with the removal of flowers of the previous day, i.e., *nirmālya*

*pidipāḍu* : authority; title deed

*piḍi-śūlndu* : walking round by a female elephant to mark the boundary, as of the gift land

*piḍi-viḷakku* : a kind of lamp borne on hand

*piḷlaigal-tanam* : [lit. status of a *piḷlai* or prince] probably officers cadre composed of the junior members of the royal family

*piḷlai-vari* : tax for the upkeep of the order of *piḷlais* or *kumāras* (princes); cf. *kumāravritti* in the inscriptions of the Western Chālukyas of Kalyāṇa

*piḷlaiyār-nōn̄bu* : *vināyaka-chaturthi*; the tax-free land endowed to celebrate the above festival; also known as *piḷlaiyār-nōn̄bu-t-tēvai* and *piḷlaiyār-nōn̄bu-p-pachchai*

*piṅgālam* : a kind of metallic vessel

*piṇju* : small work shaped like young fruit in an ornament

*pin-tōnral* : (lit. that which comes after) younger brother

*pirkūral* (piṅ-kūral) : confirmation of what was proposed first; second-  
ing the proposition

*pirabai* (prabhā) : s.a. *tiruvāṣi*

*pirama-mārāyan* : (brahma-mārāyan) title of brāhmaṇa minister in  
olden days

*pirama-mētam* : (brahma-mēdha) ; special funeral rite for a saintly  
person

*pirama-dānam* : *brahma-dāna*; gift to brāhmaṇas

*pirama-dēyam* : s.a. *brahma-dēya*

*pirasatti* : (*prasiddhi*) publication; repute

*piratṭan* (*bhrashṭa*) : one who has strayed from virtue

*pirumma-stānam* : *brahma-sthāna*; brāhmaṇa quarters where the  
village assembly, the *sabhā*, used to meet

*pītam*, *pīṭha* : pedestal; seat

*piyar* : variant of *peyar*, name

*podikūli* : wages for carrying head-loads

*pōdūtal* : s.a. *pōdal* or *pōguda*; to go, to proceed

*pōduvāl* : (netural) person managing the affairs of a temple

*pōkiyār* : (*bhōgiyār*); concubine

*pokkiśam* : treasury; officer of the treasury

*polikai*, *polisai* : s.a. *palisai*; interest

*polimurai nāgu* : heifer fit for covering

*polisai-y-ūṭṭu* : paying interest; to lend money for interest; investment  
of money to earn regular interest

*poliyūṭṭu* : s.a. *polisai-y-ūṭṭu*

*pollāppu* : objection

*pon* : a gold coin current in olden days; known also as *māḍai*

*pōnaka-k-kurutu* : young plantain leaf with pointed end, used in  
food offering to god

*pōnakam* : food offering to god

*pon-bhaṇḍāram* : gold-treasury

*pon-māḷigai* : golden palace where the king resided, especially the one  
which existed at Kāñchīpuram in the Chōḷa days

*pon-nūl* : gold wire; probably golden sacred thread

*pon-panḍāra-vāśal* : the gate of the gold-treasury; royal gold-treasury

*pon-vargam* : class of taxes payable in gold or coin

*pon-vari* : tax payable in gold; also the fee for minting gold into coins;  
*ponvari-māḍai* is probably the same



- porpu* : [golden flower] presentation in the form of a gold-flower made to a student on his graduation from the college
- porrai* : bush; low jungle; hillock; mound
- pōr-t-tani-p-pūvai* : *pōr-ch-chaya-p-pāvai* (pōr-jaya-p-pāvai) the goddess of Victory
- pōsar* : *bhōjaka*: one who enjoys a thing; possessor
- pottagam* : *pustaka*; register, as of land and revenue
- prabhāvali* : ornamental arch over the figure of a deity; *tiruvāśi*
- prachanḍa-kāṇikkai* : [*prachanḍa*—fierce, terrible, fearful] a variety of military cess, as this is found mentioned along with other military cesses like *paḍai-p-panam*, etc.
- pradhāni-jōḍi* : *inām* held on a fixed quit-rent by a minister
- prahara* : a flaw in gem
- pramādam-vilaital* : to die
- pramāṇam* : document; title deed
- prāṇāntikam* : till the close of life
- prāpti* : enjoyment; that which is obtained from; also written as *pirātti*, *pirāpti*
- prasāda-p-paḍutal* : to receive the favour or order, as of a king
- prasādam-śeydal* : to bestow, grant, as a favour
- pra-śishya* : pupil's pupil
- pratigraha* : acceptance of gifts
- pravēśakam* : admission, entry
- prīti-pramāṇam* : deed of gift out of love
- pūchchi-y-āḷudal* : to be infested with insects, as a garden
- puḍa(i)vai* : cloth
- puḍāli* : s.a. *puḍā-nāli*
- puḍā-nāli* : probably a local cess on each door or gate (house); also mentioned as *pidā-nāli*
- pudiyāḍu* : festival on the completion of the harvest; offering of the first-fruits of land to the god annually; also written as *pudiyidu*
- pudu-k-kuligai* : a coin current in olden days
- puduvadu* : anything new
- pudu-vari* : new tax
- pūjakan* : one who performs worship; temple priest
- pūjā-vritti* : tax-free land endowed to a temple for conducting worship
- pukti* (*bhukti*) : enjoyment of the property; also written as *putti*

*pulavari* : (pulam—piece of land, vari—tax, hence) tax on a piece of land; but probably to be read as *pulvari* meaning tax on grass; (s. a, *pullavari* : tax on grazing cattle)

*puli-mānya* : endowment of tax-free land for killing a tiger

*puli-y-iṭṭi-aḍuṇ-kari* : curry prepared with tamarind

*pullaḍi-k-kal* : demarcation stone

*pullandi* : an obligation of olden days, probably connected with pasture land in the nature of fine on stary cattle

*pulli* : individual

*pulli-ch-chōru* : offering of food to individuals, probably occasional visitors

*pulli-gulikai-varāhan* : a gold coin current in olden days

*puludi-pūdu* : waste land

*pulugu-kaḍamai* : fee for meeting the expenses of coating the image of god with civet; also known as *pulugu-vari*

*pū-makaḷ* : goddess Lakshmi as *pū-magaḷ* and the goddess of Earth as *bhū-magaḷ*

*pūmi-p-pirāṭṭi* : (*bhūmi* +) the goddess of Earth

*pūmi-puttirar* (*bhūmi-putra*) : Vēḷāḷas, husbandmen, as sons of the Mother Earth

*punai* : security, surety, guarantee

*puna-k-kulam* : pool formed of rain-water

*punnir* : drainage water

*punniya-gaṇa-p-perumakkaḷ* : members of the board from among the villagers managing charities

*pun-payir* : dry crops, cereals

*purai-y-iḍam* : garden

*pura-k-kaḍamai* : external taxes, i.e., taxes and fees payable to the state

*purakkaḍittal* : to expel

*pura-k-kalaṇaiyār* : group of village servants who live outside the area or whose activities lie outside the village

*purakkaḷaniyār* : people who have lands outside the village

*pura-k-koḍai* : the surrounding parts, outside, of a temple

*pura-k-kōyil* : outer-shrine

*pura-k-kuḍi* : farmer or field-labourer, not being a regular tenant

*puram* : tax-free land or village endowed for some charity

*puṇambāḍi* : outskirts of a town

- purambu* : probably s.a. *pura-k-kaḍamai*  
*purani-nāḍu* : bordering country  
*purattāḍiyār* : devotees as distinct from *agattāḍiyar* : wife  
*purattan* : deceiver; liar  
*puravari, puravu-vari* : revenue account  
*puravariyār* : revenue accountants  
*puravetti* : a variety of *vetti* or public work, probably on some piece outside their area  
*puravu* : land revenue  
*puravu-nel* : revenue paid in paddy  
*puravu-pon* : revenue paid in gold  
*puravuvvari-tinai-k-kālam, puravari-tinai-k-kālam* : the department of land revenue and revenue accounts  
*pura-v-āyam* : revenue from external sources, collected mainly in cash  
*pūri-ch-chēral* : a variety of paddy; probably *pūri-nel* is the same  
*pūri-k-kuttal-ariśi* : polished rice  
*purōhita-k-kāṇiyāṭchi* : hereditary right of officiating as priest  
*purushākāram* : human form  
*pūrvāchāram* : ancient custom  
*pushkara-p-patti-maḍal* : receptacle for sacred ashes  
*pushpa-t-taḷigai* : offering of flowers  
*pushya-rāgam* : s.a. *pushpa-rāga*  
*pūṭchi* : tax  
*puttagam* : cloth  
*puttaga-vilai* : fee levied on sellers of cloth  
*pūttai-k-kiṇaru* : well fitted with water-lift for irrigating fields  
*pū-v-iḍuvān* : one who supplies flowers to a temple  
  
*rāhasyādhikrīta, rāhasyādhikata* : privy councillor  
*rāhutta-rāyan* : cavalry chief  
*rāja-bhaṇḍāra* : royal treasury  
*rāja-drōham* : treason to the king  
*rāja-kāram* : (*rāja-griha*) palace or government; officers or authorities; also the taxes due to the same  
*rājakāram-irai-muraimai* : various items of taxes payable to government  
*rājakāram-kāṇikkai* : customary presents to be made to the palace

*rājakara-upādi* : tax payable to the palace or government officers

*rāja-kārya* : duties of the state; official work

*rājakārya-bhaṇḍāra* : treasury intended for the state business; sometimes also taken as the official committee of management

*rājakulam-kāṇi-p-parru* : land or village in the enjoyment of the members of the royal family (the term occurs along with *dēvadāna*, *brahmadēya*, *paḷḷi-ch-chandam*, etc.)

*rājanya* : officers of the king

*rājasvam* : property belonging to the king or state (by confiscation, etc.)

*rājāvartam* : a kind of gem

*rāja-vēśya-bhujāṅga* : a title borne by some kings after capturing the enemy countries, describing the *rājya-śrī* as a prostitute

*rājyam* : highest administrative division of the kingdom during the days of the Vijayanagara rule

*rakshakar* : protector

*rakshā-bhōgam* : fee or share in the produce given to a village watchman

*rāmānuja-kūṭam* : rest-house for Vaiṣṇava travellers

*raṅga-maṇḍapa* : inner hall of a temple; s.a. *tiru-v-araṅgu*

*ratta-k-kāṇikkai* : s.a. *iratta-k-kāṇikkai*

*rāśa-k-kāṇam* (*rāja* +) : revenue; payment due to the king

*rāśi-p-pon* : pure gold

*rathakāras* : artisan classes; also their association

*rāyasam* : office of a writer; clerkship; order of the king; written orders

*rāyasa-svami* : head of the *rāyasam*

*rēkai* : a gold coin current in olden days

*rēkai-p-pon* : pure gold

*rishaba-t-taḷiyilār* : a grade of the women servants or dancing women attached to a Śiva temple

*rishi-samudāya* (*ttār*) : holy men of the Jaina religion and their general assembly

*rudra* : Śaiva devotee

*rudra-gaṇa* : devotees of Śiva; their managing committee looking after the temple affairs being known as *rudra-gaṇa-p-perumakkal*

*rudra-gaṇikai* : dancing woman attached to a Śiva temple

*rudra-māhēśvara* : the two classes of Śaiva devotees, known as *rudras* and *māhēśvaras* jointly

*sabhā, sabhai* : local assembly of a brāhmaṇa village; also referred to as *kuri* in inscriptions

*sabhā-maṇjikkam* : village 'common and uncultivated waste land in the village belonging to the *sabhā*; also known as *sabhai-p-podu, ūr-p-podu, ūr-maṇjikkam, sabhā-madhyamam*, etc.

*sabhā-mārram* : instructions or reply of the *sabhā*

*sabhā-mārram-śolluvān* : executive officer who carries out the orders or instructions of the *sabhā*

*sabhā-vilai, sabhai-vilai* : public sale effected by the *sabhā*; also the price fixed for such a sale

*sabhā-viniyōgam* : individual share payable to make up the expenses of the *sabhā*

*śaḍaṅgavi, shaḍ-āṅga-vid* : one well versed in the six *aṅgas* of the Vēdas

*sadā-sērvai, sadā-sēvai* : eternal service; serving always

*sādhyam* : enjoying the fruits of the land; one of the eight kinds of enjoyment of property

*śādiram* : variant form of *śāduram* or *chatura*; square

*śādira-vāśakan* : *chatura-vāchakan*; one who speaks with dexterity and wisdom

*śaivāchārya-kshētra* : tax-free land endowed to a *śaivāchārya*

*śaiva-kalālaya-chakravarti, śaiva-chakravarti, śaiva-chūlāmaṇi, śaiv-ādirāyar* : titles conferred on temple priests and Śiva brāhmaṇas in olden days

*śākā-mūvā-p-pēr-uru* : fixed number of milch cattle endowed to the temple permanently to provide a continuous supply of ghee for temple lamps

*śakarai-y-āṇḍu* : Śaka year

*śākkai-k-kūttu* : a variety of dance performed by the *śākkiyar* in the temple

*śākkara-k-kal* : s.a. *āli-k-kal*

*śākkara-k-kānikkai* : tax on potters; also known as *tirigai-āyam*

*śākkara-k-kuligai* : a coin current in olden days; also known as *śākkara-p-paṇam*; evidently named as such considering its shape

*śākkaram* : (*chakra*) wheel of authority; king's order; officer entrusted with the execution of the same

*śākkaravālam* : *chakravāla-giri*; mythical mountain encircling the earth; horizon

*śākkattu* : a variety of pearl

*śālābhōgam* : s.a. *ara-ch-chālā-bhōgam*

- śalagai** : a lot in grain measure; land sufficient in extent for sowing that quantity of paddy
- śalāgai** : a coin current in olden days; also known as *paḷaṇśalāgai* (*achchu*) and *Śrī yakki-paḷaṇśalāgai*
- śālai** : feeding house; also the *pāṭhaśāla* or school attached to it
- śalāpam** : pearl-fishery
- śalāvaṇam** : s.a. *śrūvaṇam*; sale deed; (*āvaṇa-śalāvaṇam*)
- śāligai-t-tari**, **śāliya-t-tari** : a variety of weaving loom; loom worked by the *śāliyar*; the tax payable for the same
- śāliga-nagarattār** : guild of *śāliya* weavers
- sallēkhanā** : religious practice of the Jaina starving themselves to death in performance of a vow
- samaidal** : to be made; formed; to prepare
- samaippu** : gift to a charity
- samañjasa** : conformity; resemblance
- samañjitan** : accountant of a village or its assembly
- samaya** : religious mendicant
- samay-mudali** : religious chief
- sāmanta** : minister; feudatory chief
- samaya-darmam** : the law of the *samaya* or profession; this term is mostly met with in relation to the *nānādēśi* and *chitramēḷi* organisations
- samaya-patra** : deed of agreement; deed of compact
- śambaḍam**, **śambaḷam**, **śammādam** : food while travelling; used in compounds like *ōlai-ch-chammādam*, *nirupa ch-chammādam*, etc.; see also *śammāda-niyōgam*
- śāmi**, **svāmi** : king
- śammāda-niyōgam** : s.a. *ōlai-ch-chammādam*
- samprati** : senior accountant; manager of a temple
- samprātti**, **sam-prāpti** : that which been has been obtained; acquisition
- samudāyam** : vllage common; managing committee of a temple
- samudāyam** : village with the *gaṇabhōga* tenure
- samudāya-p-pirātti**, **samudāya-prāpti** : any acquisition from the village to be enjoyed in common by the villagers
- samudāya-t-tiru-mugam** : royal order issued to several communities of the state in common
- samvatsara-vāriyam** : annual committee appointed by the *śabhā*

- samiññai* : *saṃjñā*; [ t. symbol, sign] signature (of a king)
- śaṇḍai* : the musical instrument *cheṇḍai*
- śandai* : market; fair
- śandai-mudal* : fee collected from merchants in the market
- śaṇḍāla-p-pēru* : (chaṇḍāla+) a local cess or tax in olden days collected evidently from or for the *chaṇḍāla*
- śaṇḍa (chaṇḍa)-p-prachanḍar* : deities guarding the inner shrine of the Viṣṇu temple
- sandi* : [lit. twilight] service in the temple in the mornings and evenings; temple worship; special worship offered as endowed by certain persons in their names
- śandi-k-kunippam* ; a dance performed during worship before god in a Śiva temple
- śandi-k-kūttu* : a variety of dance performed by women before god in Śiva temple during festivals
- sandivigraha-p-pēru* : fee payable to the village *madhyasta*; also taken as the fee payable to document writers
- sandi-vigrahi* : minister in charge of peace and war; senior officers of the Foreign relations department of the state; also writer of important documents
- sandi-viḷakku* : twilight lamp, mostly in the evenings, though both in the mornings and in the evenings, in temples; s.a. *sandhyā-dīpam*
- sandhyā-dīpam* : s. a. *sandi-viḷakku*
- śāni* : wife; term by which brāhmaṇa woman was referred to in olden days
- sañjīva-rāyar* : god Hanumān
- śaṅkara-p-pāḍiyār* : oil-mongers
- śaṅpaṅkārāi* : a piece in the ornament *tāli*
- śānrār* : toddy-drawer
- santānam* : lienage
- santāna-śāpam* : curse that prevents progeny
- santānika-śaivas* : Śaivas who came in or who belonged to the line of the ācāryas of the *santāna-kuravar*
- santati-pravēśam* : from generation to generation
- śānti-k-kāran* : temple priest; also known as *śānti-y-aḍigaḷ* and *śānti-śeyvān*
- śānti-k-kūttan* : person performing the dance *śānti-k-kūttu* in the temple

*śānti-k-kūttu* : dance by women in temple during worship; probably  
s.a. *śāndi-k-kūttu*

*śappatti* : flat pearl; probably *śappaḍi* also is the same

*śapta-santānam* : merit equal to that obtainable through progeny  
accruing from seven kinds of great deeds; viz., digging of tanks  
hoarding of treasure, founding of *agrahāras*, erection of temples,  
creation of flower gardens, getting literary works written by poets,  
and the establishment of choultries; also referred to *śapta-sāntati*  
[lit. seven 'off-springs': the term is explained in an inscription  
(*Ep. Ind.*, vol. III, pp. 88 ff) as the seven meritorious acts a  
man ought to perform during his life-time : viz., procreation of  
son, composition of poem, treasure-hoard, planting of a grove,  
performance of marriage, erection of temple and digging tanks]

*śaraṇattār* : (*charaṇa*) members of the particular school of the Vēdas

*sarasvati-bhaṇḍāra* : library

*śara-vilakku* : string of lights usually hung in temples

*śarigai* : assembly, meeting ; also written as *śārīgai*

*śariram* : person ; individual

*śārru-p-paḍi* : s. a. *śāttu-p-paḍi*

*śārru-vari* : [*śāru*—sweet-toddy] tax for tapping toddy or sweet-toddy  
from palm-trees

*śarukūḍai* : (*śarugu* + *kūḍai*) right of collecting the dried foliage  
from village common

*saruppētimāṅgalam*, *śaduppēdimāṅgalam* : s. a. *chaturvēdimāṅgalam*

*sarva-mānya* : exempt from all taxes

*sarvasva-haraṇam* : total forfeiture of one's entire property

*śāśvatiya* : perpetuity ; eternity

*śātaka-k-kuḍi* : s. a. *jātaka-k-kuḍi*

*śāttā-kaṇattār* : members of the committee managing the affairs of the  
*Śāstā* or Aiyānār temple

*śaṭṭam* : a variety of ruby

*śā-t-taṇḍam* : punishment for murder

*śaṭṭa-p-perumakkal* : executive committee of the *śaṭṭar*

*śaṭṭar* : *brahmachāris* ; celebrities in charge of temple and the *śālai*  
attached to it ; see also *śāttirar*

*śaṭṭi-ch-chōru* : food offerings distributed as a perquisite to temple  
servants

*śāttimugam*, *śakti-mukha* : king's order; probably s.a. *śrīmukha*



*śatti-murram* : [lit. quadrangle of Śakti] the temple for the goddess Śakti or Durgā in the village

*śāttira-māni, śāttirar* : *brahmachāri*; celibate wedded to learning; also known as *śāttar*

*śāttiyam, śādiya* : right to the fruits of the earth; one of the eight kinds of enjoyment of the landed property; s.a. *sādhya*

*śāttu-k-kūrai* : s. a. *tiru-p-parivattam*

*śāttu(p)paḍi* : decoration to the images of deities in temple

*śāttuvam* : ladle

*śāttu-vari* : tax for grazing ground in the village

*śāttvika-dāna* : gift without the pouring of water, thus not expecting any merit in return for the gift

*śaturvēdi-bhaṭṭa-t-tāna-p-perumakkaḷ* : elders of the *sthāna* (committee) of the *chaturvēdibhaṭṭas*

*śalya-jñāna-darīśanigaḷ* : followers of a sect in Śaivism, evidently those belonging to the lineage of Meykaṇḍār

*śausti* : perhaps *svasti*; charity; grant; endowment

*śavai-h-kaḍamai* : taxes payable to the *sabhā*

*śavai-k-kaṇakku* : accountant of the *sabhā*

*śavai-vāriyam* : s. a. members of the *sabhā-vāriyam*

*śavaiyār* : members of the *sabhā* of the village

*śavakkam* : square diamond

*śāvā-mūvā-p-pēr-āḍu* : fixed number of milch sheep endowed permanently to provide a continuous supply of ghee for temple lamps [lit. sheep without death or senility, thereby indicating that the fixed number was to be maintained replacing the old and dead ones with the off-spring] cf. *śākā-mūvā-p-pēr-uru*

*savarṇa-vritti* : profession of writing documents

*śāvēru* : select band of armed warriors who, under a vow, rush in a body, endeavour to cut their way through the guards of the enemy and lose their lives in the encounter

*śāvi* : blighted grain; withered crop

*śavi* : girdle with strings of beads or bells

*śēgaṇḍi* : gong

*śekka-āyam* : tax on oil presses; also known as *śekka-irai* and *śekku-k-kaḍamai*

*śekku* : s.a. *śekkāyam*

*śekku-manrāḍi* : a tax or cess collected in olden days; probably related to *śekku*

- śekku-vāṇigar* : oil-monger; manufacturer of oil with presses  
*śella* : to the very end; to the limit of  
*śemmai* : agreement; excellence; fineness  
*śemmai-panḍāra-k-kal* : standard weight equal to the one kept in the treasury  
*śem-marudar* : good farmers or cultivators  
*śem-pādi* : equal half  
*śennai-bhōgam* : accountant; s.a. *sēnabhōva*  
*sēna-gaṇa* : a division of the Jaina community; also known as *sēnān-vaya*  
*sēnāpati-y-ālvār* : god Vishvaksēna; *sēnai-mudaliyār*  
*śēnāpati-p-peruvilai* : sale of lands of Viṣṇu temple executed in the name of Sēnai-mudaliyār  
*sēnai-y-aṅgāḍikaḷ* : a class of merchants who follow the army with their merchandize; a class of cloth merchants  
*śēṇiyar* : a class of weavers; members of a craft-guild (*śrēṇi*)  
*senkoḍi-k-kāṇam* : taken as the tax on the cultivation of the medicinal plant known variously as *śēngoḍi*, *koḍivēli* and *chitramūlam*; see also *koḍi-k-kāṇam*  
*śēṅkol* : pure gold  
*śēu-ṇaḍai* : daily expenditure in temple service  
*śēn-nīr* : clear water  
*śēn-nīr-pōḍivi* : drinking water channel  
*śēuṇīr-veṭṭi* : public work of *veṭṭi* on the drinking water channel; also known as *śēuṇīr-amañji*  
*śēṇpaka-k-kuligai* : a coin current in olden days, probably struck by the Śambuvarāyas  
*śēppu-k-kāl-tiru-ch-chirrambalam-uḍaiyān* : a measure of capacity made of copper and named *tiru-ch-chirrambalam-uḍaiyān*  
*śēppu-p-paṭṭayam*, *śēppu-p-paṭṭiram* : copper-plate grant  
*śēppu-t-tirumēṇi* : image of deity made of copper  
*śēri* : living quarter in a village; *chēri*  
*śēruvāḍi* : petty savings in money; s.a. *śīruvāḍu*  
*śēruvu* : field; *cheru*  
*śērvai*, *sēvai* : service; service *inām*; tax-free land given to servants for enjoyment in lieu of salary  
*śēṭṭiyār-magamai* : the voluntary contribution *magamai* of the merchants

*ṣeṭṭi-y-irai* : tax on merchants; also known as *ṣeṭṭirai*

*ṣevaka-k-kāṣu* : fee for the maintenance of the soldier; may also be taken as the tax levied on the soldier

*ṣevakan* : soldier

*ṣevaka-t-tēvai* : expenses in connection with the supply and maintenance of retainers of the chief or the officers during their visit to a place

*ṣevvari-y-āḍu*, *ṣevari-y-āḍu* : a variety of sheep; probably the same as *ṣemmari-y-āḍu*, the common brown sheep

*ṣeviḍu* : a small grain measure, one-fifth of an *ālākku*

*ṣeyal* : engraving; carving; setting work in jewellery

*ṣeydār-pon* : pure gold

*ṣeyyumpaḍi* : [lit. as ordered to do] king's order; written instructions

*ṣidana-k-kāṇi* : (*stri-dana* +) land obtained as dowry

*siddāyam* : fixed assessment; minor taxes; represented the minor taxes payable in cash in the days of the Vijayanagara rule also written as *sittāyam*

*siddham*, *siddhi* : right of cultivating the land; one of the eight kinds of enjoying the landed property

*siddhāntam* : Śaiva religion

*siddhāyadi* (*ṣittāyadi*) : income (from the minor taxes, etc.)

*ṣiḍukku* : a variety of ornament worn by woman

*ṣikāriyam* (*śri-kārya*) : temple management

*ṣikāriya-k-kāṇi* : supervision of temple affairs; also the officer doing the work

*ṣikāriya-p-pēru* : perquisites to the officer *śrikārya*

*sik(h)aram* : top (of the *gōḥpura* or *vimāna*)

*ṣilā-lēkhai* : inscription on stone

*ṣilandi* : a variety of precious stone, sardonyx

*ṣil-kuḍimai* : minor taxes and cesses payable to the local authority

*ṣil-l-antarāyam* : minor taxes which fall in the group *antarāyam* or *uḷ-vari*

*ṣil-āyam*, *ṣil-l-irai*, *ṣil-vari* : minor taxes

*ṣīma-vivādam*, *ṣimai-vivādam* : boundary dispute

*ṣimayam* : the Himalayas

*ṣinakaram* (*jīnakara*) : Jaina temple

*ṣiṅga-pādam* : legs of vessels or vessel-stand in the shape of lions' feet

*ṣiṅgāra-t-tōppu* : pleasure garden

*śinnam* : odd

*śinnam* : s.a. *chinnam*

*śinna-p-pillaiyāṇḍān* : junior servant under the *adaippam*

*śipādan-tāṅgikaḷ* : vehicle-bearers attached to a temple, as supporting the feet of god; also known as *śipadam* (*Śri-pādam-tāṅgikaḷ*)

*śipaṇḍāram* : *śrī-bhaṇḍāra*; temple treasury

*śippam* : small bundle

*ś(i)raddhāmantar* : those who look after the temple-affairs out of devotion

*śiragu* : row of houses, side of a street; also written as *śaragu*

*śira-p-pradāni* (*śiraḷ-pradhāni*) : senior minister

*śirappu* : periodical special worship in a temple; also the food offering at that time

*śirappu-k-kaṭṭalai* : arrangement for making special food-offerings on occasions in the temple

*śirāvaṇam*. *śrāvaṇam*, *śrāvaṇai* : sale deed; document; s.a. *āvaṇam*; also known as *śrāvaṇa-patra*

*śirimugam* : *śrimukha*; *tirumugam*; royal charter; letter from the king or a noble

*śiri-vayinnavar* : Śrī Vaishnavas

*ś(i)riyakki-palaṇśalāgai-y-achchu* : s.a. *salāgai*; also *śrī-yakki-y-achchu*

*śirmai*, *śimai* : a territorial division

*śirō-varttanai* : top portion of the Śiva-Liṅga

*śirrāyam* : minor-taxes

*śiru-aparādam* : minor offences and the fines imposed thereon

*śiru-kālai-ch-chandi* : early dawn service in the temple

*śiru-kālai ch-chirappu* : food offerings to god in a temple in the early morning service

*śiru-kuḍivāram* : share due to the cultivator in the produce of the land

*śiru-muri* : a written note

*śiru-muri-k-kāśu* : fee for small or minor documents; fee for the communication

*śiru-pāḍi-kāval* : village watch, as distinct from *perum-pāḍi-kāval* or the police duties of a larger area

*śiru-pāḍu* : small gift or offering, as to a temple

*śirupaḍukan* : a pendant in an ornament

*śiru-p-pillai* : servant

- śiru-śuṅgam* : minor tolls
- śiru-tanam* : private treasure; personal savings
- śiru-tanam* : lower of the two grades into which the official hierarchy was divided in the days of the Chōla rule
- śiru-taram* : junior grade of officials
- śi-ruttirar* : *śrirudra*; Śaiva devotees
- śitāri* (*śitāri*) : burning incense
- śittāyam* : see *siddāyam*
- śittirai-k-kār* : a variety of paddy harvested in the month of Chittirai
- śittira-mēli* : s.a. *chitramēli*; also known as *periya-nāḍu* and *periya-nāṭṭavar*; the organisation of the agriculturists; their emblem, the plough; the boundary stone with the emblem of plough planted to mark the limits of their land
- śiva-brāhmaṇa* : priest of the Śiva temple; also known as *Ādi-Śaiva*
- śivan* : title applied to a Śaiva devotee
- śivana-śēsham* : *jivana-śēsham*; maintenance
- śivanda-nir* : red water of a pearl
- śiva-panḍāri* : treasury officer of the Śiva temple
- śivappu-ch-chilai* : red-stone; ruby
- śivappu-t-tōyppār* : dyers of cloth
- śiva-yōgi* : devotee of Śiva
- shahar* : (Persian word) town
- śiva-k-kirāham-āga* : (*jiva-grāham-āga*) captured alive
- śivigai-p-puram* : land set apart for the maintenance of the palanquin service in a temple
- śivitam*, *śivita-p-paruru*, *śiviyam* : s.a. *jivitam*
- śiyar* : s.a. *jīyar*
- śōḍi* : s.a. *jōḍi*
- śokkam* : a variety of dance, known as *śuddha-nrittam*
- śokka-t-taiyilār* : dancing women attached to Śiva temple, probably those who perform *śokkam*
- śōḷiya-k-kāśu* : a copper coin introduced by the Chōlas, generally taken as one-hundredth of a *paṇam*
- śōmāśi*, *sōmayāji* : one who has performed the *śōma-yāga*
- śōṇaka-ch-chiḍukku* : a variety of ornament worn by women in olden days
- sōpānam* : steps; stairs; sloping roof; the base of the *garbha-griha* of a temple

- śōṛṛ-aḍaiṇṇu* : endowment for feeding-house  
*śōṇa-vari* (*svaṇṇavari*) : tax payable in gold; s.a. *pon-vari*  
*śōruvam*, *svaṛūpa* : estate of the *nambūdiris*, royal personages, etc. of Malai-nāḍu  
*sorkastar-ādal* (*svargastar+*) : to become a resident of heaven; to die  
*śōśiyār-tiruvāḍi* : [Jōsyar (?) +] an officer of the state; probably the royal astrologer  
*ś(r)i-bali* : daily offering of *bali* service in the temple; also known as *havir-bali* and *tī-y-eri-śōṛu*  
*ś(r)i-bali* : image of the deity taken round the temple when offering the *bali* service; the procession of circumambulating the temple at the time of the *bali* service  
*ś(r)i-bali-bhōgam* : land set apart to meet the expenses of *śrī-bali* service in the temple; also known as *śrī-bali-p-paṭṭi*  
*ś(r)i-bali-koṭṭuvār* : musical troupe of temple playing on the instruments at the time of *śrī-bali*  
*śrīdanam* : s.a. *stri-danam*; dowry  
*śrīpādangal* : exalted personage, used as a term of respect  
*śrīśandam* : a kind of jewel  
*śrī-y-ājñai* : royal order  
*śrutimān* : elders of a community looking after its affairs; perhaps derived from *kēḷvi*  
*sthānattār* : temple executive  
*śuḍar-nilai* : lamp post; standard of the lamp  
*śuḍu* : s.a. *śummāḍu*; support or pad on the head for carrying head-loads  
*śuḍu-kāṭṭu-p-pāṭṭam* : fee for the crematorium  
*śūlai-t-tirai* : fee payable by a prostitute, especially those accompanying the army; cf. usage in the Kannaḍa inscriptions  
*śūla-k-kāl* : measure of capacity marked with trident and used in Śiva temple  
*śūla-k-kal* : boundary stone bearing trident mark for the lands of the Śiva temple  
*śūla-t-tāpanam* : planting of the boundary stone *śūla-k-kal*  
*śūla-vari* : a tax payable for the upkeep probably of the Śiva temple  
*śumai* : head-load  
*śunai* : mountain pool; spring; reservoir  
*śuṇgam*, *śuṇkam* : customs; toll  
*śuṇga-śālai* : place where tolls are collected; custom house

- śuppiram* : a flaw in the pearl  
*suprayōga* : a river, probably the northern Pennāru  
*śuram* : forest [*śuram-pōkki* having driven to the forest; also written as *śuram-irakki*]  
*śuri* : part of an ornament  
*śurōttiriyam* : *śrōtriya*; land or village granted to brāhmaṇas learned in the Vēdas  
*śurru* : circumference; girth; also the *prākāra* of a temple  
*śurru-k-kallūri* : probably s. a. *tiru-ch-churru-māligai*; building round the central shrine of a temple; *prākāra*  
*śurru-p-pēlai* : coils formed in the shape of a basket  
*śurul-amudu* : betel and areca-nut, a respectful term of offering of—  
*śurutti-k-kāran* : servant who carries the paraphernalia *śurutti* or fly whisk in front of the procession  
*śutt-iṭṭikai* : burnt tile; brick; also known as *śutt-ōḍu*  
*svāmiyam, svāmyam* : ownership; right of property  
*svantiram, sutantiram, svalantra* : share, customary fee, emoluments  
*śvāstiyam* : right of hereditary enjoyment  
*svāmi-vāram* : land-lord's share; *mēlvāram*  
*svaṛṇādāyam* : revenue in gold; taxes payable in coin  
*śada-k-kaḍamai* : tax on shepherd  
*śākkai-k-kāṇi* : land set apart for the maintenance of dancers in the temples; also known as *nritya-bhōgam*  
*śāsana.baddhar* : those bound by the royal charter; original grantees  
*śamayāchāram* : religious usage; supervision of the religious and social life of the people; censoring of public morals  
  
*tachch-āchāriyam* : status of master carpenter; chiefship of carpenters  
*tachchāchārya-k-kāṇi* : the right of officiating as the chief carpenter, as also the stone-mason of a temple; the land set apart for the enjoyment of the holder of that office  
*tachcha-t-tulām* : a fee payable in olden days, probably for piccotahs or water-lifts  
*tadavi-k-kaṭṭudal* : to enchase; set in jewellery  
*taḍi* : field; a portion of cultivable land  
*taḍi* : mark of an illiterate person placed in the place of his signature  
*taḍi-mārum-kudirai-ch-chēvagar* : cavalier of the king's troops affixing his seal or mark  
*taḍi-p-padakku* : at the rate of one *padakku* for every *taḍi*

- tagattu-k-kulai* : a variety of neck ornament
- Taiñchai*: *Tañjai*; *Tañjavūr*
- taippu-muttu* : a variety of pearl
- taiviyam* : *daivya*, act of god
- taiyān* : tailor
- tākki* : s.a. *sākshin*; witness
- talai-ch-chammādu* : responsibility
- tāla-ch-chemmai-pon* : gold of the fineness prescribed by the royal treasury
- talai-k-kāṇam* : fee or tax on the *talai* or foot-binding used by toddy tappers
- talai-k-karai* : land adjoining a field or a tank bund
- talai-k-kōli* : dancing woman adept in her profession
- talai-māru* : exchange
- talai-nīr* : supply of water irrigating the fields in the upper reaches of the channel
- talai-p-pēlai* : head sluice
- talai-p-pirai* : *prathamā tithi* in the bright fortnight
- talai-vāy* : main entrance; head sluice
- talai-vāy-ch-chēri* : quarters near the main gate of the village or town
- talaiyārikkam* : tax payable for the village watchman; s.a. *talaiyāri-k-kāṇi*
- talai-y-īdu* : that which is nearest or first
- talai-y-īduvār* : temple servants who provide leaves and flowers for worship
- tala-k-kāval* : *sthala-k-kāval*; s.a. *ūr-k-kāval*; village watch
- tāla-k-kūttu-k-kambi* : an ornament
- tālam* : treasury
- tala-pātam* : army; armaments
- talattār* : s. a. *sthānattār*; committee of temple priests
- talavakāram* : a branch of the Sāma Vēda
- talaviśai* : flooring; pavement; s.a. *talavarīśai*
- taḷa-vritti* : land given for the support of temple
- taḷi* : temple
- taḷi-ch-chēri* : street or living quarters attached to a temple
- taḷi-ch-chēri-p-peṇḍugal* : women of the *taḷi-ch-chēri*; dancing girls attached to a temple



*taḷigai* : eating-plate; a certain quantity of boiled rice offered to idols in temples

*taḷigai-ch-chirappu* : special food offerings on specified occasions

*tāli-maṇi-vaḍam* : string of beads to which the *tāli* is attached

*tālimbam* : an ornament worn on the head

*taḷi-p-parivāram* : temple establishment

*taḷittal* : to sprinkle

*taḷiyilār* : persons attached to temples; temple servants, mostly women

*tāmam* : *dāmam*; garland of flowers; also known as *tonḡal*

*tambirāṭṭi(yār)* : queen; lady

*tammam* : s.a. *drachma*

*tampam* : *sthambha*; lamp-stand; lamp-post

*tānai-t-tiru-p-paṭṭigai* : girdle worn by an idol, over the cloth

*tānai-t-tūkkam* : a pendant in *tiru-p-paṭṭigai*

*tānam (sihāna)* : (lit. place) abbreviation of *dēvasthāna*; temple

*tāna-mānam* : dignity or honour attached to status or office

*tānattār* : temple priests

*taṇḍa-k-kānam* : probably s.a. *taṇḍam*

*taṇḍa-k-kurram*; *taṇḍai-kurram*, *taṇḍa-kūrram* : composed of *kurram* (fine for offences committed) and *taṇḍam* (penalties)

*taṇḍālar-mudal* : collection register of bill-collectors; register of collections made

*taṇḍal-ilakkai* : residence for the tax-collectors for halt during their stay in the village; also the expenses connected with the same

*taṇḍalir-kaḍamai*, *taṇḍar-kaḍamai* : fee payable for tax collectors; it may even be taken as the tax on bill-collectors

*taṇḍal-mēni* : surplus to cover shrinkage in the collection of taxes in grain

*taṇḍam* : punitive tax; fee or tax payable as penalty

*taṇḍa-p-paḍutal* : being fined; to be penalised

*taṇḍa-p-porul* : amount levied as fine or penalty

*taṇḍa-v-āni* : golden needle to test the fineness of gold

*taṇḍ-ēduppār* : palanquin bearers

*taṇḍ-ērudal* : to ride in a palanquin

*taṇḍēśvaran*, *taṇḍīśvaran* : s. a. *Chandēśvara*

*taṇḍesvara-p-peruvilai* : s. a. *Chandēśvara-p-peruvilai*

*taṇḍu* : (*daṇḍa*) army; going on a military expedition

- tanḍu* : collection, as of money or grain; s. a. *tanḍutal* and *tanḍal*
- tanḍu* : palanquin; pole for carrying the vehicle on which the image of a deity is set up
- tāṅgal* : pond used for irrigation
- tani-ch-chēvagar* : *ēkāṅgi-vīra*; trooper who is single; cf. *ekkaṭi* of the Telugu inscriptions
- tan-i-ch-cheygai* : cultivation of land without the help of others
- tānigar* (*sthānika*) : temple executive
- tānika-rāyar* : director of temple ceremonies
- tani-nagar*, *tani-nagaram* : mercantile town, as a separate unit
- taniśu* : loan
- tani-y-āl* : probably a supervisor; hence *tani-y-āl-pēru* : perquisites to the supervisor
- tāniya-varkkam* : *dhānya-varga*; grain group; class of taxes payable in grain
- taniyūr* : independent village, as a separate unit; free village
- tarma-pattar* : (*dharma-baddhar*); persons bound by the law; judicial officers
- tanma-sādanam* : *dharma-śāsana* ; document for the gift made for charitable purposes
- tanma-tāvalar* : (*dharma-dāvalar*) s.a. *dharma-vāriya-p-perumakkal*; also taken s.a. *dharma-vānigar*
- tan-n-ērram* : one's party; relations and followers of a person
- tanṇir-k-kāṇam* : water-cess
- tanṇir-p-paṭṭi* : land endowed for providing drinking water (*i.e.*, for watershed)
- tantati* : s a. *santati*; lineage
- tantram* : army (mainly the infantry)
- tantra-pāla* : chief of the army
- tantri* : trooper; leader of the army; temple priest; [also a weaver; most probably the words *kaikkōlar* and *aṭavi* came to signify both a soldier and a weaver on the analogy of this word *tantrin*]
- tantrimār* : members of the army; also known as *paḍaikkāṇavar*
- tantrimār* : class of persons who do worship in temples; priests
- tapasi*, *tapasvin* : ascetic; recluse; religious mendicant; also written as *tavaśi*
- tarā* : brass; alloy of eight parts of copper and five parts of tin, used for making metal vessels

- taragu* : brokerage; commission to a middle-man; tax on brokers; also known as *taragu-p-pāṭṭam*
- tārai-tāl-vāṭṭil* : a kind of vessel
- tāram* : brass; variant form of *tarā*
- taram* : grade; hence *taram-iṭṭal* : grading, as of lands
- taram-ili-nīlam* : unclassified land
- tārā-tattam* : (dārādattam) gift made with the libation of water
- tarav-iḍu-nel* : paddy given in lieu of wages
- taravu* : [lit. that which has been given] order; instruction; collection of debt or tax on pressure; also a dun
- taravu-kolluḍal* : to obtain receipt for anything given; collection of tax exercising pressure
- taravu-śāṭṭu* : an officer in the days of the Chōḷa rule, probably entrusted with the *taravu*
- tari*, *tari-k-kaḍamai*, *tari-y-irai* : tax on loom
- taripp-aruḍi* : desertion, as of a village by the inhabitants
- tari-p-puḍavai* : tax on loom payable in the shape of cloth; also known as *tari-k-kūrai*
- tari-talai* : tax on loom; probably s.a. *tari-k-kaḍamai*; (*talai-k-kāṇam*?)
- tariśana-kāṇikkai* : (darśana +) presents offered to a king or noble when meeting him
- tariśā-p-palli* : Christian church
- tar-kuri-māṭṭ-eridal* : to affix signature-mark by an illiterate person; to witness the execution of a document by an illiterate person
- taruppu* : a white stone of inferior value
- taśavāntam* : s. a. *daśavāntam*; variously explained as (1) one-tenth of revenue set apart for repairs to the tanks and wells for irrigation purposes; (2) land, the income from which would be equal to the amount, set apart for the same; (3) right of collecting one-tenth of the produce of lands irrigated from the water of a tank or well by the person who repairs the water source
- tattaḍuvu* : (taṭṭu+aḍaivu) occasional income
- tattali*, *tattāli* : a variety of musical instrument; also known as *tattali*; *tattali* is probably the same
- tattali-koṭṭuvar* : musical troupe performing on the instruments at the time of offering *śrībali* in the temple
- tattam* : eating plate; platter
- taṭṭāra-k-kāṇi* : goldsmith's holding

- taṭṭār-pāṭṭam, taṭṭāra-p-pāṭṭam* : tax on goldsmiths
- taṭṭ-oli* : (always mentioned along with *taṭṭār-pāṭṭam*) probably represents the tax on smithy or workshop of artisans like the blacksmith and others
- taṭṭoli* : metallic mirror
- taṭṭu-k-kāṇam* : s.a. *taṭṭār-paṭṭam*; fee for hammering; probably *taṭṭukk-āyam* also in the same
- taṭṭu-p-pulugu* : civet (secretion from the gland in the anal pouch of the civet-cat)
- tavaḷai-vāy* : an ornament
- tavanakam, tavanam* : *damanaka*; *marukkolundu*; a fragrant plant
- tavirttu* : to remove; to exclude
- tavukkai* : a kind of salver
- tayir-amudu, tayir-amirdu, tayir-amurdu* : curd presented as offerings to god, devotees, etc.
- tayittiriya-k-kidai-p-puram* : land endowed for scholars in the *Taittiriya śākhā* of the Yajur-Vēda
- tayyān, taiyān* : tailor
- tējamānyam* : ownership of landed property with *aṣṭa-bhōga* or the - eight kinds of enjoyment; also known as *tējasvāmyam*
- teṇḍa-kurram* : *teṇḍan-tirvai*; penal tax
- teṇṇam-paḷam* : ripe cocoanut
- terri* : elevated ground; mound
- terri-y-ambalam* : raised maṇḍapa in a temple; place where the *sabhā* used to meet
- tēṣa-kalam* : (*dēṣa* +) hour, time
- tēṣa-v-āḷi* : officer in-charge of a village or district
- tēvadānam* : s. a. *dēvadāna*
- tēv-aḍimai* : dancing-woman, as servant of god; maid servant attached to a temple
- tēvai* : affairs; business; requirement; aids
- tēva-kuḍimai* : tenancy under the control of a temple
- tēvakulam* : (*dēva-kulam*) temple
- tēvāra-dēvar* : idol set up for one's personal worship
- tēvar-aḍiyār* : woman-servants of the temple
- tēvar-aḍiyār* : Śaiva devotees; *māhēśvarar*
- tēvāram* : (*dēvāram*); temple
- tēvar-kanmi* : s. a. *dēvakarmi*

- tiḍar* : raised ground; elevation  
*tiḡular* : (Kan.) Tamils  
*tiṇai-k-kālam* : department  
*tiṇḍā-ch-chēri* : quarters where untouchables lived  
*tiṇḍal* : field  
*tiṅgal-kāsu* : an ancient tax payable every month; *tiṅgal-chōru*, *tiṅgal-ney*, *tiṅgal-mōgam*, etc. are similar ones; cf. also *māda-p-paḍi*  
*tiṇa-mālai* : [row of lights] s.a. *śaraviḷakku*  
*ti-p-pōkku-śempon* : pure refined gold  
*tiraḷ-maṇi-vaḍam* : a kind of necklace  
*tiram* : herd of eighty sheep, eighty cows and eighty buffaloes  
*tiramam* : s.a. *drachma*  
*tiraṅgal* : a flaw in pearls, being wrinkled or shrivelled  
*tirāśam* : a flaw in rubies  
*tirigai* : potter's wheel; hence *tirigai-āyam* : tax payable by the potter for his trade  
*tirikāla*, *tri-kāla* : the three parts of the day, morning noon and evening (when worship is offered in temples)  
*tiri-śūla-k-kal* : s.a. *śūla-k-kal*  
*tiriśūlam* : *trisūla*; trident  
*tiriśūla-k-kāsu* : s.a. *śūlavari*  
*tiru* : astrologer  
*tiru* : *māṅgalya*; *tālī*: wedding-badge  
*tiru-ch-chandam* : an ornament adorning the image of a deity  
*tiru-ch-chāndu-p-paṭṭi* : land set apart for meeting the expenses of coating the image of the deity with sandal and other fragrant pastes  
*tiru-ch-chari* : s.a. *śari*; an ornament  
*tiru-ch-chennaḍai* : current and daily routine expenses in a temple; also the daily worship and food offering  
*tiru-ch-chennel-naḍai* : provision of good paddy (red paddy or *śambā*) for making daily food offerings in a temple  
*tiru-ch-churrālayam* : shrines of minor deities around the central shrine in a temple  
*tiru-ch-churru-mālai*, *tiru-ch-churru-maṇḍapa*, *tiru-ch-churr-ālai*, *tiru-ch-churru-māligai* : porches surrounding the central shrine of a temple; *maṇḍapa* enclosing the central shrine; *prākāra*  
*tiru-k-kai-k-kōṭṭi*, *tiruk-k-kai-yōṭṭi* : *maṇḍapa* in the temple where sacred hymns are sung

- tiru-k-kai-k-kōṭṭi-y-ōḍuvār* : reciters of sacred hymns in temple
- tiru-k-kai-valakkam* : fixed allowance for the daily service in temple; distribution of offerings in temples to worshippers
- tiru-k-kalaśa-muḍittal* : consecration ceremony of the temple; *kumbhā-bhishēka*
- tiru-k-kannāmaḍai* : sweet rice preparation with ghee, sugar and plantain fruits for offering to god
- tiru-k-kaṇ-ṇōkku* : taking a temple deity to a *maṇḍapa*
- tiru-k-kaṇṭha-maṇi* : a variety of necklace
- tiru-k-kēṭṭai-k-kilatti* : goddess Jyēshṭā-dēvi
- tiru-k-koḍukku* : a variety of ornament
- tiru-k-kolgai* : s.a. *kavacha*; metallic cover exactly fitting the image of a deity
- tiru-k-korra-vāyṭal* : palace
- tiru-k-kośakam* : ornament in the shape of folds of the garment worn by the image of a deity
- tiru-k-kōśalai* : cow stall of the temple
- tiru-k-kugai* : s. a. *guhāi*
- tiru-maḍavalāgam*, *tiru-maḍai-vilāgam* : quarters round a temple
- tiru-maḍil* : wall round the temple
- tiru-malai* : [lit. sacred hill] central shrine, mostly of the Śiva temple
- tiru-māligai-ch-churru* : s.a. *tiru-ch-churru-māligai*
- tiru-māligai-p-patti* : small shrines or niches on the inner side of the compound wall in the prakāra of a temple
- tiru-māligai-p-pillai* : temple executive
- tiru-māligai-p-pillaiyār* : god Chaṇḍēśvara
- tiru-mandira-k-koḍi* : cloth threaded round the flag-staff of a temple during festivals
- tiru-mandiram* : temple
- tiru-mandira-pōṇakam* : food offering to a deity in temple
- tiru-mandira-pōṇa-p-puram* : land endowed for making daily food offerings in a temple
- tiru-mandira-v-ōlai* : secretary of the government; officer entrusted with the duty of communicating in writing the decisions of the king
- tiru-mandira-v-ōlai-nāyakam* : chief secretary to the government; chief of the *tiru-mandira-v-ōlai* department
- tiru-maṇjana-śalai* : s. a. *abhishēka-maṇḍapa*

- tiru-k-kāmakōṭṭam* : s.a. *kāma-k-kōṭṭam*  
*tiru-k-kāvaṇam* : s.a. *kāvaṇam*  
*tiru-k-kāvaṇa-k-kāl* : title deed; also *tōraṇa-k-kāl*  
*tiru-melukku* : washing and cleaning the temple premises  
*tiru-mēni* : image of a deity  
*tiru-mēni-kāval* : temple watch  
*tiru-mērkaṭṭi* : canopy over the idol in temple  
*tiru-mēr-kōyil* : [lit. sacred temple in the west] Viṣṇu temple being situated to the west of the village  
*tiru-mēr-pūchchu* : perfumery-paste like sandal, civet, etc. for coating the images of deities  
*tiru-mey-kāppu*, *tiru-mey-kāval* : temple watchman  
*tiru-mey-p-pūchchu* : s. a. *tiru-mēr-pūchchu*  
*tiru-muga-k-kāṇam* : expenses as wages, etc. to the person who brings the *tirumugam* (royal order) to the village  
*tirumugam* : śrī mukha; royal order  
*tiru-muga-t-tēvai* : s.a. *tirumuga-k-kāṇam*  
*tiru-naḍai-māḷigai* : procession-path round the central shrine of a temple  
*tiru-nakṣatra* : natal star; annual birthday; year  
*tiru-nal-i-yāṇḍu*, *tiru-nal-i-yāṇḍu* : prosperous regnal year (of a king)  
*tiru-nāl-tēvai* : expenses of a festival; also known as *tiru-nāl-kāṇikkai*  
*tiru-nāma-k-kāṇi*, *tiru-nāmattu-k-kāṇi* : [lit. hereditary right of enjoyment in the sacred name] land or village, generally tax-free, endowed to a Śiva temple  
*tiru-namanikai* : holy both of the deity in the temple  
*tiru-ñānam* : sacred hymns sung in front of the deity in a temple during worship  
*tiru-ñānam-perra-piḷḷaiyār* : Saint Jñānasambandha  
*tiru-ñāna-p-puṇam* : land endowed for meeting the expenses of singing sacred hymns in temples  
*tiru-nāraṇam-piḷaittal* : to break an oath taken in the name of god Nārāyaṇa  
*tiru-nār-kaṭṭir-kāl* : cot for a deity or king  
*tiru-naṭṭa-kaṇa-p-perumakkal* : members of the committee of dancers in the temple  
*tiru-nayanam* : ornament made of gold or silver resembling the eye and put on the idol; s.a. *kaṇ-malar*

- tiru-nerri-t-tiraṇai* : ornament worn on the forehead of a deity  
*tiru-nirañ-cheydal* : to gild the image of a deity  
*tiru-p-paḍaiviḍu* : sacred place of a deity  
*tiru-p-paḍi-k-karakam* : pot for keeping the holy water to be used for bathing a deity  
*tiru-p-paḍi-mārru* : articles of food offerings to deity in temple  
*tiru-p-paḍimārutal* : to provide for food offerings to a deity  
*tiru-p-paḍiyam* : s.a. *tiru-p-paḍigam*; sacred hymns, usually containing ten or eleven stanzas, as in the *Tevāram*  
*tirup-p-pali-kottuvār* : s.a. *śrībali-kottuvār*  
*tiru-p-palli-k-kaṭṭil* : throne; cot or seat of god or king  
*tiru-p-palli-t-tāmam* : s.a. *tāmam*  
*tiru-p-palli-t-toṅgal* : s.a. *toṅgal*  
*tiru-p-paṇi* : temple service; sacred service  
*tiru-p-pariśaṭṭam* : s.a. *pariśaṭṭam*  
*tiru-p-paṭṭam* : ornamental plate worn on the fore-head of an image of a deity; also the sacred diadem  
*tiru-p-paṭṭigai* : girdle worn by the image of a deity  
*tiru-p-pāvāḍai* : s. a. *pāvāḍai*  
*tiru-p-pirai* : ornament like the crescent worn on the idol of Śiva or Liṅga  
*tiru-p-pōṇakam* : food offering to a deity in temple  
*tiru-p-pudiyadu, tiru-p-pudiyidu* : first fruits paid as homage to temple  
*tiru-p-pugai* : [sacred smoke] incense; also the incense burner  
*tiru-p-pū-maṇḍapa* : maṇḍapa in the temple where flowers are woven into garlands  
*tiru-p-pura-k-koḍai* : back-yard or open space in the temple  
*tiru-p-pura-k-kuḍai* : parasol held over a deity from behind  
*tiru-t tōppu* : sacred garden attached to a temple, mostly flower garden and sometimes of fruit-bearing trees ; *nandavanam*  
*tiruttu* : land brought under cultivation; reclaimed land  
*tiruttudal* : to supervise; to execute; also to reclaim barren or waste land  
*tiru-v-aḍi* : [lit. sacred feet] ascetic; title of the ruler of Travancore; s. a. *śrīpādaṅgal*  
*tiru-v-aḍi-dēśam* : the country of Travancore; also known as *tiru-v-aḍi-rājyam*  
*tiru-v-aḍi-k-kūrai* : anklet worn to an image of deity



- tiru-v-aḍimār* : honorific title of rulers, brahmaṇa officers, heads of maṭhas and temple priests in the Malaināḍu
- tiru-v-aḍi-nilai* : *pīṭha*; pedestal for an image of deity
- tiru-v-aḍi-piḍippān* : temple priest
- tiru-v-aḍi-piḍittal* : conducting worship in a temple
- tiru-v-akkiram* : food offering to deity in temple
- tiru-v-ālikkal* : s.a. *āli-k-kal*
- tiru-v-amudu* : food offering, mainly of rice, to a deity in a temple
- tiru-v-āṇai* : royal order
- tiru-v-āṇḍ-elutt-idutal* : to date an event in the king's reign specifying the year
- tiru-v-āṇḍilal* : the temple of Śiva at Karuvūr
- tiru-v-aṇukka-vāśal* : entrance to the *garbha-griha*
- tiru-v-ārādanai* : worship of deities in temple
- tiru-v-arāṅgu* : s.a. *rāṅga-maṇḍapa*
- tiru-v-arāṅgu-irūṇḍa-peṇḍugal* : dancing women attached to a temple
- tiru-vaṭṭa-maṇi*, *tiru-vaṭṭa-maṇi-vaḍam* : a variety of necklace
- tiru-vāy-k-kēlvi* : king's oral orders; officer entrusted with the duty of receiving king's orders and communicating the same in writing to the respective departments or officers; see *kēlvi*
- tiru-v-āyppāḍi* : temple of god Kṛṣṇa; also known as *gōkulam*
- tiru-v-eluttu-ch-chāttudal* : to affix the signature (by the king)
- tiruviḍai-p-parru* : s. a. *tiruviḍaiyāṭṭam*
- tiru viḍaiyāṭṭam* : land or village, mostly tax-free, endowed to a Viṣṇu temple; also management of Viṣṇu temple affairs
- tiru-vīdi-nāyakar* : metallic image of the deity for being taken in procession along the streets round the temple
- tiru-vīdi-p-pandam* : torch borne in the procession of the deity along the streets round the temple
- tiru-viḍu* : gift-deed
- tiru-viḷakkuḍaiyār* : persons entrusted with the service of lighting lamps in temples
- tiru-viḷakku-k-kuḍi* : tenants charged with the maintenance of lamps in temples, enjoying land as *mānya* for the same
- tiru-viḷā-p-puram* : land or village set apart for meeting the expenses of celebrating festivals in temples
- tiru-viraiyā-k-kali* : sacred oath in the name of god Śiva
- tiru-v-iruppu* : temple premises; temple site
- tiru-v-uḍambu* : s. a. *tiru-mēni*; image of a deity

- tiru-v-ulagaḷattal* : to survey and measure the land  
*tiruvuḷuttu* : a variety of ornament; probably a necklace  
*tiru-v-unṇāḷi(gai)* : s.a. *unṇāḷigai*; also written as *tiru-vanṇāḷigai*  
*tittu, tittu-k-kuri* : written note; document; deed  
*tivu-karivu* : withering from sun's heat ; damage, as of crops  
*tiyadi* : date; s.a. *tēdi*  
*ti-y-eri-śōru* : s. a. *havirbali*; see *śribali*  
*toḍaiyal* : garland of flowers worn over shoulders  
*tokkai-k-kunri* : loss or waste in cultivation  
*tōlā-ch-cheviyar* : a class of people, probably having elongated ear-lobes to touch the shoulders; s. a. *lamba-karṇar*  
*tolir-pattikai* : a variety of woman's girdle with beads and scroll-work  
*tōl-ottu* : a fee payable in olden days, probably connected with hides and skins  
*tonḍar-śir-paravuvār* : [lit. one who spreads the fame of devotees] Saint Sundara, as the author of the *Tiru-t-tonḍa-t-tokai* ; also Śēkkiḷar, as the author of the *Periya-purāṇam*  
*tonḍu* : slavery; devoted service; devotion to god  
*tōṇi-k-kadamai* : tax on boats  
*tōrai* : a standard linear measure of four fingers' breadth  
*tōraṇa-k-kāl* : pillar of the aureola over the idol; s. a. *tiruvāśi-k-kāl*  
*tōraṇa-k-kāṇikkai* : presents for decorating the village with arches, etc.  
*toru* : slave; devoted servant  
*toru* : herd of cows  
*toru-nilai* : cattle-stall  
*tōṭṭa-k-kūru* : garden-land  
*tōṭṭa-p-puravu* : tax on garden lands  
*tōṭṭa-vāriya-p-perumakkaḷ* : members of the executive committee of the *sabhā* looking after the affairs of gardens  
*tuḍavai* : cultivated field  
*tuḍavu* : a liquid measure  
*tukkai* : (*duggai*) goddess Durgā  
*tūkkam* : pendant in jewels; a variety of ear-ornament  
*tūkkam* : weighing  
*tū-k-kuttal-ariśi* : well-polished rice  
*tulābhāra* : weighing the king or other exalted person against gold or other precious metals and stones and distributing the same to temples, etc.  
*tulābhāra vari* : tax collected for making the *tulābhāra* of the king

*tuḷai-niṟai, tuḷai-niṟai-pon, tuḷai-niṟai-ṣempon* : pure gold

*tuḷā-k-kūli* : fee for weighing in balance

*tulyam* : [lit. equal] true copy

*tundaka-vishayam* : Tondai-maṇḍalam

*tuṇḷiya* : who had died

*tūmbu* : sluice or an outlet; vent in a sluice to distribute water

*tūmbu* : a measure of capacity

*tūṭṭi* : *stūpa*; pinnacle of the temple *vimāna*

*turai-minṇar-pon* : a coin current in olden days

*turavu* : large well for irrigation purposes

*turu* : repeated reciting of the Vēdas to keep in memory

*turvāyakam* : (*dur-vāchaka*) abusive language

*tūśaka-t-tari* : tax in olden days, probably on looms weaving tent-materials

*tūśi-p-paḍai* : van of an army; also written as *tūśu-p-paḍai*

*ubhayam* : a tax payable in gold in olden days; evidently the tax *ubhaya-mārgam* is the same; if so, it will mean the toll collected on the highways in both the directions, *i.e.*, inward and outward

*ubhaya-nānādēśi* : the two divisions of the organisation *nānādēśi*, evidently the *nānādēśis* and the *chitramēli-p-periyanāṭṭavar*

*ubhaya-paliśai* : interest in two ways, *i.e.*, in money and in kind

*ubhaya-rāṇuvam* : the two armies

*uchham-pōḷḍu* : noon; midday

*uchchi-śandi* : noon service in the temple

*udai-kulam* : breached tank

*udai-p-paḍai* : standing army

*udaiyār* : (lit. possessor) king; lord; chief deity of a temple

*udaiyār-śālai* : feeding house attached to the temple

*udaka-dārai* : (gift) with the libation of water; also referred to as *udakañ-śeydu* and *udakam-panṇi*

*udaka-pūrvāñ-śeydal* : giving away with the libation of water

*uḍal* : capital of which only the income or interest should be utilised for expenses

*uḍanilai-k-kudirai-ch-chēvagar* : mounted soldier serving as a body-guard

*uḍankūṭṭam* : retinue; councillors and nobles forming the entourage of the king

- uḍankūṭṭattadhikāri* : officer in charge of the retinue; officers like the ministers in the retinue of the king
- uḍan-pāḍuvān* : musician who accompanies the principal singer in the performance
- uḍanvāram* : gross produce before it is divided between the landlord and the tenant
- udāśina-vāriyam* : committee which is neutral to both the parties; *madhyastha* or arbitration committee
- uḍira-p-paṭṭi* : (blood-land) land given to the descendants of persons who fell fighting
- ūḍupokku* : [lit. that which comes between] probably cultivation of two kinds of grain mixed
- uḡappār-pon* : tax payable in gold on joyous occasions like the marriage; probably *kaṇṇāla-k-kāṇam* is the same
- uḡavai* : evidently s.a. *uḡappār-pōn*
- uḡir-p-puravan* : ornament worn at the tip of the finger covering the nail
- ulag-alavu* : survey of the country
- ulagudaiya-perumāl* : king, as owning the earth
- ulaḡḡam* : work
- ulattal* : to suffer; to experience sorrow, pain or trouble
- ulattal* : getting confused
- ulavi-pon* : pure gold
- ulavu-kāṇiyāṭchi* : hereditary right of cultivation
- ulavu-kāṭchi* : probably presents offered to the king or other exalted person when going in procession round the village
- ulavu-kuḍi, ulu-kuḍi* : agricultural labourer; cultivating tenant
- ulgu* : customs; toll
- ulgūṭṭuṇ-śarakku* : articles on which customs duty are leviable
- ūliyam, ūligam* : service; service *inām*; s.a. *śēvai*
- ul-l-ālai* : inner hall; inner portion (of the palace)
- ul-l-iruppu* : reserve cash
- ulliṭṭam* : loss
- ulliṭṭār* : including those mentioned therein
- ulliya-k-kūli* : probably water-fee for irrigation from wells; also tax or wages for well-digging
- uluppai* : presents of fruits, articles of food, etc. offered to great personages; supplies gratuitously given to officials on tour by people or subordinates

- uḷ-vari** : internal revenue; taxes levied by the local body; s.a. *anta-rāyam*; also denotes the orders issued by the state fixing the amount of such taxes payable
- umbalam, umbalikkai** : land granted rent-free for the performance of services; *mānya*; also referred to as *umbalika*
- uṇḍalivu** : expenses of feeding
- uṇḍi-y-achchu** : a coin current in olden days
- uṇṇālīgai** : inner-most sanctuary of a temple; *garbha-griha*
- uṇṇālīgai-uḍaiyār** : s. a. *uṇṇālīgaiyār*
- uṇṇālīgai-vāriyam** : committee looking after the affairs of the *garbha-griha*
- uṇṇālīgaiyār** : god in the *garbha-griha* ; priests in charge of the *garbha-griha*
- uṇṇilam** : land comprised within (the boundaries described)
- upānam** : the first moulding above the plinth, in the construction of temple
- upāti** : [lit. obstruction] dues; anything payable as a debt or obligation; also found written on *opādi*
- upāyam** : [lit. means, artifice] a tax in olden days
- upattirakam** : s. a. *upadrava*
- uppāyam, uppu-k-kāśu** : salt-tax
- uppiṇji** : a variety of ginger; salted ginger
- uppu-k-kō-ch-cheygai** : royalty paid for manufacturing salt or the royal monopoly of manufacturing salt (cf. *alavaṇa guḍakshōbham*)
- ūr** : [lit. village] local assembly of the village 'consisting mainly of agriculturists (*vēḷāṇmakkaḷ*)
- ūr-āḷar** : chief or headman of the village
- ūral-vari** : tax or fee for the maintenance of the mortar husking paddy
- urai-nāli** : at the rate of one *nāli* for every *urai* of sixty *marakkāls*
- ūr-āṇmai** : land held in common by the village
- ūrāṭchi** : administration of the village ; expenses to be incurred in connection with the same ; probably *ūramai* also is the same
- ūravar** : members of the village assembly *ūr*
- ūrā-v-orri** : non-redeemable or permanent mortgage
- ūr-ch-charigai** : meeting of the village assembly
- ūr-eṭṭu** : committee of eight members of the local assembly *ūr*; also the taxes payable for the expenses of the committee [probably relates to the *eṇ-pēr-āyam* and has some reference to the eight major items of revenue]

- ur-idu-varippāḍu* : tax levied by the local village assembly *ūr*
- urimai* : (ownership, proprietorship), wife
- ūr-k-kaḍamai* : obligations and taxes payable to the village assembly *ūr*
- ūr-k-kalanai* : village servants and minor officials like the artisans of the local assembly
- ūr-kalañju* : standard gold of the required weight and fineness maintained by the local assembly
- ūr-k-kamañju* : having constituted as *ūr*; responsible to the *ūr*
- ūr-k-kaṇakkar-jivitam* : land assigned in lieu of salary to the village accountant; perquisites of the office of the village accountant
- ūr-kāval* : village watchman
- ūr-irukkai* : land adjoining a village and belonging to it; s.a. *nattam*
- ūr-k-kaṇ-chemmai* : fineness, as of gold equal to the standard maintained in the village
- ūr-k-kīl-iraiyili* : tax-free land exempted as such by the village assembly (*ūr*), the loss in the revenue on such exemption being made good by the assembly
- ūrōm* : we, the members who constitute the village assembly *ūr*
- ūrru-k-kāl* : spring channel
- ūr-u-pāḍai* : obligation of keeping in good repair the pathways and roads
- uruttira-kaṇam* : s.a. *rudra-gaṇa*; devotees of Śiva
- uruttira-kaṇikai* : s. a. *rudra-gaṇikai*
- uruttirar* : s. a. *Śrīrudra*
- ūr-vāriyam* : village committee
- uśāvaḍi* : s. a. *chāvaḍi*; territorial subdivision
- uśi-vāśi* : tax prevalent in olden days, probably connected with tailoring
- uṭchēvakam* : (*uṭ* + *śēvakam*) village service; local watch; also the expenses for the same
- uṭ-kōḷ* : expenses for the collection of taxes, etc.
- uṭ-kolḷudal* : collection of taxes
- uṭkōyil* : central shrine in the temple; *garbha-griha*
- uṭpuravu* : endowed land made tax-free by the local authority like the *sabhā*, *nāḍu*, etc.
- ūttai-p-pāṭṭam* : lease for clearance of silt
- uttama-dāni* : gift made not expecting any merit for the same; superior variety of gift

- ulvari* : [lit. disguise] fraud
- upa-sandi* : intermediary service of worship in a temple, between the morning and midday services
- ūr-mañchikkam* : village common and uncultivated waste land in the village belonging to the assembly *ūr*; also known as *ūr-p-podu*; s.a. *sabhā-mañjikkam*
- uruvu-kōl-nilan-kāśu* : amount payable in coin in addition to the share in produce from the land for the purchase of cattle
- ūr-vilai* : sale ordered and conducted by the village assembly *ūr*
- ultāna-dvādaśi* : twelfth day of the bright fortnight in the month of Kārttigai when god Viṣṇu is believed to wake up from sleep
- uttāram* : s.a. *uttaravādam*; guarantee; responsibility
- uttāram* : regular fixed payment
- ūttai-y-aṭṭudal* : to suffer disgrace
- uttara-mantrin* : chief minister
- uvā* : the full-moon and the new-moon days
- uvachcha-vari* : tax payable by or for the maintenance of the *uvachchar*
- uvachcha-k-kāṇi* : rent-free land given to *uvachchan* for service as drummer in a temple
- uvachchan* : drummer doing service in a temple; *pūjāri* or the person who conducts worship in the temples of village goddesses
- uvachchu* : a variety of drum
- uvanni* : fountain-head; head of water above the main sluice
- uvvi* : head
- vachchira-p-paḍai* : (vajra+) lower or foundation tier of the wall in a temple
- vāchchiyam* : *vādyam*; musical instrument
- vāchchiya-mārāyan* : head musician or the chief *mēlakāran* of a temple or palace; title conferred in olden days by the king on an expert in instrumental music
- vāḍā-k-kaḍamai* : permanently fixed tax; permanent and regular income
- vāḍā-k-kaḍan* : permanent loan
- vaḍakku-vāśal-śelvi* : goddess Kālī, as presiding at the northern gate of a town

*vaḍam* : strands of a garland or necklace; thick rope for drawing temple car

*vaḍḍa-vyavahāri* : a leader of the merchant guild; banker; principal moneychanger

*vadi* : way; channel; road; street; s.a. *vaḷi* or *vīdi*

*vaḍuga-vaḷi*, *vaḍuga-p-peruvaḷi* : [lit. the great northern trunk road] the *Āndhrāpatha*; the Āndhra country

*vaḍuga-vāḷi* : a kind of ear-ring

*vagaṇḍa-kāṣu* : tax payable in cash for marking the details, as of land; sub-division fees; also the fee for settlement, as of a dispute

*vagai-p-pēru* : perquisites of the survey and settlement officer

*vagai-śeydal* : to survey the lands and make a revenue settlement; hence *vagai-śeykiravar*, *vagai-śeyvār* : officers making the survey and settlement of lands

*vagai-y-aruttal* : to settle, as a dispute

*vaichchamudu* : s.a. *vechchamudu*

*vaichchamudu-maṇḍapa* : temple kitchen; s.a. *maḍai-p-paḷḷi*

*vaidya-bhāgam*, *vaidya-bhōgam* : land set apart for the maintenance of a physician; also known as *vaidya-vritti*

*vaidya-purandaran* : a title conferred by the king on a distinguished medical man in olden days

*vaigal* : dwelling, staying

*vaiḍḍu* : s.a. *vēmbu*; margosa

*vaiśya-vāṇiya-nagarattār* : guild of a class of merchants

*vaiyagattār-kal* : standard weight (of the country)

*vakkāṇittal* : to expound; disputation

*vakkānikku-maṇḍapam* : hall where disputations in the *śāstras* are held

*vaḷāgam* : place; quarters; also written as *viḷāgam*

*vālagiri* : the mythical mountain *Chakravāḷam*

*vāḷakam* : cuscuss grass

*vaḷakku-muri* : complaint; plaint

*vāḷ-vaḷi-tirantān-guḷikai* : a Pāṇḍya coin of ancient times said to have been issued by Jaṭavarman Sundara Pāṇḍya I who had the title *vāḷ-vaḷi-tirantān*

*vāla-maṇjāḍi* : probably *vāla-vari* and *vāla-k-kāṇam* are the same; tax of a *maṇjāḍi* on the extent in length of the house-site

*valāṅgai* : right-hand castes



*valaṅgai-iḍaṅgai-maganmai* : tax on the right and left-hand castes, to be paid by all able-bodied men capable of bearing arms

*valaṅṅiyar* : *baniḡigas*; merchants; members of the guild *valaṅṅiyar*; mercantile community

*valattu-k-kai* : s.a. *valaṅgai*

*vali-ch-chevvai* : road; keeping the road in good repairs

*vali-k-kaṇṇār* : descendants; progeny

*vāḷilār* : swordsmen

*valinaḍaikk-idum-ṇaṇam* : road cess

*valipāṭṭu-p-ṇuram* : land endowed for meeting the expenses of conducting worship in a temple

*valitam* : s.a. *vaṇitam*

*vali-y-āyam* : tolls on the roadway

*vali-y-echcham-arudal* : to become extinct, as a family

*valiyilār* : descendants

*vaḷḷān-vagai* : s.a. *veḷḷān-vagai*

*vāl-ṇerra-kaikkōḷar* : the infantry composed of expert swordsmen

*vaḷudi-y-achchu-varggam* : group of taxes payable in Pāṇḍya coins

*vaḷuvāḍa-nāḷi* : correct measure

*vaḷuvudal* : to be deficient; to be inaccurate

*vāmana-k-kal* : boundary stone of lands granted for religious purposes

*vāmana-mudrā* : figures of *śaṅkha* and *chakra* marked on the boundary stones set up to demarcate the lands of Viṣṇu temple

*vāṇa-vāri* : rain water

*vaṅḡiṣam, vaṅḡiṣam* : s.a. *vaṁśa*; family; lineage

*vaṇitam* : locality; region; administrative division

*vaṅja* : *vaṁśa*; lineage

*vaṇṇāṇai-k-kumpiṭṭār* : Chēraṁan Perumāḷ Nāyanār

*vaṇṇān-vari, vaṇṇāra-p-ṇārai* : tax on washerman

*vaṇṇiya-p-ṇāru* : lands held under military tenure; lands in the enjoyment of soldiers

*van-ṇāṭṭam* : fixed rent in kind due under a lease-deed which does not provide for any relief against loss due to draught

*vān-ṇāyir* : garden crops and fruit trees, especially valuable kinds of produce raised on wet land, as betel, plantain, sugarcane, etc.

*vara-grāma* : village given as gift to a temple, *maṭha* or brāhmaṇas

- varāha-muddirai* : seal or emblem bearing the figure of a boar, being the crest of the state, like the Vijayanagara, etc.
- varāhan* : a gold coin
- varāha-panam* : a coin
- varāhan-pullī-kulīṣai* : an ancient coin
- varai* : a flaw in pearls
- vāraka-kāṇam* : payable in grain, in addition as interest to the cultivation advance
- vara-k-kūli* : hire-charges for carrying paddy, etc.
- vāram* : method of reciting the Vēdas
- vāram* : share in the produce
- varaṇam* : selection or election of a person to a committee
- varā-ch-chinnam* : a fraction
- varaṭchāvi* : blighted crop; crop withered without growing grain from want of rain
- varattu* : (lit. that which is received) order
- varattu* : limit; boundary
- varavai* : income, as from tax
- vārāvaigal* : bad debt written off, but subsequently collected
- vari* : tax; revenue register; order of the king and his officers fixing the revenue payable
- varikkōlam* : a variety of dance performed in temples
- vari-k-karrai* : bundle of straw, etc. suitable for roofing
- vari-k-kūru-śeyvār, varikku-k-kūru-śeyvār* : officers grading the cultivable land and fixing the tax payable thereon
- vari-p-pāḍu* : taxation; taxes levied
- vari-p-pottagam* : tax register; officer maintaining the same
- vari-p-pottaga-nāyakam* : head office of the revenue accounts; chief officer of the same
- vari-p-pullī* : accountant; a variety of tax register
- variśai* : cultivator's share of produce
- variśai* : distinctive mark of honour or privilege granted by king
- variśai* : village dues; cess by or to the local authority
- variśaiyil-iṭṭapaḍi* : as entered in the accounts; according to the grade classified
- vari-śōru* : obligation of feeding, probably of revenue officer
- vāriyam* : executive committee; appointment as a member of that body; office of supervision
- vāriyam-śeyvār* : members of the *vāriyam* committee

- vāriyan* : supervisor  
*vāriya-p-perumakkal* : members of the *vāriyam* committee  
*variylār* : s.a. *vari-k-kūru-śeyvār*  
*variyl-īdu* : entry in the revenue register ; officer maintaining the revenue registers  
*variyl-īdutaḷ* : to enter in the revenue register  
*vari-y-ōlai* : order fixing the taxes ; statement of taxes payable deed of agreement  
*varṭtanai* : perquisites due to an office ; periodical presents to offered to an officer of rank by his subordinates and the people  
*varuṣa-kāṇikkai* : annual presents  
*varutini* : Skt. *varūthini*; army  
*vāśal* : king's court  
*vāśal* : [lit. gate] palace gate or palace; officer in charge of the same  
*vāśal-pōnda-kudimai* : [burdens of citizenship due at the gate] taxes, probably other than the land revenue, payable to the state  
*vāśal-kaṇakkān, vāśal-karaṇikam* : accountant in the *vāśal*  
*vāśal-kāṇikkai* : presents, probably annual, offered to the palace  
*vāśal-kāriyam* : officer in charge of the palace gate ; also known as *vāśal-mudali, vāśal-nirvāham*  
*vāśal-kūḷi-p-panam* : probably door-tax; i.e., house-tax based on the main doorways  
*vāśal-panam* : periodical payment due to the palace; door-tax  
*vāśal-tiramam* : door tax  
*vāśal-viniyōgam* : evidently s.a. *vāśal-kāṇikkai*  
*vasanta-maṇḍapa* : maṇḍapa in the midst of a pleasure garden where spring-festival of the deity is celebrated  
*vāśi* : rate, as of interest; portion; difference in dryage as of grain, to make up which it is collected in excess; discount in changing  
*vāśi* : wastage  
*vāstu-kṛityam* : building work  
*vāstu-parivāram* : vacant site attached to a house  
*vāṭikā* : a measure of land; also known as *ṇīlam* or *vēli*  
*vattam* : a kind of pearl, evidently roundish ones; an ornament  
*vattam, vattan* : every, each, cycle  
*vattam* : money changer's commission; trade discount  
*vattan, vatta-rāyan* : Vatsa-rāja  
*vātti* : school-teacher

- vattinai* : perquisites; s.a. *varttanai*
- vaṭṭi-nāḷi* : an obligation in olden days, probably payable at the rate of one *nāḷi* for each *vaṭṭi*
- vayakkāl* : small branch channel distributing water to fields
- vāyinam* : trade
- vayirāvi*, *vairāgi* : ascetic serving in a temple
- vayittiya-vritti* : s a. *vaidya-vritti*
- vāykkāl* : channel, canal
- vāykkāl-pāṭṭam* : channel cess; fee for keeping in good repairs the channels
- vāy-k-kēlvi*, *vāy-k-kēlviyār* : officer who hears king's oral order; officer in attendance on the king acting as the intermediary between the king and his subjects; king's order
- vāy-k-kēṭpār* : personal secretary, as to a king; s.a. *vāy-k-kēlvi*
- vāyṭal* : *vāśal*
- vāy-t-talai* : head-sluice of a channel
- vāyṭṭalaippaḍi-kulai-yaraiyargal* : members of the committee looking after the sluices, and bunds of the channel (irrigation-committee)
- vechchamudu* : cooked food
- vēda-vritti* : tax-free land set apart for meeting the expenses of reciting the Vēdas
- vēḍiḷai* : probably to be read as *vēṭṭinai*
- vejjam* : a flaw in rubies
- vēkārī* : compulsory labour (always found used in conjunction with *vetṭi*); see also *vēśārī*
- vēlā-durga-pālar* : port officer
- vēlai-k-kārar* : trusted warriors ever prepared and ready to lay down their lives in the sacrifice of their overlord
- vēlam* : harem of the king where his sword-wives (other than his crowned queens) live; service in the palace; palace servants
- vēḷan* : title conferred by the Chōḷa kings on his subordinates; probably such persons were originally members of the *vēlam*; holders of this title were always officers of rank
- vēḷār-paḍai* : evidently, the army of the *vēḷār*; probably has some connection with *vēlai-k-kārar*
- vēlichcha-p-pāḍu* : performance of oracles by one possessed
- vēli-k-kāśu*, *vēli-p-payaru* : tax payable in cash, the exact nature of which is not clear

- vēli-k-kuli-p-panam* : probably s.a. *vēli-k-kāśu*
- vēli-nāyakam* : an executive office in village administration
- vellai-vāri* : (also known as *nilam-vellai-vāri*) probably the expenses to be incurred in removing the silt and alluvial soil deposited in the fields in times of flood
- vellai-vāsi* : simple interest
- vellān* : agriculturist
- vellān-irai* : cultivation tax
- vellān-vagai* : belonging to the agricultural class, as lands in a village; ryotwari tenure
- vellān-vetti* : labour of deepening the agricultural fields by removal of silt, etc.
- vellātti* : maid-servant (later on came to denote a concubine)
- vellilai-p-parru* : bundle of betel leaves
- vellilai-y-amudu* : offering of betel, as to a deity
- vēl-pulam* : the country of the Chālukyas
- veluṅgu* : a kind of tree
- vēnāttadigaḷ* : ruler of Vēṇāḍu
- vēṇḍugōḷ; vēṇḍukōḷ* : supplication; petition; fee for the same; also known as *vēṇḍukōḷvari*
- veñjana-panḍāram* : s.a. *veñjanam*
- veñjanam* : condiment; vegetable relish
- venṇey-k-kūttan* : god Krishna
- venra-nāman-koḍuttal* : to give a person the name of his conqueror
- verrilai-vāṇiyar* : betel merchants
- verrilai-y-amudu* : betels, as offerings to deity
- vērvāli* : an ear-ornament
- vēśāri, vēśāli* : probably s.a. *vēkāri*
- vētanai, vētanam, vētinai* : wages, (used always jointly with *vetti*) probably represents wages for the labourers in the public works of the village
- vēṭkōvan* : potter
- vēṭṭāl* : probably s.a. *vēṭṭi*
- vēṭṭi* : free labour for public works in the village
- vēṭṭi* : road; pathway
- vēṭṭi-ch-chōru* : obligation of free feeding *vēṭṭi* labourers
- vēṭṭi-muttāvēl, vēṭṭi-muttāiyāl* : free labour supplied without interruption until completion for public works in the village

- veṭṭi-nilai* : free labour for common work in the village like digging the channels, repairing the roads, etc.
- veṭṭi-k-kāśu* : see *vētanai*
- veṭṭi-p-pāttam* : s.a. *veṭṭi-k-kāśu*
- veṭṭi-p-pēru* : perquisites due to *veṭṭi*
- veṭṭi-p-puḍavi* : supply, probably annually, of cloth to the *veṭṭi*
- veṭṭi-t-taniyāl* : supervisor of the *veṭṭi* labourer
- veṭṭi-vari* : see *veṭṭi-k-kāśu*
- veṭṭi-vētanai, veṭṭi-vēlinai* : (*vētana* : wages) see *vētanai*
- veyadikāṇam* : tax payable in grain, probably on thatched sheds; it may be taken also as having some connection with *vēynel*
- vēynel(lu)* : collection of bamboo-grain from forests
- vibhūti, vibhūti-kāṇikkai* : contribution paid voluntarily to a temple by its devotees while receiving the sacred ashes; later it was collected as a royal due
- vichchāḍaran, vichchāḍiran* : *vidyādhara*
- vichchātti* : *vidyārthin*; student
- viḍai-p-pēr, viḍai-p-pēru* : perquisites payable on a reply to petition to the king
- viḍai-pōr* : cattle-raid
- viḍai-y-adhikāri, viḍaiyil-adhikāri* : officer issuing royal orders
- viḍaiyil-adhikāriḡal* : probably s. a. *tiruvāy-k-kēlvi*
- vidham* : variety, kind
- viḍēlviḍugu* : command of the Pallava king; a title borne by the Pallava monarchs
- viḍupēru* : endowment, as of lands, etc.
- viḍutal* : to bestow, to give, to endow
- viḍu-tittu* : release deed; gift deed
- vidyānubhōgam* : endowment of land to the school for the encouragement of learning
- vidyāsthāna* : educational institution for higher studies
- viḡayābbhishēkam* : being crowned as a victor; anointment as victor
- viḡayasthambha* : pillar of victory
- vikāri* : *vichāri*; *purōhita*
- vikkirama-t-toḷil* : profession of arms; valour
- vilai-āvaṇam* : sale deed
- vilai-āvaṇa-k-kalari* : office where sale deeds are registered
- vilai-dravyam* : sale price

*vilai-kārutal, vilai-kūvutal* : to name the price; to offer for sale publicly, by crying out

*vilai-nilam* : arable land; cultivated land

*vilai-p-porul* : sale price in money

*vilai-p-pramāṇa-k-kachchattu* : acknowledgment for the receipt of (money for) the sale deed

*vilai-p-pramāṇam* : sale deed; s.a. *vilai-y-āvaṇam*

*vilai-p-pramāṇa-iṣaiivu-tittu* : agreement for executing a sale deed

*vilai-ś(i)rāvaṇai* : sale deed

*vilai-t-taṇḍam* : penalty for non-observance of the sale and its conditions

*vilai-t-taravu* : sale deed; receipt for sale money

*vilai-y-āvaṇam* : sale deed; also known as *vilai-y-ōlai*

*vilakkudal* : to solder

*vilakku-k-kuḍimakkal* : persons entrusted with the duty of lighting and maintaining lamps in temple

*vilakku-māḍam* : niche in the wall for lamp; place for lights in a temple

*vilakkuvān* : one who obstructs or hinders

*vilā-p-puram* : land endowed to meet the expenses of festivals

*vil-paṇam* : sale-tax; taken also as a tax on bows or archery

*vilu* : to pass, as the day

*vilu* : *vishu*; equinox; the time when the sun enters the zodiacal signs of the Aries and the Libra

*vilukkāḍu* : proportion; rate

*villāligaḷ* : bowmen; archers

*vilvari* : see *vil-paṇam*

*vimāna* : [lit. pinnacle or upper structure over the *sanctum* of temple] central shrine of a temple; *garbha-griha*

*viṇai-k-kāṇi* : right of playing on the *viṇā* before god in the temple during worship

*vinā-p-pōkkudal* : to set questions; to enquire

*vinīyōgam* : employment; use; expenditure

*viñjanam* : [Skt. *vyañjanam*] condiments and curry in food offerings; vegetable relish

*vinṇagaram* : *vishṇu-griha*; temple of Vishṇu

*viṇṇappam* : respectful representation; recitation of sacred hymns in the presence of deity; supplication

- viññapti*, *viññapti* : petitioning to the king; officer who brings to the king's notice the petitions of his subjects
- vipravinōdi* : a class of brahmanas who were adepts in jugglery and magical practices
- vipravinōdi-vari* : perquisites due for the maintenance of *vipra-vinōdins*
- virabaṇajiga* : s. a. *vīraḥaṇjīyar*
- vīrābhishēkam* : anointment as hero
- vīrabhōgam* : land assigned for the maintenance of a hero
- vīrachampan-kuḷigai* : coin struck and issued by the Śambuvarāya king Vīra Champa
- vīra-gaṇattār* : community or congregation of heroes; also a division of the Jainas
- vīra-kal* : hero-stone
- vīra-k-kodiyār* : a section of the members of the merchant-guild, *nānādēsis*; probably constituting as the army guarding their interests
- viraktan* : ascetic; man free from worldly attachment; a recluse of the Śaiva order
- vīra-mālai* : poem in praise of warrior
- vīra-muḍi* : crown of heroism
- vīramuṣṭi* : member of a militant class of temple servants who diligently protected the properties and rights of the temples; also known as *vīrabhadra*
- vīra-aṇukkan* : trusted and devoted warrior in personal attendance (of the king)
- vīra-pāñchālar* : eighteen sects of the artisan classes (included among the *nānādēsis*)
- vīra-pāñchā, an-kāśu* : a coin current in olden days
- vīra-paṭṭam* : an ornament, probably a plate worn on the fore-head, by the heroes
- vīra-paṭṭanam* : a mercantile town inhabited by *eri-vīrar*; s.a. *eri-vīra-paṭṭanam*
- vīraśāsanam* : charter of land or other property assigned to a warrior
- vīra-śēshai* : probably the provision made for the descendants of dead warriors
- viratam* : *vrata*; vow; determination to do a thing
- vīraḥaṇjīyar* : strict merchant; daring merchant, i.e. the merchant who braves the obstacles



*viraveṇbāmālai* : garland of verses (in the *veṇbā* metre) on the valour of a hero

*viravu-nilam* : mixed land

*virimuṭṭu* : probably s. a. *vīramushṭi-vari*

*virkaṇḍam* : arch, as in a building

*vīr-kāyam* : s.a. *vil-paṇam*

*vir-paṇam* : (vil+paṇam) tax on bow and arrows; it may also be taken as tax on sales

*virpidi* : sale-note

*virundam* : (*vrinda*); circle of relatives

*virundaṅgal* : wives

*virund-ūṭṭu* : feeding of guests (at a festival)

*viruttu-p-paṭṭigai* : tax in olden days, probably on the profit and the income from interest

*vīsa-k-kaṇakku* : a mode of calculation; probably *bijagaṇita*

*vīsa-k-kāṇam* : tax or share in the produce as remuneration due to a *viyavan* or village headman

*viśam, viśatam* : rate; at the rate of

*viśam* : expense

*visha-vritti* ; land set apart for the support of a poison-doctor; also known as *vishahara-bhōgam*

*vishayam* : territorial division

*viśēshāyam, viśēshādāyam* : special group of taxes

*vishṇu-griha* : Viṣṇu temple

*viśigai* : bodice

*viṭaṅgu* : part of a girdle or other ornament

*vitaram* : a precious stone

*viṭṭavan-viḷukkāḍu* : share in the food offerings to deity due to the person who made the endowment

*viṭṭōḍuṇ-kūṭṭōḍum* : throughout the house; with the house and the relations

*vittu-p-pāḍu* : area having the sowing capacity of a quantity of seed

*vīṭṭu-t-tevai* : perquisites or expenses of the local assembly, as distinct from *nāṭṭu-t-tevai*

*vittuvaśanam, vidvaj-jana* : body of learned men

*vivāha-p-paṇam* : s.a. *kaṇṇāla-k-kāṇam*

*vivasthai* : s.a. *vyavasthai*

*viyākham* : the asterism *viśākha*

*viyāḷa-vattam*, *viyāḷam* : the Jupiter cycle; the zodiacal sign in which the planet Jupiter stood at the time

*viyāpāri-nagarattōm* : we, the members of the merchant-guild

*viyayam* : (*vyaya*); expenditure, as opposed to *āyam*, income

*vritti* : means; livelihood; occupation; grant of land for one's livelihood

*vyākkyāvritti* : land set apart to meet the expenses of expounding the *purāṇas* and other *śāstras*

*vyākaraṇa-dāna-maṇḍapa* : hall in the Śiva temple at Tiruvorriyūr where the Sanskrit grammar was expounded, in remembrance of the belief that the *Māhēśvara Sūtras* on which the Sanskrit grammar has been founded were created by Śiva

*vyavasthai* : regulations; rule of proper conduct; settlement; arrangement; deed of agreement

*yādavarāyan-ṇaṇam* : coin in olden days struck and issued by the Yadavarāyas

*yāga-maṇḍapam*, *yāgaśālai* : sacrificial hall in a temple

*yakki-achchu* : coin current in olden days in the Koṅgu country

*yakki-p-paṭṭi* : land set apart for meeting the expenses of worshipping *yakshi* and *yakshini* (in the Jaina temple); probably a variety of *paḷli-ch-chandam*

*yāl-vallān* : title conferred in olden days by king on the expert in playing the musical instrument *yāl*

*yāli-k-kāl* : leg of stand, etc., shaped like a *yāli*

*yamanikai-p-ṇaḍavai* : [*yavanika*+] curtain

*yantiram* : *yantra*; mechanical contrivance, as for diverting water

*āṇai-ch-chālai* : s.a. *āṇai-ch-chālai*

*yātrā-dānam* : propitiatory gift before starting on an expedition of conquest by the king

---

*echchōru* : We have, in epigraphy, a large number of items ending with *śōru* being the obligation of free-feeding, like *pulli-ch-chōru*, *tiṅgal-chōru*, *veṭṭi-ch-chōru*, *vari-ch-chōru*, etc. It is therefore possible that *echchōru* may after all mean 'any kind of free-feeding.'

# INDEX

## A

- abhishēka* 1317, 1319  
*Ācharya* 1366  
*āchārya* 1343, 1359, 1360  
*Ādikēśava-p-perumāl temple* 1345  
*Ādikēśava Sōmayaji* 1360  
*Ādi Śaiva* 1320  
*Ādiśēsha* 1360  
*Ādivaraha (God)* 1363  
*agni (south-east)* 1331  
*agrahāra* 1311, 1326, 1327, 1329, 1331, 1333, 1338, 1340  
*agrahāra mudrā* 1327  
*Aiyaṅgarkuḷam* 1357  
*Akkuḷapaṭṭu Rājavar* 1340  
*Aḷagar Ācharya* 1366  
*Aḷagayyar* 1326, 1327, 1329, 1331, 1333, 1338, 1340  
*Aḷagiya Śiṅgar temple* 1362  
*Ālavandār* 1365, 1369, 1371  
*alli (flower)* 1345  
*Āḷudaiya Piḷḷaiyar* 1311  
*Āḷvar* 1343, 1346  
*Ānanda nilayam* 1354  
*Anantaśayanam (Trivandrum)* 1355  
*Āṇḍal* 1297, 1343, 1348  
*Andhra State* 1375  
*Āñjanēya* 1356  
*Annam* 1375  
*Araṇya (river)* 1326, 1329, 1331, 1333, 1338, 1340  
*Ārāyirappaḍi* 1343  
*archchanā* 1318  
*Arjuna* 1301  
*Aripurandān Āriyarāya gōtram* 1340  
*Ārkkāḍu-kūrāram* 1296  
*Aruḷākara* 1309  
*Aruḷāḷapperumāl* 1352  
*Ashṭabujam temple* 1362  
*asuras* 1308

- Attiyūrān temple* 1362  
*avatāra ślōka* 1343

## B

- Balaśiriyan Havyadēvan* 1296  
*balipīṭha* 1356  
*bhadrāsana* 1298  
*Bhaṭṭachārya* 1320  
*bhikshātana yātrā* 1313  
*Bhūmip-pirāṭṭiyār* 1348  
*Bhūtattaḷvar* 1345, 1346  
*Books and Periodicals*  
*Antiquities of the Madras Presidency, List of* 1326  
*Catālogue of Copper-plate grants in the Government Museum at Madras* 1327, 1329, 1332, 1334, 1338, 1340  
*Inscriptions copied from the Southern Districts* 1297, 1301, 1303, 1326  
*South Indian Inscriptions (Texts)* 1303  
*Brahmadēyam* 1296  
*brāhmaṇa* 1311, 1320, 1346, 1349, 1356  
*Brahmaśirah-khaṇḍiśvara* 1295  
*Burgess, Jas.* 1326

## C

- chakra* 1346  
*Chakrarāja* 1297, 1298  
*Chakrarāya* 1297  
*Chaturthavarṇa* 1346, 1350  
*Chaturvēda bhūmi bhavana* 1326, 1328, 1331, 1332, 1340  
*Chidanābaram* 1301, 1355  
*Chingleput* 1325  
*Chirrambalam* 1309  
*Collector of Chingleput* 1326  
*Cyclic Years*  
*Bahudanya* 1350

Kilaka 1297  
 Krōdhana 1348, 1360  
 Manmatha 1298, 1326, 1327,  
 1328, 1331, 1333, 1338, 1340  
 Naḷa 1348, 1351  
 Parābhava 1347  
 Prabhava 1349  
 Siddharti 1344, 1345, 1346  
 Ānanda 1353  
 Durmati 1351  
 Vikrama 1372  
 Chitrabhānu 1370  
 Raktākshi 1375  
 Plava 1372  
 Vyaya 1369, 1371  
 Dhātu 1369  
 Hēṇḷambi 1371  
 Rudhirōdgarin 1359  
 Tārāṇa 1370  
 Sadhārāṇa 1361  
 Śobhakrit 1359  
 Akshaya 1369  
 Subhānu 1372  
 Jaya 1370  
 Isvara 1351  
 Virōdhin 1371

## D

dabhra sabhā 1309  
 dancing-hall 1321  
 dāsi 1375  
 Dēśika 1366  
 Dēvadēva 1313  
 Dēvakanniyān Kanniyarāya gōt-  
 ram 1340  
 Dēvarāya 1298  
 Dēvarājārṇava (tank) 1356, 1357  
 dharma 1326  
 Dhūrjaṭi (temple of) 1316  
 dikshā 1308  
 Dindigul Taluk 1375  
 Dīpaprakāśar temple 1362

## Districts

Anantapur 1375  
 Arcot, South 1301  
 Madurai 1375  
 Tañjavūr 1295  
 Tiruchirapalli 1297  
 Dvāpara yuga 1344, 1345, 1346,  
 1351

## E

Ekāmbara temple 1363  
 Ekkōl Appāji or Ekkōṭi Appaji  
 1326  
 Emberumānar (Ramanuja) 1360  
 Eṭṭūr Śingarāchārya 1365  
 Eṭṭūr Tirumalai Kumāra Tāta-  
 chārya, *Vēdamārga pratishtā-*  
*chārya ubhaya vēdāntasthāpanā-*  
*chārya* 1355

## G

Ganges 1306  
 Garuḍa 1298, 1348, 1356  
 Gauri 1315  
 geḍi 1334  
 Geputi Vanniyarāya gōtram 132)  
 Girija (Parvatī) 1319  
 gōmaṭha (family) 1361  
 gōpura 1356  
 Gōvardhanapura 1365  
 Gōvindabhaṭṭar 1365, 1372  
 Gōvindamuni 1370  
 Gōvindarājar shrine 1355  
 Grantha script 1301  
*Guru paramparā prabhāvam* 1343,  
 1351

## H

Hanumān 1357  
*Hanumat vimśati* 1357  
 Hastigiri 1352, 1355, 1362

## I

Indra 1313  
 Iṣvarabhaṭṭaḷvar 1370  
 Iṣvarabhaṭṭar 1365  
 Iṣvaramuni 1359, 1365, 1369

## J

Jayantimālā 1343  
 Jñānasambandha 1311

## K

*kāhala* 1298  
 Kachchinila-[t-tiṅgal]-tuṇḍatt-  
 emberuman temple 1363  
 Kadiri 1375  
 kalaṣa 1217, 1316  
 Kali 1326, 1328, 1331, 1333,  
 1338, 1340, 1347 to 1351, 1359  
 to 1361, 1369, 1375  
 Kaḷḷar 1351  
 Kaḷvar (God) 1362, 1363  
*Kalyāṇākōṭi* 1350, 1353, 1358  
 Kāmakōshṭha (Tirukkāmakkōṭṭam)  
 1322  
 Kāmākshī amman temple 1363  
 Kamaḷananda Tātāchārya 1356  
 Kāñchīmaṇḍalam 1326, 1328,  
 1331, 1332, 1333, 1340  
 Kāñchīpuram 1343, 1344, 1352,  
 1353, 1357, 1362, 1364  
 Kaṇḍiyūr 1295  
*kāñiyāṭchi* 1375  
 Kannivaḷi Zamīn 1375  
 Kāragam temple 1362  
 Karigiri 1354, 1355  
 kaṇṇa 1299  
 Karvānam temple 1362  
 Kaṭṭumannār kōyil 1365  
 Kaumōdaki 1345  
 Kaustubha 1347  
 Khaṇḍava (forest) 1301  
*kiriṭa* 1356

Kolli 1347  
*kombu* 1299  
 Kōnaikkōṭṭam 1326, 1329, 1331,  
 1333, 1338, 1340  
 Kōnai Mattavarāya gōtram 1338  
 Kōnakōnēri Mattavarāya gōtram  
 1340  
 Kōnēri Mattavarāya gōtra 1327  
 Kōnēri mudra 1327  
 Kō-Pa-dēvar 1295  
*kōṭi kanyakā dānam* (title) 1353,  
 1365  
 Kōṭṭaiyan 1327, 1329, 1331,  
 1334, 1338, 1340  
 Kōṭṭāru 1301  
*kōyilolugu* 1359  
 Krishṇa rāya kavi 1300  
 Krishṇa vēḍu Vanniyarāya  
 Gōtran 1329  
*kshatriya* 1347  
 Kulaśēkhara 1355  
 Kulaśēkhara Āḷvar 1347  
*kulī* 1327, 1329, 1331, 1334,  
 1338, 1340  
 Kulōttuṅga Chōḷa (I) 1301, 1302  
 Kumāra (Tirujñānasambandhar)  
 1319  
*kumāra stōtra* 1311  
 Kumbakōṇam 1354  
 Kumuda Gaṇēśa 1351

## L

Lakshmī 1353  
 Lakshmī kumāra 1353, 1364,  
 1366  
 Lakshmī kumāra Tātāchārya  
 1355, 1356

## M

Mackenzie, Col. 1297, 1301, 1303,  
 1326, 1373  
 Madhurakavi 1343, 1351

**Madiram Veṭṭan Manniyarāya**  
gōtran 1340

Madras 1326, 1347

Mahādēva (god) 1295

Malaiyaṇḍi Appaya Nāyakar  
1375

Manāvatara 1304

Maṇavāla māṃuni 1361

*maṇḍapa* 1307, 1321, 1356

*maṅgala dīpa* 1311

Mannamaṇaṃgan Mannavēḍu  
1334

Mannavarāya gōtram 1340

*mannavēṭṭu* 1327

*mānya* 1375

Mathura 1300

Mayilappūr 1347

Melukōṭe 1355

Mēsha *lagna* 1369

milch cows 1317

*mleḥcha vamaśa* 1351

*month*

April 1353

October 1297, 1371

Śittirai 1326, 1328, 1331, 1333,  
1338, 1340, 1351, 1360, 1371

Vaikāśi 1350

Āni 1348, 1359

Āḍi 1348, 1369

Āvaṇi 1372, 1375

Aippaśi 1344, 1345, 1346, 1361

Kārttigai 1372

Margali 1349

Tai 1346

Maśi 1307, 1347

Mēsha 1353

Mithuna 1371

Tula 1297, 1370, 1372

Kumbha 1369

*mudrā* 1329

Museum, Government 1326

Mysore State 1355

## N

**Nakkanpaḍi** 1296

*nakshatram*

Krittika 1351

Rōhiṇī 1351, 1353

Punarvasu 1347, 1371

Makha 1348

Hasta 1369

Pūram (Pūrva Phalgunā) 1348

Uttiram 1297, 1369

Svāti 1348

Rēvati 1298

Viśākha 1350, 1372

Chitra 1351

Mūla 1361

Jyēsthā 1298, 1349

Śravishṭa 1345

Śravaṇa 1344

Śatabishaj 1346

Anuradhā 1359, 1372

Ādra 1360, 1370

Āślēsha 1372

Nālayira Divya Prabhandha 1347

nāli 1319

Nammālvar 1350

*nandavana* 1306

Nandi 1317

Naralōkavira (General) 1303,  
1304, 1308, 1311, 1315, 1318,  
1322, 1323

Narasimhāchāri 1327, 1331, 1334,  
1338, 1340

Narasimhāchārya 1365, 1366

Narasimhāchārya Tātachārya  
1365

Narasimha temple 1375

Na araja temple 1301

Natesa Sastri, Pandit S.M. 1326

Nathamuni 1359, 1365, 1366,  
1368, 1370

Niragam temple 1362

*niruli* 1327

*nitya dīpa* 1316

**P**

Pachchaivaṇṇar temple 1363  
 Paḍagam 1363  
 Padmanētra 1365  
 Padmanētrachārya 1365  
*paksha* 1348  
 Pambūṇi-kūrṇam 1295  
*pāṇa kula* 1354  
 Pañchajanya 1349  
*Pañchamata bhangam* (title) 1366  
*pañchama varṇa* 1351  
 Pañchanathastala 1326, 1327,  
 1329, 1331, 1333, 1338, 1340  
 Pañchavarṇa naḍu 1331, 1333,  
 1338, 1340  
 Paṇḍavadhūtar temple 1363  
 Paṇḍu 1301  
 Parakēsarivarman (Chōla king)  
 1295  
 Paramēśvara Vinṇagaram 1363  
 Parittipattān Tettavarāya gōtram  
 1340  
 Pavalavaṇṇar temple 1363  
 Pārvati 1321  
 Paśupati 1309  
*pāyasam* 1319  
 pearl umbrella 1298  
 Pērambalam 1312  
 Periya Kāmu 1375  
 Periyakōṇēri Mannavēḍu 1334  
 Periyālvār 1297, 1348  
 Periyaṇiyān Periya Kāmani  
 Bhūmi-pālakan Perumālaiyan  
 1334  
 Periya-perumāḷ (God) 1297  
 Periya Tirumalai Nambi 1364  
 Periyavarāya gōtram 1334  
 perpetual lamp 1295  
 Persians 1302  
 Pēyālvār 1345  
 Phaṇipati śayanam 1354, 1355  
 Pinpaḷagiya perumāḷ Jiyar 1343

pirāṭṭiyar 1343  
 pītāmbara 1322  
*pon* 1327, 1329, 1331, 1334,  
 1338  
 Ponnagiri 1329  
*poygai* (tank) 1344  
 Poygaiyār 1344, 1345  
*prākāra* 1321, 1356, 1363  
*Prapannāmritam* 1355  
 Puṇḍarikāksha 1365  
 Puṇyakōṭi 1353, 1356  
*purushakāri* 1373

**R**

Raghu (Rāma) 1300  
 Rājakēsarivarman (Chōla king)  
 1296  
 Rāmā 1354  
*Rāmanāṭaka* 1299  
 Rāmānuja 1360, 1361, 1364,  
 1365, 1372, 1373  
 Raṅgachārya 1365  
 Raṅganāthachārya 1366  
 Raṅganāthar 1300  
 Raṅganāthar temple 1297  
 Raṅgarāja nagari (Śrīraṅgam)  
 1300  
 Raṅgarājar 1365, 1371  
 Rāyar 1326, 1329, 1331, 1338  
 1340

**S**

*sabhā* 1312, 1324  
 Sabhāpati 1304, 1308  
 Sahyādri 1302  
 Śaka 1297, 1326, to 1328, 1331,  
 1333, 1338, 1340, 1353, 1359,  
 1360, 1361, 1368, 1370 to 1372'  
 1375  
 Śakēta (Ayōdhya City) 1300  
 Śakra (Indra) 1301  
 Śambhu (Śiva) 1317

*sanctum sanctorum* (mūlasthāna)

1315

*śaṅkha* 1344

*Sannidhi Guruparambarai* 1359

*saras* 1344

*Sarasvatī* 1319

*Śaṭhakōpa* 1365

*Śaṭhamarshaṇa gōtra* 1365

*Sēnai Mudaliyār* 1350

*Śēṅarpaṭṭu* 1325

*Sewell, R.* 1326

*Śimhāchalam* 1355

*Simhadri* 1354, 1355

*Śiva* 1305, 1306, 1311, 1315,  
1316

*Śiyyālapurattān Śivaraya gōtram*  
1331

*ślōka* 1311, 1312, 1318, 1343

*Śōḷiraya brāhmaṇa family* 1348

*Sonnaṇṇam śeyda Peruma!*  
temple 1362

*Śoṭṭai kula* 1361

*Śoṭṭai nambi Gōvindamuni* 1365

*Śri Bhāshyakāra* 1373

*Śrīdēvi* 1360

*Śrīkārmuka* 1351

*Śrīkaṇṭha (Śiva)* 1319

*Śrīnivasāchārya* 1365, 1366

*Śrīnivasavaradāchārya* 1366

*Śrīperumbūdūr* 1343, 1360, 1373

*Śrīnandaka* 1346

*Śrīraṅgam* 1296, 1354

*Śrīśailapūrṇa* 1364, 1372

*Śrīvaishṇava* 1360, 1362

*Śrīvatsa* 1351

*Śrīvilliputtūr* 1348

*Śūḷalaiyamarndan* 1324

*Sudarśana* 1346

*Śūḍikkoḍutta Nachchiyār* 1297,  
1348

*Sugandi* (flower) 1345

*Sundarāchārya* 1366

*Sundaramūrti Nāyanār* 1320

## T

*Taṅjavūr Taluk* 1295

*Tatachārya* 1353 to 1355, 1358,  
1359, 1364

*Tātachārya, Kōḷi kanyakādānam*  
1364

*Tatasamudram* 1357

*Tātayāchārya* 1366

*Tatayadēśika* 1354

*Tāyar shrine* 1353

*Tenkalai Śrīvaishṇavas* 1361

*Tēvaram* 1311

*Tillai* 1324

*Tillai mūvayiravar* 1311

*tīrtha* 1305

*tīrtha yātra* 1307

*Tirukkaḍalmallai (Māmallapuram)*  
1345

*Tirukkāmakkōṭṭam* 1321

*Tirukkanḍiyūr* 1296

*Tirukkuraiyalūr* 1351

*Tirukkōḷūr* 1351

*Tirukkurugai-p-pirān Piḷḷan* 1365  
1366, 1372

*Tirukkurugai* 1350

*Tirumalai* 1354, 1364, 1372

*Tirumalai Tātachārya* 1366

*Tirumaliśai* 1346

*Tirumaliśaippirān* 1346

*Tirumaṇḍanguḍi* 1349

*Tirumaṅgai mannan* 1343, 1351

*Tirupati* 1355, 1364, 1372

*Tiruppaṇalvar* 1343, 1351

*Tirupputkuli* 1363



Tiruttanka 1362  
 Tiruvantaḷvār (Ādiśeṣha) 1361  
 Tiruveḷka 1344; 1362  
 Tiruveṇḍuḍaiyan Vannarāya gōt-  
 ram 1329  
 Tiruvuḍaiya Perundāsar *alias*  
 Aṇṇar 1361

### *tithi*

Chaturthi 1348  
 Chaturdaṣi 1351, 1369  
 Paurṇami 1351, 1369  
 Ba. chaturdaṣi 1349  
 Ba. dvādaśi 1297  
 Ba. dvitīya 1351  
 Ba. prathamā 1346  
 Śu. aṣṭami 1344  
 Śu. chaturthi 1351, 1361  
 Śu. chaturdaṣi 1350  
 Śu. daśami 1359  
 Śu. dvādaśi 1347  
 Śu. ēkādaśi 1346, 1348  
 Śu. navami 1345  
 Śu. pañchamī 1360  
 Śu. tritīya 1353  
 Toṇḍaimaṇḍalam 1326; 1328,  
 1331 to 1333, 1340  
 Toṇḍaraḍippōḍi-y-aḷvār 1349  
*tulābhāra* 1358  
*tulāsi* 1348  
 Tuḷuva Chinnaiyān 1340  
 Tuḷuvai 1334  
 Tuḷuva Ponnagiri Pallavarāyan  
 1331  
 Tyāgavalli 1311, 1318

### U

Uḍaiyar Kumpan, Vanniyarāyan  
 1329  
 Uḍaiyavar 1373  
 Ulagaḷandar temple 1362, 1363  
 Uḷḷavāṇuraittavar temple 1363

Uppūr Periyān kōṭṭai Pushparishi  
 gōtram 1340  
 Uragam 1362  
 Uraiyūr 1351  
 Uttama Nambi 1297, 1298, 1000

### V

*vāhana* 1356  
*Vaijayanti Vanamālā* 1349  
 Vaikuntha (Vishṇu) 1317  
 Vaikunṭha-p-perumāl temple 1363  
 Varadarāja 1358  
 Varadarāja temple 1352, 1353,  
 1355, 1357, 1362  
 Veḷḷuḍaiyān Vanniyar Manna-  
 vēḍu 1334  
 Veḷḷuḍaiyān Vanniyarāya gōtram  
 1329  
 Veḷukkai Śiṅga-p-perumāl temple  
 1362  
 Vempurattān Veḷikarāya gōtram  
 1331  
*venbā* 1303  
 Vēnkaṭa 1355  
 Vēnkaṭachārya 1366  
 Vēnkaṭādri 1354, 1355  
 Vēnkaṭavaradachārya 1366  
 Vēnkaṭavarada Dēśika 1366  
 Vēnkaṭavarada Tātachārya 1366  
 Vēnkaṭa Virarāghavachārya 1366  
 Vēnkaṭēśa (god) 1364  
 Vijayarāghava temple 1363  
 Viḷakkoḷi-k-kōyil 1362  
 Villuḍaiyān Vilvarāya gōtram  
 1340  
*vimāna* 1353, 1354, 1356  
 Viramuḍaiyān Virarāya gōtram  
 1340  
 Virarāghava Tātachārya 1366  
 Virarāghava Vēdāntachārya 1366  
 Vira Śaṅguḍaiyān, Chōḷarāja  
 1326, 1328, 1331, 1333, 1338,  
 1340

civ

Viratṭānēśvara temple 1295  
 Virūpaksha 1365  
 Viṣṇu 1344, 1345, 1346, 1347,  
 1349, 1351, 1363  
 Viṣṇu temple 1362, 1363  
 Viṣṇuchitta 1348  
 Viṣṇuvardhana 1365  
*vithidīpa* 1305  
 Voḍayan Kumban Vanniyān  
 Mannavēḍu 1334  
 Vriṣhādri 1354, 1355

W

*Week days*  
 Sunday 1298, 1346, 1348  
 Tuesday 1344, 1348, 1349,  
 1369

Wednesday 1297, 1345, 1351,  
 1359  
 Thursday 1346, 1347, 1351,  
 1360, 1361  
 Friday 1350, 1351  
 Saturday 1353

Y

Yadavādri 1354  
 Yadhu (Kriṣṇa) 1300  
 Yamunā 1365  
 Yāmunāchārya 1369  
 Yāmunāya (Ālavandar) 1364  
 Yathōktakāri temple 1362, 1363  
 Yatipati (Rāmānuja) 1361  
 Yeluppōḍu Agrahāram 1334

## பொருட்குறிப்பு அகராதி

அ

அக்கிரஹாரமுத்திரை 1327  
அத்திகிரி 1354  
அத்தியூர் 1363  
அந்தணர் 1311  
அபிவேகம் 1319, 1353  
அமிருதம் 1314, 1317  
அம்பிகை 1314  
அயோத்தி 1301  
அருளாகரன் 1310  
அர்ச்சுனன் 1302  
அவதார சுலோகங்கள் 1344  
அழகய்யர் 1326 - 1340  
அழகிய சிங்கர் 1363  
அனந்த சயனம் (திருவனந்தபுரம்) 1355  
அனந்தபூர் ஜில்லா 1375  
அஷ்டபுஜம் 1363

ஆ

ஆசாரியர் 1343  
ஆஞ்சநேயர் 1357, 1358  
ஆண்டாள் 1344  
ஆதிகேசவ சோமயாஜி 1360  
ஆதிகேசவப் பெருமாள் கோவில் 1345  
ஆதிகேஷன் 1360  
ஆதிசைவர் 1321  
ஆந்திர ராஜ்யம் 1375  
ஆர்க்காடு கூற்றம் 1296  
ஆழ்வார் 1298, 1343, 1344  
ஆளவந்தார் 1367  
ஆளுடைய பிள்ளையார் (திருஞான சம்பந்தர்) 1312, 1326  
ஆறுயிரப்படி குருபரம்பரா பரபாவம் 1344

ஆனந்த நிலயம் 1354

இ

இந்திரன் 1302, 1314  
இராகவையங்கார், மு. 1324  
இராம நாடகம் 1299  
இராமன் 1301  
இராமாநுஜர் 1367, 1373  
இராமாநுஜர் ஆலயம் 1373

ஈ

ஈச்வரபட்டாழ்வார் 1370  
ஈசுவர மூனி 1369

உ

உத்தம நம்பி 1296, 1298-1300  
உத்தமநம்பி வயிசம் 1298, 1301  
உலகளந்தார் கோயில் 1364  
உள்ளவாறு உரைத்தவர் 1364  
உறையூர் 1351

ஊ

ஊஞ்சல் 1357  
ஊரகம் 1363

எ

எக்கோடி அப்பாஜி 1326  
எம்பெருமானார் (இராமாநுஜர்) 1360

ஏ

ஏகாம்பரேசுவரர் ஆலயம் 1364  
ஏட்டூர் சிங்கராசாரியார் 1365  
ஏட்டூர் திருமலை குமார தாதாசாரியார்  
வேதமார்க்க பிரதிஷ்டாசாரிய  
உபயவேதாந்தஸ்தாபநாசாரிய  
1355

ஐ

ஐயங்கார்குளம் 1358

க

கங்கா ஜலம் 1306  
 கச்சி நிலாத்திங்கள் துண்டத்தெம்  
 பெருமான் 1364  
 கண்டியூர் 1295  
 கதிரி 1375  
 கமலாநந்த தாதாசாரியார் 1357  
 கர்ணவாத்தியம் 1299  
 கர்ப்பகிருகம் 1295  
 கரிசிரி 1356, 1357  
 கருடன் 1298  
 கல்யாணகோடி 1353, 1357, 1358  
 கல்வெட்டு 1343  
 கவி 1351, 1359, 1362, 1369,  
 1370  
 கலெக்டர், செங்கல்பட்டு ஜில்லா 1325  
 கலைமகள் 1320, 1355  
 கள்வர் 1363, 1364  
 கள்ளர் குலம் 1351  
 கன்னிவாடி ஜமீன் 1375

கா

காசுமீரம் 1357  
 காட்டுமன்றார் கோயில் 1365  
 காண்டவ வனம் 1302  
 காஞ்சீபுரம் 1343, 1344, 1352,  
 1356  
 காஞ்சீபுரம், சின்னக் 1363  
 காமாட்சி அம்மன் கோவில் 1364  
 கார்வானத்துப் பெருமாள் 1363  
 கார்வானம் 1363  
 காரகம் 1363  
 காஹள வாத்தியம் 1299, 1314

கி

கிருஷ்ணராய கவி 1301, 1306  
 கிரீடம் 1314  
 கிரீடம், மணி இழைத்த 1357  
 கிருஷ்ணன் 1301  
 கிழமை

ஞாயிறு 1298

செவ்வாய் 1369  
 புதன் 1297, 1351  
 வியாழன் 1351, 1362  
 சனி 1353

கு

குமார ஏட்டுர் திருமலதாதாசாரிய அய்  
 யன் 1356  
 குமாரன் 1312  
 குமார ஸ்தோத்ர பாராயணம் 1312  
 கும்பகோணம் 1355  
 குமுதகணேசர் 1351  
 குருபரம்பரா ப்ரபாவம் 1343, 1351  
 குலசேகரர் 1356  
 குலோத்துங்க சோழன் 1302, 1303

கே

கேளப்படை 1302

கோ

கொம்பு (ஊது குழல்) 1299

கோ

கோடி கன்யாதானம் (விருது) 1353  
 கோட்டாறு (கோட்டை) 1302  
 கோபுரம் 1357  
 கோமடம் (குடி) 1362  
 கோயிலொழுகு (தூல்) 1359  
 கோவிந்த பட்டர் 1372  
 கோவிந்தராஜர் 1355, 1370

கௌ

கௌமோதகி 1353  
 கௌரிபதி 1315  
 கௌஸ்துபம் 1347

ச

சக்கரம் 1346  
 சக்கரராஜர் 1298  
 சங்கு 1344  
 சடகோபர் 1365

சதுர்வேத பூமிபவனம் 1326-1340  
சந்நிதானம் 1318  
சந்நிதி குருபரம்பரை (தூல்) 1359  
சபாபதி 1304  
சம்பு 1318

சா

சாரதா ஸார்வபெளமர் 1355

சி

சிங்கராசாரியார், ஏட்டுர் 1367  
சிதம்பரம் 1301, 1356  
சிதம்பரம் தாலூகா 1301  
சிற்சபை 1310  
சிவபெருமான் 1321  
சிவிகை, மணி இழைத்த 1357

சு

சுந்தரமூர்த்தி நாயனார் 1312, 1321

சூ

சூரியன் 1305, 1308, 1309

சே

செங்கற்பட்டு 1325  
செப்பேடுகள் 1326  
சென்னை 1325  
சென்னை ராஜதானியில் புராதனச்  
சின்னங்களின் அட்டவணை 1325

சே

சேஷகிரி 1354  
சேஷசயனம் 1355

சோ

சொட்டைக்குலம் 1362, 1367  
சொன்ன வண்ணம் செய்த பெருமாள்  
1363

சோ

சோழ சேனாபதி 1303  
சோழிராய (குலம்) 1348

த

தஞ்சாவூர் தாலூகா 1295  
தஞ்சாவூர் ஜில்லா 1295  
தடாகம் 1308  
தமிழ் ஸம்ஸ்கிருத சாசனங்கள் 1325

தா

தாதசமுத்திரம் 1358  
தாதாசாரியார் 1353, 1355, 1356  
1358, 1364  
தாதாசாரியர், வேதமார்க்க ப்ரதிஷ்  
டாசாரிய உபய வேதாந்த ஸ்தாப  
நாசார்ய ஏட்டுர் திருமல குமார  
1356  
தாயார் ஆலயம் 1353  
தானம் 1323

தி

திண்டுக்கல் தாலூகா 1375  
தியாகவல்லி 1319  
திதி

துவிதியை 1351, 1369  
திரிதியை 1353  
சதுர்த்தி 1352  
தசமி 1359  
துவாதசி 1297  
பௌர்ணமி 1351

திராவிட சிசு 1312  
திருக்கடன்மல்லை (மாமல்லபுரம்)  
1345

திருக்கண்டியூர் 1296  
திருக்காமக்கோட்டம் 1318, 1321  
1323

திருக்குருகைப் பிரான் பிள்ளான்  
1372

திருக்குறையலூர் 1351  
திருக்கோளுர் 1352  
திருச்சிராப்பள்ளி ஜில்லா 1291  
திருஞானசம்பந்தர் 1312  
திருத்தண்கா 1363  
திருப்பணி 1303, 1304, 1357

திருப்பதி 1854, 1856

திருப்பதியம் 1312

திருப்பாணாழ்வார் 1844, 1851

திருப்புட்குழி 1864

திருமங்கை மன்னன் 1844, 1851

திருமண்டங்குடி 1349

திருமலநாத உத்தம நம்பி 1299

திருமலை 1367, 1372

திருமலை நம்பி 1372, 1373

திருமழிசைப்பிரான் 1346

திருமேனி 1320, 1367

திருவனந்தபுரம் 1355

திருவனந்தாழ்வார் 1362

திருவுருவம் 1321

திருவுலா 1313, 1314

திருவெஃகா 1363

திருவேங்கடப் பெருமான் 1364

தில்லைச் சிற்றம்பலம் 1324

தில்லைச் சுடலையமர்ந்தான் கோவில்  
4132

தில்லைவாழ் அந்தணர் 1312

தினகரன் (சூரியன்) 1305

தீ

திப்பரகாசர் 1363

தீர்த்த யாத்திரை 1307, 1308

திவட்டி 1299

து

துலாபாரம் 1358

துவாபரபுகம் 1344, 1345, 1346

1351

துளசி 1348

து

துர்ஜடி 1316

தே

தெரு விளக்கு 1305

தென் ஆர்க்காடு ஜில்லா 1301

தென்னிந்திய சாசனங்கள் 1303

தென் ஜில்லாக்களின் சாசன அட்ட

ஷணை 1296, 1301, 1303 1326

தே

தேவர்கள் 1306, 1314, 1315, 1318

தேவராஜன் 1299

தேவராஜார்ணவம் (எரி) 1355

தோ

தொண்டரடிப்பொடியாழ்வார் 1349

தொண்டை மண்டலம் 1326, 1340

ந

நடராஜப்பெருமான் 1315

நடராஜர் கோவில் 1301

நடன அரங்கு 1321

நடேச சாஸ்திரி, பண்டத எஸ். எம்  
1325

நந்தவனம் 1307

நந்திசப்பெருமான் 1318

நம்மாழ்வார் 1340

நரசிம்மஸ்வாமி ஆலயம் 1375

நாலோக வீரன் 1303, 1304, 1308

1311, 1315, 1316, 1318, 1319

1323

நகத்திரம்

திருத்திகை 1351

ரோஷிணி 1351, 1353

திருவாதிரை 1370

புளர்ப்பூசம் 1371

ஆயில்யம் 1373

உத்தரம் 1298

ஹஸ்தம் 1369

விசாகம் 1332

மூலம் 1362

அனுஷம் 1372, 1359

உத்திராடம் 1370

ரேவதி 1298

நா

நாகலோகம் 1312

நாதமுனிகள் 1359, 1369, 1371

நாலாயிர திவ்யப்பாபந்தம் 1344

நி

சித்திய தீபம் 1316

நீ

நீரகம் 1363

நூ

நூற்றுக்கால் மண்டபம் 1310

ப

பசுபதி 1310

பச்சை வண்ணர் 1364

பஞ்சமத பங்கம் (விருது) 1366

பஞ்சம வர்ணம் 1351

பஞ்சநதஸ்தலம் 1326-1340

பஞ்சவர்ண நாடு 1331-1340

பட்டாசாரி 1321

பணிபதினிரி 1354

பணிபதிசயனம் 1355

பத்ராசனம் 1299

பர்ஜஸ், ஜேம்ஸ் 1325

பரமசிவன் 1311

பரமேச்வர விண்ணகரம் 1364

பரிகலங்கள் 1314

பலிபீடம் 1357

பவழவண்ணர் 1364

பகூம்

கிருஷ்ண—1297, 1351, 1369

சுக்ல—1353, 1359, 1362

பா

பாஞ்சஜன்யம் 1349

பாடகம் 1364

பாணர் குலம் 1351

பாண்டவ தூதர் 1364

பாண்டவ புத்திரன் 1302

பாண்டியர் ஜவர் 1302, 1303

பாயஸம் 1320

பாரசீக நாடு 1303

பாற்பசு 1317

a—xvii

பி

பிரபந்த வகை 1304

பிரபந்நாமிருதம் (தூல்) 1356

பிரம்மசிரக் கண்டிச்வரர் 1295

பிராகாரம் 1321, 1357, 1364

பிராட்டியார் 1344

பிராம்மண குலம் 1321

பிள்ளை லோகார்ய ஜீயர் 1362

பிக்ஷாடன மூர்த்தி 1313

பின்பழகிய பெருமாள் ஜீயர் 1344

பி

பீதாம்பரம் 1322

பு

புண்ணிய தீர்த்தம் 1305

புண்ய கோடி 1353, 1357

புருஷகாரி (காரியகர்த்தா) 1374

புஷ்கரிணி 1310

பூ

பூதத்தாழ்வார் 1345

பூமி 1316

பூமிப்பிராட்டியார் 1348

பெ

பெரிய திருமலை நம்பி 1367

பெரியபெருமாள் (ஸ்ரீரங்கம் அரங்க  
நாதர்) 1298

பெரியாழ்வார் 1298, 1345

பெருந்தொகை 1324

பே

பேயாழ்வார் 1346

பேரம்பலம் 1313

பொ

பொய்கையாழ்வார் 1344

பொருட்காட்சி சாலை, சென்னை 1325

பொன் கலசம் 1298, 1316

ம

மஞ்ஞாபிஷேகம் 1356  
 மக்கென்வி 1296, 1301, 1308  
 1325, 1326, 1373  
 மங்கல தீபம் 1311  
 மண்டபம் 1357  
 மண்வானமாமுனி 1361  
 மதுரகவி ஆழ்வார் 1344  
 மதுரா 1301  
 மதுரை லிவ்வா 1375  
 மலைமகள் 1320, 1321

மா

மாசிக்கடலாடுதல் 1307  
 மாதம்  
 சித்திரை 1370  
 ஆனி 1359, 1371, 1374  
 ஆடி 1370  
 ஆவணி 1372  
 ஐப்பசி 1362  
 கார்த்திகை 1351, 1373  
 மாகி 1307  
 மேஷம் 1353  
 துலா 1297, 1370, 1372  
 கும்பம் 1369  
 ஜ்யேஷ்டம் 1298  
 மாநாவதாரன் 1304

மி

மிலேச்ச வமிசம் 1351

மு

முத்துக்குடை 1299

மே

மேல்கோட்டை 1358

மேஷ வகன்ம் 1369

மை

மைசூர் ராஜ்யம் 1356

ய

யதிபதி (இராமா நுஜர்) 1361  
 யதிந்திர ப்ரணவப் பிரபாவம் 1362  
 யது வமிசம் 1303  
 யதோத்தகாரிப் பெருமாள் 1363,  
 1364

யா

யாதவாத்ரி 1355, 1356, 1365, 1364  
 யாமுநாசார்யர் (ஆனவந்தார்) 1367,  
 1370

யே

யெக்கோல் அப்பாஜி (எக்கோடி அப்  
 பாஜி) 1325

ர

ரகு வமிசம் 1301  
 ரங்கநாதர் 1298, 1300,  
 ரங்கநாதர் கோயில் 1297  
 ரங்கராஜர் 1371  
 ரங்கராஜநகரி (ஸ்ரீரங்கம்) 1300  
 ரங்காசாரியார் 1367  
 ரமா தாதாசாரியர் 1354

ரா

ராமா நுஜர்—இராமா நுஜர்  
 ராயர் 1326-1340  
 ராஜேஸ்வரிலா (தர்மம்) 1325

ல

லக்ஷ்மீகுமாரதாதாசாரியர் 1356, 1374  
 லக்ஷ்மீகுமாரர் 1353  
 லக்ஷ்மீகுமாரர், கோடி கன்யாதானம்  
 1367

வ

வடமொழி 1303  
 வரதராஜர் 1357  
 வரதராஜர் கோவில் 1352, 1353  
 1356, 1357, 1358, 1363



வருஷம்

பிரமோதன 1354

தாத 1370

விக்கிரம 1372

சுபானு 1373

சித்திரபானு 1370

தாரண 1370

விய 1369, 1371

விரோதி 1371

ஜய 1371

மன்மத 1298

ஹேவினம்பி 1371

பிலவ 1372

சோபகிருத 1359

லேக 1297

ஸாதாரண 1362

ஆனந்த 1353

ரண 1351

துன்மதி 1351

ருத்திரோத்காரி 1359

அக்ய 1370

வா

வாகனம் 1313, 1355

வி

விமானம் 1353, 1354, 1357

விருது 1298

விருக்ஷவாடி 1358

விருஷபக் கொடியோன் 1311

விருஷபம் 1313

விருஷாத்ரி 1355, 1356

விருபாக்ஷதேவன் 1367

விளக்கொளிக் கோவில் 1363

விஜயராகவர கோவில் 1364

விஷ்ணுசித்தர் (பெரியாழ்வார்) 1348

வீ

வீதிதீபம் 1305

வீரட்டானேசுவரர் கோயில் 1295

வீரசங்குடையான் சோழராஜா 1326-1340

வே

வெண்பா 1305

வே

வேங்கடபதி 1354

வேங்கடபதிதேவ மகாராயர் 1356

வேங்கடாத்திரி 1355, 1356

வேதம் 1321

வேளுக்கை சிங்கபெருமான் கோவில் 1363

வேள்வி 1358

வை

வைகுந்தப்பெருமான் கோவில் 1364

வைகுந்தப் பெருமான் (விஷ்ணு) 1318

வைஜந்திவனமலை 1349

ஜ

ஜகநானந்த நிலயம் 1354

ஜகன்மாதா 1344

ஜயந்திமாலா 1344

ஜயஸ்தம்பம் 1302, 1303

ஜே

ஜேம்ஸ் பர்ஜஸ் 1325

ஸ

ஸஹ்யாத்ரி மலை 1303

ஸா

ஸாகேதம் (அயோத்தி) 1300

ஸி

ஸிம்ஹாசனம் 1356

ஸிம்ஹாத்ரி 1355, 1356

ஸு  
ஸுகந்தி புஷ்பம் 1345  
ஸுதர்சனம் 1347  
ஸுவல் துரை 1325

ஹ  
ஹநுமத்விம்சதி 1358  
ஹரன் 1318  
ஹஸ்திகிரி 1352

ஸ்ரீ  
ஸ்ரீகண்டன் 1320  
ஸ்ரீகாரியதூரந்தரர் 1356

ஸ்ரீகாரியம் 1294  
ஸ்ரீகார்முகாம்சம் 1351  
ஸ்ரீசைலபூர்ணர் 1367, 1372  
ஸ்ரீதேவி 1360  
ஸ்ரீநந்தகாம்சம் 1346  
ஸ்ரீபாஷியகாரர் 1373  
ஸ்ரீபெரும்புதூர் 1343, 1344, 1378  
ஸ்ரீமார்க்கதாஸ்யபதி 1299  
ஸ்ரீரங்கம் 1296, 1355  
ஸ்ரீரங்கராஜநகரி 1301  
ஸ்ரீவத்ஸாம்சம் 1351  
ஸ்ரீவில்லிபுத்தூர் 1348

---

